


# CONCISE INORGANIC CHEMISTRY

Fifth edition



J.D. Lee

**JOIN US ON THE INTERNET VIA WWW, GOPHER, FTP OR EMAIL:**

**WWW** <http://www.thomson.com>

**GOPHER** <gopher.thomson.com>

**FTP** <ftp.thomson.com>

**EMAIL** [findit@kiosk.thomson.com](mailto:findit@kiosk.thomson.com)

A service of **ITP<sup>®</sup>**




# CONCISE INORGANIC CHEMISTRY

---

FIFTH EDITION

\_\_\_\_ J.D. Lee \_\_\_\_

Senior Lecturer in Inorganic Chemistry  
Loughborough University



*b*

Blackwell  
Science

© 1964, 1965, 1977, 1991, 1996, J D Lee

Published by

Blackwell Science Ltd

Osney Mead, Oxford OX2 0EL

25 John Street, London WC1N 2BL

23 Ainslie Place, Edinburgh EH3 6AJ

350 Main Street, Malden

MA 02148 5018, USA

54 University Street, Carlton

Victoria 3053, Australia

10, rue Casimir Delavigne

75006 Paris, France

Other Editorial Offices

Blackwell Wissenschafts-Verlag GmbH

Kurfürstendamm 57

10707 Berlin, Germany

Blackwell Science KK

MG Kodenmacho Building

7-10 Kodenmacho Nihombashi

Chuo-ku, Tokyo 104, Japan

The right of the Author to be identified

as the Author of this Work has been

asserted in accordance with the

Copyright, Designs and Patents Act 1988

All rights reserved No part of  
this publication may be reproduced,  
stored in a retrieval system, or  
transmitted, in any form or by any  
means, electronic, mechanical,  
photocopying, recording or otherwise,  
except as permitted by the UK  
Copyright, Designs and Patents Act  
1988, without the prior permission  
of the copyright owner

First published 1964

(Chapman & Hall)

Second edition 1965

Third edition 1977

Reprinted 1989, 1990

Fourth edition 1991

Reprinted 1992, 1993, 1994

Fifth edition 1996

Reprinted 1998, 1999, 2000, 2001, 2002

(Blackwell Science)

Set by Best set Typesetter Hong Kong

Printed and bound in India

by Gopsons Papers Ltd., Noida

#### DISTRIBUTORS

Marston Book Services Ltd

PO Box 269

Abingdon, Oxon OX14 4YN

(Orders Tel 01235 465500

Fax 01235 465555)

#### USA

Blackwell Science, Inc

Commerce Place

350 Main Street

Malden, MA 02148 5018

(Orders Tel 800 759 6102

781 388 8250

Fax 781 388 8255)

#### Canada

Login Brothers Book Company

324 Saulteaux Crescent

Winnipeg, Manitoba R3J 3T2

(Orders Tel 204 837-2987)

#### Australia

Blackwell Science Pty Ltd

54 University Street

Carlton, Victoria 3053

(Orders Tel 3 9347 0300

Fax 3 9347 5001)

A catalogue record for this title  
is available from the British Library

ISBN 0-632-05293-7

For further information on  
Blackwell Science, visit our website  
[www.blackwell-science.com](http://www.blackwell-science.com)

The Blackwell Science logo is a  
trade mark of Blackwell Science Ltd,  
registered at the United Kingdom  
Trade Marks Registry

**MBM LIBRARY**



**73812**

# Contents

Preface to the fifth edition	xxx
SI units	xxxiv
Nomenclature in the periodic table	xxxv
 <b>PART ONE THEORETICAL CONCEPTS AND HYDROGEN</b>	 <b>1</b>
<b>Chapter 1 Atomic structure and the periodic table</b>	<b>3</b>
The atom as a nucleus with orbital electrons	3
Atomic spectra of hydrogen and the Bohr theory	4
Refinements to the Bohr theory	8
The dual nature of electrons – particles or waves	10
The Heisenberg uncertainty principle	11
The Schrödinger wave equation	12
Radial and angular functions	15
Pauli exclusion principle	21
Build-up of the elements, Hund's rule	21
Sequence of energy levels	24
Arrangement of the elements in groups in the periodic table	25
Further reading	27
Problems	27
 <b>Chapter 2 Introduction to bonding</b>	 <b>30</b>
Attainment of a stable configuration	30
Types of bonds	30
Transitions between the main types of bonding	32
Ionic bonds	32
Covalent bonds	33
Oxidation numbers	34
Coordinate bonds	34
Double and triple bonds	35
Metallic bonds and metallic structures	36
Melting points	39
Conductivity	40
Solubility	40
Speed of reactions	40

Chapter 3 The ionic bond	43
Structures of ionic solids	43
Radius ratio rules	43
Calculation of some limiting radius ratio values	44
Coordination number 3 (planar triangle)	44
Coordination number 4 (tetrahedral)	44
Coordination number 6 (octahedral)	45
Close packing	46
Classification of ionic structures	47
Ionic compounds of the type AX (ZnS NaCl CsCl)	47
Structures of zinc sulphide	47
Sodium chloride structure	47
Caesium chloride structure	48
Ionic compounds of the type AX <sub>2</sub> (CaF <sub>2</sub> TiO <sub>2</sub> SiO <sub>2</sub> )	48
Calcium fluoride (fluorite) structure	48
Rutile structure	48
$\beta$ cristobalite (silica) structure	49
Layer structures (CdI <sub>2</sub> CdCl <sub>2</sub> [NiAs])	49
Cadmium iodide structure	49
Cadmium chloride structure	51
Nickel arsenide structure	51
Structures containing polyatomic ions	51
A more critical look at radius ratios	52
A cautionary word on radius ratios	52
Lattice energy	54
Features of solids	58
Stoichiometric defects	59
Schottky defects	59
Frenkel defects	59
Nonstoichiometric defects	61
Metal excess	61
F centres	61
Interstitial ions and electrons	62
Metal deficiency	62
Positive ions absent	63
Extra interstitial negative ions	63
Semiconductors and transistors	63
Rectifiers	65
Photovoltaic cell	66
Transistors	66
Micro miniaturized semiconductor devices – integrated circuits	68
Further reading	68
Problems	69

<b>Chapter 4 The covalent bond</b>	<b>72</b>
Introduction	72
The Lewis theory	72
The octet rule	72
Exceptions to the octet rule	73
Sidgwick–Powell theory	74
Valence shell electron pair repulsion (VSEPR) theory	74
Effect of lone pairs	75
Effect of electronegativity	76
Isoelectronic principle	77
Some examples using the VSEPR theory	77
$\text{BF}_3$ and the $[\text{BF}_4]^-$ ion	77
Ammonia $\text{NH}_3$	77
Water $\text{H}_2\text{O}$	77
Phosphorus pentachloride $\text{PCl}_5$	78
Chlorine trifluoride $\text{ClF}_3$	78
Sulphur tetrafluoride $\text{SF}_4$	79
The triiodide ion $\text{I}_3^-$	79
Sulphur hexafluoride $\text{SF}_6$	80
Iodine heptafluoride $\text{IF}_7$	80
Valence bond theory	80
Hybridization	81
The extent of $d$ orbital participation in molecular bonding	85
Sigma and pi bonds	87
Molecular orbital method	89
LCAO method	90
<i>s</i> – <i>s</i> combinations of orbitals	90
<i>s</i> – <i>p</i> combinations of orbitals	93
<i>p</i> – <i>p</i> combinations of orbitals	94
<i>p</i> – <i>d</i> combinations of orbitals	96
<i>d</i> – <i>d</i> combinations of orbitals	96
Non-bonding combinations of orbitals	96
Rules for linear combination of atomic orbitals	97
Examples of molecular orbital treatment for homonuclear diatomic molecules	98
$\text{H}_2^+$ molecule ion	99
$\text{H}_2$ molecule	99
$\text{He}_2^+$ molecule ion	99
$\text{He}_2$ molecule	99
$\text{Li}_2$ molecule	100
$\text{Be}_2$ molecule	100
$\text{B}_2$ molecule	101
$\text{C}_2$ molecule	101
$\text{N}_2$ molecule	102
$\text{O}_2$ molecule	104
$\text{O}_2^-$ ion	105
	105

$\text{O}_2^{2-}$ ion	107
$\text{F}_2$ molecule	107
Examples of molecular orbital treatment for heteronuclear diatomic molecules	107
NO molecule	109
CO molecule	110
HCl molecule	112
Examples of molecular orbital treatment involving delocalized $\pi$ bonding	112
Carbonate ion $\text{CO}_3^{2-}$	112
Nitrate ion $\text{NO}_3^-$	114
Sulphur trioxide $\text{SO}_3$	114
Ozone $\text{O}_3$	115
Nitrite ion $\text{NO}_2^-$	116
Carbon dioxide $\text{CO}_2$	116
Azide ion $\text{N}_3^-$	117
Summary of multi centre $\pi$ bonded structures	117
United atom method	118
Further reading	119
Problems	120
 Chapter 5 The metallic bond	 121
General properties of metals	121
Conductivity	121
Lustre	122
Malleability and cohesive force	122
Crystal structures of metals	126
Bond lengths	127
Theories of bonding in metals	127
Free electron theory	128
Valence bond theory	128
Molecular orbital or band theory	128
Conductors insulators and semiconductors	131
Alloys	132
Ionic compounds	132
Interstitial alloys and related compounds	132
Substitutional alloys	135
Superconductivity	140
Further reading	144
Problems	145
 Chapter 6 General properties of the elements	 146
Size of atoms and ions	146
Size of atoms	146
Size of ions	146
Problems with ionic radii	148
Trends in ionic radii	148

Ionization energies	149
Electron affinity	153
Born–Haber cycle	154
Polarizing power and polarizability – Fajans’ rules	156
Electronegativity	157
Pauling	158
Mulliken	161
Allred and Rochow	162
Metallic character	163
Variable valency and oxidation states	164
Standard electrode potentials and electrochemical series	165
Oxidation–reduction reactions	170
The use of reduction potentials	172
The occurrence and isolation of the elements	178
Mechanical separation of elements that exist in the native form	178
Thermal decomposition methods	179
Displacement of one element by another	180
High temperature chemical reduction methods	181
Reduction by carbon	181
Reduction by another metal	182
Self-reduction	182
Reduction of oxides with hydrogen	182
Electrolytic reduction	182
In aqueous solution	183
In other solvents	183
In fused melts	183
Factors influencing the choice of extraction process	183
Thermodynamics of reduction processes	183
Horizontal, vertical and diagonal relationships in the periodic table	189
Further reading	190
Problems	191
<b>Chapter 7 Coordination compounds</b>	<b>194</b>
Double salts and coordination compounds	194
Werner’s work	195
More recent methods of studying complexes	198
Effective atomic numbers	200
Shapes of <i>d</i> orbitals	201
Bonding of transition metal complexes	202
Valence bond theory	202
Crystal field theory	202
Molecular orbital theory	202
Valence bond theory	203
Crystal field theory	204
Octahedral complexes	205
Effects of crystal field splitting	210

Tetragonal distortion of octahedral complexes (Jahn–Teller distortion)	214
Square planar arrangements	217
Tetrahedral complexes	219
Chelates	222
Magnetism	225
Extension of the crystal field theory to allow for some covalency	226
Molecular orbital theory	227
$\pi$ acceptors	229
$\pi$ donors	229
Nomenclature of coordination compounds	230
Isomerism	232
Polymerization isomerism	232
Ionization isomerism	232
Hydrate isomerism	233
Linkage isomerism	233
Coordination isomerism	233
Coordination position isomerism	234
Geometric isomerism or stereoisomerism	234
Optical isomerism	234
Further reading	236
Problems	236
 Chapter 8 Hydrogen and the hydrides	 240
Electronic structure	240
Position in the periodic table	240
Abundance of hydrogen	241
Preparation of hydrogen	241
Properties of molecular hydrogen	243
Isotopes of hydrogen	245
<i>Ortho</i> and <i>para</i> hydrogen	248
Hydrides	248
Ionic or salt-like hydrides	249
Covalent hydrides	250
Metallic (or interstitial) hydrides	252
Intermediate hydrides	254
The hydrogen ion	254
Hydrogen bonding	255
Acids and bases	256
Arrhenius theory	258
Acids and bases in proton solvents	260
Bronsted–Lowry theory	262
Lewis theory	265
The solvent system	265
The Lux–Flood definition	267
The Usanovich definition	267
Hard and soft acids and bases	267



Further reading	268
Problems	271
<b>PART TWO THE <i>s</i>-BLOCK ELEMENTS</b>	<b>273</b>
<b>Chapter 9 Group 1 – the alkali metals</b>	<b>275</b>
Introduction	275
Occurrence and abundance	276
Extraction of the metals	277
Uses of Group 1 metals and their compounds	278
Electronic structure	280
Size of atoms and ions	280
Density	280
Ionization energy	281
Electronegativity and bond type	281
Born–Haber cycle: energy changes in the formation of ionic compounds	282
Structures of the metals, hardness and cohesive energy	285
Melting and boiling points	286
Flame colours and spectra	286
Colour of compounds	287
Chemical properties	288
Reaction with water	288
Reaction with air	289
Reaction with dinitrogen	289
Oxides, hydroxides, peroxides and superoxides	290
Reaction with air	290
Normal oxides – monoxides	290
Hydroxides	290
Peroxides and superoxides	291
Sulphides	293
Sodium hydroxide	294
Sodium hydrogencarbonate ( <i>sodium bicarbonate</i> )	294
Sodium sulphate	294
Oxosalts – carbonates, bicarbonates, nitrates and nitrites	295
Halides and polyhalides	296
Hydrides	297
Solubility and hydration	298
Solutions of metals in liquid ammonia	302
Compounds with carbon	303
Organic and organometallic compounds	303
Complexes, crowns and crypts	305
Biological importance	308
Differences between lithium and the other Group 1 elements	309
Further reading	311
Problems	312

<b>Chapter 10 The chlor-alkali industry</b>	<b>315</b>
Leblanc process	315
Weldon and Deacon processes	317
Electrolytic processes	317
Diaphragm cell	318
Mercury cathode cell	319
Quantities	321
Sodium carbonate	321
The Solvay (or ammonia–soda) process	323
Further reading	324
Problems	324
<b>Chapter 11 Group 2 – the alkaline earth elements</b>	<b>325</b>
Introduction	325
Electronic structure	326
Occurrence and abundance	326
Extraction of the metals	327
Dow sea water process	329
Dow natural brine process	329
Size of atoms and ions	329
Ionization energy	330
Electronegativity	331
Hydration energies	331
Anomalous behaviour of beryllium	332
Solubility and lattice energy	334
Solutions of the metals in liquid ammonia	335
Chemical properties	335
Reaction with water	335
Hydroxides	336
Hardness of water	337
Reaction with acids and bases	338
Oxides and peroxides	338
Sulphates	341
Nitrates	342
Hydrides	342
Halides	344
Nitrides	345
Carbides	346
Insoluble salts	347
Organometallic compounds	347
Complexes	349
Biological role of $\text{Mg}^{2+}$ and $\text{Ca}^{2+}$	353
Differences between beryllium and the other Group 2 elements	353
Further reading	354
Problems	354

<b>PART THREE THE <i>p</i>-BLOCK ELEMENTS</b>	<b>357</b>
<b>Chapter 12 The group 13 elements</b>	<b>359</b>
General properties	359
Occurrence and abundance	360
Extraction and uses of the elements	360
Extraction of boron	360
Uses of boron	361
Extraction of aluminium	362
Uses of aluminium	363
Gallium, indium and thallium	363
Oxidation states and type of bonds	364
The (+III) oxidation state	364
The (+I) oxidation state – the ‘inert pair effect’	365
The (+II) oxidation state	366
Melting points, boiling points and structures	366
Size of atoms and ions	367
Electropositive character	368
Ionization energy	369
Reactions of boron	370
Reactions of the other elements	370
Reaction with water and air	370
Reaction with acids and alkalis	371
Reaction with dioxygen	372
Reaction with the halogens and sulphate	372
Alums	372
Cement	373
Reactions of Ga, In and Tl	373
Some properties of thallium(I)	373
Compounds of boron and oxygen	374
Boron sesquioxide and the borates	374
Acidic properties of $\text{H}_3\text{BO}_3$ or $\text{B}(\text{OH})_3$	375
Structures of borates	376
Borax	377
Sodium peroxoborate	379
Isopolyacids of B, Si and P	379
Qualitative analysis of boron compounds	380
Fluoboric acid	380
Borides	380
The other Group 13 oxides	381
Qualitative analysis of aluminium	382
Amphoteric behaviour – aluminates	382
Tetrahydridoborates (borohydrides)	383
Trihalides	385
Dihalides	388
Monohalides	388

Complexes	389
Differences between boron and the other elements	389
Boron hydrides	390
Compounds known	390
Preparation	390
Reactions of the boranes	392
Hydroboration	392
Reaction with ammonia	393
Some other reactions of boranes	395
Structures of the boranes	395
Organometallic compounds	397
Further reading	398
Problems	400
 Chapter 13 The group 14 elements	 402
Introduction	402
Occurrence of the elements	403
Extraction and uses of the elements	403
Carbon	403
Silicon	404
Germanium	405
Tin	405
Lead	406
Structure and allotropy of the elements	407
Differences between carbon, silicon and the remaining elements	409
Carbon dating	410
Physical properties	411
Covalent radii	411
Ionization energy	411
Melting points	412
Metallic and non-metallic character	412
Four covalent compounds	412
Chemical reactivity	413
Inert pair effect	413
Standard reduction potentials	414
Graphite compounds	414
Carbides	416
Salt-like carbides	417
Interstitial carbides	418
Covalent carbides	418
Oxygen compounds	419
Carbon monoxide CO	419
Carbon dioxide CO <sub>2</sub>	423
Carbon suboxides	425
Carbonates	425
The carbon cycle	427
Sulphides	428

Oxides of silicon	430
Oxides of germanium, tin and lead	432
Silicates	432
Occurrence in the earth's crust	432
Soluble silicates	433
Principles of silicate structures	434
Classification of silicates	434
Orthosilicates (neso-silicates)	435
Pyrosilicates (soro-silicates, disilicates)	436
Cyclic silicates	436
Chain silicates	437
Sheet silicates (phyllo-silicates)	440
Three-dimensional silicates	443
Silicates in technology	445
Alkali silicates	445
Cement	445
Ceramics	445
Glass	446
Organosilicon compounds and the silicones	446
Organosilicon compounds	446
Preparation of organosilicon compounds	447
Silicones	448
Hydrides	451
Cyanides	453
Complexes	455
Internal $\pi$ bonding using $d$ orbitals	456
Tetrahalides	457
Carbon	457
Freons	458
Silicon	459
Germanium, tin and lead	460
Catenated halides	461
Dihalides	461
Cluster compounds	462
Reaction mechanisms	462
Organic derivatives	463
Further reading	464
Problems	466
<b>Chapter 14 The group 15 elements</b>	<b>468</b>
Electronic structure and oxidation states	468
Occurrence, extraction and uses	468
Nitrogen	468
Phosphorus	468
Arsenic, antimony and bismuth	470
General properties and structures of the elements	471
Nitrogen	472
	472

The nitrogen cycle	473
Phosphorus	474
Arsenic, antimony and bismuth	475
Bond type	476
Metallic and non-metallic character	477
Reactivity	478
Hydrides	478
Ammonia $\text{NH}_3$	479
Ammonium salts	480
Phosphine $\text{PH}_3$	481
Arsine $\text{AsH}_3$ , stibine $\text{SbH}_3$ and bismuthine $\text{BiH}_3$	481
Structure of the hydrides	481
Donor properties	482
Hydrazine $\text{N}_2\text{H}_4$	483
Hydroxylamine $\text{NH}_2\text{OH}$	485
Liquid ammonia as a solvent	486
Hydrogen azide and the azides	487
Standard reduction potentials	490
Fertilizers	489
Nitrogen fixation	489
Cyanamide process	492
Haber – Bosch process	492
Urea	494
Phosphate fertilizers	494
Halides	494
Trihalides	494
Pentahalides	496
Oxides of nitrogen	498
Nitrous oxide $\text{N}_2\text{O}$	499
Nitric oxide $\text{NO}$	499
Nitrogen sesquioxide $\text{N}_2\text{O}_3$	501
Nitrogen dioxide $\text{NO}_2$ and dinitrogen tetroxide $\text{N}_2\text{O}_4$	501
Dinitrogen pentoxide $\text{N}_2\text{O}_5$	503
Oxoacids of nitrogen	503
Nitrous acid $\text{HNO}_2$	503
Nitric acid $\text{HNO}_3$	504
Oxides of phosphorus, arsenic and bismuth	508
Trioxides	508
Pentoxides	509
Other oxides	511
Oxoacids of phosphorus	511
The phosphoric acid series	511
Orthophosphoric acids	511
Polyphosphates	513
Long chain polyphosphates – linear metaphosphates	516
Metaphosphates – cyclophosphates	517
Hypophosphoric acid $\text{H}_4\text{P}_2\text{O}_6$	518

The phosphorous acid series	519
Orthophosphorous acid $\text{H}_3\text{PO}_3$	519
Metaphosphorous acid $(\text{HPO}_2)_n$	520
Hypophosphorous acid $\text{H}_3\text{PO}_2$	520
Major uses of phosphates	520
Sulphides of phosphorus	521
$\text{P}_4\text{S}_3$	522
$\text{P}_4\text{S}_{10}$	523
Phosphazenes and cyclophosphazenes (phosphonitrilic compounds)	524
Organometallic compounds	526
Further reading	527
Problems	529
<b>Chapter 15 Group 16 – the chalcogens</b>	<b>532</b>
General properties	532
Electronic structure and oxidation states	533
Abundance of the elements	534
Extraction and uses of the elements	535
Extraction and separation of dioxygen	535
Uses of dioxygen	535
Extraction of sulphur	536
Acid rain and $\text{SO}_2$	538
Uses of sulphur	539
Extraction and uses of selenium and tellurium	539
Discovery and production of polonium	540
Structure and allotropy of the elements	540
Oxygen	540
Sulphur	541
Selenium, tellurium and polonium	543
Chemistry of ozone	543
Oxidation states (+II), (+IV) and (+VI)	545
Standard reduction potentials	546
Bond lengths and $p\pi-d\pi$ bonding	546
Differences between oxygen and the other elements	547
General properties of oxides	547
Normal oxides	547
Peroxides	548
Suboxides	548
Basic oxides	548
Amphoteric oxides	549
Acidic oxides	549
Neutral oxides	549
Reactions between oxides	549
Oxides of sulphur, selenium, tellurium and polonium	551
Dioxides $\text{MO}_2$	551
Trioxides $\text{MO}_3$	553

Other oxides	554
Detergents	554
Oxoacids of sulphur	556
Sulphurous acid series	557
Sulphuric acid series	559
Thionic acid series	562
Peroxoacid series	563
Oxoacids of selenium and tellurium	563
Oxohalides	564
Thionyl compounds	564
Sulphuryl compounds	565
Hydrides	566
Water	569
Other hydrides	569
Peroxides and polysulphides	570
Hydrogen peroxide	572
Halides	575
Compounds of sulphur and nitrogen	577
Organic derivatives	578
Further reading	580
Problems	582
 Chapter 16 Group 17 – the halogens	582
Introduction	583
Occurrence and abundance	584
Extraction and uses of the elements	584
Fluorine	587
Chlorine	588
Bromine	589
Iodine	590
Astatine	591
Size of atoms and ions	591
Ionization energy	592
Type of bonds formed and oxidation states	593
Melting and boiling points	594
Bond energy in $X_2$ molecule	594
Oxidizing power	596
Reaction with water	597
Reactivity of the elements	599
Hydrogen halides HX	599
HF	600
HCl	601
HBr and HI	605
Halides	605
Ionic halides	605
Molecular (covalent) halides	605



Bridging halides	606
Preparation of anhydrous halides	606
Direct reaction of the elements	606
Reacting the oxide with carbon and the halogen	606
Reaction of metal with anhydrous HX	607
Reaction of oxides with halogen compounds	607
Halogen exchange	607
Dehydrating hydrated halides	607
Halogen oxides	607
OF <sub>2</sub> Oxygen difluoride	608
O <sub>2</sub> F <sub>2</sub> Dioxygen difluoride	608
Cl <sub>2</sub> O Dichlorine monoxide	609
ClO <sub>2</sub> Chlorine dioxide	610
Chlorine perchlorate Cl·ClO <sub>4</sub>	611
Cl <sub>2</sub> O <sub>6</sub> Dichlorine hexoxide	611
Dichlorine heptoxide Cl <sub>2</sub> O <sub>7</sub>	611
Oxides of bromine	612
Oxides of iodine	612
Standard reduction potentials	613
Oxoacids	614
Hypohalous acids HOX	615
Halous acids HXO <sub>2</sub>	616
Halic acids HXO <sub>3</sub>	617
Perhalic acids HXO <sub>4</sub>	618
Strength of the oxoacids	621
Interhalogen compounds	621
AX compounds	622
AX <sub>3</sub> compounds	623
AX <sub>5</sub> compounds	626
AX <sub>7</sub> compounds	627
Polyhalides	627
Basic properties of the halogens	629
Pseudohalogens and pseudohalides	631
Further reading	632
Problems	633
<b>Chapter 17 Group 18 – the noble gases</b>	<b>635</b>
Name of group and their electronic structures	635
Occurrence and recovery of the elements	635
Uses of the elements	636
Physical properties	637
Special properties of helium	637
Chemical properties of the noble gases	638
Molecular ions formed under excited conditions	638
Clathrate compounds	638
Chemistry of xenon	639
Xenon fluoride complexes	642

Structure and bonding in xenon compounds	643
XeF <sub>2</sub>	643
XeF <sub>4</sub>	645
XeF <sub>6</sub>	647
Valediction	647
Further reading	649
Problems	649
 <b>PART FOUR THE <i>d</i>-BLOCK ELEMENTS</b>	 <b>651</b>
<b>Chapter 18 An introduction to the transition elements</b>	<b>653</b>
Introduction	653
Metallic character	654
Variable oxidation state	654
Stability of the various oxidation states	656
Complexes	657
Size of atoms and ions	659
Density	661
Melting and boiling points	661
Reactivity of metals	661
Ionization energies	661
Colour	662
Polarization	662
Incompletely filled <i>d</i> or <i>f</i> shell	662
Magnetic properties	663
Measurement of magnetic moments	666
An example	669
Catalytic properties	671
Nonstoichiometry	672
Abundance	673
Differences between the first row and the other two rows	674
Metal–metal bonding and cluster compounds	674
Stability of oxidation states	675
Complexes	675
Size	675
Magnetism	675
Abundance	676
Further reading	676
Problems	677
 <b>Chapter 19 Group 3 – the scandium group</b>	 <b>679</b>
Introduction	679
Occurrence, separation, extraction and uses	679
Oxidation state	680
Size	681
Chemical properties	681

Complexes	683
Further reading	683
<b>Chapter 20 Group 4 – the titanium group</b>	<b>684</b>
Introduction	684
Occurrence and abundance	684
Extraction and uses	685
Kroll process	686
The van Arkel–de Boer method	686
Oxidation states	687
Size	687
Reactivity and passive behaviour	688
Standard reduction potentials	688
(+IV) state	689
Oxides	689
Mixed oxides	690
Peroxides	691
Halides	691
(+III) state	692
Organometallic compounds	694
Ziegler–Natta catalysts	694
Other compounds	695
Further reading	696
<b>Chapter 21 Group 5 – the vanadium group</b>	<b>697</b>
Introduction	697
Abundance, extraction and uses	697
Oxidation states	699
Size	699
General properties	699
Colour	700
Compounds with nitrogen, carbon and hydrogen	700
Halides	701
(+V) halides	701
(+IV) halides	703
(+III) halides	704
Spectra	704
Nb and Ta halides	705
(+II) halides	705
Standard reduction potentials	706
Oxides	707
(+V) oxides	707
(+IV) oxides	708
(+III) oxides	709
(+II) oxides	709
Vanadates	709
Low oxidation states	709
	710

Organometallic compounds	711
Further reading	711
<b>Chapter 22 Group 6 – the chromium group</b>	<b>713</b>
Introduction	713
Abundance, extraction and uses	713
Oxidation states	715
General properties	716
Standard reduction potentials	717
(+VI) state	718
Chromate and dichromate	718
Peroxo compounds	719
Chromium trioxide (chromic acid)	719
$\text{MoO}_3$ and $\text{WO}_3$	720
Mixed oxides	720
Oxohalides	721
Halides	721
(+V) state	721
(+IV) state	722
(+III) state	722
Chromium	722
Spectra	724
Molybdenum and tungsten	724
(+II) state	725
(+I) state	727
Zero state, (–I) and (–II)	727
Chromates, molybdates and tungstates	728
Tungsten bronzes	731
Biological importance	732
Further reading	732
<b>Chapter 23 Group 7 – the manganese group</b>	<b>734</b>
Introduction	734
Abundance, extraction and uses	734
Oxidation states	736
Standard reduction potentials	737
General properties	737
Lower oxidation states	739
(+II) state	740
(+III) state	742
(+IV) state	745
(+V) state	748
(+VI) state	748
(+VII) state	748
Biological importance	751
Further reading	751

<b>Chapter 24 Group 8 – the iron group</b>	<b>753</b>
Iron, cobalt and nickel groups	753
Introduction to the iron group	753
Abundance, extraction and uses	754
Extraction of iron	755
Blast furnace	755
Reactions involved	756
Steel making	757
Puddling	757
Bessemer and Thomas processes	757
Siemens open hearth processes	758
Siemens electric arc furnace	758
Basic oxygen process	759
Phase diagram	760
Production figures and uses	760
Extraction of ruthenium and osmium	760
Oxidation states	760
General properties	761
Low oxidation states	763
(+II) state	765
Oxides	765
Halides	765
Complexes	766
(+III) state	769
Oxides and hydrated oxides	770
Halides	771
Complexes	772
Ruthenium and osmium	773
(+IV) and higher states	773
(+V) state	773
(+VI) state	774
(+VIII) state	774
Bioinorganic chemistry of iron	775
Haemoglobin	775
Myoglobin	777
Cytochromes	777
Ferretin	777
Catalases and peroxidases	778
Ferredoxins	778
Haemerythrin	779
Cyclopentadienyl and related compounds	779
Further reading	781
 <b>Chapter 25 Group 9 – the cobalt group</b>	 <b>783</b>
Occurrence, extraction and uses	783
Oxidation states	785

General properties	785
Lower oxidation states	787
(+I) state	788
(+II) state	790
(+III) state	794
(+IV) state	798
(+V) and (+VI) states	799
Further reading	799
<b>Chapter 26 Group 10 – the nickel group</b>	<b>800</b>
Introduction	800
Occurrence extraction and uses	800
Nickel	800
Palladium and platinum	802
Oxidation states	803
General properties	803
Low valency states (–I) (0) (+I)	805
(+II) state	806
(+III) state	811
(+IV) state	813
(+V) and (+VI) states	814
Horizontal comparisons in the iron cobalt and nickel groups	814
Further reading	815
<b>Chapter 27 Group 11 – the copper group coinage metals</b>	<b>816</b>
Introduction	816
Abundance extraction and uses of the elements	816
Copper	817
Silver	818
Gold	818
Oxidation states	819
Standard reduction potentials	820
General properties	820
(+I) state	822
Photography	826
(+II) state	827
(+III) state	831
(+V) state	832
Biological role of copper	832
Further reading	833
<b>Chapter 28 Group 12 – the zinc group</b>	<b>835</b>
Introduction	835
Abundance and occurrence	836
Extraction and uses	836
Extraction of zinc	836
Extraction of cadmium	837

Extraction of mercury	837
Uses of zinc	838
Uses of cadmium	838
Uses of mercury	838
Oxidation states	839
Size	839
Ionization energies	840
General properties	840
Standard reduction potentials	842
Oxides	842
Dihalides	843
Complexes	845
Mercury (+I) compounds	846
X-ray diffraction	847
Equilibrium constant	848
Concentration cell	848
Raman spectra	849
Magnetic properties	849
Cryoscopic measurements	849
Polycations	849
Organometallic compounds	850
Biological role of zinc	851
Toxicity of cadmium and mercury	852
Further reading	854
Problems (Chapters 19–28)	854
 PART FIVE THE f-BLOCK ELEMENTS	 857
Chapter 29 The lanthanide series	859
Introduction	859
Electronic structure	859
Oxidation states	860
Abundance and number of isotopes	861
Extraction and uses	862
Separation of the lanthanide elements	864
Precipitation	864
Thermal reaction	864
Fractional crystallization	864
Complex formation	864
Solvent extraction	865
Valency change	865
Ion exchange	866
Chemical properties of (+III) compounds	866
Oxidation state (+IV)	868
Oxidation state (+II)	869
Solubility	870
Colour and spectra	870

Magnetic properties	872
Lanthanide contraction	874
Complexes	875
Further reading	877
Problems	878
 Chapter 30 The actinides	 879
Electronic structure and position in the periodic table	879
Oxidation states	881
Occurrence and preparation of the elements	882
Preparation of the actinides	883
General properties	886
Thorium	887
Protactinium	889
Uranium	890
Occurrence	891
Extraction	891
Nuclear fission	891
Chemical properties	893
Hydrides	893
Oxides	894
Halides	894
Neptunium, plutonium and americium	895
The later actinide elements	896
Further extension of the periodic table	898
Further reading	900
Problems	901
 PART SIX OTHER TOPICS	 903
 Chapter 31 The atomic nucleus	 905
Structure of the nucleus	905
Liquid drop model	905
Shell model	906
Forces in the nucleus	907
Stability and the ratio of neutrons to protons	908
Modes of decay	909
Beta emission	909
Neutron emission	910
Positron emission	910
Orbital or K-electron capture	910
Proton emission	911
Gamma radiation	911
Half life period	911
Binding energy and nuclear stability	912
Alpha decay	913
Radioactive displacement laws	915



Radioactive decay series	915
Thorium ( $4n$ ) series	916
Neptunium ( $4n + 1$ ) series	916
Uranium ( $4n + 2$ ) series	916
Actinium ( $4n + 3$ ) series	916
Induced nuclear reactions	917
Nuclear fission	918
Chain reaction	919
Critical mass	920
The story behind production of the atomic bomb	920
Separation of isotopes	920
Thermal diffusion	921
Electromagnetic separation of $\text{UCl}_4$ using a mass spectrometer	921
Gaseous diffusion of $\text{UF}_6$	921
Using a gas centrifuge to separate $^{235}\text{UF}_6$ and $^{238}\text{UF}_6$	921
Bomb making	922
Nuclear power stations	923
Moderators	923
Fuel	924
Types of reactor in use	924
Gas cooled thermal reactors	924
Magnox reactors	924
Advanced gas cooled reactors	924
High temperature reactor	924
Water cooled thermal reactors	925
Canadian deuterium uranium reactor	925
Pressurized water reactor	925
Boiling water reactor	925
Steam generating heavy water reactor	925
Fast breeder reactors	925
Nuclear fusion	925
Thermonuclear weapons	927
Controlled fusion reactions	927
The genesis of the elements	928
Some applications of radioactive isotopes	932
Some units and definitions	934
Further reading	935
Problems	935
 Chapter 32 Spectra	
Energy levels in an atom	938
Coupling of orbital angular momenta	938
$p^2$ configuration	940
$p^3$ configuration	940
$d^2$ configuration	941
Coupling of spin angular momenta	941
	942

$p^2$ or $d^2$ case	942
$p^3$ or $d^3$ case	942
Spin orbit coupling	943
Spin orbit coupling $p^2$ case	943
Determining the ground state terms – Hund's rules	946
Hole formulation	947
Derivation of the term symbol for a closed subshell	948
Derivation of the terms for a $d^2$ configuration	948
Calculation of the number of microstates	950
Electronic spectra of transition metal complexes	951
Laporte 'orbital' selection rule	951
Spin selection rule	952
Splitting of electronic energy levels and spectroscopic states	953
Spectra of $d^1$ and $d^9$ ions	954
Spectra of $d^2$ and $d^8$ ions	958
Spectra of $d^5$ ions	965
Tanabe–Sugano diagrams	967
Further reading	970
Problems	971
 Appendix A Abundance of the elements in the earth's crust	 973
Appendix B Melting points of the elements	974
Appendix C Boiling points of the elements	976
Appendix D Densities of the solid and liquid elements	978
Appendix E Electronic structures of the elements	980
Appendix F Some average single bond energies and some double and triple bond energies	983
Appendix G Solubilities of main group compounds in water	984
Appendix H Atomic weights based on $^{12}\text{C} = 12.000$	985
Appendix I Values of some fundamental physical constants	987
Appendix J Electrical resistivity of the elements at the stated temperature	988
Appendix K Top fifty chemicals in the USA, 1994	989
Appendix L Inorganic chemicals manufactured in large tonnages worldwide	991

Appendix M Minerals used in large amounts	993
Appendix N Hardness of minerals – Mohs' scale	995
Appendix O Standard textbooks	997
Index	999

## Preface to the fifth edition

It is 32 years since the first edition of *Concise Inorganic Chemistry* – a long life for any book. The size of the book has gradually but inevitably grown, but I am pleased that this, the fifth edition, is no larger than the fourth edition. Robert Baden Powell (the founder of the Scout movement) said 'So much to do, so little time to do it'. I might paraphrase this to 'So much to write, so little space to write it'. Perhaps the size has reached a plateau and who knows – a future edition may be smaller!

The aims of the fifth edition remain exactly the same as those of the first edition.

- To provide a modern textbook of inorganic chemistry that is long enough to cover the essentials, yet short enough to be interesting
- To provide a simple and logical framework into which the reader should be able to fit factual knowledge, and extrapolate from this to predict unknown facts
- To fill the gap between school books and final year honours degree chemistry texts
- The book is aimed primarily at first or second year degree students in chemistry at UK universities, but will also be useful for those doing chemistry as ancillary subjects, and also for BTECH courses and Part I Grad RIC in technical colleges. Some parts will be usable by good sixth form students
- Above all it is intended to be easy to read and understand, and is based on descriptive chemistry combined with some of the reasons why

The structure of the book is unchanged, comprising six sections: theoretical concepts and hydrogen, s block, p-block, d-block, f block, and other topics. As previously, there is a very large and comprehensive index, and a large table of contents. Every chapter has been updated and the groups of elements are now labelled from 1 to 18 in accordance with IUPAC nomenclature. Descriptive material necessarily has a large place, but the book attempts to show the reasons for the structure, properties and reactions of compounds, wherever this is possible with elementary methods. Most chapters include a section on further reading, with easy to

understand articles (in journals such as the *Journal of Chemical Education*, *Chemistry in Britain* and *Education in Chemistry*), references to specialized textbooks, and review articles (such as *Quarterly Reviews*, *Coordination Chemistry Reviews*, and the proceedings of specialist conferences and symposia). There is a very small number of references to articles in the primary literature, where these have special or historical significance. Examples include the use of Ellingham diagrams, the Sidgwick–Powell theory of molecular shape, and the discovery of ferrocene and of warm superconductors.

Chemistry has always been, and still is, a practical subject. The adage 'where there's muck there's money' holds particularly true for the chemical industry. Unless chemicals were needed and used in large amounts there would be no chemical industry, and hence no students in chemistry, no teachers of chemistry, and no need for textbooks. An American professor told me he divided inorganic chemistry books into two types: theoretical and practical. In deciding how to classify any particular book, he first looked to see if the extraction of the two most produced metals (Fe and Al) was adequately covered, what impurities were likely to be present, and how the processing was adapted to remove them. Second, he looked to see if the treatment of the bonding in xenon compounds and ferrocene was longer than that of the production of ammonia. Third, he looked to see if the production and uses of phosphates were covered adequately. This book is intentionally what my American friend would call the 'practical' type. For some years there has been a trend for chemistry teaching to become more theoretical. There is always theoretical interest in another interesting oxidation state or another unusual complex, but the balance of this book is tilted to ensure that they do not exclude the commonplace, the mundane and the commercially important.

I think it is important that students are aware of which chemicals are commercially important, especially those produced in very large tonnages. Linked to this is what are they used for, the processes by which they are manufactured and where the raw materials come from. This relates college chemistry to the real world, but regrettably few books cover these details. The data on tonnages of chemicals produced and the main sources of minerals have been completely updated. Data are mainly from *World Mineral Statistics*, published by the British Geological Survey, and from the *Industrial Statistics Yearbook* published by the United Nations, New York, and from direct contact with about 250 firms. The figures vary only slightly from year to year, and illustrate the general scale of use and main sources of raw materials. Not only is the production of major chemicals such as  $\text{H}_2\text{SO}_4$ ,  $\text{NH}_3$ ,  $\text{NaOH}$ ,  $\text{Cl}_2$ ,  $\text{O}_2$  and  $\text{N}_2$  adequately covered, but other important materials such as cement and steel, polymers such as polythene, silicones and teflon, soap and detergents are also covered.

Chemistry is exciting, and is going on all around us. Many smaller scale but fascinating applications are also described and explained. These include baking powder, photography, superconductors, transistors, photocopiers, carbon dating, the atomic bomb, uses of radioisotopes and many

others. There is currently a greater awareness of environmental issues. Problems such as freons and the ozone layer, chlorinated fluorocarbon replacements, the greenhouse effect, acid rain, lead pollution, the toxic effects of tin and mercury, asbestos, excessive use of phosphates and nitrates, and the toxic effects of various materials in drinking water are discussed. Other sections cover the development of the atomic bomb and the peaceful uses of atomic energy.

While much inorganic chemistry remains the same, it is a living subject and the approach to our current thinking and the direction of future work have altered. In particular, our ideas on bonding have changed. Until 1950 inorganic chemistry was largely descriptive. The research and development which led to the production of the atomic bomb in 1946 is probably the greatest chemical achievement of the century. The impetus from this led to the discovery of many new elements in the actinide and lanthanide series. This was followed by a period of great interest in physical inorganic chemistry, where instead of just observing what happened we looked for the reasons why. Thermodynamics and kinetics were applied to chemical reactions, and magnetism and UV-visible spectroscopy were explored. There was a flurry of activity when it was found that the noble gases really did form compounds. This was followed by a concentrated phase of preparing organometallic compounds and attempting to explain the bonding in these compounds, many of which defied rational explanation by existing theories. Future developments seem likely to fall in two main areas, bioinorganic chemistry and new materials. Much bioinorganic work is in progress into how enzymes and catalysts function, how haemoglobin and chlorophyll really work, and how bacteria incorporate atmospheric nitrogen so easily when we find it so difficult. Work on new materials includes the production of polymers, alloys, superconductors and semiconductors. I hope that the book will not only help students to pass examinations, but that it will help them understand the subject, and stimulate them to study the subject further.

This book is mainly about the chemistry of the elements, which is properly regarded as inorganic chemistry. I consider it unhelpful for students to put information into rigid compartments, since the ideas in one subject may well relate to other subjects, and the boundaries between subjects are partly artificial. The book incorporates information on the chemistry of the elements regardless of the source of that chemistry. Thus, in places the book crosses boundaries into analytical chemistry, biochemistry, materials science, nuclear chemistry, organic chemistry, physics and polymer chemistry. It is worth remembering that in 1987 the Nobel Prize for Chemistry was given for work on complexes using crowns and crypts which have biological overtones, and the Nobel Prize for Physics was for discoveries in the field of warm superconductors. Both involve chemistry. One could ask if the fullerenes were inorganic or organic compounds!

It is inevitable in a book of this size and complexity that there will be occasional errors. These are mine alone, and I will endeavour to correct

them in future editions. I am always pleased to hear from readers. The final paragraph from the Preface to the First Edition is printed unchanged:

A large amount of chemistry is quite easy, but some is enormously difficult. I can find no better way to conclude than that by the late Professor Silvanus P. Thompson in his book *Calculus Made Easy*, 'I beg to present my fellow fools with the parts that are not hard. Master these thoroughly, and the rest will follow. What one fool can do, another can.'

J.D. Lee  
Loughborough 1996

## SI UNITS

SI units for energy are used throughout the fifth edition, thus making a comparison of thermodynamic properties easier. Ionization energies are quoted in  $\text{kJ mol}^{-1}$ , rather than ionization potentials in eV. Older data from other sources use eV and may be converted into SI units ( $1 \text{ kcal} = 4.184 \text{ kJ}$ , and  $1 \text{ eV} = 23.06 \times 4.184 \text{ kJ mol}^{-1}$ ).

Metres are strictly the SI units for distance, and bondlengths are sometimes quoted in nanometres ( $1 \text{ nm} = 10^{-9} \text{ m}$ ). However ångström units Å ( $10^{-10} \text{ m}$ ) are a permitted unit of length and are widely used by crystallographers because they give a convenient range of numbers for bondlengths. Most bonds are between 1 and 2 Å (0.1 to 0.2 nm). Ångström units are used throughout for bondlengths.

The positions of absorption peaks in spectra are quoted in wave numbers  $\text{cm}^{-1}$ , because instruments are calibrated in these units. It must be remembered that these are not SI units and should be multiplied by 100 to give SI units of  $\text{m}^{-1}$ , or multiplied by 11.96 to give  $\text{J mol}^{-1}$ .

The SI units of density are  $\text{kg m}^{-3}$ , making the density of water  $1000 \text{ kg m}^{-3}$ . This convention is not widely accepted so the older units of  $\text{g cm}^{-3}$  are retained so water has a density of  $1 \text{ g cm}^{-3}$ .

In the section on magnetism both SI units and Debye units are given, and the relation between the two is explained. For inorganic chemists who simply want to find the number of unpaired electron spins in a transition metal ion then Debye units are much more convenient.



# NOMENCLATURE IN THE PERIODIC TABLE

For a long time chemists have arranged the elements in groups within the periodic table in order to relate the electronic structures of the elements to their properties, and to simplify learning. There have been several methods of naming the groups.

A number of well known books name the main groups and the transition elements as A and B subgroups, which dates back to the older Mendeleef periodic table of half a century ago. Its disadvantages are that it may overemphasize slight similarities between the A and B subgroups, and there are a large number of elements in Group VIII.

In earlier versions of this book the *s*-block and the *p*-block were numbered as groups I to VII and 0, depending on the number of electrons in the outer shell of the atoms, and the transition elements were dealt with as triads of elements and named as the top element in each group of three.

The IUPAC has recommended that the main groups and the transition metals should be numbered from 1 to 18. This system has gained acceptance, and has now been adopted throughout this book.

Names of the various groups

I	II											III	IV	V	VI	VII	0
IA	IIA	IIIA	IVA	VA	VIA	VIIA	⟨--- VIII ---⟩			IB	IIB	IIIB	IVB	VB	VIB	VIIB	0'
H Li Na K Rb Cs	Be Mg Ca Sr Ba	Sc Y La	Ti Zr Hf	V Nb Ta	Cr Mo W	Mn Tc Re	Fe Ru Os	Co Rh Ir	Ni Pd Pt	Cu Ag Au	Zn Cd Hg	B Al Ga In Tl	C Si Ge Sn Pb	N P As Sb Bi	O S Se Te Po	F Cl Br I At	He Ne Ar Kr Xe Rn
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18

# **Theoretical Concepts and Hydrogen**

## **Part One**

# Atomic structure and the periodic table

# 1


## THE ATOM AS A NUCLEUS WITH ORBITAL ELECTRONS

All atoms consist of a central nucleus surrounded by one or more orbital electrons. The nucleus always contains protons and all nuclei heavier than hydrogen contain neutrons too. The protons and neutrons together make up most of the mass of the atom. Both protons and neutrons are particles of unit mass, but a proton has one positive charge and a neutron is electrically neutral (i.e. carries no charge). Thus the nucleus is always positively charged. The number of positive charges on the nucleus is exactly balanced by an equal number of orbital electrons, each of which carries one negative charge. Electrons are relatively light – about  $1/1836$  the mass of a proton. The 103 or so elements at present known are all built up from these three fundamental particles in a simple way.

Hydrogen is the first and most simple element. It consists of a nucleus containing one proton and therefore has one positive charge, which is balanced by one negatively charged orbital electron. The second element is helium. The nucleus contains two protons, and so has a charge of +2. The nuclear charge of +2 is balanced by two negatively charged orbital electrons. The nucleus also contains two neutrons, which minimize the repulsion between the protons in the nucleus, and increase the mass of the atom. All nuclei heavier than hydrogen contain neutrons, but the number present cannot be predicted reliably.

This pattern is repeated for the rest of the elements. Element 3, lithium, has three protons in the nucleus (plus some neutrons). The nuclear charge is +3 and is balanced by three orbital electrons. Element 103, lawrencium, has 103 protons in the nucleus (plus some neutrons). The nuclear charge is +103 and is balanced by 103 orbital electrons. The number of positive charges on the nucleus of an atom always equals the number of orbital electrons, and is called the atomic number of the element.

In the simple planetary theory of the atom, we imagine that these electrons move round the nucleus in circular orbits, in much the same way as the planets orbit round the sun. Thus hydrogen and helium (Figure 1.1) have one and two electrons respectively in their first orbit. The first orbit is then full. The next eight atoms are lithium, beryllium, boron, carbon,



**Figure 1.1** Structures of (a) hydrogen, symbol H, atomic number 1; and (b) helium, symbol He, atomic number 2.




Figure 1 2 Structures of the elements lithium to neon

nitrogen, oxygen, fluorine and neon. Each has one more proton in the nucleus than the preceding element, and the extra electrons go into a second orbit (Figure 1 2). This orbit is then full. In the next eight elements (with atomic numbers 11 to 18), the additional electrons enter a third shell.

The negatively charged electrons are attracted to the positive nucleus by electrostatic attraction. An electron near the nucleus is strongly attracted by the nucleus and has a low potential energy. An electron distant from the nucleus is less firmly held and has a high potential energy.

### ATOMIC SPECTRA OF HYDROGEN AND THE BOHR THEORY

When atoms are heated or subjected to an electric discharge, they absorb energy, which is subsequently emitted as radiation. For example, if sodium chloride is heated in the flame of a Bunsen burner, sodium atoms are produced which give rise to the characteristic yellow flame coloration. (There are two lines in the emission spectrum of sodium corresponding to wavelengths of 589.0 nm and 589.6 nm.) Spectroscopy is a study of either the radiation absorbed or the radiation emitted. Atomic spectroscopy is an important technique for studying the energy and the arrangement of electrons in atoms.

If a discharge is passed through hydrogen gas ( $H_2$ ) at a low pressure, some hydrogen atoms ( $H$ ) are formed, which emit light in the visible region. This light can be studied with a spectrometer, and is found to comprise a series of lines of different wavelengths. Four lines can be seen by eye, but many more are observed photographically in the ultraviolet region. The lines become increasingly close together as the wavelength ( $\lambda$ ) decreases, until the continuum is reached (Figure 1 3). Wavelengths, in metres, are related to the frequency,  $\nu$ , in Hertz (cycles/second) by the equation

$$\nu = \frac{c}{\lambda}$$




Figure 1.3 Spectrum of hydrogen in the visible region (Balmer series.)

where  $c$  is the velocity of light ( $2.9979 \times 10^8 \text{ m s}^{-1}$ ). In spectroscopy, frequencies are generally expressed as wave numbers  $\bar{\nu}$ , where  $\bar{\nu} = 1/\lambda \text{ m}^{-1}$ .

In 1885 Balmer showed that the wave number  $\bar{\nu}$  of any line in the visible spectrum of atomic hydrogen could be given by the simple empirical formula:

$$\bar{\nu} = R \left( \frac{1}{2^2} - \frac{1}{n^2} \right)$$

where  $R$  is the Rydberg constant and  $n$  has the values 3, 4, 5..., thus giving a series of lines.

The lines observed in the visible region are called the Balmer series, but several other series of lines may be observed in different regions of the spectrum (Table 1.1).

Similar equations were found to hold for the lines in the other series in the hydrogen spectrum.

$$\text{Lyman} \quad \bar{\nu} = R \left( \frac{1}{1^2} - \frac{1}{n^2} \right) \quad n = 2, 3, 4, 5 \dots$$

$$\text{Balmer} \quad \bar{\nu} = R \left( \frac{1}{2^2} - \frac{1}{n^2} \right) \quad n = 3, 4, 5, 6 \dots$$

Table 1.1 Spectral series found in atomic hydrogen

	Region of spectrum
Lyman series	ultraviolet
Balmer series	visible/ultraviolet
Paschen series	infrared
Brackett series	infrared
Pfund series	infrared
Humphries series	infrared

$$\text{Paschen} \quad \bar{\nu} = R \left( \frac{1}{3^2} - \frac{1}{n^2} \right) \quad n = 4, 5, 6, 7$$

$$\text{Brackett} \quad \bar{\nu} = R \left( \frac{1}{4^2} - \frac{1}{n^2} \right) \quad n = 5, 6, 7, 8$$

$$\text{Pfund} \quad \bar{\nu} = R \left( \frac{1}{5^2} - \frac{1}{n^2} \right) \quad n = 6, 7, 8, 9$$

In the early years of this century, attempts were made to obtain a physical picture of the atom from this and other evidence. Thomson had shown in 1896 that the application of a high electrical potential across a gas gave electrons, suggesting that these were present in atoms. Rutherford suggested from alpha particle scattering experiments that an atom consisted of a heavy positively charged nucleus with a sufficient number of electrons round it to make the atom electrically neutral. In 1913, Niels Bohr combined these ideas and suggested that the atomic nucleus was surrounded by electrons moving in orbits like planets round the sun. He was awarded the Nobel Prize for Physics in 1922 for his work on the structure of the atom. Several problems arise with this concept.

- 1 The electrons might be expected to slow down gradually
- 2 Why should electrons move in an orbit round the nucleus?
- 3 Since the nucleus and electrons have opposite charges, they should attract each other. Thus one would expect the electrons to spiral inwards until eventually they collide with the nucleus.

To explain these problems Bohr postulated

- 1 An electron did not radiate energy if it stayed in one orbit, and therefore did not slow down.
- 2 When an electron moved from one orbit to another it either radiated or absorbed energy. If it moved towards the nucleus energy was radiated and if it moved away from the nucleus energy was absorbed.
- 3 For an electron to remain in its orbit the electrostatic attraction between the electron and the nucleus which tends to pull the electron towards the nucleus must be equal to the centrifugal force which tends to throw the electron out of its orbit. For an electron of mass  $m$ , moving with a velocity  $v$  in an orbit of radius  $r$

$$\text{centrifugal force} = \frac{mv^2}{r}$$

If the charge on the electron is  $e$ , the number of charges on the nucleus  $Z$ , and the permittivity of a vacuum  $\epsilon_0$

$$\text{Coulombic attractive force} = \frac{Ze^2}{4\pi\epsilon_0 r^2}$$

so

$$\frac{mv^2}{r} = \frac{Ze^2}{4\pi\epsilon_0 r^2} \quad (1.1)$$

hence

$$v^2 = \frac{Ze^2}{4\pi\epsilon_0 mr} \quad (1.2)$$

According to Planck's quantum theory, energy is not continuous but is discrete. This means that energy occurs in 'packets' called quanta, of magnitude  $h/2\pi$ , where  $h$  is Planck's constant. The energy of an electron in an orbit, that is its angular momentum  $mvr$ , must be equal to a whole number  $n$  of quanta.

$$mvr = \frac{nh}{2\pi}$$

$$v = \frac{nh}{2\pi mr}$$

$$v^2 = \frac{n^2 h^2}{4\pi^2 m^2 r^2}$$

Combining this with equation (1.2)

$$\frac{Ze^2}{4\pi\epsilon_0 mr} = \frac{n^2 h^2}{4\pi^2 m^2 r^2}$$

hence

$$r = \frac{\epsilon_0 n^2 h^2}{\pi m e^2 Z} \quad (1.3)$$

For hydrogen the charge on the nucleus  $Z = 1$ , and if

$$n = 1 \text{ this gives a value } r = 1^2 \times 0.0529 \text{ nm}$$

$$n = 2 \quad r = 2^2 \times 0.0529 \text{ nm}$$

$$n = 3 \quad r = 3^2 \times 0.0529 \text{ nm}$$

This gives a picture of the hydrogen atom where an electron moves in circular orbits of radius proportional to  $1^2, 2^2, 3^2, \dots$ . The atom will only radiate energy when the electron jumps from one orbit to another. The kinetic energy of an electron is  $-\frac{1}{2}mv^2$ . Rearranging equation (1.1)

$$E = -\frac{1}{2}mv^2 = -\frac{Ze^2}{8\pi\epsilon_0 r}$$

Substituting for  $r$  using equation (1.3)

$$E = -\frac{Z^2 e^4 m}{8\epsilon_0^2 n^2 h^2}$$

If an electron jumps from an initial orbit  $i$  to a final orbit  $f$ , the change in energy  $\Delta E$  is

$$\Delta E = \left( -\frac{Z^2 e^4 m}{8 \epsilon_0^2 n_f^2 h^2} \right) - \left( -\frac{Z^2 e^4 m}{8 \epsilon_0^2 n_i^2 h^2} \right)$$

$$= \frac{Z^2 e^4 m}{8 \epsilon_0^2 h^2} \left( \frac{1}{n_i^2} - \frac{1}{n_f^2} \right)$$

Energy is related to wavelength ( $E = hc\bar{\nu}$  so this equation is of the same form as the Rydberg equation

$$\bar{\nu} = \frac{Z^2 e^4 m}{8 \epsilon_0^2 h^3 c} \left( \frac{1}{n_i^2} - \frac{1}{n_f^2} \right) \quad (1.4)$$

$$\bar{\nu} = R \left( \frac{1}{n_i^2} - \frac{1}{n_f^2} \right) \quad (\text{Rydberg equation})$$

Thus the Rydberg constant

$$R = \frac{Z^2 e^4 m}{8 \epsilon_0^2 h^3 c}$$

The experimental value of  $R$  is  $1.097373 \times 10^7 \text{ m}^{-1}$ , in good agreement with the theoretical value of  $1.096776 \times 10^7 \text{ m}^{-1}$ . The Bohr theory provides an explanation of the atomic spectra of hydrogen. The different series of spectral lines can be obtained by varying the values of  $n_i$  and  $n_f$  in equation (1.4). Thus with  $n_f = 1$  and  $n_i = 2, 3, 4, \dots$  we obtain the Lyman series of lines in the UV region. With  $n_f = 2$  and  $n_i = 3, 4, 5, \dots$  we get the Balmer series of lines in the visible spectrum. Similarly,  $n_f = 3$  and  $n_i = 4, 5, 6, \dots$  gives the Paschen series,  $n_f = 4$  and  $n_i = 5, 6, 7, \dots$  gives the Brackett series, and  $n_f = 6$  and  $n_i = 7, 8, 9, \dots$  gives the Pfund series. The various transitions which are possible between orbits are shown in Figure 1.4.

## REFINEMENTS TO THE BOHR THEORY

It has been assumed that the nucleus remains stationary except for rotating on its own axis. This would be true if the mass of the nucleus were infinite, but the ratio of the mass of an electron to the mass of the hydrogen nucleus is  $1/1836$ . The nucleus actually oscillates slightly about the centre of gravity, and to allow for this the mass of the electron  $m$  is replaced by the reduced mass  $\mu$  in equation (1.4)

$$\mu = \frac{mM}{m + M}$$

where  $M$  is the mass of the nucleus. The inclusion of the mass of the nucleus explains why different isotopes of an element produce lines in the spectrum at slightly different wavenumbers.

The orbits are sometimes denoted by the letters K, L, M, N counting outwards from the nucleus, and they are also numbered 1, 2, 3, 4. This number is called the principal quantum number, which is given the symbol






Figure 1.4 Bohr orbits of hydrogen and the various series of spectral lines.

$n$ . It is therefore possible to define which circular orbit is under consideration by specifying the principal quantum number.

When an electron moves from one orbit to another it should give a single sharp line in the spectrum, corresponding precisely to the energy difference between the initial and final orbits. If the hydrogen spectrum is observed with a high resolution spectrometer it is found that some of the lines reveal 'fine structure'. This means that a line is really composed of several lines close together. Sommerfeld explained this splitting of lines by assuming that some of the orbits were elliptical, and that they precessed in space round the nucleus. For the orbit closest to the nucleus, the principal quantum number  $n = 1$ , and there is a circular orbit. For the next orbit, the principal quantum number  $n = 2$ , and both circular and elliptical orbits are possible. To define an elliptical orbit, a second quantum number  $k$  is needed. The shape of the ellipse is defined by the ratio of the lengths of the major and minor axes. Thus

$$\frac{\text{major axis}}{\text{minor axis}} = \frac{n}{k}$$

$k$  is called the azimuthal or subsidiary quantum number, and may have values from 1, 2, ...  $n$ . Thus for  $n = 2$ ,  $n/k$  may have the values 2/2 (circular




Figure 1.5 Bohr-Sommerfeld orbits when  $n = 3$ .

orbit) and  $2/1$  (elliptical orbit). For the principal quantum number  $n = 3$ ,  $n/k$  may have values  $3/3$  (circular),  $3/2$  (ellipse) and  $3/1$  (narrower ellipse).

The presence of these extra orbits, which have slightly different energies from each other, accounts for the extra lines in the spectrum revealed under high resolution. The original quantum number  $k$  has now been replaced by a new quantum number  $l$ , where  $l = k - 1$ . Thus for

$$n = 1 \quad l = 0$$

$$n = 2 \quad l = 0 \text{ or } 1$$

$$n = 3 \quad l = 0 \text{ or } 1 \text{ or } 2$$

$$n = 4 \quad l = 0 \text{ or } 1 \text{ or } 2 \text{ or } 3$$

This explained why some of the spectral lines are split into two, three, four or more lines. In addition some spectral lines are split still further into two lines (a doublet). This is explained by assuming that an electron spins on its axis in either a clockwise or an anticlockwise direction. Energy is quantized, and the value of the spin angular momentum was first considered to be  $m_s \cdot h/2\pi$ , where  $m_s$  is the spin quantum number with values of  $\pm \frac{1}{2}$ . (Quantum mechanics has since shown the exact expression to be  $\sqrt{s(s+1)} \cdot h/2\pi$ , where  $s$  is either the spin quantum number or the resultant of several spins.)

Zeeman showed that if atoms were placed in a strong magnetic field additional lines appeared on the spectrum. This is because elliptical orbits can only take up certain orientations with respect to the external field, rather than precessing freely. Each of these orientations is associated with a fourth quantum number  $m$  which can have values of  $l, (l-1), \dots, 0, \dots, (-l+1), -l$ .

Thus a single line in the normal spectrum will appear as  $(2l+1)$  lines if a magnetic field is applied.

Thus in order to explain the spectrum of the hydrogen atom, four quantum numbers are needed, as shown in Table 1.2. The spectra of other atoms may be explained in a similar manner.

## THE DUAL NATURE OF ELECTRONS – PARTICLES OR WAVES

The planetary theory of atomic structure put forward by Rutherford and Bohr describes the atom as a central nucleus surrounded by electrons in

Table 1.2 The four main quantum numbers

	Symbol	Values
Principal quantum number	$n$	1, 2, 3, ...
Azimuthal or subsidiary quantum number	$l$	0, 1, ... $(n-1)$
Magnetic quantum number	$m$	$-l, \dots, 0, \dots, +l$
Spin quantum number	$m_s$	$\pm \frac{1}{2}$

certain orbits. The electron is thus considered as a particle. In the 1920s it was shown that moving particles such as electrons behaved in some ways as waves. This is an important concept in explaining the electronic structure of atoms.

For some time light has been considered as either particles or waves. Certain materials such as potassium emit electrons when irradiated with visible light, or in some cases with ultraviolet light. This is called the photoelectric effect. It is explained by light travelling as particles called photons. If a photon collides with an electron, it can transfer its energy to the electron. If the energy of the photon is sufficiently large it can remove the electron from the surface of the metal. However, the phenomena of diffraction and interference of light can only be explained by assuming that light behaves as waves. In 1924, de Broglie postulated that the same dual character existed with electrons – sometimes they are considered as particles, and at other times it is more convenient to consider them as waves. Experimental evidence for the wave nature of electrons was obtained when diffraction rings were observed photographically when a stream of electrons was passed through a thin metal foil. Electron diffraction has now become a useful tool in determining molecular structure, particularly of gases. Wave mechanics is a means of studying the build-up of electron shells in atoms, and the shape of orbitals occupied by the electrons.

### THE HEISENBERG UNCERTAINTY PRINCIPLE

Calculations on the Bohr model of an atom require precise information about the position of an electron and its velocity. It is difficult to measure both quantities accurately at the same time. An electron is too small to see and may only be observed if perturbed. For example, we could hit the electron with another particle such as a photon or an electron, or we could apply an electric or magnetic force to the electron. This will inevitably change the position of the electron, or its velocity and direction. Heisenberg stated that the more precisely we can define the position of an electron, the less certainly we are able to define its velocity, and vice versa. If  $\Delta x$  is the uncertainty in defining the position and  $\Delta v$  the uncertainty in the velocity, the uncertainty principle may be expressed mathematically as:

$$\Delta x \cdot \Delta v \geq \frac{h}{4\pi}$$

where  $h$  = Planck's constant  $\approx 6.6262 \times 10^{-34}$  J s. This implies that it is impossible to know both the position and the velocity exactly.

The concept of an electron following a definite orbit, where its position and velocity are known exactly, must therefore be replaced by the probability of finding an electron in a particular position, or in a particular volume of space. The Schrödinger wave equation provides a satisfactory description of an atom in these terms. Solutions to the wave equation are

called wave functions and given the symbol  $\psi$ . The probability of finding an electron at a point in space whose coordinates are  $x$ ,  $y$  and  $z$  is  $\psi^2(x, y, z)$ .

### THE SCHRÖDINGER WAVE EQUATION

For a standing wave (such as a vibrating string) of wavelength  $\lambda$ , whose amplitude at any point along  $x$  may be described by a function  $f(x)$ , it can be shown that

$$\frac{d^2f(x)}{dx^2} = -\frac{4\pi^2}{\lambda^2} f(x)$$

If an electron is considered as a wave which moves in only one dimension then

$$\frac{d^2\psi}{dx^2} = -\frac{4\pi^2}{\lambda^2} \psi$$

An electron may move in three directions  $x$ ,  $y$  and  $z$  so this becomes

$$\frac{\partial^2\psi}{\partial x^2} + \frac{\partial^2\psi}{\partial y^2} + \frac{\partial^2\psi}{\partial z^2} = -\frac{4\pi^2}{\lambda^2} \psi$$

Using the symbol  $\nabla$  instead of the three partial differentials, this is shortened to

$$\nabla^2\psi = -\frac{4\pi^2}{\lambda^2} \psi$$

The de Broglie relationship states that

$$\lambda = \frac{h}{mv}$$

(where  $h$  is Planck's constant,  $m$  is the mass of an electron and  $v$  its velocity), hence

$$\nabla^2\psi = -\frac{4\pi^2 m^2 v^2}{h^2} \psi$$

or

$$\nabla^2\psi + \frac{4\pi^2 m^2 v^2}{h^2} \psi = 0 \quad (1.5)$$

However, the total energy of the system  $E$  is made up of the kinetic energy  $K$  plus the potential energy  $V$

$$E = K + V$$

so

$$K = E - V$$

But the kinetic energy  $= \frac{1}{2}mv^2$  so

$$\frac{1}{2}mv^2 = E - V$$

and

$$v^2 = \frac{2}{m} (E - V)$$

Substituting for  $v^2$  in equation (1.5) gives the well-known form of the Schrödinger equation

$$\nabla^2\psi + \frac{8\pi^2m}{h^2} (E - V)\psi = 0$$

Acceptable solutions to the wave equation, that is solutions which are physically possible, must have certain properties:

1.  $\psi$  must be continuous.
2.  $\psi$  must be finite.
3.  $\psi$  must be single valued.
4. The probability of finding the electron over all the space from plus infinity to minus infinity must be equal to one.

The probability of finding an electron at a point  $x, y, z$  is  $\psi^2$ , so

$$\int_{-\infty}^{+\infty} \psi^2 dx dy dz = 1$$

Several wave functions called  $\psi_1, \psi_2, \psi_3 \dots$  will satisfy these conditions to the wave equation, and each of these has a corresponding energy  $E_1, E_2, E_3 \dots$ . Each of these wave functions  $\psi_1, \psi_2$ , etc. is called an *orbital*, by analogy with the *orbits* in the Bohr theory. In a hydrogen atom, the single electron normally occupies the lowest of the energy levels  $E_1$ . This is called the ground state. The corresponding wave function  $\psi_1$  describes the orbital, that is the volume in space where there is a high probability of finding the electron.

For a given type of atom, there are a number of solutions to the wave equation which are acceptable, and each orbital may be described uniquely by a set of three quantum numbers,  $n, l$  and  $m$ . (These are the same quantum numbers – principal, subsidiary and magnetic – as were used in the Bohr theory).

The subsidiary quantum number  $l$  describes the shape of the orbital occupied by the electron.  $l$  may have values 0, 1, 2 or 3. When  $l = 0$ , the orbital is spherical and is called an *s* orbital; when  $l = 1$ , the orbital is dumb-bell shaped and is called a *p* orbital; when  $l = 2$ , the orbital is double dumb-bell shaped and is called a *d* orbital; and when  $l = 3$  a more complicated *f* orbital is formed (see Figure 1.6). The letters *s, p, d* and *f* come from the spectroscopic terms *sharp, principal, diffuse* and *fundamental*, which were used to describe the lines in the atomic spectra.

Examination of a list of all the allowed solutions to the wave equation shows that the orbitals fall into groups.

In the first group of solutions the value of the wave function  $\psi$ , and





Figure 1.6 (a) Wave functions  $\psi$  for  $s$ ,  $p$  and  $d$  atomic orbitals (Note that the + and - signs refer to symmetry, not charge) (b) Different ways of representing  $\psi^2$  for a  $2p$  orbital (as a contour diagram or as a 90% boundary surface).



hence the probability of finding the electron  $\psi^2$ , depends only on the distance  $r$  from the nucleus, and is the same in all directions.

$$\psi = f(r)$$

This leads to a spherical orbital, and occurs when the subsidiary quantum number  $l$  is zero. These are called  $s$  orbitals. When  $l = 0$ , the magnetic quantum number  $m = 0$ , so there is only one such orbital for each value of  $n$ .

In the second group of solutions to the wave equation,  $\psi$  depends both on the distance from the nucleus, and on the direction in space ( $x$ ,  $y$  or  $z$ ). Orbitals of this kind occur when the subsidiary quantum number  $l = 1$ . These are called  $p$  orbitals and there are three possible values of the magnetic quantum number ( $m = -1, 0$  and  $+1$ ). There are therefore three orbitals which are identical in energy, shape and size, which differ only in their direction in space. These three solutions to the wave equation may be written

$$\psi_x = f(r) \cdot f(x)$$

$$\psi_y = f(r) \cdot f(y)$$

$$\psi_z = f(r) \cdot f(z)$$

Orbitals that are identical in energy are termed degenerate, and thus three degenerate  $p$  orbitals occur for each of the values of  $n = 2, 3, 4, \dots$

The third group of solutions to the wave equation depend on the




Table 1.3 Atomic orbitals

Principal quantum number $n$	Subsidiary quantum number $l$	Magnetic quantum numbers $m$	Symbol
1	0	0	1s (one orbital)
2	0	0	2s (one orbital)
2	1	-1, 0, +1	2p (three orbitals)
3	0	0	3s (one orbital)
3	1	-1, 0, +1	3p (three orbitals)
3	2	-2, -1, 0, +1, +2	3d (five orbitals)
4	0	0	4s (one orbital)
4	1	-1, 0, +1	4p (three orbitals)
4	2	-2, -1, 0, +1, +2	4d (five orbitals)
4	3	-3, -2, -1, 0, +1, +2, -3	4f (seven orbitals)

distance from the nucleus  $r$  and also on two directions in space, for example

$$\psi = f(r) \cdot f(x) \cdot f(y)$$

This group of orbitals has  $l = 2$ , and these are called  $d$  orbitals. There are five solutions corresponding to  $m = -2, -1, 0, +1$  and  $+2$ , and these are all equal in energy. Thus five degenerate  $d$  orbitals occur for each of the values of  $n = 3, 4, 5, \dots$

A further set of solutions occurs when  $l = 3$ , and these are called  $f$  orbitals. There are seven values of  $m$ :  $-3, -2, -1, 0, +1, +2$  and  $+3$ , and seven degenerate  $f$  orbitals are formed when  $n = 4, 5, 6, \dots$

## RADIAL AND ANGULAR FUNCTIONS

The Schrödinger equation can be solved completely for the hydrogen atom, and for related ions which have only one electron such as  $\text{He}^+$  and  $\text{Li}^{2+}$ . For other atoms only approximate solutions can be obtained. For most calculations, it is simpler to solve the wave equation if the cartesian coordinates  $x, y$  and  $z$  are converted into polar coordinates  $r, \theta$  and  $\phi$ . The coordinates of the point A measured from the origin are  $x, y$ , and  $z$  in cartesian coordinates, and  $r, \theta$  and  $\phi$  in polar coordinates. It can be seen from Figure 1.7 that the two sets of coordinates are related by the following expressions:

$$z = r \cos \theta$$

$$y = r \sin \theta \sin \phi$$

$$x = r \sin \theta \cos \phi$$

The Schrödinger equation is usually written:

$$\nabla^2 \psi + \frac{8\pi^2 m}{h^2} (E - V) \psi = 0$$




Figure 1.7 The relationship between cartesian and polar coordinates

where

$$\nabla^2\psi = \frac{\partial^2\psi}{\partial x^2} + \frac{\partial^2\psi}{\partial y^2} + \frac{\partial^2\psi}{\partial z^2}$$

Changing to polar coordinates,  $\nabla^2\psi$  becomes

$$\frac{1}{r^2} \frac{\partial}{\partial r} \left( r^2 \frac{\partial \psi}{\partial r} \right) + \frac{1}{r^2 \sin^2 \theta} \frac{\partial^2 \psi}{\partial \phi^2} + \frac{1}{r^2 \sin \theta} \frac{\partial}{\partial \theta} \left( \sin \theta \frac{\partial \psi}{\partial \theta} \right)$$

The solution of this is of the form

$$\psi = R(r) \Theta(\theta) \Phi(\phi) \quad (1.6)$$

$R(r)$  is a function that depends on the distance from the nucleus, which in turn depends on the quantum numbers  $n$  and  $l$

$\Theta(\theta)$  is a function of  $\theta$ , which depends on the quantum numbers  $l$  and  $m$

$\Phi(\phi)$  is a function of  $\phi$ , which depends only on the quantum number  $m$

Equation (1.6) may be rewritten

$$\psi = R(r)_{nl} A_{ml}$$

This splits the wave function into two parts which can be solved separately

- 1  $R(r)$  the radial function, which depends on the quantum numbers  $n$  and  $l$
- 2  $A_{ml}$  the total angular wave function, which depends on the quantum numbers  $m$  and  $l$

The radial function  $R$  has no physical meaning, but  $R^2$  gives the probability of finding the electron in a small volume  $dv$  near the point at which  $R$  is measured. For a given value of  $r$  the number of small volumes is  $4\pi r^2$ , so the probability of the electron being at a distance  $r$  from the nucleus is  $4\pi r^2 R^2$ . This is called the radial distribution function. Graphs of the







Figure 1.8 Radial distribution functions for various orbitals in the hydrogen atom.

radial distribution function for hydrogen plotted against  $r$  are shown in Figure 1.8.

These diagrams show that the probability is zero at the nucleus (as  $r = 0$ ), and by examining the plots for  $1s$ ,  $2s$  and  $3s$  that the most probable distance increases markedly as the principal quantum number increases. Furthermore, by comparing the plots for  $2s$  and  $2p$ , or  $3s$ ,  $3p$  and  $3d$  it can be seen that the most probable radius decreases slightly as the subsidiary quantum number increases. All the  $s$  orbitals except the first one ( $1s$ ) have a shell-like structure, rather like an onion or a hailstone, consisting of concentric layers of electron density. Similarly, all but the first  $p$  orbitals ( $2p$ ) and the first  $d$  orbitals ( $3d$ ) have a shell structure.

The angular function  $A$  depends only on the direction, and is independent of the distance from the nucleus ( $r$ ). Thus  $A^2$  is the probability of



**Figure 1.9** Boundary surface for the angular part of the wave function  $A(\theta, \phi)$  for the 1s, 2p and 3d orbitals for a hydrogen atom shown as polar diagrams

finding an electron at a given direction  $\theta, \phi$  at any distance from the nucleus to infinity. The angular functions  $A$  are plotted as polar diagrams in Figure 1.9. It must be emphasized that *these polar diagrams do not represent the total wave function  $\psi$* , but only the angular part of the wave function. (The total wave function is made up from contributions from both the radial and the angular functions.)

$$\psi = R(r) \cdot A$$

Thus the probability of finding an electron simultaneously at a distance  $r$  and in a given direction  $\theta, \phi$  is  $\psi_{r,\theta,\phi}^2$ .

$$\psi_{r,\theta,\phi}^2 = R^2(r) \cdot A^2(\theta, \phi)$$

Polar diagrams, that is drawings of the the angular part of the wave function, are commonly used to illustrate the overlap of orbitals giving bonding between atoms. Polar diagrams are quite good for this purpose, as they show the signs  $+$  and  $-$  relating to the symmetry of the angular function. For bonding like signs must overlap. These shapes are slightly different from the shapes of the total wave function. There are several points about such diagrams:

1. It is difficult to picture an angular wave function as a mathematical equation. It is much easier to visualize a boundary surface, that is a solid shape, which for example contains 90% of the electron density. To emphasize that  $\psi$  is a continuous function, the boundary surfaces have been extended up to the nucleus in Figure 1.9. For  $p$  orbitals the electron density is zero at the nucleus, and some texts show a  $p$  orbital as two spheres which do not touch.
2. These drawings show the symmetry for the  $1s, 2p, 3d$  orbitals. However, in the others,  $2s, 3s, 4s \dots, 3p, 4p, 5p \dots, 4d, 5d \dots$  the sign (symmetry) changes inside the boundary surface of the orbital. This is readily seen as nodes in the graphs of the radial functions (Figure 1.8).




Figure 1.10 The angular part of the wave function squared  $A^2(\theta, \phi)$  for the  $2p$  orbitals for a hydrogen atom.




Figure 1.11 Total wave function (orbitals) for hydrogen

3. The probability of finding an electron at a direction  $\theta, \phi$  is the wave function squared,  $A^2$ , or more precisely  $\psi_\theta^2\psi_\phi^2$ . The diagrams in Figure 1.9 are of the angular part of the wave function  $A$ , not  $A^2$ . Squaring does not change the shape of an  $s$  orbital, but it elongates the lobes of  $p$  orbitals (Figure 1.10). Some books use elongated  $p$  orbitals, but strictly these should not have signs, as squaring removes any sign from the symmetry. Despite this, many authors draw shapes approximating to the probabilities, i.e. squared wave functions, and put the signs of the wave function on the lobes, and refer to both the shapes and the wave functions as orbitals.
4. A full representation of the probability of finding an electron requires the total wave function squared and includes both the radial and angular probabilities squared. It really needs a three-dimensional model to display this probability, and show the shapes of the orbitals. It is difficult to do this adequately on a two-dimensional piece of paper, but a representation is shown in Figure 1.11. The orbitals are not drawn to scale. Note that the  $p$  orbitals are not simply two spheres, but are ellipsoids of revolution. Thus the  $2p_x$  orbital is spherically symmetrical about the  $x$  axis, but is not spherical in the other direction. Similarly the  $p_y$  orbital is spherically symmetrical about the  $y$  axis, and both the  $p_z$  and the  $3d_{z^2}$  are spherically symmetrical about the  $z$  axis.

### PAULI EXCLUSION PRINCIPLE

Three quantum numbers  $n, l$  and  $m$  are needed to define an orbital. Each orbital may hold up to two electrons, provided they have opposite spins. An extra quantum number is required to define the spin of an electron in an orbital. Thus four quantum numbers are needed to define the energy of an electron in an atom. The Pauli exclusion principle states that no two electrons in one atom can have all four quantum numbers the same. By permutating the quantum numbers, the maximum number of electrons which can be contained in each main energy level can be calculated (see Figure 1.12).

### BUILD-UP OF THE ELEMENTS, HUND'S RULE

When atoms are in their ground state, the electrons occupy the lowest possible energy levels.

The simplest element, hydrogen, has one electron, which occupies the  $1s$  level; this level has the principal quantum number  $n = 1$ , and the subsidiary quantum number  $l = 0$ .

Helium has two electrons. The second electron also occupies the  $1s$  level. This is possible because the two electrons have opposite spins. This level is now full.

The next atom lithium has three electrons. The third electron occupies the next lowest level. This is the  $2s$  level, which has the principal quantum number  $n = 2$  and subsidiary quantum number  $l = 0$ .










Figure 1.12 Quantum numbers, the permissible number of electrons and the shape of the periodic table

The fourth electron in beryllium also occupies the  $2s$  level. Boron must have its fifth electron in the  $2p$  level as the  $2s$  level is full. The sixth electron in carbon is also in the  $2p$  level. Hund's rule states that the number of unpaired electrons in a given energy level is a maximum. Thus in the ground state the two  $p$  electrons in carbon are unpaired. They occupy separate  $p$  orbitals and have parallel spins. Similarly in nitrogen the three  $p$  electrons are unpaired and have parallel spins.

To show the positions of the electrons in an atom, the symbols  $1s$ ,  $2s$ ,  $2p$ , etc. are used to denote the main energy level and sub-level. A superscript indicates the number of electrons in each set of orbitals. Thus for hydrogen, the  $1s$  orbital contains one electron, and this is shown as  $1s^1$ . For helium the  $1s$  orbital contains two electrons, denoted  $1s^2$ . The electronic structures of the first few atoms in the periodic table may be written:

H	$1s^1$
He	$1s^2$
Li	$1s^2 2s^1$
Be	$1s^2 2s^2$
B	$1s^2 2s^2 2p^1$
C	$1s^2 2s^2 2p^2$
N	$1s^2 2s^2 2p^3$
O	$1s^2 2s^2 2p^4$
F	$1s^2 2s^2 2p^5$
Ne	$1s^2 2s^2 2p^6$
Na	$1s^2 2s^2 2p^6 3s^1$

An alternative way of showing the electronic structure of an atom is to draw boxes for orbitals, and arrows for the electrons.



Electronic structure of C atom in the ground state	1s $\uparrow\downarrow$	2s $\uparrow\downarrow$	2p $\uparrow\uparrow$		
Electronic structure of N atom in the ground state	1s $\uparrow\downarrow$	2s $\uparrow\downarrow$	2p $\uparrow\uparrow\uparrow$		
Electronic structure of O atom in the ground state	1s $\uparrow\downarrow$	2s $\uparrow\downarrow$	2p $\uparrow\downarrow\uparrow$		
Electronic structure of F atom in the ground state	1s $\uparrow\downarrow$	2s $\uparrow\downarrow$	2p $\uparrow\downarrow\uparrow\downarrow$		
Electronic structure of Ne atom in the ground state	1s $\uparrow\downarrow$	2s $\uparrow\downarrow$	2p $\uparrow\downarrow\uparrow\downarrow$	3s $\uparrow\downarrow$	3p $\uparrow\downarrow\uparrow\downarrow$
Electronic structure of Na atom in the ground state	1s $\uparrow\downarrow$	2s $\uparrow\downarrow$	2p $\uparrow\downarrow\uparrow\downarrow$	3s $\uparrow\downarrow$	3p $\uparrow\downarrow\uparrow\downarrow$

The process continues in a similar way

### SEQUENCE OF ENERGY LEVELS

It is important to know the sequence in which the energy levels are filled. Figure 1.13 is a useful aid. From this it can be seen that the order of filling of energy levels is 1s, 2s, 2p, 3s, 3p, 4s, 3d, 4p, 5s, 4d, 5p, 6s, 4f, 5d, 6p, 7s, etc.

After the 1s, 2s, 2p, 3s and 3p levels have been filled at argon, the next two electrons go into the 4s level. This gives the elements potassium and calcium. Once the 4s level is full the 3d level is the next lowest in energy, not the 3p level. Thus the 3d starts to fill at scandium. The elements from scandium to copper have two electrons in the 4s level and an incomplete 3d level, and all behave in a similar manner chemically. Such a series of atoms is known as a transition series.

A second transition series starts after the 5s orbital has been filled, at strontium, because in the next element, yttrium, the 4d level begins to fill up. A third transition series starts at lanthanum where the electrons start to fill the 5d level after the 6d level has been filled with two electrons.

A further complication arises here because after lanthanum, which has one electron in the 5d level, the 4f level begins to fill, giving the elements from cerium to lutetium with from one to 14f electrons. These are sometimes called the inner transition elements but are usually known as the lanthanides or rare earth metals.




Figure 1.13 Sequence of filling energy levels



## ARRANGEMENT OF THE ELEMENTS IN GROUPS IN THE PERIODIC TABLE

The chemical properties of an element are largely governed by the number of electrons in the outer shell, and their arrangement. If the elements are arranged in groups which have the same outer electronic arrangement, then elements within a group should show similarities in chemical and physical properties. One great advantage of this is that initially it is only necessary to learn the properties of each group rather than the properties of each individual element.

Elements with one *s* electron in their outer shell are called Group 1 (the alkali metals) and elements with two *s* electrons in their outer shell are called Group 2 (the alkaline earth metals). These two groups are known as the *s*-block elements, because their properties result from the presence of *s* electrons.

Elements with three electrons in their outer shell (two *s* electrons and one *p* electron) are called Group 13, and similarly Group 14 elements have four outer electrons, Group 15 elements have five outer electrons, Group 16 elements have six outer electrons and Group 17 elements have seven outer electrons. Group 18 elements have a full outer shell of electrons. Groups 13, 14, 15, 16, 17 and 18 all have *p* orbitals filled and because their properties are dependent on the presence of *p* electrons, they are called jointly the *p*-block elements.

In a similar way, elements where *d* orbitals are being filled are called the *d*-block, or transition, elements. In these, *d* electrons are being added to the penultimate shell. For example, the element scandium Sc is the first transition element, and follows immediately after the element calcium Ca, which is in Group 2. The outer shell of calcium contains two *s* electrons. Scandium also has two *s* electrons, but also has one *d* electron (albeit in the penultimate shell); hence the scandium group is called Group 3. Similarly, titanium Ti (the second transition element) has two *s* electrons, and also two *d* electrons (in the penultimate shell); hence the titanium group is called Group 4. Up to ten *d* electrons can be added; hence the transition metals are arranged in Group 3 to Group 12 inclusive.

Finally, elements where *f* orbitals are filling are called the *f*-block, and here the *f* electrons are entering the antepenultimate (or second from the outside) shell.

In the periodic table (Table 1.4), the elements are arranged in order of increasing atomic number, that is in order of increased nuclear charge, or increased number of orbital electrons. Thus each element contains one more orbital electron than the preceding element. Instead of listing the 103 elements as one long list, the periodic table arranges them into several horizontal rows or periods, in such a way that each row begins with an alkali metal and ends with a noble gas. The sequence in which the various energy levels are filled determines the number of elements in each period, and the periodic table can be divided into four main regions according to whether the *s*, *p*, *d* or *f* levels are being filled.

Table 1.4 The periodic table

	s-block											p-block	
Group Period	1	2											
1	<sup>1</sup> H												<sup>1</sup> H <sup>2</sup> He
2	<sup>3</sup> Li	<sup>4</sup> Be	<i>d</i> -block										<sup>5</sup> B <sup>6</sup> C <sup>7</sup> N <sup>8</sup> O <sup>9</sup> F <sup>10</sup> Ne
3	<sup>11</sup> Na	<sup>12</sup> Mg	3	4	5	6	7	8	9	10	11	12	<sup>13</sup> Al <sup>14</sup> Si <sup>15</sup> P <sup>16</sup> S <sup>17</sup> Cl <sup>18</sup> Ar
4	<sup>19</sup> K	<sup>20</sup> Ca	<sup>21</sup> Sc	<sup>22</sup> Ti	<sup>23</sup> V	<sup>24</sup> Cr	<sup>25</sup> Mn	<sup>26</sup> Fe	<sup>27</sup> Co	<sup>28</sup> Ni	<sup>29</sup> Cu	<sup>30</sup> Zn	<sup>31</sup> Ga <sup>32</sup> Ge <sup>33</sup> As <sup>34</sup> Se <sup>35</sup> Br <sup>36</sup> Kr
5	<sup>37</sup> Rb	<sup>38</sup> Sr	<sup>39</sup> Y	<sup>40</sup> Zr	<sup>41</sup> Nb	<sup>42</sup> Mo	<sup>43</sup> Tc	<sup>44</sup> Ru	<sup>45</sup> Rh	<sup>46</sup> Pd	<sup>47</sup> Ag	<sup>48</sup> Cd	<sup>49</sup> In <sup>50</sup> Sn <sup>51</sup> Sb <sup>52</sup> Te <sup>53</sup> I <sup>54</sup> Xe
6	<sup>55</sup> Cs	<sup>56</sup> Ba	<sup>57</sup> La	<sup>72</sup> Hf	<sup>73</sup> Ta	<sup>74</sup> W	<sup>75</sup> Re	<sup>76</sup> Os	<sup>77</sup> Ir	<sup>78</sup> Pt	<sup>79</sup> Au	<sup>80</sup> Hg	<sup>81</sup> Tl <sup>82</sup> Pb <sup>83</sup> Bi <sup>84</sup> Po <sup>85</sup> At <sup>86</sup> Rn
7	<sup>87</sup> Fr	<sup>88</sup> Ra	<sup>89</sup> Ac										
<i>f</i> -block													
Lanthanides			<sup>58</sup> Ce	<sup>59</sup> Pr	<sup>60</sup> Nd	<sup>61</sup> Pm	<sup>62</sup> Sm	<sup>63</sup> Eu	<sup>64</sup> Gd	<sup>65</sup> Tb	<sup>66</sup> Dy	<sup>67</sup> Ho	<sup>68</sup> Er <sup>69</sup> Tm <sup>70</sup> Yb <sup>71</sup> Lu
Actinides			<sup>88</sup> Th - <sup>91</sup> Pa	<sup>92</sup> U	<sup>93</sup> Np	<sup>94</sup> Pu	<sup>95</sup> Am	<sup>96</sup> Cm	<sup>97</sup> Bk	<sup>98</sup> Cf	<sup>99</sup> Es	<sup>100</sup> Fm <sup>101</sup> Md <sup>102</sup> No <sup>103</sup> Lr	

1st period	1s				elements in this period 2
2nd period	2s		2p		elements in this period 8
3rd period	3s		3p		elements in this period 8
4th period	4s	3d	4p		elements in this period 18
5th period	5s	4d	5p		elements in this period 18
6th period	6s	4f	5d	6p	elements in this period 32

The alkali metals appear in a vertical column labelled Group 1, in which all elements have one *s* electron in their outer shell, and hence have similar properties. Thus when one element in a group reacts with a reagent, the other elements in the group will probably react similarly, forming compounds which have similar formulae. Thus reactions of new compounds and their formulae may be predicted by analogy with known compounds. Similarly the noble gases all appear in a vertical column labelled Group 18, and all have a complete outer shell of electrons. This is called the long form of the periodic table. It has many advantages, the most important being that it emphasizes the similarity of properties within a group and the relation between the group and the electron structure. The *d*-block elements are referred to as the transition elements as they are situated between the *s*- and *p*-blocks.

Hydrogen and helium differ from the rest of the elements because there are no *p* orbitals in the first shell. Helium obviously belongs to Group 18, the noble gases, which are chemically inactive because their outer shell of electrons is full. Hydrogen is more difficult to place in a group. It could be included in Group 1 because it has one *s* electron in its outer shell, is univalent and commonly forms univalent positive ions. However, hydrogen is not a metal and is a gas whilst Li, Na, K, Rb and Cs are metals and are solids. Similarly, hydrogen could be included in Group 17 because it is one electron short of a complete shell, or in Group 14 because its outer shell is half full. Hydrogen does not resemble the alkali metals, the halogens or Group 14 very closely. Hydrogen atoms are extremely small, and have many unique properties. Thus there is a case for placing hydrogen in a group on its own.

### FURTHER READING

Karplus, M. and Porter, R.N. (1971) *Atoms and Molecules*, Benjamin, New York.  
Greenwood, N.N. (1980) *Principles of Atomic Orbitals*, Royal Institute of Chemistry Monographs for Teachers No. 8, 3rd ed., London.

### PROBLEMS

1. Name the first five series of lines that occur in the atomic spectrum of hydrogen. Indicate the region in the electromagnetic spectrum where these series occur, and give a general equation for the wavenumber applicable to all the series.

- 2 What are the assumptions on which the Bohr theory of the structure of the hydrogen atom is based?
- 3 Give the equation which explains the different series of lines in the atomic spectrum of hydrogen. Who is the equation named after? Explain the various terms involved.
- 4 (a) Calculate the radii of the first three Bohr orbits for hydrogen (Planck's constant  $h = 6.6262 \times 10^{-34} \text{ Js}$ , mass of electron  $m = 9.1091 \times 10^{-31} \text{ kg}$ , charge on electron  $e = 1.60210 \times 10^{-19} \text{ C}$ , permittivity of vacuum  $\epsilon_0 = 8.854185 \times 10^{-12} \text{ kg}^{-1} \text{ m}^{-3} \text{ A}^2$ )  
(Answers:  $0.529 \times 10^{-10} \text{ m}$ ,  $2.12 \times 10^{-10} \text{ m}$ ,  $4.76 \times 10^{-10} \text{ m}$ , that is  $0.529 \text{ \AA}$ ,  $2.12 \text{ \AA}$  and  $4.76 \text{ \AA}$ )  
(b) Use these radii to calculate the velocity of an electron in each of these three orbits  
(Answers:  $2.19 \times 10^6 \text{ ms}^{-1}$ ,  $1.09 \times 10^6 \text{ ms}^{-1}$ ,  $7.29 \times 10^5 \text{ ms}^{-1}$ )
- 5 The Balmer series of spectral lines for hydrogen appear in the visible region. What is the lower energy level that these electronic transitions start from and what transitions correspond to the spectral lines at 379.0 nm and 430.0 nm respectively?
- 6 What is the wavenumber and wavelength of the first transition in the Lyman, Balmer and Paschen series in the atomic spectra of hydrogen?
- 7 Which of the following species does the Bohr theory apply to? (a) H (b)  $\text{H}^+$  (c) He (d)  $\text{He}^+$ , (e) Li, (f)  $\text{Li}^+$  (g)  $\text{Li}^{+2}$ , (h) Be, (g)  $\text{Be}^+$ , (h)  $\text{Be}^{2+}$  (i)  $\text{Be}^{3+}$
- 8 How does the Bohr theory of the hydrogen atom differ from that of Schrodinger?
- 9 (a) Write down the general form of the Schrodinger equation and define each of the terms in it.  
(b) Solutions to the wave equation that are physically possible must have four special properties. What are they?
- 10 What is a radial distribution function? Draw this function for the 1s, 2s, 3s, 2p, 3p and 4p orbitals in a hydrogen atom.
- 11 Explain (a) the Pauli exclusion principle, and (b) Hund's rule. Show how these are used to specify the electronic arrangements of the first 20 elements in the periodic table.
- 12 What is an orbital? Draw the shapes of the 1s, 2s,  $2p_x$ ,  $2p_y$ ,  $2p_z$ ,  $3d_{xy}$ ,  $3d_x$ ,  $3d_y$ ,  $3d_{z^2}$ , and  $3d_{yz}$  orbitals.
- 13 Give the names and symbols of the four quantum numbers required to define the energy of electrons in atoms. What do these quantum numbers relate to and what numerical values are possible for each? Show how the shape of the periodic table is related to these quantum numbers.

14. The first shell may contain up to 2 electrons, the second shell up to 8, the third shell up to 18, and the fourth shell up to 32. Explain this arrangement in terms of quantum numbers.
15. Give the values of the four quantum numbers for each electron in the ground state for (a) the oxygen atom, and (b) the scandium atom. (Use positive values for  $m_l$  and  $m_s$  first.)
16. Give the sequence in which the energy levels in an atom are filled with electrons. Write the electronic configurations for the elements of atomic number 6, 11, 17 and 25, and from this decide to which group in the periodic table each element belongs.
17. Give the name and symbol for each of the atoms which have the ground state electronic configurations in their outer shells: (a)  $2s^2$ , (b)  $3s^2 3p^5$ , (c)  $3s^2 3p^6 4s^2$ , (d)  $3s^2 3p^6 3d^6 4s^2$ , (e)  $5s^2 5p^2$ , (f)  $5s^2 5p^6$ .

# 2

## Introduction to bonding

### ATTAINMENT OF A STABLE CONFIGURATION

How do atoms combine to form molecules and why do atoms form bonds? A molecule will *only be formed* if it is more stable, and has a lower energy, than the individual atoms

To understand what is happening in terms of electronic structure, consider first the Group 18 elements. These comprise the noble gases, helium, neon, argon, krypton, xenon and radon, which are noteworthy for their chemical inertness. Atoms of the noble gases do not normally react with any other atoms, and their molecules are monatomic, i.e. contain only one atom. The lack of reactivity is because the atoms already have a low energy, and it cannot be lowered further by forming compounds. The low energy of the noble gases is associated with their having a complete outer shell of electrons. This is often called a *noble gas structure*, and it is an exceptionally stable arrangement of electrons.

Normally only electrons in the outermost shell of an atom are involved in forming bonds, and by forming bonds each atom acquires a stable electron configuration. The most stable electronic arrangement is a noble gas structure, and many molecules have this arrangement. However, less stable arrangements than this are commonly attained by transition elements.

### TYPES OF BONDS

Atoms may attain a stable electronic configuration in three different ways by losing electrons, by gaining electrons, or by sharing electrons.

Elements may be divided into

- 1 Electropositive elements, whose atoms give up one or more electrons fairly readily
- 2 Electronegative elements, which will accept electrons
- 3 Elements which have little tendency to lose or gain electrons

Three different types of bond may be formed, depending on the electropositive or electronegative character of the atoms involved.

Electropositive element	}	Ionic bond
+ Electronegative element		
Electronegative element	}	Covalent bond
+ Electronegative element		
Electropositive element	}	Metallic bond
+ Electropositive element		

Ionic bonding involves the complete transfer of one or more electrons from one atom to another. Covalent bonding involves the sharing of a pair of electrons between two atoms, and in metallic bonding the valency electrons are free to move throughout the whole crystal.

These types of bonds are idealized or extreme representations, and though one type generally predominates, in most substances the bond type is somewhere between these extreme forms. For example, lithium chloride is considered to be an ionic compound, but it is soluble in alcohol, which suggests that it also possesses a small amount of covalent character. If the three extreme bond types are placed at the corners of a triangle, then compounds with bonds predominantly of one type will be represented as points near the corners. Compounds with bonds intermediate between two types will occur along an edge of the triangle, whilst compounds with bonds showing some characteristics of all three types are shown as points inside the triangle.




Figure 2.1 Triangle illustrating the transitions between ionic, covalent and metallic bonding. (Reproduced from *Chemical Constitution*, by J.A.A. Ketelaar, Elsevier.)


## TRANSITIONS BETWEEN THE MAIN TYPES OF BONDING

Few bonds are purely ionic covalent or metallic. Most are intermediate between the three main types and show some properties of at least two and sometimes of all three types.


### Ionic bonds

Ionic bonds are formed when electropositive elements react with electronegative elements.

Consider the ionic compound sodium chloride. A sodium atom has the electronic configuration  $1s^2 2s^2 2p^6 3s^1$ . The first and second shells of electrons are full, but the third shell contains only one electron. When this atom reacts it will do so in such a way that it attains a stable electron configuration. The noble gases have a stable electron arrangement and the nearest noble gas to sodium is neon, whose configuration is  $1s^2 2s^2 2p^6$ . If the sodium atom can lose one electron from its outer shell, it will attain this configuration and in doing so the sodium acquires a net charge of +1 and is called a sodium ion  $\text{Na}^+$ . The positive charge arises because the nucleus contains 11 protons, each with a positive charge, but there are now only 10 electrons. Sodium atoms tend to lose an electron in this way when they are supplied with energy, and so sodium is an electropositive element.




Chlorine atoms have the electronic configuration  $1s^2 2s^2 2p^6 3s^2 3p^5$ . They are only one electron short of the stable noble gas configuration of argon  $1s^2 2s^2 2p^6 3s^2 3p^6$ , and when chlorine atoms react they gain an electron. Thus chlorine is an electronegative element.




Through gaining an electron, an electrically neutral chlorine atom becomes a chloride ion with a net charge of -1.

When sodium and chlorine react together, the outer electron of the sodium atoms is transferred to the chlorine atoms to produce sodium ions  $\text{Na}^+$  and chloride ions  $\text{Cl}^-$ . Electrostatic attraction between the positive and negative ions holds the ions together in a crystal lattice. The process is energetically favourable as both sorts of atoms attain the stable noble gas configuration, and sodium chloride  $\text{Na}^+\text{Cl}^-$  is formed readily. This may be illustrated diagrammatically in a Lewis diagram showing the outer electrons as dots.






The formation of calcium chloride  $\text{CaCl}_2$  may be considered in a similar way. Ca atoms have two electrons in their outer shell. Ca is an electropositive element, so each Ca atom loses two electrons to two Cl atoms, forming a calcium ion  $\text{Ca}^{2+}$  and two chloride ions  $\text{Cl}^-$ . Showing the outer electrons only, this may be represented as follows:



### Covalent bonds


When two electronegative atoms react together, both atoms have a tendency to gain electrons, but neither atom has any tendency to lose electrons. In such cases the atoms share electrons so as to attain a noble gas configuration.

First consider diagrammatically how two chlorine atoms Cl react to form a chlorine molecule  $\text{Cl}_2$  (only the outer electrons are shown in the following diagrams):



Each chlorine atom gives a share of one of its electrons to the other atom. A pair of electrons is shared equally between both atoms, and each atom now has eight electrons in its outer shell (a stable octet) – the noble gas structure of argon. In this electron dot picture (Lewis structure), the shared electron pair is shown as two dots between the atoms  $\text{Cl} : \text{Cl}$ . In the valence bond representation, these dots are replaced by a line, which represents a bond  $\text{Cl}-\text{Cl}$ .


In a similar way a molecule of tetrachloromethane  $\text{CCl}_4$  is made up of one carbon and four chlorine atoms:



The carbon atom is four electrons short of the noble gas structure, so it forms four bonds, and the chlorine atoms are one electron short, so they each form one bond. By sharing electrons in this way, both the carbon and all four chlorine atoms attain a noble gas structure. It must be emphasized

that although it is possible to build up molecules in this way in order to understand their electronic structures, it does not follow that the atoms will react together directly. In this case, carbon and chlorine do not react directly, and tetrachloromethane is made by indirect reactions.

A molecule of ammonia  $\text{NH}_3$  is made up of one nitrogen and three hydrogen atoms



H

The nitrogen atom is three electrons short of a noble gas structure, and the hydrogen atoms are one electron short of a noble gas structure. Nitrogen forms three bonds, and the hydrogen atoms one bond each, so all four atoms attain a stable configuration. One pair of electrons on the N atom is not involved in bond formation and this is called a *lone pair* of electrons.

Other examples of covalent bonds include water (with two covalent bonds and two lone pairs of electrons), and hydrogen fluoride (one covalent bond and three lone pairs)



H

### Oxidation numbers


The oxidation number of an element in a covalent compound is calculated by assigning shared electrons to the more electronegative element, and then counting the theoretical charge left on each atom. (Electronegativity is described in Chapter 6.) An alternative approach is to break up (theoretically) the molecule by removing all the atoms as ions, and counting the charge left on the central atom. It must be emphasized that molecules are not really broken, nor electrons really moved. For example in  $\text{H}_2\text{O}$ , removal of two  $\text{H}^+$  leaves a charge of  $-2$  on the oxygen atom so the oxidation state of O in  $\text{H}_2\text{O}$  is  $(-II)$ . Similarly in  $\text{H}_2\text{S}$  the oxidation state of S is  $(-II)$ , in  $\text{F}_2\text{O}$  the oxidation state of O is  $(+II)$ , in  $\text{SF}_4$  the oxidation state of S is  $(+IV)$  whilst in  $\text{SF}_6$  the oxidation state of S is  $(+VI)$ . The concept of oxidation numbers works equally well with ionic compounds and in  $\text{CrCl}_3$  the Cr atom has an oxidation state of  $(+III)$  and it forms  $\text{Cr}^{3+}$  ions. Similarly in  $\text{CrCl}_2$  Cr has the oxidation state  $(+II)$  and exists as  $\text{Cr}^{2+}$  ions.

### Coordinate bonds


A covalent bond results from the sharing of a pair of electrons between two atoms where each atom contributes one electron to the bond. It is also

possible to have an electron pair bond where both electrons originate from one atom and none from the other. Such bonds are called coordinate bonds or dative bonds. Since, in coordinate bonds, two electrons are shared by two atoms, they differ from normal covalent bonds only in the way they are formed, and once formed they are identical to normal covalent bonds.


Even though the ammonia molecule has a stable electron configuration, it can react with a hydrogen ion  $H^+$  by donating a share in the lone pair of electrons, forming the ammonium ion  $NH_4^+$ :




Covalent bonds are usually shown as straight lines joining the two atoms, and coordinate bonds as arrows indicating which atom is donating the electrons. Similarly ammonia may donate its lone pair to boron trifluoride, and by this means the boron atom attains a share in eight electrons:



In a similar way, a molecule of  $BF_3$  can form a coordinate bond by accepting a share in a lone pair from a  $F^-$  ion.




There are many other examples, including:



### Double and triple bonds

Sometimes more than two electrons are shared between a pair of atoms. If four electrons are shared, then there are two bonds, and this arrangement is called a double bond. If six electrons are shared then there are three bonds, and this is called a triple bond:



### Metallic bonds and metallic structures

Metals are made up of positive ions packed together usually in one of the three following arrangements

- 1 Cubic close packed (also called face centred cubic)
- 2 Hexagonal close packed
- 3 Body centred cubic

Negatively charged electrons hold the ions together. The number of positive and negative charges are exactly balanced as the electrons originated from the neutral metal atoms. The outstanding feature of metals is their extremely high electrical conductivity and thermal conductivity both of which are because of the mobility of these electrons through the lattice.

The arrangements of atoms in the three common metallic structures are shown in Figure 2.2. Two of these arrangements (cubic close packed and hexagonal close packed) are based on the closest packing of spheres. The metal ions are assumed to be spherical and are packed together to fill the space most effectively as shown in Figure 2.3a. Each sphere touches six other spheres within this one layer.

A second layer of spheres is arranged on top of the first layer, the protruding parts of the second layer fitting into the hollows in the first layer as shown in Figure 2.4a. A sphere in the first layer touches three spheres in the layer above it and similarly touches three spheres in the layer below it plus six spheres in its own layer, making a total of 12. The coordination number or number of atoms or ions in contact with a given atom is therefore 12 for a close packed arrangement. With a close packed arrangement the spheres occupy 74% of the total space.

When adding a third layer of spheres, two different arrangements are possible, each preserving the close packed arrangement.

If the first sphere of the third layer is placed in the depression X shown in Figure 2.4a, then this sphere is exactly above a sphere in the first layer. It follows that every sphere in the third layer is exactly above a sphere in the first layer as shown in Figure 2.2a. If the first layer is represented by A and the second layer by B, the repeating pattern of close packed sheets is ABABAB. This structure has hexagonal symmetry and it is therefore said to be hexagonal close packed.

Alternatively, the first sphere of the third layer may be placed in a




Figure 2.2 The three metallic structures. (a) Hexagonal close-packed structure showing the repeat pattern of layers ABABAB... and the 12 neighbours surrounding each sphere. (b) Cubic close-packed structure (coordination number is also 12) showing repeat pattern of layers ABCABC. (c) Body-centred cubic structure showing the 8 neighbours surrounding each sphere.




Figure 2.3 Possible ways of packing equal spheres in two dimensions (a) Close packed (fills 74% of space) (b) Body centred cubic (fills 68% of space)




Figure 2.4 Superimposed layers of close packed spheres (a) Two layers of close packed spheres (second layer is shaded) (b) Three layers of close packed spheres (second layer shaded third layer bold circles) Note that the third layer is not above the first layer hence this is an ABCABC (cubic close packed) arrangement




Figure 2.5 Arrangement of 12 nearest neighbours in hexagonal and cubic close packed arrangements (Note that the top and middle layers are the same but in the cubic close packed structure the bottom layer is rotated  $60^\circ$  relative to the hexagonal close packed)

depression such as Y in Figure 2.4a. The sphere is not exactly above a sphere in the first layer and it follows that all the spheres in the third layer are not exactly above spheres in the first layer (Figure 2.4b). If the three layers are represented by A, B and C then the repeating pattern of sheets is ABCABCABC (Figure 2.2b). This structure has cubic symmetry and is said to be cubic close packed. An alternative name for this structure is face centred cubic. The difference between hexagonal and cubic close packing is illustrated in Figure 2.5.

Random forms of close packing such as ABABC or ACBACB are possible but occur only rarely. Hexagonal ABABAB and cubic ABCABC close packing are common.

The third common metallic structure is called body centred cubic (Figure 2.2c). The spheres are packed in sheets as shown in Figure 2.3b. The second layer occupies the hollows in this first sheet. The third layer occupies hollows in the second layer and the third layer is immediately above the first layer. This form of packing is less efficient at filling the space

than closest packing (compare Figures 2.3a and b). In a body-centred cubic structure the spheres occupy 68% of the total space and have a co-ordination number of 8, compared with close-packed structures where 74% of the space is occupied and the coordination number is 12. Metallic structures always have high coordination numbers.

The theories of bonding in metals and alloys are described in Chapter 5.

Metallic bonding is found not only in metals and alloys, but also in several other types of compound:

1. Interstitial borides, carbides, nitrides and hydrides formed by the transition elements (and by some of the lanthanides too). Some low oxidation states of transition metal halides also belong to this group, where the compounds show electrical conductivity, and are thought to contain free electrons in conduction bands.
2. Metal cluster compounds of the transition metals, and cluster compounds of boron, where the covalent bonding is delocalized over several atoms, and is equivalent to a restricted form of metallic bonding.
3. A group of compounds including the metal carbonyls which contain a metal-metal bond. The cluster compounds, and the compounds with metal-metal bonds, may help to explain the role of metals as catalysts.

### Melting points

Ionic compounds are typically solids and usually have high melting and boiling points. In contrast covalent compounds are typically gases, liquids or low melting solids. These differences occur because of differences in bonding and structure.

Ionic compounds are made up of positive and negative ions arranged in a regular way in a lattice. The attraction between ions is electrostatic, and is non-directional, extending equally in all directions. Melting the compound involves breaking the lattice. This requires considerable energy, and so the melting point and boiling point are usually high, and the compounds are very hard.

Compounds with covalent bonds are usually made up of discrete molecules. The bonds are directional, and strong covalent bonding forces hold the atoms together to make a molecule. In the solid, molecules are held together by weak van der Waals forces. To melt or boil the compound we only need supply the small amount of energy needed to break the van der Waals forces. Hence covalently bonded compounds are often gases, liquids or soft solids with low melting points.

In a few cases such as diamond, or silica  $\text{SiO}_2$ , the structures are covalent giant lattices instead of discrete molecules. In these cases there is a three-dimensional lattice, with strong covalent bonds in all directions. It requires a large amount of energy to break this lattice, and so diamond, silica and other materials with giant three-dimensional lattices are very hard and have high melting points.

### Conductivity

Ionic compounds conduct electricity *when the compound is melted, or in solution*. Conduction is achieved by the ions migrating towards the electrodes under the influence of an electric potential. If an electric current is passed through a solution of sodium chloride  $\text{Na}^+$  ions are attracted to the negatively charged electrode (cathode) where they gain an electron and form sodium atoms. The  $\text{Cl}^-$  ions are attracted to the positive electrode (anode) where they lose an electron and become chlorine atoms. This process is called electrolysis. The changes amount to the transfer of electrons from cathode to anode, but *conduction occurs by an ionic mechanism involving the migration of both positive and negative ions in opposite directions*.

In the solid state the ions are trapped in fixed places in the crystal lattice, and as they cannot migrate, they cannot conduct electricity in this way. It is, however, wrong to say that ionic solids do not conduct electricity without qualifying the statement. The crystal may conduct electricity *to a very small extent* by semiconduction if the crystal contains some defects. Suppose that a lattice site is unoccupied, and there is a 'hole' where an ion is missing. An ion may migrate from its lattice site to the vacant site, and in so doing it makes a 'hole' somewhere else. The new 'hole' is filled by another ion and so on, so eventually the hole migrates across the crystal and a charge is carried in the other direction. Plainly the amount of current carried by this mechanism is extremely small, but semiconductors are of great importance in modern electronic devices.

Metals conduct electricity better than any other material, but the mechanism is by the movement of electrons instead of ions.

Covalent compounds contain neither ions (as in ionic compounds) nor mobile electrons (as in metals), so they are unable to conduct electricity in either the solid, liquid or gaseous state. Covalent compounds are therefore insulators.

### Solubility


If they dissolve at all, ionic compounds are usually soluble in polar solvents. These are solvents of high dielectric constant such as water, or the mineral acids. Covalent compounds are not normally soluble in these solvents but if they dissolve at all they are soluble in non polar (organic) solvents of low dielectric constant, such as benzene and tetrachloro methane. The general rule is sometimes stated that 'like dissolves like', and so ionic compounds usually dissolve in ionic solvents, and covalent compounds usually dissolve in covalent solvents.

### Speed of reactions



Ionic compounds usually react very rapidly, whilst covalent compounds usually react slowly. For ionic reactions to occur, the reacting species are



ions, and as these already exist, they have only to collide with the other type of ion. For example, when testing a solution for chloride ions (by adding silver nitrate solution), precipitation of AgCl is very rapid.




Reactions of covalent compounds usually involve breaking a bond and then substituting or adding another group. Energy is required to break the bond. This is called the activation energy, and it often makes reactions slow. Collisions between the reactant molecules will only cause reaction if they have enough energy. For example, reduction of preparative amounts of nitrobenzene to aniline takes several hours. Similarly the reaction of  $\text{H}_2$  and  $\text{Cl}_2$  is typically slow except in direct sunlight when the mixture may explode!



It is important to realize that bonds are not necessarily 100% covalent or 100% ionic, and that bonds of intermediate character exist. If a molecule is made up of two identical atoms, both atoms have the same electronegativity, and so have an equal tendency to gain electrons. (See Chapter 6.) In such a molecule the electron pair forming the bond is equally shared by both atoms. This constitutes a 100% covalent bond, and is sometimes called a *non-polar covalent bond*.

More commonly molecules are formed between different types of atoms, and the electronegativity of the two atoms differs. Consider for example the molecules ClF and HF. Fluorine is the most electronegative atom, and it attracts electrons more strongly than any other element when covalently bonded. The bonding electrons spend more time round the F than round the other atom, so the F atom has a very small negative charge  $\delta^-$  and the atom (Cl or H) has a small positive charge  $\delta^+$ .



Though these bonds are largely covalent, they possess a small amount of ionic character, and are sometimes called *polar covalent bonds*. In such molecules, a positive charge, and an equal negative charge, are separated by a distance. This produces a permanent dipole moment in the molecule.

The dipole moment measures the tendency of the molecule to turn and line up its charges when placed in an electric field. Polar molecules have a high dielectric constant, and non-polar molecules have a low dielectric constant. The dielectric constant is the ratio of the capacitance of a condenser with the material between the plates, to the capacitance of the same condenser with a vacuum between them. By measuring the capacitance with the substance between the plates and then with a vacuum, we

can obtain the dielectric constant. Its size indicates whether the material is polar or non-polar.

Ionic, covalent and metallic bonds are considered in more detail in the following chapters.

# The ionic bond

## 3

### STRUCTURES OF IONIC SOLIDS

Ionic compounds include salts, oxides, hydroxides, sulphides, and the majority of inorganic compounds. Ionic solids are held together by the electrostatic attraction between the positive and negative ions. Plainly there will be repulsion if ions of the same charge are adjacent, and attraction will occur when positive ions are surrounded by negative ions, and vice versa. The attractive force will be a maximum when each ion is surrounded by the greatest possible number of oppositely charged ions. The number of ions surrounding any particular ion is called the coordination number. Positive and negative ions will both have the same coordination number when there are equal numbers of both types of ions, as in NaCl, but the coordination numbers for positive and negative ions are different when there are different numbers of the ions, as in  $\text{CaCl}_2$ .

### RADIUS RATIO RULES

The structures of many ionic solids can be accounted for by considering the relative sizes of the positive and negative ions, and their relative numbers. Simple geometric calculations allow us to work out how many ions of a given size can be in contact with a smaller ion. Thus we can predict the coordination number from the relative sizes of the ions.

When the coordination number is three in an ionic compound AX, three  $\text{X}^-$  ions are in contact with one  $\text{A}^+$  ion (Figure 3.1a). A limiting case arises (Figure 3.1b) when the  $\text{X}^-$  ions are also in contact with one another. By simple geometry this gives the ratio ( $\text{radius A}^+/\text{radius X}^-$ ) = 0.155. This is the lower limit for a coordination number of 3. If the radius ratio is less than 0.155 then the positive ion is not in contact with the negative ions, and it 'rattles' in the hole, and the structure is unstable (Figure 3.1c). If the radius ratio is greater than 0.155 then it is possible to fit three  $\text{X}^-$  ions round each  $\text{A}^+$  ion. As the difference in the size of the two ions increases, the radius ratio also increases, and at some point (when the ratio exceeds 0.225), it becomes possible to fit four ions round one, and so on for six ions round one, and eight ions round one. Coordination numbers of 3, 4, 6 and




Figure 3.1 Sizes of ions for coordination number 3.

Table 3 1 Limiting radius ratios and structures

Limiting radius ratio $r^+/r^-$	Coordination number	Shape
$< 0.155$	2	Linear
$0.155 \rightarrow 0.225$	3	Planar triangle
$0.225 \rightarrow 0.414$	4	Tetrahedral
$0.414 \rightarrow 0.732$	4	Square planar
$0.414 \rightarrow 0.732$	6	Octahedral
$0.732 \rightarrow 0.999$	8	Body-centred cubic

8 are common and the appropriate limiting radius ratios can be worked out by simple geometry, and are shown in Table 3 1

If the ionic radii are known the radius ratio can be calculated and hence the coordination number and shape may be predicted. This simple concept predicts the correct structure in many cases.

### CALCULATION OF SOME LIMITING RADIUS RATIO VALUES

This section may be skipped except by those interested in the origin of the limiting radius ratio values.

#### Coordination number 3 (planar triangle)

Figure 3 2a shows the smaller positive ion of radius  $r^+$  in contact with three larger negative ions of radius  $r^-$ . Plainly  $AB = BC = AC = 2r^-$ ,  $BE = r^-$ ,  $BD = r^+ + r^-$ . Further, the angle  $A-B-C$  is  $60^\circ$ , and the angle  $D-B-E$  is  $30^\circ$ . By trigonometry

$$\cos 30^\circ = BE/BD$$

$$BD = BE/\cos 30^\circ$$

$$r^+ + r^- = r^-/\cos 30^\circ = r^-/0.866 = r^- \times 1.155$$

$$r^+ = (1.155r^-) - r^- = 0.155r^-$$

hence  $r^+/r^- = 0.155$

#### Coordination number 4 (tetrahedral)

Figure 3 2b shows a tetrahedral arrangement inscribed in a cube. Part of this tetrahedral arrangement is drawn in Figure 3 2c. It can be seen that the angle  $ABC$  is the tetrahedral angle of  $109^\circ 28'$  and hence the angle  $ABD$  is half of this, that is  $54^\circ 44'$ . In the triangle  $ABD$

$$\sin ABD = 0.8164 = \frac{AD}{AB} = \frac{r^-}{r^+ + r^-}$$




Figure 3.2 Limiting radius ratios for coordination numbers 3, 4 and 6. (a) Cross-section through a planar triangle site; (b) tetrahedron inscribed in a cube; (c) diagram for tetrahedral case; (d) cross-section through an octahedral site.

taking reciprocals

$$\frac{r^+ + r^-}{r^-} + \frac{1}{0.8164} = 1.225$$

rearranging

$$\frac{r^+}{r^-} + 1 = 1.225$$


hence

$$r^+/r^- = 0.225$$


Coordination number 6 (octahedral)

A cross-section through an octahedral site is shown in Figure 3.2d, and the smaller positive ion (of radius  $r^+$ ) touches six larger negative ions (of radius  $r^-$ ). (Note that only four negative ions are shown in this section, and one is above and another below the plane of the paper.) It is obvious that  $AB = r^+ + r^-$  and  $BD = r^-$ . The angle ABC is  $45^\circ$ . In the triangle ABD


$$\cos ABD = 0.7071 = \frac{BD}{AB} = \frac{r^-}{r^+ + r^-}$$



(a)



(b)



(c)

taking reciprocals

$$\frac{r^+ + r^-}{r^-} = \frac{1}{0.7071} = 1.414$$

rearranging

$$\frac{r^+}{r^-} + 1 = 1.414$$

hence

$$r^+/r^- = 0.414$$

### CLOSE PACKING

Many common crystal structures are related to, and may be described in terms of, hexagonal or cubic close-packed arrangements. Because of their shape, spheres cannot fill space completely. In a close-packed arrangement of spheres, 74% of the space is filled. Thus 26% of the space is unoccupied, and may be regarded as holes in the crystal lattice. Two different types of hole occur. Some are bounded by four spheres and are called tetrahedral holes (marked T in Figure 3.3a), and others are bounded by six spheres and are called octahedral holes (marked O in Figure 3.3a). For every

Table 3.2 Some structures based on close packing

Formula	Type of cp	Tetrahedral	Octahedral	Coordination No	
				A	X
AX	NaCl	ccp	all	6	6
	NiAs	hcp	all	6	6
	ZnS zinc blende	ccp	$\frac{1}{2}$	4	4
	ZnS wurtzite	hcp	$\frac{1}{2}$	4	4
AX <sub>2</sub>	F <sub>2</sub> Ca* fluorite	ccp*	all	8	4
	CdI <sub>2</sub>	hcp	$\frac{1}{2}$	6	3
	CdCl <sub>2</sub>	ccp	$\frac{1}{2}$	6	3
	β-ZnCl <sub>2</sub>	hcp	$\frac{1}{4}$	4	2
	HgI <sub>2</sub>	ccp	$\frac{1}{4}$	4	2
MX <sub>3</sub>	BiI <sub>3</sub>	hcp	$\frac{1}{3}$	6	2
	CrCl <sub>3</sub>	ccp	$\frac{1}{3}$	6	2
MX <sub>4</sub>	SnI <sub>4</sub>	hcp	$\frac{1}{8}$	4	1
MX <sub>6</sub>	α-WCl <sub>6</sub> and UCl <sub>6</sub>	ccp	$\frac{1}{6}$	6	1
M <sub>2</sub> X <sub>3</sub>	α-Al <sub>2</sub> O <sub>3</sub> corundum	hcp	$\frac{2}{3}$	6	4

\* The metal ions adopt a face-centred cubic arrangement, which is exactly like cubic close packing except that the ions do not touch. (Note it is the M<sup>+</sup> ions that are almost close packed, not the negative ions as with the other examples.)

the close-packed arrangement there is one octahedral hole and two tetrahedral holes. The octahedral holes are larger than the tetrahedral holes.

An ionic structure is composed of oppositely charged ions. If the larger ions are close packed, then the smaller ions may occupy either the octahedral holes or the tetrahedral holes depending on their size. Normally the type of hole occupied can be determined from the radius ratio. An ion occupying a tetrahedral hole has a coordination number of 4, whilst one occupying an octahedral hole has a coordination number of 6. In some compounds the relative sizes of the ions are such that the smaller ions are too large to fit in the holes, and they force the larger ions out of contact with each other so that they are no longer close packed. Despite this, the relative positions of the ions remain unchanged, and it is convenient to retain the description in terms of close packing.

## CLASSIFICATION OF IONIC STRUCTURES

It is convenient to divide ionic compounds into groups AX, AX<sub>2</sub>, AX<sub>3</sub> depending on the relative numbers of positive and negative ions.

### IONIC COMPOUNDS OF THE TYPE AX (ZnS, NaCl, CsCl)

Three structural arrangements commonly found are the zinc sulphide, sodium chloride and caesium chloride structures.


#### Structures of zinc sulphide

In zinc sulphide, ZnS, the radius ratio of 0.40 suggests a tetrahedral arrangement. Each Zn<sup>2+</sup> ion is tetrahedrally surrounded by four S<sup>2-</sup> ions and each S<sup>2-</sup> ion is tetrahedrally surrounded by four Zn<sup>2+</sup> ions. The coordination number of both ions is 4, so this is called a 4:4 arrangement. Two different forms of zinc sulphide exist, zinc blende and wurtzite (Figure 3.4). Both are 4:4 structures.

These two structures may be considered as close-packed arrangements of S<sup>2-</sup> ions. Zinc blende is related to a cubic close-packed structure whilst wurtzite is related to a hexagonal close-packed structure. In both structures the Zn<sup>2+</sup> ions occupy tetrahedral holes in the lattice. Since there are twice as many tetrahedral holes as there are S<sup>2-</sup> ions, it follows that to obtain a formula ZnS only half of the tetrahedral holes are occupied by Zn<sup>2+</sup> ions (that is every alternate tetrahedral site is unoccupied).

#### Sodium chloride structure

For sodium chloride, NaCl, the radius ratio is 0.52 and this suggests an octahedral arrangement. Each Na<sup>+</sup> ion is surrounded by six Cl<sup>-</sup> ions at the corners of a regular octahedron and similarly each Cl<sup>-</sup> ion is surrounded by six Na<sup>+</sup> ions (Figure 3.5). The coordination is thus 6:6. This structure



**Figure 3.4** Structures of ZnS: (a) zinc blende and (b) wurtzite. (Reproduced with permission from Wells, A.F., *Structural Inorganic Chemistry*, 5th ed., Oxford University Press, Oxford, 1984.)




Figure 3 5 Rock salt (NaCl) structure (Reproduced by permission of Wells A F *Structural Inorganic Chemistry* 5th ed, Oxford University Press Oxford 1984 )




Figure 3 6 Caesium chloride (CsCl) structure (Reproduced by permission of Wells A F *Structural Inorganic Chemistry* 5th ed, Oxford University Press 1984 )




Figure 3 7 Fluorite (CaF<sub>2</sub>) structure (Reproduced by permission of Wells A F, *Structural Inorganic Chemistry*, 5th ed, Oxford University Press Oxford, 1984 )

may be regarded as a cubic close packed array of Cl<sup>-</sup> ions, with Na<sup>+</sup> ions occupying all the octahedral holes

### Caesium chloride structure

In caesium chloride CsCl, the radius ratio is 0.93. This indicates a body centred cubic type of arrangement, where each Cs<sup>+</sup> ion is surrounded by eight Cl<sup>-</sup> ions and vice versa (Figure 3 6). The coordination is thus 8/8. Note that this structure is not close packed and is not strictly body centred cubic.

In a body centred cubic arrangement the atom at the centre of the cube is identical to those at the corners. This structure is found in metals, but in CsCl if the ions at the corners are Cl<sup>-</sup> then there will be a Cs<sup>+</sup> ion at the body centred position so it is not strictly body centred cubic. The caesium chloride structure should be described as a *body centred cubic type of arrangement* and not *body centred cubic*.

### IONIC COMPOUNDS OF THE TYPE AX<sub>2</sub> (CaF<sub>2</sub>, TiO<sub>2</sub>, SiO<sub>2</sub>)

The two most common structures are fluorite, CaF<sub>2</sub> (Figure 3 7), and rutile, TiO<sub>2</sub> (Figure 3 8), and many difluorides and dioxides have one of these structures. Another fairly common structure is one form of SiO<sub>2</sub> called  $\beta$  cristobalite (Figure 3 9). These are true ionic structures. Layer structures are formed instead if the bonding becomes appreciably covalent.

### Calcium fluoride (fluorite) structure

In fluorite each Ca<sup>2+</sup> ion is surrounded by eight F<sup>-</sup> ions, giving a body centred cubic arrangement of F<sup>-</sup> round Ca<sup>2+</sup>. Since there are twice as many F<sup>-</sup> ions as Ca<sup>2+</sup> ions, the coordination number of both ions is different, and four Ca<sup>2+</sup> ions are tetrahedrally arranged around each F<sup>-</sup> ion. The coordination numbers are therefore 8 and 4, so this is called an 8/4 arrangement. The fluorite structure is found when the radius ratio is 0.73 or above.

An alternative description of the structure is that the Ca<sup>2+</sup> ions form a face centred cubic arrangement. The Ca<sup>2+</sup> ions are too small to touch each other, so the structure is not close packed. However, the structure is related to a close packed arrangement, since the Ca<sup>2+</sup> occupy the same relative positions as for a cubic close packed structure, and the F<sup>-</sup> ions occupy all the tetrahedral holes.

### Rutile structure

TiO<sub>2</sub> exists in three forms called anatase, brookite and rutile. The rutile structure is found in many crystals where the radius ratio is between 0.41 and 0.73. This suggests a coordination number of 6 for one ion and from the formula it follows that the coordination number of the other ion must



be 3. This is a 6:3 structure. Each  $\text{Ti}^{4+}$  is octahedrally surrounded by six  $\text{O}^{2-}$  ions and each  $\text{O}^{2-}$  ion has three  $\text{Ti}^{4+}$  ions round it in a plane triangular arrangement.

The rutile structure is not close packed. The unit cell, i.e. the repeating unit of this structure, is not a cube, since one of the axes is 30% shorter than the other two. It is convenient to describe it as a considerably distorted cube (though the distortion is rather large). The structure may then be described as a considerably distorted body-centred cubic lattice of  $\text{Ti}^{4+}$  ions. Each  $\text{Ti}^{4+}$  ion is surrounded octahedrally by six  $\text{O}^{2-}$  ions, and the  $\text{O}^{2-}$  are in positions of threefold coordination, that is each  $\text{O}^{2-}$  is surrounded by three  $\text{Ti}^{4+}$  ions at the corners of an equilateral triangle. Three-coordination is not common in solids. There are no examples of three-coordination in compounds of the type  $\text{AX}$ , but there is another example in the compounds of type  $\text{AX}_2$ , that is  $\text{CdI}_2$ , though in this case the shape is not an equilateral triangle. The structure of  $\text{CaCl}_2$  is also a 6:3 structure, and is similar to  $\text{CdI}_2$ . These are described later.

There are only a few cases where the radius ratio is below 0.41. Examples include silica  $\text{SiO}_2$  and beryllium fluoride  $\text{BeF}_2$ . These have coordination numbers of 4 and 2, but radius ratio predictions are uncertain since they are appreciably covalent.

#### $\beta$ -cristobalite (silica) structure

Silica  $\text{SiO}_2$  exists in six different crystalline forms as quartz, cristobalite and tridymite, each with an  $\alpha$  and  $\beta$  form.  $\beta$ -cristobalite is related to zinc blende, with two interpenetrating close-packed lattices, one lattice arising from Si occupying the  $\text{S}^{2-}$  positions, and the other lattice from Si occupying the  $\text{Zn}^{2+}$  positions (i.e. the tetrahedral holes in the first lattice). The oxygen atoms lie midway between the Si atoms, but are shifted slightly off the line joining the Si atoms, so the bond angle  $\text{Si}-\text{O}-\text{Si}$  is not  $180^\circ$ . The radius ratio predicts a coordination number of 4, and this is a 4:2 structure.

#### LAYER STRUCTURES ( $\text{CdI}_2$ , $\text{CdCl}_2$ , $[\text{NiAs}]$ )

##### Cadmium iodide structure

Many  $\text{AX}_2$  compounds are not sufficiently ionic to form the perfectly regular ionic structures described. Many chlorides, bromides, iodides and sulphides crystallize into structures which are very different from those described. Cadmium fluoride  $\text{CdF}_2$  forms an ionic lattice with the  $\text{CaF}_2$  structure, but in marked contrast cadmium iodide  $\text{CdI}_2$  is much less ionic, and does not form the fluorite structure. The radius ratio for  $\text{CdI}_2$  is 0.45, and this indicates a coordination number of 6 for cadmium. The structure is made up of electrically neutral layers of  $\text{Cd}^{2+}$  ions with layers of  $\text{I}^-$  ions on either side – rather like a sandwich where a layer of  $\text{Cd}^{2+}$  corresponds to the meat in the middle, and layers of  $\text{F}^-$  correspond to the bread on either




Figure 3.8 Rutile ( $\text{TiO}_2$ ) structure.




Figure 3.9  $\beta$ -cristobalite structure.

side. This is called a layer structure, and it is not a completely regular ionic structure. With a sandwich, bread is separated from bread by the meat, but in a pile of sandwiches, bread from one sandwich touches bread from the next sandwich. Similarly, in  $\text{CdI}_2$  two sheets of  $\text{I}^-$  ions are separated by  $\text{Cd}^{2+}$  within a 'sandwich', but between one 'sandwich' and the next, two  $\text{I}^-$  layers are in contact. Whilst there is strong electrostatic bonding between  $\text{Cd}^{2+}$  and  $\text{I}^-$  layers, there are only weak van der Waals forces holding the adjacent layers of  $\text{I}^-$  together. The packing of layers in the crystal structure is not completely regular, and the solid is flaky, and it cleaves into two parallel sheets quite easily. This structure is adopted by many transition metal diiodides (Ti, V, Mn, Fe, Co, Zn, Cd) and by some main group diiodides and dibromides (Mg, Ca, Ge and Pb). Many hydroxides have similar layer structures ( $\text{Mg}(\text{OH})_2$ ,  $\text{Ca}(\text{OH})_2$ ,  $\text{Fe}(\text{OH})_2$ ,  $\text{Co}(\text{OH})_2$ ,  $\text{Ni}(\text{OH})_2$ , and  $\text{Cd}(\text{OH})_2$ ).

In cadmium iodide, the third layer of  $\text{I}^-$  ions is directly above the first layer, so the repeating pattern is ABABAB. The  $\text{I}^-$  ions may be regarded as an approximately hexagonal close-packed arrangement. The  $\text{Cd}^{2+}$  ions occupy half of the octahedral sites. Rather than half filling the octahedral sites in a regular way throughout the whole structure, all of the octahedral sites are filled between two  $\text{I}^-$  layers, and none of the octahedral sites is filled between the next two layers of  $\text{I}^-$  ions. All of the octahedral holes are filled between the next two layers of  $\text{I}^-$  ions, none between the next pair, and so on.




Figure 3.10 Part of two layers of cadmium iodide ( $\text{CdI}_2$ ) structure

### Cadmium chloride structure

Cadmium chloride forms a closely related layer structure, but in this the chloride ions occur approximately in a cubic close-packed arrangement (ABCABC...).

Layer structures are intermediate in type between the extreme cases of:

1. A totally ionic crystal with a regular arrangement of ions and strong electrostatic forces in all directions.
2. A crystal in which small discrete molecules are held together by weak residual forces such as van der Waals forces and hydrogen bonds.

### Nickel arsenide structure

The structure of nickel arsenide NiAs is related to the structure of  $\text{CdI}_2$ . In NiAs (Figure 3.11), the arsenic atoms form a hexagonal close-packed type of lattice with nickel atoms occupying all of the octahedral sites between all of the layers of arsenic atoms. (In  $\text{CdI}_2$  all of the octahedral sites between half of the layers are filled, whilst with NiAs all of the octahedral sites between all of the layers are filled.)

In the nickel arsenide structure each atom has six nearest neighbours of the other type of atom. Each arsenic atom is surrounded by six nickel atoms at the corners of a trigonal prism. Each nickel atom is surrounded octahedrally by six arsenic atoms, but with two more nickel atoms sufficiently close to be bonded to the original nickel atom. This structure is adopted by many transition elements combined with one of the heavier elements from the *p*-block (Sn, As, Sb, Bi, S, Se, Te) in various alloys. These are better regarded as intermetallic phases rather than true compounds. They are opaque, have metallic lustre, and sometimes have a variable composition.

For details of other ionic structures, such as perovskite and spinels, see Chapter 20 and the Further Reading (Adams, Addison, Douglas McDaniel and Alexander, Greenwood, Wells) at the end of this chapter.

### Structures containing polyatomic ions

There are many ionic compounds of types AX and  $\text{AX}_2$  where A, or X, or both ions are replaced by complex ions. When the complex ion is roughly spherical, the ions often adopt one of the more symmetrical structures described above. Ions such as  $\text{SO}_4^{2-}$ ,  $\text{ClO}_4^-$  and  $\text{NH}_4^+$  are almost spherical. In addition, the transition metal complex  $[\text{Co}(\text{NH}_3)_6]\text{I}_2$  adopts the  $\text{CaF}_2$  (fluorite) structure.  $\text{K}_2[\text{PtCl}_6]$  adopts an anti-fluorite structure, which is the same as a fluorite structure except that the sites occupied by positive and negative ions are interchanged. Both ions may be complex:  $[\text{Ni}(\text{H}_2\text{O})_6][\text{SnCl}_6]$ , for example, forms a slightly distorted CsCl structure. Other ions ( $\text{CN}^-$  and  $\text{SH}^-$ ) sometimes attain effective spherical symmetry by free rotation, or by random orientation. Examples include CsCN, TiCN and  $\text{CsSH}$ .




Figure 3.11 Nickel arsenide structure.

FACULTY OF ENGINEERING, URBAN  
 THE UNIVERSITY OF JOHANNESBURG  
 Date 20/03/2018 73812




Figure 3 12 Calcium carbide structure

Sometimes the presence of non spherical ions simply distorts the lattice. Calcium carbide has a face centred structure like NaCl, except that the linear  $C_2^{2-}$  ions are all oriented in the same direction along one of the unit cell axes. This elongates the unit cell in that direction (Figure 3 12). Similarly calcite,  $CaCO_3$ , has a structure related to NaCl, but the planar triangular  $CO_3^{2-}$  ion distorts the unit cell along a threefold axis of symmetry, rather than along one of the cell axes. Several divalent metal carbonates, a number of nitrates,  $LiNO_3$  and  $NaNO_3$ , and some borates,  $ScBO_3$ ,  $YBO_3$  and  $InBO_3$ , also have the calcite structure.

### A MORE CRITICAL LOOK AT RADIUS RATIOS

To a first approximation, the relative numbers and sizes of the ions will determine the structure of the crystal. The radius ratios of the alkali metal halides and the alkaline earth metal oxides, sulphides, selenides and tellurides are shown in Table 3 3.

All of the crystals with a radius ratio between 0.41 and 0.73 (enclosed by full line in Table 3 3) would be expected to have the sodium chloride structure. In fact all but four of the compounds listed have a sodium chloride structure at normal temperatures. A lot more compounds adopt the NaCl structure than would be predicted. The exceptions are CsCl, CsBr and CsI, which have a caesium chloride structure, and MgTe, which has a zinc sulphide structure. RbCl and RbBr are unusual since they both form a NaCl structure with a coordination number of 6 when crystallized at normal room temperatures and pressures, but they adopt a CsCl structure with a coordination number of 8 if crystallized at high pressures or temperatures. The fact that they can form both structures indicates that the difference in lattice energy between the two structures is small, and hence there is only a small difference in stability between them.

### A CAUTIONARY WORD ON RADIUS RATIOS

Radius ratios provide a useful guide to what is possible on geometric grounds, and also a first guess at the likely structure, but there are other factors involved. Radius ratios do not necessarily provide a completely reliable method for predicting which structure is actually adopted.

Table 3 3 Radius ratios of Group 1 halides and Group 2 oxides

	$F^-$	$Cl^-$	$Br^-$	$I^-$		$O^{2-}$	$S^{2-}$	$Se^{2-}$	$Te^{2-}$
$Li^+$	0.57	0.41	0.39	0.35	Be				
$Na^+$	0.77	0.55	0.52	0.46	$Mg^{2+}$	0.51	0.39	0.36	0.33
$K^+$	0.96*	0.75	0.70	0.63	$Ca^{2+}$	0.71	0.54	0.51	0.45
$Rb^+$	0.88*	0.83	0.78	0.69	$Sr^{2+}$	0.84	0.64	0.60	0.53
$Cs^+$	0.80*	0.91	0.85	0.76	$Ba^{2+}$	0.96	0.73	0.68	0.61

\* Indicates reciprocal value of  $r^-/r^+$  since the normal ratio is greater than unity

Though radius ratios indicate the correct structure in many cases, there are a significant number of exceptions where they predict the wrong structure. It is therefore worth examining the assumptions behind the radius ratio concept, to see if they are valid. The assumptions are:

1. That accurate ionic radii are known.
2. That ions behave as hard inelastic spheres.
3. That stable arrangements are only possible if the positive and negative ions touch.
4. That ions are spherical in shape.
5. That ions always adopt the highest possible coordination number.
6. That bonding is 100% ionic.

Values for ionic radii cannot be measured absolutely, but are estimated. They are not completely accurate or reliable. Though it is possible to measure the interatomic distance between two different ions very accurately by X-ray crystallography, it is much less certain how to divide the distance between the two ions to obtain ionic radii. Furthermore the radius of an ion is not constant but changes depending on its environment. In particular the radius changes when the coordination number changes. The radii usually quoted are for a coordination number of 6, but the radius effectively increases 3% when the coordination number is changed from 6 to 8, and decreases 6% when the coordination number changes from 6 to 4.

Ions are not hard inelastic spheres. They are sometimes fitted into 'holes' that are slightly too small, that is the ions are compressed, and the lattice may be distorted.

The assumption that the ions touch is necessary to calculate the critical lower limit for radius ratios. In principle positive and negative ions should touch, so as to get the ions close together, and get the maximum electrostatic attraction. (Electrostatic attraction depends on the product of the charges on the ions divided by the distance between them.) Theoretically structures where the smaller metal ion 'rattles' in its hole (that is, it does not touch the neighbouring negative ions) should be unstable. A more favourable electrostatic attraction should be obtained by adopting a different geometric arrangement with a smaller coordination number, so that the ions can get closer. It has already been shown that in the alkali halides and alkaline earth oxides the NaCl structure with coordination numbers of 6:6 is sometimes adopted when other structures are predicted by radius ratios. It follows that, since the smaller ion no longer fits the site it occupies, it must either 'rattle', or be compressed.

Are ions spherical? It is reasonable to consider ions with a noble gas structure as spherical. This includes the majority of the ions formed by elements in the main groups. There are a small number of exceptions where the ions have an inert pair ( $\text{Ga}^+$ ,  $\text{In}^+$ ,  $\text{Tl}^+$ ,  $\text{Sn}^{2+}$ ,  $\text{Pb}^{2+}$ ,  $\text{I}^+$ ,  $\text{I}^{3+}$ ). These ions do not have a centre of symmetry, and the structures they form usually show some distortion, with the metal ion slightly displaced off-centre from its expected position. Transition metal ions with partially filled  $d$  orbitals are not spherical, though in contrast to inert pair distortion they

usually have a centre of symmetry. The arrangement of electrons in these  $d$  orbitals gives rise to Jahn–Teller distortion (See Chapter 28). A partially filled  $d$  orbital pointing towards a coordinated ion will repel it. A completely filled  $d$  orbital will repel the ion even more. This can give rise to a structure with some long and some short bonds, depending on both the electronic structure of the metal ion, and the crystal structure adopted, i.e. the positions of the coordinating ions.

It is most unlikely that bonding is ever 100% ionic. The retention of a NaCl structure by a number of compounds which might be expected to adopt a CsCl structure is largely because there is a small covalent contribution to the bonding. The three  $p$  orbitals are at  $90^\circ$  to each other, and in a NaCl structure they point towards the six nearest neighbours, so covalent overlap of orbitals is possible. The geometric arrangement of the NaCl structure is ideally suited to allow some covalent contribution to bonding. This is not so for the CsCl structure.

*Thus radius ratios provide a rough guide to what structures are geometrically possible. Radius ratios often predict the correct structure, but they do not always predict the correct structure. Ultimately the reason why any particular crystal structure is formed is that it gives the most favourable lattice energy.*

## LATTICE ENERGY

The lattice energy ( $U$ ) of a crystal is the energy evolved when one gram molecule of the crystal is formed from gaseous ions.



Lattice energies cannot be measured directly, but experimental values are obtained from thermodynamic data using the Born–Haber cycle (see Chapter 6).

Theoretical values for lattice energy may be calculated. The ions are treated as point charges and the electrostatic (coulombic) energy  $E$  between two ions of opposite charge is calculated

$$E = -\frac{z^+ z^- e^2}{r}$$

where

$z^+$  and  $z^-$  are the charges on the positive and negative ions

$e$  is the charge on an electron

$r$  is the inter ionic distance

For more than two ions, the electrostatic energy depends on the number of ions and also on  $A$ , their arrangement in space. For one mole the attractive energy is

$$E = -\frac{N_A z^+ z^- e^2}{r}$$

Table 3.4 Madelung constants

Type of structure	<i>A</i>	<i>M</i>
zinc blende ZnS	1.63806	1.63806
wurtzite ZnS	1.64132	1.64132
sodium chloride NaCl	1.74756	1.74756
caesium chloride CsCl	1.76267	1.76267
rutile TiO <sub>2</sub>	2.408	4.816
fluorite CaF <sub>2</sub>	2.51939	5.03878
corundum Al <sub>2</sub> O <sub>3</sub>	4.17186	25.03116

where

$N_0$  is the Avogadro constant – the number of molecules in a mole – which has the value  $6.023 \times 10^{23} \text{ mol}^{-1}$

*A* is the Madelung constant, which depends on the geometry of the crystal

Values for the Madelung constant have been calculated for all common crystal structures, by summing the contributions of all the ions in the crystal lattice. Some values are given in Table 3.4. (It should be noted that different values from these are sometimes given where the term  $z^+z^-$  is replaced by  $z^2$ , where  $z$  is the highest common factor in the charges on the ions. The Madelung constant is rewritten  $M = Az^+z^-/z^2$ . This practice is not recommended.)

The equation for the attractive forces between the ions gives a negative value for energy, that is energy is given out when a crystal is formed. The inter-ionic distance  $r$  occurs in the denominator of the equation. Thus the smaller the value of  $r$ , the greater the amount of energy evolved when the crystal lattice is formed, and hence the more stable the crystal will be. Mathematically, the equation suggests that an infinite amount of energy should be evolved if the distance  $r$  is zero. Plainly this is not so. When the inter-ionic distance becomes small enough for the ions to touch, they begin to repel each other. This repulsion originates from the mutual repulsion of the electron clouds on the two atoms or ions. The repulsive forces increase rapidly as  $r$  decreases. The repulsive force is given by  $B/r^n$ , where  $B$  is a

Table 3.5 Average values for the Born exponent

Electronic structure of ion	<i>n</i>	Examples
He	5	Li <sup>+</sup> , Be <sup>2+</sup>
Ne	7	Na <sup>+</sup> , Mg <sup>2+</sup> , O <sup>2-</sup> , F <sup>-</sup>
Ar	9	K <sup>+</sup> , Ca <sup>2+</sup> , S <sup>2-</sup> , Cl <sup>-</sup> , Cu <sup>+</sup>
Kr	10	Rb <sup>+</sup> , Br <sup>-</sup> , Ag <sup>+</sup>
Xe	12	Cs <sup>+</sup> , I <sup>-</sup> , Au <sup>+</sup>

Average values are used, e.g. in LiCl, Li<sup>+</sup> = 5, Cl<sup>-</sup> = 9, hence for LiCl,  $n = (5 + 9)/2 = 7$

constant that depends on the structure, and  $n$  is a constant called the Born exponent. For one gram molecule the total repulsive force is  $(N_o B)/r^n$ . The Born exponent may be determined from compressibility measurements. Often chemists use a value of 9, but it is better to use values for the particular ions in the crystal.

The total energy holding the crystal together is  $U$  the lattice energy. This is the sum of the attractive and the repulsive forces.

$$U = \underbrace{-\frac{N_o A z^+ z^- e^2}{r}}_{\text{attractive force}} + \underbrace{\frac{N_o B}{r^n}}_{\text{repulsive force}} \quad (3.1)$$

( $A$  is the Madelung constant and  $B$  is a repulsion coefficient, which is a constant which is approximately proportional to the number of nearest neighbours.)

The equilibrium distance between ions is determined by the balance between the attractive and repulsion terms. At equilibrium,  $dU/dr = 0$ , and the equilibrium distance  $r = r_o$ .

$$\frac{dU}{dr} = \frac{N_o A z^+ z^- e^2}{r_o^2} - \frac{n N_o B}{r_o^{n+1}} = 0 \quad (3.2)$$

Rearranging this gives an equation for the repulsion coefficient  $B$ .

$$B = \frac{A z^+ z^- e^2 r_o^{n-1}}{n}$$

Substituting equation (3.3) into (3.1)

$$U = -\frac{N_o A z^+ z^- e^2}{r_o} \left(1 - \frac{1}{n}\right)$$

This equation is called the *Born-Landé equation*. It allows the lattice energy to be calculated from a knowledge of the geometry of the crystal, and hence the Madelung constant, the charges  $z^+$  and  $z^-$ , and the inter ionic distance. When using SI units, the equation takes the form

$$U = -\frac{N_o A z^+ z^- e^2}{4\pi\epsilon_o r_o} \left(1 - \frac{1}{n}\right) \quad (3.4)$$

where  $\epsilon_o$  is the permittivity of free space  $= 8.854 \times 10^{-12} \text{ F m}^{-1}$ .

This equation gives a calculated value of  $U = -778 \text{ kJ mol}^{-1}$  for the lattice energy for sodium chloride, which is close to the experimental value of  $-775 \text{ kJ mol}^{-1}$  at  $25^\circ\text{C}$  (obtained using the Born-Haber cycle). The experimental and theoretical values for the alkali metal halides and the oxides and halides of the alkaline earths (excluding Be), all agree within 3%.

Other expressions, for example the Born-Mayer and Kapustinskii equations, are similar, but calculate the repulsive contribution in a slightly different way. Agreement is even better if allowances are made for van der Waals forces and zero point energy.

Several important points arise from the Born-Landé equation



1. The lattice becomes stronger (i.e. the lattice energy  $U$  becomes more negative), as  $r$  the inter-ionic distance decreases.  $U$  is proportional to  $1/r$ .

	$r$ (Å)	$U$ (kJ mol <sup>-1</sup> )
LiF	2.01	-1004
CsI	3.95	-527

2. The lattice energy depends on the product of the ionic charges, and  $U$  is proportional to  $(z^+ \cdot z^-)$ .

	$r$ (Å)	$(z^+ \cdot z^-)$	$U$ (kJ mol <sup>-1</sup> )
LiF	2.01	1	-1004
MgO	2.10	4	-3933

3. The close agreement between the experimental lattice energies and those calculated by the Born–Landé equation for the alkali metal halides does not of itself prove that the equation itself, or the assumptions on which it is based, are correct. The equation is remarkably self-compensating, and tends to hide errors. There are two opposing factors in the equation. Increasing the inter-ionic distance  $r$  reduces the lattice energy. It is almost impossible to change  $r$  without changing the structure, and therefore changing the Madelung constant  $A$ . Increasing  $A$  increases the lattice energy: hence the effects of changing  $r$  and  $A$  may largely cancel each other.

This may be illustrated by choosing a constant value for  $n$  in the Born–Landé equation. Then changes in inter-ionic distance can be calculated for either changes in the coordination number, or in crystal structure. Taking a constant value of  $n = 9$ , we may compare the inter-ionic distances with those for six-coordination:

Coordination number	12	8	6	4
Ratio of inter-ionic distance	1.091	1.037	1.000	0.951

For a change of coordination number from 6 (NaCl structure) to 8 (CsCl structure) the inter-ionic distance increases by 3.7%, and the Madelung constants (NaCl  $A = 1.74756$ , and CsCl  $A = 1.76267$ ) change by only 0.9%. Thus a change in coordination number from 6 to 8 would result in a reduction in lattice energy, and in theory the NaCl structure should always be more stable than the CsCl structure. In a similar way reducing the coordination number from 6 to 4 decreases  $r$  by 4.9%. The decrease in  $A$  is 6.1% or 6.3% (depending on whether a zinc blende or wurtzite structure is formed), but in either case it more than compensates for the change in  $r$ , and in theory coordination number 6 is more stable than 4.

This suggests that neither four- nor eight-coordinate structures should exist, since the six-coordinate NaCl structure is more stable. Since ZnS is known (coordination number 4), and CsCl, CsBr and CsI have a coordination number of 8, this suggestion is plainly incorrect. We must

Table 3.6 Inter-ionic distances and ionic charges related to  $m$ ,  $p$  and hardness

	$r(\text{\AA})$	$(z^+ \ z^-)$	$m \ p \ (^{\circ}\text{C})$	Hardness (Mohs' scale)
NaF	2 310	1	990	3 2
BeO	1 65	4	2530	9 0
MgO	2 106	4	2800	6 5
CaO	2 405	4	2580	4 5
SrO	2 580	4	2430	3 5
BaO	2 762	4	1923	3 3
TiC	2 159	16	3140	8-9

therefore look for a mistake in the theoretical assumptions made. First the value of  $n$  was assumed to be 9, when it may vary from 5 to 12. Second, the calculation of electrostatic attraction assumes that the ions are point charges. Third, the assumption is made that there is no reduction in charge because of the interaction (i.e. the bonds are 100% ionic).

- 4 Crystals with a high lattice energy usually melt at high temperatures, and are very hard. Hardness is measured on Mohs' scale (See Appendix N). High lattice energy is favoured by a small inter-ionic distance, and a high charge on the ions.

It has been seen that a number of salts which might be expected from radius ratio considerations to have a CsCl structure in fact adopt a NaCl structure. The Madelung constant for CsCl is larger than for NaCl, and would give an increased lattice energy. However, the inter-ionic distance  $r$  will be larger in a CsCl type of structure than in a NaCl type of structure, and this would decrease the lattice energy. These two factors work in opposite directions and partly cancel each other. This makes the lattice energy more favourable for a NaCl type of lattice in some cases where a CsCl structure is geometrically possible. Consider a case such as RbBr where the radius ratio is close to borderline between six-coordination (NaCl structure) and eight coordination (CsCl structure). If the CsCl structure is adopted, the Madelung constant is larger than for NaCl, and *this increases the lattice energy by 0.86%*. At the same time the inter-ionic distance in a CsCl structure increases by 3%, and *this decreases the lattice energy by 3%*. Clearly the NaCl structure is preferred.

## FEATURES OF SOLIDS

The essential feature of crystalline solids is that the constituent molecules, atoms or ions are arranged in a completely regular three-dimensional pattern. Models built to show the detailed structure of crystalline materials are usually grossly misleading, for they imply a perfect static pattern. Since the atoms or ions have a considerable degree of thermal vibration, the

crystalline state is far from static, and the pattern is seldom perfect. Many of the most useful properties of solids are related to the thermal vibrations of atoms, the presence of impurities and the existence of defects.

## STOICHIOMETRIC DEFECTS

Stoichiometric compounds are those where the numbers of the different types of atoms or ions present are exactly in the ratios indicated by their chemical formulae. They obey the law of constant composition that *'the same chemical compound always contains the same elements in the same composition by weight'*. At one time these were called Daltonide compounds, in contrast to Berthollide or nonstoichiometric compounds where the chemical composition of a compound was variable, not constant.

Two types of defects may be observed in stoichiometric compounds, called Schottky and Frenkel defects respectively. At absolute zero, crystals tend to have a perfectly ordered arrangement. As the temperature increases, the amount of thermal vibration of ions in their lattice sites increases, and if the vibration of a particular ion becomes large enough, it may jump out of its lattice site. This constitutes a point defect. The higher the temperature, the greater the chance that lattice sites may be unoccupied. Since the number of defects depends on the temperature, they are sometimes called thermodynamic defects.

### Schottky defects

A Schottky defect consists of a pair of 'holes' in the crystal lattice. One positive ion and one negative ion are absent (see Figure 3.13). This sort of defect occurs mainly in highly ionic compounds where the positive and negative ions are of a similar size, and hence the coordination number is high (usually 8 or 6), for example NaCl, CsCl, KCl and KBr.

The number of Schottky defects formed per  $\text{cm}^3$  ( $n_s$ ) is given by

$$n_s = N \exp\left(-\frac{W_s}{2kT}\right)$$

where  $N$  is the number of sites per  $\text{cm}^3$  that could be left vacant,  $W_s$  is the work necessary to form a Schottky defect,  $k$  is the gas constant and  $T$  the absolute temperature.

### Frenkel defects

A Frenkel defect consists of a vacant lattice site (a 'hole'), and the ion which ideally should have occupied the site now occupies an interstitial position (see Figure 3.14).

Metal ions are generally smaller than the anions. Thus it is easier to squeeze  $A^+$  into alternative interstitial positions, and consequently it is more common to find the positive ions occupying interstitial positions. This type of defect is favoured by a large difference in size between the positive




Figure 3.13 Schottky defect.




Figure 3.14 Frenkel defect.

and negative ions, and consequently the coordination number is usually low (4 or 6). Since small positive ions are highly polarizing and large negative ions are readily polarized, these compounds have some covalent character. This distortion of ions, and the proximity of like charges, leads to a high dielectric constant. Examples of this type of defect are ZnS, AgCl, AgBr and AgI.

The number of Frenkel defects formed per  $\text{cm}^3$  ( $n_f$ ) is given by

$$n_f = \sqrt{NN'} \exp\left(-\frac{W_f}{2kT}\right)$$

where  $N$  is the number of sites per  $\text{cm}^3$  that could be left vacant,  $N'$  is the number of alternative interstitial positions per  $\text{cm}^3$ ,  $W_f$  is the work necessary to form a Frenkel defect,  $k$  is the gas constant and  $T$  the absolute temperature.

The energy needed to form either a Schottky defect or a Frenkel defect depends on the work needed to form the defect, and on the temperature. In a given compound one type generally predominates.

In NaCl, the energy to form a Schottky defect is about  $200 \text{ kJ mol}^{-1}$  compared with a lattice energy of approximately  $750 \text{ kJ mol}^{-1}$ . It is therefore much easier to form a defect than to break the lattice.

The number of defects formed is relatively small, and at room temperature NaCl has only one defect in  $10^{15}$  lattice sites, this value rising to one in  $10^6$  sites at  $500^\circ\text{C}$  and one in  $10^4$  sites at  $800^\circ\text{C}$ .

A consequence of these defects is that a crystalline solid that has defects may conduct electricity to a small extent. Electrical conductivity in a chemically pure, stoichiometric semiconductor is called '*intrinsic semiconduction*'. In the above cases, intrinsic semiconduction occurs by an ionic mechanism. If an ion moves from its lattice site to occupy a 'hole' it creates a new 'hole'. If the process is repeated many times a 'hole' may migrate across a crystal, which is equivalent to moving a charge in the opposite direction. (This type of semiconduction is responsible for the unwanted background noise produced by transistors.)

Crystals with Frenkel defects have only one type of hole, but crystals containing Schottky defects have holes from both positive and negative ions, and conduction may arise by using either one type of hole or both types. Migration of the smaller ion (usually the positive ion) into the appropriate holes is favoured at low temperatures, since moving a small

Table 3.7 Percentage of conduction by cations and anions

Temp ( $^\circ\text{C}$ )	NaF		NaCl		NaBr	
	cation %	anion %	cation %	anion %	cation %	anion %
400	100	0	100	0	98	2
500	100	0	98	2	94	6
600	92	8	91	9	89	11

ion requires less energy. However, migration of both types of ions in opposite directions (using both types of holes) occurs at high temperatures. For example, at temperatures below 500°C the alkali halides conduct by migration of the cations, but at higher temperatures both anions and cations migrate. Further, the amount of anionic conduction increases with temperature, as shown in Table 3.7.

The density of a defect lattice should be different from that of a perfect lattice. The presence of 'holes' should lower the density, but if there are too many 'holes' there may be a partial collapse or distortion of the lattice – in which case the change in density is unpredictable. The presence of ions in interstitial positions may distort (expand) the lattice and increase the unit cell dimensions.

### NONSTOICHIOMETRIC DEFECTS

Nonstoichiometric or Berthollide compounds exist over a range of chemical composition. The ratio of the number of atoms of one kind to the number of atoms of the other kind does not correspond exactly to the ideal whole number ratio implied by the formula. Such compounds do not obey the law of constant composition. There are many examples of these compounds, particularly in the oxides and sulphides of the transition elements. Thus in FeO, FeS or CuS the ratio of Fe : O, Fe : S or Cu : S differs from that indicated by the ideal chemical formula. If the ratio of atoms is not exactly 1 : 1 in the above cases, there must be either an excess of metal ions, or a deficiency of metal ions (e.g.  $\text{Fe}_{0.84}\text{O}$ – $\text{Fe}_{0.94}\text{O}$ ,  $\text{Fe}_{0.9}\text{S}$ ). Electrical neutrality is maintained either by having extra electrons in the structure, or changing the charge on some of the metal ions. This makes the structure irregular in some way, i.e. it contains defects, which are in addition to the normal thermodynamic defects already discussed.

#### Metal excess

This may occur in two different ways.

##### F-centres

A negative ion may be absent from its lattice site, leaving a 'hole' which is occupied by an electron, thereby maintaining the electrical balance (see Figure 3.15). This is rather similar to a Schottky defect in that there are 'holes' and not interstitial ions, but only one 'hole' is formed rather than a pair. This type of defect is formed by crystals which would be expected to form Schottky defects. When compounds such as NaCl, KCl, LiH or  $\delta\text{-TiO}$  are heated with excess of their constituent metal vapours, or treated with high energy radiation, they become deficient in the negative ions, and their formulae may be represented by  $\text{AX}_{1-\delta}$ , where  $\delta$  is a small fraction. The nonstoichiometric form of NaCl is yellow, and the nonstoichiometric




Figure 3.15 Metal excess defect because of absent anion.

form of KCl is blue-lilac in colour. Note the similarity with the flame colorations for Na and K.

The crystal lattice has vacant anion sites, which are occupied by electrons. Anion sites occupied by electrons in this way are called *F*-centres (*F* is an abbreviation for *Farbe*, the German word for colour). These *F*-centres are associated with the colour of the compound and the more *F*-centres present, the greater the intensity of the coloration. Solids containing *F*-centres are paramagnetic, because the electrons occupying the vacant sites are unpaired. When materials with *F*-centres are irradiated with light they become photoconductors. When electrons in the *F*-centres absorb sufficient light (or heat) energy, the electron is promoted into a conduction band, rather similar to the conduction bands present in metals. Since conduction is by electrons it is *n* type semiconduction.




Figure 3.16 Metal excess defects caused by interstitial cations

#### Interstitial ions and electrons

Metal excess defects also occur when an extra positive ion occupies an interstitial position in the lattice, and electrical neutrality is maintained by the inclusion of an interstitial electron (see Figure 3.16). Their composition may be represented by the general formula  $A_{1+\delta}X$ .

This type of defect is rather like a Frenkel defect in that ions occupy interstitial positions, but there are no 'holes', and there are also interstitial electrons. This kind of metal excess defect is much more common than the first, and is formed in crystals which would be expected to form Frenkel defects (i.e. the ions are appreciably different in size, have a low coordination number, and have some covalent character). Examples include ZnO, CdO,  $Fe_2O_3$  and  $Cr_2O_3$ .

If this type of defect oxide is heated in dioxygen, then cooled to room temperature, its conductivity decreases. This is because the dioxygen oxidizes some of the interstitial ions, and these subsequently remove interstitial electrons, which reduces the conductivity.

Crystals with either type of metal excess defect contain free electrons, and if these migrate they conduct an electric current. Since there are only a small number of defects, there are only a few free electrons that can conduct electricity. Thus the amount of current carried is very small compared with that in metals, fused salts or salts in aqueous solutions, and these defect materials are called *semiconductors*. Since the mechanism is normal electron conduction, these are called *n* type semiconductors. These free electrons may be excited to higher energy levels giving absorption spectra, and in consequence their compounds are often coloured, e.g. nonstoichiometric NaCl is yellow, nonstoichiometric KCl is lilac, and ZnO is white when cold but yellow when hot.

#### Metal deficiency

Metal deficient compounds may be represented by the general formula  $A_{1-\delta}X$ . In principle metal deficiency can occur in two ways. Both require

variable valency of the metal, and might therefore be expected with the transition metals.

#### *Positive ions absent*

If a positive ion is absent from its lattice site, the charges can be balanced by an adjacent metal ion having an extra positive charge (see Figure 3.17). Examples of this are FeO, NiO,  $\delta$ -TiO, FeS and CuI. (If an  $\text{Fe}^{2+}$  is missing from its lattice site in FeO, then there must be two  $\text{Fe}^{3+}$  ions somewhere in the lattice to balance the electrical charges. Similarly if a  $\text{Ni}^{2+}$  is missing from its lattice site in NiO, there must be two  $\text{Ni}^{3+}$  present in the lattice.)

Crystals with metal deficiency defects are semiconductors. Suppose the lattice contains  $A^+$  and  $A^{2+}$  metal ions. If an electron 'hops' from an  $A^+$  ion to the positive centre (an  $A^{2+}$  ion), the original  $A^+$  becomes a new positive centre. There has been an apparent movement of  $A^{2+}$ . With a series of similar 'hops', an electron may be transferred in one direction across the structure, and at the same time the positive hole migrates in the opposite direction across the structure. This is called positive hole, or *p-type semiconduction*.

If a defect oxide of this type is heated in dioxygen, its room temperature conductivity increases, because the dioxygen oxidizes some of the metal ions, and this increases the number of positive centres.

#### *Extra interstitial negative ions*

In principle it might be possible to have an extra negative ion in an interstitial position and to balance the charges by means of an extra charge on an adjacent metal ion (see Figure 3.18). However, since negative ions are usually large, it would be difficult to fit them into interstitial positions. No examples of crystals containing such negative interstitial ions are known at present.

## SEMICONDUCTORS AND TRANSISTORS

Semiconductors are solids where there is only a small difference in energy, called a *band gap*, between the filled valency band of electrons and a conduction band. If cooled to absolute zero, the electrons occupy their lowest possible energy levels. The conduction band is empty, and the material is a perfect insulator. At normal temperatures, some electrons are thermally excited from the valency band to the conduction band, and hence they can conduct electricity by the passage of electrons at normal temperatures. The conductivity is in between that of a metal and an insulator and depends on the number of electrons in the conduction band.

Germanium and, to an even greater extent, silicon are the most important commercial examples of semiconductors. The crystal structures of both are like diamond. Atoms of Si and Ge both have four electrons in their outer shell, which form four covalent bonds to other atoms. In both




Figure 3.17 Metal deficiency caused by missing positive ion.




Figure 3.18 Metal deficiency caused by interstitial negative ions.

Table 3.8 Band gaps of some semiconductors at absolute zero

Compound	Energy gap (kJ mol <sup>-1</sup> )	Compound	Energy gap (kJ mol <sup>-1</sup> )
$\alpha$ Sn	0	GaAs	145
PbTe	19	Cu <sub>2</sub> O	212
Te	29	CdS	251
PbS	29	GaP	278
Ge	68	ZnO	328
Si	106	ZnS	376
InP	125	Diamond	579

Si and Ge at very low temperatures the valence band is filled and the conduction band is empty. Under these conditions, Si and Ge are both insulators and cannot carry any electric current.

The band gaps are only 68 kJ mol<sup>-1</sup> for Ge, and 106 kJ mol<sup>-1</sup> for Si, and at room temperature a few valence electrons gain sufficient energy from the thermal vibration of the atoms to be promoted into the conduction band. If the crystal is connected in an electric circuit, these thermally excited electrons carry a small current, and make the Si or Ge crystal slightly conducting. This is termed *intrinsic semiconduction*. Expressed in another way, some bonds are broken, and these valence electrons can migrate and conduct electricity.

As the temperature is increased the conductivity increases, that is the electrical resistance decreases. (This is the opposite of the situation with metals.) Above 100°C so many valence electrons are promoted to the conduction band in Ge that the crystal lattice disintegrates. With Si the maximum working temperature is 150°C. This intrinsic semiconduction is undesirable and precautions must be taken to limit the working temperature of transistors.



Pure Si and Ge can be made semiconducting in a controlled way by adding impurities which act as charge carriers. Si or Ge are first obtained extremely pure by zone refining. Some atoms with five outer electrons such as arsenic As are deliberately added to the silicon crystal. This process is called 'doping' the crystal. A minute proportion of Si atoms are randomly replaced by As atoms with five electrons in their outer shell. Only four of the outer electrons on each As atom are required to form bonds in the lattice. At absolute zero or low temperatures, the fifth electron is localized on the As atom. However, at normal temperatures some of these fifth electrons on As are excited into the conduction band where they can carry current quite readily. This is *extrinsic conduction*, and it increases the amount of semiconduction far above that possible by intrinsic conduction. Since the current is carried by excess electrons, it is *n type semiconduction*.

Alternatively a crystal of pure Si may be doped with some atoms with only three outer electrons such as indium In. Each indium atom uses its




three outer electrons to form three bonds in the lattice, but they are unable to form four bonds to complete the covalent structure. One bond is incomplete, and the site normally occupied by the missing electron is called a 'positive hole'. At absolute zero or low temperatures, the positive holes are localized around the indium atoms. However, at normal temperatures a valence electron on an adjacent Si atom may gain sufficient energy to move into the hole. This forms a new positive hole on the Ge atom. The positive hole seems to have moved in the opposite direction to the electron. By a series of 'hops', the 'positive hole' can migrate across the crystal. This is equivalent to moving an electron in the opposite direction, and thus current is carried. Since current is carried by the migration of positive centres, this is *p-type semiconduction*.

Silicon must be ultra-highly purified before it can be used in semiconductors. First impure silicon (98% pure) is obtained by reducing  $\text{SiO}_2$  with carbon in an electric furnace at about  $1900^\circ\text{C}$ . This may be purified by reacting with  $\text{HCl}$ , forming trichlorosilane  $\text{SiHCl}_3$ , which may be distilled to purify it, then decomposed by heating to give pure silicon.




The final purification is by zone refining, where a rod of silicon is melted near one end by an electric furnace. As the furnace is slowly moved along the rod, the narrow molten zone gradually moves to the other end of the rod. The impurities are more soluble in the liquid melt than in the solid, so they concentrate in the molten zone, and eventually move to the end of the rod. The impure end is removed, leaving an ultra-purified rod, with a purity of at least 1 part in  $10^{10}$ . Purified silicon (or germanium) crystals can be converted to *p*-type or *n*-type semiconductors by high temperature diffusion of the appropriate dopant element, up to a concentration of 1 part in  $10^8$ . In principle any of the Group III elements boron, aluminium, gallium or indium can be used to make *p*-type semiconductors, though indium is the most used because of its low melting point. Similarly Group V elements such as phosphorus or arsenic can be used to make *n*-type semiconductors, but because of its low melting point arsenic is most used.

If a single crystal is doped with indium at one end, and with arsenic at the other end, then one part is a *p*-type semiconductor and the other an *n*-type semiconductor. In the middle there will be a boundary region where the two sides meet, which is a *p-n* junction. Such junctions are the important part of modern semiconductor devices.




(Ge) Germanium nucleus + 28 electrons  
 • Valence electron  
 — Covalent bond

(a)



(b)



(c)

Figure 3.19 (a) Pure germanium. (b) *n*-type germanium. (c) *p*-type germanium.

## RECTIFIERS

A rectifier will only allow current from an outside source to flow through it in one direction. This is invaluable in converting alternating current AC into direct current DC, and it is common to use a square of four diodes in a




Figure 3 20 An  $n p$  junction as a rectifier

circuit to do this. A diode is simply a transistor with two zones, one  $p$  type and the other  $n$  type, with a  $p n$  junction in between.

Suppose that a positive voltage is applied to the  $p$  type region, and a negative (or more negative) voltage applied to the  $n$ -type region. In the  $p$  type region, positive holes will migrate towards the  $p n$  junction. In the  $n$  type region, electrons will migrate towards the junction. At the junction, the two destroy each other. Expressed in another way, at the junction the migrating electrons from the  $n$  type region move into the vacant holes in the valence band of the  $p$  type region. The migration of electrons and holes can continue indefinitely, and a current will flow for as long as the external voltage is applied.

Consider what will happen if the voltages are reversed, so the  $p$  type region is negative and the  $n$  type region positive. In the  $p$  type region, positive holes migrate away from the junction, and in the  $n$  type region, electrons migrate away from the junction. At the junction, there are neither positive holes nor electrons, so no current can flow.

## PHOTOVOLTAIC CELL

If a  $p n$  junction is irradiated with light, provided that the energy of the light photons exceeds the band gap, then some bonds will break, giving electrons and positive holes, and these electrons are promoted from the valence band to the conduction band. The extra electrons in the conduction band make the  $n$  type region more negative, whilst in the  $p$  type region, the electrons are trapped by some positive holes. If the two regions are connected in an external circuit, then electrons can flow from the  $n$  type region to the  $p$  type region, that is, current flows from the  $p$  type to the  $n$  type region. Such a device acts as a battery that can generate electricity from light. Efforts are being made to make efficient cells of this type to harness solar energy.

## TRANSISTORS

Transistors are typically single crystals of silicon which have been doped to give three zones. In Britain  $p n p$  transistors are mainly used, whilst in the USA  $n p n$  transistors are most widely used. Both types have many uses, for example as amplifiers and oscillators in radio, TV and hi fi circuits and in computers. They are also used as phototransistors, tunnel diodes, solar cells, thermistors, and in the detection of ionizing radiation.

Different voltages must be applied to the three regions of a transistor to make it work. Typical bias potentials for a  $p n p$  transistor are shown in Figure 3 21. The base is typically  $-0.2$  volts and the collector is typically  $-2.0$  volts with respect to the emitter. The charge carriers in the emitter are positive holes, and these migrate from the emitter at 0 volts to the base at  $-0.2$  volts. The positive holes cross the emitter/base  $p n$  junction, and in the  $n$  type base region, some positive holes combine with electrons and are destroyed. There is a flow of electrons in the reverse direction, from the




Figure 3.21 *n-p-n* and *p-n-p* transistors.

base to the emitter. There is thus a small base current. However, the base is very thin, and the collector has a much greater negative voltage, so most of the positive holes pass through the base to the collector, where they combine with electrons from the circuit. At the emitter, electrons leave the *p*-type semiconductor and enter the circuit, and in doing so they produce more positive holes. Typically, if the emitter current is 1 mA, the base current is 0.02 mA, and the collector current 0.98 mA.

The most common method of using a transistor as an amplifier is the *common or grounded emitter circuit* (Figure 3.22a). The emitter is common to both the base and collector circuits, and is sometimes grounded (earthed). The base current is the input signal, and the collector current is the output signal. If the base current is reduced, for example by increasing  $R_1$ , the base becomes positively charged, and this reduces the movement of positive holes to the collector. In a typical transistor, a change in the base current can produce a change 50 times as great in the collector current, giving a current amplification factor of 50. A small change in input current to the base produces a much larger change in the collector current, so the original signal is amplified.

In practice the bias for both the base and the collector are often obtained from one battery by having the resistance of  $R_1$  much greater than that of  $R_2$  (Figure 3.22b).




Figure 3.22 Common emitter amplifier circuits. e = emitter, b = base, c = collector.

Finally,  $n p n$  transistors work in a similar way, except that the polarity of the bias voltages is reversed so the collector and base are positive with respect to the emitter

### MICRO MINATURIZED SEMICONDUCTOR DEVICES INTEGRATED CIRCUITS

It is now possible to manufacture computer chips with the equivalent of many thousands of single crystal transistor junctions on a small wafer of silicon, only a few millimetres square (Memory chips for computers are readily available which store 64K 256K 1 megabyte and even 4 megabytes of data on a single chip )

The steps in the manufacture of such chips is

- 1 A fairly large single crystal of Si is doped to make it an  $n$  type semiconductor, and then it is carefully cut into thin slices
- 2 A slice is heated in air to form a thin surface layer of  $\text{SiO}_2$
- 3 The oxide layer is then coated with a photosensitive film, sometimes called a photoresist
- 4 A mask is placed over the photoresist and the slice is exposed to UV light Those parts of the photoresist exposed to light are changed and are removed by treatment with acid but the unexposed parts remain protected by the photoresist
- 5 The slice is then treated with HF, which etches (removes) the exposed areas of  $\text{SiO}_2$  After this, the unchanged photoresist is removed
- 6 The surface is exposed to the vapour of a Group 13 element Some of the surface is covered by a film of  $\text{SiO}_2$ , and some has exposed silicon The parts covered by a  $\text{SiO}_2$  film are unaffected, but in the parts where the silicon itself is exposed, some Si atoms are randomly replaced, forming a layer of  $p$  type semiconductor
- 7 The steps (2) to (5) are repeated using a different mask, and the exposed areas of Si exposed to the vapour of a Group 15 element, to produce another layer of  $n$  type semiconductor
- 8 Steps (2) to (5) are repeated using a mask to produce the openings into which metal can be deposited to 'wire together' the various semiconductors so produced into an integrated circuit
- 9 Finally the chip is packaged in plastic or ceramic, connecting pins are soldered on so that it may be plugged in to a socket on a circuit board and the chip is tested A significant number turn out to be faulty Faulty chips cannot be repaired, and are discarded

### FURTHER READING


- Adams, D M (1974) *Inorganic Solids* Wiley Interscience New York  
 Addison, W E (1961) *Structural Principles in Inorganic Compounds* Longmans London  
 Bamfield, P (ed ) (1986) *Fine Chemicals for the Electronic Industry* Royal Society of Chemistry Special Publication No 40 London

- Burdett, J.K. (1982) New ways to look at solids, *Acc. Chem. Res.*, **15**, 34.
- Cartmell, E. and Fowles, G.W.A. (1977) *Valency and Molecular Structure*, 4th ed., Butterworths, London.
- Cox, P.A. (1987) *The Electronic Structure and Chemistry of Solids*, Oxford University Press.
- Dasent, W.E. (1982) *Inorganic Energetics: An Introduction* (Cambridge Texts in Chemistry and Biochemistry Series), Cambridge University Press.
- Douglas, B., McDaniel, D.H. and Alexander J.J. (1983) *Concepts and Models in Inorganic Chemistry*, 2nd ed., Wiley, New York.
- Ebsworth, E.A.V., Rankin, D.W.H. and Cradock, S. (1987) *Structural Methods in Inorganic Chemistry*, Blackwell Scientific, Oxford.
- Galasso, F.S. (1970) *Structure and Properties of Inorganic Solids*, Pergamon, Oxford. (Contains extensive tables.)
- Galwey, A.K. (1967) *Chemistry of Solids*, Chapman & Hall, London.
- Greenwood, N.N. (1968) *Ionic Crystals, Lattice Defects and Non-Stoichiometry*, Butterworths, London. (Still the best single volume book on the subject.)
- Ho, S.M. and Douglas, B.E. (1972) Structures of the elements and the PTOT system, *J. Chem. Ed.*, **49**, 74.
- Hyde, B.G. and Andersson, S. (1989) *Inorganic Crystal Structures*, Wiley, New York.
- Jenkins, H.D.B. (1979) The calculation of lattice energy: some problems and some solutions, *Revue de Chimie Minerale*, **16**, 134–150.
- Ladd, M.F.C. (1974) *Structure and Bonding in Solid State Chemistry*, Wiley, London.
- Moss, S.J and Ledwith, A. (eds) (1987) *The Chemistry of the Semiconductor Industry*, Blackie.
- Parish, R.V. (1976) *The Metallic Elements*, Longmans, London.
- Rao, C.N.R. (ed.) (1974) *Solid State Chemistry*, Dekker, New York.
- Rao, C.N.R. and Gopalakrishnan, J. (1986) *New Directions in Solid State Chemistry*, Cambridge University Press, Cambridge.
- Shannon R.D. (1976) Revised effective ionic radii. *Acta Cryst.*, **A32**, 751–767. (The most up to date and generally accepted values for ionic radii.)
- Walton, A. (1978) *Molecular and Crystal Structure Models*, Ellis Horwood, Chichester.
- Wells, A.F. (1984) *Structural Inorganic Chemistry*, 5th ed., Oxford University Press, Oxford. (The standard text, with excellent diagrams.)
- West, A.R. (1984) *Solid State Chemistry and its Applications*, Wiley, New York.


## PROBLEMS

1. Relate the tendency of atoms to gain or lose electrons to the types of bonds they form.
2. Indicate to what extent the following will conduct electricity, and give the mechanism of conduction in each case:
  - (a) NaCl (fused)
  - (b) NaCl (aqueous solution)
  - (c) NaCl (solid)
  - (d) Cu (solid)
  - (e) CCl<sub>4</sub> (liquid).
3. Why are ionic compounds usually high melting, whilst most simple covalent compounds have low melting points? Explain the high melting point of diamond.

- 4 How are the minimum values of radius ratio arrived at for various coordination numbers, and what are these limits? Give examples of the types of crystal structure associated with each coordination number
- 5 Show by means of a diagram, and a simple calculation, the minimum value of the radius ratio  $r^+/r^-$  which permits a salt to adopt a caesium chloride type of structure
- 6 Give the coordination numbers of the ions and describe the crystal structures of zinc blende, wurtzite and sodium chloride in terms of close packing and the occupancy of tetrahedral and octahedral holes
- 7 CsCl, CsI, TlCl and TlI all adopt a caesium chloride structure. The inter ionic distances are Cs-Cl 3.06 Å, Cs-I 3.41 Å, Tl-Cl 2.55 Å and Tl-I 2.90 Å. Assuming that the ions behave as hard spheres and that the radius ratio in TlI has the limiting value, calculate the ionic radii for  $\text{Cs}^+$ ,  $\text{Tl}^+$ ,  $\text{Cl}^-$ ,  $\text{I}^-$  in eight coordination
- 8 Write down the Born-Landé equation and define the terms in it. Use the equation to show why some crystals, which according to the radius ratio concept should adopt a coordination number of 8, in fact have a coordination number of 6
- 9 Outline a Born-Haber cycle for the formation of an ionic compound MCl. Define the terms used and state how these might be measured or calculated. How do these enthalpy terms vary throughout the periodic table? Use these variations to suggest how the properties of NaCl might differ from those of CuCl
- 10 Explain the term lattice energy as applied to an ionic solid. Calculate the lattice energy of caesium chloride using the following data




- 11 (a) Draw the structures of CsCl and  $\text{TiO}_2$ , showing clearly the coordination of the cations and anions. (b) Show how the Born-Haber cycle may be used to estimate the enthalpy of the hypothetical reaction



Explain why CaCl(s) has never been made even though the enthalpy for this reaction is negative

- 12 The standard enthalpy changes  $\Delta H^\circ$  at 298 K for the reaction



are given for the first row transition metals:

	Sc	Ti	V	Cr	Mn	Fe	Co	Ni	Cu
$\Delta H^\circ/\text{kJ mol}^{-1}$	-339	-209	-138	-160	+22	-59	+131	+280	+357

Use a Born–Haber cycle to account for the change in  $\Delta H^\circ$  as the atomic number of the metal increases. Comment on the relative stabilities of the +II and +III oxidation states of the 3d metals.

13. List the types of defect that occur in the solid state and give an example of each. Explain in each case if any electrical conduction is possible and by what mechanism.

## INTRODUCTION

There are several different theories which explain the electronic structures and shapes of known molecules, and attempt to predict the shape of molecules whose structures are so far unknown. Each theory has its own virtues and shortcomings. None is rigorous. Theories change in the light of new knowledge and fashion. If we knew or could prove what a bond was we would not need theories, which by definition cannot be proved. The value of a theory lies more in its usefulness than in its truth. Being able to predict the shape of a molecule is important. In many cases all the theories give the correct answer.

## THE LEWIS THEORY


## The octet rule

The Lewis theory was the first explanation of a covalent bond in terms of electrons that was generally accepted. If two electrons are shared between two atoms, this constitutes a bond and binds the atoms together. For many light atoms a stable arrangement is attained when the atom is surrounded by eight electrons. This octet can be made up from some electrons which are 'totally owned' and some electrons which are 'shared'. Thus atoms continue to form bonds until they have made up an octet of electrons. This is called the 'octet rule'. The octet rule explains the observed valencies in a large number of cases. There are exceptions to the octet rule, for example, hydrogen is stable with only two electrons. Other exceptions are discussed later. A chlorine atom has seven electrons in its outer shell, so by sharing one electron with another chlorine atom both atoms attain an octet and form a chlorine molecule  $\text{Cl}_2$ .




A carbon atom has four electrons in its outer shell, and by sharing all four electrons and forming four bonds it attains octet status in  $\text{CCl}_4$ .







In a similar way, a nitrogen atom has five outer electrons, and in  $\text{NH}_3$  it shares three of these, forming three bonds and thus attaining an octet. Hydrogen has only one electron, and by sharing it attains a stable arrangement of two electrons.



In a similar way an atom of oxygen attains an octet by sharing two electrons in  $\text{H}_2\text{O}$  and an atom of fluorine attains an octet by sharing one electron in  $\text{HF}$ .





Double bonds are explained by sharing four electrons between two atoms, and triple bonds by sharing six electrons.



### Exceptions to the octet rule

The octet rule is broken in a significant number of cases:

1. For example, for atoms such as Be and B which have less than four outer electrons. Even if all the outer electrons are used to form bonds an octet cannot be attained.



2. The octet rule is also broken where atoms have an extra energy level which is close in energy to the  $p$  level, and may accept electrons and be

used for bonding  $\text{PF}_3$  obeys the octet rule, but  $\text{PF}_5$  does not.  $\text{PF}_5$  has ten outer electrons, and uses one  $3s$ , three  $3p$  and one  $3d$  orbitals. Any compound with more than four covalent bonds must break the octet rule, and these violations become increasingly common in elements after the first two periods of eight elements in the periodic table.

- 3 The octet rule does not work in molecules which have an odd number of electrons, such as  $\text{NO}$  and  $\text{ClO}_2$ , nor does it explain why  $\text{O}_2$  is paramagnetic and has two unpaired electrons.

Despite these exceptions, the octet rule is surprisingly reliable and did a great deal to explain the number of bonds formed in simple cases. However, it gives no indication of the shape adopted by the molecule.

### SIDGWICK-POWELL THEORY

In 1940 Sidgwick and Powell (see Further Reading) reviewed the structures of molecules then known. They suggested that for molecules and ions that only contain single bonds, the approximate shape can be predicted from the number of electron pairs in the outer or valence shell of the central atom. The outer shell contains one or more bond pairs of electrons, but it may also contain unshared pairs of electrons (lone pairs). Bond pairs and lone pairs were taken as equivalent, since all electron pairs take up some space, and since all electron pairs repel each other. Repulsion is minimized if the electron pairs are orientated in space as far apart as possible.







- 1 If there are two pairs of electrons in the valence shell of the central atom, the orbitals containing them will be oriented at  $180^\circ$  to each other. It follows that if these orbitals overlap with orbitals from other atoms to form bonds, then the molecule formed will be linear.
- 2 If there are three electron pairs on the central atom, they will be at  $120^\circ$  to each other, giving a plane triangular structure.
- 3 For four electron pairs the angle is  $109^\circ 28'$ , and the shape is tetrahedral.
- 4 For five pairs, the shape is a trigonal bipyramid.
- 5 For six pairs the angles are  $90^\circ$  and the shape is octahedral.

### VALENCE SHELL ELECTRON PAIR REPULSION (VSEPR) THEORY

In 1957 Gillespie and Nyholm (see Further Reading) improved the Sidgwick-Powell theory to predict and explain molecular shapes and bond angles more exactly. The theory was developed extensively by Gillespie as the Valence Shell Electron Pair Repulsion (VSEPR) theory. This may be summarized.

- 1 The shape of the molecule is determined by repulsions between all of the electron pairs present in the valence shell. (This is the same as the Sidgwick-Powell theory.)

Table 4.1 Molecular shapes predicted by Sidgwick–Powell theory

Number of electron pairs in outer shell	Shape of molecule	Bond angles
2	linear 	180°
3	plane triangle 	120°
4	tetrahedron 	109°28'
5	trigonal bipyramid 	120° and 90°
6	octahedron 	90°
7	pentagonal bipyramid 	72° and 90°

- A lone pair of electrons takes up more space round the central atom than a bond pair, since the lone pair is attracted to one nucleus whilst the bond pair is shared by two nuclei. It follows that repulsion between two lone pairs is greater than repulsion between a lone pair and a bond pair, which in turn is greater than the repulsion between two bond pairs. Thus the presence of lone pairs on the central atom causes slight distortion of the bond angles from the ideal shape. If the angle between a lone pair, the central atom and a bond pair is increased, it follows that the actual bond angles between the atoms must be decreased.
- The magnitude of repulsions between bonding pairs of electrons depends on the electronegativity difference between the central atom and the other atoms.
- Double bonds cause more repulsion than single bonds, and triple bonds cause more repulsion than a double bond.

### Effect of lone pairs

Molecules with four electron pairs in their outer shell are based on a tetrahedron. In  $\text{CH}_4$  there are four bonding pairs of electrons in the outer shell of the C atom, and the structure is a regular tetrahedron with bond angles  $\text{H—C—H}$  of 109°28'. In  $\text{NH}_3$  the N atom has four electron pairs in the outer shell, made up of three bond pairs and one lone pair. Because of the lone pair, the bond angle  $\text{H—N—H}$  is reduced from the theoretical tetrahedral angle of 109°28' to 107°48'. In  $\text{H}_2\text{O}$  the O atom has four electron pairs in the outer shell. The shape of the  $\text{H}_2\text{O}$  molecule is based on a tetrahedron with two corners occupied by bond pairs and the other two corners occupied by lone pairs. The presence of two lone pairs reduces the bond angle further to 104°27'.

In a similar way  $\text{SF}_6$  has six bond pairs in the outer shell and is a regular octahedron with bond angles of exactly 90°. In  $\text{BrF}_5$  the Br also has six outer pairs of electrons, made up of five bond pairs and one lone pair. The

lone pair reduces the bond angles to  $84^{\circ}30'$ . Whilst it might be expected that two lone pairs would distort the bond angles in an octahedron still further, in  $\text{XeF}_4$  the angles are  $90^{\circ}$ . This is because the lone pairs are *trans* to each other in the octahedron, and hence the atoms have a regular square planar arrangement.

Molecules with five pairs of electrons are all based on a trigonal bipyramid. Lone pairs distort the structures as before. The lone pairs always occupy the equatorial positions (in the triangle), rather than the apical positions (up and down). Thus in the  $\text{I}_3^-$  ion the central I atom has five electron pairs in the outer shell, made of two bond pairs and three lone pairs. The lone pairs occupy all three equatorial positions and the three atoms occupy the top, middle, and bottom positions in the trigonal bipyramid, thus giving a linear arrangement with a bond angle of exactly  $180^{\circ}$  (Table 4.2).

### Effect of electronegativity

$\text{NF}_3$  and  $\text{NH}_3$  both have structures based on a tetrahedron with one corner occupied by a lone pair. The high electronegativity of F pulls the bonding electrons further away from N than in  $\text{NH}_3$ . Thus repulsion between bond pairs is less in  $\text{NF}_3$  than in  $\text{NH}_3$ . Hence the lone pair in  $\text{NF}_3$  causes a greater distortion from tetrahedral and gives a  $\text{F}-\text{N}-\text{F}$  bond angle of  $102^{\circ}30'$ , compared with  $107^{\circ}48'$  in  $\text{NH}_3$ . The same effect is found in  $\text{H}_2\text{O}$  (bond angle  $104^{\circ}27'$ ) and  $\text{F}_2\text{O}$  (bond angle  $102^{\circ}$ ).

Table 4.2 The effects of bonding and lone pairs on bond angles

	Orbitals on central atom	Shape	Number of bond pairs	Number of lone pairs	Bond angle
$\text{BeCl}_2$	2	Linear	2	0	$180^{\circ}$
$\text{BF}_3$	3	Plane triangle	3	0	$120^{\circ}$
$\text{CH}_4$	4	Tetrahedral	4	0	$109^{\circ}28'$
$\text{NH}_3$	4	Tetrahedral	3	1	$107^{\circ}48'$
$\text{NF}_3$	4	Tetrahedral	3	1	$102^{\circ}30'$
$\text{H}_2\text{O}$	4	Tetrahedral	2	2	$104^{\circ}27'$
$\text{F}_2\text{O}$	4	Tetrahedral	2	2	$102^{\circ}$
$\text{PCl}_5$	5	Trigonal bipyramid	5	0	$120^{\circ}$ and $90^{\circ}$
$\text{SF}_4$	5	Trigonal bipyramid	4	1	$101^{\circ}36'$ and $86^{\circ}33'$
$\text{ClF}_3$	5	Trigonal bipyramid	3	2	$87^{\circ}40'$
$\text{I}_3^-$	5	Trigonal bipyramid	2	3	$180^{\circ}$
$\text{SF}_6$	6	Octahedral	6	0	$90^{\circ}$
$\text{BrF}_4$	6	Octahedral	5	1	$84^{\circ}30'$
$\text{XeF}_4$	6	Octahedral	4	2	$90^{\circ}$

### Isoelectronic principle

Isoelectronic species usually have the same structure. This may be extended to species with the same number of valence electrons. Thus  $\text{BF}_4^-$ ,  $\text{CH}_4$  and  $\text{NH}_4^+$  are all tetrahedral,  $\text{CO}_3^{2-}$ ,  $\text{NO}_3^-$  and  $\text{SO}_3$  are all planar triangles, and  $\text{CO}_2$ ,  $\text{N}_3^-$  and  $\text{NO}_2^+$  are all linear.

### SOME EXAMPLES USING THE VSEPR THEORY

#### $\text{BF}_3$ and the $[\text{BF}_4]^-$ ion

Consider  $\text{BF}_3$  first. The VSEPR theory only requires the number of electron pairs in the outer shell of the central atom. Since B is in Group 13 it has three electrons in the outer shell. (Alternatively the electronic structure of B (the central atom), is  $1s^2 2s^2 2p^1$ , so there are three electrons in the outer valence shell.) If all three outer electrons are used to form bonds to three F atoms, the outer shell then has a share in six electrons, that is three electron pairs. Thus the structure is a planar triangle. Though this gives the correct shape, its bonds are actually shorter than would be expected for single bonds, and the reason for this is discussed under 'Trihalides' in Chapter 12.

The  $[\text{BF}_4]^-$  ion may be regarded as being formed by adding a  $\text{F}^-$  ion to a  $\text{BF}_3$  molecule by means of a coordinate bond. Thus the B atom now has three electron pairs from the  $\text{BF}_3$  plus one electron pair from the  $\text{F}^-$ . There are therefore four electron pairs in the outer shell: hence the  $\text{BF}_4^-$  ion has a tetrahedral structure.

#### Ammonia $\text{NH}_3$

N is the central atom. It is in Group 15 and has five electrons in the outer valence shell. (The electronic structure of N is  $1s^2 2s^2 2p^3$ .) Three of these electrons are used to form bonds to three H atoms, and two electrons take no part in bonding and constitute a 'lone pair'. The outer shell then has a share in eight electrons, that is three bond pairs of electrons and one lone pair. Four electron pairs give rise to a tetrahedral structure and in this case three positions are occupied by H atoms and the fourth position is occupied by the lone pair (Figure 4.1). The shape of  $\text{NH}_3$  may either be described as tetrahedral with one corner occupied by a lone pair, or alternatively as pyramidal. The presence of the lone pair causes slight distortion from  $109^\circ 28'$  to  $107^\circ 48'$ .

#### Water $\text{H}_2\text{O}$

O is the central atom. It is in Group 16 and hence has six outer electrons. (The electronic structure of O is  $1s^2 2s^2 2p^4$ .) Two of these electrons form bonds with two H atoms, thus completing the octet. The other four outer electrons on O are non-bonding. Thus in  $\text{H}_2\text{O}$  the O atom has eight outer electrons (four electron pairs) so the structure is based on a tetrahedron. There are two bond pairs and two lone pairs. The structure is described as




Figure 4.1 Structure of  $\text{NH}_3$ .




Figure 4.2 Structure of  $\text{H}_2\text{O}$ .

tetrahedral with two positions occupied by lone pairs. The two lone pairs distort the bond angle from  $109^{\circ}28'$  to  $104^{\circ}27'$  (Figure 4.2)

Any triatomic molecule must be either linear with a bond angle of  $180^{\circ}$ , or else angular that is bent. In  $\text{H}_2\text{O}$  the molecule is based on a tetrahedron and is therefore bent.

### Phosphorus pentachloride $\text{PCl}_5$

Gaseous  $\text{PCl}_5$  is covalent. P (the central atom) is in Group 15 and so has five electrons in the outer shell. (The electronic structure of P is  $1s^2 2s^2 2p^6 3s^2 3p^3$ .) All five outer electrons are used to form bonds to the five Cl atoms. In the  $\text{PCl}_5$  molecule the valence shell of the P atom contains five electron pairs; hence the structure is a trigonal bipyramid. There are no lone pairs, so the structure is not distorted. However, a trigonal bipyramid is not a completely regular structure, since some bond angles are  $90^{\circ}$  and others  $120^{\circ}$ . Symmetrical structures are usually more stable than asymmetrical ones. Thus  $\text{PCl}_5$  is highly reactive and in the solid state it splits into  $[\text{PCl}_4]^+$  and  $[\text{PCl}_6]^-$  ions, which have tetrahedral and octahedral structures respectively.




Figure 4.3 Structure of  $\text{PCl}_5$  molecule

### Chlorine trifluoride $\text{ClF}_3$

The chlorine atom is at the centre of the molecule and determines its shape. Cl is in Group 17 and so has seven outer electrons. (The electronic structure of Cl is  $1s^2 2s^2 2p^6 3s^2 3p^5$ .) Three electrons form bonds to F, and four electrons do not take part in bonding. Thus in  $\text{ClF}_3$  the Cl atom has five electron pairs in the outer shell; hence the structure is a trigonal bipyramid. There are three bond pairs and two lone pairs.

It was noted previously that a trigonal bipyramid is not a regular shape since the bond angles are not all the same. It therefore follows that the corners are not equivalent. Lone pairs occupy two of the corners, and F atoms occupy the other three corners. Three different arrangements are theoretically possible, as shown in Figure 4.4.

The most stable structure will be the one of lowest energy, that is the one with the minimum repulsion between the five orbitals. The greatest repulsion occurs between two lone pairs. Lone pair-bond pair repulsions are next strongest, and bond pair-bond pair repulsions the weakest.




Figure 4.4 Chlorine trifluoride molecule

Groups at  $90^\circ$  to each other repel each other strongly, whilst groups  $120^\circ$  apart repel each other much less.

Structure 1 is the most symmetrical, but has six  $90^\circ$  repulsions between lone pairs and atoms. Structure 2 has one  $90^\circ$  repulsion between two lone pairs, plus three  $90^\circ$  repulsions between lone pairs and atoms. Structure 3 has four  $90^\circ$  repulsions between lone pairs and atoms. These factors indicate that structure 3 is the most probable. The observed bond angles are  $87^\circ 40'$ , which is close to the theoretical  $90^\circ$ . This confirms that the correct structure is (3), and the slight distortion from  $90^\circ$  is caused by the presence of the two lone pairs.

As a general rule, if lone pairs occur in a trigonal bipyramid they will be located in the equatorial positions (round the middle) rather than the apical positions (top and bottom), since this arrangement minimizes repulsive forces.

### Sulphur tetrafluoride $\text{SF}_4$

S is in Group 16 and thus has six outer electrons. (The electronic configuration of S is  $1s^2 2s^2 2p^6 3s^2 3p^4$ .) Four outer electrons are used to form bonds with the F atoms, and two electrons are non-bonding. Thus in  $\text{SF}_4$  the S has five electron pairs in the outer shell: hence the structure is based on a trigonal bipyramid. There are four bond pairs and one lone pair. To minimize the repulsive forces the lone pair occupies an equatorial position, and F atoms are located at the other four corners, as shown in Figure 4.5.





Figure 4.5 Sulphur tetrafluoride molecule.

### The triiodide ion $\text{I}_3^-$

If iodine is dissolved in aqueous potassium iodide, the triiodide ion  $\text{I}_3^-$  is formed. This is an example of a polyhalide ion, which is similar in structure to  $\text{BrCl}_2^-$  (see Chapter 15). The  $\text{I}_3^-$  ion (Figure 4.6) has three atoms, and must be either linear or angular in shape. It is convenient to consider the structure in a series of stages – first an I atom, then an  $\text{I}_2$  molecule, and then the  $\text{I}_3^-$  ion made up of an  $\text{I}_2$  molecule with an  $\text{I}^-$  bonded to it by means of a coordinate bond.



Iodine is in Group 17 and so has seven outer electrons. (The electronic configuration of I is  $1s^2 2s^2 2p^6 3s^2 3p^6 3d^{10} 4s^2 4p^6 4d^{10} 5s^2 5p^5$ .) One of the outer electrons is used to bond with another I atom, thus forming an  $\text{I}_2$  molecule. The I atoms now have a share in eight electrons. One of the I atoms in the  $\text{I}_2$  molecule accepts a lone pair from an  $\text{I}^-$  ion, thus forming an  $\text{I}_3^-$  ion. The outer shell of the central I atom now contains ten electrons, that is five electron pairs. Thus the shape is based on a trigonal bipyramid. There are two bond pairs and three lone pairs. To minimize the repulsive forces the three lone pairs occupy the equatorial positions, and I atoms are located at the centre and in the two apical positions. The ion is therefore linear in shape, with a bond angle of exactly  $180^\circ$ .




Figure 4.6 The triiodide ion.




Figure 4.7 Sulphur hexafluoride molecule

### Sulphur hexafluoride $\text{SF}_6$

Sulphur is in Group 16 and thus has six outer electrons (The electronic structure of S is  $1s^2 2s^2 2p^6 3s^2 3p^4$ ). All six of the outer electrons are used to form bonds with the F atoms. Thus in  $\text{SF}_6$  the S has six electron pairs in the outer shell hence the structure is octahedral. There are no lone pairs so the structure is completely regular with bond angles of  $90^\circ$ .

### Iodine heptafluoride $\text{IF}_7$

This is the only common example of a non transition element using seven orbitals for bonding giving a pentagonal bipyramid (See Chapter 15).

The total numbers of outer orbitals, bonding orbitals and lone pairs are related to the commonly occurring shapes of molecules in Table 4.1.

## VALENCE BOND THEORY

This theory was proposed by Linus Pauling who was awarded the Nobel Prize for Chemistry in 1954. The theory was very widely used in the period 1940–1960. Since then it has to some extent fallen out of fashion. However, it is still much used by organic chemists and it provides a basis for simple description of small inorganic molecules.

Atoms with unpaired electrons tend to combine with other atoms which also have unpaired electrons. In this way the unpaired electrons are paired up and the atoms involved all attain a stable electronic arrangement. This is usually a full shell of electrons (i.e. a noble gas configuration). Two electrons shared between two atoms constitute a bond. The number of bonds formed by an atom is usually the same as the number of unpaired electrons in the ground state, i.e. the lowest energy state. However, in some cases the atom may form more bonds than this. This occurs by excitation of the atom (i.e. providing it with energy) when electrons which were paired in the ground state are unpaired and promoted into suitable empty orbitals. This increases the number of unpaired electrons, and hence the number of bonds which can be formed.

The shape of the molecule is determined primarily by the directions in which the orbitals point. Electrons in the valence shell of the original atom which are paired are called lone pairs.




A covalent bond results from the pairing of electrons (one from each atom). The spins of the two electrons must be opposite (antiparallel) because of the Pauli exclusion principle that no two electrons in one atom can have all four quantum numbers the same.

Consider the formation of a few simple molecules

- 1 In  $\text{HF}$ , H has a singly occupied  $s$  orbital that overlaps with a singly filled  $2p$  orbital on F.
- 2 In  $\text{H}_2\text{O}$  the O atom has two singly filled  $2p$  orbitals each of which overlaps with a singly occupied  $s$  orbital from two H atoms.



3. In  $\text{NH}_3$ , there are three singly occupied  $p$  orbitals on N which overlap with  $s$  orbitals from three H atoms.
4. In  $\text{CH}_4$ , the C atom in its ground state has the electronic configuration  $1s^2, 2s^2, 2p_x^1, 2p_y^1$  and only has two unpaired electrons, and so can form only two bonds. If the C atom is excited, then the  $2s$  electrons may be unpaired, giving  $1s^2, 2s^1, 2p_x^1, 2p_y^1, 2p_z^1$ . There are now four unpaired electrons which overlap with singly occupied  $s$  orbitals on four H atoms.

Electronic structure of carbon atom – ground state	$1s$ 
Carbon atom – excited state	$1s$ 
Carbon atom having gained four electrons from H atoms in $\text{CH}_4$ molecule	

The shape of the  $\text{CH}_4$  molecule is not immediately apparent. The three  $p$  orbitals  $p_x$ ,  $p_y$  and  $p_z$  are mutually at right angles to each other, and the  $s$  orbital is spherically symmetrical. If the  $p$  orbitals were used for bonding then the bond angle in water should be  $90^\circ$ , and the bond angles in  $\text{NH}_3$  should also be  $90^\circ$ . The bond angles actually found differ appreciably from these:

$\text{CH}_4$	$\text{H—C—H} = 109^\circ 28'$
$\text{NH}_3$	$\text{H—N—H} = 107^\circ 48'$
$\text{H}_2\text{O}$	$\text{H—O—H} = 104^\circ 27'$

### Hybridization

The chemical and physical evidence indicates that in methane  $\text{CH}_4$  there are four equivalent bonds. If they are equivalent, then repulsion between electron pairs will be a minimum if the four orbitals point to the corners of a tetrahedron, which would give the observed bond angle of  $109^\circ 28'$ .

Each electron can be described by its wave function  $\psi$ . If the wave functions of the four outer atomic orbitals of C are  $\psi_{2s}$ ,  $\psi_{2p_x}$ ,  $\psi_{2p_y}$ , and  $\psi_{2p_z}$ ; then the tetrahedrally distributed orbitals will have wave functions  $\psi_{sp^3}$  made up from a linear combination of these four atomic wave functions.

$$\psi_{sp^3} = c_1\psi_{2s} + c_2\psi_{2p_x} + c_3\psi_{2p_y} + c_4\psi_{2p_z}$$

There are four different combinations with different weighting constants  $c_1$ ,  $c_2$ ,  $c_3$  and  $c_4$ .

$$\psi_{sp^3(1)} = \frac{1}{2}\psi_{2s} + \frac{1}{2}\psi_{2p_x} + \frac{1}{2}\psi_{2p_y} + \frac{1}{2}\psi_{2p_z}$$

$$\psi_{sp^3(2)} = \frac{1}{2}\psi_{2s} + \frac{1}{2}\psi_{2p_x} - \frac{1}{2}\psi_{2p_y} - \frac{1}{2}\psi_{2p_z}$$

$$\psi_{sp^3(1)} = \frac{1}{2}\psi_{2s} - \frac{1}{2}\psi_{2p_x} + \frac{1}{2}\psi_{2p_y} - \frac{1}{2}\psi_{2p_z}$$

$$\psi_{sp^3(2)} = \frac{1}{2}\psi_{2s} - \frac{1}{2}\psi_{2p_x} - \frac{1}{2}\psi_{2p_y} + \frac{1}{2}\psi_{2p_z}$$

Combining or mixing the wave functions for the atomic orbitals in this way is called hybridization. Mixing one  $s$  and three  $p$  orbitals in this way gives four  $sp^3$  hybrid orbitals. The shape of an  $sp^3$  orbital is shown in Figure 4.8. Since one lobe is enlarged, it can overlap more effectively than an  $s$  orbital or a  $p$  orbital on its own. Thus  $sp^3$  hybrid orbitals form stronger bonds than the original atomic orbitals. (See Table 4.3.)





Figure 4.8 Combination of  $s$  and  $p$  atomic orbitals to give an  $sp^3$  hybrid orbital (a)  $2s$  atomic orbital (b)  $2p_x$  atomic orbital and (c)  $sp^3$  hybrid orbital

Table 4.3 Approximate strengths of bonds formed by various orbitals

Orbital	Relative bond strength
$s$	1.0
$p$	1.73
$sp$	1.93
$sp^2$	1.99
$sp^3$	2.00

It is possible to mix other combinations of atomic orbitals in a similar way. The structure of a boron trifluoride  $\text{BF}_3$  molecule is a planar triangle with bond angles of  $120^\circ$ . The B atom is the central atom in the molecule and it must be excited to give three unpaired electrons so that it can form three covalent bonds.



BF<sub>3</sub> molecule having gained a share in three electrons by bonding to three F atoms



$sp^2$  hybridization of the three orbitals in outer shell, hence structure is a planar triangle

Combining the wave functions of the  $2s$ ,  $2p_x$  and  $2p_y$  atomic orbitals gives three hybrid  $sp^2$  orbitals.

$$\psi_{sp^2(1)} = \frac{1}{\sqrt{3}} \psi_{2s} + \frac{2}{\sqrt{6}} \psi_{2p_x}$$

$$\psi_{sp^2(2)} = \frac{1}{\sqrt{3}} \psi_{2s} + \frac{1}{\sqrt{6}} \psi_{2p_x} + \frac{1}{\sqrt{2}} \psi_{2p_y}$$

$$\psi_{sp^2(3)} = \frac{1}{\sqrt{3}} \psi_{2s} + \frac{1}{\sqrt{6}} \psi_{2p_x} - \frac{1}{\sqrt{2}} \psi_{2p_y}$$

These three orbitals are equivalent, and repulsion between them is minimized if they are distributed at  $120^\circ$  to each other giving a planar triangle. In the hybrid orbitals one lobe is bigger than the other, so it can overlap more effectively and hence form a stronger bond than the original atomic orbitals. (See Table 4.3.) Overlap of the  $sp^2$  orbitals with  $p$  orbitals from F atoms gives the planar triangular molecule BF<sub>3</sub> with bond angles of  $120^\circ$ . Though this gives the correct shape, the bonds are actually shorter than would be expected for single bonds, and the reason for this is discussed under Trihalides in Chapter 12.




Figure 4.9 (a)  $sp^2$  hybrid orbitals and (b) the BF<sub>3</sub> molecule.

The structure of a gaseous molecule of beryllium fluoride BeF<sub>2</sub> is linear F—Be—F. Be is the central atom in this molecule and determines the shape of the molecule formed. The ground state electronic configuration of Be is  $1s^2 2s^2$ . This has no unpaired electrons, and so can form no bonds. If energy is supplied, an excited state will be formed by unpairing and promoting a  $2s$  electron to an empty  $2p$ -level, giving  $1s^2 2s^1 2p^1$ . There are now two unpaired electrons, so the atom can form the required two bonds.





Figure 4 10 (a) *s* orbital (b) *p* orbital (c) formation of two *sp* hybrid orbitals and (d) their use in forming beryllium difluoride



Hybridizing the  $2s$  and  $2p_x$  atomic orbitals gives two equivalent  $sp$  hybrid orbitals

$$\psi_{sp(1)} = \frac{1}{\sqrt{2}} \psi_{2s} + \frac{1}{\sqrt{2}} \psi_{2p_x}$$

$$\psi_{sp(2)} = \frac{1}{\sqrt{2}} \psi_{2s} - \frac{1}{\sqrt{2}} \psi_{2p_x}$$

Because of their shape these *sp* orbitals overlap more effectively and result in stronger bonds than the original atomic orbitals. Repulsion is minimized if these two hybrid orbitals are oriented at 180° to each other. If these orbitals overlap with *p* orbitals on F atoms, a linear BeF<sub>2</sub> molecule is obtained.

It should in principle be possible to calculate the relative strength of bonds formed using *s*, *p* or various hybrid orbitals. However, the wave equation can only be solved exactly for atoms containing one electron, that is hydrogen like species H, He<sup>+</sup>, Li<sup>2+</sup>, Be<sup>3+</sup> etc. Attempts to work out the relative bond strengths involve approximations, which may or may not be valid. On this basis it has been suggested that the relative strengths of

Table 4.4 Number of orbitals and type of hybridization

Number of outer orbitals	Type of hybridization	Distribution in space of hybrid orbitals
2	$sp$	Linear
3	$sp^2$	Plane triangle
4	$sp^3$	Tetrahedron
5	$sp^3d$	Trigonal bipyramid
6	$sp^3d^2$	Octahedron
7	$sp^3d^3$	Pentagonal bipyramid
(4	$dsp^2$ )	Square planar


bonds using *s*, *p* and various hybrid atomic orbitals may be as shown in Table 4.3.

Hybridization and the mixing of orbitals is a most useful concept. Mixing of *s* and *p* orbitals is well accepted, but the involvement of *d* orbitals is controversial. For effective mixing, the energy of the orbitals must be nearly the same.

It is a common misconception that hybridization is the cause of a particular molecular shape. This is not so. The reason why any particular shape is adopted is its energy. It is also important to remember that the hybridized state is a theoretical step in going from an atom to a molecule, and the hybridized state never actually exists. It cannot be detected even spectroscopically, so the energy of hybrid orbitals cannot be measured and can only be estimated theoretically.

### THE EXTENT OF *d* ORBITAL PARTICIPATION IN MOLECULAR BONDING

The bonding in  $\text{PCl}_5$  may be described using hybrids of the *3s*, *3p* and *3d* atomic orbitals for P – see below. However, there are doubts as to whether *d* orbitals can take part and this has led to the decline of this theory.




However, *d* orbitals are in general too large and too high in energy to mix completely with *s* and *p* orbitals. The difference in size is illustrated by

the mean values for the radial distance for different phosphorus orbitals  $3s = 0.47 \text{ \AA}$ ,  $3p = 0.55 \text{ \AA}$  and  $3d = 2.4 \text{ \AA}$ . The energy of an orbital is proportional to its mean radial distance, and since the  $3d$  orbital is much larger it is much higher in energy than the  $3s$  and  $3p$  orbitals. It would at first seem unlikely that hybridization involving  $s$ ,  $p$  and  $d$  orbitals could possibly occur.

Several factors affect the size of orbitals. The most important is the charge on the atom. If the atom carries a formal positive charge then all the electrons will be pulled in towards the nucleus. The effect is greatest for the outer electrons. If the central P atom is bonded to a highly electronegative element such as F, O or Cl, then the electronegative element attracts more than its share of the bonding electrons and the F or Cl atom attains a  $\delta^-$  charge. This leaves a  $\delta^+$  charge on P, which makes the orbitals contract. Since the  $3d$  orbital contracts in size very much more than the  $3s$  and  $3p$  orbitals, the energies of the  $3s$ ,  $3p$  and  $3d$  orbitals may become close enough to allow hybridization to occur in  $\text{PCl}_5$ . Hydrogen does not cause this large contraction, so  $\text{PH}_5$  does not exist.

In a similar way the structure of  $\text{SF}_6$  can be described by mixing the  $3s$ , three  $3p$  and two  $3d$  orbitals, that is  $sp^3d^2$  hybridization.



The presence of six highly electronegative F atoms causes a large contraction of the  $d$  orbitals, and lowers their energy, so mixing may be possible.

A second factor affecting the size of  $d$  orbitals is the number of  $d$  orbitals occupied by electrons. If only one  $3d$  orbital is occupied on an S atom the

Table 4.5 Sizes of orbitals

$(sp^3d^2 \text{ configuration})$	Mean radial distance ( $\text{\AA}$ )		
	$3s$	$3p$	$3d$
S atom (neutral no charge)	0.88	0.94	1.60
S atom (charge +0.6)	0.87	0.93	1.40

average radial distance is  $2.46 \text{ \AA}$ , but when two  $3d$  orbitals are occupied the distance drops to  $1.60 \text{ \AA}$ . The effect of changing the charge can be seen in Table 4.5.


A further small contraction of  $d$  orbitals may arise by coupling of the spins of electrons occupying different orbitals.

It seems probable that  $d$  orbitals do participate in bonding in cases where  $d$  orbital contraction occurs.

## SIGMA AND PI BONDS


All the bonds formed in these examples result from end to end overlap of orbitals and are called sigma  $\sigma$  bonds. In  $\sigma$  bonds the electron density is concentrated in between the two atoms, and on a line joining the two atoms. Double or triple bonds occur by the sideways overlap of orbitals, giving pi  $\pi$  bonds. In  $\pi$  bonds the electron density also concentrates between the atoms, but on either side of the line joining the atoms. The shape of the molecule is determined by the  $\sigma$  bonds (and lone pairs) but not by the  $\pi$  bonds. Pi bonds merely shorten the bond lengths.

Consider the structure of the carbon dioxide molecule. Since C is typically four-valent and O is typically two-valent, the bonding can be simply represented



Triatomic molecules must be either linear or angular. In  $\text{CO}_2$ , the C atom must be excited to provide four unpaired electrons to form the four bonds required.


Electronic structure of carbon atom – ground state



Electronic structure of carbon atom – excited state



Carbon atom having gained four electrons from oxygen atoms by forming four bonds



There are two  $\sigma$  bonds and two  $\pi$  bonds in the molecule. Pi orbitals are ignored in determining the shape of the molecule. The remaining  $s$  and  $p$  orbitals are used to form the  $\sigma$  bonds. (These could be hybridized and the two  $sp^2$  orbitals will point in opposite directions. Alternatively VSEPR theory suggests that these two orbitals will be oriented as far apart as possible.) These two orbitals overlap with  $p$  orbitals from two O atoms, forming a linear molecule with a bond angle of  $180^\circ$ . The  $2p_y$  and  $2p_z$  orbitals on C used for  $\pi$  bonding are at right angles to the bond, and




Figure 4.11 Sigma and pi overlap: (a) sigma overlap (lobes point along the nuclei); (b) pi overlap (lobes are at right angles to the line joining the nuclei).


overlap sideways with  $p$  orbitals on the O atoms at either side. This  $\pi$  overlap shortens the C—O distances but does not affect the shape.

The sulphur dioxide molecule  $\text{SO}_2$  may be considered in a similar way. S shows oxidation states of (+II), (+IV) and (+VI), whilst O is two valent. The structure may be represented



Triatomic molecules are either linear or bent. The S atom must be excited to provide four unpaired electrons.

Electronic structure of sulphur atom – ground state



Electronic structure of sulphur atom – excited state



Sulphur atom having gained four electrons from four bonds to oxygen atoms in  $\text{SO}_2$  molecule






Figure 4.12 Sulphur dioxide molecule

The two electron pairs which form the  $\pi$  bonds do not affect the shape of the molecule. The remaining three orbitals point to the corners of a triangle, and result in a planar triangular structure for the molecule with two corners occupied by O atoms and one corner occupied by a lone pair. The  $\text{SO}_2$  molecule is thus angular or V shaped (Figure 4.12).

The  $\pi$  bonds do not alter the shape but merely shorten the bond lengths. The bond angle is reduced from the ideal value of  $120^\circ$  to  $119^\circ 30'$  because of the repulsion by the lone pair of electrons. Problems arise when we examine exactly which AOs are involved in  $\pi$  overlap. If the  $\sigma$  bonding occurs in the  $xy$  plane then  $\pi$  overlap can occur between the  $3p$  orbital on S and the  $2p$  orbital on one O atom to give one  $\pi$  bond. The second  $\pi$  bond involves a  $d$  orbital. Though the  $3d$  orbital on S is in the correct orientation for  $\pi$  overlap with the  $2p$  orbital on the other O atom, the symmetry of the  $3d_{xy}$  orbital is wrong (both lobes have a + sign) whilst for a  $p$  orbital one lobe is + and the other –. Thus overlap of these orbitals does not result in bonding. The  $3d_{xz}$  orbital on S is in the correct orientation, and has the correct symmetry to overlap with the  $2p$  orbital on the second O atom and could give the second  $\pi$  bond. It is surprising that  $\pi$  bonds involving  $p$  and  $d$  orbitals both have the same energy (and bond length). This calls into question whether it is correct to treat molecules with two  $\pi$  bonds as containing two discrete  $\pi$  bonds. A better approach is to treat the  $\pi$  bonds as being delocalized over several atoms. Examples of this treatment are given near the end of this chapter.



In the sulphur trioxide molecule  $\text{SO}_3$  valency requirements suggest the structure




The central S atom must be excited to provide six unpaired electrons to form six bonds.

Electronic structure of sulphur atom – excited state



Sulphur atom having gained six electrons from six bonds to oxygen atoms in  $\text{SO}_3$  molecule



The three  $\pi$  bonds are ignored in determining the shape of the molecule. The three  $\sigma$  orbitals are directed towards the corners of an equilateral triangle, and the  $\text{SO}_3$  molecule is a completely regular plane triangle (Figure 4.13). The  $\pi$  bonds shorten the bond lengths, but do not affect the shape. This approach explains the  $\sigma$  bonding and shape of the molecule, but the explanation of  $\pi$  bonding is unsatisfactory. It presumes:

1. That one  $3p$  and two  $3d$  orbitals on S are in the correct orientation to overlap sideways with the  $2p_y$  or  $2p_z$  orbitals on three different O atoms, and
2. That the  $\pi$  bonds formed are all of equal strength.

This calls into question the treatment of  $\pi$  bonds. In molecules with more than one  $\pi$  bond, or molecules where the  $\pi$  bond could equally well exist in more than one position, it is better to treat the  $\pi$  bonding as being delocalized over several atoms rather than localized between two atoms. This approach is developed near the end of this chapter.




Figure 4.13 Sulphur trioxide molecule.

## MOLECULAR ORBITAL METHOD

In the valence bond (electron pair) theory, a molecule is considered to be made up of atoms. Electrons in atoms occupy atomic orbitals. These may or may not be hybridized. If they are hybridized, atomic orbitals from the same atom combine to produce hybrid orbitals which can overlap more effectively with orbitals from other atoms, thus producing stronger bonds. Thus the atomic orbitals (or the hybrid orbitals) are thought to remain even when the atom is chemically bonded in a molecule.

In the molecular orbital theory, the valency electrons are considered to

be associated with all the nuclei in the molecule. Thus the atomic orbitals *from different atoms* must be combined to produce molecular orbitals.

Electrons may be considered either as particles or waves. An electron in an atom may therefore be described as occupying an atomic orbital or by a wave function  $\psi$  which is a solution to the Schrödinger wave equation. Electrons in a molecule are said to occupy molecular orbitals. The wave function describing a molecular orbital may be obtained by one of two procedures:

1. Linear combination of atomic orbitals (LCAO)
2. United atom method

### LCAO METHOD

Consider two atoms A and B which have atomic orbitals described by the wave functions  $\psi_{(A)}$  and  $\psi_{(B)}$ . If the electron clouds of these two atoms overlap when the atoms approach, then the wave function for the molecule (molecular orbital  $\psi_{(AB)}$ ) can be obtained by a linear combination of the atomic orbitals  $\psi_{(A)}$  and  $\psi_{(B)}$ :

$$\psi_{(AB)} = N(c_1\psi_{(A)} + c_2\psi_{(B)})$$

where  $N$  is a normalizing constant chosen to ensure that the probability of finding an electron in the whole of the space is unity, and  $c_1$  and  $c_2$  are constants chosen to give a minimum energy for  $\psi_{(AB)}$ . If atoms A and B are similar, then  $c_1$  and  $c_2$  will have similar values. If atoms A and B are the same, then  $c_1$  and  $c_2$  are equal.

The probability of finding an electron in a volume of space  $dV$  is  $\psi^2 dV$ , so the probability density for the combination of two atoms as above is related to the wave function squared:

$$\psi_{(AB)}^2 = (c_1^2\psi_{(A)}^2 + 2c_1c_2\psi_{(A)}\psi_{(B)} + c_2^2\psi_{(B)}^2)$$

If we examine the three terms on the right of the equation, the first term  $c_1^2\psi_{(A)}^2$  is related to the probability of finding an electron on atom A if A is an isolated atom. The third term  $c_2^2\psi_{(B)}^2$  is related to the probability of finding an electron on atom B if B is an isolated atom. The middle term becomes increasingly important as the overlap between the two atomic orbitals increases, and this term is called the overlap integral. This term represents the main difference between the electron clouds in individual atoms and in the molecule. The larger this term, the stronger the bond.

### s-s combinations of orbitals

Suppose the atoms A and B are hydrogen atoms, then the wave functions  $\psi_{(A)}$  and  $\psi_{(B)}$  describe the 1s atomic orbitals on the two atoms. Two combinations of the wave functions  $\psi_{(A)}$  and  $\psi_{(B)}$  are possible:

1. Where the signs of the two wave functions are the same
2. Where the signs of the two wave functions are different

(If one of the wave functions  $\psi_{(A)}$  is arbitrarily assigned a +ve sign, the other may be either +ve or -ve.) Wave functions which have the same sign may be regarded as waves that are in phase, which when combined add up to give a larger resultant wave. Similarly wave functions of different signs correspond to waves that are completely out of phase and which cancel each other by destructive interference. (The signs + and - refer to signs of the wave functions, which determine their symmetry, and have nothing to do with electrical charges.) The two combinations are:

$$\psi_{(g)} = N\{\psi_{(A)} + \psi_{(B)}\}$$

and

$$\psi_{(u)} = N\{\psi_{(A)} + [-\psi_{(B)}]\} \equiv N\{\psi_{(A)} - \psi_{(B)}\}$$

The latter equation should be regarded as the summation of the wave functions and *not* as the mathematical difference between them.




Figure 4.14 s-s combinations of atomic orbitals.

When a pair of atomic orbitals  $\psi_{(A)}$  and  $\psi_{(B)}$  combine, they give rise to a pair of molecular orbitals  $\psi_{(g)}$  and  $\psi_{(u)}$ . The number of molecular orbitals produced must always be equal to the number of atomic orbitals involved. The function  $\psi_{(g)}$  leads to increased electron density in between the nuclei, and is therefore a bonding molecular orbital. It is lower in energy than the original atomic orbitals. Conversely  $\psi_{(u)}$  results in two lobes of opposite sign cancelling and hence giving zero electron density in between the nuclei. This is an antibonding molecular orbital which is higher in energy (Figure 4.15).

The molecular orbital wave functions are designated  $\psi_{(g)}$  and  $\psi_{(u)}$ ; g stands for *gerade* (even) and u for *ungerade* (odd). g and u refer to the symmetry of the orbital about its centre. If the sign of the wave function is unchanged when the orbital is reflected about its centre (i.e. x, y and z are replaced by -x, -y and -z) the orbital is *gerade*. An alternative method




Figure 4 15 Energy of  $\psi(g)$  and  $\psi(u)$  molecular orbitals

for determining the symmetry of the molecular orbital is to rotate the orbital about the line joining the two nuclei and then about a line perpendicular to this. If the sign of the lobes remains the same, the orbital is *gerade*, and if the sign changes, the orbital is *ungerade*.

The energy of the bonding molecular orbital  $\psi(g)$  passes through a minimum (Figure 4 15), and the distance between the atoms at this point corresponds to the internuclear distance between the atoms when they form a bond. Consider the energy levels of the two  $1s$  atomic orbitals, and of the bonding  $\psi(g)$  and antibonding  $\psi(u)$  orbitals (Figure 4 16).

The energy of the bonding molecular orbital is lower than that of the atomic orbital by an amount  $\Delta$ . This is known as the stabilization energy.




Figure 4 16 Energy levels of  $s-s$  atomic and molecular orbitals

Similarly the energy of the antibonding molecular orbital is increased by  $\Delta$ . Atomic orbitals may hold up to two electrons (provided that they have opposite spins) and the same applies to molecular orbitals. In the case of two hydrogen atoms combining, there are two electrons to be considered: one from the  $1s$  orbital of atom A and one from the  $1s$  orbital of atom B. When combined, these two electrons both occupy the bonding molecular orbital  $\psi_{(g)}$ . This results in a saving of energy of  $2\Delta$ , which corresponds to the bond energy: It is only because the system is stabilized in this way that a bond is formed.

Consider the hypothetical case of two He atoms combining. The  $1s$  orbitals on each He contain two electrons, making a total of four electrons to put into molecular orbitals. Two of the electrons occupy the bonding MO, and two occupy the antibonding MO. The stabilization energy  $2\Delta$  derived from filling the bonding MO is offset by the  $2\Delta$  destabilization energy from using the antibonding MO. Since overall there is no saving of energy,  $\text{He}_2$  does not exist, and this situation corresponds to non-bonding.

Some further symbols are necessary to describe the way in which the atomic orbitals overlap. Overlap of the orbitals along the axis joining the nuclei produces  $\sigma$  molecular orbitals, whilst lateral overlap of atomic orbitals forms  $\pi$  molecular orbitals.

### $s-p$ combinations of orbitals

An  $s$  orbital may combine with a  $p$  orbital provided that the lobes of the  $p$  orbital are pointing along the axis joining the nuclei. When the lobes which overlap have the same sign this results in a bonding MO with an increased electron density between the nuclei. When the overlapping lobes have




Figure 4.17  $s-p$  combination of atomic orbitals.

opposite signs this gives an antibonding MO with a reduced electron density in between the nuclei (Figure 4 17)

### $p$ - $p$ combinations of orbitals

Consider first the combination of two  $p$  orbitals which both have lobes pointing along the axis joining the nuclei. Both a bonding MO and an antibonding MO are produced (Figure 4 18)

Next consider the combination of two  $p$  orbitals which both have lobes perpendicular to the axis joining the nuclei. Lateral overlap of orbitals will




Figure 4 18  $p$ - $p$  combination of atomic orbitals




Figure 4 19  $p$ - $p$  combinations giving  $\pi$  bonding

occur, resulting in  $\pi$  bonding and  $\pi^*$  antibonding MOs being produced (Figure 4.19).

There are three points of difference between these molecular orbitals and the  $\sigma$  orbitals described previously:

1. For  $\pi$  overlap the lobes of the atomic orbitals are perpendicular to the line joining the nuclei, whilst for  $\sigma$  overlap the lobes point along the line joining the two nuclei.
2. For  $\pi$  molecular orbitals,  $\psi$  is zero along the internuclear line and consequently the electron density  $\psi^2$  is also zero. This is in contrast to  $\sigma$  orbitals.
3. The symmetry of  $\pi$  molecular orbitals is different from that shown by  $\sigma$  orbitals. If the bonding  $\pi$  MO is rotated about the internuclear line a change in the sign of the lobe occurs. The  $\pi$  bonding orbitals are therefore *ungerade*, whereas all  $\sigma$  bonding MOs are *gerade*. Conversely the antibonding  $\pi$  MO is *gerade* whilst all  $\sigma$  antibonding MOs are *ungerade*.

$\pi$  bonding is important in many organic compounds such as ethene (where there is one  $\sigma$  bond and one  $\pi$  bond between the two carbon atoms), ethyne (one  $\sigma$  and two  $\pi$ ), and benzene, and also in a number of inorganic compounds such as  $\text{CO}_2$  and  $\text{CN}^-$ .

Ethene contains a localized double bond, which involves only the two carbon atoms. Experimental measurements show that the two C atoms and the four H atoms are coplanar, and the bond angles are close to  $120^\circ$ . Each C atom uses its  $2s$  and two  $2p$  orbitals to form three  $sp^2$  hybrid orbitals that form  $\sigma$  bonds to the other C atom and two H atoms. The remaining  $p$  orbital on each C atom is at right angles to the  $\sigma$  bonds so far formed. In the valence bond theory these two  $p$  orbitals overlap sideways to give a  $\pi$  bond. This sideways overlap is not as great as the end to end overlap in  $\sigma$  bonds so a  $\text{C}=\text{C}$ , though stronger than a  $\text{C}-\text{C}$  bond, is not twice as strong ( $\text{C}-\text{C}$  in ethane  $346\text{ kJ mol}^{-1}$ ,  $\text{C}=\text{C}$  in ethene  $598\text{ kJ mol}^{-1}$ ). The molecule can be twisted about the  $\text{C}-\text{C}$  bond in ethane, but it cannot be twisted in ethene since this would reduce the amount of  $\pi$  overlap. In the molecular orbital theory the explanation of the  $\pi$  bonding is slightly different. The two  $p$  orbitals involved in  $\pi$  bonding combine to form two  $\pi$  molecular orbitals, one bonding and one antibonding. Since there are only two electrons involved, these occupy the  $\pi$  bonding MO since this has the lower energy. The molecular orbital explanation becomes more important in cases where there is non-localized  $\pi$  bonding, that is where  $\pi$  bonding covers several atoms as in benzene,  $\text{NO}_3^-$  and  $\text{CO}_3^{2-}$ .

In ethyne each C atom uses  $sp$  hybrid orbitals to form  $\sigma$  bonds to the other C atom and a H atom. These four atoms form a linear molecule. Each C atom has two  $p$  orbitals at right angles to one another, and these overlap sideways with the equivalent  $p$  orbitals on the other C atom, thus forming two  $\pi$  bonds. Thus a  $\text{C}\equiv\text{C}$  triple bond is formed, which is stronger than a  $\text{C}=\text{C}$  double bond ( $\text{C}\equiv\text{C}$  in ethyne  $813\text{ kJ mol}^{-1}$ ).

The majority of strong  $\pi$  bonds occur between elements of the first short

period in the periodic table, for example  $\text{C}\equiv\text{C}$ ,  $\text{C}\equiv\text{N}$ ,  $\text{C}\equiv\text{O}$ ,  $\text{C}=\text{C}$  and  $\text{C}=\text{O}$ . This is mainly because the atoms are smaller and hence the orbitals involved are reasonably compact, so it is possible to get substantial overlap of orbitals. There are a smaller number of cases where  $\pi$  bonding occurs between different types of orbitals, for example the  $2p$  and  $3d$  orbitals. Though these orbitals are much larger, the presence of nodes may concentrate electron density in certain parts of the orbitals.

### $p$ - $d$ combinations of orbitals

A  $p$  orbital on one atom may overlap with a  $d$  orbital on another atom as shown, giving bonding and antibonding combinations. Since the orbitals do not point along the line joining the two nuclei, overlap must be of the  $\pi$  type (Figure 4.20). This type of bonding is responsible for the short bonds found in the oxides and oxoacids of phosphorus and sulphur. It also occurs in transition metal complexes such as the carbonyls and cyanides.




Figure 4.20  $p$ - $d$  combinations of atomic orbitals

### $d$ - $d$ combinations of orbitals

It is possible to combine two  $d$  atomic orbitals, producing bonding and antibonding MOs which are called  $\delta$  and  $\delta^*$  respectively. On rotating these orbitals about the internuclear axis, the sign of the lobes changes four times compared with two changes with  $\pi$  overlap and no change for  $\sigma$  overlap.

### Non bonding combinations of orbitals

All the cases of overlap of atomic orbitals considered so far have resulted in a bonding MO of lower energy, and an antibonding MO of higher energy. To obtain a bonding MO with a concentration of electron density in between the nuclei, the signs (symmetry) of the lobes which overlap




Figure 4.21  $\delta$  bonding by  $d$  orbitals (sideways overlap of two  $x^2-y^2$  orbitals)






Figure 4.22 Some non-bonding combinations of atomic orbitals.

must be the same. Similarly for antibonding MOs the signs of the overlapping lobes must be different. In the combinations shown in Figure 4.22 any stabilization which occurs from overlapping + with + is destabilized by an equal amount of overlap of + with -. There is no overall change in energy, and this situation is termed non-bonding. It should be noted that in all of these non-bonding cases the symmetry of the two atomic orbitals is different, i.e. rotation about the axis changes the sign of one.

## RULES FOR LINEAR COMBINATION OF ATOMIC ORBITALS

In deciding which atomic orbitals may be combined to form molecular orbitals, three rules must be considered:

1. The atomic orbitals must be roughly of the same energy. This is important when considering overlap between two different types of atoms.
2. The orbitals must overlap one another as much as possible. This implies that the atoms must be close enough for effective overlap and that the radial distribution functions of the two atoms must be similar at this distance.
3. In order to produce bonding and antibonding MOs, either the symmetry of the two atomic orbitals must remain unchanged when rotated about the internuclear line, or both atomic orbitals must change symmetry in an identical manner.

In the same way that each atomic orbital has a particular energy, and may be defined by four quantum numbers, each molecular orbital has a definite energy, and is also defined by four quantum numbers.

1. The principal quantum number  $n$  has the same significance as in atomic orbitals.
2. The subsidiary quantum number  $l$  also has the same significance as in atomic orbitals.
3. The magnetic quantum number of atomic orbitals is replaced by a new quantum number  $\lambda$ . In a diatomic molecule, the line joining the nuclei is taken as a reference direction and  $\lambda$  represents the quantization of angular momentum in  $h/2\pi$  units with respect to this axis.  $\lambda$  takes the same values as  $m$  takes for atoms, i.e.


$$\lambda = -l, \quad , -3, -2, -1, 0, +1, +2, +3, \quad , +l$$

When  $\lambda = 0$ , the orbitals are symmetrical around the axis and are called  $\sigma$  orbitals. When  $\lambda = \pm 1$  they are called  $\pi$  orbitals and when  $\lambda = \pm 2$  they are called  $\delta$  orbitals.

- 4 The spin quantum number is the same as for atomic orbitals and may have values of  $\pm \frac{1}{2}$ .

The Pauli exclusion principle states that *in a given atom no two electrons can have all four quantum numbers the same*. The Pauli principle also applies to molecular orbitals. *No two electrons in the same molecule can have all four quantum numbers the same*.


The order of energy of molecular orbitals has been determined mainly from spectroscopic data. In simple homonuclear diatomic molecules, the order is



Note that the  $2p_y$  atomic orbital gives  $\pi$  bonding and  $\pi^*$  antibonding MOs and the  $2p_z$  atomic orbital gives  $\pi$  bonding and  $\pi^*$  antibonding MOs. The bonding  $\pi 2p_y$  and  $\pi 2p_z$  MOs have exactly the same energy and are said to be double degenerate. In a similar way the antibonding  $\pi^* 2p_y$  and  $\pi^* 2p_z$  MOs have the same energy and are also doubly degenerate.

A similar arrangement of MOs exists from  $\sigma 3s$  to  $\sigma^* 3p_x$ , but the energies are known with less certainty.

The energies of the  $\sigma 2p$  and  $\pi 2p$  MOs are very close together. The order of MOs shown above is correct for oxygen and heavier elements, but for the lighter elements boron, carbon and nitrogen the  $\pi 2p_y$  and  $\pi 2p_z$  are probably lower than  $\sigma 2p_x$ . For these atoms the order is



### EXAMPLES OF MOLECULAR ORBITAL TREATMENT FOR HOMONUCLEAR DIATOMIC MOLECULES

In the build up of atoms, electrons are fed into atomic orbitals. The *Aufbau* principle is used.

- 1 Orbitals of lowest energy are filled first.
- 2 Each orbital may hold up to two electrons, provided that they have opposite spins.

Hund's rule states that when several orbitals have the same energy (that is they are degenerate), electrons will be arranged so as to give the maximum number of unpaired spins.

In the molecular orbital method, we consider the whole molecule rather than the constituent atoms, and use molecular orbitals rather than atomic orbitals. In the build-up of the molecule, the total number of electrons from all the atoms in the molecule is fed into molecular orbitals. The *Aufbau* principle and Hund's rule are used as before.

For simplicity homonuclear diatomic molecules will be examined first. Homonuclear means that there is only one type of nucleus, that is one element present, and diatomic means that the molecule is composed of two atoms.

### $\text{H}_2^+$ molecule ion

This may be considered as a combination of a H atom with a  $\text{H}^+$  ion. This gives one electron in the molecular ion which occupies the lowest energy MO:



The electron occupies the  $\sigma 1s$  bonding MO. The energy of this ion is thus lower than that of the constituent atom and ion, by an amount  $\Delta$ , so there is some stabilization. This species exists but it is not common since  $\text{H}_2$  is much more stable. However,  $\text{H}_2^+$  can be detected spectroscopically when  $\text{H}_2$  gas under reduced pressure is subjected to an electric discharge.

### $\text{H}_2$ molecule

There is one electron from each atom, and hence there are two electrons in the molecule. These occupy the lowest energy MO:



This is shown in Figure 4.23. The bonding  $\sigma 1s$  MO is full, so the stabilization energy is  $2\Delta$ . A  $\sigma$  bond is formed, and the  $\text{H}_2$  molecule exists and is well known.





Figure 4.23 Electronic configuration, atomic and molecular orbitals for hydrogen.

**He<sub>2</sub><sup>+</sup> molecule ion**


This may be considered as a combination of a He atom and a He<sup>+</sup> ion. There are three electrons in the molecular ion, which are arranged in MOs



The filled  $\sigma 1s$  bonding MO gives  $2\Delta$  stabilization, whilst the half filled  $\sigma 1s^*$  gives  $\Delta$  destabilization. Overall there is  $\Delta$  stabilization. Thus the helium molecule ion can exist. It is not very stable, but it has been observed spectroscopically.

**He<sub>2</sub> molecule**

There are two electrons from each atom, and the four electrons are arranged in MOs



The  $2\Delta$  stabilization energy from filling the  $\sigma 2s$  MO is cancelled by the  $2\Delta$  destabilization energy from filling the  $\sigma^* 1s$  MO. Thus a bond is not formed, and the molecule does not exist.

**Li<sub>2</sub> molecule**

Each Li atom has two electrons in its inner shell, and one in its outer shell, giving three electrons. Thus there is a total of six electrons in the molecule, and these are arranged in MOs



This is shown in Figure 4.24. The inner shell of filled  $\sigma 1s$  and  $\sigma^* 1s$  MOs do not contribute to the bonding in much the same way as in He<sub>2</sub>. They are essentially the same as the atomic orbitals from which they were formed, and are sometimes written



However, bonding occurs from the filling of the  $\sigma 2s$  level, and Li<sub>2</sub> molecules do exist in the vapour state. However, in the solid it is energetically more favourable for lithium to form a metallic structure. Other Group 1 metals such as sodium behave in an analogous way.

**Be<sub>2</sub> molecule**

A beryllium atom has two electrons in the first shell plus two electrons in the second shell. Thus in the Be<sub>2</sub> molecule there are eight electrons. These are arranged in MOs






Figure 4.24 Electronic configuration, atomic and molecular orbitals for lithium.




or



Ignoring the inner shell as before, it is apparent that the effects of the bonding  $\sigma_{2s}$  and antibonding  $\sigma^*_{2s}$  levels cancel, so there is no stabilization and the molecule would not be expected to exist.

### $\text{B}_2$ molecule

Each boron atom has 2 + 3 electrons. The  $\text{B}_2$  molecule thus contains a total of ten electrons, which are arranged in MOs:



This may be shown diagrammatically (Figure 4.25). Note that B is a light atom and the order of energies of MOs is different from the 'usual' arrangement. Thus the  $\pi_{2p}$  orbitals are lower in energy than the  $\sigma_{2p_x}$ . Since the  $\pi_{2p_y}$  and  $\pi_{2p_z}$  orbitals are degenerate (identical in energy), Hund's rule applies, and each is singly occupied. The inner shell does not




Figure 4 25 Electronic configuration atomic and molecular orbitals for boron

participate in bonding. The effects of bonding and antibonding  $\sigma_{2s}$  orbitals cancel but stabilization occurs from the filling of the  $\pi_{2p}$  orbitals and hence a bond is formed and  $B_2$  exists.

#### $C_2$ molecule

A carbon atom has  $2 + 4$  electrons. A  $C_2$  molecule would contain a total of 12 electrons and these would be arranged in MOs.




Figure 4.26 Electronic configuration, atomic and molecular orbitals for carbon.

$$\sigma 1s^2, \sigma^* 1s^2, \sigma 2s^2, \sigma^* 2s^2, \begin{cases} \pi 2p_y^2 \\ \pi 2p_z^2 \end{cases}$$

This is shown diagrammatically in Figure 4.26.

The molecule should be stable, since the two  $\pi 2p$  bonding orbitals provide  $4\Delta$  of stabilization energy, giving two bonds. In fact carbon exists as a macromolecule in graphite and diamond, since these are an even more stable arrangement (where each carbon forms four bonds): hence diamond and graphite are formed in preference to  $C_2$ .




Figure 4 27 Electronic configuration, atomic and molecular orbitals for nitrogen

### $N_2$ molecule

A nitrogen atom has  $2 + 5 = 7$  electrons. Thus the  $N_2$  molecule contains 14 electrons. These are arranged in MOs

$$\sigma 1s^2, \sigma^* 1s^2, \sigma 2s^2, \sigma^* 2s^2, \left\{ \begin{array}{l} \pi 2p_y^2 \\ \pi 2p_z^2 \end{array} \right\} \sigma 2p_x^2,$$



This is shown diagrammatically (Figure 4.27).

Assuming that the inner shell does not participate in bonding, and that the bonding and antibonding  $2s$  levels cancel, one  $\sigma$  and two  $\pi$  bonding pairs remain, giving a total of three bonds. This is in agreement with the valence bond formulation as  $\text{N}\equiv\text{N}$ .


### $\text{O}_2$ molecule

Each oxygen atom has  $2 + 6 = 8$  electrons. Thus the  $\text{O}_2$  molecule contains a total of 16 electrons. These are arranged in MOs:

$$\sigma 1s^2, \sigma^* 1s^2, \sigma 2s^2, \sigma^* 2s^2, \sigma 2p_x^2, \left\{ \begin{array}{l} \pi 2p_y^2 \\ \pi 2p_z^2 \end{array} \right\}, \left\{ \begin{array}{l} \pi^* 2p_y^1 \\ \pi^* 2p_z^1 \end{array} \right\}$$

This is shown diagrammatically in Figure 4.28.

The antibonding  $\pi^* 2p_y$  and  $\pi^* 2p_z$  orbitals are singly occupied in accordance with Hund's rule. Unpaired electrons give rise to paramagnetism. Since there are two unpaired electrons with parallel spins, this explains why dioxygen is paramagnetic. If this treatment is compared with the Lewis electron pair theory or the valence bond theory, these do not predict unpaired electrons or paramagnetism.



This was the first success of the molecular orbital theory in successfully predicting the paramagnetism of  $\text{O}_2$ , a fact not even thought of with a valence bond representation of  $\text{O}=\text{O}$ .

As in the previous examples, the inner shell does not participate in bonding and the bonding and antibonding  $2s$  orbitals cancel each other. A  $\sigma$  bond results from the filling of  $\sigma 2p_x^2$ . Since  $\pi^* 2p_y^1$  is half filled and therefore cancels half the effect of the completely filled  $\pi 2p_y^2$  orbital, half of a  $\pi$  bond results. Similarly another half of a  $\pi$  bond arises from  $\pi 2p_z^2$  and  $\pi^* 2p_z^1$ , giving a total of  $1 + \frac{1}{2} + \frac{1}{2} = 2$  bonds. The bond order is thus two.

Instead of working out the bond order by cancelling the effects of filled bonding and antibonding MOs, the bond order may be calculated as half the difference between the number of bonding and antibonding electrons:

$$\text{Bond order} = \frac{\left( \begin{array}{c} \text{number of electrons} \\ \text{occupying bonding orbitals} \end{array} \right) - \left( \begin{array}{c} \text{number of electrons} \\ \text{in antibonding orbitals} \end{array} \right)}{2}$$

In the case of  $\text{O}_2$  the bond order calculates as  $(10 - 6)/2 = 2$ , which corresponds to a double bond.

### $\text{O}_2^-$ ion

The compound potassium superoxide  $\text{KO}_2$  contains the superoxide ion  $\text{O}_2^-$ . The  $\text{O}_2^-$  ion has 17 electrons, and has one more electron than the  $\text{O}_2$




Figure 4 28 Electronic configuration, atomic and molecular orbitals for oxygen

molecule This extra electron occupies either the  $\pi^*_{2p_y}$  or  $\pi^*_{2p_z}$  orbital It does not matter which it occupies since they are the same energy

$$\sigma_{1s}^2, \sigma^*_{1s}^2, \sigma_{2s}^2, \sigma^*_{2s}^2, \sigma_{2p_z}^2, \left\{ \begin{array}{l} \pi_{2p_y}^2 \\ \pi_{2p_z}^2 \end{array} \right\}, \left\{ \begin{array}{l} \pi^*_{2p_y}^1 \\ \pi^*_{2p_z}^1 \end{array} \right\}$$

The inner shell of electrons does not take part in bonding The bonding  $\sigma_{2s}^2$  and antibonding  $\sigma^*_{2s}^2$  cancel The  $\sigma_{2p_z}^2$  orbital is filled and forms a

$\sigma$  bond. The effects of the bonding  $\pi 2p_y^2$  and antibonding  $\pi 2p_y^2$  orbitals cancel, and the completely filled bonding  $\pi 2p_z^2$  is half cancelled by the half filled antibonding  $\pi 2p_z^1$ , thus giving half a  $\pi$  bond. The bond order is thus  $1 + \frac{1}{2} = 1\frac{1}{2}$ . Alternatively the bond order may be calculated like this: (bonding – antibonding)/2, that is  $(10 - 7)/2 = 1\frac{1}{2}$ . This corresponds to a bond that is intermediate in length between a single and a double bond. The superoxide ion has an unpaired electron and is therefore paramagnetic. (A bond order of  $1\frac{1}{2}$  is well accepted in benzene.)

### $O_2^{2-}$ ion

In a similar way sodium peroxide  $Na_2O_2$  contains the peroxide ion  $O_2^{2-}$ . This ion has 18 electrons, arranged:

$$\sigma 1s^2, \sigma^* 1s^2, \sigma 2s^2, \sigma^* 2s^2, \sigma 2p_x^2, \begin{cases} \pi 2p_y^2 \\ \pi 2p_z^2 \end{cases}, \begin{cases} \pi^* 2p_y^2 \\ \pi^* 2p_z^2 \end{cases}$$

Once again the inner shell takes no part in bonding. The bonding and antibonding  $2s$  orbitals completely cancel each other. One  $\sigma$  bond forms from the filled  $2p_x$  orbital. Both the bonding  $2p_y$  and  $2p_z$  orbitals are cancelled out by their corresponding antibonding orbitals. Thus the bond order is one, that is a single bond. Alternatively the bond order may be calculated as (bonding – antibonding)/2, that is  $(10 - 8)/2 = 1$ .

### $F_2$ molecule

Fluorine atoms have  $2 + 7$  electrons, so an  $F_2$  molecule contains 18 electrons. These are arranged:

$$\sigma 1s^2, \sigma^* 1s^2, \sigma 2s^2, \sigma^* 2s^2, \sigma 2p_x^2, \begin{cases} \pi 2p_y^2 \\ \pi 2p_z^2 \end{cases}, \begin{cases} \pi^* 2p_y^2 \\ \pi^* 2p_z^2 \end{cases}$$

This is shown diagrammatically in Figure 4.29.

The inner shell is non-bonding, and the filled bonding  $2s$ ,  $2p_y$  and  $2p_z$  are cancelled by the equivalent antibonding orbitals. This leaves a  $\sigma$  bond from the filled  $\sigma 2p_x^2$  orbital, and thus a bond order of one. Alternatively the bond order may be calculated as (bonding – antibonding)/2, that is  $(10 - 8)/2 = 1$ .

It should be noted that  $Cl_2$  and  $Br_2$  have structures analogous to  $F_2$ , except that additional inner shells of electrons are full.

The F—F bond is rather weak (see Chapter 15) and this is attributed to the small size of fluorine and repulsion between lone pairs of electrons on adjacent atoms.

## EXAMPLES OF MOLECULAR ORBITAL TREATMENT FOR HETERONUCLEAR DIATOMIC MOLECULES

The same principles apply when combining atomic orbitals from two different atoms as applied when the atoms were identical, that is:




Figure 4 29 Electronic configuration, atomic and molecular orbitals for fluorine

- 1 Only atomic orbitals of about the same energy can combine effectively
- 2 They should have the maximum overlap
- 3 They must have the same symmetry

Since the two atoms are different, the energies of their atomic orbitals are slightly different. A diagram showing how they combine to form molecular orbitals is given in Figure 4 30




Figure 4.30 The relative energy levels of atomic orbitals and molecular orbitals for a heteronuclear diatomic molecule AB.

The problem is that in many cases the order of MO energy levels is not known with certainty. Thus we will consider first some examples where the two different atoms are close to each other in the periodic table, and consequently it is reasonable to assume that the order of energies for the MOs are the same as for homonuclear molecules.

### NO molecule

The nitrogen atom has  $2 + 5 = 7$  electrons, and the oxygen atom has  $2 + 6 = 8$  electrons, making 15 electrons in the molecule. The order of energy levels of the various MOs are the same as for homonuclear diatomic molecules heavier than  $C_2$ , so the arrangement is:

$$\sigma 1s^2, \sigma^* 1s^2, \sigma 2s^2, \sigma^* 2s^2, \sigma 2p_x^2, \left\{ \begin{array}{l} \pi 2p_y^2, \\ \pi 2p_z^2 \end{array} \right\}, \left\{ \begin{array}{l} \pi^* 2p_y^1 \\ \pi^* 2p_z^0 \end{array} \right\}$$

This is shown in Figure 4.31.

The inner shell is non-bonding. The bonding and antibonding  $2s$  orbitals cancel, and a  $\sigma$  bond is formed by the filled  $\sigma 2p_x^2$  orbital. A  $\pi$  bond is formed by the filled  $\pi 2p_z^2$  orbital. The half-filled  $\pi^* 2p_y^1$  half cancels the filled  $\pi 2p_y^2$  orbital, thus giving half a bond. The bond order is thus  $2\frac{1}{2}$ , that is in between a double and a triple bond. Alternatively the bond order may be worked out as  $(\text{bonding} - \text{antibonding})/2$ , that is  $(10 - 5)/2 = 2\frac{1}{2}$ . The molecule is paramagnetic since it contains an unpaired electron. In NO there is a significant difference of about  $250 \text{ kJ mol}^{-1}$  in the energy of the AOs involved, so that combination of AOs to give MOs is less effective than in  $O_2$  or  $N_2$ . The bonds are therefore weaker than might be expected. Apart from this the molecular orbital pattern (Figure 4.31)




Figure 4.31 Electronic configuration, atomic orbitals and molecular orbitals for nitric oxide (This diagram is essentially the same as that for homonuclear diatomic molecules such as  $N_2$ ,  $O_2$  or  $F_2$ . The difference is that the atomic energy levels of N and O are not the same. The  $\sigma 1s$  and  $\sigma^* 1s$  MOs are omitted for simplicity.)

is similar to that for homonuclear diatomic molecules. Removal of one electron to make  $NO^+$  results in a shorter and stronger bond because the electron is removed from an antibonding orbital, thus increasing the bond order to 3.

### CO molecule

The carbon atom has  $2 + 4 = 6$  electrons and the O atom has  $2 + 6 = 8$  electrons, so the CO molecule contains 14 electrons. In this case we are rather less certain of the order of energies of the MOs since they are different for C and O. Assume the order is the same as for light atoms like C.




Figure 4.32 Electronic configuration, atomic orbitals and molecular orbitals for carbon monoxide. (The  $\sigma 1s$  and  $\sigma^* 1s$  MOs are omitted for simplicity.)

$$\sigma 1s^2, \sigma^* 1s^2, \sigma 2s^2, \sigma^* 2s^2, \left\{ \begin{array}{l} \pi 2p_y^2 \\ \pi 2p_z^2 \end{array} \right\} \sigma 2p_x^2$$

This is shown in Figure 4.32.

The inner shell is non-bonding, and the bonding and antibonding 2s orbitals cancel, leaving one  $\sigma$  and two  $\pi$  bonds – and thus a bond order of 3. Alternatively the bond order may be calculated using the formula  $(\text{bonding} - \text{antibonding})/2$ , that is  $(10 - 4)/2 = 3$ . This simple picture is not adequate, since if CO is ionized to give  $\text{CO}^+$  by removal of one electron from the  $\sigma 2p_x$  orbital then the bond order should be reduced to  $2\frac{1}{2}$  and the bond length increased. In fact the bond length in CO is 1.128 Å and in  $\text{CO}^+$  it is 1.115 Å. Thus the bond length decreases when we expected it to increase, and it indicates that the electron must have been removed from an antibonding orbital. The problem remains if we assume

the order of energy for the MOs is the same as for atoms heavier than C, since this only reverses the position of the  $\sigma 2p_x$  and the ( $\pi 2p_y$  and  $\pi 2p_z$ ) MOs. The most likely explanation of the bond shortening when CO is changed to  $\text{CO}^+$  is that the  $\sigma 2s$  and  $\sigma^* 2s$  molecular orbitals differ in energy more than is shown in the figure. This means that they are wider apart, and the  $\sigma^* 2s$  MO is higher in energy than the  $\sigma 2p_x$ ,  $\pi 2p_y$ , and  $\pi 2p_z$  MOs. This illustrates very plainly that the order of MO energy levels for simple homonuclear diatomic molecules used above is not automatically applicable when two different types of atoms are bonded together, and it is certainly incorrect in this particular heteronuclear case.

### HCl molecule

With heteronuclear atoms it is not obvious which AOs should be combined by the LCAO method to form MOs. In addition because the energy levels of the AOs on the two atoms are not identical some MOs will contain a bigger contribution from one AO than the other. This is equivalent to saying that the MO 'bulges' more towards one atom, or the electrons in the MO spend more time round one atom than the other. Thus some degree of charge separation  $\delta^+$  and  $\delta^-$  occurs resulting in a dipole. Thus partial ionic contributions may play a significant part in the bonding.

Consider the HCl molecule. Combination between the hydrogen  $1s$  AO and the chlorine  $1s$ ,  $2s$ ,  $2p$  and  $3s$  orbitals can be ruled out because their energies are too low. If overlap occurred between the chlorine  $3p_y$  and  $3p_z$  orbitals it would be non bonding (see Figure 4.22) because the positive lobe of hydrogen will overlap equally with the positive and negative lobes of the chlorine orbitals. Thus the only effective overlap is with the chlorine  $3p_x$  orbital. The combination of  $\text{H } 1s^1$  and  $\text{Cl } 3p_x^1$  gives both bonding and antibonding orbitals, and the two electrons occupy the bonding MO, leaving the antibonding MO empty. It is assumed that all the chlorine AOs except  $3p_x$  are localized on the chlorine atom and retain their original AO status, and the  $3s$ ,  $3p_y$  and  $3p_z$  orbitals are regarded as non bonding lone pairs.

This over simplification ignores any ionic contribution such as can be shown with the valence bond resonance structures



The former would be expected to contribute significantly, resulting in a stronger bond.


### EXAMPLES OF MOLECULAR ORBITAL TREATMENT INVOLVING DELOCALIZED $\pi$ BONDING

#### Carbonate ion $\text{CO}_3^{2-}$

The structure of the carbonate ion is a planar triangle with bond angles of  $120^\circ$ . The C atom at the centre uses  $sp^2$  orbitals. All three oxygen atoms




are equivalent, and the C—O bonds are shorter than single bonds. A single valence bond structure such as that shown would have different bond lengths, and so fails to describe the structure adequately.



The problem is simply that an electron cannot be represented as a dot, or a pair of electrons as a line (bond). The fourth electron pair that makes up the double bond is not localized in one of the three positions, but is somehow spread out over all three bonds, so that each bond has a bond order of  $1\frac{1}{3}$ .

Pauling adapted the valence bond notation to cover structures where electrons are delocalized. Three contributing structures can be drawn for the carbonate ion:



These contributing structures do not actually exist. The  $\text{CO}_3^{2-}$  does not consist of a mixture of these structures, nor is there an equilibrium between them. The true structure is somewhere in between, and is called a *resonance hybrid*. Resonance was widely accepted in the 1950s but is now regarded at best as clumsy and inadequate, and at worst as misleading or wrong!

Delocalized  $\pi$  bonding is best described by multi-centre bonds, which involve  $\pi$  molecular orbitals. The steps in working this out are:

1. Find the basic shape of the molecule or ion, either experimentally, or from the VSEPR theory using the number of  $\sigma$  bonds and lone pairs on the central atom.
2. Add up the total number of electrons in the outer (valence) shell of all the atoms involved, and add or subtract electrons as appropriate to form ions.
3. Calculate the number of electrons used in  $\sigma$  bonds and lone pairs, and by subtracting this from the total determine the number of electrons which can participate in  $\pi$  bonding.
4. Count the number of atomic orbitals which can take part in  $\pi$  bonding. Combine these to give the same number of molecular orbitals which are delocalized over all of the atoms. Decide whether MOs are bonding, non-bonding or antibonding, and feed the appropriate number of  $\pi$  electrons into the MOs (two electrons per MO). The orbitals with lowest energy are filled first. The number of  $\pi$  bonds formed can easily be determined from the MOs which have been filled.


The structure of the  $\text{CO}_3^{2-}$  will be examined in this way. There are 24 electrons in the valence shell (four from C, six from each of the three O atoms and two from the charges on the ion).

Of these, six are used to form the  $\sigma$  bonds between C and the three O atoms. Each O has four non-bonding electrons. This leaves six electrons available for  $\pi$  bonding.

The atomic orbitals available for  $\pi$  bonding are the  $2p_z$  orbital on C and the  $2p_z$  orbitals from the three O atoms. Combining these four atomic orbitals gives four four-centre  $\pi$  molecular orbitals. Each of these covers all four atoms in the ion. The lowest energy MO is bonding, the highest is antibonding, and the remaining two are non-bonding (and are also degenerate, i.e. the same in energy). The six  $\pi$  electrons occupy the MOs of lowest energy. Two electrons fill the bonding MO and four electrons fill both of the non-bonding MOs and thus contribute one  $\pi$  bond to the molecule. Each of the C—O bonds has a bond order of  $1\frac{1}{2}$ , 1 from the  $\sigma$  bond and  $\frac{1}{2}$  from the  $\pi$  bond.

### Nitrate ion $\text{NO}_3^-$

The structure of the nitrate ion is a planar triangle. The N atom at the centre uses  $sp^2$  orbitals. All three oxygen atoms are equivalent, and the bond lengths N—O are all a little shorter than for a single bond. This cannot be explained by a valence bond structure:




There are 24 electrons in the valence shell (five from N, six from each of the three O atoms and one from the charge on the ion).

Of these, six are used to form the  $\sigma$  bonds between N and the three O atoms. Each O has four non-bonding electrons. This leaves six electrons available for  $\pi$  bonding.

The atomic orbitals used for  $\pi$  bonding are the  $2p_z$  orbitals on N and the three O atoms. Combining these four atomic orbitals gives four four-centre  $\pi$  molecular orbitals. The lowest in energy is bonding, the highest is antibonding, and the remaining two are degenerate (the same in energy) and are non-bonding. The six  $\pi$  electrons fill the bonding MO and both of the non-bonding MOs and thus contribute one  $\pi$  bond to the molecule. Each of the N—O bonds has a bond order of  $1\frac{1}{2}$ , 1 from the  $\sigma$  bond and  $\frac{1}{2}$  from the  $\pi$  bond.

### Sulphur trioxide $\text{SO}_3$

The structure of  $\text{SO}_3$  is a planar triangle. The S atom at the centre uses  $sp^2$  orbitals. All three oxygen atoms are equivalent, and the S—O bonds are much shorter than single bonds. The valence bond structure is:



The multi-centre  $\pi$  MO explanation is as follows. There are 24 electrons in the valence shell (six from S and six from each of the three O atoms).


Of these, six are used to form the  $\sigma$  bonds between S and the three O atoms. Each O has four non-bonding electrons. This leaves six electrons available for  $\pi$  bonding.

$\text{SO}_3$  has 24 outer electrons like the  $\text{NO}_3^-$  ion. If  $\text{SO}_3$  followed the same pattern as the  $\text{NO}_3^-$  ion and used the  $3p_z$  AO on S and the  $2p_z$  AOs on the three O atoms, four MOs would be formed, one bonding, two non-bonding and one antibonding, and the six  $\pi$  electrons would occupy the bonding and non-bonding MOs, thus contributing one  $\pi$  bond to the molecule and giving a S—O bond order of  $1\frac{1}{2}$ . The bonds are much shorter than this would imply. Though  $\text{SO}_3$  has the same number of outer electrons as  $\text{NO}_3^-$ , the two are not isoelectronic. The S atom has three shells of electrons, so there is the possibility of using  $d$  orbitals in the bonding scheme.

The six atomic orbitals available for  $\pi$  bonding are the  $2p_z$  orbitals on the three O atoms and the  $3p_z$ ,  $3d_{xz}$  and  $3d_{yz}$  orbitals on S. Combining one  $2p_z$  AO with the  $3p_z$  AO gives two MOs, one bonding and the other antibonding. Similarly, combining the second  $2p_z$  AO with the  $3d_{xz}$  AO gives one bonding MO and one antibonding MO, and combining the third  $2p_z$  AO with the  $3d_{yz}$  AO gives one bonding MO and one antibonding MO. Thus we obtain three bonding MOs and three antibonding MOs. The six electrons available for  $\pi$  bonding occupy the three bonding MOs, and thus contribute three  $\pi$  bonds to the molecule. Each of the S—O bonds has a bond order of approximately 2, 1 from the  $\sigma$  bond and approximately 1 from the  $\pi$  bond. The reason why the bond order is approximate is that the extent of  $d$  orbital participation depends on the number of electrons and the size and energy of the orbitals involved. This involves detailed calculation.

### Ozone $\text{O}_3$

Ozone  $\text{O}_3$  forms a V-shaped molecule. Both bond lengths are  $1.278 \text{ \AA}$ , and the bond angle is  $116^\circ 48'$ . We assume that the central O atom uses roughly  $sp^2$  orbitals for  $\sigma$  bonding. The valence bond representation of the structure is inadequate since it suggests that the bonds are of different lengths, though it could be explained in terms of resonance hybrids.



The double bonding in the structure is best explained by means of delocalized three centre  $\pi$  bonding. There is a total of 18 electrons in the valence shell made up of six from each of the three O atoms.

The central O atom forms a  $\sigma$  bond with each of the other O atoms, which accounts for four electrons. The central O atom uses  $sp^2$  orbitals, one of which is a lone pair. If the 'end' O atoms also use  $sp^2$  atomic orbitals, each O contains two non bonding pairs of electrons. Thus lone pairs account for 10 electrons. Sigma bonds and lone pairs together account for 14 electrons, thus leaving four electrons for  $\pi$  bonding.

The atomic orbitals involved in  $\pi$  bonding are the  $2p_z$  orbitals on each of the three O atoms. These give rise to three molecular orbitals. These are three centre  $\pi$  molecular orbitals. The lowest energy MO is bonding, the highest energy MO is antibonding, and the middle one is non bonding. There are four  $\pi$  electrons and two fill the bonding MO and two fill the non bonding MO, thus contributing one  $\pi$  bond over the molecule. This gives a bond order of 1.5 for the O—O bonds. The  $\pi$  system is thus a four electron three centre bond.

#### Nitrite ion $\text{NO}_2^-$

The nitrite ion  $\text{NO}_2^-$  is V shaped. This is based on a plane triangular structure, with N at the centre, two corners occupied by O atoms, and the third corner occupied by a lone pair. Thus the N atom is roughly  $sp^2$  hybridized.

In the  $\text{NO}_2^-$  ion there are 18 electrons in the valence shell. These are made up of five from N, six from each of the two O atoms, and one from the charge on the ion.

The N atom forms  $\sigma$  bonds to each of the O atoms, which accounts for four electrons, and the N atom has a lone pair accounting for two electrons. If the O atoms also use  $sp^2$  atomic orbitals (one for bonding and two for lone pairs), the lone pairs on the O atoms account for eight more electrons. A total of 14 electrons has been accounted for, leaving four electrons for  $\pi$  bonding.

Three atomic orbitals are involved in  $\pi$  bonding: the  $2p_z$  orbitals on the N atom and on both of the O atoms. These three atomic orbitals form three molecular orbitals. These are three centre  $\pi$  molecular orbitals. The lowest in energy is bonding, the highest is antibonding, and the middle one is non bonding. Two of the four  $\pi$  electrons fill the bonding MO and two fill the non bonding MO, thus contributing one  $\pi$  bond over the molecule. The bond order of the N—O bonds is thus 1.5, and the N—O distances are in between those for a single and double bond.

#### Carbon dioxide $\text{CO}_2$

The structure of  $\text{CO}_2$  is linear O—C—O, and the C atom uses  $sp$  hybrid orbitals for  $\sigma$  bonds. Both C—O bonds are the same length, but are much shorter than a single bond. This is best explained by delocalized  $\pi$  bonding,

and involves multi-centre  $\pi$  molecular orbitals. The molecule contains 16 outer shell electrons, made up from six electrons from each of the two O atoms and four electrons from the C atom.

The C atom forms  $\sigma$  bonds to both the O atoms, thus accounting for four electrons. There are no lone pairs of electrons on the C atom. If the O atoms also use  $sp$  hybrid orbitals then there is one lone pair of electrons on each O atom, accounting for a further four electrons. This accounts for eight electrons altogether, leaving eight electrons available for  $\pi$  bonding.

If the  $\sigma$  bonding and lone pairs of electrons occupy the  $2s$  and  $2p_x$  atomic orbitals on each O atom, then the  $2p_y$  and  $2p_z$  atomic orbitals can be used for  $\pi$  bonding. Thus there are six atomic orbitals available for  $\pi$  bonding. The three  $2p_y$  atomic orbitals (one from C and one from each of the O atoms) form three three-centre  $\pi$  molecular orbitals which cover all three atoms. The MO with the lowest energy is called a bonding molecular orbital. The MO with the highest energy is called an antibonding MO, and the remaining MO is non-bonding. In a similar way, the three  $2p_z$  atomic orbitals also form bonding, non-bonding and antibonding three-centre  $\pi$  molecular orbitals. Each of these MOs covers all three atoms in the molecule. The eight  $\pi$  electrons occupy the MOs of lowest energy, in this case two electrons in the bonding  $2p_y$  MO, two electrons in the bonding  $2p_z$  MO, then two electrons in the non-bonding  $2p_y$  MO and two electrons in the non-bonding  $2p_z$  MO. This gives a net contribution of two  $\pi$  bonds to the molecule, in addition to the two  $\sigma$  bonds. Thus the bond order C—O is thus two.

#### Azide ion $N_3^-$

The  $N_3^-$  ion has 16 outer electrons (five from each N and one from the charge on the ion). It is isoelectronic with  $CO_2$ , and is linear N—N—N like  $CO_2$ . We assume the central N uses  $sp$  hybrid orbitals for  $\sigma$  bonding.

Four electrons are used for the two  $\sigma$  bonds. Each of the end N atoms has one non-bonding pair of electrons, accounting for four more electrons. This leaves eight electrons for  $\pi$  bonding.

If the bonding and non-bonding electrons are assumed to use the  $2s$  and  $2p_x$  orbitals, this leaves six atomic orbitals for  $\pi$  bonding. These are three  $2p_y$  AOs and three  $2p_z$  AOs. The three  $2p_y$  orbitals form three three-centre  $\pi$  molecular orbitals. The lowest in energy is bonding, the highest is antibonding, and the remaining MO is non-bonding. In a similar way the three  $2p_z$  atomic orbitals give bonding, non-bonding and antibonding MOs. The eight  $\pi$  electrons fill both of the bonding MOs, and both of the non-bonding MOs. Thus there are two  $\sigma$  and two  $\pi$  bonds, giving a bond order of 2. Thus both N—N bonds are the same length, 1.16 Å.

#### SUMMARY OF MULTI-CENTRE $\pi$ BONDED STRUCTURES

Isoelectronic species have the same shape and the same bond order (Table 4.6).

Table 4.6 Multi-centre bonded structures

Species	Number of outer electrons	Shape	Bond order
CO <sub>2</sub>	16	Linear	2
N <sub>3</sub>	16	Linear	2
O <sub>3</sub>	18	V-shaped	1.5
NO <sub>2</sub> <sup>+</sup>	18	V-shaped	1.5
CO <sub>3</sub> <sup>2-</sup>	24	Plane triangle	1.33
NO <sub>3</sub> <sup>-</sup>	24	Plane triangle	1.33

## UNITED ATOM METHOD

The LCAO method described above is tantamount to bringing the atoms from infinity to their equilibrium positions in the molecule. The united atom method is an alternative approach. It starts with a hypothetical 'united atom' where the nuclei are superimposed, and then moved to their equilibrium distance apart. The united atom has the same number of orbitals as a normal atom, but it contains the electrons from two atoms. Thus some electrons must be promoted to higher energy levels in the




Figure 4.33 Mulliken correlation for like atoms forming a diatomic molecule

united atom. Further, the energy of the united atom orbitals differs from that of the atomic orbitals because of the greater nuclear charge. Thus the molecular orbitals are in an intermediate position between the orbitals in the united atom and those in the separate atom. If lines are drawn between the energies of the electrons in the separate atoms and in the united atom (that is a graph of internal energy against the distance between the nuclei from  $r = 0$  to  $r = \infty$ ), a correlation diagram is obtained (Figure 4.33).

## FURTHER READING

- Atkins, P.W. (1983) *Molecular Quantum Mechanics*, Oxford University Press, Oxford.
- Ballhausen, C.J. and Gray, H.B. (1964) *Molecular Orbital Theory*, Benjamin, Menlo Park, California.
- Ballhausen, C.J. and Gray, H.B. (1980) *Molecular Electronic Structures*, Benjamin-Cummings, Menlo Park, California.
- Brown, I.D. (1978) A simple structural model for inorganic chemistry, *Chem. Soc. Rev.*, 7, 359.
- Burdett, J.K. (1980) *Molecular Shapes: Theoretical Models for Inorganic Stereochemistry*, Wiley-Interscience, New York.
- Cartmell, E. and Fowles, G.W.A. (1977) *Valency and Molecular Structure*, 4th ed., Butterworths, London.
- Coulson, C.A. (1982) revised by McWeeny, R., *The Shape and Structure of Molecules*, 2nd ed., Clarendon Press, Oxford.
- Coulson, C.A. (1979) revised by McWeeny, R., *Valence*, 3rd ed., Oxford University Press, Oxford. (An updated version of Coulson's 1969 book.)
- DeKock, R.L. and Bosma, W.B. (1988) The three-center, two-electron chemical bond, *J. of Chem. Ed.*, 65, 194–197.
- DeKock, R.L. and Gray, H.B. (1980) *Chemical Structure and Bonding*, Benjamin/Cummings, Menlo Park, California.
- Douglas, B., McDaniel, D.H. and Alexander J.J. (1983) *Concepts and Models in Inorganic Chemistry*, 2nd ed., Wiley, New York.
- Ebsworth, E.A.V., Rankin, D.W.H. and Cradock, S. (1987) *Structural Methods in Inorganic Chemistry*, Blackwell Scientific, Oxford.
- Ferguson, J.E. (1974) *Stereochemistry and Bonding in Inorganic Chemistry*, Prentice Hall, Englewood Cliffs, N.J.
- Gillespie, R.J. (1972) *Molecular Geometry*, Van Nostrand Reinhold, London. (The latest on the VSEPR theory.)
- Gillespie, R.J. and Nyholm, R.S. (1957) *Q. Rev. Chem. Soc.*, 11, 339. (Develops the Sidgwick–Powell theory into the modern VSEPR theory.)
- Karplus, M. and Porter, R.N. (1970) *Atoms and Molecules*, Benjamin, New York.
- Kettle, S.F.A. (1985) *Symmetry and Structure*, Wiley, London.
- Kutzelnigg, W. (1984) Chemical bonding in higher main group elements, *Angew. Chemie* (International edition in English), 23, 272.
- Murrell, J.N., Kettle, S.F.A. and Tedder, J.M. (1985) *The Chemical Bond*, 2nd ed., Wiley, London.
- O'Dwyer, M.F., Kent, J.E. and Brown, R.D. (1978) *Valency*, 2nd ed., Springer (reprinted 1986).
- Pauling, L. (1961) *The Nature of the Chemical Bond*, 3rd ed., Oxford University Press, Oxford. (A classical text on bonding.)
- Pauling, L. (1967) *The Chemical Bond*, Oxford University Press, Oxford. (A shorter and updated book on bonding.)
- Sidgwick, N.V. and Powell H.M. (1940) *Proc. R. Soc.*, 176A, 153. (The original paper on electron pair repulsion theory.)

- Speakman, J.C. (1977) *Molecular Structure: Its Study by Crystal Diffraction*, Royal Society for Chemistry, Monographs for Teachers 30.  
 Urch, D.S. (1970) *Orbitals and Symmetry*, Penguin.  
 Wade, K. (1971) *Electron Deficient Compounds*, Nelson, London  
 Worrall, J. and Worrall I.J. (1969) *Introduction to Valence Theory*, American Elsevier Publishing Co., New York.

Bond lengths and bond angles of molecular structures in the crystalline and gaseous states are given in The Chemical Society's Special Publication 11 (*Interatomic Distances*) and Special Publication 18 (*Interatomic Distances Supplement*)

### PROBLEMS

1. Show by drawings how an *s* orbital, a *p* orbital or a *d* orbital on one atom may overlap with *s*, *p* or *d* orbitals of an adjacent atom.
2. List three rules for the linear combination of atomic orbitals.
3. Show how the LCAO approximation gives rise to bonding and anti-bonding orbitals. Illustrate your answer by reference to three different diatomic molecules.
4. Use the molecular orbital theory to explain why the bond strength in a  $N_2$  molecule is greater than that in a  $F_2$  molecule.
5. Use the MO theory to predict the bond order and the number of unpaired electrons in  $O_2^{2-}$ ,  $O_2^-$ ,  $O_2$ ,  $O_2^+$ , NO and CO.
6. Draw MO energy level diagrams for  $C_2$ ,  $O_2$  and CO. Show which orbitals are occupied, and work out the bond orders and magnetic properties of these molecules.
7. Name the three types of hybrid orbital that may be formed by an atom with only *s* and *p* orbitals in its valence shell. Draw the shapes and stereochemistry of the hybrid orbitals so produced.
8. What are the geometric arrangements of  $sp^3d^2$ ,  $sp^3d$  and  $dsp^2$  hybrid orbitals?
9. Predict the structure of each of the following, and indicate whether the bond angles are likely to be distorted from the theoretical values: (a)  $BeCl_2$ ; (b)  $BCl_3$ ; (c)  $SiCl_4$ ; (d)  $PCl_5$  (vapour); (e)  $PF_5$ ; (f)  $F_2O$ ; (g)  $SF_4$ ; (h)  $IF_5$ ; (i)  $SO_2$ ; (j)  $SF_6$ .
10. How and why does the cohesive force in metals change on descending a group, or on moving from one group to another? What physical properties follow these changes in cohesive force?
11. Use energy level diagrams and the band theory to explain the difference between conductors, insulators and semiconductors



# The metallic bond

5

## GENERAL PROPERTIES OF METALS

All metals have characteristic physical properties:

1. They are exceptionally good conductors of electricity and heat.
2. They have a characteristic metallic lustre – they are bright, shiny and highly reflective.
3. They are malleable and ductile.
4. Their crystal structures are almost always cubic close-packed, hexagonal close-packed, or body-centred cubic.
5. They form alloys readily.

### Conductivity

All metals are exceptionally good conductors of heat and electricity. Electrical conduction arises by the movement of electrons. This is in contrast to the movement of ions which is responsible for conduction in aqueous solution or fused melts of ionic compounds like sodium chloride, where sodium ions migrate to the cathode, and chloride ions migrate to the anode. In the solid state, ionic compounds may conduct to a very small extent (semiconduction) if defects are present in the crystal. There is an enormous difference in the conductivity between metals and any other type of solid (Table 5.1).

Table 5.1 Electrical conductivity of various solids

Substance	Type of bonding	Conductivity (ohm cm <sup>-1</sup> )
Silver	Metallic	$6.3 \times 10^5$
Copper	Metallic	$6.0 \times 10^5$
Sodium	Metallic	$2.4 \times 10^5$
Zinc	Metallic	$1.7 \times 10^5$
Sodium chloride	Ionic	$10^{-7}$
Diamond	Covalent giant molecule	$10^{-14}$
Quartz	Covalent giant molecule	$10^{-14}$

Most of the elements to the left of carbon in the periodic table are metals. A carbon atom has four outer electrons. If these are all used to form four bonds, the outer shell is complete and there are no electrons free to conduct electricity.

		2s	2p
Carbon atom – excited state	full inner shell	$\uparrow$	$\uparrow \uparrow \uparrow$
Carbon atom having gained a share in four more electrons by forming four bonds	full inner shell	$\uparrow\downarrow$	$\uparrow\downarrow \uparrow\downarrow \uparrow\downarrow$

Elements to the left of carbon have fewer electrons, and so they must have vacant orbitals. Both the number of electrons present in the outer shell, and the presence of vacant orbitals in the valence shell, are important features in explaining the conductivity and bonding of metals.

The conductivity of metals decreases with increasing temperature. Metals show some degree of paramagnetism, which indicates that they possess unpaired electrons.


### Lustre

Smooth surfaces of metals typically have a lustrous shiny appearance. All metals except copper and gold are silvery in colour. (Note that when finely divided most metals appear dull grey or black.) The shininess is rather special, and is observed at all viewing angles, in contrast to the shininess of a few non-metallic elements such as sulphur and iodine which appear shiny when viewed at low angles. Metals are used as mirrors because they reflect light at all angles. This is because of the 'free' electrons in the metal which absorb energy from light and re-emit it when the electron drops back from its excited state to its original energy level. Since light of all wavelengths (colours) is absorbed, and is immediately re-emitted, practically all the light is reflected back – hence the lustre. The reddish and golden colours of copper and gold occur because they absorb some colours more readily than others.

Many metals emit electrons when exposed to light – the photoelectric effect. Some emit electrons when irradiated with short wave radiation and others emit electrons on heating (thermionic emission).

### Malleability and cohesive force

The mechanical properties of metals are that they are typically malleable and ductile. This shows that there is not much resistance to deformation of the structure but that a large cohesive force holds the structure together.



**Table 5.2** Enthalpies of atomization  $\Delta H^\circ$  ( $\text{kJ mol}^{-1}$ ) (Measured at 25°C except for Hg)

Metal	$\Delta H^\circ$	Melting point (°C)	Boiling point (°C)
Li	162	181	1331
Na	108	98	890
K	90	64	766
Rb	82	39	701
Cs	78	29	685
Be	324	1277	2477
Mg	146	650	1120
Ca	178	838	1492
Sr	163	768	1370
Ba	178	714	1638
B	565	2030	3927
Al	326	660	2447
Ga	272	30	2237
Sc	376	1539	2480
Ti	469	1668	3280
V	562	1900	3380
Cr	397	1875	2642
Mn	285	1245	2041
Fe	415	1537	2887
Co	428	1495	2887
Ni	430	1453	2837
Cu	339	1083	2582
Zn	130	420	908

Enthalpies of atomization from Brewer, L., *Science*, 1968, **161**, 115, with some additions.

The cohesive force may be measured as the heat of atomization. Some numerical values of  $\Delta H^\circ$ , the heats of atomization at 25°C, are given in Table 5.2. The heats of atomization (cohesive energy) decrease on descending a group in the periodic table Li–Na–K–Rb–Cs, showing that they are inversely proportional to the internuclear distance.

The cohesion energy increases across the periodic table from Group 1 to Group 2 to Group 13. This suggests that the strength of metallic bonding is related to the number of valency electrons. The cohesive energy increases at first on crossing the transition series Sc–Ti–V as the number of unpaired *d* electrons increases. Continuing across the transition series the number of electrons per atom involved in metallic bonding eventually falls, as the *d* electrons become paired, reaching a minimum at Zn.

The melting points and to an even greater extent the boiling points of the metals follow the trends in the cohesive energies. The cohesive energies vary over an appreciable range, and they approach the magnitude of the lattice energy which holds ionic crystals together. The cohesive

energies are much larger than the weak van der Waals forces which hold discrete covalent molecules together in the solid state

There are two rules about the cohesive energy and structure of metals (or alloys), and these are examined below

*Rule 1 The bonding energy of a metal depends on the average number of unpaired electrons available for bonding on each atom*

*Rule 2 The crystal structure adopted depends on the number of  $s$  and  $p$  orbitals on each atom that are involved with bonding*

Consider the first rule – Group 1 metals have the outer electronic configuration  $ns^1$ , and so have one electron for bonding. In the ground state (lowest energy), Group 2 elements have the electronic configuration  $ns^2$ , but if the atom is excited, an outer electron is promoted, giving the configuration  $ns^1, np^1$  with two unpaired electrons, which can form two bonds. Similarly Group 13 elements in the ground state have the configuration  $ns^2, np^1$ , but when excited to  $ns^1, np^2$ , they can use three electrons for metallic bonding.

The second rule attempts to relate the number of  $s$  and  $p$  electrons available for bonding to the crystal structure adopted (Table 5.3). Apart from Group 1 metals, the atoms need to be excited, and the structures adopted are shown in Table 5.4.

Table 5.3 Prediction of metal structures from the number of  $s$  and  $p$  electrons involved in metallic bonding

Number of $s$ and $p$ electrons per atom involved in bonding	Structure
Less than 1.5	Body centred cubic
1.7–2.1	Hexagonal close packed
2.5–3.2	Cubic close packed
Approaching 4	Diamond structure – not metallic

Group 1 elements have a body centred cubic structure, and follow the rule. In Group 2, only Be and Mg have a hexagonal close-packed structure and strictly follow the rule. In Group 13, Al has a cubic close packed structure as expected. However, not all the predictions are correct. There is no obvious reason why Ca and Sr form cubic close packed structures. However, the high temperature forms of Ca and Sr, and the room temperature form of Ba, form body centred cubic structures (like Group 1), instead of the expected hexagonal close packed structure. The explanation is probably that the paired  $s$  electron is excited to a  $d$  level instead of a  $p$  level, and hence there is only one  $s$  or  $p$  electron per atom participating in metallic bonding. This also explains why the first half of the transition metals also form body centred cubic structures. In the second half of the transition series, the extra electrons may be put in the  $p$  level, to avoid

**Table 5.4** Type of structure adopted by metals in the periodic table (The room temperature structure is shown at the bottom. Other structures which occur at higher temperatures are listed above this in order of temperature stability)

Li bcc		Be hcp																		B C N					
Na bcc		Mg hcp																		Al ccp	Si d	P	S		
K bcc	Ca bcc ccp	Sc bcc hcp	Ti bcc hcp	V bcc	Cr bcc β χ	Mn bcc ccp	Fe bcc ccp bcc	Co ccp hcp	Ni ccp	Cu ccp	Zn hcp											Ga ●	Ge d	As ● α	Se
Rb bcc	Sr bcc hcp ccp	Y bcc hcp	Zr bcc hcp	Nb bcc	Mo bcc	Tc hcp	Ru hcp	Rh ccp	Pd ccp	Ag ccp	Cd hcp											In ●	Sn d	Sb ● α	Te
Cs bcc	Ba bcc	La bcc ccp hcp	Hf bcc hcp	Ta bcc	W bcc	Re hcp	Os hcp	Ir ccp	Pt ccp	Au ccp	Hg											Tl bcc hcp	Pb ccp	Bi ● α	Po

bcc = body-centred cubic

ccp = cubic close-packed

ccp\* = distorted cubic close-packed

hcp = hexagonal close-packed

d = diamond structure

α = rhombohedral – puckered sheets

χ = other structure

● = special case (see individual group)

pairing  $d$  electrons, and so allow the maximum participation of  $d$  orbitals in metallic bonding. This increases the number of  $s$  and  $p$  electrons involved in metallic bonding, and for example in Cu, Ag and Au the excited electronic state involved in bonding is probably  $d^8, s^1, p^2$ , giving a cubic close packed structure and five bonds per atom (two  $d$ , one  $s$  and two  $p$  electrons). At Zn the  $d$  orbitals are full, and the excited state used for bonding is  $3d^{10}, 4s^1, 4p^1$ , giving two bonds per atom and a body centred cubic structure. The enthalpies of atomization are in general agreement with these ideas on bonding.

### Crystal structures of metals

Metallic elements usually have a close-packed structure with a coordination number of 12. There are two types of close packing depending on the arrangement of adjacent layers in the structure: cubic close packing ABCABC and hexagonal close packing ABAB (see Metallic bonds and metallic structures in Chapter 2). However, some metals have a body-centred cubic type of structure (which fills the space slightly less efficiently) where there are eight nearest neighbours, with another six next nearest neighbours about 15% further away. If this small difference in distance between nearest and next-nearest neighbours is disregarded, the coordination number for a body-centred cubic structure may be regarded loosely as 14. The mechanical properties of malleability and ductility depend on the ease with which adjacent planes of atoms can glide over each other, to give an equivalent arrangement of spheres. These properties are also affected by physical imperfections such as grain boundaries and dislocations, by point defects in the crystal lattice and by the presence of traces of impurity in the lattice. The possibility of planes gliding is greatest in cubic close-packed structures, which are highly symmetrical and have possible slip planes of close-packed layers in four directions (along the body diagonals), compared with only one direction in the hexagonal close-packed structure. This explains why cubic close packed structures are generally softer and more easily deformed than hexagonal or body centred cubic structures. Impurities may cause dislocations in the normal metal lattice, and the localized bonding increases the hardness. Some soft metals like Cu become work hardened – it is harder to bend the metal a second time. This is because dislocations are caused by the first bending, and these disrupt the slip planes. Other metals such as Sb and Bi are brittle. This is because they have directional bonds, which pucker layers, preventing one layer from slipping over another.

The type of packing varies with the position of the element in the periodic table (Table 5.4), which is related to the number of  $s$  and  $p$  electrons on each atom that can take part in metallic bonding. This has been described earlier.

Metallic elements commonly react with other metallic elements, often over a wide range of composition, forming a variety of alloys which look like metals, and have the properties of metals.

**Table 5.5** Interatomic distances in  $M_2$  molecules and metal crystals

	Distance in metal ( $\text{\AA}$ )	Distance in $M_2$ molecule ( $\text{\AA}$ )
Li	3.04	2.67
Na	3.72	3.08
K	4.62	3.92
Rb	4.86	4.22
Cs	5.24	4.50

### Bond lengths

If the valence electrons in a metal are spread over a large number of bonds, each bond should be weaker and hence longer. The alkali metals exist as diatomic molecules in the vapour state, and the interatomic distances in the metal crystal are longer than in the diatomic molecule (Table 5.5).

Though the bonds in the metal are longer and weaker, there are many more of them than in the  $M_2$  molecule, so the total bonding energy is greater in the metal crystal. This can be seen by comparing the enthalpy of sublimation of the metal crystal with the enthalpy of dissociation of the  $M_2$  molecules (Table 5.6).

### THEORIES OF BONDING IN METALS

The bonding and structures adopted by metals and alloys are less fully understood than those with ionic and covalent compounds. Any successful theory of metallic bonding must explain both the bonding between a large number of identical atoms in a pure metal, and the bonding between widely different metal atoms in alloys. The theory cannot involve directional bonds, since most metallic properties remain even when the metal is in the liquid state (for example mercury), or when dissolved in a suitable

**Table 5.6** Comparison of enthalpies of sublimation and dissociation

	Enthalpy of sublimation of metal ( $\text{kJ mol}^{-1}$ )	$\frac{1}{2}$ enthalpy of dissociation of $M_2$ molecule ( $\text{kJ mol}^{-1}$ )
Li	161	54
Na	108	38
K	90	26
Rb	82	24
Cs	78	21

solvent (for example solutions of sodium in liquid ammonia) Further, the theory should explain the great mobility of electrons


### Free electron theory

As early as 1900, Drude regarded a metal as a lattice with electrons moving through it in much the same way as molecules of a gas are free to move. The idea was refined by Lorentz in 1923, who suggested that metals comprised a lattice of rigid spheres (positive ions), embedded in a gas of free valency electrons which could move in the interstices. This model explains the free movement of electrons, and cohesion results from electrostatic attraction between the positive ions and the electron cloud. Whilst it does explain in a rough qualitative way why an increased number of valency electrons results in an increased cohesive energy, quantitative calculations are much less successful than similar calculations for the lattice energies of ionic compounds.

### Valence bond theory

Consider a simple metal such as lithium, which has a body-centred cubic structure, with eight nearest neighbours and six next-nearest neighbours at a slightly greater distance. A lithium atom has one electron in its outer shell, which may be shared with one of its neighbours, forming a normal two electron bond. The atom could equally well be bonded to any of its other eight neighbours so many different arrangements are possible, and Figures 5.1a and b are two examples.

A lithium atom may form two bonds if it ionizes, and it can then form many structures similar to those in Figures 5.1c and d. Pauling suggested that the true structure is a mixture of all the many possible bonding forms. The more possible structures there are, the lower the energy. This means that the cohesive force which holds the structure together is large, and in metallic lithium the cohesive energy is three times greater than in a  $\text{Li}_2$  molecule. The cohesive energy increases from Group 1 to 2 to 13, and this is explained by the atoms being able to form an increased number of bonds, and give an even larger number of possible structures. The presence of ions could explain the electrical conduction, but the theory does not explain the conduction of heat in solids, or the lustre, or the retention of metallic properties in the liquid state or in solution.



### Molecular orbital or band theory

The electronic structure of a lithium atom is




Figure 5.1 Representations of some bonding possibilities in lithium




The  $\text{Li}_2$  molecule exists in the vapour state, and bonding occurs using the  $2s$  atomic orbital. There are three empty  $2p$  orbitals in the valence shell, and the presence of empty AOs is a prerequisite for metallic properties. (Carbon in its excited state, nitrogen, oxygen, fluorine, and neon all lack empty AOs in the valence shell and are all non-metals.)

The valence shell has more AOs than electrons, so even if the electrons are all used to form normal two-electron bonds, the atom cannot attain a noble gas structure. Compounds of this type are termed 'electron deficient'.

Empty AOs may be utilized to form additional bonds in two different ways:

1. Empty AOs may accept lone pairs of electrons from other atoms or ligands, forming coordinate bonds.
2. Cluster compounds may be formed, where each atom shares its few electrons with several of its neighbours, and obtains a share in their electrons. Clustering occurs in the boron hydrides and carboranes, and is a major feature of metals.

The molecular orbital description of an  $\text{Li}_2$  molecule has been discussed earlier in Chapter 4, in the examples of MO treatment. There are six electrons arranged in molecular orbitals:



Bonding occurs because the  $\sigma 2s$  bonding MO is full and the corresponding antibonding orbital is empty. Ignoring any inner electrons, the  $2s$  AOs on each of the two Li atoms combine to give two MOs – one bonding and one antibonding. The valency electrons occupy the bonding MO (Figure 5.2a).

Suppose three Li atoms joined to form  $\text{Li}_3$ . Three  $2s$  AOs would combine to form three MOs – one bonding, one non-bonding and one antibonding. The energy of the non-bonding MO is between that for the bonding and antibonding orbitals. The three valency electrons from the three atoms would occupy the bonding MO (two electrons) and the non-bonding MO (one electron) (Figure 5.2b).

In  $\text{Li}_4$ , the four AOs would form four MOs – two bonding, and two antibonding. The presence of two non-bonding MOs between the bonding and antibonding orbitals reduces the energy gap between the orbitals. The four valency electrons would occupy the two lowest energy MOs, which are both bonding orbitals, as shown in Figure 5.2c.

As the number of electrons in the cluster increases, the spacing between the energy levels of the various orbitals decreases further, and when there are a large number of atoms, the energy levels of the orbitals are so close together that they almost form a continuum (Figure 5.2d).

The number of MOs must by definition be equal to the number of constituent AOs. Since there is only one valence electron per atom in lithium, and a MO can hold two electrons, it follows that only half the MOs in the  $2s$  valence band are filled – i.e. the bonding MOs. It requires




Figure 5.2 Development of molecular orbitals into bands in metals

only a minute amount of energy to perturb an electron to an unoccupied MO

The MOs extend in three dimensions over all the atoms in the crystal, so electrons have a high degree of mobility. The mobile electrons account for the high thermal and electrical conduction of metals.

If one end of a piece of metal is heated, electrons at that end gain energy and move to an unoccupied MO where they can travel rapidly to any other part of the metal, which in turn becomes hot. In an analogous manner, electrical conduction takes place through a minor perturbation in energy




Figure 5.3 Two methods by which conduction can occur: (a) metallic molecular orbitals for lithium showing half-filled band; (b) metallic molecular orbitals for beryllium showing overlapping bands.

promoting an electron to an unfilled level, where it can move readily. In the absence of an electric field, equal numbers of electrons will move in all directions. If a positive electrode is placed at one end, and a negative electrode at the other, then electrons will move towards the anode much more readily than in the opposite direction; hence an electric current flows.

Conduction occurs because the MOs extend over the whole crystal, and because there is effectively no energy gap between the filled and unfilled MOs. The absence of an energy gap in lithium is because only half the MOs in the valence band are filled with electrons (Figure 5.3a).

In beryllium there are two valence electrons, so the valence electrons would just fill the 2s valence band of MOs. In an isolated beryllium atom, the 2s and 2p atomic orbitals differ in energy by  $160 \text{ kJ mol}^{-1}$ . In much the same way as the 2s AOs form a band of MOs, the 2p AOs form a 2p band of MOs. The upper part of the 2s band overlaps with the lower part of the 2p band (Figure 5.3b). Because of this overlap of the bands some of the 2p band is occupied and some of the 2s band is empty. It is both possible and easy to perturb electrons to an unoccupied level in the conduction band, where they can move throughout the crystal. Beryllium therefore behaves as a metal. It is only because the bands overlap that there is no energy gap, so perturbation from the filled valence band to the empty conduction band can occur.

## CONDUCTORS, INSULATORS AND SEMICONDUCTORS

In electrical conductors (metals), either the valence band is only partly full, or the valence and conduction bands overlap. There is therefore no

significant gap between filled and unfilled MOs, and perturbation can occur readily

In insulators (non metals), the valence band is full, so perturbation within the band is impossible, and there is an appreciable difference in energy (called the band gap) between the valence band and the next empty band. Electrons cannot therefore be promoted to an empty level where they could move freely

Intrinsic semiconductors are basically insulators, where the energy gap between adjacent bands is sufficiently small for thermal energy to be able to promote a small number of electrons from the full valence band to the empty conduction band. Both the promoted electron in the conduction band and the unpaired electron left in the valence band can conduct electricity. The conductivity of semiconductors increases with temperature because the number of electrons promoted to the conduction band increases as the temperature increases. Both *n*-type and *p*-type semiconductors are produced by doping an insulator with a suitable impurity. The band from the impurity lies in between the valence and conduction bands in the insulator, and acts as a bridge, so that electrons may be excited from the insulator bands to the impurity bands, or vice versa (Figure 5.4) (Defects and semiconductors are discussed at the end of Chapter 3)

## ALLOYS

When two metals are heated together, or a metal is mixed with a non-metallic element then one of the following will occur

- 1 An ionic compound may be formed
- 2 An interstitial alloy may be formed
- 3 A substitutional alloy may be formed
- 4 A simple mixture may result

Which of these occurs depends on the chemical nature of the two elements concerned and on the relative sizes of the metal atoms and added atoms

### Ionic compounds

Consider first the chemical nature of the two elements. If an element of high electronegativity (e.g. F 4.0, Cl 3.0 or O 3.5) is added to a metal of low electronegativity (e.g. Li 1.0, Na 0.9) the product will be ionic not metallic

### Interstitial alloys and related compounds

Next consider the relative sizes of the atoms. The structure of many metals is a close-packed lattice of spherical atoms or ions. There are therefore many tetrahedral and octahedral holes. If the element added has small atoms, they can be accommodated in these holes without altering the




Figure 5.4 Conductors, insulators, impurity and intrinsic semiconductors

structure of the metal. Hydrogen is small enough to occupy tetrahedral holes, but most other elements occupy the larger octahedral holes.

The invading atoms occupy interstitial positions in the metal lattice, instead of replacing the metal atoms. The chemical composition of compounds of this type may vary over a wide range depending on how many holes are occupied. Such alloys are called interstitial solid solutions, and are formed by a wide range of metals with hydrogen, boron, carbon, nitrogen and other elements. The most important factor is the size of the invading atoms. For octahedral holes to be occupied, the radius ratio of




Figure 5.5 Part of the iron-carbon phase diagram (X = eutectic, Y = eutectoid, P = pearlite)

the smaller atom/larger atom should be in the range 0.414–0.732. The invasion of interstitial sites does not significantly alter the metal structure. It still looks like a metal, and still conducts heat and electricity. However, filling some of the holes has a considerable effect on the physical properties, particularly the hardness, malleability and ductility of the metal. This is because filling holes makes it much more difficult for one layer of metal ions to slip over another.

Interstitial bonds, carbides and nitrides are extremely inert chemically, have very high melting points, and are extremely hard. Interstitial carbides of iron are of great importance in the various forms of steel.

The iron-carbon phase diagram is of great importance in the ferrous metal industry, and part of this is shown in Figure 5.5. The most important part is from pure Fe to the compound iron carbide or cementite,  $\text{Fe}_3\text{C}$ . Pure Fe exists as two allotropic forms: one is  $\alpha$ -ferrite or austenite, with a body-centred cubic structure, which is stable up to  $910^\circ\text{C}$ ; above this temperature it changes to  $\gamma$ -ferrite with a face-centred-cubic structure. Above  $1401^\circ\text{C}$   $\gamma$ -ferrite changes back to a body-centred cubic structure, but is now called  $\delta$ -ferrite.

The upper part of the curve is typical of two solids which are only partly miscible, and a eutectic point occurs at X, between  $\gamma$ -ferrite, iron carbide and liquid. A similar triple point occurs at Y, but since it occurs in a completely solid region it is called a eutectoid point. A solid with the

eutectoid composition (a mixture of  $\gamma$ -ferrite and iron carbide) is called pearlite. This is a mixture, not a compound, and is marked P in the diagram. The name pearlite refers to the mother-of-pearl-like appearance when examined under a microscope. The various solid regions  $\alpha$ ,  $\gamma$ ,  $\delta$  are the different allotropic forms of iron and all contain varying amounts of carbon in interstitial positions.

Steel contains up to 2% carbon. The more carbon present, the harder and more brittle the alloy. When steel is heated, the solid forms austenite, which can be hot rolled, bent or pressed into any required shape. On cooling, the phases separate, and the way in which the cooling is carried out affects the grain size and the mechanical properties. The properties of steel can be changed by heat treatment such as annealing and tempering.

Cast iron contains more than 2% carbon. Iron carbide is extremely hard, and brittle. Heating cast iron does not produce a homogeneous solid solution (similar to austenite for steel), so cast iron cannot be worked mechanically, and the liquid must be cast into the required shape.

### Substitutional alloys

If two metals are completely miscible with each other they can form a continuous range of solid solutions. Examples include Cu/Ni, Cu/Au, K/Rb, K/Cs and Rb/Cs. In cases like these, one atom may replace another at random in the lattice.

In the Cu/Au case at temperatures above 450°C a disordered structure exists (Figure 5.7c), but on slow cooling the more ordered superlattice may be formed (Figure 5.7d). Only a few metals form this type of continuous solid solution, and Hume-Rothery has shown that for complete miscibility the following three rules should apply.





Figure 5.6 Cu/Ni – a continuous series of solid solutions. (After W.J. Moore, *Physical Chemistry*.)



**Figure 5.7** Metal and alloy structures (a) pure metal lattice, (b) interstitial alloy (X atoms occupy interstitial positions), (c) random substitutional alloy and (d) superlattice (ordered substitutional alloy)

- 1 The two metals must be similar in size – their metallic radii must not differ by more than 14–15%
- 2 Both metals must have the same crystal structure
- 3 The chemical properties of the metals must be similar – in particular the number of valency electrons should be the same


Consider an alloy of Cu and Au. The metallic radii differ by only 12.5%, both have cubic close packed structures, and both have similar properties since they are in the same vertical group in the periodic table. The two metals are therefore completely miscible. The Group 1 elements are chemically similar, and all have body centred cubic structures. The size differences between adjacent pairs of atoms are Li–Na 22.4%, Na–K 22.0%, K–Rb 9.3% and Rb–Cs 6.9%. Because of the size difference, complete miscibility is found with K/Rb and Rb/Cs alloys, but not with Li/Na and Na/K alloys.

If only one or two of these rules is satisfied then random substitutional solid solutions will only occur over a very limited range at the two extremes of composition.

Consider alloys of tin and lead. The radii differ by only 8.0%, and they are both in Group 14, and so have similar properties. However, their structures are different, so they are only partly miscible. (See Figure 5.8) Solder is an alloy of Sn and Pb with typically about 30% Sn, but it may have 2–63% Sn. The phase diagram is shown in Figure 5.8. There are two small areas of complete miscibility, labelled  $\alpha$  and  $\beta$ , at the extremes of composition at the extreme left and right of the diagram. With plumbers







**Figure 5.8** Phase diagram for Sn/Pb showing partial miscibility and only a limited range of solid solutions (The eutectic occurs at 62% Sn and eutectoid points occur at 19.5% Sn and 97.4% Sn)


solder (30% Sn 70% Pb) the liquid and solid curves are far apart so that there is a temperature interval of nearly 100°C over which the solder is pasty with solid solution suspended in liquid. When in this part solid part liquid state a solder joint can be 'wiped' smooth.

Similar behaviour is found with the Na/K alloy, and the Al/Cu alloy. The metallic radii of Na and K differ by 22.0%, so despite their structural and chemical similarities they only form solid solutions over a limited range of composition.

In other cases where only a limited range of solid solutions are formed the tendency of the different metals to form compounds instead of solutions is important. One or more intermetallic phases may exist each of which behaves as a compound of the constituent metals though the exact stoichiometry may vary over a limited range. For example in the Cu/Zn system the metallic radii differ by only 7.0% but they have different structures (Cu is cubic close packed and Zn is hexagonal close packed) and they have a different number of valence electrons. Only a limited range of solid solutions is expected but the atoms have a strong tendency to form compounds and five different structures may be distinguished as shown in Table 5.8.

Table 5.8 Table of intermetallic phases

Phase	Zn Composition	Structure
$\alpha$	0–35%	Random substitutional solid solution of Zn in Cu
$\beta$	45–50%	Intermetallic compound of approximate stoichiometry CuZn. Structure body-centred cubic
$\gamma$	60–65%	Intermetallic compound of approximate stoichiometry Cu <sub>5</sub> Zn <sub>8</sub> . Structure complex cubic
$\epsilon$	82–88%	Intermetallic compound of approximate stoichiometry CuZn <sub>3</sub> . Structure hexagonal close-packed
$\eta$	97–100%	Random substitutional solid solution of Cu in Zn

Figure 5.9 Phase diagram for Cu/Zn alloy systems. (Copyright Bohm and Klemm, *Z. Anorg. Chem.*, 243, 69, 1939.)

**Table 5.9** Some intermetallic compounds with various ratios of valency electrons to number of atoms

Ideal formula	No. of valency electrons	
	No. of atoms	
CuZn	3/2	β phases
Cu <sub>3</sub> Al	6/4 = 3/2	
Cu <sub>5</sub> Sn	9/6 = 3/2	
AgZn	3/2	
Cu <sub>3</sub> Si	9/6 = 3/2	
Ag <sub>3</sub> Al	6/4 = 3/2	
CoZn <sub>1</sub>	3/2*	γ phases
Cu <sub>5</sub> Zn <sub>8</sub>	21/13	
Cu <sub>9</sub> Al <sub>4</sub>	21/13	
Na <sub>31</sub> Pb <sub>8</sub>	21/13	
Co <sub>5</sub> Zn <sub>21</sub>	21/13*	
CuZn <sub>3</sub>	7/4	ε phases
Cu <sub>3</sub> Si	7/4	
Ag <sub>5</sub> Al <sub>3</sub>	14/8 = 7/4	
Au <sub>5</sub> Al <sub>3</sub>	14/8 = 7/4	

\* Metals of the Fe, Co and Ni groups are assumed to have zero valence electrons for metallic bonding

The relation between the various phases is shown in the phase diagram (Figure 5.9). Each phase can be represented by a typical composition or ideal formula even though it exists over a range of composition. Hume-Rothery studied the compositions of the phases formed and found that the β phase always occurs in alloys when the ratio of the sum of the valency electrons to the number of atoms is 3/2. In a similar way the γ phase always occurs when the ratio is 21/13 and the η phase always occurs when the ratio is 7/4 irrespective of the particular metals involved (Table 5.9).

The explanation of why similar binary metallic phases are formed at similar electron to atom ratios is not fully understood but seems to lie in filling the electronic bands in such a way as to give the minimum energy.

## SUPERCONDUCTIVITY

Metals are good conductors of electricity and their conductivity increases as the temperature is lowered. In 1911 the Dutch scientist Heike Kamerlingh Onnes discovered that metals such as Hg and Pb became superconductors at temperatures near absolute zero. A superconductor has zero or almost zero electrical resistance. It can therefore carry an electric current without losing energy and in principle the current can flow for ever. There is a critical temperature  $T_c$  at which the resistance drops sharply and superconduction occurs. Later Meissner and Ochsenfeld found that some superconducting materials will not permit a magnetic field to penetrate.

their bulk. This is now called the Meissner effect, and gives rise to 'levitation'. Levitation occurs when objects float on air. This can be achieved by the mutual repulsion between a permanent magnet and a superconductor. A superconductor also expels all internal magnetic fields (arising from unpaired electrons), so superconductors are diamagnetic. In many cases the change in magnetic properties is easier to detect than the increased electrical conductivity, since the passage of high currents or strong magnetic fields may destroy the superconductive state. Thus there is also a critical current and critical magnetization which are linked to  $T_c$ .

A superconducting alloy of niobium and titanium, which has a  $T_c$  of about 4 K and requires liquid helium to cool it, has been known since the 1950s. Considerable effort has been put into finding alloys which are superconductors at higher temperatures. Alloys of  $Nb_3Sn$ ,  $Nb_3Ge$ ,  $Nb_3Al$  and  $V_3Si$  all show superconductivity and have  $T_c$  values of about 20 K. It is interesting that these alloys all have the same  $\beta$ -tungsten structure. The  $Nb_3Sn$  and  $Nb_3Ge$  alloys have  $T_c$  values of 22 K and 24 K respectively. These alloys are used to make the wire for extremely powerful electromagnets. These magnets have a variety of uses:

1. In linear accelerators used as atom smashers for high energy particle physics research
2. In nuclear fusion research to make powerful magnetic fields which act as a magnetic bottle for a plasma
3. For military purposes
4. For nuclear magnetic resonance machines in chemical laboratories and for imaging (which is used in diagnostic medicine).

An extremely high current can be passed through a very fine wire made of a superconductor. Thus small coils with a large number of turns can be used to make extremely powerful high field electromagnets. Because the superconductor has effectively zero resistance, the wire does not get hot. Since there is no current loss, once the current is flowing in the coil it continues indefinitely. For example, in large superconducting magnets used in plasma research, the current used by a Nb/Ta superconducting alloy at 4 K was only 0.3% of the current used in an electromagnet of similar power using copper wire for the metal turns. A major obstacle to the widespread use of these *low temperature superconductors* has been the very low value of the transition temperature  $T_c$ . The only way of attaining these low temperatures was to use liquid helium, which is very expensive.

The first non-metallic superconductor was found in 1964. This was a metal oxide with a perovskite crystal structure and is a different type of superconductor from the alloys. It was of no practical use since the  $T_c$  is only 0.01 K.

The perovskite structure is formed by compounds of formula  $ABO_3$ , where the oxidation states of A and B add up to 6. Examples include  $BaTiO_3$ ,  $CaTiO_3$  and  $NaNbVO_3$ . The perovskite crystal structure is cubic. A  $Ca^{2+}$  ion is located at the body-centred position (at the centre of the cube), the smaller  $Ti^{4+}$  ions are located at each corner, and the  $O^{2-}$  are




Figure 5.10 Perovskite.





Figure 5.11 The 1-2-3 structure of  $\text{YBa}_2\text{Cu}_3\text{O}_{7-x}$

located half way along each of the edges of the cube. Thus the  $\text{Ca}^{2+}$  has a coordination number of 12 since it is surrounded by 12 O atoms, and the  $\text{Ti}^{4+}$  are surrounded octahedrally by 6 O atoms. This structure is illustrated in Figure 5.10.

Superconductivity has also been observed in certain organic materials with flat molecules stacked on top of each other, and in certain sulphides called Chevrel compounds.

In 1986 Georg Bednorz and Alex Muller (who were working for IBM in Zurich, Switzerland) reported a new type of superconductor with a  $T_c$  value of 35 K. This temperature was appreciably higher than that for the alloys. This compound is a mixed oxide in the Ba-La-Cu-O system. Though originally given a different formula, it has now been reformulated as  $\text{La}_{(2-x)}\text{Ba}_x\text{CuO}_{(4-y)}$  where  $x$  is between 0.15 and 0.20 and  $y$  is small. This compound has a perovskite structure based on  $\text{La}_2\text{CuO}_4$ . Though  $\text{La}_2\text{CuO}_4$  itself is non-conducting, superconductors can be made by replacing 7.5–10% of the  $\text{La}^{3+}$  ions by  $\text{Ba}^{2+}$ . There is a small deficiency of  $\text{O}^{2-}$ . It seems reasonable that the oxygen loss from the lattice is balanced by the reduction of an easily reducible metal cation, in this case  $\text{Cu}^{3+}$ .



The publication of this paper stimulated enormous interest in 'ceramic' superconductors and a flood of papers was published in 1987. Different laboratories prepared similar compounds, replacing  $\text{Ba}^{2+}$  with  $\text{Ca}^{2+}$  or  $\text{Sr}^{2+}$ , substituting different lanthanides, and varying the preparative conditions to control the amount of oxygen. In the main syntheses stoichiometric quantities of the appropriate metal oxides or carbonates are heated in air, cooled, ground, heated in dioxygen and annealed. Compounds were made with  $T_c$  values of about 50 K. Bednorz and Muller were awarded the Nobel Prize for Physics in 1987.

Another very significant superconducting system based on the Y-Ba-Cu-O system was reported in March 1987 by Wu, Chu and coworkers. This was important because it was the first report of a superconductor which worked at 93 K. This temperature was significant for practical reasons. It allows liquid nitrogen (boiling point 77 K) to be used as coolant rather than the more expensive liquid helium. The compound is formulated as  $\text{YBa}_2\text{Cu}_3\text{O}_{7-x}$ . This is called the 1-2-3 system because of the ratio of the metals present. Like the previous  $\text{La}_2\text{CuO}_4$  system, the 1-2-3 structure contains Cu and is based on a perovskite structure. This comprises three cubic perovskite units stacked one on top of the other, giving an elongated (tetragonal) unit cell.

The upper and lower cubes have a  $\text{Ba}^{2+}$  ion at the body-centred position and the smaller  $\text{Cu}^{2+}$  ions at each corner. The middle cube is similar but has a  $\text{Y}^{3+}$  ion at the body centre. A perovskite structure has the formula  $\text{ABO}_3$ , and the stoichiometry of this compound would be  $\text{YBa}_2\text{Cu}_3\text{O}_9$ . Since the formula actually found is  $\text{YBa}_2\text{Cu}_3\text{O}_{7-x}$ , there is a massive oxygen deficiency, and about one quarter of the oxygen sites in the crystal are vacant. In a perovskite cube,  $\text{O}^{2-}$  are located half-way along each of the 12 edges of the cube. Neutron diffraction shows that the O vacancies are ordered. All the O which should be present at the same height up the z axis as the Y atom are absent: half of the O atoms around Cu and between the Ba planes are also missing.

Several lanthanides, including Sm, Eu, Nd, Dy and Yb, have been substituted for Y in 1-2-3 structures. Values of  $T_c$  up to 93 K are well established. These are called *warm superconductors*.

In 1988 new systems were reported using Bi or Tl instead of the lanthanides. For example, in the system  $\text{Bi}_2\text{Sr}_2\text{Ca}_{(n-1)}\text{Cu}_n\text{O}_{(2n+4)}$  compounds are known where  $n$  is 1, 2, 3 and 4. These all have a perovskite structure and have  $T_c$  values of 12 K, 80 K, 110 K and 90 K respectively. A similar range of compounds  $\text{Tl}_2\text{Ba}_2\text{Ca}_{(n-1)}\text{Cu}_n\text{O}_{(2n+4)}$  are known with  $T_c$  values of 90 K, 110 K, 122 K and 119 K respectively. There are claims that the compound  $\text{Bi}_{1.7}\text{Pb}_{0.2}\text{Sb}_{0.1}\text{Sr}_2\text{Ca}_2\text{Cu}_{2.8}\text{O}_y$  has a  $T_c$  value of 164 K.

$\text{BaBiO}_3$  has a perovskite structure, but is not a superconductor. However, replacing some of the Ba sites with K, or replacing some of the Bi sites with Pb, gives other superconducting phases such as  $\text{K}_x\text{Ba}_{(1-x)}\text{BiO}_3$  and  $\text{BaPb}_{(1-x)}\text{Bi}_x\text{O}_3$ . These compounds have relatively low  $T_c$  values, but are of theoretical interest because they do not contain Cu or a lanthanide element.

The race to discover superconductors which work at higher temperatures continues. The prospect of making superconductors which work at room temperature will continue to attract attention, since its technical applications have great financial benefits. What are these potential uses?

1. The possibility of power transmission using a superconductor is highly attractive. There are obvious difficulties about making long cables from a ceramic material. However, low loss transmission of DC through resistanceless cables from electricity generating power stations rather than AC through normal wire is economically attractive.
2. Use in computers. One of the biggest difficulties in further miniaturization of computer chips is how to get rid of unwanted heat. If superconductors were used, the heat problems would be dramatically reduced. The greater speed of chips is hindered by the time it takes to charge a capacitor, due to the resistance of the interconnecting metal film. Superconductors could lead to faster chips.
3. Powerful electromagnets using superconducting windings are already used. It would be much easier to do this at higher temperatures.
4. Levitation – much pioneering work was done by Eric Laithwaite at

Imperial College on linear motors, and a prototype of a train which floats on a magnetic field has been built in Japan.

Superconductivity of metals and alloys is thought to involve two electrons at a time (Bardeen *et al*, 1957, Ogg, 1946). There is no one accepted explanation of how high temperature superconduction occurs in these mixed oxide (ceramic) systems. However, it seems appropriate to draw together the apparent facts at this time.

- 1 Many, but not all, warm superconductors contain Cu. Two features of Cu chemistry are that it exists in three oxidation states, (+I), (+II) and (+III), and that Cu(II) forms many tetragonally distorted octahedral complexes. Both of these factors may be important. In the  $\text{La}_2\text{CuO}_4$  compounds some  $\text{Ba}^{2+}$  ions are substituted for  $\text{La}^{3+}$ . To balance the charges some Cu(II) atoms change into Cu(III). Superconductivity in this system is thought to involve the transfer of electrons from Cu(II) to Cu(III), but if the process involves two electrons as in the metal superconductors it could involve electron transfer from Cu(I) to Cu(III).
- 2 It is also significant that these superconductors are all related to the perovskite structure.
- 3 Another common feature is that the oxygen deficiency seems to be critical. There is strong evidence from neutron diffraction that the vacancies left by missing O are ordered. It seems reasonable to suppose that, since Cu is normally octahedrally surrounded by six O atoms, when an O vacancy occurs (that is when an O is omitted), then two Cu atoms may interact directly with each other. Interactions such as  $\text{Cu}^{\text{II}}-\text{Cu}^{\text{III}}$  or  $\text{Cu}^{\text{I}}-\text{Cu}^{\text{III}}$  could occur by transferring an electron between the two Cu atoms. Similarly superconductivity in the  $\text{YBa}_2\text{Cu}_3\text{O}_{7-x}$  is thought to be associated with the ready transfer of electrons between Cu(I), Cu(II) and Cu(III).

## FURTHER READING

- Adams, D M (1974) *Inorganic Solids*, Wiley, New York
- Addison, C C (1974) The chemistry of liquid metals, *Chemistry in Britain*, 10, 331
- Brewer, L (1968) *Science*, 161, 115 (Enthalpies of atomisation)
- Burdett, J K (1982) New ways to look at solids, *Acc Chem Res*, 15, 34
- Chemistry in Britain*, May 1969 – The whole issue is devoted to metals and alloys
- Cox, P A (1987) *The Electronic Structure and Chemistry of Solids*, Oxford University Press, Oxford
- Duffy, J A (1983) Band theory of conductors, semiconductors and insulators, *Education in Chemistry*, 20, 14–18
- Galwey, A K (1967) *Chemistry of Solids*, Chapman Hall, London
- Ho, S M and Douglas, B E (1972) Structures of the elements and the PTOT system, *J Chem Ed*, 49, 74
- Hume-Rothery, W (1964) Review of bonding in metals, *Metallurgist*, 3, 11
- Hume-Rothery, W (1964) A note on the intermetallic chemistry of the later transition elements, *J Less Common Metals*, 7, 152
- Hume-Rothery, W J and Raynor, G V (1962) *The Structure of Metals and Alloys*, 4th ed, Institute of Metals, London



- Hume-Rothery, W.J., Christian, J.W. and Pearson, W.B. (1952) *Metallurgical Equilibrium Diagrams*, Institute of Physics, London.
- Jolly, W.L. (1976) *The Principles of Inorganic Chemistry*, (Chapter 11: Metals; Chapter 12: Semiconductors), McGraw Hill, New York.
- Metal Structures Conference (Brisbane 1983), (ISBN 0-85825-183-3), Gower Publishing Company.
- Parish, R.V. (1976) *The Metallic Elements*, Longmans, London.
- Parish, R.V. (1976) *The Metallic Elements*, Longmans, London.

### Superconductivity

- Bardeen, J., Cooper, L.N. and Schreiffer, J.R. (1957) *Phys. Rev.*, **106**, 162. (Development of the BCS theory of superconductivity in metals arising from the movement of electron pairs.)
- Bednorz, J.G. and Müller, A. (1986) Possible high  $T_c$  superconductivity in the Ba-La-Cu-O system, *Z. Phys., B.*, **64**, 189. (The paper which started interest in metal oxide superconductors.)
- Edwards, P.P., Harrison, M.R. and Jones, R. (1987) Superconductivity returns to chemistry, *Chemistry in Britain*, **23**, 962-966.
- Ellis, A.B. (1987) Superconductors, *J. Chem. Ed.*, **64**, 836-841.
- Khurana, A. (1989) *Physics Today*, April, 17-19.
- Murray Gibson, J. (1987) Superconducting ceramics, *Nature*, **329**, 763.
- Ogg, R.A. (1946) *Phys. Rev.*, **69**, 243. (First suggestion that superconduction in alloys is by electron pairs.)
- Sharp, J.H. (1990) A review of the crystal chemistry of mixed oxide superconductors, *Br. Ceram. Trans. J.*, **89**, 1-7. (An understandable review of warm superconductors which attempts to relate properties and structure - the best so far.)
- Tilley, D.R. and Tilley, J. (1986) *Superfluidity and Superconductivity*, 2nd ed., Hilger, Bristol.
- Wu, M.K. et al., (1987) Superconductivity at 93 K in a new mixed phase Y-Ba-Cu-O compound system at ambient pressure, *Phys. Rev. Lett.*, **58**, 908-910.

### PROBLEMS

1. List the physical and chemical properties associated with metals.
2. Name and draw the three common crystal structures adopted by metals.
3. Aluminium has a face-centred cubic structure: The unit cell length is 4.05 Å. Calculate the radius of Al in the metal. (Answer: 1.43 Å.)
4. Explain why the electrical conductivity of a metal decreases as the temperature is raised, but the opposite occurs with semiconductors.
5. Describe the structures of interstitial and substitutional alloys and outline the factors determining which is formed.
6. What is superconductivity? What uses and potential uses are there for superconductors? What types of materials are superconductors?

## General properties of the elements

### SIZE OF ATOMS AND IONS

#### Size of atoms

The size of atoms decreases from left to right across a period in the periodic table. For example, on moving from lithium to beryllium, one extra positive charge is added to the nucleus, and an extra orbital electron is also added. Increasing the nuclear charge results in all of the orbital electrons being pulled closer to the nucleus. In a given period, the alkali metal is the largest atom and the halogen the smallest. When a horizontal period contains ten transition elements, the contraction in size is larger, and when in addition there are 14 inner transition elements in a horizontal period, the contraction in size is even more marked.

On descending a group in the periodic table, such as that containing lithium, sodium, potassium, rubidium and caesium, the sizes of the atoms increase due to the effect of extra shells of electrons being added; this outweighs the effect of increased nuclear charge.

#### Size of ions

Metals usually form positive ions. These are formed by removing one or more electrons from the metal atom. Metal ions are smaller than the atoms from which they were formed for two reasons:

1. The whole of the outer shell of electrons is usually ionized, i.e. removed. This is one reason why cations are much smaller than the original metal atom.
2. A second factor is the effective nuclear charge. In an atom, the number of positive charges on the nucleus is exactly the same as the number of orbital electrons. When a positive ion is formed, the number of positive charges on the nucleus exceeds the number of orbital electrons, and the effective nuclear charge (which is the ratio of the number of charges on the nucleus to the number of electrons) is increased. This results in the remaining electrons being more strongly attracted by the nucleus. Thus the electrons are pulled in – further reducing the size.

Table 6.1 Covalent radii of the elements

Group Period		1	2	Group												13	14	15	16	17	18
1		H • ~0.30														H He • • ~0.30 1.20*					
2		Li Be • • 1.23 0.89														B C N O F Ne • • • • • 0.80 0.77 0.74 0.74 0.72 1.60*					
3		Na Mg • • 1.57 1.36														Al Si P S Cl Ar • • • • • 1.25 1.17 1.10 1.04 0.99 1.91*					
4		K Ca • • 2.03 1.74		3	4	5	6	7	8	9	10	11	12	Ga Ge As Se Br Kr • • • • • 1.25 1.22 1.21 1.14 1.14 2.00*							
5		Rb Sr • • 2.16 1.91		Sc Ti V Cr Mn Fe Co Ni Cu Zn • • • • • 1.44 1.32 1.22 1.17 1.17 1.16 1.15 1.17 1.25													In Sn Sb Te I Xe • • • • • 1.50 1.40 1.41 1.37 1.33 2.20*				
6		Cs Ba • • 2.35 1.98		Y Zr Nb Mo Tc Ru Rh Pd Ag Cd • • • • • 1.62 1.45 1.34 1.29 - 1.24 1.25 1.28 1.34 1.41													Tl Pb Bi Po At Rn • • • • • 1.55 1.46 1.52				
7		Fr Ra	Ac																		
Lanthanides				Ce	Pr	Nd	Pm	Sm	Eu	Gd	Tb	Dy	Ho	Er	Tm	Yb	Lu				
				•	•	•	-	•	•	•	•	•	•	•	•	•	•				
				1.65	1.64	1.64	-	1.66	1.85	1.61	1.59	1.59	1.58	1.57	1.56	1.56	1.70	1.56			

## COVALENT RADII OF THE ELEMENTS

(Numerical values are given in Ångstrom units. \*The values for the noble gases are atomic radii, i.e. non-bonded radii, and should be compared with van der Waals radii rather than with covalent bonded radii. Large circles indicate large radii and small circles small radii.)

After Moeller, T., *Inorganic Chemistry*, Wiley 1952

A positive ion is always smaller than the corresponding atom and the more electrons which are removed (that is, the greater the charge on the ion), the smaller the ion becomes

Metallic radius Na	1.86 Å	Atomic radius Fe	1.17 Å
Ionic radius Na <sup>+</sup>	1.02 Å	Ionic radius Fe <sup>2+</sup>	0.780 Å (high spin)
		Ionic radius Fe <sup>3+</sup>	0.645 Å (high spin)

When a negative ion is formed, one or more electrons are added to an atom, the effective nuclear charge is reduced and hence the electron cloud expands. Negative ions are bigger than the corresponding atom

Covalent radius Cl	0.99 Å
Ionic radius Cl <sup>-</sup>	1.84 Å

### Problems with ionic radii

There are several problems in obtaining an accurate set of ionic radii

- 1 Though it is possible to measure the internuclear distances in a crystal very accurately by X-ray diffraction, for example the distance between Na<sup>+</sup> and F<sup>-</sup> in NaF, there is no universally accepted formula for apportioning this to the two ions. Historically several different sets of ionic radii have been estimated. The main ones are by Goldschmidt, Pauling and Ahrens. These are all calculated from observed internuclear distances, but differ in the method used to split the distance between the ions. The most recent values, which are probably the most accurate, are by Shannon (1976).
- 2 Corrections to these radii are necessary if the charge on the ion is changed.
- 3 Corrections must also be made for the coordination number, and the geometry.
- 4 The assumption that ions are spherical is probably true for ions from the *s*- and *p* blocks with a noble gas configuration, but is probably untrue for transition metal ions with an incomplete *d* shell.
- 5 In some cases there is extensive delocalization of *d* electrons, for example in TiO where they give rise to metallic conduction, or in cluster compounds. This also changes the radii.

Thus ionic radii are not absolute constants, and are best seen as a working approximation.

### Trends in ionic radii

Irrespective of which set of ionic radii are used, the following trends are observed

- 1 In the main groups, radii increase on descending the group, e.g. Li<sup>+</sup> = 0.76 Å, Na<sup>+</sup> = 1.02 Å, K<sup>+</sup> = 1.38 Å, because extra shells of electrons are added.

2. The ionic radii decrease moving from left to right across any period in the periodic table, e.g.  $\text{Na}^+ = 1.02 \text{ \AA}$ ,  $\text{Mg}^{2+} = 0.720 \text{ \AA}$  and  $\text{Al}^{3+} = 0.535 \text{ \AA}$ . This is partly due to the increased number of charges on the nucleus, and also to the increasing charge on the ions.
3. The ionic radius decreases as more electrons are ionized off, that is as the valency increases, e.g.  $\text{Cr}^{2+} = 0.80 \text{ \AA}$  (high spin),  $\text{Cr}^{3+} = 0.615 \text{ \AA}$ ,  $\text{Cr}^{4+} = 0.55 \text{ \AA}$ ,  $\text{Cr}^{5+} = 0.49 \text{ \AA}$  and  $\text{Cr}^{6+} = 0.44 \text{ \AA}$ .
4. The  $d$  and  $f$  orbitals do not shield the nuclear charge very effectively. Thus there is a significant reduction in the size of ions just after  $10d$  or  $14f$  electrons have been filled in. The latter is called the lanthanide contraction, and results in the sizes of the second and third row transition elements being almost the same. This is discussed in Chapter 30.

## IONIZATION ENERGIES

If a small amount of energy is supplied to an atom, then an electron may be promoted to a higher energy level, but if the amount of energy supplied is sufficiently large the electron may be completely removed. The energy required to remove the most loosely bound electron from an isolated gaseous atom is called the ionization energy.

Ionization energies are determined from spectra and are measured in  $\text{kJ mol}^{-1}$ . It is possible to remove more than one electron from most atoms. The first ionization energy is the energy required to remove the first electron and convert  $M$  to  $M^+$ ; the second ionization energy is the energy required to remove the second electron and convert  $M^+$  to  $M^{2+}$ ; the third ionization energy converts  $M^{2+}$  to  $M^{3+}$ , and so on.

The factors that influence the ionization energy are:

1. The size of the atom.
2. The charge on the nucleus.
3. How effectively the inner electron shells screen the nuclear charge.
4. The type of electron involved ( $s$ ,  $p$ ,  $d$  or  $f$ ).

These factors are usually interrelated. In a small atom the electrons are tightly held, whilst in a larger atom the electrons are less strongly held. Thus the ionization energy decreases as the size of the atoms increases.

Table 6.2 Ionization energies for Group 1 and 2 elements ( $\text{kJ mol}^{-1}$ )

	1st	2nd		1st	2nd	3rd
Li	520	7296	Be	899	1757	14 847
Na	496	4563	Mg	737	1450	7 731
K	419	3069	Ca	590	1145	4 910
Rb	403	2650	Sr	549	1064	4 207
Cs	376	2420	Ba	503	965	
Fr			Ra	509	979	3 281*

\* Estimated value.

This trend is shown for example by Group 1 and Group 2 elements (see Table 6.2) and also by the other main groups.

Comparison of the first and second ionization energies for the Group 1 elements shows that removal of a second electron involves a great deal more energy, between 7 and 14 times more than the first ionization energy. Because the second ionization energy is so high, a second electron is not removed. The large difference between the first and second ionization energies is related to the structure of the Group 1 atoms. These atoms have just one electron in their outer shell. Whilst it is relatively easy to remove the single outer electron, it requires much more energy to remove a second electron, since this involves breaking into a filled shell of electrons.

The ionization energies for the Group 2 elements show that the first ionization energy is almost double the value for the corresponding Group 1 element. This is because the increased nuclear charge results in a smaller size for the Group 2 element. Once the first electron has been removed, the ratio of charges on the nucleus to the number of orbital electrons (the effective nuclear charge) is increased, and this reduces the size. For example,  $\text{Mg}^+$  is smaller than the Mg atom. Thus the remaining electrons in  $\text{Mg}^+$  are even more tightly held, and consequently the second ionization energy is greater than the first. Removal of a third electron from a Group 2 element is very much harder for two reasons:

- 1 The effective nuclear charge has increased, and hence the remaining electrons are more tightly held.
- 2 Removing another electron would involve breaking a completed shell of electrons.

The ionization energy also depends on the type of electron which is removed. *s*, *p*, *d* and *f* electrons have orbitals with different shapes. An *s* electron penetrates nearer to the nucleus, and is therefore more tightly held than a *p* electron. For similar reasons a *p* electron is more tightly held than a *d* electron, and a *d* electron is more tightly held than an *f* electron. Other factors being equal, the ionization energies are in the order  $s > p > d > f$ . Thus the increase in ionization energy is not quite smooth on moving from left to right in the periodic table. For example, the first ionization energy for a Group 13 element (where a *p* electron is being removed) is actually less than that for the adjacent Group 2 element (where an *s* electron is being removed).

In general, the ionization energy decreases on descending a group and increases on crossing a period. Removal of successive electrons becomes

Table 6.3 Comparison of some first ionization energies ( $\text{kJ mol}^{-1}$ )

Li 520	Be 899	B 801	C 1086	N 1403	O 1410	F 1681	Ne 2080
Na 496	Mg 737	Al 577	Si 786	P 1012	S 999	Cl 1255	Ar 1521

Table 6.4 First ionization energies of the elements

Group Period			1	2	Group										13	14	15	16	17	18	
1			H ● 1311															He ● 2372			
2			Li ● 520	Be ● 899										B ● 801	C ● 1086	N ● 1403	O ● 1410	F ● 1681	Ne ● 2080		
3			Na ● 496	Mg ● 737										Al ● 577	Si ● 786	P ● 1012	S ● 999	Cl ● 1255	Ar ● 1521		
4			K ● 419	Ca ● 590	Sc ● 631	Ti ● 656	V ● 650	Cr ● 652	Mn ● 717	Fe ● 762	Co ● 758	Ni ● 736	Cu ● 745	Zn ● 906	Ga ● 579	Ge ● 760	As ● 947	Se ● 941	Br ● 1142	Kr ● 1351	
5			Rb ● 403	Sr ● 549	Y ● 616	Zr ● 674	Nb ● 664	Mo ● 685	Tc ● 703	Ru ● 711	Rh ● 720	Pd ● 804	Ag ● 731	Cd ● 876	In ● 558	Sn ● 708	Sb ● 834	Te ● 869	I ● 1191	Xe ● 1170	
6			Cs ● 376	Ba ● 503	La ● 541	Hf ● 760	Ta ● 760	W ● 770	Re ● 759	Os ● 840	Ir ● 900	Pt ● 870	Au ● 889	Hg ● 1007	Tl ● 589	Pb ● 715	Bi ● 703	Po ● 813	At ● 912	Rn ● 1037	
7			Fr	Ra	Ac																

## FIRST IONIZATION ENERGIES OF THE ELEMENTS

(Numerical values are given in  $\text{kJ mol}^{-1}$ .)

(Large circles indicate high values and small circles low values.)

After Sanderson, R.T., *Chemical Periodicity*, Reinhold, New York.




Figure 6.1 First ionization energies of the elements

more difficult and first ionization energy < second ionization energy < third ionization energy. There are a number of deviations from these generalizations.

The variation in the first ionization energies of the elements are shown in Figure 6.1. The graph shows three features:

- 1 The noble gases He, Ne, Ar, Kr, Xe and Rn have the highest ionization energies in their respective periods.
- 2 The Group 1 metals Li, Na, K and Rb have the lowest ionization energies in their respective periods.
- 3 There is a general upward trend in ionization energy within a horizontal period, for example from Li to Ne or from Na to Ar.


The values for Ne and Ar are the highest in their periods because a great deal of energy is required to remove an electron from a stable filled shell of electrons.

The graph does not increase smoothly. The values for Be and Mg are high, and this is attributed to the stability of a filled *s* level. The values for N and P are also high, and this indicates that a half-filled *p* level is also particularly stable. The values for B and Al are lower because removal of



one electron leaves a stable filled  $s$  shell, and similarly with O and S a stable half-filled  $p$  shell is left.

*Electronic arrangements with extra stability*



In general the first ionization energy decreases in a regular way on descending the main groups. A departure from this trend occurs in Group 13, where the expected decrease occurs between B and Al, but the values for the remaining elements Ga, In and Tl do not continue the trend, and are irregular. The reason for the change at Ga is that it is preceded by ten elements of the first transition series (where the  $3d$  shell is being filled). This makes Ga smaller than it would otherwise be. A similar effect is observed with the second and third transition series, and the presence of the three transition series not only has a marked effect on the values for Ga, In and Tl, but the effect still shows in Groups 14 and 15.

**Table 6.5** Ionization energies for Group 13 elements ( $\text{kJ mol}^{-1}$ )

	1st	2nd	3rd
B	801	2427	3659
Al	577	1816	2744
Ga	579	1979	2962
In	558	1820	2704
Tl	589	1971	2877

The ionization energies of the transition elements are slightly irregular, but the third row elements starting at Hf have lower values than would be expected due to the interpolation of the 14 lanthanide elements between La and Hf.

## ELECTRON AFFINITY

The energy released when an extra electron is added to a neutral gaseous atom is termed the electron affinity. Usually only one electron is added, forming a uninegative ion. Since energy is evolved these terms have a negative sign. Electron affinities depend on the size and effective nuclear

Table 6 7 Comparison of theoretical and experimental lattice energies

	Theoretical lattice energy (kJ mol <sup>-1</sup> )	Born-Haber lattice energy (kJ mol <sup>-1</sup> )	% difference
LiCl	-825	-817	0.8
NaCl	-764	-764	0.0
KCl	-686	-679	1.0
KI	-617	-606	1.8
CaF <sub>2</sub>	-2584	-2611	1.0
CdI <sub>2</sub>	-1966	-2410	22.6

The 'noble behaviour' of many transition metals, that is their resistance to chemical attack, is related to a similar series of energy changes. Noble character is favoured by a high heat of sublimation, high ionization energy and low enthalpy of solvation of the ions.

Lattice energies may also provide some information about the ionic/covalent nature of the bonding. If the lattice energy is calculated theoretically assuming ionic bonding then the value can be compared with the experimental value for the lattice energy obtained from the experimentally measured quantities in the Born-Haber cycle. Close agreement indicates that the assumption that bonding is ionic is in fact true, whilst poor agreement may indicate that the bonding is not ionic. A number of lattice energies are compared in Table 6 7. The agreement is good for all the compounds listed except for CdI<sub>2</sub>, confirming that these are ionic. The large discrepancy for CdI<sub>2</sub> indicates that the structure is not ionic, and in fact it forms a layer structure which is appreciably covalent.

### POLARIZING POWER AND POLARIZABILITY – FAJANS' RULES

Consider making a bond theoretically by bringing two ions A<sup>+</sup> and B<sup>-</sup> together to their equilibrium distance. Will the bond remain ionic, or will it become covalent? Ionic and covalent bonding are two extreme types of bonding, and almost always the bonds formed are intermediate in type and this is explained in terms of polarizing (that is deforming) the shape of the ions.

The type of bond between A<sup>+</sup> and B<sup>-</sup> depends on the effect one ion has on the other. The positive ion attracts the electrons on the negative ion and at the same time it repels the nucleus, thus distorting or polarizing the negative ion. The negative ion will also polarize the positive ion, but since anions are usually large, and cations small, the effect of a large ion on a small one will be much less pronounced. If the degree of polarization is quite small, then the bond remains largely ionic. If the degree of polarization is large, electrons are drawn from the negative ion towards the positive ion, resulting in a high concentration of electrons between the two nuclei and a large degree of covalent character results.

The extent to which ion distortion occurs depends on the power of an ion to distort the other ion (that is on its polarizing power) and also on how susceptible the ion is to distortion (that is on its polarizability). Generally the polarizing power increases as ions become smaller and more highly charged. The polarizability of a negative ion is greater than that of a positive ion since the electrons are less firmly bound because of the differences in effective nuclear charge. Large negative ions are more polarizable than small ones.

Fajans put forward four rules which summarize the factors favouring polarization and hence covalency.

1. *A small positive ion favours covalency.*

In small ions the positive charge is concentrated over a small area. This makes the ion highly polarizing, and very good at distorting the negative ion.

2. *A large negative ion favours covalency.*

Large ions are highly polarizable, that is easily distorted by the positive ion, because the outermost electrons are shielded from the charge on the nucleus by filled shells of electrons.

3. *Large charges on either ion, or on both ions, favour covalency.*

This is because a high charge increases the amount of polarization.

4. *Polarization, and hence covalency, is favoured if the positive ion does not have a noble gas configuration.*

Examples of ions which do not have a noble gas configuration include a few main group elements such as  $\text{Tl}^+$ ,  $\text{Pb}^{2+}$  and  $\text{Bi}^{3+}$ , many transition metal ions such as  $\text{Ti}^{3+}$ ,  $\text{V}^{3+}$ ,  $\text{Cr}^{2+}$ ,  $\text{Mn}^{2+}$  and  $\text{Cu}^+$ , and some lanthanide metal ions such as  $\text{Ce}^{3+}$  and  $\text{Eu}^{2+}$ . A noble gas configuration is the most effective at shielding the nuclear charge, so ions without the noble gas configuration will have high charges at their surfaces, and thus be highly polarizing.

## ELECTRONEGATIVITY

In 1931, Pauling defined the electronegativity of an atom as the tendency of the atom to attract electrons to itself *when combined in a compound*.


The implication of this is that when a covalent bond is formed, the electrons used for bonding need not be shared equally by both atoms. If the bonding electrons spend more time round one atom, that atom will have a  $\delta^-$  charge, and consequently the other atom will have a  $\delta^+$  charge. In the extreme case where the bonding electrons are round one atom all of the time, the bond is ionic. Pauling and others have attempted to relate the electronegativity difference between two atoms to the amount of ionic character in the bond between them.

Generally, small atoms attract electrons more strongly than large ones, and hence small atoms are more electronegative. Atoms with nearly filled shells of electrons tend to have higher electronegativities than those with sparsely occupied ones. Electronegativity values are very difficult to




measure. Even worse, a particular type of atom in different molecules may well be in a different environment. It is unlikely that the electronegativity of an atom remains constant regardless of its environment, though it is invariably assumed that it is constant. Some of the more important approaches to obtaining electronegativity values are outlined below.

### Pauling

Pauling pointed out that since reactions of the type



are almost always exothermic, the bond formed between the two atoms A and B must be stronger than the average of the single bond energies of A—A and B—B molecules. For example



The bonding molecular orbital for AB ( $\phi_{AB}$ ) is made up from contributions from the wave functions for the appropriate atomic orbitals ( $\psi_A$  and  $\psi_B$ )

$$\phi_{AB} = (\psi_A) + \text{constant} (\psi_B)$$

If the constant is greater than 1, the molecular orbital is concentrated on the B atom, which therefore acquires a partial negative charge, and the bond is partly polar



Conversely, if the constant is less than 1, atom A gains a partial negative charge. Because of this partial ionic character, the A—B bond is stronger than would be expected for a pure covalent bond. The extra bond energy is called delta  $\Delta$ .

$$\Delta = (\text{actual bond energy}) - (\text{energy for 100\% covalent bond})$$

The bond energy can be measured, but the energy of a 100% covalent bond must be calculated. Pauling suggested the 100% covalent bond energy be calculated as the geometric mean of the covalent energies of A—A and B—B molecules

$$E_{100\% \text{ covalent } A-B} = \sqrt{(E_{A-A} \cdot E_{B-B})}$$

The bond energy in A—A and B—B molecules can be measured and so

$$\Delta = (\text{actual bond energy}) - \sqrt{(E_{A-A} \cdot E_{B-B})}$$

Pauling states that the electronegativity difference between two atoms is equal to  $0.208\sqrt{\Delta}$ , where  $\Delta$  is the extra bond energy in  $\text{kcal mol}^{-1}$ .

(Converting the equation to SI units gives  $0.1017/\Delta$ , where  $\Delta$  is measured in  $\text{kJ mol}^{-1}$ .)

Pauling evaluated  $0.208/\Delta$  for a number of bonds and called this the electronegativity difference between A and B. Repeating Pauling's calculation with SI units for energy, we can evaluate  $0.1017/\Delta$ :

Bond	$\Delta(\text{kJ mol}^{-1})$	$0.1017/\Delta$	
C—H	24.3	0.50	i.e. $\chi_{\text{C}} - \chi_{\text{H}} = 0.50$
H—Cl	102.3	1.02	i.e. $\chi_{\text{Cl}} - \chi_{\text{H}} = 1.02$
N—H	105.9	1.04	i.e. $\chi_{\text{N}} - \chi_{\text{H}} = 1.04$

( $\chi$  (chi) = electronegativity of atom)

If  $\chi_{\text{H}} = 0$  then the electronegativity values for C, Cl and N would be 0.50, 1.02 and 1.04 respectively. Pauling changed the origin of the scale from  $\chi_{\text{H}} = 0$  to  $\chi_{\text{H}} = 2.05$  to avoid having any negative values in the table of values, and this made the value for C become 2.5 and the value for F become 4.0. At the same time the values for a number of other elements approximated to whole numbers: Li = 1.0, B = 2.0, N = 3.0. Thus by adding 2.05 to the values calculated in this way we can obtain the usually accepted electronegativity values (Table 6.8).

If two atoms have similar electronegativities, that is a similar tendency to attract electrons, the bond between them will be predominantly covalent. Conversely a large difference in electronegativity leads to a bond with a high degree of polar character, that is a bond that is predominantly ionic.

Rather than have two extreme forms of bond (ionic and covalent), Pauling introduced the idea that the ionic character of a bond varies with

Table 6.8 Pauling's electronegativity coefficients (for the most common oxidation states of the elements)

						H 2.1
Li 1.0	Be 1.5	B 2.0	C 2.5	N 3.0	O 3.5	F 4.0
Na 0.9						Cl 3.0
K 0.8						Br 2.8
Rb 0.8						I 2.5
Cs 0.7						

Table 6.9 Pauling's electronegativity values

Group Period	1	2	13	14	15	16	17	18
1	H ● 2.1						H ● 2.1	He
2	Li ● 1.0	Be ● 1.5	B ● 2.0	C ● 2.5	N ● 3.0	O ● 3.5	F ● 4.0	Ne
3	Na ● 0.9	Mg ● 1.2	Al ● 1.5	Si ● 1.8	P ● 2.1	S ● 2.5	Cl ● 3.0	Ar
4	K ● 0.8	Ca ● 1.0	Ga ● 1.6	Ge ● 1.8	As ● 2.0	Se ● 2.4	Br ● 2.8	Kr
5	Rb ● 0.8	Sr ● 1.0	In ● 1.7	Sn ● 1.8	Sb ● 1.9	Te ● 2.1	I ● 2.5	Xe
6	Cs ● 0.7	Ba ● 0.9	Tl ● 1.8	Pb ● 1.8	Bi ● 1.9	Po ● 2.0	At ● 2.2	Rn
7	Fr ● 0.7	Ra ● 0.9						

# PAULING'S ELECTRONEGATIVITY VALUES

Electronegativity values with the oxidation state of the element. The values given are for the most common oxidation states. (Large circles indicate high values and small circles small values.)  
Copyright 1964, Cornell University. Adapted by permission of Cornell University Press.




Figure 6.3 Electronegativity difference.

the difference in electronegativity as shown in Figure 6.3. This graph is based on the ionic characters HI 4% ionic, HBr 11%, HCl 19% and HF 45%, which are known from dipole measurements. Fifty per cent ionic character occurs when the electronegativity difference between the atoms is about 1.7, so for a larger difference than this a bond is more ionic than covalent. Similarly, if the electronegativity difference is less than 1.7, the bond is more covalent than ionic. It is better to describe a bond such as one of those in  $\text{BF}_3$  as 63% ionic, rather than just ionic.

### Mulliken

In 1934, Mulliken suggested an alternative approach to electronegativity based on the ionization energy and electron affinity of an atom. Consider two atoms A and B. If an electron is transferred from A to B, forming ions  $\text{A}^+$  and  $\text{B}^-$ , then the energy change is the ionization energy of atom A ( $I_A$ ) minus the electron affinity of atom B ( $E_B$ ), that is  $I_A - E_B$ . Alternatively, if the electron was transferred the other way to give  $\text{B}^+$  and  $\text{A}^-$  ions, then the energy change would be  $I_B - E_A$ . If  $\text{A}^+$  and  $\text{B}^-$  are actually formed, then this process requires less energy, and

$$(I_A - E_B) < (I_B - E_A)$$

Rearranging

$$(I_A + E_A) < (I_B + E_B)$$

Thus Mulliken suggested that electronegativity could be regarded as the average of the ionization energy and the electron affinity of an atom.

$$\text{Electronegativity} = \frac{(I + E)}{2}$$

Mulliken used  $I$  and  $E$  values measured in electron volts, and the values were about 2.8 times larger than the Pauling values. We now measure  $I$  and

$E$  in  $\text{kJ mol}^{-1}$  The energy  $1 \text{ eV/molecule} = 96.48 \text{ kJ mol}^{-1}$ , so the commonly accepted Pauling values are more nearly obtained by performing this calculation  $(I + E)/(2 \times 2.8 \times 96.48)$  or  $(I + E)/540$

This method has a simple theoretical basis, and also has the advantage that different values can be obtained for different oxidation states of the same element. It suffers from the limitation that only a few electron affinities are known. It is more usual to use the approach based on bond energies.

### Allred and Rochow

In 1958 Allred and Rochow considered electronegativity in a different way and worked out values for 69 elements (See Further Reading). They defined electronegativity as the attractive force between a nucleus and an electron at a distance equal to the covalent radius. This force  $F$  is electrostatic, and is given by

$$F = \frac{e^2 Z_{\text{effective}}}{r^2}$$

where  $e$  is the charge on an electron,  $r$  is the covalent radius, and  $Z_{\text{effective}}$  is the effective nuclear charge. The latter is the nuclear charge modified by screening factors for the orbital electrons. The screening factors vary depending on the principal quantum number (the shell that the electron occupies), and the type of electron,  $s$ ,  $p$ ,  $d$  or  $f$ . Screening factors have been worked out by Slater, so this provides a convenient method of calculating electronegativity values. These  $F$  values may be converted to electronegativity values on the Pauling scale of values using an empirical relationship

$$\chi = 0.744 + \frac{0.359 Z_{\text{effective}}}{r^2}$$

The electronegativity values so obtained agree quite closely with those obtained by Pauling and Mulliken.

As the oxidation number of an atom increases, the attraction for the electrons increases, so the electronegativity should also increase. Allred and Rochow's method gives slightly different values

Mo(II)	2.18	Fe(II)	1.83	Tl(I)	1.62	Sn(II)	1.80
Mo(III)	2.19	Fe(III)	1.96	Tl(III)	2.04	Sn(IV)	1.96
Mo(IV)	2.24						
Mo(V)	2.27						
Mo(VI)	2.35						

Allred and Rochow's method depends on measuring covalent radii (and these are obtained with great accuracy by X-ray crystallography) so it might be expected to yield very accurate electronegativity values. This is not so, because although the interatomic distances can be measured very



precisely, covalent radii are much less well known because the multiplicity of the bond is not known for certain, that is the bond may possess some double bond character.

The electronegativity values given in this book are those due to Pauling, but others have been calculated from different theoretical assumptions by Mulliken, Allred and Rochow and Sanderson. For details of these and several modern reviews of electronegativity values see Further Reading. *It is now considered that attempts to measure very accurate values for electronegativity are unjustified, and it is better to retain a loose definition of electronegativity, and use it for a more qualitative description of bonds.* For this purpose, it is worth remembering a few electronegativity values (see Table 6.8). From these it is possible to make a reasonable guess at the values for other elements, and hence predict the nature of the bonds formed. Bonds between atoms with similar electronegativity values will be largely non-polar (covalent), and bonds between atoms with a large electronegativity difference will be largely polar (ionic). Predictions using electronegativity in general agree with those made using Fajans' rules.

The basic properties of elements are inversely related to the electronegativity. Thus on descending one of the main groups, the electronegativity decreases, and basic properties increase. Similarly, on going across a period the elements become more electronegative, and less basic.


## METALLIC CHARACTER

Metals are electropositive and have a tendency to lose electrons, if supplied with energy:



The stronger this tendency, the more electropositive and more metallic an element is. The tendency to lose electrons depends on the ionization energy. It is easier to remove an electron from a large atom than from a small one, so metallic character increases as we descend the groups in the periodic table. Thus in Group 14, carbon is a non-metal, germanium shows some metallic properties, and tin and lead are metals. Similarly, metallic character decreases from left to right across the periodic table because the size of the atoms decreases and the ionization energy increases. Thus sodium and magnesium are more metallic than silicon, which, in turn, is more metallic than chlorine. The most electropositive elements are found in the lower left of the periodic table and the most non-metallic in the top right.

Electropositivity is really the converse of electronegativity, but it is convenient to use the concept of electropositivity when describing metals. Strongly electropositive elements give ionic compounds. Metallic oxides and hydroxides are basic since they ionize, and give hydroxyl ions:



Oxides which are insoluble in water cannot produce  $\text{OH}^-$  in this way and these are regarded as basic if they react with acids to form salts. Thus in the main groups of the periodic table, basic properties increase on descending a group because the elements become more electropositive and more ionic. However, this generalization does not hold for the  $d$  block, and particularly for the central groups of transition elements (Cr, Mn, Fe, Co, Ni) where basicity and the ability to form simple ions decreases on descending the group.

The degree of electropositivity is shown in a variety of ways. Strongly electropositive elements react with water and acids. They form strongly basic oxides and hydroxides, and they react with oxoacids to give stable salts such as carbonates, nitrates and sulphates. Weakly electropositive elements are unaffected by water and are much less readily attacked by acids. Their oxides are frequently amphoteric and react with both acids and alkalis. They are not basic enough to form stable carbonates.

The electropositive nature of a metal is also shown in the degree of hydration of the ions. In the change  $\text{M}^+ \rightarrow [(\text{H}_2\text{O})_n \rightarrow \text{M}]^+$  the positive charge becomes spread over the whole complex ion. Since the charge is no longer localized on the metal, this is almost the same as the change  $\text{M}^+ \rightarrow \text{M}$ . Strongly electropositive metals have a great tendency to the opposite change,  $\text{M} \rightarrow \text{M}^+$  so that they are not readily hydrated. The less electropositive the metal, the weaker the tendency  $\text{M} \rightarrow \text{M}^+$  and the stronger the degree of hydration. Thus the elements in Group 2 are less electropositive than those of Group 1, and Group 2 ions are more heavily hydrated than those in Group 1. The degree of hydration also decreases down a group, e.g.  $\text{MgCl}_2 \cdot 6\text{H}_2\text{O}$  and  $\text{BaCl}_2 \cdot 2\text{H}_2\text{O}$ .

Salts of strongly electropositive metals have little tendency to hydrolyse and form oxosalts. Since the metal ion is large, it has little tendency to form complexes. On the other hand, salts of weakly electropositive elements hydrolyse and may form oxosalts. Because they are smaller, the metal ions have a greater tendency to form complexes.

## VARIABLE VALENCY AND OXIDATION STATES

In the  $s$  block the oxidation state is always the same as the group number. For  $p$  block elements, the oxidation state is normally (the group number - 10) or (18 - the group number). Variable valency does occur to a limited extent in the  $p$ -block. In these cases the oxidation state always changes by two, e.g.  $\text{TiCl}_3$  and  $\text{TiCl}_4$ ,  $\text{SnCl}_4$  and  $\text{SnCl}_2$ ,  $\text{PCl}_5$  and  $\text{PCl}_3$ , and is due to a pair of electrons remaining paired and not taking part in bonding (the inert pair effect). The term oxidation state is preferred to valency. The oxidation state may be defined as the charge left on the central atom when all the other atoms of the compound have been removed in their usual oxidation states. Thus Ti shows oxidation states of (+III) and (+IV), Sn of (+IV) and (+II), and P of (+V) and (+III). The oxidation number can be calculated equally well for ionic or covalent compounds and without knowing the types of bonds. The oxidation number of S in  $\text{H}_2\text{SO}_4$  can be worked out as

follows. O usually has an oxidation state of  $(-II)$  (except in  $O_2$  and  $O_2^{2-}$ ). H usually has an oxidation state of  $(+I)$  (except in  $H_2$  and  $H^-$ ). The sum of the oxidation numbers of all the atoms in  $H_2SO_4$  is zero, so:

$$(2 \times 1) + (S^x) + (4 \times -2) = 0$$

Thus  $x$ , the oxidation state of  $S$ , is  $(+VI)$ . In the case of the oxidation state of  $Mn$  in  $KMnO_4$ , the compound ionizes into  $K^+$  and  $MnO_4^-$  ions. In  $MnO_4^-$  the sum of the oxidation states is equal to the charge on the ion, so:

$$Mn^x + (4 \times -2) = -1$$


Thus  $x$ , the oxidation state of  $Mn$ , is 7, i.e.  $(+VII)$ .

One of the most striking features of the transition elements is that the elements usually exist in several different oxidation states. Furthermore, the oxidation states change in units of 1, e.g.  $Fe^{3+}$  and  $Fe^{2+}$ ,  $Cu^{2+}$  and  $Cu^+$ . This is in contrast to the  $s$ -block and  $p$ -block elements. The reason why this occurs is that a different number of  $d$  electrons may take part in bonding.

Though the oxidation number is the same as the charge on the ion for ions such as  $Tl^+$  and  $Tl^{3+}$ , the two are not necessarily the same. Thus  $Mn$  exists in the oxidation state  $(+VII)$  but  $Mn^{7+}$  does not exist, as  $KMnO_4$  ionizes into  $K^+$  and  $MnO_4^-$ .

## STANDARD ELECTRODE POTENTIALS AND ELECTROCHEMICAL SERIES

When a metal is immersed in water, or a solution containing its own ions, the metal tends to lose positive metal ions into the solution. Thus the metal acquires a negative charge.



The size of the electric potential  $E$  set up between the two depends on the particular metal, the number of electrons involved, the activity of the ions in solution, and the temperature.  $E^\circ$  is the standard electrode potential, which is a constant for any particular metal and is in fact the electrode potential measured under standard conditions of temperature and with unit activity. These terms are related by the equation:

$$E = E^\circ + \frac{RT}{nF} \ln (I/a_{Mn+})$$

(where  $R$  is the gas constant,  $T$  the absolute temperature,  $a_{Mn+}$  the activity of the ions in solution,  $n$  the valency of the ion and  $F$  the Faraday). For most purposes, the activity,  $a_{Mn+}$ , may be replaced by the concentration of ions in solution.

The potential of a single electrode cannot be measured, but if a second electrode of known potential is placed in the solution, the potential difference between the two electrodes can be measured. The standard against which all electrode potentials are compared is the hydrogen electrode.

Table 6 10 Standard electrode potentials (volts at 25 °C)

$\text{Li}^+$	Li	-3.05
$\text{K}^+$	K	-2.93
$\text{Ca}^{2+}$	Ca	-2.84
$\text{Al}^{3+}$	Al	-1.66
$\text{Mn}^{2+}$	Mn	-1.08
$\text{Zn}^{2+}$	Zn	-0.76
$\text{Fe}^{2+}$	Fe	-0.44
$\text{Cd}^{2+}$	Cd	-0.40
$\text{Co}^{2+}$	Co	-0.27
$\text{Ni}^{2+}$	Ni	-0.23
$\text{Sn}^{2+}$	Sn	-0.14
$\text{Pb}^{2+}$	Pb	-0.13
$\text{H}^+$	$\text{H}_2$	0.00
$\text{Cu}^{2+}$	Cu	+0.35
$\text{Ag}^+$	Ag	+0.80
$\text{Au}^{3+}$	Au	+1.38

Table 6 11 Standard electrode potentials (V)


$\text{O}_2   \text{OH}^-$	+0.40
$\text{I}_2   \text{I}^-$	+0.57
$\text{Br}_2   \text{Br}$	+1.07
$\text{Cl}_2   \text{Cl}^-$	+1.36
$\text{F}_2   \text{F}^-$	+2.85

(This comprises a platinized platinum electrode, which is saturated with hydrogen at one atmosphere pressure and immersed in a solution of  $\text{H}_3\text{O}^+$  at unit activity. The potential developed by this electrode is arbitrarily fixed as zero.)

If the elements are arranged in order of increasing standard electrode potentials, the resulting Table 6 10 is called the electrochemical series.

Electrode potentials can also be measured for elements such as oxygen and the halogens which form negative ions (Table 6 11).

In the electrochemical series the most electropositive elements are at the top and the least electropositive at the bottom. The greater the negative value of the potential, the greater is the tendency for a metal to ionize. Thus a metal high in the electrochemical series will displace another metal lower down the series from solution. For example, iron is above copper in the electrochemical series, and scrap iron is sacrificed to displace  $\text{Cu}^{2+}$  ions from solution of  $\text{CuSO}_4$  in the recovery of metallic copper.




In the Daniell cell zinc displaces copper from copper salts in solution. This causes the potential difference between the plates.

Table 6.12 Some standard reduction potentials in acid solution at 25 °C (volts)

Group 1	$E^\circ$	Group 15	$E^\circ$	Group 17	$E^\circ$
$\text{Li}^+ + e \rightarrow \text{Li}$	-3.05	$\text{As} + 3e \rightarrow \text{AsH}_3$	-0.60	$\text{I}_3^- + 2e \rightarrow 3\text{I}^-$	+0.54
$\text{K}^+ + e \rightarrow \text{K}$	-2.93	$\text{Sb} + 3e \rightarrow \text{SbH}_3$	-0.51	$\text{Br}_3^- + 2e \rightarrow 3\text{Br}^-$	+1.05
$\text{Rb}^+ + e \rightarrow \text{Rb}$	-2.93	$\text{H}_3\text{PO}_2 + e \rightarrow \text{P}$	-0.51	$2\text{ICl}_2^- + 2e \rightarrow \text{I}_2$	+1.06
$\text{Cs}^+ + e \rightarrow \text{Cs}$	-2.92	$\text{H}_3\text{PO}_3 + 2e \rightarrow \text{H}_3\text{PO}_2$	-0.50	$\text{Br}_2 + 2e \rightarrow 2\text{Br}^-$	+1.07
$\text{Na}^+ + e \rightarrow \text{Na}$	-2.71	$\text{H}_3\text{PO}_4 + 2e \rightarrow \text{H}_3\text{PO}_3$	-0.28	$2\text{IO}_3^- + 10e \rightarrow \text{I}_2$	+1.20
		$\frac{1}{2}\text{N}_2 + 3e \rightarrow \text{NH}_4^+$	-0.27	$\text{Cl}_2 + 2e \rightarrow 2\text{Cl}^-$	+1.36
		$\frac{1}{2}\text{N}_2 + 2e \rightarrow \frac{1}{2}\text{N}_2\text{H}_5^+$	-0.23	$2\text{HOI} + 2e \rightarrow \text{I}_2$	+1.45
Group 2		$\text{P} + 3e \rightarrow \text{PH}_3$	+0.06	$\text{H}_5\text{IO}_6 + 2e \rightarrow \text{IO}_3^-$	+1.60
$\text{Ba}^{2+} + 2e \rightarrow \text{Ba}$	-2.90	$\frac{1}{2}\text{Sb}_2\text{O}_3 + 3e \rightarrow \text{Sb}$	+0.15	$2\text{HOCl} + 2e \rightarrow \text{Cl}_2$	+1.63
$\text{Sr}^{2+} + 2e \rightarrow \text{Sr}$	-2.89	$\text{HAsO}_2 + 3e \rightarrow \text{As}$	+0.25	$\text{F}_2 + 2e \rightarrow 2\text{F}^-$	+2.65
$\text{Ca}^{2+} + 2e \rightarrow \text{Ca}$	-2.87	$\text{H}_3\text{AsO}_4 + 2e \rightarrow \text{HAsO}_2$	+0.56		
$\text{Mg}^{2+} + 2e \rightarrow \text{Mg}$	-2.37	$\text{HN}_3 + 8e \rightarrow 3\text{NH}_4^+$	+0.69	Transition Metals	
$\text{Be}^{2+} + 2e \rightarrow \text{Be}$	-1.85	$\text{NO}_3^- + 3e \rightarrow \text{NO}$	+0.96	$\text{La}^{3+} + 3e \rightarrow \text{La}$	-2.52
		$\text{HNO}_2 + e \rightarrow \text{NO}$	+1.00	$\text{Sc}^{3+} + 3e \rightarrow \text{Sc}$	-2.08
Group 13		$\frac{1}{2}\text{N}_2\text{O}_4 + 2e \rightarrow \text{NO}$	+1.03	$\text{Mn}^{2+} + 2e \rightarrow \text{Mn}$	-1.18
$\text{Al}^{3+} + 3e \rightarrow \text{Al}$	-1.66	$\frac{1}{2}\text{N}_2\text{H}_5^+ + 2e \rightarrow \text{NH}_4^+$	+1.28	$\text{Zn}^{2+} + 2e \rightarrow \text{Zn}$	-0.76
$\text{Ga}^{3+} + 3e \rightarrow \text{Ga}$	-0.53	$\text{NH}_3\text{OH} + 2e \rightarrow \text{NH}_4^+$	+1.35	$\text{Cr}^{3+} + 3e \rightarrow \text{Cr}$	-0.74
$\text{In}^{3+} + 3e \rightarrow \text{In}$	-0.34			$\text{Fe}^{2+} + 2e \rightarrow \text{Fe}$	-0.44
$\text{Tl}^+ + e \rightarrow \text{Tl}$	-0.34	Group 16		$\text{Cr}^{3+} + e \rightarrow \text{Cr}^{2+}$	-0.41
$\text{Tl}^{3+} + 2e \rightarrow \text{Tl}^+$	+1.25	$\text{Te} + 2e \rightarrow \text{H}_2\text{Te}$	-0.72	$\text{Cd}^{2+} + 2e \rightarrow \text{Cd}$	-0.40
		$\text{Se} + 2e \rightarrow \text{H}_2\text{Se}$	-0.40	$\text{Ni}^{2+} + 2e \rightarrow \text{Ni}$	-0.25
Group 14		$\text{S}_4\text{O}_6^{2-} + 2e \rightarrow 2\text{S}_2\text{O}_3^{2-}$	+0.08	$\text{Cu}^{2+} + e \rightarrow \text{Cu}^+$	+0.15
$\text{SiO}_2 + 4e \rightarrow \text{Si}$	-0.86	$\text{S} + 2e \rightarrow \text{H}_2\text{S}$	+0.14	$\text{Hg}_2\text{Cl}_2 + 2e \rightarrow 2\text{Hg}$	+0.27
$\text{PbSO}_4 + 2e \rightarrow \text{Pb}$	-0.36	$\text{HSO}_4^- + 2e \rightarrow \text{H}_2\text{SO}_3$	+0.17	$\text{Cu}^{2+} + 2e \rightarrow \text{Cu}$	+0.35
$\text{CO}_2 + 4e \rightarrow \text{C}$	-0.20	$\text{H}_2\text{SO}_3 + 2e \rightarrow \frac{1}{2}\text{S}_2\text{O}_3^{2-}$	+0.40	$[\text{Fe}(\text{CN})_6]^{3-} + e \rightarrow [\text{Fe}(\text{CN})_6]^{4-}$	+0.36
$\text{GeO}_2 + 4e \rightarrow \text{Ge}$	-0.15	$\text{H}_2\text{SO}_3 + 4e \rightarrow \text{S}$	+0.45	$\text{Cu}^+ + e \rightarrow \text{Cu}$	+0.50
$\text{Sn}^{2+} + 2e \rightarrow \text{Sn}$	-0.14	$4\text{H}_2\text{SO}_3 + 6e \rightarrow \text{S}_4\text{O}_6^{2-}$	+0.51	$\text{Cu}^{2+} + e \rightarrow \text{CuCl}$	+0.54
$\text{Pb}^{2+} + 2e \rightarrow \text{Pb}$	-0.13	$\text{S}_2\text{O}_6^{2-} + 2e \rightarrow 2\text{H}_2\text{SO}_4$	+0.57	$\text{MnO}_4^- + e \rightarrow \text{MnO}_3^{2-}$	+0.56
$\text{Si} + 4e \rightarrow \text{SiH}_4$	+0.10	$\text{O}_2 + 2e \rightarrow \text{H}_2\text{O}_2$	+0.68	$\text{Fe}^{3+} + e \rightarrow \text{Fe}^{2+}$	+0.77
$\text{C} + 4e \rightarrow \text{CH}_4$	+0.13	$\text{H}_2\text{SeO}_3 + 4e \rightarrow \text{Se}$	+0.74	$\text{Hg}_2^{2+} + 2e \rightarrow 2\text{Hg}$	+0.79
$\text{Sn}^{4+} + 2e \rightarrow \text{Sn}^{2+}$	+0.15	$\text{SeO}_4^{2-} + 2e \rightarrow \text{H}_2\text{SeO}_3$	+1.15	$2\text{Hg}_2^{2+} + 2e \rightarrow \text{Hg}_2^{2+}$	+0.92
$\text{PbO}_2 + 2e \rightarrow \text{PbSO}_4$	+1.69	$\frac{1}{2}\text{O}_2 + 2e \rightarrow \text{H}_2\text{O}$	+1.23	$\text{MnO}_2 + 2e \rightarrow \text{Mn}^{2+}$	+1.23
		$\text{H}_2\text{O}_2 + 2e \rightarrow 2\text{H}_2\text{O}$	+1.77	$\frac{1}{2}\text{Cr}_2\text{O}_7^{2-} + 3e \rightarrow \text{Cr}^{3+}$	+1.33
		$\text{S}_2\text{O}_8^{2-} + 2e \rightarrow 2\text{SO}_4^{2-}$	+2.01	$\text{MnO}_4^- + 5e \rightarrow \text{Mn}^{2+}$	+1.54
		$\text{O}_3 + 2e \rightarrow \text{O}_2$	+2.07	$\text{NiO}_2 + 2e \rightarrow \text{Ni}^{2+}$	+1.68
				$\text{MnO}_4^- + 3e \rightarrow \text{MnO}_2$	+1.70

Table 6 12 is a table of standard reduction potentials. From this table we can see that the standard reduction potential for  $\text{Cu}^{2+}/\text{Cu}$  is 0.35 V. What does this mean?

$\text{Cu}^{2+}/\text{Cu}$  is referred to as a redox couple and as written it refers to the half reaction (or electrode reaction)



In general, redox couples are written *ox/red* where *ox* is the oxidized form and is written on the left and *red* is the reduced form and is written on the right.

Standard reduction potential values are determined relative to a hydrogen electrode, that is the redox couple  $\text{H}^+/\text{H}_2$  at 25°C for 1M concentrations (or one atmosphere pressure) of all chemical species in the equations. (The concentration of water is included in the constant.)

Thus,  $\text{Cu}^{2+}/\text{Cu}$   $E^\circ = +0.35 \text{ V}$  really means that the standard reduction potential of the reaction is 0.35 V.



Similarly the standard reduction potential of the couple  $\text{Zn}^{2+}/\text{Zn}$  is  $-0.76 \text{ V}$ .



Subtracting equation (6.2) from (6.1) gives



Both of the standard potentials are relative to the  $\text{H}^+/\text{H}_2$  couple and therefore  $\text{H}^+$  and  $\text{H}_2$  disappear when the  $\text{Cu}^{2+}/\text{Cu}$  couple is combined with the  $\text{Zn}^{2+}/\text{Zn}$  couple.

From experience the oxidized forms of couples of high positive potential, for example  $\text{MnO}_4^- + 5\text{e}^- \rightarrow \text{Mn}^{2+}$   $E^\circ = +1.54 \text{ V}$ , are termed strong oxidizing agents. Conversely the reduced forms of couples of high negative potential, for example  $\text{Li}^+ + \text{e}^- \rightarrow \text{Li}$   $E^\circ = -3.05 \text{ V}$ , are termed strong reducing agents. It follows that at some intermediate potential the oxidizing power of the oxidized form and the reducing power of the reduced form are similar. What is the value of this potential at which there is a change over from oxidizing to reducing properties? The first point to note is that it is not at 0 V, the value assigned arbitrarily to the  $\text{H}^+/\text{H}$  couple. Hydrogen is known to be a reducing agent. A group of chemical species which are used in classical (analytical) chemistry as weak reducing agents (e.g. sulphite and tin(II)) are the reduced forms of couples with potentials between 0 and about +0.6 V. On the other hand  $\text{VO}^{2+}$  is the stable form of vanadium and  $\text{VO}_2^+$  is a weak oxidizing agent; the potential  $\text{VO}_2^+/\text{VO}^{2+}$  is +1.00 V. Thus from experience as a general rule of thumb we can say that if  $E^\circ \approx 0.8 \text{ V}$  then the oxidized and reduced forms are of about equal stability in redox processes.

It is not very discriminating to term a metal a reducing agent; most metals may be called reducing agents. It is useful to divide metals into four groups in regard to the ease of reduction of their metal ions.

1. The noble metals (with  $E^\circ$  more positive than 0 V).
2. Metals which are easily reduced (e.g. with coke) ( $E^\circ$  0 – (–0.5) V).
3. Typically reactive transition metals ( $E^\circ$  (–0.5) – (–1.5) V) which are often prepared by reduction with electropositive metals.
4. The electropositive metals ( $E^\circ$  more negative than –1.5 V) which can be prepared by electrochemical reduction.

When a solution is electrolysed the externally applied potential must overcome the electrode potential. The minimum voltage necessary to cause deposition is equal and opposite in sign to the potential between the solution and the electrode. Elements low down in the series discharge first; thus  $\text{Cu}^{2+}$  discharges before  $\text{H}^+$ , so copper may be electrolysed in aqueous solution. However, hydrogen and other gases often require a considerably higher voltage than the theoretical potential before they discharge. For hydrogen, this extra or over-voltage may be 0.8 volts, and thus it is possible to electrolyse zinc salts in aqueous solution.

Several factors affect the value of the standard potential. The conversion of  $\text{M}$  to  $\text{M}^+$  in aqueous solution may be considered in a series of steps:

1. sublimation of a solid metal
2. ionization of a gaseous metal atom
3. hydration of a gaseous ion

These are best considered in a Born–Haber type of cycle (Figure 6.4).

The enthalpy of sublimation and the ionization energy are positive since energy must be put into the system, and the enthalpy of hydration is negative since energy is evolved. Thus

$$E = +\Delta H_s + I + \Delta H_h$$




Figure 6.4 Energy cycle for electrode potentials. (Strictly  $E$  is the free energy change associated with electrode potential)

Consider first a transition metal. Most transition metals have high melting points, hence the enthalpy of sublimation is high. Similarly they are fairly small atoms and have high ionization energies. Thus the value for the electrode potential  $E$  is low, and the metal has little tendency to form ions, hence it is unreactive or noble.

In contrast the  $s$  block metals (Groups 1 and 2) have low melting points (hence low enthalpies of sublimation), and the atoms are large and therefore have low ionization energies. Thus the electrode potential  $E$  is high and the metals are reactive.

Electrons are lost when a substance is oxidized and electrons are gained when it is reduced. A reducing agent must therefore supply electrons, and elements having large negative electrode potentials are strong reducing agents. The strengths of oxidizing and reducing agents may be measured by the size of the potential between a solution and an inert electrode. Standard reduction potentials are obtained when the concentrations of oxidized and reduced forms are 1 M, and the potential developed is measured against a standard hydrogen electrode. The most powerful oxidizing agents have a large positive oxidation potential and strong reducing agents have a large negative potential. Standard oxidation potentials allow us to predict which ions should oxidize or reduce other ions. The potentials indicate if the energy changes for the process are favourable or unfavourable. It is important to realize that though the potentials may suggest that a reaction is possible, they do not give any kinetic information concerning the rate of the reaction. The rate of the reaction may be very fast or slow, and in some cases a catalyst may be required for it to occur at all – for example in the oxidation of sodium arsenite by ceric sulphate.

## OXIDATION-REDUCTION REACTIONS

Oxidation is the removal of electrons from an atom, and reduction is the addition of electrons to an atom. The standard electrode potentials given in Table 6.10 are written by convention with the oxidized species on the left, and the reduced species on the right.



or



The potential developed by the half cell is therefore written as a reduction potential, since electron(s) are being added. A fuller list of reduction potentials in acid solution is given in Table 6.12.

Oxidation-reduction (redox) potentials can be used to great advantage in explaining oxidation-reduction reactions in aqueous solution. The reduction potential is related to energy by the equation

$$\Delta G = -nFE^\circ$$

(where  $\Delta G$  is the change in Gibbs free energy,  $n$  the valency of the ion,  $F$  the Faraday and  $E^\circ$  the standard electrode potential). This is really an



application of thermodynamics. Ultimately whether a reaction occurs or not depends on energy. A reaction will not proceed if the free energy change  $\Delta G$  is positive, and thus thermodynamics saves us the trouble of trying the reaction. If  $\Delta G$  is negative, then the reaction is thermodynamically possible. It does not follow that because a reaction is thermodynamically possible, it will necessarily occur. Thermodynamics does not give any information on the rate of a reaction, which may be fast, slow, or infinitely slow, nor does it indicate if another reaction is even more favourable.

Consider the corrosion that may occur when a sheet of galvanized iron is scratched. (Galvanized iron is iron which has been coated with zinc to prevent rusting.) Half reactions and the corresponding reduction potentials are shown below.




When in contact with water, either metal might be oxidized and lose metal ions, so we require the reverse reactions, and the potentials for these are called oxidation potentials, and have the same magnitude but the opposite sign to the reduction potentials.



Plainly, since  $\text{Zn} \rightarrow \text{Zn}^{2+}$  produces the largest positive  $E^\circ$  value, and since  $\Delta G = -nFE^\circ$ , it will produce the largest negative  $\Delta G$  value. Thus it is energetically more favourable for the Zn to dissolve, and hence the Zn will corrode away in preference to the Fe.


It is possible that when the galvanized steel is scratched, the air may oxidize some iron. The  $\text{Fe}^{2+}$  so produced is immediately reduced to iron by the zinc, and rusting does not occur.




Similar applications in which one metal is sacrificed to protect another are the attaching of sacrificial blocks of magnesium to underground steel pipelines and the hulls of ships to prevent the rusting of iron.

Thus the coating of zinc serves two purposes – first it covers the iron and prevents its oxidation (rather like a coat of paint) and second it provides anodic protection.


A table of standard reduction potentials (Table 6.12) may be used to predict if a reaction is possible, and what the equilibrium constant will be. Consider for example if the triiodide ion  $\text{I}_3^-$  will oxidize As(III) in arsenious acid  $\text{HAsO}_2$  into As(V).



Since the table lists reduction potentials, we must find the half reactions for  $\text{H}_3\text{AsO}_4 + 2e \rightarrow \text{products}$ , and  $\text{I}_3^- + 2e \rightarrow \text{products}$ .



The reaction we are investigating requires the first half reaction in the reverse direction, added to the second half reaction.  $E^\circ$  values for half reactions must not be added together, since they do not take account of the number of electrons involved. However,  $E^\circ$  values may be converted to the corresponding  $\Delta G$  values which may be added to give  $\Delta G$  for the overall reaction.




The  $\Delta G$  free energy change so calculated is positive, which indicates that the reaction will not proceed spontaneously in the forward direction, and suggests that it is energetically feasible for the reaction to proceed in the reverse direction. It should be noted that the value of  $\Delta G$  is very small and thus it is unwise to draw very firm conclusions. The  $E^\circ$  values relate to standard conditions, and since  $\Delta G$  is small, a small change in conditions such as varying the concentration, or the pH, or the temperature, could change the potentials and hence change  $\Delta G$  sufficiently to make the reaction proceed in either direction. There are volumetric methods of analysis for reducing arsenic acid with iodide ions in 5M acid, and for oxidizing arsenous acid by triiodide ion at pH 7.

## THE USE OF REDUCTION POTENTIALS

Enormous use may be made of reduction potentials for summarizing what species will oxidize or reduce something else, what the products of the reaction will be, and what oxidation states are stable with respect to the solvent, and also with respect to disproportionation. This topic is often insufficiently understood, so a number of examples are given.

A great deal of useful information about an element can be shown by the appropriate half reactions and reduction potentials. Consider some half reactions involving iron.



Where an element exists in several different oxidation states (in this case Fe(VI), Fe(III), Fe(II), and Fe(0)), it is convenient to display all of the reduction potentials for the half reactions in a single reduction potential diagram. In this the highest oxidation state is written at the left, and the

lowest state at the right, and species such as electrons,  $H^+$  and  $H_2O$  are omitted.

oxidation state	VI	III	II	0
$E^\circ$ (V)	$FeO_4^{2-}$	$Fe^{3+}$	$Fe^{2+}$	$Fe$
		2.20	0.77	-0.47
				-0.057

The potential for the reduction of  $FeO_4^{2-}$  to  $Fe^{3+}$  is +2.20 volts. Since  $\Delta G = -nFE^\circ$ , it follows that  $\Delta G$  for this change will be large and negative. This means that the reaction is thermodynamically possible since it releases a large amount of energy, and  $FeO_4^{2-}$  is a strong oxidizing agent.

Standard electrode potentials are measured on a scale with




Since hydrogen is normally regarded as a reducing agent, reactions with negative value for  $E^\circ$  are more strongly reducing than hydrogen, that is they are strongly reducing. Materials which are generally accepted as oxidizing agents have  $E^\circ$  values above +0.8 volts, those such as  $Fe^{3+} \rightarrow Fe^{2+}$  of about 0.8 volts are stable (equally oxidizing and reducing), and those below +0.8 volts become increasingly reducing.

For the change  $Fe^{3+}/Fe^{2+}$ ,  $E^\circ$  is +0.77 V. This is close to the value of 0.8 V, and therefore  $Fe^{3+}$  and  $Fe^{2+}$  are of almost equal stability with respect to oxidation and reduction. The  $E^\circ$  values for the changes  $Fe^{3+} \rightarrow Fe$  and for  $Fe^{2+} \rightarrow Fe$  are both negative: hence  $\Delta G$  is positive, so neither  $Fe^{3+}$  nor  $Fe^{2+}$  have any tendency to reduce to Fe.

One of the most important facts which can be obtained from a reduction potential diagram is whether any of the oxidation states are unstable with regard to disproportionation. Disproportionation is where one oxidation state decomposes, forming some ions in a higher oxidation state, and some in a lower oxidation state. This happens when a given oxidation state is a stronger oxidizing agent than the next highest oxidation state, and this situation occurs when a reduction potential on the right is more positive than one on the left. In the diagram of iron reduction potentials, the values become progressively more negative on moving from left to right, and hence  $Fe^{3+}$  and  $Fe^{2+}$  are stable with respect to disproportionation.


At first sight the potential of -0.057 V for  $Fe^{3+} \rightarrow Fe$  seems wrong since the potentials for  $Fe^{3+} \rightarrow Fe^{2+}$  and  $Fe^{2+} \rightarrow Fe$  are 0.77 V and -0.47 V respectively, and adding 0.77 and -0.47 does *not* give -0.057. Potentials for complete reactions may be added since there are no electrons left over in the process. Potentials may not be added for half reactions since the electrons may not balance. However, potentials can always be converted into free energies using the equation  $\Delta G = -nFE^\circ$  where  $n$  is the number of electrons involved and  $F$  is the Faraday. Since the Gibbs free energy  $G$  is a thermodynamic function, free energies may be added, and the final total free energy converted back to an  $E^\circ$  value:



Hence  $E^\circ$  can be calculated for the reaction  $\text{Fe}^{3+} \rightarrow \text{Fe}$


$$E^\circ = \frac{\Delta G}{-nF} = \frac{0.17F}{-3F} = -0.057 \text{ V}$$

The reduction potential diagram for copper in acid solution is




\*Disproportionates

The potential, and hence the energy released when  $\text{Cu}^{2+}$  is reduced to  $\text{Cu}^+$ , are both very small, and so  $\text{Cu}^{2+}$  is not an oxidizing agent but is stable. On moving from left to right the potentials  $\text{Cu}^{2+} - \text{Cu}^+ - \text{Cu}$  become more positive. Whenever this is found, the species in the middle ( $\text{Cu}^+$  in this case) disproportionates, that is it behaves as both a self oxidizing and self reducing agent because it is energetically favourable for the following two changes to occur together




Thus in solution  $\text{Cu}^+$  disproportionates into  $\text{Cu}^{2+}$  and  $\text{Cu}$  and hence  $\text{Cu}^+$  is only found in the solid state

The reduction potential diagram for oxygen is shown



\*Disproportionates

On moving from left to right, the reduction potentials increase, and hence  $\text{H}_2\text{O}_2$  is unstable with respect to disproportionation



It must be remembered that the solvent may impose a limitation on what species are stable or exist at all. Very strong oxidizing reagents will oxidize

water to  $O_2$ , whilst strong reducing agents will reduce it to  $H_2$ . Thus very strong oxidizing or reducing agents can not exist in aqueous solution. The following half reactions are of special importance:

*Reduction of water*

neutral solution	$H_2O + e^- \rightarrow OH^- + \frac{1}{2}H_2$	$E^\circ = -0.414 \text{ V}$
1.0 M acid solution	$H_3O^+ + e^- \rightarrow H_2O + \frac{1}{2}H_2$	$E^\circ = 0.000 \text{ V}$
1.0 M base solution	$H_2O + e^- \rightarrow OH^- + \frac{1}{2}H_2$	$E^\circ = -0.828 \text{ V}$

*Oxidation of water*

neutral solution	$\frac{1}{2}O_2 + 2H^+ + 2e^- \rightarrow H_2O$	$E^\circ = +0.185 \text{ V}$
1.0 M acid solution	$\frac{1}{2}O_2 + 2H^+ + 2e^- \rightarrow H_2O$	$E^\circ = +1.229 \text{ V}$
1.0 M base solution	$\frac{1}{2}O_2 + H_2O + 2e^- \rightarrow 2OH^-$	$E^\circ = +0.401 \text{ V}$


These reactions limit the *thermodynamic stability* of any species in aqueous solution.

Thus the minimum reduction potentials required to oxidize water to dioxygen is  $E^\circ > +0.185 \text{ V}$  in neutral solution,  $E^\circ > +1.229 \text{ V}$  in 1.0 M acid solution and  $E^\circ > +0.401 \text{ V}$  in 1.0 M basic solution.

In the same way half reactions with  $E^\circ$  potentials less than zero (that is negative values) should reduce water to  $H_2$  in 1.0 M acid solution, whilst an  $E^\circ < -0.414 \text{ V}$  is required in neutral solution, and  $E^\circ < -0.828 \text{ V}$  in 1.0 M basic solution.


Often when the  $E^\circ$  values are just large enough to suggest that a reaction is thermodynamically possible, we find that it does not appear to happen. It must be remembered that a substance may be thermodynamically unstable, but kinetically stable, since the activation energy for the reaction is high. This means that the rates of these reactions are very slow. If the potentials are appreciably more positive or negative than these limits then reaction with the solvent is usually observed.

The reduction potentials for americium show that  $Am^{4+}$  is unstable with regard to disproportionation.




\* Disproportionates

The potential for the couple  $AmO_2^+ \rightarrow Am^{3+}$  can be calculated by converting the values of 0.86 and 2.62 volts into free energies, adding them, then converting back to give a potential of 1.74 volts. When this step is added to the diagram it becomes apparent that the potentials do not decrease from  $AmO_2^{2+}$  to  $AmO_2^+$  to  $Am^{3+}$ , and hence  $AmO_2^+$  is unstable with regard to disproportionation to  $AmO_2^{2+}$  and  $Am^{3+}$ . Finally, the potential for the couple  $AmO_2^{2+} \rightarrow Am^{3+}$  can be worked out to be +1.726 volts. Thus considering  $AmO_2^{2+} \rightarrow Am^{3+} \rightarrow Am$ ,  $Am^{3+}$  is stable:




## \* Disproportionates

It is important to include all the possible half reactions in a reduction potential diagram, or incorrect conclusions may be drawn. Examination of the incomplete diagram for chlorine in basic solution would indicate that  $\text{ClO}_2$  should disproportionate into  $\text{ClO}_3^-$  and  $\text{OCl}^-$ , and that  $\text{Cl}_2$  should disproportionate into  $\text{OCl}^-$  and  $\text{Cl}^-$ . Both of these deductions are correct.



## \* Disproportionates

The incomplete data also suggest that  $\text{OCl}^-$  should be stable with regard to disproportionation, but this is not true. The species which disproportionate are 'ignored', and a single potential calculated for the change  $\text{ClO}_3^- \rightarrow \text{OCl}^-$  to replace the values  $+0.33\text{ V}$  and  $+0.66\text{ V}$ . Similarly a single potential is calculated for  $\text{OCl}^- \rightarrow \text{Cl}^-$ .




## \* Disproportionates

When the complete diagram is examined, it is apparent that the potentials around  $\text{OCl}^-$  do not decrease from left to right, and hence  $\text{OCl}^-$  is unstable with respect to disproportionation into  $\text{ClO}_3^-$  and  $\text{Cl}^-$ .




In the same way, the potentials round  $\text{ClO}_3^-$  do not decrease from left to right




Similarly  $\text{ClO}_3^-$  should disproportionate into  $\text{ClO}_4^-$  and  $\text{OCl}^-$ , and  $\text{OCl}^-$  should disproportionate to give  $\text{Cl}^-$  and more  $\text{ClO}_3^-$ .

Reduction potential diagrams may also be used to predict the products of reactions in which the elements have several oxidation states. Consider for example the reaction between an acidified solution of  $\text{KMnO}_4$  and  $\text{KI}$ . The reduction potential diagrams are





\* Disproportionates


If we assume that the reactions are thermodynamically controlled, that is equilibrium is reached fairly quickly, then since  $\text{MnO}_4^{2-}$ ,  $\text{Mn}^{3+}$  and  $\text{HOI}$  disproportionate, they need not be considered. The half reaction  $\text{Mn}^{2+} \rightarrow \text{Mn}$  has a large negative  $E^\circ$  value, and hence  $\Delta G$  will have a large positive value, so this will not occur, and can be ignored. Thus the reduction potential diagrams may be simplified:




If the reaction is carried out by adding KI solution dropwise to an acidified solution of  $\text{KMnO}_4$ , the products of the reaction must be stable in the presence of  $\text{KMnO}_4$ . Thus  $\text{Mn}^{2+}$  cannot be formed, since  $\text{KMnO}_4$  would oxidize it to  $\text{MnO}_2$ . In a similar way,  $\text{I}_2$  cannot be formed, since  $\text{KMnO}_4$  would oxidize it. The fact that the half reaction potentials for  $\text{IO}_4^- \rightarrow \text{IO}_3^-$  and  $\text{H}_5\text{IO}_6 \rightarrow \text{IO}_3^-$  are close to the  $\text{MnO}_4^- \rightarrow \text{MnO}_2$  potential is a complication, and it is not obvious whether  $\text{IO}_3^-$ ,  $\text{IO}_4^-$  or  $\text{H}_5\text{IO}_6$  will be the product. In fact  $\text{I}^-$  is oxidized to a mixture of  $\text{IO}_3^-$  and  $\text{IO}_4^-$ .



If the reaction is carried out in a different way, by adding the  $\text{KMnO}_4$  dropwise to the KI solution, then the products formed must be stable in the presence of  $\text{I}^-$ . Thus  $\text{MnO}_2$  cannot be formed, since it would oxidize  $\text{I}^-$  to  $\text{I}_2$ . Similarly,  $\text{IO}_3^-$  cannot be formed since it would oxidize any excess  $\text{I}^-$  to  $\text{I}_2$ . The reaction which takes place is



Since there is an excess of  $I^-$  ions any  $I_2$  formed will dissolve as the triiodide ion  $I_3^-$  but this does not affect the reaction



Note that the products formed depend on which reactant is in excess

### THE OCCURRENCE AND ISOLATION OF THE ELEMENTS

The most abundant elements in the earth's crust (by weight) are shown in Table 6.13. It is worth noting that the first five elements comprise almost 92% by weight of the earth's crust, that the first ten make up over 99.5% and the first twenty make up 99.97%. Thus a few elements are very abundant but most of the elements are very scarce.

Table 6.13 The most abundant elements

	Parts per million of earth's crust	% of earth's crust
1 oxygen	455 000	45.5
2 silicon	272 000	27.2
3 aluminium	83 000	8.3
4 iron	62 000	6.2
5 calcium	46 000	4.66
6 magnesium	27 640	2.764
7 sodium	22 700	2.27
8 potassium	18 400	1.84
9 titanium	6 320	0.632
10 hydrogen	1 520	0.152
11 phosphorus	1 120	0.112
12 manganese	1 060	0.106

A full table of abundances is given in Appendix A.

Other very abundant elements are nitrogen (78% of the atmosphere) and hydrogen which occurs as water in the oceans. The chemistry of these abundant elements is well known but some elements which are rare are also well known because they occur in concentrated deposits – for example lead as  $PbS$  (galena) and boron as  $Na B_4O_7 \cdot 10H_2O$  (borax).

The different methods for separating and extracting elements may be divided into five classes (see Ives, D.J.G. in Further Reading).

#### Mechanical separation of elements that exist in the native form

A surprisingly large number of elements occur in the free elemental state. They have remained in the native form because they are unreactive. Only the least reactive of the metals – those of Group 11 (copper/silver/gold) and the platinum metals – occur in significant amounts as native elements.

- 1 Gold is found in the native form – as grains in quartz – as nuggets and in the silt of river beds. Gold has a density of  $19.3 \text{ g cm}^{-3}$  which is very



much higher than that of the rocks or silt it is mixed with, and gold can be separated by 'panning'. (In recent times it has been more commonly extracted by amalgamating with mercury.) Silver and copper are some times found in the native form as 'nuggets'. All three metals are noble or unreactive, and this is associated with their position in the electro-chemical series below hydrogen, and with the non-metals.

2. Palladium and platinum are also found as native metals. In addition natural alloys of the Pt group are found.

The platinum metals are      Ru   Rh   Pd  
   Os   Ir   Pt

The names of these natural alloys indicate their composition: osmidium, iridosmine.


3. Liquid droplets of mercury are found associated with cinnabar  $\text{HgS}$ . Non-metals which occur as native elements in the earth's crust are from the carbon and sulphur groups, but the atmosphere comprises  $\text{N}_2$ ,  $\text{O}_2$  and the noble gases.
4. Diamonds are found in the earth, and are obtained by mechanical separation of large amounts of earth and rock. The largest deposits are in Australia, Zaire, Botswana, the USSR and South Africa. Diamonds are mostly used for making cutting tools, and some for jewellery. Graphite is mined mainly in China, South Korea, the USSR, Brazil and Mexico. It is used for making electrodes, in steel making, as a lubricant, and in pencils, brake linings and brushes for electric motors. It is also used as the moderator in the cores of gas cooled nuclear reactors.
5. Deposits of sulphur are also found deep underground in Louisiana (USA), Poland, Mexico and the USSR. These are extracted by the *Frasch process*. Small amounts of selenium and tellurium are often present in sulphur.
6. The atmosphere is made up of about 78% nitrogen, 22% oxygen and traces of the noble gases argon, helium and neon. These may be separated by fractional distillation of liquid air. Helium is also obtained from some natural gas deposits.

### Thermal decomposition methods

A few compounds will decompose into their constituent elements simply by heating.

1. A number of hydrides will decompose in this way, but since hydrides are usually made from the metal itself, the process is of no commercial significance. The hydrides arsine  $\text{AsH}_3$  and stibine  $\text{SbH}_3$  are produced in Marsh's test, where an arsenic or antimony compound is converted to the hydride with  $\text{Zn}/\text{H}_2\text{SO}_4$  and the gaseous hydrides are decomposed to give a silvery mirror of metal by passing the hydride through a heated tube.
2. Sodium azide  $\text{NaN}_3$  decomposes to give sodium and pure dinitrogen on


*gentle heating* Considerable care is needed as azides are often explosive. This method is not used commercially, but it is useful for making small quantities of very pure dinitrogen in the laboratory







- 3 Nickel carbonyl  $\text{Ni}(\text{CO})_4$  is gaseous and may be produced by warming Ni with CO at  $50^\circ\text{C}$ . Any impurities in the Ni sample remain solid and the gas is heated to  $230^\circ\text{C}$ , when it decomposes to give pure metal and CO which is recycled. This was the basis of the *Mond process* for purifying nickel which was used in South Wales from 1899 until the 1960s. A new plant in Canada uses the same principle but uses  $150^\circ\text{C}$  and 20 atmospheres pressure to form  $\text{Ni}(\text{CO})_4$ .



- 4 The iodides are the least stable of the halides, and the *van Arkel de Boer process* has been used to purify small quantities of zirconium and boron. The impure element is heated with iodine, producing a volatile iodide  $\text{ZrI}_4$  or  $\text{BI}_3$ . These are decomposed by passing the gas over an electrically heated filament of tungsten or tantalum which is white hot. The element is deposited on the filament and the iodine is recycled. The filament grows fatter, and is eventually removed. The tungsten core is drilled out of the centre, and a small amount of high purity Zr or B is obtained.
- 5 Most oxides are thermally stable at temperatures up to  $1000^\circ\text{C}$  but the metals below hydrogen in the electrochemical series decompose fairly easily. Thus  $\text{HgO}$  and  $\text{Ag}_2\text{O}$  decompose on heating. The mineral cinnabar  $\text{HgS}$  is roasted in air to give the oxide, which then decomposes on heating. Silver residues from the laboratory and photographic processing are collected as  $\text{AgCl}$  and treated with  $\text{Na}_2\text{CO}_3$ , giving  $\text{Ag}_2\text{CO}_3$ , which decomposes on heating, first to  $\text{Ag}_2\text{O}$  and then to Ag.



- 6 Dioxygen may be produced by heating hydrogen peroxide  $\text{H}_2\text{O}_2$ , barium peroxide  $\text{BaO}_2$ , silver oxide  $\text{Ag}_2\text{O}$  or potassium chlorate  $\text{KClO}_3$ .




#### Displacement of one element by another


In principle any element may be displaced from solution by another element which is higher in the electrochemical series. The method is in

applicable to elements which react with water, and to be economic must involve sacrificing a cheap element to obtain a more expensive element.


1. Copper ores which are too lean in CuS for the Cu to be extracted by roasting in air are left to be weathered by air and rain to form a solution of  $\text{CuSO}_4$ . The  $\text{Cu}^{2+}$  ions are displaced as Cu metal by sacrificing scrap iron which turns into  $\text{Fe}^{2+}$  because iron is above copper in the electrochemical series.



2. Cadmium occurs in small amounts with zinc ores. The Zn is recovered by electrolysing a solution of  $\text{ZnSO}_4$  which contains traces of  $\text{CdSO}_4$ . After a time the amount of  $\text{Cd}^{2+}$  has concentrated, and since Zn is above Cd in the electrochemical series some Zn metal is sacrificed to displace the  $\text{Cd}^{2+}$  from solution as Cd metal. The Zn which was sacrificed is subsequently recovered by electrolysis.








3. Sea water contains  $\text{Br}^-$  ions. Chlorine is above bromine in the electrochemical series, and bromine is obtained by passing chlorine into sea water.



### High temperature chemical reduction methods



A large number of commercial processes come into this group. Carbon can be used to reduce a number of oxides and other compounds, and because of the low cost and availability of coke this method is widely used. The disadvantages are that a high temperature is needed, which is expensive and necessitates the use of a blast furnace, and many metals combine with carbon, forming carbides. Some examples are:

#### *Reduction by carbon*





*Reduction by another metal*





If the temperature needed for carbon to reduce an oxide is too high for economic or practical purposes, the reduction may be effected by another highly electropositive metal such as aluminium, which liberates a large amount of energy ( $1675 \text{ kJ mol}^{-1}$ ) on oxidation to  $\text{Al}_2\text{O}_3$ . This is the basis of the *Thermite process*



Magnesium is used in a similar way to reduce oxides. In certain cases where the oxide is too stable to reduce, electropositive metals are used to reduce halides

*Self reduction*

A number of metals occur as sulphide ores (for example  $\text{PbS}$ ,  $\text{CuS}$  and  $\text{Sb}_2\text{S}_3$ ) which may be roasted first in air to partially convert them to the oxide and then further roasted in the absence of air, causing self reduction

*Reduction of oxides with hydrogen*

This method is not widely used, because many metals react with hydrogen at elevated temperatures, forming hydrides. There is also a risk of explosion from hydrogen and dioxygen in the air.

*Electrolytic reduction*

The strongest possible reducing agent is an electron. Any ionic material may be electrolysed and reduction occurs at the cathode. This is an excellent method, and gives very pure products but electricity is expensive. Electrolysis may be performed

*In aqueous solution*

Provided that the products do not react with water, electrolysis can be carried out conveniently and cheaply in aqueous solution. Copper and zinc are obtained by electrolysis of aqueous solutions of their sulphates.

*In other solvents*

Electrolysis can be carried out in solvents other than water. Fluorine reacts violently with water, and it is produced by electrolysis of  $\text{KHF}_2$  dissolved in anhydrous HF. (The reaction has many technical difficulties in that HF is corrosive, the hydrogen produced at the cathode must be kept separate from the fluorine produced at the anode or an explosion will occur, water must be rigorously excluded, and the fluorine produced attacks the anode and the reaction vessel.)

*In fused melts*

Elements that react with water are often extracted from fused melts of their ionic salts. These melts are frequently corrosive, and involve large fuel bills to maintain the high temperatures required. Aluminium is obtained by electrolysis of a fused mixture of  $\text{Al}_2\text{O}_3$  and cryolite  $\text{Na}_3[\text{AlF}_6]$ . Both sodium and chlorine are obtained from the electrolysis of fused  $\text{NaCl}$ : in this case up to two thirds by weight of  $\text{CaCl}_2$  is added as an impurity to lower the melting point from  $803^\circ\text{C}$  to  $505^\circ\text{C}$ .

**Factors influencing the choice of extraction process**

The type of process used commercially for any particular element depends on a number of factors.

1. Is the element unreactive enough to exist in the free state?
2. Are any of its compounds unstable to heat?
3. Does the element exist as an ionic compound, and is the element stable in water? If both are true, is there a cheap element above it in the electrochemical series which can be sacrificed to displace it from solution?
4. Does the element occur as sulphide ores which can be roasted, or oxide ores which can be reduced – using carbon is the cheapest whilst the use of Mg, Al and Na as reducing agents is more expensive.
5. If all other methods fail, electrolysis usually works for ionic materials, but is expensive. If the element is stable in water, electrolysis of aqueous solutions is cheaper than using fused melts.

**Thermodynamics of reduction processes**

The extraction of metals from their oxides using carbon or other metals, and by thermal decomposition, involves a number of points which merit detailed discussion.


Table 6 14 Reduction potentials and extraction methods

Element	$E^\circ$ (V)	Materials	Extraction method
Lithium	$\text{Li}^+   \text{Li}$ -3.05	$\text{LiCl}$	Electrolysis of fused salts, usually chlorides
Potassium	$\text{K}^+   \text{K}$ -2.93	$\text{KCl}, [\text{KCl} \cdot \text{MgCl}_2 \cdot 6\text{H}_2\text{O}]$	
Calcium	$\text{Ca}^{2+}   \text{Ca}$ -2.84	$\text{CaCl}_2$	
Sodium	$\text{Na}^+   \text{Na}$ -2.71	$\text{NaCl}$	
Magnesium	$\text{Mg}^{2+}   \text{Mg}$ -2.37	$\text{MgCl}_2$ $\text{MgO}$	Electrolysis of $\text{MgCl}_2$ High temperature reduction with C
Aluminium	$\text{Al}^{3+}   \text{Al}$ -1.66	$\text{Al}_2\text{O}_3$	Electrolysis of $\text{Al}_2\text{O}_3$ dissolved in molten $\text{Na}_3[\text{AlF}_6]$
Manganese	$\text{Mn}^{2+}   \text{Mn}$ -1.08	$\text{Mn}_2\text{O}_3$ $\text{MnO}_2$	Reduction with Al Thermite process
Chromium	$\text{Cr}^{3+}   \text{Cr}$ -0.74	$\text{FeCr}_2\text{O}_4$	
Zinc	$\text{Zn}^{2+}   \text{Zn}$ -0.76	$\text{ZnS}$	Chemical reduction of oxides by C Sulphides are converted to oxides then reduced by C or sometimes $\text{H}_2$
Iron	$\text{Fe}^{2+}   \text{Fe}$ -0.44	$\text{Fe}_2\text{O}_3$ $\text{Fe}_3\text{O}_4$	
Cobalt	$\text{Co}^{2+}   \text{Co}$ -0.27	$\text{CoS}$	
Nickel	$\text{Ni}^{2+}   \text{Ni}$ -0.23	$\text{NiS}$ , $\text{NiAs}_2$	
Tin	$\text{Sn}^{2+}   \text{Sn}$ -0.14	$\text{SnO}_2$	
Lead	$\text{Pb}^{2+}   \text{Pb}$ -0.13	$\text{PbS}$	
Copper	$\text{Cu}^{2+}   \text{Cu}$ +0.35	$\text{Cu}(\text{metal})$ $\text{CuS}$	Found as native metal, or compounds easily decomposed by heat (Also cyanide extraction)
Silver	$\text{Ag}^+   \text{Ag}$ +0.80	$\text{Ag}(\text{metal})$ , $\text{Ag}_2\text{S}$ , $\text{AgCl}$	
Mercury	$\text{Hg}^{2+}   \text{Hg}$ +0.85	$\text{HgS}$	
Gold	$\text{Au}^{3+}   \text{Au}$ +1.38	$\text{Au}(\text{metal})$	

For a spontaneous reaction, the free energy change  $\Delta G$  must be negative

$$\Delta G = \Delta H - T\Delta S$$

$\Delta H$  is the enthalpy change during the reaction,  $T$  is the absolute temperature, and  $\Delta S$  is the change in entropy during the reaction. Consider a reaction such as the formation of an oxide



Dioxygen is used up in the course of this reaction. Gases have a more random structure (less ordered) than liquids or solids. Consequently gases have a higher entropy than liquids or solids. In this reaction  $S$  the entropy or randomness decreases, and hence  $\Delta S$  is negative. Thus if the temperature is raised then  $T\Delta S$  becomes more negative. Since  $T\Delta S$  is subtracted in the equation, then  $\Delta G$  becomes less negative. Thus the free energy change increases with an increase of temperature.

The free energy changes that occur when one gram molecule of a




Figure 6.5 Ellingham diagram showing the change in free energy  $\Delta G$  with temperature for oxides (based on 1 g mol of dioxygen in each case).

common reactant (in this case dioxygen) is used may be plotted graphically against temperature for a number of reactions of metals to their oxides. This graph is shown in Figure 6.5 and is called an Ellingham diagram (for oxides). Similar diagrams can be produced for one gram molecule of sulphur, giving an Ellingham diagram for sulphides, and similarly for halides.

The Ellingham diagram for oxides shows several important features:



1. The graphs for metal to metal oxide all slope upwards, because the free energy change increases with an increase of temperature as discussed above.
2. The free energy changes all follow a straight line unless the materials melt or vaporize, when there is a large change in entropy associated with the change of state, which changes the slope of the line (for example the Hg–HgO line changes slope at 356 °C when Hg boils, and similarly Mg–MgO changes at 1120 °C).

- 3 When the temperature is raised a point will be reached where the graph crosses the  $\Delta G = 0$  line. Below this temperature the free energy of formation of the oxide is negative, so the oxide is stable. Above this temperature the free energy of formation of the oxide is positive and the oxide becomes unstable, and should decompose into the metal and dioxygen.

Theoretically all oxides can be decomposed to give the metal and dioxygen if a sufficiently high temperature can be attained. In practice the oxides of Ag, Au and Hg are the only oxides which can be decomposed at temperatures which are easily attainable, and these metals can therefore be extracted by thermal decomposition of their oxides.

- 4 In a number of processes, one metal is used to reduce the oxide of another metal. Any metal will reduce the oxide of other metals which lie above it in the Ellingham diagram because the free energy will become more negative by an amount equal to the difference between the two graphs at that particular temperature. Thus Al reduces FeO, CrO and NiO in the well known Thermite reaction, but Al will not reduce MgO at temperatures below  $1500^{\circ}\text{C}$ .

In the case of carbon reacting with dioxygen two reactions are possible



In the first reaction, the volume of  $\text{CO}_2$  produced is the same as the volume of  $\text{O}_2$  used, so the change in entropy is very small and  $\Delta G$  hardly changes with temperature. Thus the graph of  $\Delta G$  against  $T$  is almost horizontal.





Figure 6.6 Ellingham diagram for carbon. (The composite curve is the solid line.)




The second reaction produces two volumes of CO for every one volume of dioxygen used. Thus  $\Delta S$  is positive, and hence  $\Delta G$  becomes increasingly negative as  $T$  increases. Consequently the line on the Ellingham diagram slopes downwards (Figure 6.6). The two lines for  $C \rightarrow CO_2$  and  $C \rightarrow CO$  cross at about  $710^\circ C$ . Below this temperature the reaction to form  $CO_2$  is energetically more favourable, but above  $710^\circ C$  the formation of CO is preferred.

Carbon is extensively used to reduce iron oxide in the extraction of iron, but it may also be used to reduce any other of the oxides above it on the Ellingham diagram. Since the  $\Delta G$  line slopes downwards it will eventually cross and lie below all the other graphs for metal/metal oxide. Thus in principle carbon could be used to reduce any metal oxide if a sufficiently high temperature were used. At one time MgO was reduced by C at  $2000^\circ C$ , followed by shock (i.e. rapid) cooling, though this process is now obsolete. Similarly the reduction of very stable oxides like  $TiO_2$ ,  $Al_2O_3$  and MgO is theoretically possible, but is not attempted because of the high cost and practical difficulties of using extremely high temperatures. A further limitation on the use of carbon for extracting metals is that at high temperatures many metals react with carbon, forming carbides.

Many metals occur as sulphide ores. Though carbon is a good reducing agent for oxides, it is a poor reducing agent for sulphides. The reason why carbon reduces so many oxides at elevated temperatures is that the  $\Delta G^\circ/T$  line for CO has a negative slope. There is no compound CS analogous to CO with a steep negative  $\Delta G^\circ/T$  line. Thus sulphides are normally roasted in air to form oxides before reducing with carbon.



In a similar way hydrogen is of limited use as a reducing agent for extracting metals from their oxides since the  $\Delta G^\circ/T$  line has a positive slope, and runs parallel to many metal oxide lines.



Thus only those metals with metal  $\rightarrow$  metal oxide lines above the hydrogen line will be reduced, and this does not change with temperature. A further problem with  $H_2$  is that many metals react with hydrogen, forming hydrides, and if hydrogen remains dissolved in the metal (interstitial hydrides) it significantly affects the properties of the metal.

Thermodynamic arguments about what will reduce a given compound have two limitations. They assume that the reactants and products are in equilibrium, which is often untrue, and they indicate whether a reaction is possible but do not predict the rate of reaction, or if some alternative reaction is even more favourable.

Further details of extraction processes and Ellingham diagrams for halides and sulphides are given in Further Reading (see Ives D.J.G., and Ellingham, H.J.T.).

**Table 6 IS** Extraction methods and the periodic table

[illegible]

## Notes

- 1 Al F and Cl are obtained by electrolysis of solutions
- 2 Br is obtained by displacement
- 3 I is obtained by reduction
- 4 Te does not occur in nature


## HORIZONTAL, VERTICAL AND DIAGONAL RELATIONSHIPS IN THE PERIODIC TABLE

On moving across a period in the periodic table, the number of electrons in the outer shell increases from one to eight. Thus Group 1 elements all have one electron in their outer shell. When they react they are univalent, because the loss of one electron leaves a noble gas structure. Similarly Group 2 elements have two electrons in their outer shell and are divalent. The valency of an *s*-block element is the group number. For *p*-block elements, the valency is normally (the group number  $- 10$ ) or  $(18 - \text{the group number})$ . This is the same as the number of *s* and *p* electrons in the outer shell, or  $(8 - \text{this number of electrons})$ . Group 15 elements (e.g. nitrogen) have five outer electrons. If three of these are shared in covalent bonds with other atoms, the nitrogen atom has a share in eight electrons and has a stable configuration. Thus nitrogen is trivalent, for example in ammonia  $\text{NH}_3$ . The halogens are in Group 17 and have seven outer electrons. The valency should be  $18 - 17 = 1$ . A stable structure is attained by gaining one electron either by forming an ionic or a covalent bond. The number of outer electrons thus determines the valency of the element.

On moving from left to right across a period, the size of the atoms decreases because of the additional nuclear charge. Thus the orbital electrons are more tightly held, and the ionization energy increases. The metallic character of the element also decreases, and the oxides of the elements become less basic. Thus  $\text{Na}_2\text{O}$  is strongly basic;  $\text{Al}_2\text{O}_3$  is amphoteric and reacts with both acids and bases;  $\text{SO}_2$  is an acidic oxide since it dissolves in water to form sulphurous acid ( $\text{H}_2\text{SO}_3$ ) and reacts with bases to form sulphites. Generally, metallic oxides are basic, whilst non-metallic oxides are acidic.

On descending a group in the periodic table, the elements all have the same number of outer electrons and the same valency, but the size increases. Thus the ionization energy decreases and the metallic character increases. This is particularly apparent in Groups 14 and 15, which begin with the non-metals carbon and nitrogen and end with the metals lead and bismuth. The oxides become increasingly basic on descending the group.

On moving diagonally across the periodic table the elements show certain similarities. These are usually weaker than the similarities within a group, but are quite pronounced in the following pairs of elements:



On moving across a period, the charge on the ions increases and the size decreases, causing the polarizing power to increase. On moving down a group, the size increases and the polarizing power decreases. On moving diagonally these two effects partly cancel each other, so that there is no marked change in properties. The type and strength of bond formed and

the properties of the compounds are often similar, although the valency is different. Thus lithium is similar to magnesium in many of its properties and beryllium is similar to aluminium. These similarities are examined in more detail in the chapters on Groups 1, 2 and 13. Diagonal similarities are most important among the lighter elements, but the line separating the metals from the non metals also runs diagonally.

### FURTHER READING

Size, ionization energy, electron affinity, energetics and Born–Haber cycle, electronegativity

- Allred A L and Rochow E G (1958) *J Inorg Nucl Chem* **5** 264 (Original paper on Allred and Rochow scale of electronegativity values )
- Allred A L (1961) *J Inorg Nucl Chem* **17** 215 (More on electronegativity values )
- Ashcroft S J and Beech G (1973) *Inorganic Thermodynamics* Van Nostrand
- Bratsch S G (1988) Revised Mulliken electronegativities *J Chem Ed* Part I **65** 34–41, Part II **65** 223–226
- Blustin P H and Raynes W T (1981) An electronegativity scale based on geometry changes on ionization *J Chem Soc (Dalton)* 1237
- Emeleus H J and Sharpe A G (1973) *Modern Aspects of Inorganic Chemistry* 4th ed (Chapter 5 Structures and energetics of inorganic molecules Chapter 6 Inorganic chemistry in aqueous media) Routledge and Kegan Paul London
- Huheey J E (1972) *Inorganic Chemistry* Harper and Row New York (Discussion on electronegativity )
- Lieberman J F (1973) Ionization enthalpies and electron attachment enthalpies *J Chem Ed* **50** 831
- Mulliken R S (1934 1935) *J Chem Phys* **2** 782 **3** 573 (Mulliken electronegativity scale )
- Pauling L (1960) *The Nature of the Chemical Bond* 3rd ed Oxford University Press London (An old but classic text )
- Sanderson R T (1945) A scale of electronegativity *J Chem Ed* **31** 2 (Original paper on Sanderson electronegativity scale )
- Sanderson R T (1986) The Inert Pair Effect and Electronegativity *Inorganic Chemistry* **25** 1856–1858
- Sanderson R T (1988) Principles of electronegativity *J Chem Ed* Part I **65** 112–118 Part II **65** 227–231
- Shannon R D (1976) Revised effective ionic radii *Acta Cryst* **A32** 751–767 (The most recent and widely accepted values for ionic radii )
- Sharpe A G (1981) *Inorganic Chemistry* (Chapter 3 Electronic configurations and some physical properties of atoms ) Longmans London
- Zhang Y (1982) Electronegativities of elements in valence states *Inorganic Chemistry* **21** 3886–3889

### Standard electrode potentials, redox reactions

- Baes C F and Mesmer R E (1976) *The Hydrolysis of Cations* Wiley Interscience London 1976 (Comprehensive but understandable )
- Bard A J Parsons R and Jordan J (1985) *Standard Potentials in Aqueous Solution* (Monographs in Electroanalytical Chemistry and Electrochemistry Series Vol 6) Marcel Dekker New York (Commissioned by IUPAC to replace the earlier values in Latimer's book )
- Burgess J (1988) *Ions in Solution* Ellis Horwood Chichester
- Fromhold A T Jr (1980) *Theory of Metal Oxidation* North Holland Publishing Co Amsterdam and Oxford

- Jolly, W.L. (1976) *Inorganic Chemistry*, McGraw Hill, New York. (Redox reactions, and aqueous solutions.)
- Johnson, D.A. (1968) *Some Thermodynamic Aspects of Inorganic Chemistry*, Cambridge University Press, Cambridge. (Lattice energies etc.)
- Latimer, W.M. (1952) *The Oxidation States of the Elements and Their Potentials in Aqueous Solution*, 2nd ed., Prentice Hall, New York. (Old, but until very recently the standard source of oxidation potential data.)
- Rosotti, H. (1978) *The Study of Ionic Equilibria in Aqueous Solution*, Longmans, London. (Redox reactions, solubility.)
- Sanderson, R.T. (1966) The significance of electrode potentials, *J. Chem. Ed.*, **43**, 584–586.
- Sharpe, A.G. (1969) *Principles of Oxidation and Reduction* (Royal Institute of Chemistry Monographs for Teachers No. 2), London.
- Sharpe A.G. (1981) *Inorganic Chemistry*, (Chapter 7: Inorganic chemistry in aqueous media), Longmans, London.
- Vincent, A. (1985) *Oxidation and Reduction in Inorganic and Analytical Chemistry: A Programmed Introduction*, John Wiley, Chichester.

### Abundance and extraction of the elements

- Cox, P.A. (1989) *The Elements: Their origins, Abundance and Distribution*, Oxford University Press, Oxford.
- Ellingham, H.J.T. (1944, 1948) *J. Soc. Chem. Ind. Lond.*, **63**, 125; *Disc. Faraday Soc.*, **4**, 126, 161. (Original paper on Ellingham diagrams.)
- Fergusson, J.E. (1982) *Inorganic Chemistry and the Earth: Chemical Resources, Their Extraction, Use and Environmental Impact* (Pergamon Series on Environmental Science, Vol. 6), Pergamon Press, Oxford.
- Ives, D.J.G. (1969) *Principles of the Extraction of Metals* (Royal Institute of Chemistry Monographs for Teachers No. 3), London.
- Jeffes, J.H.E. (1969) Extraction Metallurgy, *Chemistry in Britain*, **5**, 189–192.

### PROBLEMS

- How does the size of atoms vary from left to right in a period, and on descending a group in the periodic table? What are the reasons for these changes?
  - Can you explain the large atomic radii of the noble gases?
  - Why is the decrease in size between Li and Be much greater than that between Na and Mg or K and Ca?
- Explain what is meant by the ionization energy of an element. How does this vary between hydrogen and neon in the periodic table? Discuss how the variation can be related to the electronic structure of the atoms.
- What is the correlation between atomic size and ionization energy?
  - Account for the fact that there is a decrease in first ionization energy from Be to B, and Mg to Al.
  - Suggest the reason for the decrease in first ionization energy from N to O, and P to S.
  - Explain why the substantial decrease in first ionization energy

- observed between Na and K, and Mg and Ca, is not observed between A and Ga
- (e) What is the significance of the large increase in the third ionization energy of Ca and the fifth ionization energy of Si?
  - (f) Why is the first ionization energy of the transition elements reasonably constant?
- 4 (a) What is electronegativity, and how is it related to the type of bond formed?
  - (b) What are Fajans' rules?
  - (c) Predict the type of bonds formed in HCl, CsCl,  $\text{NH}_3$ ,  $\text{CS}_2$  and  $\text{GeBr}_4$
  - 5 (a) List the different scales of electronegativity and briefly describe the theoretical basis behind each
  - (b) Give four examples to show how electronegativity values may be used to predict the type of bond formed in a compound
  - 6 Use a modified Born-Haber cycle suitable for the estimation of electrode potentials to explain
    - (a) Why Li is as strong a reducing agent as Cs
    - (b) Why Ag is a noble metal and K a highly reactive metal
  - 7 (a) What are the standard electrode potentials, and how are they related to the electrochemical series?
  - (b) Explain the recovery of copper from solution using scrap iron
  - (c) How is it possible to preferentially deposit metals electrolytically, e.g. Cu, Ni, and Zn from a solution containing all three?
  - (d) Why is it possible to obtain zinc by electrolysis of an aqueous solution even though the electrode potentials would suggest that the water should decompose first?
  - 8 (a) Explain why  $\text{Cu}^+$  disproportionates in solution
  - (b) Explain why the standard reduction potentials for  $\text{Cu}^{2+} \rightarrow \text{Cu}^+$  and  $\text{Cu}^+ \rightarrow \text{Cu}$  are +0.15 and +0.50 volt, respectively, yet that for  $\text{Cu}^{2+} \rightarrow \text{Cu}$  is +0.34 volt
  - 9 Name the eight most abundant elements in the earth's crust and place them in the correct order
  - 10 Describe the following named metallurgical processes (a) Bessemer, (b) BOP, (c) Kroll, (d) Van Arkel, (e) Hall-Hérault, (f) Parkes
  - 11 Which elements occur in the native state?
  - 12 List five ores which are smelted, and give equations to show what occurs during smelting
  - 13 Describe the extraction of three different elements using carbon as the reducing agent
  - 14 Draw an Ellingham diagram for metal oxides and explain what information can be obtained from it. In addition explain why most of





the lines slope upwards from left to right, why the lines change in slope, and what happens when a line crosses the  $\Delta G = 0$  axis..

15. Use the Ellingham diagram for oxides to find:
  - (a) if Al will reduce chromium oxide
  - (b) at what temperature C will reduce magnesium oxide, and
  - (c) at what temperature mercuric oxide will decompose into its elements.
16. Explain in detail the processes involved in the production of pig iron and steel.
17. Describe the extraction of two metals and two non-metals by electrolysis.
18. Describe the extraction of magnesium and bromine from sea water.

# Coordination compounds

## DOUBLE SALTS AND COORDINATION COMPOUNDS

Addition compounds are formed when stoichiometric amounts of two or more stable compounds join together. For example



Addition compounds are of two types

- 1 Those which lose their identity in solution (double salts)
- 2 Those which retain their identity in solution (complexes)

When crystals of carnallite are dissolved in water, the solution shows the properties of  $\text{K}^+$ ,  $\text{Mg}^{2+}$  and  $\text{Cl}^-$  ions. In a similar way, a solution of potassium alum shows the properties of  $\text{K}^+$ ,  $\text{Al}^{3+}$  and  $\text{SO}_4^{2-}$  ions. These are both examples of double salts which exist only in the crystalline state.

When the other two examples of coordination compounds dissolve they do not form simple ions –  $\text{Cu}^{2+}$ , or  $\text{Fe}^{2+}$  and  $\text{CN}^-$  – but instead their complex ions remain intact. Thus the cuproammonium ion  $[\text{Cu}(\text{H}_2\text{O})_6(\text{NH}_3)_4]^{2+}$  and the ferrocyanide ion  $[\text{Fe}(\text{CN})_6]^{4-}$  exist as distinct entities both in the solid and in solution. Complex ions are shown by the use of square brackets. Compounds containing these ions are called coordination compounds. The chemistry of metal ions in solution is essentially the chemistry of their complexes. Transition metal ions, in particular, form many stable complexes. In solution 'free' metal ions are coordinated either to water or to other ligands. Thus  $\text{Cu}^{2+}$  exists as the pale blue complex ion  $[\text{Cu}(\text{H}_2\text{O})_6]^{2+}$  in aqueous solution (and also in hydrated



crystalline salts). If aqueous ammonia is added to this solution, the familiar deep blue cuproammonium ion is formed:



Note that this reaction is a substitution reaction, and the  $\text{NH}_3$  replaces water in the complex ion.

## WERNER'S WORK

Werner's coordination theory in 1893 was the first attempt to explain the bonding in coordination complexes. It must be remembered that this imaginative theory was put forward before the electron had been discovered by J.J. Thompson in 1896, and before the electronic theory of valency. This theory and his painstaking work over the next 20 years won Alfred Werner the Nobel Prize for Chemistry in 1913.


Complexes must have been a complete mystery without any knowledge of bonding or structure. For example, why does a stable salt like  $\text{CoCl}_3$  react with a varying number of stable molecules of a compound such as  $\text{NH}_3$  to give several new compounds:  $\text{CoCl}_3 \cdot 6\text{NH}_3$ ,  $\text{CoCl}_3 \cdot 5\text{NH}_3$  and  $\text{CoCl}_3 \cdot 4\text{NH}_3$ ? What are their structures? At that time X-ray diffraction, which is the most powerful method of determining the structures of crystals, had yet to be discovered. Werner did not have at his disposal any of the modern instrumental techniques, and all his studies were made using simple reaction chemistry. *Werner was able to explain the nature of bonding in complexes, and he concluded that in complexes the metal shows two different sorts of valency:*

1. *Primary valencies.* These are non-directional. The modern explanation would be as follows. The complex commonly exists as a positive ion. The primary valency is the number of charges on the complex ion. In compounds, this charge is matched by the same number of charges from negative ions. Primary valency applies equally well to simple salts and to complexes. Thus in  $\text{CoCl}_2$  ( $\text{Co}^{2+} + 2\text{Cl}^-$ ) there are two primary valencies, i.e. two ionic bonds. The complex  $[\text{Co}(\text{NH}_3)_6]\text{Cl}_3$  actually exists as  $[\text{Co}(\text{NH}_3)_6]^{3+}$  and  $3\text{Cl}^-$ . Thus the primary valency is 3, as there are three ionic bonds.
2. *Secondary valencies.* These are directional. In modern terms the number of secondary valencies equals the number of ligand atoms coordinated to the metal. This is now called the coordination number. Ligands are commonly negative ions such as  $\text{Cl}^-$ , or neutral molecules such as  $\text{NH}_3$ . Less commonly, ligands may be positive ions such as  $\text{NO}^+$ . Each metal has a characteristic number of secondary valencies. Thus in  $[\text{Co}(\text{NH}_3)_6]\text{Cl}_3$  the three  $\text{Cl}^-$  are held by primary valencies. The six  $\text{NH}_3$  groups are held by secondary valencies.

Secondary valencies are directional, and so a complex ion has a particular shape, e.g. the complex ion  $[\text{Co}(\text{NH}_3)_6]^{3+}$  is octahedral. Werner deduced the shapes of many complexes. He did this by preparing as many

different isomeric complexes of a system as was possible. He noted the number of isomers formed and related this number to the number of isomers predicted for different geometric shapes. The most common coordination number in transition metal complexes is 6, and the shape is usually octahedral. The coordination number 4 is also common, and this gives rise to either tetrahedral or square planar complexes.

Werner treated cold solutions of a series of coordination complexes with an excess of silver nitrate, and weighed the silver chloride precipitated. The stoichiometries of complex-AgCl formed were as follows:



Werner deduced that in  $\text{CoCl}_3 \cdot 6\text{NH}_3$  the three chlorines acted as primary valencies and the six ammonias as secondary valencies. In modern terms the complex is written  $[\text{Co}(\text{NH}_3)_6]\text{Cl}_3$ . The three  $\text{Cl}^-$  are ionic and hence are precipitated as AgCl by  $\text{AgNO}_3$ . The six  $\text{NH}_3$  ligands form coordinate bonds to  $\text{Co}^{3+}$  forming a complex ion  $[\text{Co}(\text{NH}_3)_6]^{3+}$  (Figure 7 1a).

Werner deduced that loss of one  $\text{NH}_3$  from  $\text{CoCl}_3 \cdot 6\text{NH}_3$  should give  $\text{CoCl}_3 \cdot 5\text{NH}_3$  and at the same time one Cl changed from being a primary valency to a secondary valency. Thus this complex had two primary valencies and six secondary valencies. In modern terms the complex  $[\text{Co}(\text{NH}_3)_5\text{Cl}]\text{Cl}_2$  ionizes to give  $[\text{Co}(\text{NH}_3)_5\text{Cl}]^{2+}$  and two  $\text{Cl}^-$  ions. Thus only two of the three chlorine atoms are ionic and thus only two are precipitated as AgCl with  $\text{AgNO}_3$ . Five  $\text{NH}_3$  and one Cl form coordinate bonds to  $\text{Co}^{3+}$ , forming a complex ion (Figure 7 1b).

Similarly in  $\text{CoCl}_3 \cdot 4\text{NH}_3$  Werner deduced that one Cl formed a primary valency, and that there were six secondary valencies (two Cl and four  $\text{NH}_3$ ). In modern terms the complex  $[\text{Co}(\text{NH}_3)_4\text{Cl}_2]\text{Cl}$  ionizes to give  $[\text{Co}(\text{NH}_3)_4\text{Cl}_2]^+$  and  $\text{Cl}^-$  and so only one  $\text{Cl}^-$  can be precipitated as AgCl. The coordination number of  $\text{Co}^{3+}$  is 6, in this case four  $\text{NH}_3$  and two  $\text{Cl}^-$  form coordinate bonds to  $\text{Co}^{3+}$ . The old and modern ways of writing the formulae of these complexes are shown in Table 7 1.

Thus Werner established that the number of secondary valencies (that is the coordination number) was 6 in these complexes. He then attempted to




Figure 7 1 Structures of (a)  $[\text{Co}(\text{NH}_3)_6]\text{Cl}_3$  and (b)  $[\text{Co}(\text{NH}_3)_5\text{Cl}]\text{Cl}_2$

Table 7.1 Formulae of some cobalt complexes


Old	New
$\text{CoCl}_3 \cdot 6\text{NH}_3$	$[\text{Co}(\text{NH}_3)_6]^{3+} \quad 3\text{Cl}^-$
$\text{CoCl}_3 \cdot 5\text{NH}_3$	$[\text{Co}(\text{NH}_3)_5\text{Cl}]^{2+} \quad 2\text{Cl}^-$
$\text{CoCl}_3 \cdot 4\text{NH}_3$	$[\text{Co}(\text{NH}_3)_4\text{Cl}_2]^+ \quad \text{Cl}^-$

find the shapes of the complexes. The possible arrangements of six groups round one atom are a planar hexagon, a trigonal prism, and an octahedron (Figure 7.2). Werner then compared the number of isomeric forms he had obtained with the theoretical number for each of the possible shapes (Table 7.2).


Table 7.2 Number of isomers predicted and actually found

Complex	Observed	Predicted		
		Octahedral	Planar hexagon	Trigonal prism
$[\text{MX}_6]$	1	1	1	1
$[\text{MX}_5\text{Y}]$	1	1	1	1
$[\text{MX}_4\text{Y}_2]$	2	2	3	3
$[\text{MX}_3\text{Y}_3]$	2	2	3	3


These results strongly suggested that these complexes have an octahedral shape. This proof was not absolute proof, as it was just possible that the correct experimental conditions had not been found for preparing all the isomers. More recently the X-ray structures have been determined, and these establish that the shape is octahedral (Figure 7.3).



Planar hexagon



Trigonal prism



Octahedron

Figure 7.2 Possible geometric shapes for six-coordination.




Figure 7.3 Isomers in octahedral complexes.

More recently, with a bidentate ligand such as ethylenediamine (1,2 diaminoethane), two optically active isomers have been found (Figure 7.4)




Figure 7.4 Optical isomerism in octahedral complexes




Figure 7.5 Isomerism in square planar complexes

In a similar way, Werner studied a range of complexes which included  $[\text{Pt}^{\text{II}}(\text{NH}_3)_2\text{Cl}_2]$  and  $[\text{Pd}^{\text{II}}(\text{NH}_3)_2\text{Cl}_2]$ . The coordination number is 4, and the shape could be either tetrahedral or square planar. Werner was able to prepare two different isomers for these complexes. A tetrahedral complex can only exist in one form, but a square planar complex can exist in two isomeric forms. This proved these complexes are square planar rather than tetrahedral (Figure 7.5).

### MORE RECENT METHODS OF STUDYING COMPLEXES

The electrical conductivity of a solution of an ionic material depends on

- 1 The concentration of solute
- 2 The number of charges on the species which are formed on dissolution

Molar conductivities relate to a 1 M solution and thus the concentration factor is removed. The total number of charges on the species formed when the complex dissolves can be deduced by comparison of its molar conductivity with that of known simple ionic materials (Table 7.3). These conductivities suggest the same structures for the cobalt/ammonia/chlorine

Table 7.3 Conductivities of salts and complexes (molar conductivities measured at 0.001 M concentration)


			$\text{ohm}^{-1} \text{cm}^2 \text{mol}^{-1}$
$\text{LiCl}$	$\rightarrow \text{Li}^+ \text{Cl}^-$	(total of 2 charges)	112.0
$\text{CaCl}_2$	$\rightarrow \text{Ca}^{2+} 2\text{Cl}^-$	(total of 4 charges)	260.8
$\text{CoCl}_3 \cdot 5\text{NH}_3$			261.3
$\text{CoBr}_3 \cdot 5\text{NH}_3$			257.6
$\text{LaCl}_3$	$\rightarrow \text{La}^{3+} 3\text{Cl}^-$	(total of 6 charges)	393.5
$\text{CoCl}_3 \cdot 6\text{NH}_3$			431.6
$\text{CoBr}_3 \cdot 6\text{NH}_3$			426.9

Table 7.4 Number of charges related to modern and Werner structures

	Charges	Primary valency ionizable chlorines	Secondary valency
$[\text{Co}(\text{NH}_3)_6]^{3+} \quad 3\text{Cl}^-$	6	3	$6\text{NH}_3 = 6$
$[\text{Co}(\text{NH}_3)_5\text{Cl}]^{2+} \quad 2\text{Cl}^-$	4	2	$5\text{NH}_3 + 1\text{Cl}^- = 6$
$[\text{Co}(\text{NH}_3)_4\text{Cl}_2]^+ \quad \text{Cl}^-$	2	1	$4\text{NH}_3 + 2\text{Cl}^- = 6$

complexes mentioned earlier, as do the results from Werner's AgCl experiments, shown in Table 7.4.

The freezing point of a liquid is lowered when a chemical substance is dissolved in it. Cryoscopic measurements involve measuring how much the freezing point is lowered. The depression of freezing point obtained depends on the number of particles present. Cryoscopic measurements can be used to find if a molecule dissociates, and how many ions are formed. If a molecule dissociates into two ions it will give twice the expected depression for a single particle. If three ions are formed this will give three times the expected depression. Thus:



The number of particles formed from a complex molecule determines the size of the depression of freezing point. Note that the number of particles formed may be different from the total number of charges which can be obtained from conductivity measurements. The two types of information can be used together to establish the structure (Table 7.5).

The magnetic moment can be measured (see Chapter 18 – Magnetic properties). This provides information about the number of unpaired electron spins present in a complex. From this it is possible to decide how the electrons are arranged and which orbitals are occupied. Sometimes the structure of the complex can be deduced from this. For example, the compound  $\text{Ni}^{II}(\text{NH}_3)_4(\text{NO}_3)_2 \cdot 2\text{H}_2\text{O}$  might contain four ammonia mol-

Table 7.5 Establishing the structure of complexes

Formula	Cryoscopic measurement	Molar conductivity	Structure
$\text{CoCl}_3 \cdot 6\text{NH}_3$	4 particles	6 charges	$[\text{Co}(\text{NH}_3)_6]^{3+} \quad 3\text{Cl}^-$
$\text{CoCl}_3 \cdot 5\text{NH}_3$	3 particles	4 charges	$[\text{Co}(\text{NH}_3)_5\text{Cl}]^{2+} \quad 2\text{Cl}^-$
$\text{CoCl}_3 \cdot 4\text{NH}_3$	2 particles	2 charges	$[\text{Co}(\text{NH}_3)_4\text{Cl}_2]^+ \quad \text{Cl}^-$
$\text{CoCl}_3 \cdot 3\text{NH}_3$	1 particle	0 charge	$[\text{Co}(\text{NH}_3)_3\text{Cl}_3]$
$\text{Co}(\text{NO}_2)_3 \cdot \text{KNO}_2 \cdot 2\text{NH}_3$	2 particles	2 charges	$\text{K}^+ [\text{Co}(\text{NH}_3)_2(\text{NO}_2)_4]^-$
$\text{Co}(\text{NO}_2)_3 \cdot 2\text{KNO}_2 \cdot \text{NH}_3$	3 particles	4 charges	$2\text{K}^+ [\text{Co}(\text{NH}_3)(\text{NO}_2)_5]^{2-}$
$\text{Co}(\text{NO}_2)_3 \cdot 3\text{KNO}_2$	4 particles	6 charges	$3\text{K}^+ [\text{Co}(\text{NO}_2)_6]^{3-}$

ecules coordinated to Ni in a square planar  $[\text{Ni}(\text{NH}_3)_4]^{2+}$  ion and two molecules of water of crystallization and have no unpaired electrons. Alternatively the water might be coordinated to the metal, giving an octahedral  $[\text{Ni}(\text{H}_2\text{O})_2(\text{NH}_3)_4]^{2+}$  complex with two unpaired electrons. Both these complex ions exist and their structures can be deduced from magnetic measurements.

Dipole moments may also yield structural information but only for non ionic complexes. For example, the complex  $[\text{Pt}(\text{NH}_3)_2\text{Cl}_2]$  is square planar and can exist as *cis* or *trans* forms. The dipole moments from the various metal-ligand bonds cancel out in the *trans* configuration. However, a finite dipole moment is given by the *cis* arrangement (Figure 7.5).

Electronic spectra (UV and visible) also provide valuable information on the energy of the orbitals, and on the shape of the complex. By this means it is possible to distinguish between tetrahedral and octahedral complexes, and whether the shape is distorted or regular.

The most powerful method, however, is the X-ray determination of the crystal structure. This provides details of the exact shape and the bond lengths and angles of the atoms in the structure.

## EFFECTIVE ATOMIC NUMBERS

The number of secondary valencies in the Werner theory is now called the coordination number of the central metal in the complex. This is the number of ligand atoms bonded to the central metal ion. Each ligand donates an electron pair to the metal ion, thus forming a coordinate bond. Transition metals form coordination compounds very readily because they have vacant *d* orbitals which can accommodate these electron pairs. The electronic arrangement of the noble gases is known to be very stable. Sidgwick, with his effective atomic number rule, suggested that electron pairs from ligands were added until the central metal was surrounded by the same number of electrons as the next noble gas. Consider potassium hexacyanoferrate(II)  $\text{K}_4[\text{Fe}(\text{CN})_6]$  (formerly called potassium ferrocyanide). An iron atom has 26 electrons, and so the central metal ion  $\text{Fe}^{2+}$  has 24 electrons. The next noble gas Kr has 36 electrons. Thus the addition of six electron pairs from six  $\text{CN}^-$  ligands adds 12 electrons, thus raising the effective atomic number (EAN) of  $\text{Fe}^{2+}$  in the complex  $[\text{Fe}(\text{CN})_6]^{4-}$  to 36.

$$[24 + (6 \times 2) = 36]$$

Further examples are given in Table 7.6.

The EAN rule correctly predicts the number of ligands in many complexes. There are, however, a significant number of exceptions where the EAN is not quite that of a noble gas. If the original metal ion has an odd number of electrons, for example, the adding of electron pairs cannot result in a noble gas structure. The tendency to attain a noble gas configuration is a significant factor but not a necessary condition for complex formation. It is also necessary to produce a symmetrical structure (tetra


Table 7.6 Effective atomic numbers of some metals in complexes

Atom	Atomic number	Complex	Electrons lost in ion formation	Electrons gained by coordination	EAN
Cr	24	[Cr(CO) <sub>6</sub> ]	0	12	36
Fe	26	[Fe(CN) <sub>6</sub> ] <sup>4-</sup>	2	12	36
Fe	26	[Fe(CO) <sub>5</sub> ]	0	10	36
Co	27	[Co(NH <sub>3</sub> ) <sub>6</sub> ] <sup>3+</sup>	3	12	36
Ni	28	[Ni(CO) <sub>4</sub> ]	0	8	36
Cu	29	[Cu(CN) <sub>4</sub> ] <sup>3-</sup>	1	8	36
Pd	46	[Pd(NH <sub>3</sub> ) <sub>6</sub> ] <sup>4+</sup>	4	12	54
Pt	78	[PtCl <sub>6</sub> ] <sup>2-</sup>	4	12	86
					(Kr)
					(Xe)
					(Rn)
Fe	26	[Fe(CN) <sub>6</sub> ] <sup>3-</sup>	3	12	35
Ni	28	[Ni(NH <sub>3</sub> ) <sub>6</sub> ] <sup>2+</sup>	2	12	38
Pd	46	[PdCl <sub>4</sub> ] <sup>2-</sup>	2	8	52
Pt	78	[Pt(NH <sub>3</sub> ) <sub>4</sub> ] <sup>2+</sup>	2	8	84

hedral, square planar, octahedral) irrespective of the number of electrons involved.

### SHAPES OF *d* ORBITALS

Since *d* orbitals are often used in coordination complexes it is important to study their shapes and distribution in space. The five *d* orbitals are not identical and the orbitals may be divided into two sets. The three *t<sub>2g</sub>* orbitals have identical shape and point between the axes, *x*, *y* and *z*. The

Figure 7.6 Shapes of *d* orbitals.

two  $e_g$  orbitals have different shapes and point along the axes (Figure 7.6). Alternative names for  $t_{2g}$  and  $e_g$  are  $d_{xy}$  and  $d_{yz}$  respectively.

## BONDING IN TRANSITION METAL COMPLEXES

There are three theories of metal to ligand bonding in complexes, all dating back to the 1930s.

### Valence bond theory

This theory was developed by Pauling. Coordination compounds contain complex ions, in which ligands form coordinate bonds to the metal. Thus the ligand must have a lone pair of electrons, and the metal must have an empty orbital of suitable energy available for bonding. The theory considers which atomic orbitals on the metal are used for bonding. From this the shape and stability of the complex are predicted. The theory has two main limitations. Most transition metal complexes are coloured, but the theory provides no explanation for their electronic spectra. Further, the theory does not explain why the magnetic properties vary with temperature. For these reasons it has largely been superseded by the crystal field theory. However, it is of interest for study as it shows the continuity of the development of modern ideas from Werner's theory.

### Crystal field theory

This theory was proposed by Bethe and van Vleck. The attraction between the central metal and ligands in the complex is considered to be purely electrostatic. Thus bonding in the complex may be ion-ion attraction (between positive and negative ions such as  $\text{Co}^{3+}$  and  $\text{Cl}^-$ ). Alternatively ion-dipole attractions may give rise to bonding (if the ligand is a neutral molecule such as  $\text{NH}_3$  or  $\text{CO}$ ).  $\text{NH}_3$  has a dipole moment with a  $\delta^-$  charge on N and  $\delta^+$  charges on H. Thus in  $[\text{Co}(\text{NH}_3)_6]^{3+}$  the  $\delta^-$  charge on the N atom of each  $\text{NH}_3$  points towards the  $\text{Co}^{3+}$ . This theory is simple. It has been remarkably successful in explaining the electronic spectra and magnetism of transition metal complexes, particularly when allowance is made for the possibility of some covalent interaction between the orbitals on the metal and ligand. When some allowance is made for covalency, the theory is often renamed as the ligand field theory. Three types of interaction are possible:  $\sigma$  overlap of orbitals,  $\pi$  overlap of orbitals or  $d\pi$ - $p\pi$  bonding (back bonding) due to  $\pi$  overlap of full  $d$  orbitals on the metal with empty  $p$  orbitals on the ligands.

### Molecular orbital theory

Both covalent and ionic contributions are fully allowed for in this theory. Though this theory is probably the most important approach to chemical bonding, it has not displaced the other theories. This is because the quantitative calculations involved are difficult and lengthy, involving the use



## VALENCE BOND THEORY

full inner shell)       $3d$        $4s$        $4p$        $4d$

full  
inner  
shell

$3d$

$4p$

$4d$

$(sp^3d^2 \text{ hybridization})$   
octahedral shape  
outer orbital complex  
high-spin complex


full  
inner  
shell

3d 4s 4p 4d

( $d^2sp^3$  hybridization)  
octahedral shape  
inner orbital complex  
low-spin complex

Since low energy inner  $d$ -orbitals are used this is called an *inner orbital complex*. Such complexes are more stable than the outer orbital complexes. The unpaired electrons in the metal ion have been forced to pair up and so this is now a low spin complex. In this particular case all the electrons are paired so the complex will be diamagnetic.

The metal ion could also form four coordinate complexes and two different arrangements are possible. *It must be remembered that hybrid orbitals do not actually exist.* Hybridization is a mathematical manipulation of the wave equations for the atomic orbitals involved.



The theory does not explain the colour and spectra of complexes. The theory shows the number of unpaired electrons. From this the magnetic moment can be calculated (see Chapter 18). However, it does not explain why the magnetic moment varies with temperature.

## CRYSTAL FIELD THEORY

The crystal field theory is now much more widely accepted than the valence bond theory. It assumes that the attraction between the central metal and the ligands in a complex is purely electrostatic. The transition metal which forms the central atom in the complex is regarded as a positive ion of charge equal to the oxidation state. This is surrounded by negative ligands or neutral molecules which have a lone pair of electrons. If the ligand is a neutral molecule such as  $\text{NH}_3$ , the negative end of the dipole in the molecule is directed towards the metal ion. The electrons on the central metal are under repulsive forces from those on the ligands. Thus the electrons occupy the  $d$  orbitals furthest away from the direction of approach of ligands. In the crystal field theory the following assumptions are made:

- 1 Ligands are treated as point charges.
- 2 There is no interaction between metal orbitals and ligand orbitals.
- 3 The  $d$  orbitals on the metal all have the same energy (that is degenerate) in the free atom. However, when a complex is formed the ligands destroy the degeneracy of these orbitals, i.e. the orbitals now have

different energies. In an isolated gaseous metal ion, the five  $d$  orbitals do all have the same energy, and are termed degenerate. If a spherically symmetrical field of negative charges surrounds the metal ion, the  $d$  orbitals remain degenerate. However, the energy of the orbitals is raised because of repulsion between the field and the electrons on the metal. In most transition metal complexes, either six or four ligands surround the metal, giving octahedral or tetrahedral structures. In both of these cases the field produced by the ligands is not spherically symmetrical. Thus the  $d$  orbitals are not all affected equally by the ligand field.

### Octahedral complexes

In an octahedral complex, the metal is at the centre of the octahedron, and the ligands are at the six corners. The directions  $x$ ,  $y$  and  $z$  point to three adjacent corners of the octahedron as shown in Figure 7.7.

The lobes of the  $e_g$  orbitals ( $d_{x^2-y^2}$  and  $d_{z^2}$ ) point along the axes  $x$ ,  $y$  and  $z$ . The lobes of the  $t_{2g}$  orbitals ( $d_{xy}$ ,  $d_{xz}$  and  $d_{yz}$ ) point in between the axes. It follows that the approach of six ligands along the  $x$ ,  $y$ ,  $z$ ,  $-x$ ,  $-y$  and  $-z$  directions will increase the energy of the  $d_{x^2-y^2}$  and  $d_{z^2}$  orbitals (which point along the axes) much more than it increases the energy of the  $d_{xy}$ ,  $d_{xz}$  and  $d_{yz}$  orbitals (which point between the axes). Thus under the influence of an octahedral ligand field the  $d$  orbitals split into two groups of different energies (Figure 7.8).

Rather than referring to the energy level of an isolated metal atom, the weighted mean of these two sets of perturbed orbitals is taken as the zero: this is sometimes called the Bari centre. The difference in energy between the two  $d$  levels is given either of the symbols  $\Delta_o$  or  $10 Dq$ . It follows that




Figure 7.7 The directions in an octahedral complex.




Figure 7.8 Crystal field splitting of energy levels in an octahedral field.




Figure 7.9 Diagram of the energy levels of  $d$  orbitals in an octahedral field

the  $e_g$  orbitals are  $+0.6\Delta_o$  above the average level, and the  $t_{2g}$  orbitals are  $-0.4\Delta_o$  below the average (Figure 7.9)

The size of the energy gap  $\Delta_o$  between the  $t_{2g}$  and  $e_g$  levels can be measured easily by recording the UV-visible spectrum of the complex. Consider a complex like  $[\text{Ti}(\text{H}_2\text{O})_6]^{3+}$ . The  $\text{Ti}^{3+}$  ion has one  $d$  electron. In the complex this will occupy the orbital with the lowest energy, that is one of the  $t_{2g}$  orbitals (Figure 7.10a). The complex absorbs light of the correct wavelength (energy) to promote the electron from the  $t_{2g}$  level to the  $e_g$  level (Figure 7.10b).

The electronic spectrum for  $[\text{Ti}(\text{H}_2\text{O})_6]^{3+}$  is given in Figure 7.11. The steep part of the curve from  $27\,000$  to  $30\,000\text{ cm}^{-1}$  (in the UV region) is due to charge transfer. The  $d-d$  transition is the single broad peak with a maximum at  $20\,300\text{ cm}^{-1}$ . Since  $1\text{ kJ mol}^{-1} = 83.7\text{ cm}^{-1}$ , the value of  $\Delta_o$




Figure 7.10  $d^1$  configuration (a) ground state, (b) excited state




Figure 7.11 Ultraviolet and visible absorption spectrum of  $[\text{Ti}(\text{H}_2\text{O})_6]^{3+}$ .

for  $[\text{Ti}(\text{H}_2\text{O})]^{3+}$  is  $20\,300/83.7 = 243 \text{ kJ mol}^{-1}$ . This is much the same as the energy of many normal single bonds (see Appendix F).

The above method is the most convenient way of measuring  $\Delta_o$  values. However,  $\Delta_o$  values can also be obtained from values of observed lattice energies and those calculated using the Born–Landé equation (see Chapter 3).

Solutions containing the hydrated  $\text{Ti}^{3+}$  ion are reddish violet coloured. This is because yellow and green light are absorbed to excite the electron. Thus the transmitted light is the complementary colour red–violet (Table 7.7).

Because of the crystal field splitting of  $d$  orbitals, the single  $d$  electron in  $[\text{Ti}(\text{H}_2\text{O})]^{3+}$  occupies an energy level  $2/5\Delta_o$  below the average energy of the  $d$  orbitals. As a result the complex is more stable. The crystal field stabilization energy (CFSE) is in this case  $2/5 \times 243 = 97 \text{ kJ mol}^{-1}$ .

Table 7.7 Colours absorbed and colours observed

Colour absorbed	Colour observed	Wavenumber observed ( $\text{cm}^{-1}$ )
yellow–green	red–violet	24 000–26 000
yellow	indigo	23 000–24 000
orange	blue	21 000–23 000
red	blue–green	20 000–21 000
purple	green	18 000–20 000
red–violet	yellow–green	17 300–18 000
indigo	yellow	16 400–17 300
blue	orange	15 300–16 400
blue–green	red	12 800–15 300

Table 7.8 Crystal field splittings by various ligands

Complex	Absorption peak	
	( $\text{cm}^{-1}$ )	( $\text{kJ mol}^{-1}$ )
$[\text{Cr}^{\text{III}}\text{Cl}_6]^{3-}$	13 640	163
$[\text{Cr}^{\text{III}}(\text{H}_2\text{O})_6]^{3+}$	17 830	213
$[\text{Cr}^{\text{III}}(\text{NH}_3)_6]^{3+}$	21 680	259
$[\text{Cr}^{\text{III}}(\text{CN})_6]^{3-}$	26 280	314

The magnitude of  $\Delta_o$  depends on three factors

- 1 The nature of the ligands
- 2 The charge on the metal ion
- 3 Whether the metal is in the first, second or third row of transition elements

Examination of the spectra of a series of complexes of the same metal with different ligands shows that the position of the absorption band (and hence the value of  $\Delta_o$ ) varies depending on the ligands which are attached (Table 7.8)

Ligands which cause only a small degree of crystal field splitting are termed weak field ligands. Ligands which cause a large splitting are called strong field ligands. Most  $\Delta$  values are in the range  $7000\text{ cm}^{-1}$  to  $30000\text{ cm}^{-1}$ . The common ligands can be arranged in ascending order of crystal field splitting  $\Delta$ . The order remains practically constant for different metals, and this series is called the spectrochemical series (see Further Reading Tsuchida, 1938, Jørgensen, 1962)

#### Spectrochemical series

##### *weak field ligands*

$\text{I}^- < \text{Br}^- < \text{S}^{2-} < \text{Cl}^- < \text{NO}_3^- < \text{F}^- < \text{OH}^- < \text{EtOH} < \text{oxalate} < \text{H}_2\text{O} < \text{EDTA} < (\text{NH}_3 \text{ and pyridine}) < \text{ethylenediamine} < \text{dipyridyl} < o\text{-phenanthroline} < \text{NO}_2^- < \text{CN}^- < \text{CO}$

##### *strong field ligands*

The spectrochemical series is an experimentally determined series. It is difficult to explain the order as it incorporates both the effects of  $\sigma$  and  $\pi$  bonding. The halides are in the order expected from electrostatic effects. In other cases we must consider covalent bonding to explain the order. A pattern of increasing  $\sigma$  donation is followed

halide donors  $<$  O donors  $<$  N donors  $<$  C donors

The crystal field splitting produced by the strong field  $\text{CN}^-$  ligand is about double that for weak field ligands like the halide ions. This is attributed to  $\pi$  bonding in which the metal donates electrons from a filled  $t_{2g}$  orbital into a vacant orbital on the ligand. In a similar way, many unsaturated N donors and C donors may also act as  $\pi$  acceptors.

The magnitude of  $\Delta_o$  increases as the charge on the metal ion increases

Table 7.9 Crystal field splittings for hexa-aqua complexes of  $M^{2+}$  and  $M^{3+}$ 

Oxidation state		Ti	V	Cr	Mn	Fe	Co	Ni	Cu
(+II)	Electronic configuration	$d^2$	$d^3$	$d^4$	$d^5$	$d^6$	$d^7$	$d^8$	$d^9$
	$\Delta_o$ in $\text{cm}^{-1}$	—	12 600	13 900	7 800	10 400	9 300	8 500	12 600
	$\Delta_o$ in $\text{kJ mol}^{-1}$	—	151	(166)	93	124	111	102	(151)
(+III)	Electronic configuration	$d^1$	$d^2$	$d^3$	$d^4$	$d^5$	$d^6$	$d^7$	$d^8$
	$\Delta_o$ in $\text{cm}^{-1}$	20 300	18 900	17 830	21 000	13 700	18 600	—	—
	$\Delta_o$ in $\text{kJ mol}^{-1}$	243	226	213	(251)	164	222	—	—

Values for  $d^4$  and  $d^9$  are approximate because of tetragonal distortion.

Table 7.10  $\Delta_o$  crystal field splittings in one group

	$\text{cm}^{-1}$	$\text{kJ mol}^{-1}$
$[\text{Co}(\text{NH}_3)_6]^{3+}$	24 800	296
$[\text{Rh}(\text{NH}_3)_6]^{3+}$	34 000	406
$[\text{Ir}(\text{NH}_3)_6]^{3+}$	41 000	490

For first row transition metal ions, the values of  $\Delta_o$  for  $M^{3+}$  complexes are roughly 50% larger than the values for  $M^{2+}$  complexes (Table 7.9).

The value of  $\Delta_o$  also increases by about 30% between adjacent members down a group of transition elements (Table 7.10). The crystal field stabilization energy in  $[\text{Ti}(\text{H}_2\text{O})_6]^{3+}$ , which has a  $d^1$  configuration, has previously been shown to be  $-0.4\Delta_o$ . In a similar way, complexes containing a metal ion with a  $d^2$  configuration will have a CFSE of  $2 \times -0.4\Delta_o = -0.8\Delta_o$  by singly filling two of the  $t_{2g}$  orbitals. (This is in agreement with Hund's rule that the arrangement with the maximum number of unpaired electrons is the most stable.) Complexes of  $d^3$  metal ions have a CFSE of  $3 \times -0.4\Delta_o = -1.2\Delta_o$ .

Complexes with a metal ion with a  $d^4$  configuration would be expected to have an electronic arrangement in accordance with Hund's rule (Figure 7.12a) with four unpaired electrons, and the CFSE will be  $(3 \times -0.4\Delta_o) + (0.6\Delta_o) = -0.6\Delta_o$ . An alternative arrangement of electrons which does not comply with Hund's rule is shown in Figure 7.12b. This arrangement has two unpaired electrons, and the CFSE is  $(4 \times -0.4\Delta_o) = -1.6\Delta_o$ . The CFSE is larger than in the previous case. However, the energy  $P$  used to pair the electrons must be allowed for, so the total stabilization energy is  $-1.6\Delta_o + P$ . These two arrangements differ in the number of unpaired electrons. The one with the most unpaired electrons is called 'high-spin' or 'spin-free', and the other one the 'low-spin' or 'spin-paired' arrangement. Both arrangements have been found to exist. Which arrangement occurs for any particular complex depends on whether the energy to promote an




Figure 7.12 High and low spin complexes (a)  $d^4$  high spin arrangement (weak ligand field), (b)  $d^4$  low spin arrangement (strong ligand field)

Table 7.11 CFSE and pairing energy for some complexes

Complex	Configuration	$\Delta_o$ ( $\text{cm}^{-1}$ )	$P$ ( $\text{cm}^{-1}$ )	Predicted	Found
$[\text{Fe}^{II}(\text{H}_2\text{O})_6]^{2+}$	$d^6$	10 400	17 600	high spin	high spin
$[\text{Fe}^{II}(\text{CN})_6]^{4-}$	$d^6$	32 850	17 600	low spin	low spin
$[\text{Co}^{III}\text{F}_6]^{3-}$	$d^7$	13 000	21 000	high spin	high spin
$[\text{Co}^{III}(\text{NH}_3)_6]^{3+}$	$d^7$	23 000	21 000	low spin	low spin

electron to the upper  $e_g$  level (that is the crystal field splitting  $\Delta_o$ ) is greater than the energy to pair electrons (that is  $P$ ) in the lower  $t_{2g}$  level. For a given metal ion  $P$  is constant. Thus the amount of crystal field splitting is determined by the strength of the ligand field. A weak field ligand such as  $\text{Cl}^-$  will only cause a small splitting of energy levels  $\Delta_o$ . Thus it will be more favourable energetically for electrons to occupy the upper  $e_g$  level and have a high-spin complex, rather than to pair electrons. In a similar way, strong field ligands such as  $\text{CN}^-$  cause a large splitting  $\Delta_o$ . In this case it requires less energy to pair the electrons and form a low-spin complex. Similar arguments apply to high- and low spin complexes of metal ions with  $d^5$ ,  $d^6$  and  $d^7$  configurations. These are summarized in Table 7.12.

### EFFECTS OF CRYSTAL FIELD SPLITTING

In octahedral complexes, the filling of  $t_{2g}$  orbitals decreases the energy of a complex, that is makes it more stable by  $-0.4\Delta_o$  per electron. Filling  $e_g$



Table 7.12 CFSE and electronic arrangements in octahedral complexes

Number of $d$ electrons	Arrangement in weak ligand field				Arrangement in strong ligand field			
	$t_{2g}$	$e_g$	CFSE $\Delta_o$	Spin only magnetic moment $\mu_s(D)$	$t_{2g}$	$e_g$	CFSE $\Delta_o$	Spin only magnetic moment $\mu_s(D)$
$d^1$	$\uparrow \square \square$	$\square \square$	-0.4	1.73	$\uparrow \square \square$	$\square \square$	-0.4	1.73
$d^2$	$\uparrow \uparrow \square$	$\square \square$	-0.8	2.83	$\uparrow \uparrow \square$	$\square \square$	-0.8	2.83
$d^3$	$\uparrow \uparrow \uparrow$	$\square \square$	-1.2	3.87	$\uparrow \uparrow \uparrow$	$\square \square$	-1.2	3.87
$d^4$	$\uparrow \uparrow \uparrow$	$\uparrow \square$	-1.2 +0.6 = -0.6	4.90	$\uparrow \downarrow \uparrow \uparrow$	$\square \square$	-1.6	2.83
$d^5$	$\uparrow \uparrow \uparrow$	$\uparrow \uparrow$	-1.2 +1.2 = -0.0	5.92	$\uparrow \downarrow \uparrow \downarrow \uparrow$	$\square \square$	-2.0	1.73
$d^6$	$\uparrow \downarrow \uparrow \uparrow$	$\uparrow \uparrow$	-1.6 +1.2 = -0.4	4.90	$\uparrow \downarrow \uparrow \downarrow \uparrow \downarrow$	$\square \square$	-2.4	0.00
$d^7$	$\uparrow \downarrow \uparrow \downarrow \uparrow$	$\uparrow \uparrow$	-2.0 +1.2 = -0.8	3.87	$\uparrow \downarrow \uparrow \downarrow \uparrow \downarrow$	$\uparrow \square$	-2.4 +0.6 = -1.8	1.73
$d^8$	$\uparrow \downarrow \uparrow \downarrow \uparrow \downarrow$	$\uparrow \uparrow$	-2.4 +1.2 = -1.2	2.83	$\uparrow \downarrow \uparrow \downarrow \uparrow \downarrow$	$\uparrow \uparrow$	-2.4 +1.2 = -1.2	2.83
$d^9$	$\uparrow \downarrow \uparrow \downarrow \uparrow \downarrow$	$\uparrow \downarrow \uparrow$	-2.4 +1.8 = -0.6	1.73	$\uparrow \downarrow \uparrow \downarrow \uparrow \downarrow$	$\uparrow \downarrow \uparrow$	-2.4 +1.8 = -0.6	1.73
$d^{10}$	$\uparrow \downarrow \uparrow \downarrow \uparrow \downarrow$	$\uparrow \downarrow \uparrow \downarrow$	-2.4 +2.4 = 0.0	0.00	$\uparrow \downarrow \uparrow \downarrow \uparrow \downarrow$	$\uparrow \downarrow \uparrow \downarrow$	-2.4 +2.4 = 0.0	0.00

orbitals increases the energy by  $+0.6\Delta_o$  per electron. The total crystal field stabilization energy is given by

$$\text{CFSE}_{(\text{octahedral})} = -0.4n_{(t_{2g})} + 0.6n_{(e_g)}$$

where  $n_{(t_{2g})}$  and  $n_{(e_g)}$  are the number of electrons occupying the  $t_{2g}$  and  $e_g$  orbitals respectively. The CFSE is zero for ions with  $d^0$  and  $d^{10}$  configurations in both strong and weak ligand fields. The CFSE is also zero for  $d^5$  configurations in a weak field. All the other arrangements have some


Table 7 13 Measured and calculated lattice energies

Compound	Structure	Measured lattice energy (kJ mol <sup>-1</sup> )	Calculated lattice energy (kJ mol <sup>-1</sup> )	Difference (measured - calculated) (kJ mol <sup>-1</sup> )
NaCl	Sodium chloride	-764	-764	0
AgCl	Sodium chloride	-916	-784	-132
AgBr	Sodium chloride	-908	-759	-149
MgF	Rutile	-2908	-2915	+7
MnF	Rutile	-2770	-2746	-24
FeF <sub>2</sub>	Rutile	-2912	-2752	-160
NiF <sub>2</sub>	Rutile	-3046	-2917	-129
CuF <sub>2</sub>	Rutile	-3042	-2885	-157

CFSE which increases the thermodynamic stability of the complexes. Thus many transition metal compounds have a higher measured lattice energy (obtained by calculations using the terms in the Born-Haber cycle) than is calculated using the Born-Landé, Born-Meyer or Kapustinskii equations. In contrast, the measured (Born-Haber) and calculated values for compounds of the main groups (which have no CFSE) are in close agreement (Table 7 13). There is also close agreement in MnF<sub>2</sub> which has a  $d^5$  configuration and a weak field ligand; hence there is no CFSE.

A plot of the lattice energies of the halides of the first row transition elements in the divalent state is given in Figure 7 13. In the solid, the coordination number of these metals is 6, and so the structures are analogous to octahedral complexes. The graphs for each halide show a minimum at Mn<sup>2+</sup> which has a  $d^5$  configuration. In a weak field this has a high spin arrangement with zero CFSE. The configurations  $d^0$  and  $d^{10}$  also have zero CFSE. The broken line through Ca<sup>2+</sup>, Mn<sup>2+</sup> and Zn<sup>2+</sup> represents zero stabilization. The heights of other points above this line are the crystal field stabilization energies.

The hydration energies of the M<sup>2+</sup> ions of the first row transition elements are plotted in Figure 7 14a.



The ions Ca<sup>2+</sup>, Mn<sup>2+</sup> and Zn<sup>2+</sup> have  $d^0$ ,  $d^5$  and  $d^{10}$  configurations and have zero CFSE. An almost straight line can be drawn through these points. The distance of the other points above this line corresponds to the CFSE. Values obtained in this way agree with those obtained spectroscopically. A similar graph of the M<sup>3+</sup> ions is shown in Figure 7 14b; here the  $d^0$ ,  $d^5$  and  $d^{10}$  species are Sc<sup>3+</sup>, Fe<sup>3+</sup> and Ga<sup>3+</sup>.

The ionic radii for M<sup>2+</sup> ions might be expected to decrease smoothly from Ca<sup>2+</sup> to Zn<sup>2+</sup> because of the increasing nuclear charge, and the poor shielding by  $d$  electrons. A plot of these radii is given in Figure 7 15. The change in size is not regular.

A smooth (broken) line is drawn through Ca<sup>2+</sup>, Mn<sup>2+</sup> and Zn<sup>2+</sup>. These




Figure 7.13 CFSE of dihalides of the first transition series. (After T.C. Waddington, Lattice energies and their significance in inorganic chemistry, *Advances in Inorganic Chemistry and Radiochemistry*, 1, Academic Press, New York, 1959.)




Figure 7.14 Enthalpies of hydration for  $M^{2+}$  and  $M^{3+}$ , in  $\text{kJ mol}^{-1}$ .




Figure 7.15 Octahedral ionic radii of  $M^{2+}$  for first row transition elements

have  $d^0$ ,  $d^5$  and  $d^{10}$  configurations as the  $d$  orbitals are empty, half full or full. These arrangements constitute an almost spherical field round the nucleus. In  $Ti^{2+}$  the  $d$  electrons occupy orbitals away from the ligands providing little or no shielding of the nuclear charge. Thus the ligands are drawn closer to the nucleus. The increased nuclear charge has an even greater effect in the case of  $V^{2+}$ . At  $Cr^{2+}$  the  $e_g$  level contains one electron. This is concentrated in the direction of the ligands, thus providing very good shielding. Thus the ligands can no longer approach so closely and the ionic radius increases. This increase in size is continued with the filling of the second  $e_g$  orbital at  $Mn^{2+}$ . The screening by the  $e_g$  orbitals is so good that the radius of  $Mn^{2+}$  is slightly smaller than it would be if it were in a truly spherical field. The same sequence of size changes is repeated in the second half of the series.













### TETRAGONAL DISTORTION OF OCTAHEDRAL COMPLEXES (JAHN-TELLER DISTORTION)

The shape of transition metal complexes is determined by the tendency of electron pairs to occupy positions as far away from each other as possible. This is the same as for the main group compounds and complexes. In addition, the shapes of transition metal complexes are affected by whether the  $d$  orbitals are symmetrically or asymmetrically filled.

Repulsion by six ligands in an octahedral complex splits the  $d$  orbitals on the central metal into  $t_{2g}$  and  $e_g$  levels. It follows that there is a corresponding repulsion between the  $d$  electrons and the ligands. If the  $d$  electrons are symmetrically arranged, they will repel all six ligands equally. Thus the structure will be a completely regular octahedron. The symmetrical arrangements of  $d$  electrons are shown in Table 7.14.

All other arrangements have an asymmetrical arrangement of  $d$  electrons. If the  $d$  electrons are asymmetrically arranged, they will repel some ligands in the complex more than others. Thus the structure is distorted because some ligands are prevented from approaching the metal.







Table 7.14 Symmetrical electronic arrangements

Electronic configuration	$t_{2g}$	$e_g$	Nature of ligand field	Examples
$d^0$			Strong or weak	$\text{Ti}^{\text{IV}}\text{O}_2$ , $[\text{Ti}^{\text{IV}}\text{F}_6]^{2-}$ $[\text{Ti}^{\text{IV}}\text{Cl}_6]^{2-}$
$d^3$			Strong or weak	$[\text{Cr}^{\text{III}}(\text{oxalate})_3]^{3-}$ $[\text{Cr}^{\text{III}}(\text{H}_2\text{O})_6]^{3+}$
$d^5$			Weak	$[\text{Mn}^{\text{II}}\text{F}_6]^{4-}$ $[\text{Fe}^{\text{III}}\text{F}_6]^{3-}$
$d^6$			Strong	$[\text{Fe}^{\text{II}}(\text{CN})_6]^{4-}$ $[\text{Co}^{\text{III}}(\text{NH}_3)_6]^{3+}$
$d^8$			Weak	$[\text{Ni}^{\text{II}}\text{F}_6]^{4-}$ $[\text{Ni}^{\text{II}}(\text{H}_2\text{O})_6]^{2+}$
$d^{10}$			Strong or weak	$[\text{Zn}^{\text{II}}(\text{NH}_3)_6]^{2+}$ $[\text{Zn}^{\text{II}}(\text{H}_2\text{O})_6]^{2+}$

as closely as others. The  $e_g$  orbitals point directly at the ligands. Thus asymmetric filling of the  $e_g$  orbitals results in some ligands being repelled more than others. This causes a significant distortion of the octahedral shape. In contrast the  $t_{2g}$  orbitals do not point directly at the ligands, but point in between the ligand directions. Thus asymmetric filling of the  $t_{2g}$  orbitals has only a very small effect on the stereochemistry. Distortion caused by asymmetric filling of the  $t_{2g}$  orbitals is usually too small to measure. The electronic arrangements which will produce a large distortion are shown in Table 7.15.

The two  $e_g$  orbitals  $d_{x^2-y^2}$  and  $d_{z^2}$  are normally degenerate. However, if they are asymmetrically filled then this degeneracy is destroyed, and the two orbitals are no longer equal in energy. If the  $d_{z^2}$  orbital contains one

Table 7.15 Asymmetrical electronic arrangements

Electronic configuration	$t_{2g}$	$e_g$	Nature of ligand field	Examples
$d^4$			Weak field (high-spin complex)	$\text{Cr}(+\text{II})$ , $\text{Mn}(+\text{III})$
$d^7$			Strong field (low-spin complex)	$\text{Co}(+\text{II})$ , $\text{Ni}(+\text{III})$
$d^9$			Either strong or weak	$\text{Cu}(+\text{II})$

more electron than the  $d_{x-y}$  orbital then the ligands approaching along  $+z$  and  $-z$  will encounter greater repulsion than the other four ligands. The repulsion and distortion result in elongation of the octahedron along the  $z$  axis. This is called tetragonal distortion. Strictly it should be called tetragonal elongation. This form of distortion is commonly observed.

If the  $d_{x-y}$  orbital contains the extra electron, then elongation will occur along the  $x$  and  $y$  axes. This means that the ligands approach more closely along the  $z$  axis. Thus there will be four long bonds and two short bonds. This is equivalent to compressing the octahedron along the  $z$  axis and is called tetragonal compression. Tetragonal elongation is much more common than tetragonal compression, and it is not possible to predict which will occur.

For example, the crystal structure of  $\text{CrF}_2$  is a distorted rutile ( $\text{TiO}_2$ ) structure.  $\text{Cr}^{2+}$  is octahedrally surrounded by six  $\text{F}^-$ , and there are four  $\text{Cr}-\text{F}$  bonds of length  $1.98-2.01 \text{ \AA}$ , and two longer bonds of length  $2.43 \text{ \AA}$ . The octahedron is said to be tetragonally distorted. The electronic arrangement in  $\text{Cr}^{2+}$  is  $d^4$ .  $\text{F}^-$  is a weak field ligand, and so the  $t_{2g}$  level contains three electrons and the  $e_g$  level contains one electron. The  $d_{x-y}$  orbital has four lobes whilst the  $d_z$  orbital has only two lobes pointing at the ligands. To minimize repulsion with the ligands, the single  $e_g$  electron will occupy the  $d_z$  orbital. This is equivalent to splitting the degeneracy of the  $e_g$  level so that  $d_z$  is of lower energy, i.e. more stable, and  $d_{x-y}$  is of higher energy, i.e. less stable. Thus the two ligands approaching along the  $+z$  and  $-z$  directions are subjected to greater repulsion than the four ligands along  $+x$ ,  $-x$ ,  $+y$  and  $-y$ . This causes tetragonal distortion with four short bonds and two long bonds. In the same way  $\text{MnF}_2$  contains  $\text{Mn}^{2+}$  with a  $d^5$  configuration, and forms a tetragonally distorted octahedral structure.

Many  $\text{Cu}(\text{II})$  salts and complexes also show tetragonally distorted octahedral structures.  $\text{Cu}^{2+}$  has a  $d^9$  configuration.



To minimize repulsion with the ligands, two electrons occupy the  $d_z$  orbital and one electron occupies the  $d_{x-y}$  orbital. Thus the two ligands along  $+z$  and  $-z$  are repelled more strongly than are the other four ligands (see Chapter 27, under +II state for copper).

The examples above show that whenever the  $d_z$  and  $d_{x-y}$  orbitals are unequally occupied, distortion occurs. This is known as Jahn-Teller distortion. The Jahn-Teller theorem states that 'Any non linear molecular system in a degenerate electronic state will be unstable, and will undergo some sort of distortion to lower its symmetry and remove the degeneracy. More simply, molecules or complexes (of any shape except linear), which have an unequally filled set of orbitals (either  $t_{2g}$  or  $e_g$ ), will be distorted. In octahedral complexes distortions from the  $t_{2g}$  level are too small to be

detected. However, distortions resulting from uneven filling of the  $e_g$  orbitals are very important.




Figure 7.16  $d^8$  arrangement in weak octahedral field.




Figure 7.17  $d^8$  arrangement in very strong octahedral field. Tetragonal distortion splits (a) the  $e_g$  level; and (b) also splits the  $t_{2g}$  level. The  $d_{xy}$  orbital is higher in energy than the  $d_{xz}$  or  $d_{yz}$ . (For simplicity this is sometimes ignored.)

## SQUARE PLANAR ARRANGEMENTS

If the central metal ion in a complex has a  $d^8$  configuration, six electrons will occupy the  $t_{2g}$  orbitals and two electrons will occupy the  $e_g$  orbitals. The arrangement is the same in a complex with weak field ligands. The electrons are arranged as shown in Figure 7.16. The orbitals are symmetrically filled, and a regular octahedral complex is formed, for example by  $[\text{Ni}^{II}(\text{H}_2\text{O})_6]^{2+}$  and  $[\text{Ni}^{II}(\text{NH}_3)_6]^{2+}$ .

The single electron in the  $d_{x^2-y^2}$  orbital is being repelled by four ligands whilst the electron in the  $d_{z^2}$  orbital is only being repelled by two ligands. Thus the energy of the  $d_{x^2-y^2}$  increases relative to that of  $d_{z^2}$ . If the ligand field is sufficiently strong, the difference in energy between these two orbitals becomes larger than the energy needed to pair the electrons. Under these conditions, a more stable arrangement arises when both the  $e_g$  electrons pair up and occupy the lower energy  $d_{z^2}$  orbital. This leaves the  $d_{x^2-y^2}$  orbital empty (Figure 7 17). Thus four ligands can now approach along the  $+x$ ,  $-x$ ,  $+y$  and  $-y$  directions without any difficulty as the  $d_{x^2-y^2}$  orbital is empty. However, ligands approaching along the  $+z$  and  $-z$  directions meet very strong repulsive forces from the filled  $d_{z^2}$  orbital (Figure 7 18). Thus only four ligands succeed in bonding to the metal. A square planar complex is formed, the attempt to form an octahedral complex being unsuccessful.




Figure 7 18  $d^8$  arrangement strong field (The  $d_{z^2}$  orbital is full the  $d_{x^2-y^2}$  empty)

The amount of tetragonal distortion that occurs depends on the particular metal ion and ligands. Sometimes the tetragonal distortion may become so large that the  $d_{z^2}$  orbital is lower in energy than the  $d_{xy}$  orbital as shown in Figure 7 19. In square planar complexes of  $\text{Co}^{II}$ ,  $\text{Ni}^{II}$  and  $\text{Cu}^{II}$  the  $d_{z^2}$  orbital has nearly the same energy as the  $d_{xz}$  and  $d_{yz}$  orbitals. In  $[\text{PtCl}_4]^{2-}$  the  $d_{z^2}$  orbital is lower in energy than the  $d_{xz}$  and  $d_{yz}$  orbitals.

Square planar complexes are formed by  $d^8$  ions with strong field ligands for example  $[\text{Ni}^{II}(\text{CN})_4]^{2-}$ . The crystal field splitting  $\Delta_o$  is larger for second and third row transition elements, and for more highly charged species. All the complexes of  $\text{Pt}(+II)$  and  $\text{Au}(+III)$  are square planar – including those with weak field ligands such as halide ions.




Figure 7 19 Tetragonal distortion



Table 7.16 Ions that form square planar complexes

Electronic configuration	Ions	Type of field	Number of unpaired electrons
$d^4$	Cr(+II)	Weak	4
$d^6$	Fe(+II)	(Haem)	2
$d^7$	Co(+II)	Strong	1
$d^8$	Ni(+II), Rh(+I), Ir(+I)	Strong	0
	Pd(+II), Pt(+II), Au(+III)	Strong and weak	0
$d^9$	Cu(+II), Ag(+II)	Strong and weak	1

Square planar structures can also arise from  $d^4$  ions in a weak ligand field. In this case the  $d_{x^2-y^2}$  orbital only contains one electron.

### TETRAHEDRAL COMPLEXES

A regular tetrahedron is related to a cube. One atom is at the centre of the cube, and four of the eight corners of the cube are occupied by ligands as shown in Figure 7.20.

The directions  $x$ ,  $y$  and  $z$  point to the centres of the faces of the cube. The  $e_g$  orbitals point along  $x$ ,  $y$  and  $z$  (that is to the centres of the faces). The  $t_{2g}$  orbitals point between  $x$ ,  $y$  and  $z$  (that is towards the centres of the edges of the cube) (Figure 7.21).

The direction of approach of the ligands does not coincide exactly with






Figure 7.20 Relation of a tetrahedron to a cube.

Figure 7.21 Orientation of  $d$  orbitals relative to a cube.




Figure 7.22 Crystal field splitting of energy levels in a tetrahedral field

either the  $e_g$  or the  $t_{2g}$  orbitals. The angle between an  $e_g$  orbital, the central metal and the ligand is half the tetrahedral angle  $= 109^\circ 28' / 2 = 54^\circ 44'$ . The angle between a  $t_{2g}$  orbital, the central metal and the ligand is  $35^\circ 16'$ . Thus the  $t_{2g}$  orbitals are nearer to the direction of the ligands than the  $e_g$  orbitals. (Alternatively the  $t_{2g}$  orbitals are half the side of the cube away from the approach of the ligands, whilst the  $e_g$  orbitals are half the diagonal of the cube away.) The approach of the ligands raises the energy of both sets of orbitals. The energy of the  $t_{2g}$  orbitals is raised most because they are closest to the ligands. This crystal field splitting is the opposite way round to that in octahedral complexes (Figure 7.22).

The  $t_{2g}$  orbitals are  $0.4\Delta_t$  above the weighted average energy of the two groups (the Bary centre) and the  $e_g$  orbitals are  $0.6\Delta_t$  below the average (Figure 7.23).

The magnitude of the crystal field splitting  $\Delta_t$  in tetrahedral complexes is considerably less than in octahedral fields. There are two reasons for this:

- 1 There are only four ligands instead of six, so the ligand field is only two thirds the size hence the ligand field splitting is also two thirds the size.
- 2 The direction of the orbitals does not coincide with the direction of the ligands. This reduces the crystal field splitting by roughly a further two thirds.

Thus the tetrahedral crystal field splitting  $\Delta_t$  is roughly  $2/3 \times 2/3 = 4/9$  of the octahedral crystal field splitting  $\Delta_o$ . Strong field ligands cause a bigger energy difference between  $t_{2g}$  and  $e_g$  than weak field ligands. However, the tetrahedral splitting  $\Delta_t$  is always much smaller than the octahedral splitting  $\Delta_o$ . Thus it is never energetically favourable to pair electrons, and all tetrahedral complexes are high spin.




Figure 7.23 Energy levels for  $d$  orbitals in a tetrahedral field.

The CFSE in both octahedral and tetrahedral environments is given in Table 7.17. This shows that for  $d^0$ ,  $d^5$  and  $d^{10}$  arrangements the CFSE is zero in both octahedral and tetrahedral complexes. For all other electronic arrangements there is some CFSE, and the octahedral CFSE is greater than the tetrahedral CFSE. It follows that octahedral complexes are generally more stable and more common than tetrahedral complexes. This is partly because there are six bond energy terms rather than four, and partly because there is a larger CFSE term. Despite this some tetrahedral complexes are formed, and are stable. Tetrahedral complexes are favoured:

1. Where the ligands are large and bulky and could cause crowding in an octahedral complex.
2. Where attainment of a regular shape is important. For tetrahedral structures  $d^0$ ,  $d^2$ ,  $d^5$ ,  $d^7$  and  $d^{10}$  configurations are regular. Some tetrahedral complexes which are regular are:  $\text{Ti}^{\text{IV}}\text{Cl}_4$  ( $e_g^0, t_{2g}^0$ ),  $[\text{Mn}^{\text{VII}}\text{O}_4]^-$  ( $e_g^0, t_{2g}^0$ ),  $[\text{Fe}^{\text{VI}}\text{O}_4]^{2-}$  ( $e_g^2, t_{2g}^0$ ),  $[\text{Fe}^{\text{III}}\text{Cl}_4]^-$  ( $e_g^2, t_{2g}^3$ ),  $[\text{Co}^{\text{II}}\text{Cl}_4]^{2-}$  ( $e_g^4, t_{2g}^3$ ) and  $[\text{Zn}^{\text{II}}\text{Cl}_4]^{2-}$  ( $e_g^4, t_{2g}^6$ ).
3. When the ligands are weak field, and the loss in CFSE is thus less important.
4. Where the central metal has a low oxidation state. This reduces the magnitude of  $\Delta$ .
5. Where the electronic configuration of the central metal is  $d^0$ ,  $d^5$  or  $d^{10}$  as there is no CFSE.
6. Where the loss of CFSE is small, e.g.  $d^1$  and  $d^6$  where the loss in CFSE is  $0.13\Delta_o$  or  $d^2$  and  $d^7$  where the loss is  $0.27\Delta_o$ .

Many transition metal chlorides, bromides and iodides form tetrahedral structures.

Table 7.17 CFSE and electronic arrangements in tetrahedral complexes


Number of $d$ electrons	Arrangement of electrons		Spin only magnetic moment $\mu(D)$	Tetrahedral CFSE $\Delta_t$	Tetrahedral CFSE scaled for comparison with octahedral values, assuming $\Delta_t = \frac{4}{9}\Delta_o$	Octahedral CFSE $\Delta_o$	
	$e_g$	$t_{2g}$				Weak field	Strong field
$d^1$	$\uparrow$		1.73	-0.6	-0.27	-0.4	-0.4
$d^2$	$\uparrow \uparrow$		2.83	-1.2	-0.53	-0.8	-0.8
$d^3$	$\uparrow \uparrow$	$\uparrow$	3.87	$-1.2 + 0.4 = -0.8$	-0.36	-1.2	-1.2
$d^4$	$\uparrow \uparrow$	$\uparrow \uparrow$	4.90	$-1.2 + 0.8 = -0.4$	-0.18	-0.6	-1.6
$d_5$	$\uparrow \uparrow$	$\uparrow \uparrow \uparrow$	5.92	$-1.2 + 1.2 = 0.0$	0.00	0.0	-2.0
$d^6$	$\uparrow \downarrow \uparrow$	$\uparrow \uparrow \uparrow$	4.90	$-1.8 + 1.2 = -0.6$	-0.27	-0.4	-2.4
$d_7$	$\uparrow \downarrow \uparrow \downarrow$	$\uparrow \uparrow \uparrow$	3.87	$-2.4 + 1.2 = -1.2$	-0.53	-0.8	-1.8
$d^8$	$\uparrow \downarrow \uparrow \downarrow$	$\uparrow \downarrow \uparrow \uparrow$	2.83	$-2.4 + 1.6 = -0.8$	-0.36	-1.2	-1.2
$d^9$	$\uparrow \downarrow \uparrow \downarrow$	$\uparrow \downarrow \uparrow \downarrow \uparrow$	1.73	$-2.4 + 2.0 = -0.4$	-0.18	-0.6	-0.6
$d^{10}$	$\uparrow \downarrow \uparrow \downarrow$	$\uparrow \downarrow \uparrow \downarrow \uparrow \downarrow$	0.00	$-2.4 + 2.4 = 0.0$	0.00	0.0	0.0

### CHELATES

Some of the factors that favour complex formation have already been mentioned

- 1 Small highly charged ions with suitable vacant orbitals of the right energy
- 2 The attainment of a noble gas structure (effective atomic number rule)
- 3 The attainment of a symmetrical shape and a high CFSE

In some complexes a ligand occupies more than one coordination position. Thus more than one atom in the ligand is bonded to the central metal. For example, ethylenediamine forms a complex with copper ions



In this complex the copper is surrounded by four  $\text{—NH}_2$  groups. Thus each ethylenediamine molecule is bonded to the copper in two places. For this reason ethylenediamine is called a bidentate group or ligand. (Bidentate means literally two teeth!) A ring structure is thus formed (in this case a pair of five-membered rings) and such ring structures are called chelates. (Chelos is the Greek word for crab.) Chelated complexes are more stable than similar complexes with unidentate ligands, as dissociation of the complex involves breaking two bonds rather than one. Some common polydentate ligands are listed in Figure 7.24.

The more rings that are formed, the more stable the complex is. Chelating agents with three, four and six donor atoms are known and are termed tridentate, tetradentate and hexadentate ligands. An important example of the latter is ethylenediaminetetraacetic acid. This bonds through two N and four O atoms to the metal, and so forms five rings. Due to this




Figure 7.24 Some common polydentate ligands.





Figure 7 25 EDTA



Resonance in acetylacetonate chelate  
Figure 7 26 Some chelate complexes

bonding EDTA can form complexes with most metal ions. Even complexes with large ions such as  $\text{Ca}^{2+}$  are relatively stable (The  $\text{Ca}^{2+}$ -EDTA complex is only formed completely at pH 8 not at lower pH).

Chelate compounds are even more stable when they contain a system of alternate double and single bonds. This is better represented as a system in which electron density is delocalized and spread over the ring. Examples of this include acetylacetonate and porphyrin complexes with metals (Figure 7 26).

Several chelate compounds are of biological importance. Haemoglobin in the red blood cells contains an iron-porphyrin complex. Chlorophyll in green plants contains a magnesium-porphyrin complex. Vitamin  $\text{B}_{12}$  is a cobalt complex and the cytochrome oxidase enzymes contain iron and copper. The body contains several materials which will form chelate compounds with metals, for example adrenaline, citric acid and cortisone. Metal poisoning by lead, copper, iron, chromium and nickel results in these materials forming unwanted complexes, thus preventing normal metabolism. For this reason dermatitis from chromium or nickel salts is treated with EDTA cream. Lead and copper poisoning are treated by drinking an aqueous solution of EDTA. This complexes with the unwanted lead or copper ions. Unfortunately it also complexes with other metal ions which are needed, particularly  $\text{Ca}^{2+}$ . The metal-EDTA complexes are excreted in the urine. (The problem of excreting  $\text{Ca}^{2+}$  may be partly overcome by using the Ca-EDTA complex rather than EDTA itself.)

## MAGNETISM

The magnetic moment can be measured using a Gouy balance (see Chapter 18). If we assume that the magnetic moment arises entirely from unpaired electron spins then the 'spin only' formula can be used to estimate  $n$ , the number of unpaired electrons. This gives reasonable agreement for complexes of the first row of transition metals.


$$\mu_s = \sqrt{n(n+2)}$$

Once the number of unpaired electrons is known, either the valence bond or the crystal field theory can be used to work out the shape of the complex, the oxidation state of the metal, and, for octahedral complexes, whether inner or outer  $d$  orbitals are used. For example,  $\text{Co}(+III)$  forms many complexes, all of which are octahedral. Most of them are diamagnetic, but  $[\text{CoF}_6]^{3-}$  is paramagnetic with an observed magnetic moment of 5.3 BM. Crystal field theory explains this (Figure 7.27).


$\text{Co}(+II)$  forms both tetrahedral and square planar four-coordinate complexes. These can be distinguished by magnetic measurements (Figure 7.28).

However, orbital angular momentum also contributes to a greater or lesser degree to the magnetic moment. For the second and third row transition elements not only is this contribution significant, but spin orbit coupling may occur. Because of this, the 'spin only' approximation is no longer valid, and there is extensive temperature-dependent paramagnetism. Thus the simple interpretation of magnetic moments in terms of the number of unpaired electrons cannot be extended from the first row of

### $\text{Co}^{3+}$ octahedral complex with strong field ligands



### $\text{Co}^{3+}$ octahedral complex with weak field ligands




assuming  $\mu_s = \sqrt{n(n+2)} = \sqrt{4(4+2)} = 4.90 \text{ BM}$

Figure 7.27  $\text{Co}^{3+}$  in high-spin and low-spin complexes.

Co<sup>2+</sup> in a tetrahedral field


Energy



3 unpaired electrons  $\mu = \sqrt{3(3 + 2)} = \sqrt{15} = 3.87 \text{ BM}$

Co<sup>2+</sup> in square planar complex

Energy



1 unpaired electron  $\mu = \sqrt{1(1 + 2)} = \sqrt{3} = 1.73 \text{ BM}$

Figure 7.28 Co<sup>2+</sup> in tetrahedral and square planar complexes

transition elements to the second and third rows. The temperature dependence is explained by the spin orbit coupling. This removes the degeneracy from the lowest energy level in the ground state. Thermal energy then allows a variety of levels to be populated.

### EXTENSION OF THE CRYSTAL FIELD THEORY TO ALLOW FOR SOME COVALENCY

The crystal field theory is based on purely electrostatic attraction. At first sight this seems to be a most improbable assumption. Nevertheless, the theory is remarkably successful in explaining the shapes of complexes, their spectra and their magnetic properties. Calculations can be carried out quite simply. The disadvantage of the theory is that it ignores evidence that some covalent bonding does occur in at least some transition metal complexes.

- 1 Compounds in the zero oxidation state such as nickel carbonyl  $[\text{Ni}^0(\text{CO})_4]$  have no electrostatic attraction between the metal and the ligands. Thus the bonding must be covalent.
- 2 The order of ligands in the spectrochemical series cannot be explained solely on electrostatic grounds.
- 3 There is some evidence from nuclear magnetic resonance and electron



spin resonance that there is some unpaired electron density on the ligands. This suggests the sharing of electrons, and hence some covalency.

The Racah interelectron repulsion parameter  $B$  is introduced into the interpretation of spectra. This makes some allowance for covalency arising from the delocalization of  $d$  electrons from the metal onto the ligand. If  $B$  is reduced below the value for a free metal ion, the  $d$  electrons are delocalized onto the ligand. The more  $B$  is reduced the greater the delocalization and the greater the amount of covalency. In a similar way an electron delocalization factor  $k$  can be used in interpreting magnetic measurements.

## MOLECULAR ORBITAL THEORY

The molecular orbital theory incorporates covalent bonding. Consider a first row transition element forming an octahedral complex, for example




Figure 7.29 Molecular orbital diagram for  $[\text{Co}^{\text{III}}(\text{NH}_3)_6]^{3+}$

$[\text{Co}^{\text{III}}(\text{NH}_3)_6]^{3+}$  The atomic orbitals on  $\text{Co}^{3+}$  which are used to make molecular orbitals are  $3d_{x^2-y^2}$ ,  $3d_{z^2}$ ,  $4s$ ,  $4p_x$ ,  $4p_y$  and  $4p_z$ . A  $2p$  atomic orbital from each  $\text{NH}_3$  containing a lone pair is also used to make molecular orbitals. Thus there are 12 atomic orbitals, which combine to give 12 molecular orbitals (six bonding MOs and six antibonding MOs). The 12 electrons from the six ligand lone pairs are placed in the six bonding MOs. This accounts for the six bonds. The transition metal  $\text{Co}^{3+}$  has other  $d$  orbitals, which have so far been ignored. These are the  $3d_{xy}$ ,  $3d_{xz}$  and  $3d_{yz}$  orbitals. These form non bonding MOs, and in  $\text{Co}^{3+}$  they contain six electrons, but contribute nothing to the bonding. The antibonding MOs are all empty. The arrangement is shown in Figure 7.29. We would predict that the complex should be diamagnetic as all the electrons are paired. The complex should be coloured since promotion of electrons from the non bonding MOs to the antibonding  $e_g^*$  MOs is feasible. The energy jump  $\Delta_o$  is  $23000\text{ cm}^{-1}$ . The six non bonding  $d$  electrons are paired in this complex because  $\Delta_o$  is larger than the pairing energy of  $19000\text{ cm}^{-1}$ .

A similar MO diagram can be drawn for the complex  $[\text{Co}^{\text{III}}\text{F}_6]^{3-}$




Figure 7.30 Molecular orbital diagram for  $[\text{CoF}_6]^{3-}$

However, the energies of the  $2p$  orbitals on  $F^-$  are much lower than the energy of the corresponding orbital on N in  $NH_3$ . This alters the spacing of the MO energy levels (Figure 7.30). Spectroscopic measurements show that  $\Delta_o$  is  $13\,000\text{ cm}^{-1}$ . Thus the gap between the non-bonding MOs and the antibonding  $e_g^*$  MOs is less than the pairing energy of  $19\,000\text{ cm}^{-1}$ . Thus the non-bonding  $d$  electrons do not pair up as in the  $[Co(NH_3)_6]^{3+}$  complex because there is a net gain in energy if electrons are left unpaired. Thus  $[CoF_6]^{3-}$  has four unpaired electrons and is a high-spin complex, whilst  $[Co(NH_3)_6]^{3+}$  has no unpaired electrons and is a low-spin complex.

Thus the MO theory explains the magnetic properties and spectra of complexes equally as well as the crystal field theory. Both theories rely on spectra to measure the energy of  $\Delta_o$ . Either theory may be used depending on which is the most convenient.

The MO theory is based on wave mechanics and so has the disadvantage that enthalpies of formation and bond energies cannot be calculated directly. So far we have considered  $\sigma$  bonding between ligands and the central metal. The MO theory has the great advantage that it is easily extended to cover  $\pi$  bonding.  $\pi$  bonding helps to explain how metals in low oxidation states (e.g.  $[Ni^0(CO)_4]$ ) can form complexes. It is impossible to explain any attractive force in such a complex using the crystal field theory because of the lack of charge on the metal.  $\pi$  bonding also helps to explain the position of some ligands in the spectrochemical series. There are two cases:

1. Where the ligands act as  $\pi$  acceptors, by accepting electrons from the central metal. Examples include  $CO$ ,  $CN^-$ ,  $NO^+$  and phosphines.
2. Where the ligands act as  $\pi$  donors and transfer charge from ligand to metal in  $\pi$  interactions as well as  $\sigma$  interactions.  $\pi$  bonding of this kind commonly occurs in oxoions of metals in high oxidation states, e.g.  $[Mn^{VII}O_4]^-$  and  $[Cr^{VI}O_4]^{2-}$ .

#### $\pi$ acceptors

Ligands such as  $CO$ ,  $CN^-$  and  $NO^+$  have empty  $\pi$  orbitals with the correct symmetry to overlap with the metal  $t_{2g}$  orbitals, forming  $\pi$  bonds. This is often described as back bonding. Normally the  $\pi$  orbitals on the ligands are of higher energy than the metal  $t_{2g}$  orbitals. No more electrons are added to the scheme as the ligand  $\pi$  orbitals are empty, but the  $\pi$  interaction increases the value of  $\Delta_o$ . This accounts for the position of these ligands as 'strong field ligands' at the right of the spectrochemical series.

#### $\pi$ donors

The ligand has filled  $\pi$  orbitals which overlap with the metal  $t_{2g}$  orbitals, giving a  $\pi$  bond. Thus electron density is transferred from the ligand to the metal. The  $\sigma$  bonding also transfers charge to the metal. This type of complex is favoured when the central metal has a high oxidation state,

and 'is short of electrons' The ligand  $\pi$  orbitals are lower in energy than the metal  $t_{2g}$  orbitals. Delocalizing  $\pi$  electrons from the ligand to the metal in this way reduces the value of  $\Delta$ . It is not always clear if  $\pi$  donor bonding has occurred, but it is most likely with ligands at the left of the spectrochemical series.

## NOMENCLATURE OF COORDINATION COMPOUNDS

The International Union of Pure and Applied Chemistry (IUPAC) publication *Nomenclature of Inorganic Chemistry* (1989), Blackwell Scientific Publishers, contains the rules for the systematic naming of coordination compounds. The basic rules are summarized here.

- 1 The positive ion is named first followed by the negative ion.
- 2 When writing the name of a complex, the ligands are quoted in alphabetical order, regardless of their charge (followed by the metal).
- 3 When writing the formula of complexes, the complex ion should be enclosed by square brackets. The metal is named first, then the coordinated groups are listed in the order: negative ligands, neutral ligands, positive ligands (and alphabetically according to the first symbol within each group).

(a) The names of negative ligands end in -o, for example

$F^-$	fluoro	$H^-$	hydrido	$HS^-$	mercapto
$Cl^-$	chloro	$OH^-$	hydroxo	$S^{2-}$	thio
$Br^-$	bromo	$O^{2-}$	oxo	$CN^-$	cyano
$I^-$	iodo	$O_2^{2-}$	peroxo	$NO_2^-$	nitro

(b) Neutral groups have no special endings. Examples include  $NH_3$  ammine,  $H_2O$  aqua,  $CO$  carbonyl and  $NO$  nitrosyl. The ligands  $N_2$  and  $O_2$  are called dinitrogen and dioxygen. Organic ligands are usually given their common names, for example phenyl, methyl, ethylenediamine, pyridine, triphenylphosphine.

(c) Positive groups end in -ium, e.g.  $NH_2-NH_2$  hydrazinium.

- 4 Where there are several ligands of the same kind, we normally use the prefixes di, tri, tetra, penta and hexa to show the number of ligands of that type. An exception occurs when the name of the ligand includes a number, e.g. dipyriddy or ethylenediamine. To avoid confusion in such cases, bis, tris and tetrakis are used instead of di, tri and tetra and the name of the ligand is placed in brackets.
- 5 The oxidation state of the central metal is shown by a Roman numeral in brackets immediately following its name (i.e. no space, e.g. titanium(III)).
- 6 Complex positive ions and neutral molecules have no special ending but complex negative ions end in -ate.
- 7 If the complex contains two or more metal atoms, it is termed polynuclear. The bridging ligands which link the two metal atoms together are indicated by the prefix  $\mu$ . If there are two or more bridging

groups of the same kind, this is indicated by di- $\mu$ -, tri- $\mu$ - etc. Bridging groups are listed alphabetically with the other groups unless the symmetry of the molecule allows a simpler name. If a bridging group bridges more than two metal atoms it is shown as  $\mu_3$ ,  $\mu_4$ ,  $\mu_5$  or  $\mu_6$  to indicate how many atoms it is bonded to.

8. Sometimes a ligand may be attached through different atoms. Thus  $M-\text{NO}_2$  is called nitro and  $M-\text{ONO}$  is called nitrito. Similarly the SCN group may bond  $M-\text{SCN}$  thiocyanato or  $M-\text{NCS}$  isothiocyanato. These may be named systematically thiocyanato-S or thiocyanato-N to indicate which atom is bonded to the metal. This convention may be extended to other cases where the mode of linkage is ambiguous.
9. If any lattice components such as water or solvent of crystallization are present, these follow the name, and are preceded by the number of these groups in Arabic numerals.

These rules are illustrated by the following examples:

#### Complex anions


$[\text{Co}(\text{NH}_3)_6]\text{Cl}_3$	Hexaamminecobalt(III) chloride
$[\text{CoCl}(\text{NH}_3)_5]^{2+}$	Pentaamminechlorocobalt(III) ion
$[\text{CoSO}_4(\text{NH}_3)_4]\text{NO}_3$	Tetraamminesulphatocobalt(III) nitrate
$[\text{Co}(\text{NO}_2)_3(\text{NH}_3)_3]$	Triamminetrinitrocobalt(III)
$[\text{CoCl} \cdot \text{CN} \cdot \text{NO}_2 \cdot (\text{NH}_3)_3]$	Triamminechlorocyanonitrocobalt(III)
$[\text{Zn}(\text{NCS})_4]^{2+}$	Tetrathiocyanato-N-zinc(II)
$[\text{Cd}(\text{SCN})_4]^{2+}$	Tetrathiocyanato-S-cadmium(II)

#### Complex cations


$\text{Li}[\text{AlH}_4]$	Lithium tetrahydridoaluminate(III) ( <i>lithium aluminium hydride</i> )
$\text{Na}_2[\text{ZnCl}_4]$	Sodium tetrachlorozincate(II)
$\text{K}_4[\text{Fe}(\text{CN})_6]$	Potassium hexacyanoferrate(II)
$\text{K}_3[\text{Fe}(\text{CN})_5\text{NO}]$	Potassium pentacyanonitrosylferrate(II)
$\text{K}_2[\text{OsCl}_5\text{N}]$	Potassium pentachloronitridoosmate(VI)
$\text{Na}_3[\text{Ag}(\text{S}_2\text{O}_3)_2]$	Sodium bis(thiosulphato)argentate(I)
$\text{K}_2[\text{Cr}(\text{CN})_2\text{O}_2(\text{O}_2)\text{NH}_3]$	Potassium amminedicyanodioxoperoxo chromate(VI)

#### Organic groups


$[\text{Pt}(\text{py})_4][\text{PtCl}_4]$	Tetrapyridineplatinum(II) · tetrachloroplatinate(II)
$[\text{Cr}(\text{en})_3]\text{Cl}_3$	<i>d</i> or <i>l</i> Tris(ethylenediamine)chromium(III) chloride
$[\text{CuCl}_2(\text{CH}_3\text{NH}_2)_2]$	Dichlorobis(methylamine)copper(II)
$\text{Fe}(\text{C}_5\text{H}_5)_2$	Bis(cyclopentadienyl)iron(II)
$[\text{Cr}(\text{C}_6\text{H}_6)_2]$	Bis(benzene)chromium(0)

*Bridging groups*


$\mu$  amidobis[pentaamminecobalt(III)] nitrate



Tri  $\mu$  carbonyl bis(tricarbonyliron(0))  
(di iron enneacarbonyl)



Hexa  $\mu$  acetato(O O')  $\mu_3$  oxo  
tetraberyllium(II)  
(basic beryllium acetate)

*Hydrates*

Aluminium potassium sulphate 12 water

## ISOMERISM

Compounds that have the same chemical formula but different structural arrangements are called isomers. Because of the complicated formulae of many coordination compounds the variety of bond types and the number of shapes possible many different types of isomerism occur. Werner's classification into polymerization, ionization, hydrate linkage, coordination, coordination position and geometric and optical isomerism is still generally accepted.

## Polymerization isomerism

This is not true isomerism because it occurs between compounds having the same empirical formula but different molecular weights. Thus  $[\text{Pt}(\text{NH}_3)_2\text{Cl}_2]$ ,  $[\text{Pt}(\text{NH}_3)_4][\text{PtCl}_4]$ ,  $[\text{Pt}(\text{NH}_3)_4][\text{Pt}(\text{NH}_3)\text{Cl}_3]_2$  and  $[\text{Pt}(\text{NH}_3)_3\text{Cl}]_2[\text{PtCl}_4]$  all have the same empirical formula. Polymerization isomerism may be due to a different number of nuclei in the complex as shown in Figure 7.31.




Figure 7.31 Polymerization isomers

## Ionization isomerism

This type of isomerism is due to the exchange of groups between the complex ion and the ions outside it.  $[\text{Co}(\text{NH}_3)_5\text{Br}]\text{SO}_4$  is red-violet. An aqueous solution gives a white precipitate of  $\text{BaSO}_4$  with  $\text{BaCl}_2$  solution thus confirming the presence of free  $\text{SO}_4^{2-}$  ions. In contrast  $[\text{Co}(\text{NH}_3)_5\text{SO}_4]\text{Br}$  is red. A solution of this complex does not give a positive sulphate test with  $\text{BaCl}_2$ . It does give a cream coloured precipitate

of AgBr with AgNO<sub>3</sub>, thus confirming the presence of free Br<sup>-</sup> ions. Note that the sulphate ion occupies only one coordination position even though it has two negative charges. Other examples of ionization isomerism are [Pt(NH<sub>3</sub>)<sub>4</sub>Cl<sub>2</sub>]Br<sub>2</sub> and [Pt(NH<sub>3</sub>)<sub>4</sub>Br<sub>2</sub>]Cl<sub>2</sub>, and [Co(en)<sub>2</sub>NO<sub>2</sub>·Cl]SCN, [Co(en)<sub>2</sub>NO<sub>2</sub>·SCN]Cl and [Co(en)<sub>2</sub>Cl·SCN]NO<sub>2</sub>.

### Hydrate isomerism

Three isomers of CrCl<sub>3</sub>·6H<sub>2</sub>O are known. From conductivity measurements and quantitative precipitation of the ionized chlorine, they have been given the following formulae:

[Cr(H <sub>2</sub> O) <sub>6</sub> ]Cl <sub>3</sub>	violet	(three ionic chlorines)
[Cr(H <sub>2</sub> O) <sub>5</sub> Cl]Cl <sub>2</sub> ·H <sub>2</sub> O	green	(two ionic chlorines)
[Cr(H <sub>2</sub> O) <sub>4</sub> Cl <sub>2</sub> ]·Cl·2H <sub>2</sub> O	dark green	(one ionic chlorine)

### Linkage isomerism

Certain ligands contain more than one atom which could donate an electron pair. In the NO<sub>2</sub><sup>-</sup> ion, either N or O atoms could act as the electron pair donor. Thus there is the possibility of isomerism. Two different complexes [Co(NH<sub>3</sub>)<sub>5</sub>NO<sub>2</sub>]Cl<sub>2</sub> have been prepared, each containing the NO<sub>2</sub><sup>-</sup> group in the complex ion. One is red and is easily decomposed by acids to give nitrous acid. It contains Co—ONO and is a nitrito complex. The other complex is yellow and is stable to acids. It contains the Co—NO<sub>2</sub> group and is a nitro compound. The two materials are represented in Figure 7.32. This type of isomerism also occurs with other ligands such as SCN<sup>-</sup>.




Figure 7.32 Nitrito and nitro complexes.

### Coordination isomerism

When both the positive and negative ions are complex ions, isomerism may be caused by the interchange of ligands between the anion and cation, for example [Co(NH<sub>3</sub>)<sub>6</sub>][Cr(CN)<sub>6</sub>] and [Cr(NH<sub>3</sub>)<sub>6</sub>][Co(CN)<sub>6</sub>]. Intermediate types between these extremes are also possible.





Figure 7.33 Coordination position isomers

**Coordination position isomerism**


In polynuclear complexes an interchange of ligands between the different metal nuclei gives rise to positional isomerism. An example is given in Figure 7.33

**Geometric isomerism or stereoisomerism**

In disubstituted complexes, the substituted groups may be adjacent or opposite to each other. This gives rise to geometric isomerism. Thus square planar complexes such as  $[\text{Pt}(\text{NH}_3)_2\text{Cl}_2]$  can be prepared in two forms *cis* and *trans*. If the complex is prepared by adding  $\text{NH}_4\text{OH}$  to a solution of  $[\text{PtCl}_4]^{2-}$  ions, the complex has a finite dipole moment and must therefore be *cis*. The complex prepared by treating  $[\text{Pt}(\text{NH}_3)_4]^{2+}$  with  $\text{HCl}$  has no dipole, and must therefore be *trans*. The two complexes are shown in Figure 7.34. The same sort of isomerism can also occur in square planar chelate complexes if the chelating group is not symmetrical. An example of *cis-trans* isomerism is found in the complex between glycine and platinum (Figure 7.35).

Figure 7.34 *Cis* and *trans* isomers

In a similar way disubstituted octahedral complexes such as  $[\text{Co}(\text{NH}_3)_4\text{Cl}_2]^+$  exists in *cis* and *trans* forms (Figure 7.36). (This method of drawing an octahedral complex might suggest that the positions in the square are different from the up and down positions. This is not the case as all six positions are equivalent.)

Figure 7.35 *Cis* and *trans* glycine complexes**Optical isomerism**

At one time it was thought that optical isomerism was associated only with carbon compounds. It exists in inorganic molecules as well. If a molecule is






Figure 7.36 *Cis* and *trans* octahedral complexes (geometric isomerism).

asymmetric, it cannot be superimposed on its mirror image. The two forms have the type of symmetry shown by the left and right hands and are called an enantiomorphic pair. The two forms are optical isomers. They are called either *dextro* or *laevo* (often shortened to *d* or *l*). This depends on the direction they rotate the plane of polarized light in a polarimeter. (*d* rotates to the right, *l* to the left.) Optical isomerism is common in octahedral complexes involving bidentate groups. For example,  $[\text{Co}(\text{en})_2\text{Cl}_2]^+$




Figure 7.37 Isomers of  $[\text{Co}(\text{en})_2\text{Cl}_2]^+$ .





Figure 7.39 *d*, *l* and *meso* forms.



shows *cis* and *trans* forms (geometric isomerism). In addition the *cis* form is optically active and exists in *d* and *l* forms making a total of three isomers (Figure 7.37). Optical activity occurs also in polynuclear complexes such as that shown in Figure 7.38. This has been resolved into two optically active forms (*d* and *l*) and an optically inactive form which is internally compensated and is called the *meso* form (Figure 7.39).

### FURTHER READING

- Ahrland, S., Chatt, J. and Davies, N. R. (1958) The relative affinities of ligand atoms for acceptor molecules and ions *Q. Rev. Chem. Soc.* **12**, 265–276.
- Bell, C. F. (1977) *Principles and Applications of Metal Chelation*. Oxford University Press, Oxford.
- Emeléus, H. J. and Sharpe, A. G. (1973) *Modern Aspects of Inorganic Chemistry* 4th ed. (Complexes of Transition Metals: Chapter 14. Structure; Chapter 15. Bonding; Chapter 16. Magnetic Properties; Chapter 17. Electronic Spectra). Routledge and Kegan Paul, London.
- Gerloch, M. (1981) The sense of Jahn–Teller distortions in octahedral copper(II) and other transition metal complexes *Inorg. Chem.* **20**, 638–640.
- Hogfeldt, E. (ed.) (1982) *Stability Constants of Metal Ion Complexes*. Pergamon, Oxford. (Inorganic ligands.)
- Johnson, B. F. G. (1973) *Comprehensive Inorganic Chemistry*, Vol. IV (Chapter 52. Transition metal chemistry). Pergamon Press, Oxford.
- Jørgensen, C. K. (1962) *Absorption Spectra and Chemical Bonding in Complexes* (Chapter 7). Pergamon Press, Oxford.
- Kauffman, G. B. (1966) *Alfred Werner Founder of Coordination Theory*. Springer, Berlin.
- Kauffman, G. B. (ed.) (1968, 1976, 1978) *Classics in Coordination Chemistry*. Part I. The Selected Papers of Alfred Werner; Part II. Selected Papers (1798–1899); Part III. Twentieth Century Papers. Dover, New York.
- Kauffman, G. B. (1973) Alfred Werner's research on structural isomerism *Coord. Chem. Rev.* **11**, 161–188.
- Kauffman, G. B. (1974) Alfred Werner's research on optically active coordination compounds *Coord. Chem. Rev.* **12**, 105–149.
- Martell, A. E. (ed.) (1971, 1978) *Coordination Chemistry*, Vol. I and II. Van Nostrand Reinhold, New York.
- Munro, D. (1977) Misunderstandings over the chelate effect *Chemistry in Britain* **13**, 100. (A simple article on the chelate effect.)
- Perrin, D. (ed.) (1979) *Stability Constants of Metal Ion Complexes*. Chemical Society, Pergamon. (Organic ligands.)
- Sillen, L. G. and Martell, A. E. (1964, 1971) *Stability Constants of Metal Ion Complexes* (Special Publications of the Chemical Society, no. 17 and no. 25). The Chemical Society, London.
- Tsuchida, R. (1938) Absorption spectra of coordination compounds *Bull. Soc. Japan* **1938**, 388–400, 434–450 and 471–480.

### PROBLEMS

1. List and explain the factors which affect the stability of coordination complexes.
2. Describe the methods by which the presence of complex ions may be detected in solution.

3. Draw all of the isomers of an octahedral complex which has six unidentate ligands; two of type A and four of type B.
4. Draw all of the isomers of an octahedral complex which has three unidentate ligands of type A and three unidentate ligands of type B.
5. Draw all of the isomers of an octahedral complex which has three identical bidentate ligands.
6. Draw all of the isomers of both tetrahedral and square planar complexes which have two unidentate ligands of type A and two unidentate ligands of type B.
7. Draw each of the possible stereoisomers of the octahedral complexes listed: (a)  $\text{Ma}_3\text{bcd}$ , (b)  $\text{Ma}_2\text{bcde}$  and (c)  $\text{M}(\text{AA})(\text{AA})\text{cd}$ . The lower case letters a, b, c, d, and e represent monodentate ligands, and upper case letters (AA) represent the donor atoms of a bidentate ligand. Indicate which isomers are optically active (chiral).
8. Draw the shapes of the various  $d$  orbitals, and explain why they are split into two groups  $t_{2g}$  and  $e_g$  in an octahedral ligand field.
9. Draw a diagram to show how the  $d$  orbitals are split into groups with different energy in an octahedral ligand field. Some electronic configurations may exist in both high-spin and low-spin arrangements in an octahedral field. Draw all of these cases, and suggest which metal ions and which ligands might give rise to each.
10. Draw an energy level diagram to show the lifting of the degeneracy of the  $3d$  orbitals in a tetrahedral ligand field.
11. Draw energy level diagrams and indicate the occupancy of the orbitals in the following complexes:
  - (a)  $d^6$ , octahedral, low-spin
  - (b)  $d^9$ , octahedral with tetragonal elongation
  - (c)  $d^8$ , square planar
  - (d)  $d^6$ , tetrahedral.Calculate in units of  $\Delta_o$  the difference in crystal field stabilization energy between complexes (a) and (d) assuming that the ligands are strong field ligands.  
(Answer: octahedral  $-2.4\Delta_o$ , tetrahedral  $-0.27\Delta_o$ , difference  $-2.13\Delta_o$ .)
12. Calculate the crystal field stabilization energy for a  $d^8$  ion such as  $\text{Ni}^{2+}$  in octahedral and tetrahedral complexes. Use units of  $\Delta_o$  in both cases. Which is the most stable? State any assumptions made.
13. Calculate the spin only magnetic moment for a  $d^8$  ion in octahedral, square planar and tetrahedral ligand fields.
14. Show by means of a diagram how the pattern of  $d$  orbital splitting changes as an octahedral complex undergoes tetragonal distortion and eventually becomes a square planar complex.

- 15 Why are  $d-d$  electronic transitions forbidden? Why are they weakly absorbing and why do they occur at all?
- 16 Why are compounds of  $Ti^{4+}$  and  $Zn^{2+}$  typically white? Why are  $Mn^{2+}$  compounds very pale in colour? What  $d-d$  transitions are spin allowed for a  $d^5$  ion?
- 17 What is the spectrochemical series, and what is its importance?
- 18 Given that the maximum absorption in the  $d-d$  peak for  $[Ti(H_2O)_6]^{3+}$  occurs at  $20300\text{ cm}^{-1}$ , predict where the peaks will occur for  $[Ti(CN)_6]^{3-}$  and  $[Ti(Cl)_6]^{3-}$ .
- 19 Describe how  $\Delta_o$  changes as the charge on the central metal changes from  $M^{2+}$  to  $M^{3+}$ , and how it changes in a vertical group or triad between a first row, second row or third row transition element.
- 20 What would you expect the crystal field stabilization energy to be and what value of magnetic moment would you expect, for the following complexes (a)  $[CoF_6]^{3-}$ , (b)  $[Co(NH_3)_6]^{3+}$ , (c)  $[Fe(H_2O)_6]^{2+}$ , (d)  $[Fe(CN)_6]^{4-}$  and (e)  $[Fe(CN)_6]^{3-}$ .
- 21 In the crystal structure of  $CuF_2$ , the  $Cu^{2+}$  is six coordinate with four  $F^-$  at a distance of  $1.93\text{ \AA}$  and two  $F^-$  at  $2.27\text{ \AA}$ . Explain the reason for this.
- 22 Describe and explain the Jahn–Teller effect in octahedral complexes of  $Cr^{2+}$  and  $Cu^{2+}$ .
- 23 The complex  $[Ni(CN)_4]^{2-}$  is diamagnetic, but  $[NiCl_4]^{2-}$  is paramagnetic and has two unpaired electrons. Explain these observations and deduce the structures of the two complexes.
- 24 What methods could be used to distinguish between *cis* and *trans* isomers of a complex?
- 25 Name the individual isomers of each of the following
  - (a)  $[Pt(NH_3)_2Cl_2]$
  - (b)  $CrCl_3 \cdot 6H_2O$
  - (c)  $[Co(NH_3)_5NO_2](NO_3)_2$
  - (d)  $Co(NH_3)_5(SO_4)(Cl)$
  - (e)  $\left[ \begin{array}{ccc} & NH_2 & \\ (en)_2Co & & Co(en)_2 \\ & NO_2 & \end{array} \right] Br_4$
  - (f)  $Co(en)_2NH_3BrSO_4$
  - (g)  $[Pt(NH_3)(H_2O)(C_5H_5N)(NO_2)]Cl$
- 26 Account for the following
  - (a)  $Ni(CO)_4$  is tetrahedral
  - (b)  $[Ni(CN)_4]^{2-}$  is square planar
  - (c)  $[Ni(NH_3)_6]^{2+}$  is octahedral

27. What is the oxidation number of the metal in each of the following complexes:

- (a)  $[\text{Co}(\text{NH}_3)_6]\text{Cl}_3$
- (b)  $[\text{CoSO}_4(\text{NH}_3)_4]\text{NO}_3$
- (c)  $[\text{Cd}(\text{SCN})_4]^{2+}$
- (d)  $[\text{Cr}(\text{en})_3]\text{Cl}_3$
- (e)  $[\text{CuCl}_2(\text{CH}_3\text{NH}_2)_2]$
- (f)  $[\text{AlH}_4]^-$
- (g)  $[\text{Fe}(\text{CN})_6]^{4-}$
- (h)  $[\text{OsCl}_5\text{N}]^{2-}$
- (i)  $[\text{Ag}(\text{S}_2\text{O}_3)_2]^{3-}$

28. Write the formula for each of the following complexes:

- (a) hexamminecobalt(III) chloride
- (b) potassium iron(III) hexacyanoferrate(II)
- (c) diamminedichloroplatinum(II)
- (d) tetracarbonylnickel(0)
- (e) triamminechlorocyanonitrocobalt(III)
- (f) lithium tetrahydridoaluminate(III)
- (g) sodium bis(thiosulphato)argentate(I)
- (h) nickel hexachloroplatinate(IV)
- (i) tetraammineplatinum(II) amminetrichloroplatinate(II)

29. Write the formula for each of the following complexes:

- (a) tetraamminecopper(II) sulphate
- (b) potassium tetracyanonickelate(0)
- (c) bis(cyclopentadienyl)iron(II)
- (d) tetrathiocyanato-N-zinc(II)
- (e) diamminebis(ethylenediamine)cobalt(III) chloride
- (f) tetraamminedithiocyanatochromium(III)
- (g) potassium tetraoxomanganate(VII)
- (h) potassium trioxalatoaluminate(III)
- (i) tetrapyridineplatinum(II) tetrachloroplatinate(II)

## ELECTRONIC STRUCTURE

Hydrogen has the simplest atomic structure of all the elements, and consists of a nucleus containing one proton with a charge +1 and one orbital electron. The electronic structure may be written as  $1s^1$ . Atoms of hydrogen may attain stability in three different ways

- 1 *By forming an electron pair (covalent) bond with another atom*  
Non-metals typically form this type of bond with hydrogen, for example  $H_2$ ,  $H_2O$ ,  $HCl_{(g)}$  or  $CH_4$ , and many metals do so too
- 2 *By losing an electron to form  $H^+$*   
A proton is extremely small (radius approximately  $1.5 \times 10^{-5} \text{ \AA}$ , compared with  $0.7414 \text{ \AA}$  for hydrogen, and  $1-2 \text{ \AA}$  for most atoms). Because  $H^+$  is so small, it has a very high polarizing power, and therefore distorts the electron cloud on other atoms. Thus protons are always associated with other atoms or molecules. For example, in water or aqueous solutions of  $HCl$  and  $H_2SO_4$ , protons exist as  $H_3O^+$ ,  $H_5O_2^+$  or  $H(H_2O)_n^+$  ions. Free protons do not exist under 'normal conditions', though they are found in low pressure gaseous beams, for example in a mass spectrometer
- 3 *By gaining an electron to form  $H^-$*   
Crystalline solids such as  $LiH$  contain the  $H^-$  ion and are formed by highly electropositive metals (all of Group 1, and some of Group 2). However,  $H^-$  ions are uncommon

Since hydrogen has an electronegativity of 2.1, it may use any of the three methods, but the most common way is forming covalent bonds.

## POSITION IN THE PERIODIC TABLE

Hydrogen is the first element in the periodic table, and is unique. There are only two elements in the first period, hydrogen and helium. Hydrogen is quite reactive, but helium is inert. There is no difficulty relating the structure and properties of helium to those of the other noble gases in

Group 18, but the properties of hydrogen cannot be correlated with any of the main groups in the periodic table, and hydrogen is best considered on its own.

The structure of hydrogen atoms is in some ways like that of the alkali metals. The alkali metals (Group 1) also have just one electron in their outer shell, but they tend to lose this electron in reactions and form positive ions  $M^+$ . Though  $H^+$  are known, hydrogen has a much greater tendency to pair the electron and form a covalent bond.

The structure of hydrogen atoms is in some ways like that of the halogens (Group 17), since both are one electron short of a noble gas structure. In many reactions the halogens gain an electron and so form negative ions  $X^-$ . Hydrogen does not typically form a negative ion, although it does form ionic hydrides  $M^+H^-$  (e.g.  $LiH$  and  $CaH_2$ ) with a few highly electropositive metals.

In some ways the structure of hydrogen resembles that of the Group 14 elements, since both have a half filled shell of electrons. There are a number of similarities between hydrides and organometallic compounds since the groups  $CH_3-$  and  $H-$  both have one remaining valency. Thus the hydride is often considered as part of a series of organometallic compounds, for example  $LiH$ ,  $LiMe$ ,  $LiEt$ ;  $NH_3$ ,  $NMe_3$ ,  $NEt_3$ ; or  $SiH_4$ ,  $CH_3SiH_3$ ,  $(CH_3)_2SiCl_2$ ,  $(CH_3)_3SiCl$ ,  $(CH_3)_4Si$ . However, hydrogen is best treated as a group on its own.


## ABUNDANCE OF HYDROGEN

Hydrogen is the most abundant element in the universe. Some estimates are that 92% of the universe is made up of hydrogen, and 7% helium, leaving only 1% for all of the other elements. However, the abundance of  $H_2$  in the earth's atmosphere is very small. This is because the earth's gravitational field is too small to hold so light an element, though some  $H_2$  is found in volcano gases. In contrast, hydrogen is the tenth most abundant element in the earth's crust (1520 ppm or 0.152% by weight). It also occurs in vast quantities as water in the oceans. Compounds containing hydrogen are very abundant, particularly water, living matter (carbohydrates and proteins), organic compounds, fossil fuels (coal, petroleum, and natural gas), ammonia and acids. In fact hydrogen is present in more compounds than any other element.


## PREPARATION OF HYDROGEN

Hydrogen is manufactured on a large scale by a variety of methods:



1. Hydrogen is made cheaply, and in large amounts, by passing steam over red hot coke. The product is water gas, which is a mixture of  $CO$  and  $H_2$ . This is an important industrial fuel since it is easy to make and it burns, evolving a lot of heat.




It is difficult to obtain pure  $\text{H}_2$  from water gas, since  $\text{CO}$  is difficult to remove. The  $\text{CO}$  may be liquified at a low temperature under pressure, thus separating it from  $\text{H}_2$ . Alternatively the gas mixture can be mixed with steam, cooled to  $400^\circ\text{C}$  and passed over iron oxide in a shift converter, giving  $\text{H}_2$  and  $\text{CO}_2$ . The  $\text{CO}_2$  so formed is easily removed either by dissolving in water under pressure, or reacting with  $\text{K}_2\text{CO}_3$  solution, giving  $\text{KHCO}_3$ , and thus giving  $\text{H}_2$  gas.





- 2 Hydrogen is also made in large amounts by the steam reformer process. The hydrogen produced in this way is used in the Haber process to make  $\text{NH}_3$ , and for hardening oil's. Light hydrocarbons such as methane are mixed with steam and passed over a nickel catalyst at  $800\text{--}900^\circ\text{C}$ . These hydrocarbons are present in natural gas, and are also produced at oil refineries when 'cracking' hydrocarbons.



The gas emerging from the reformer contains  $\text{CO}$ ,  $\text{CO}_2$ ,  $\text{H}_2$  and excess steam. The gas mixture is mixed with more steam, cooled to  $400^\circ\text{C}$  and passed into a shift converter. This contains an iron/copper catalyst and  $\text{CO}$  is converted into  $\text{CO}_2$ .





Finally the  $\text{CO}_2$  is absorbed in a solution of  $\text{K}_2\text{CO}_3$  or ethanolamine  $\text{HOCH}_2\text{CH}_2\text{NH}_2$ . The  $\text{K}_2\text{CO}_3$  or ethanolamine are regenerated by heating.





- 3 In oil refineries, natural hydrocarbon mixtures of high molecular weight such as naphtha and fuel oil are 'cracked' to produce lower molecular weight hydrocarbons which can be used as petrol. Hydrogen is a valuable by product.
- 4 Very pure hydrogen (99.9% pure) is made by electrolysis of water or solutions of  $\text{NaOH}$  or  $\text{KOH}$ . This is the most expensive method. Water does not conduct electricity very well, so it is usual to electrolyse aqueous solutions of  $\text{NaOH}$  or  $\text{KOH}$  in a cell with nickel anodes and




iron cathodes. The gases produced in the anode and cathode compartments must be kept separate.



5. A large amount of pure hydrogen is also formed as a by-product from the chlor-alkali industry, in which aqueous NaCl is electrolysed to produce NaOH, Cl<sub>2</sub> and H<sub>2</sub>.
6. The usual laboratory preparation is the reaction of dilute acids with metals, or of an alkali with aluminium.



7. Hydrogen can be prepared by the reaction of salt-like hydrides with water.



## PROPERTIES OF MOLECULAR HYDROGEN

Hydrogen is the lightest gas known, and because of its low density, it is used instead of helium to fill balloons for meteorology. It is colourless, odourless and almost insoluble in water. Hydrogen forms diatomic molecules H<sub>2</sub>, and the two atoms are joined by a very strong covalent bond (bond energy 435.9 kJ mol<sup>-1</sup>).

Hydrogen is not very reactive under normal conditions. The lack of reactivity is due to kinetics rather than thermodynamics, and relates to the strength of the H—H bond. An essential step in H<sub>2</sub> reacting with another element is the breaking of the H—H bond to produce atoms of hydrogen. This requires 435.9 kJ mol<sup>-1</sup>; hence there is a high activation energy to such reactions. Consequently many reactions are slow, or require high temperatures, or catalysts (often transition metals). Many important reactions of hydrogen involve heterogeneous catalysis, where the catalyst first reacts with H<sub>2</sub> and either breaks or weakens the H—H bond, and thus lowers the activation energy. Examples include:



1. The Haber process for the manufacture of NH<sub>3</sub> from N<sub>2</sub> and H<sub>2</sub> using a catalyst of activated Fe at 380–450°C and 200 atmospheres pressure.
2. The hydrogenation of a variety of unsaturated organic compounds, (including the hardening of oils), using finely divided Ni, Pd or Pt as catalysts.
3. The production of methanol by reducing CO with H<sub>2</sub> over a Cu/Zn catalyst at 300°C.

Thus hydrogen will react directly with most elements *under the appropriate conditions*.

Hydrogen burns in air or dioxygen, forming water, and liberates a large amount of energy. This is used in the oxy hydrogen flame for welding and cutting metals. Temperatures of almost 3000°C can be attained. Care should be taken with these gases since mixtures of H<sub>2</sub> and O<sub>2</sub> close to a 2 : 1 ratio are often explosive.




Hydrogen reacts with the halogens. The reaction with fluorine is violent even at low temperatures. The reaction with chlorine is slow in the dark but the reaction is catalysed by light (photocatalysis), and becomes faster in daylight, and explosive in sunlight. Direct combination of the elements is used to produce HCl.




A number of metals react with H<sub>2</sub>, forming hydrides. The reactions are not violent, and usually require a high temperature. These are described in a later section.


Large quantities of H<sub>2</sub> are used in the industrial production of ammonia by the Haber process. The reaction is reversible, and the formation of NH<sub>3</sub> is favoured by high pressure, the presence of a catalyst (Fe) and a low temperature. In practice a high temperature of 380–450°C and a pressure of 200 atmospheres are used to get a reasonable conversion in a reasonable time.




Large amounts of H<sub>2</sub> are used for hydrogenation reactions, in which hydrogen is added to a double bond in an organic compound. An important example is the hardening of fats and oils. Unsaturated fatty acids are hydrogenated with H<sub>2</sub> and a palladium catalyst, forming saturated fatty acids which have higher melting points. By removing double bonds in the carbon chain in this way, edible oils which are liquid at room temperature may be converted into fats which are solid at room temperature. The reason for doing this is that solid fats are more useful than oils, for example in the manufacture of margarine.



Hydrogen is also used to reduce nitrobenzene to aniline (dyestuffs industry), and in the catalytic reduction of benzene (the first step in the production of nylon 66). It also reacts with CO to form methyl alcohol.



The hydrogen molecule is very stable, and has little tendency to dissociate at normal temperatures, since the dissociation reaction is highly endothermic.



However, at high temperatures, in an electric arc, or under ultraviolet light,  $H_2$  does dissociate. The atomic hydrogen produced exists for less than half a second, after which it recombines to give molecular hydrogen and a large amount of heat. This reaction has been used in welding metals. Atomic hydrogen is a strong reducing agent, and is commonly prepared in solution by means of a zinc-copper couple or a mercury-aluminium couple.

There has been much talk of *the hydrogen economy*. (See Further Reading.) The idea is that hydrogen could replace coal and oil as the major source of energy. Burning hydrogen in air or dioxygen forms water and liberates a great deal of energy. In contrast to burning coal or oil in power stations, or petrol or diesel fuel in motor engines, burning hydrogen produces no pollutants like  $SO_2$  and oxides of nitrogen that are responsible for acid rain, nor  $CO_2$  that is responsible for the greenhouse effect, nor carcinogenic hydrocarbons, nor lead compounds. Hydrogen can be produced readily by electrolysis, and chemical methods. Hydrogen can be stored and transported as gas in cylinders, as liquid in very large cryogenic vacuum flasks, or 'dissolved' in various metals. (For example, the alloy  $LaNi_5$  can absorb seven moles of hydrogen per mole of alloy at 2.5 atmospheres pressure and room temperature.) Liquid hydrogen is used as a fuel in space rockets for the Saturn series and the space shuttle in the US space programme. Car engines have been modified to run on hydrogen. Note that the use of hydrogen involves the risk of an explosion, but so does the use of petrol.

## ISOTOPES OF HYDROGEN

If atoms of the same element have different mass numbers they are called isotopes. The difference in mass number arises because the nucleus contains a different number of neutrons. Naturally occurring hydrogen contains three isotopes: protium  ${}^1_1H$  or H, deuterium  ${}^2_1H$  or D, and tritium  ${}^3_1H$  or T. Each of the three isotopes contains one proton and 0, 1 or 2 neutrons respectively in the nucleus. Protium is by far the most abundant.

Naturally occurring hydrogen contains 99.986% of the  ${}^1_1H$  isotope, 0.014% of  ${}^2_1D$  and  $7 \times 10^{-16}\%$   ${}^3_1T$ , so the properties of hydrogen are essentially those of the lightest isotope.

These isotopes have the same electronic configuration and have essentially the same chemical properties. The only differences in chemical properties are the rates of reactions, and equilibrium constants. For example:

1.  $H_2$  is more rapidly adsorbed on to surfaces than  $D_2$ .
2.  $H_2$  reacts over 13 times faster with  $Cl_2$  than  $D_2$ , because  $H_2$  has a lower energy of activation.

Differences in properties which arise from differences in mass are called *isotope effects*. Because hydrogen is so light, the percentage difference in mass between protium  ${}^1_1H$ , deuterium  ${}^2_1H$  and tritium  ${}^3_1H$  is greater than

Table 8 1 Physical constants for hydrogen deuterium and tritium


Physical constant	H <sub>2</sub>	D <sub>2</sub>	T <sub>2</sub>
Mass of atom (amu)	1 0078	2 0141	3 0160
Freezing point (°C)	-259 0	-254 3	-252 4
Boiling point (°C)	-252 6	-249 3	-248 0
Bond length (Å)	0 7414	0 7414	(0 7414)
Heat of dissociation† (kJ mol <sup>-1</sup> )	435 9	443 4	446 9
Latent heat of fusion (kJ mol <sup>-1</sup> )	0 117	0 197	0 250
Latent heat of vaporization (kJ mol <sup>-1</sup> )	0 904	1 226	1 393
Vapour pressure* (mm Hg)	54	5 8	-

\* Measured at -259 1°C

† Measured at 25°C

between the isotopes of any other element. Thus the isotopes of hydrogen show much greater differences in physical properties than are found between the isotopes of other elements. Some physical constants for H<sub>2</sub>, D<sub>2</sub> and T<sub>2</sub> are given in Table 8 1.

Protium water H<sub>2</sub>O dissociates to about three times the extent that heavy water D<sub>2</sub>O does. The equilibrium constant for the dissociation of H<sub>2</sub>O is  $1.0 \times 10^{-14}$  whilst for D<sub>2</sub>O it is  $3.0 \times 10^{-15}$ .



Protium bonds are broken more readily than deuterium bonds (up to 18 times more readily in some cases). Thus when water is electrolysed, H<sub>2</sub> is liberated much faster than D<sub>2</sub>, and the remaining water thus becomes enriched in heavy water D<sub>2</sub>O. If the process is continued until only a small volume remains, then almost pure D<sub>2</sub>O is obtained. About 29 000 litres of water must be electrolysed to give 1 litre of D<sub>2</sub>O that is 99% pure. This is the normal way of separating deuterium. Heavy water D<sub>2</sub>O undergoes all of the reactions of ordinary water, and is useful in the preparation of other deuterium compounds. Because D<sub>2</sub>O has a lower dielectric constant, ionic


Table 8 2 Physical constants for water and heavy water

Physical constant	H <sub>2</sub> O	D <sub>2</sub> O
Freezing point (°C)	0	3 82
Boiling point (°C)	100	101 42
Density at 20°C (g cm <sup>-3</sup> )	0 917	1 017
Temperature of maximum density (°C)	4	11 6
Ionic product $K_w$ at 25°C	$1.0 \times 10^{-14}$	$3.0 \times 10^{-15}$
Dielectric constant at 20°C	82	80 5
Solubility g NaCl/100 g water at 25°C	35 9	30 5
Solubility g BaCl <sub>2</sub> /100 g water at 25°C	35 7	28 9


compounds are less soluble in it than in water. Some physical properties of  $\text{H}_2\text{O}$  and  $\text{D}_2\text{O}$  are compared in Table 8.2.

Deuterium compounds are commonly prepared by 'exchange' reactions where under suitable conditions deuterium is exchanged for hydrogen in compounds. Thus  $\text{D}_2$  reacts with  $\text{H}_2$  at high temperatures, forming  $\text{HD}$ , and it also exchanges with  $\text{NH}_3$  and  $\text{CH}_4$  to give  $\text{NH}_2\text{D}$ ,  $\text{NHD}_2$ ,  $\text{ND}_3$  and  $\text{CH}_3\text{D}$ — $\text{CD}_4$ . It is usually easier to prepare deuterated compounds using  $\text{D}_2\text{O}$  rather than  $\text{D}_2$ . The  $\text{D}_2\text{O}$  may be used directly in the preparation instead of  $\text{H}_2\text{O}$ , or exchange reactions may be carried out using  $\text{D}_2\text{O}$ .

#### Exchange reactions




#### Direct reactions




Tritium is radioactive and decays by  $\beta$  emission.




It has a relatively short half life time of 12.26 years. Thus any T present when the earth was formed has decayed already, and the small amount now present has been formed recently by reactions induced by cosmic rays in the upper atmosphere.



Tritium only occurs to the extent of one part  $\text{T}_2$  to  $7 \times 10^{17}$  parts  $\text{H}_2$ . It was first made by bombarding  $\text{D}_3\text{PO}_4$  and  $(\text{ND}_4)_2\text{SO}_4$  with deuterons  $\text{D}^+$



It is now produced on a large scale by irradiating lithium with slow neutrons in a nuclear reactor.




Tritium is used to make thermonuclear devices, and for research into fusion reactions as a means of producing energy. The gas is usually stored by making  $\text{UT}_3$ , which on heating to  $400^\circ\text{C}$  releases  $\text{T}_2$ . Tritium is widely used as a radioactive tracer, since it is relatively cheap, and it is easy to work with. It only emits low energy  $\beta$  radiation, with no  $\gamma$  radiation. The  $\beta$  radiation is stopped by 0.6 cm of air, so no shielding is required. It is non-toxic, except if labelled compounds are swallowed.


Tritiated compounds are made from  $\text{T}_2$  gas.  $\text{T}_2\text{O}$  is made as follows:



or



Many tritiated organic compounds can be made by storing the compound under  $\text{T}_2$  gas for a few weeks, when exchange of H and T occurs. Many compounds can be made by catalytic exchange in solution using either  $\text{T}_2$  gas dissolved in the water, or  $\text{T}_2\text{O}$ .



### ORTHO AND PARA HYDROGEN

The hydrogen molecule  $\text{H}_2$  exists in two different forms known as *ortho* and *para* hydrogen. The nucleus of an atom has nuclear spin, in a similar way to electrons having a spin. In the  $\text{H}_2$  molecule, the two nuclei may be spinning in either the same direction, or in opposite directions. This gives rise to spin isomerism, that is two different forms of  $\text{H}_2$  may exist. These are called *ortho* and *para* hydrogen. Spin isomerism is also found in other symmetrical molecules whose nuclei have spin momenta, e.g.  $\text{D}_2$ ,  $\text{N}_2$ ,  $\text{F}_2$ ,  $\text{Cl}_2$ . There are considerable differences between the physical properties (e.g. boiling points, specific heats and thermal conductivities) of the *ortho* and *para* forms, because of differences in their internal energy. There are also differences in the band spectra of the *ortho* and *para* forms of  $\text{H}_2$ .

The *para* form has the lower energy, and at absolute zero the gas contains 100% of the *para* form. As the temperature is raised, some of the *para* form changes into the *ortho* form. At high temperatures the gas contains about 75% *ortho* hydrogen.

*Para* hydrogen is usually prepared by passing a mixture of the two forms of hydrogen through a tube packed with charcoal cooled to liquid air temperature. *Para* hydrogen prepared in this way can be kept for weeks at room temperature in a glass vessel, because the *ortho-para* conversion is slow in the absence of catalysts. Suitable catalysts include activated charcoal, atomic hydrogen, metals such as Fe, Ni, Pt and W and paramagnetic substances or ions (which contain unpaired electrons) such as  $\text{O}_2$ , NO,  $\text{NO}_2$ ,  $\text{Co}^{2+}$  and  $\text{Cr}_2\text{O}_3$ .

### HYDRIDES

Binary compounds of the elements with hydrogen are called hydrides. The type of hydride which an element forms depends on its electronegativity and hence on the type of bond formed. Whilst there is not a sharp division between ionic, covalent and metallic bonding, it is convenient to consider hydrides in three classes (Figure 8.2).

- 1 ionic or salt like hydrides
- 2 covalent or molecular hydrides
- 3 metallic or interstitial hydrides




Figure 8.1 *Ortho* and *para* hydrogen (a) *ortho* parallel spins (b) *para* opposite

		s-block										p-block						
Group	1	2	Intermediate Hydrides										13	14	15	16	17	18
Period																		
1																		
2	<sup>3</sup> Li		d-block															
3	<sup>11</sup> Na		3	4	5	6	7	8	9	10	11	12						
4	<sup>19</sup> K	<sup>20</sup> Ca	<sup>21</sup> Sc	<sup>22</sup> Ti	<sup>23</sup> V	<sup>24</sup> Cr				<sup>28</sup> Ni	<sup>29</sup> Cu	<sup>30</sup> Zn						
5	<sup>37</sup> Rb	<sup>38</sup> Sr	<sup>39</sup> Y	<sup>40</sup> Zr	<sup>41</sup> Nb					<sup>46</sup> Pd		<sup>48</sup> Cd						
6	<sup>55</sup> Cs	<sup>56</sup> Ba	<sup>57</sup> La	<sup>72</sup> Hf	<sup>73</sup> Ta							<sup>80</sup> Hg	<sup>81</sup> Tl					
7	<sup>87</sup> Fr	<sup>88</sup> Ra	<sup>89</sup> Ac											Covalent Hydrides				
Ionic Hydrides			f-block															
Lanthanides			<sup>58</sup> Ce	<sup>59</sup> Pr	<sup>60</sup> Nd		<sup>62</sup> Sm	<sup>63</sup> Eu	<sup>64</sup> Gd	<sup>65</sup> Tb	<sup>66</sup> Dy	<sup>67</sup> Ho	<sup>68</sup> Er	<sup>69</sup> Tm	<sup>70</sup> Yb	<sup>71</sup> Lu		
Actinides			<sup>90</sup> Th	<sup>91</sup> Pa	<sup>92</sup> U	<sup>93</sup> Np	<sup>94</sup> Pu	<sup>95</sup> Am										

## Metallic Hydrides

Figure 8.2 Types of hydride and the periodic table.

## Ionic or salt-like hydrides

At high temperatures the metals of Group 1 (alkali metals) and the heavier Group 2 metals (alkaline earth metals) Ca, Sr and Ba form ionic hydrides such as NaH and CaH<sub>2</sub>. These compounds are solids with high melting points, and are classified as ionic (salt-like) hydrides. The evidence that they are ionic is:

1. Molten LiH (m.p. 691 °C) conducts electricity, and H<sub>2</sub> is liberated at the anode, thus confirming the presence of the hydride ion H<sup>-</sup>
2. The other ionic hydrides decompose before melting, but they may be dissolved in melts of alkali halides (e.g. CaH<sub>2</sub> dissolves in a eutectic mixture of LiCl/KCl), and when the melt is electrolysed then H<sub>2</sub> is evolved at the anode.
3. The crystal structures of these hydrides are known, and they show no evidence of directional bonding.

Lithium is more polarizing and hence more likely to form covalent compounds than the other metals. Thus if LiH is largely ionic, the others must be ionic, and thus contain the hydride ion H<sup>-</sup>

The density of these hydrides is greater than that of the metal from which they were formed. This is explained by H<sup>-</sup> ions occupying holes in the lattice of the metal, without distorting the metal lattice. Ionic hydrides have high heats of formation, and are always stoichiometric.


This type of hydride is only formed by elements with an electronega-

tivity value appreciably lower than the value of 2.1 for hydrogen, thus allowing the hydrogen to attract an electron from the metal, forming  $M^+$  and  $H^-$ .


Group 1 hydrides are more reactive than the corresponding Group 2 hydrides, and reactivity increases down the group.

Except for  $LiH$ , ionic hydrides decompose into their constituent elements on strong heating ( $400-500^\circ C$ ).


The hydride ion  $H^-$  is not very common, and it is unstable in water. Thus ionic hydrides all react with water and liberate hydrogen.



They are powerful reducing agents, especially at high temperatures, though their reactivity towards water limits their usefulness.



$NaH$  has a number of uses as a reducing agent in synthetic chemistry. It is used to produce other important hydrides, particularly lithium aluminium hydride  $Li[AlH_4]$  and sodium borohydride  $Na[BH_4]$ , which have important uses as reducing agents in both organic and inorganic syntheses.



### Covalent hydrides




Hydrides of the  $p$  block elements are covalent. This would be expected since there is only a small difference in electronegativity between these atoms and hydrogen. The compounds usually consist of discrete covalent molecules, with only weak van der Waals forces holding the molecules together, and so they are usually volatile, and have low melting and boiling points. They do not conduct electricity. The formula of these hydrides is  $XH_n$  or  $XH_{(8-n)}$ , where  $n$  is the group in the periodic table to which  $X$  belongs. These hydrides are produced by a variety of synthetic methods.

1. A few may be made by direct action



Group	13	14	15	16	17
	B	C	N	O	F
	Al	Si	P	S	Cl
	Ga	Ge	As	Se	Br
	In	Sn	Sb	Te	I
		Pb	Bi	Po	

Figure 8.3 Elements which form covalent hydrides by direct action









2. Reaction of a halide with  $\text{Li}[\text{AlH}_4]$  in a dry solvent such as ether.




3. Treating the appropriate binary compound with acid.



4. Reaction of an oxoacid with  $\text{Na}[\text{BH}_4]$  in aqueous solution.



5. Converting one hydride into another by pyrolysis (heating).



6. A silent electric discharge or microwave discharge may produce long chains from simple hydrides.




**Table 8.3** Melting and boiling points of some covalent hydrides

Compound	m.p. (°C)	b.p. (°C)
$\text{B}_2\text{H}_6$	-165	-90
$\text{CH}_4$	-183	-162
$\text{SiH}_4$	-185	-111
$\text{GeH}_4$	-166	-88
$\text{SnH}_4$	-150	-52
$\text{NH}_3$	-78	-33
$\text{PH}_3$	-134	-88
$\text{AsH}_3$	-117	-62
$\text{SbH}_3$	-88	-18
$\text{H}_2\text{O}$	0	+100
$\text{H}_2\text{S}$	-86	-60
$\text{HF}$	-83	+20
$\text{HCl}$	-115	-84
$\text{HBr}$	-89	-67
$\text{HI}$	-51	-35

The Group 13 hydrides are unusual in that they are electron deficient and polymeric, although they do not contain direct bonds between the Group 13 elements. The simplest boron hydride is called diborane  $B_2H_6$ , though more complicated structures such as  $B_4H_{10}$ ,  $B_5H_9$ ,  $B_5H_{11}$ ,  $B_6H_{10}$  and  $B_{10}H_{14}$  are known. Aluminium hydride is polymeric  $(AlH_3)_n$ . In these structures, hydrogen appears to be bonded to two or more atoms, and this is explained in terms of multi-centre bonding. This is discussed in Chapter 12.

In addition to the simple hydrides, the rest of the lighter elements except the halogens form polynuclear hydrides. The tendency to do this is strongest with the elements C, N and O, and two or more of the non-metal atoms are directly bonded to each other. The tendency is greatest with C which catenates (forms chains) of several hundreds of atoms. These are grouped into three homologous series of aliphatic hydrocarbons, and aromatic hydrocarbons based on benzene.



The alkanes are saturated, but alkenes have double bonds, and alkynes have triple bonds. Si and Ge only form saturated compounds, and the maximum chain length is  $Si_{10}H_{22}$ . The longest hydride chains formed by other elements are  $Sn_2H_6$ ,  $N_2H_4$  and  $HN_3$ ,  $P_3H_5$ ,  $As_3H_5$ ,  $H_2O_2$  and  $H_2O_3$  and  $H_2S_2$ ,  $H_2S_3$ ,  $H_2S_4$ ,  $H_2S_5$  and  $H_2S_6$ .

The melting point and boiling point of water stand out in Table 8.3 as being much higher than the others, but on closer examination the values for  $NH_3$  and  $HF$  also seem higher than would be expected in their respective groups. This is due to hydrogen bonding, which is discussed later in this chapter.

### Metallic (or interstitial) hydrides

Many of the elements in the *d*-block, and the lanthanide and actinide elements in the *f*-block, react with  $H_2$  and form metallic hydrides. However, the elements in the middle of the *d*-block do not form hydrides. The absence of hydrides in this part of the periodic table is sometimes called *the hydrogen gap* (See Figure 8.2).

Metallic hydrides are usually prepared by heating the metal with hydrogen under high pressure. (If heated to higher temperatures the hydrides decompose, and this may be used as a convenient method of making very pure hydrogen.)

These hydrides generally have properties similar to those of the parent metals: they are hard, have a metallic lustre, conduct electricity, and have magnetic properties. The hydrides are less dense than the parent metal because the crystal lattice has expanded through the inclusion of hydrogen.

This distortion of the crystal lattice may make the hydride brittle. Thus when the hydride is formed a solid piece of metal turns into finely powdered hydride. If the finely powdered hydrides are heated they decompose, giving hydrogen and very finely divided metal. These finely divided metals may be used as catalysts. They are also used in metallurgy in powder fabrication, and zirconium hydride has been used as a moderator in nuclear reactors.

In many cases the compounds are nonstoichiometric, for example  $\text{LaH}_n$ ,  $\text{TiH}_n$  and  $\text{PdH}_n$ , where the chemical composition is variable. Typical formulae are  $\text{LaH}_{2.87}$ ,  $\text{YbH}_{2.55}$ ,  $\text{TiH}_{1.8}$ ,  $\text{ZrH}_{1.9}$ ,  $\text{VH}_{1.6}$ ,  $\text{NbH}_{0.7}$  and  $\text{PdH}_{0.7}$ . Such compounds were originally called *interstitial hydrides*, and it was thought that a varying number of interstitial positions in the metal lattice could be filled by hydrogen.

The nonstoichiometric compounds may be regarded as solid solutions. Metals which can 'dissolve' varying amounts of hydrogen in this way can act as catalysts for hydrogenation reactions. The catalysts are thought to be effective through providing H atoms rather than  $\text{H}_2$  molecules. It is not certain whether the hydrogen is present in the interstitial sites as atoms of hydrogen, or alternatively as  $\text{H}^+$  ions with delocalized electrons, but they have strongly reducing properties.

Even small amounts of hydrogen dissolved in a metal adversely affect its strength and make it brittle. Titanium is extracted by reducing  $\text{TiCl}_4$  with Mg or Na in an inert atmosphere. If an atmosphere of  $\text{H}_2$  is used, the Ti dissolves  $\text{H}_2$ , and is brittle. Titanium is used to make supersonic aircraft, and since strength is important, it is produced in an atmosphere of argon.

The bonding is more complicated than was originally thought, and is still the subject of controversy.

1. Many of the hydrides have structures where hydrogen atoms occupy tetrahedral holes in a cubic close-packed array of metal atoms. If all of the tetrahedral sites are occupied then the formula is  $\text{MH}_2$ , and a fluorite structure is formed. Generally some sites are unoccupied, and hence the compounds contain less hydrogen. This accounts for the compounds of formula  $\text{MH}_{1.5-2}$  formed by the scandium and titanium groups, and most of the lanthanides and actinides.
2. Two of the lanthanide elements, europium and ytterbium, are unusual in that they form ionic hydrides  $\text{EuH}_2$  and  $\text{YbH}_2$ , which are stoichiometric and resemble  $\text{CaH}_2$ . The lanthanides are typically trivalent, but Eu and Yb form divalent ions (associated with stable electronic structures  $\text{Eu}(+II) 4f^7$  (half filled *f* shell), and  $\text{Yb}(+II) 4f^{14}$  (filled *f* shell)).
3. The compounds  $\text{YH}_2$  and  $\text{LaH}_2$ , as well as many of the lanthanide and actinide hydrides  $\text{MH}_2$ , can absorb more hydrogen, forming compounds of limiting composition  $\text{MH}_3$ . Compositions such as  $\text{LaH}_{2.76}$  and  $\text{CeH}_{2.69}$  are found. The structures of these are complex, sometimes cubic and sometimes hexagonal. The third hydrogen atom is more loosely held than the others, and rather surprisingly it may occupy an octahedral hole.

- 4 Uranium is unusual and forms two different crystalline forms of  $\text{UH}_3$  that are stoichiometric
- 5 Some elements (V, Nb, Ta, Cr, Ni and Pd) form hydrides approximating to  $\text{MH}$ . Formulae such as  $\text{NbH}_{0.7}$  and  $\text{PdH}_{0.6}$  are typical. These are less stable than the other hydrides, are nonstoichiometric and exist over a wide range of composition

The Pd/ $\text{H}_2$  system is both extraordinary and interesting. When red hot Pd is cooled in  $\text{H}_2$  it may absorb or occlude up to 935 times its own volume of  $\text{H}_2$  gas. This may be used to separate  $\text{H}_2$  or deuterium  $\text{D}_2$  from He or other gases. The hydrogen is given off when the metal is heated, and this provides an easy method of weighing  $\text{H}_2$ . The limiting formula is  $\text{PdH}_{0.7}$  but neither the structure nor the nature of the interaction between Pd and H are understood. As hydrogen is absorbed, the metallic conductivity decreases, and the material eventually becomes a semiconductor. The hydrogen is mobile and diffuses throughout the metal. It is possible that the erroneous reports of producing energy by 'cold fusion' by electrolysis of  $\text{D}_2\text{O}$  at room temperature between Pd electrodes was really energy from the reaction between Pd and  $\text{D}_2$  rather than nuclear fusion of hydrogen or deuterium to give helium (See Chapter 31)

### Intermediate hydrides

A few hydrides do not fit easily into the above classification. Thus  $(\text{BeH}_2)_n$  is polymeric, and is thought to be a chain polymer with hydrogen bridges.  $\text{MgH}_2$  has properties in between those of ionic and covalent hydrides.

$\text{CuH}$ ,  $\text{ZnH}_2$ ,  $\text{CdH}_2$  and  $\text{HgH}_2$  have properties intermediate between metallic and covalent hydrides. They are probably electron deficient like  $(\text{AlH}_3)_n$ .  $\text{CuH}$  is endothermic, that is energy must be put in to make the compound, and is formed by reducing  $\text{Cu}^{2+}$  with hypophosphorous acid. The hydrides of Zn, Cd and Hg are made by reducing the chlorides with  $\text{LiAlH}_4$ .

### THE HYDROGEN ION

The energy required to remove the electron from a hydrogen atom (i.e. the ionization energy of hydrogen) is  $1311 \text{ kJ mol}^{-1}$ . This is a very large amount of energy, and consequently the bonds formed by hydrogen in the gas phase are typically covalent. Hydrogen fluoride is the compound most likely to contain ionic hydrogen (i.e.  $\text{H}^+$ ), since it has the greatest difference in electronegativity, but even here the bond is only 45% ionic.

Thus compounds containing  $\text{H}^+$  will only be formed if the ionization energy can be provided by some other process. Thus if the compound is dissolved, for example in water, then the hydration energy may offset the very high ionization energy. In water  $\text{H}^+$  are solvated, forming  $\text{H}_3\text{O}^+$  and the energy evolved is  $1091 \text{ kJ mol}^{-1}$ . The remainder of the  $1311 \text{ kJ mol}^{-1}$  ionization energy comes from the electron affinity (the energy evolved in

forming the negative ion), and also the solvation energy of the negative ion.

Compounds which form solvated hydrogen ions in a suitable solvent are called acids. Even though the ions present are  $\text{H}_3\text{O}^+$  (or even  $\text{H}_9\text{O}_4^+$ ), it is customary to write the ion as  $\text{H}^+$ , indicating a hydrated proton.

## HYDROGEN BONDING

In some compounds a hydrogen atom is attracted by rather strong forces to two atoms, for example in  $[\text{F}-\text{H}-\text{F}]^-$ . (Sometimes hydrogen is attracted to more than two atoms.) It was at first thought that hydrogen formed two covalent bonds, but it is now recognized that, since hydrogen has the electronic structure  $1s^1$ , it can only form one covalent bond. The hydrogen bond is most simply regarded as a weak electrostatic attraction between a lone pair of electrons on one atom, and a covalently bonded hydrogen atom that carries a fractional charge  $\delta+$ .

Hydrogen bonds are formed only with the most electronegative atoms. (Of these, F, O, N and Cl are the four most important elements.) These bonds are very weak, and are typically about  $10 \text{ kJ mol}^{-1}$ , though hydrogen bonds may have a bond energy from 4 to  $45 \text{ kJ mol}^{-1}$ . This must be compared with a C—C covalent bond of  $347 \text{ kJ mol}^{-1}$ . Despite their low bond energy, hydrogen bonds are of great significance both in biochemical systems and in normal chemistry. They are extremely important because they are responsible for linking polypeptide chains in proteins, and for linking pairs of bases in large nucleic acid-containing molecules. The hydrogen bonds maintain these large molecules in specific molecular configurations, which is important in the operation of genes and enzymes. Hydrogen bonds are responsible for water being liquid at room temperature, and but for this, life as we know it would not exist. Since hydrogen bonds have a low bond energy, they also have a low activation energy, and this results in their playing an important part in many reactions at normal temperatures.

Hydrogen bonding was first used to explain the weakness of trimethylammonium hydroxide as a base compared with tetramethylammonium hydroxide. In the trimethyl compound the OH group is hydrogen bonded to the  $\text{Me}_3\text{NH}$  group (shown by a dotted line in Figure 8.4), and this makes it more difficult for the OH group to ionize, and hence it is a weak base. In the tetramethyl compound, hydrogen bonding cannot occur, so the OH group ionizes and the tetramethyl compound is thus a much stronger base.




Figure 8.4 Structures of trimethyl and tetramethyl ammonium hydroxide.




Figure 8 5 Structures of *ortho*, *meta* and *para* nitrophenol

In a similar way the formation of an intramolecular hydrogen bond in *o* nitrophenol reduces its acidity compared with *m* nitrophenol and *p*-nitrophenol, where the formation of a hydrogen bond is not possible (Figure 8 5)

Intermolecular hydrogen bonding may also take place, and it has a striking effect on the physical properties such as melting points, boiling points, and the enthalpies of vaporization and sublimation (Figure 8 6) In general the melting and boiling points for a related series of compounds increase as the atoms get larger, owing to the increase in dispersive force. Thus by extrapolating the boiling points of  $\text{H}_2\text{Te}$ ,  $\text{H}_2\text{Se}$  and  $\text{H}_2\text{S}$  one would predict that the boiling point of  $\text{H}_2\text{O}$  should be about  $-100^\circ\text{C}$ , whilst it is actually  $+100^\circ\text{C}$ . Thus water boils about  $200^\circ\text{C}$  higher than it would in the absence of hydrogen bonding.

In much the same way the boiling point of  $\text{NH}_3$  is much higher than would be expected by comparison with  $\text{PH}_3$ ,  $\text{AsH}_3$  and  $\text{SbH}_3$ , and similarly  $\text{HF}$  boils much higher than  $\text{HCl}$ ,  $\text{HBr}$  and  $\text{HI}$ . The reason for the higher than expected boiling points is hydrogen bonding. Note that the boiling points of the Group 14 hydrides  $\text{CH}_4$ ,  $\text{SiH}_4$ ,  $\text{GeH}_4$  and  $\text{SnH}_4$  change smoothly, as they do not involve hydrogen bonding.

The hydrogen bonds in  $\text{HF}$  link the F atom of one molecule with the H atom of another molecule, thus forming a zig-zag chain  $(\text{HF})_n$  in both the liquid and also in the solid (Figure 8 7). Some hydrogen bonding also occurs in the gas, which consists of a mixture of cyclic  $(\text{HF})_6$  polymers, dimeric  $(\text{HF})_2$ , and monomeric  $\text{HF}$ . (The hydrogen bond in  $\text{F}-\text{H} \cdots \text{F}$  is  $29 \text{ kJ mol}^{-1}$  in  $\text{HF}_{(\text{gas})}$ .)

A similar pattern can be seen in the melting points and the enthalpies of vaporization of the hydrides, indicating hydrogen bonding in  $\text{NH}_3$ ,  $\text{H}_2\text{O}$  and  $\text{HF}$ , but not in  $\text{CH}_4$  (Figure 8 6c).

Strong evidence for hydrogen bonding comes from structural studies. Examples include ice, which has been determined both by X-ray and neutron diffraction, the dimeric structure of formic acid (determined in the gas phase by electron diffraction), X-ray structures of the solids for sodium hydrogencarbonate and boric acid (Figure 8 8), and many others.

Another technique for studying hydrogen bonds is infra-red absorption spectra in  $\text{CCl}_4$  solution, which allows the  $\text{O}-\text{H}$  and  $\text{N}-\text{H}$  stretching frequencies to be studied.

## ACIDS AND BASES

There are several so called *theories* of acids and bases, but they are not really theories but merely different definitions of what we choose to call an acid or a base. Since it is only a matter of definition, no theory is more right or wrong than any other, and we use the most convenient theory for a particular chemical situation. Which is the most useful theory or definition of acids and bases? There is no simple answer to this. The answer depends

on whether we are considering ionic reactions in aqueous solution, in non-aqueous solution, or in a fused melt, and whether we require a measure of the strengths of acids and bases. For this reason we need to know several theories.





Figure 8.6 (a) Boiling points of hydrides. (b) Melting points of hydrides. (c) Enthalpies of vaporization of hydrides. (Adapted from Lagowski, J.J., *Modern Inorganic Chemistry*, Marcel Dekker, New York, p. 174.)




Figure 8.6 continued




Figure 8.7 Hydrogen bonded chain in solid HF

### Arrhenius theory

In the early stages of chemistry, acids were distinguished by their sour taste and their effect on certain plant pigments such as litmus. Bases were substances which reacted with acids to form salts. Water was used almost exclusively for reactions in solution, and in 1884 Arrhenius suggested the theory of electrolytic dissociation and proposed the self-ionization of water.








Figure 8.8 Hydrogen bonded structures. (a) Formic acid dimer,  $(\text{HCOOH})_2$ . (b) Ice (From L. Pauling, *The Nature of the Chemical Bond*, 3rd ed., pp. 449–504, Cornell University Press, Ithaca, 1960.) (c) A layer of crystalline  $\text{H}_3\text{BO}_3$ .



Thus substances producing  $\text{H}^+$  were called acids, and substances producing  $\text{OH}^-$  were called bases. A typical neutralization reaction is



or simply



In aqueous solutions the concentration of  $\text{H}^+$  is often given in terms of pH, where

$$\text{pH} = \log_{10} \frac{1}{[\text{H}^+]} = -\log_{10}[\text{H}^+]$$


where  $[\text{H}^+]$  is the hydrogen ion concentration. More strictly the activity of the hydrogen ions should be used. This logarithmic scale was introduced by S. P. L. Sørensen in 1909. It then is very useful for expressing concentrations over several orders of magnitude (e.g.  $1\text{M H}^+$  is pH 0,  $10^{-14}\text{M H}^+$  is pH 14).

Until the turn of the nineteenth century it was thought that water was the only solvent in which ionic reactions could occur. Studies made by Cady in 1897 and by Franklin and Kraus in 1898 on reactions in liquid ammonia, and by Walden in 1899 on reactions in liquid sulphur dioxide, revealed many analogies with reactions in water. These suggested that the three media were ionizing solvents and could be useful for ionic reactions, and that acids, bases and salts were common to all three systems.

Although water is still the most widely used solvent, its exclusive use limited chemistry to those compounds which are stable in its presence. Non-aqueous solvents are now used increasingly in inorganic chemistry because many new compounds can be prepared which are unstable in water, and some anhydrous compounds can be prepared, such as anhydrous copper nitrate, which differ markedly from the well known hydrated form. The concepts of acids and bases based on the aqueous system need extending to cover non aqueous solvents.

#### Acids and bases in proton solvents

Water self-ionizes



The equilibrium constant for this reaction depends on the concentration of water  $[\text{H}_2\text{O}]$ , and on the concentrations of the ions  $[\text{H}_3\text{O}^+]$  and  $[\text{OH}^-]$

$$K_1 = \frac{[\text{H}_3\text{O}^+][\text{OH}^-]}{[\text{H}_2\text{O}]^2}$$

Since water is in large excess, its concentration is effectively constant, so the ionic product of water may be written


$$K_w = [\text{H}_3\text{O}^+][\text{OH}^-] = 10^{-14} \text{ mol}^2 \text{ l}^{-2}$$

The value of  $K_w$  is  $1.00 \times 10^{-14} \text{ mol}^2 \text{ l}^{-2}$  at  $25^\circ\text{C}$ , but it varies with temperature. Thus at  $25^\circ\text{C}$  there will be  $10^{-7} \text{ mol l}^{-1}$  of  $\text{H}_3\text{O}^+$  and  $10^{-7} \text{ mol l}^{-1}$  of  $\text{OH}^-$  in pure water.

**Table 8.4** Ionic product of water at various temperatures

Temperature ( $^\circ\text{C}$ )	$K_w(\text{mol}^2 \text{ l}^{-2})$
0	$0.12 \times 10^{-14}$
10	$0.29 \times 10^{-14}$
20	$0.68 \times 10^{-14}$
25	$1.00 \times 10^{-14}$
30	$1.47 \times 10^{-14}$
40	$2.92 \times 10^{-14}$
100	$47.6 \times 10^{-14}$

Acids such as HA increase the concentration of  $\text{H}_3\text{O}^+$ :



$$K_w = \frac{[\text{H}_3\text{O}^+][\text{A}^-]}{[\text{HA}][\text{H}_2\text{O}]}$$

In dilute solution water is in such a large excess that the concentration of water is effectively constant (approximately 55M), and this constant can be incorporated in the constant at the left hand side. Thus:

$$K_a = \frac{[\text{H}_3\text{O}^+][\text{A}^-]}{[\text{HA}]}$$

**Table 8.5** Relation between pH,  $[\text{H}^+]$  and  $[\text{OH}^-]$

pH	$[\text{H}^+] (\text{mol l}^{-1})$	$[\text{OH}^-] (\text{mol l}^{-1})$	
0	$10^0$	$10^{-14}$	} Acidic
1	$10^{-1}$	$10^{-13}$	
2	$10^{-2}$	$10^{-12}$	
3	$10^{-3}$	$10^{-11}$	
4	$10^{-4}$	$10^{-10}$	
5	$10^{-5}$	$10^{-9}$	
6	$10^{-6}$	$10^{-8}$	} Neutral
7	$10^{-7}$	$10^{-7}$	
8	$10^{-8}$	$10^{-6}$	} Basic
9	$10^{-9}$	$10^{-5}$	
10	$10^{-10}$	$10^{-4}$	
11	$10^{-11}$	$10^{-3}$	
12	$10^{-12}$	$10^{-2}$	
13	$10^{-13}$	$10^{-1}$	
14	$10^{-14}$	$10^0$	

The pH scale is used to measure the activity of hydrogen ions ( $\text{pH} = -\log[\text{H}^+]$ ) and it refers to the number of powers of ten used to express the concentration of hydrogen ions. In a similar way the acid dissociation constant  $K_a$  may be expressed as a  $\text{p}K_a$  value

$$\text{p}K_a = \log \frac{1}{K_a} = -\log K_a$$


Thus  $\text{p}K_a$  is a measure of the strength of an acid. If the acid ionizes almost completely (high acid strength) then  $K_a$  will be large and thus  $\text{p}K_a$  will be small. The  $\text{p}K_a$  values given below show that acid strength increases on moving from left to right in the periodic table.

	$\text{CH}_4$	$\text{NH}_3$	$\text{H}_2\text{O}$	$\text{HF}$
$\text{p}K_a$	46	35	16	3

Acid strength also increases on moving down a group

	$\text{HF}$	$\text{HCl}$	$\text{HBr}$	$\text{HI}$
$\text{p}K_a$	3	-7	-9	-10

With oxoacids containing more than one hydrogen atom successive dissociation constants rapidly become more positive i.e. the phosphate species formed on successive removal of  $\text{H}^+$  become less acidic




If an element forms a series of oxoacids then the more oxygen atoms present the more acidic it will be. The reason for this is that the electrostatic attraction for the proton decreases as the negative charge is spread over more atoms thus facilitating ionization.

<i>very weak acid</i>	<i>weak acid</i>	<i>strong acid</i>	<i>very strong acid</i>
$\text{HNO}_2$ $\text{p}K_a = 3.3$	$\text{HNO}_3$ $\text{p}K_a = -1.4$		
$\text{H}_2\text{SO}_3$ $\text{p}K_a = 1.9$	$\text{H}_2\text{SO}_4$ $\text{p}K_a = (-1)$		
$\text{HOCl}$ $\text{p}K_a = 7.2$	$\text{HClO}$ $\text{p}K_a = 2.0$	$\text{HClO}_2$ $\text{p}K_a = -1$	$\text{HClO}_4$ $\text{p}K_a = (-10)$

### Bronsted-Lowry theory

In 1923 Bronsted and Lowry independently defined acids as proton donors and bases as proton acceptors




For aqueous solutions this definition does not differ appreciably from the Arrhenius theory. Water self ionizes as shown above. Substances that increase the concentration of  $[\text{H}_3\text{O}]^+$  in an aqueous solution above the


value of  $10^{-7} \text{ mol}^2 \text{ l}^{-2}$  from the self-ionization are acids, and those that decrease it are bases.

The Bronsted-Lowry theory is useful in that it extends the scope of acid-base systems to cover solvents such as liquid ammonia, glacial acetic acid, anhydrous sulphuric acid, and all hydrogen-containing solvents. It should be emphasized that bases accept protons, and there is no need for them to contain  $\text{OH}^-$ .


In liquid ammonia:




or simply:




Similarly in sulphuric acid:



Chemical species that differ in composition only by a proton are called 'a conjugate pair'. Thus every acid has a conjugate base, which is formed when the acid donates a proton. Similarly every base has a conjugate acid.




In water



In the above reaction, HCl is an acid since it donates protons, and in doing so forms  $\text{Cl}^-$ , its conjugate base. Since  $\text{H}_2\text{O}$  accepts protons it is a base, and forms  $\text{H}_3\text{O}^+$ , its conjugate acid. A strong acid has a weak conjugate base and vice versa.

In liquid ammonia:



In liquid ammonia all ammonium salts act as acids since they can donate protons, and the sulphide ion acts as a base since it accepts protons. The

reaction is reversible, and it will proceed in the direction that produces the weaker species, in this case  $\text{HS}^-$  and  $\text{NH}_3$


*A limitation of the Bronsted-Lowry theory is that the extent to which a dissolved substance can act as an acid or a base depends largely on the solvent. The solute only shows acidic properties if its proton donating properties exceed those of the solvent. This sometimes upsets our traditional ideas on what are acids, which are based on our experience of what happens in water. Thus  $\text{HClO}_4$  is an extremely strong proton donor. If liquid  $\text{HClO}_4$  is used as a solvent, then  $\text{HF}$  dissolved in this solvent is forced to accept protons, and thus act as a base*




In a similar way  $\text{HNO}_3$  is forced to accept protons and thus act as a base in both  $\text{HClO}_4$  and liquid  $\text{HF}$  as solvent

Water has only a weak tendency to donate protons. The mineral acids ( $\text{HCl}$ ,  $\text{HNO}_3$ ,  $\text{H}_2\text{SO}_4$  etc.) all have a much stronger tendency to donate protons. Thus in aqueous solutions the mineral acids all donate protons to the water, thus behaving as acids, and in the process the mineral acids ionize completely


In liquid ammonia as solvent, the acids which were strong acids in water all react completely with the ammonia, forming  $\text{NH}_4^+$




Acids which were slightly less strong in water also react completely with  $\text{NH}_3$ , forming  $\text{NH}_4^+$



Weak acids in water, such as oxalic acid, also react completely with  $\text{NH}_3$




The acid strengths have all been levelled by the solvent liquid ammonia hence liquid ammonia is called a levelling solvent. It even makes some molecules, such as urea, which show no acidic properties in water, behave as weak acids




Differentiating solvents such as glacial acetic acid emphasize the difference in acid strength, and several mineral acids are only partially ionized in this solvent. This is because acetic acid itself is a proton donor, and if a substance dissolved in acetic acid is to behave as an acid, it must donate protons more strongly than acetic acid. Thus the dissolved material must force the acetic acid to accept protons (i.e. the acetic acid behaves as a base). Thus the solvent acetic acid makes it more difficult for the usual acids to ionize, and conversely it will encourage the usual bases to ionize completely. It follows that a differentiating solvent for acids will act as a levelling solvent for bases, and vice versa

### Lewis theory

Lewis developed a definition of acids and bases that did not depend on the presence of protons, nor involve reactions with the solvent. He defined acids as materials which accept electron pairs, and bases as substances which donate electron pairs. Thus a proton is a Lewis acid and ammonia is a Lewis base since the lone pair of electrons on the nitrogen atom can be donated to a proton:






Similarly hydrogen chloride is a Lewis acid because it can accept a lone pair from a base such as water though this is followed by ionization:



Though this is a more general approach than that involving protons, it has several drawbacks:

1. Many substances, such as  $\text{BF}_3$  or metal ions, that are not normally regarded as acids, behave as Lewis acids. This theory also includes reactions where no ions are formed, and neither hydrogen ions nor any other ions are transferred (e.g.  $\text{Ni}(\text{CO})_4$ ).

acid      base




2. There is no scale of acid or basic strength, since the strength of an acid or a base compound is not constant, and varies from one solvent to another, and also from one reaction to another.
3. Almost all reactions become acid–base reactions under this system.

### The solvent system

Perhaps the most convenient general definition of acids and bases is due to Cady and Elsey, and can be applied in all cases where the solvent undergoes self-ionization, regardless of whether it contains protons or not.


Many solvents undergo self-ionization, and form positive and negative ions in a similar way to water:




Acids are defined as substances that increase the concentration of the positive ions characteristic of the solvent ( $\text{H}_3\text{O}^+$  in the case of water,  $\text{NH}_4^+$  in liquid ammonia, and  $\text{NO}^+$  in  $\text{N}_2\text{O}_4$ ). Bases are substances that increase the concentration of the negative ions characteristic of the solvent ( $\text{OH}^-$  in water,  $\text{NH}_2^-$  in ammonia,  $\text{NO}_3^-$  in  $\text{N}_2\text{O}_4$ ).

There are two advantages to this approach. First, most of our traditional ideas on what are acids and bases in water remain unchanged, as do neutralization reactions. Second, it allows us to consider non aqueous solvents by analogy with water.


Thus water ionizes, giving  $\text{H}_3\text{O}^+$  and  $\text{OH}^-$  ions. Substances providing  $\text{H}_3\text{O}^+$  (e.g.  $\text{HCl}$ ,  $\text{KNO}_3$  and  $\text{H}_2\text{SO}_4$ ) are acids, and substances providing  $\text{OH}^-$  (e.g.  $\text{NaOH}$  and  $\text{NH}_4\text{OH}$ ) are bases. Neutralization reactions are of the type *acid + base  $\rightarrow$  salt + water*.



Similarly liquid ammonia ionizes, giving  $\text{NH}_4^+$  and  $\text{NH}_2^-$  ions. Thus ammonium salts are acids since they provide  $\text{NH}_4^+$  ions, and sodamide  $\text{NaNH}_2$  is a base since it provides  $\text{NH}_2^-$  ions. Neutralization reactions are of the type *acid + base  $\rightarrow$  salt + solvent*.




$\text{N}_2\text{O}_4$  self ionizes into  $\text{NO}^+$  and  $\text{NO}_3^-$  ions. Thus in  $\text{N}_2\text{O}_4$  as solvent,  $\text{NOCl}$  is an acid since it produces  $\text{NO}^+$ , and  $\text{NaNO}_3$  is a base since it produces  $\text{NO}_3^-$ .



Clearly this definition applies equally well to proton and non proton systems. This broader definition also has advantages when considering protonic solvents, since it explains why the acidic or basic properties of a solute are not absolute, and depend in part on the solvent. We normally regard acetic acid as an acid, because in water it produces  $\text{H}_3\text{O}^+$ .




However, acetic acid behaves as a base when sulphuric acid is the solvent since  $\text{H}_2\text{SO}_4$  is a stronger proton donor than  $\text{CH}_3\text{COOH}$ . In a similar way  $\text{HNO}_3$  is forced to behave as a base in  $\text{H}_2\text{SO}_4$  as solvent, and this is important in producing nitronium ions  $\text{NO}_2^+$  in the nitration of organic compounds by a mixture of concentrated  $\text{H}_2\text{SO}_4$  and  $\text{HNO}_3$ .






### The Lux–Flood definition

Lux originally proposed a different definition of acids and bases which was extended by Flood. Instead of using protons, or ions characteristic of the solvent, they defined acids as oxides which accept oxygen, and bases as oxides which donate oxygen. Thus:



This system is very useful in dealing with anhydrous reactions in fused melts of oxides, and other high temperature reactions such as are found in metallurgy and ceramics.

This theory has an inverse relationship to aqueous chemistry, since Lux–Flood acids are oxides which react with water, giving bases in water, and Lux–Flood bases react with water, giving acids.



### The Usanovich definition

This defines an acid as any chemical species which reacts with bases, gives up cations, or accepts anions or electrons. Conversely a base is any chemical species which reacts with acids, gives up anions or electrons, or combines with cations. This is a very wide definition and includes all the Lewis acid–base type of reactions, and in addition it includes redox reactions involving the transfer of electrons.

### Hard and soft acids and bases

Metal ions may be divided into two types depending on the strength of their complexes with certain ligands.

*Type (a) metals* include the smaller ions from Groups 1 and 2, and the left hand side of the transition metals, particularly when in high oxidation states, and these form the most stable complexes with nitrogen and oxygen donors (ammonia, amines, water, ketones, alcohols), and also with  $\text{F}^-$  and  $\text{Cl}^-$ .

*Type (b) metals* include ions from the right hand side of the transition series, and also transition metal complexes with low oxidation states, such as the carbonyls. These form the most stable complexes with ligands such as  $\text{I}^-$ ,  $\text{SCN}^-$  and  $\text{CN}^-$ .

This empirical classification was useful in predicting the relative stabilities of complexes. Pearson extended the concept into a broad range of acid–base interactions. Type (a) metals are small and not very polariz-

Table 8.6 Some hard and soft acids and bases

<i>Hard acids</i>	<i>Soft acids</i>
$H^+$	$Pd^{2+}, Pt^{2+}, Cu^+, Ag^+, Au^+, Hg^{2+}$
$Li^+, Na^+, K^+,$	$(Hg_2)^{2+}, Tl^+$
$Be^{2+}, Mg^{2+}, Ca^{2+}, Sr^{2+},$	$B(CH_3)_3, B_2H_6, Ga(CH_3)_3, GaCl_3,$
$Al^{3+}, BF_3, Al(CH_3)_3, AlCl_3,$	$GaBr_3, GaI_3$
$Sc^{3+}, Ti^{4+}, Zr^{4+}, VO^{2+}, Cr^{3+},$	$[Fe(CO)_5], [Co(CN)_5]^{1-}$
$MoO^{3+}, WO^{4+},$	
$Ce^{3+}, Lu^{3+}$	
$CO_2, SO_3$	
<i>Hard bases</i>	<i>Soft bases</i>
$NH_3, RNH_2, N_2H_4$	$H^-, CN^-, SCN^-, S_2O_3^{2-}, I^-, RS^-,$
$H_2O, ROH, R_2O$	$R_2S, CO, B_2H_6, C_2H_4, R_3P, P(OR)_3$
$OH^-, NO_2^-, ClO_4^-, CO_3^{2-}, SO_4^{2-},$	
$PO_4^{3-}, CH_3COO^-, F^-, Cl^-$	

able, and these prefer ligands that are also small and not very polarizable. Pearson called these metals hard acids, and the ligands hard bases. In a similar way, type (b) metals and the ligands they prefer are larger and more polarizable, and he called these soft acids and soft bases. He stated the relationship *hard acids prefer to react with hard bases, and soft acids react with soft bases*. This definition takes in the usually accepted acid-base reactions ( $H^+$  strong acid,  $OH^-$  and  $NH_3$  strong bases), and in addition a great number of reactions involving the formation of simple complexes, and complexes with  $\pi$  bonding ligands.

## FURTHER READING

### Hydrogen

- Brown, H. C. (1979) Hydride reductions. A 40 year revolution in organic chemistry, *Chem. Eng. News*, March 5, 24-29.
- Emeléus, H. J. and Sharpe, A. G. (1973) *Modern Aspects of Inorganic Chemistry*, 4th ed. (Chapter 8: Hydrogen and the Hydrides), Routledge and Kegan Paul, London.
- Evans, E. A. (1974) *Tritium and its Compounds*, 2nd ed., Butterworths, London (Contains over 4000 references).
- Grant, W. J. and Redfearn, S. L. (1977) Industrial gases, in *The Modern Inorganic Chemicals Industry* (ed. Thompson, R.), The Chemical Society, London. Special Publication no. 31.
- Jolly, W. L. (1976) *The Principles of Inorganic Chemistry*, (Chapters 4 and 5) McGraw Hill, New York.
- Mackay, K. M. (1966) *Hydrogen Compounds of the Metallic Elements*, Spon, London.
- Mackay, K. M. (1973) *Comprehensive Inorganic Chemistry*, Vol. 1 (Chapter 1: The element hydrogen, Chapter 2: Hydrides), Pergamon Press, Oxford.

- Mackay, K.M. and Dove, M.F.A. (1973) *Comprehensive Inorganic Chemistry*, Vol. 1 (Chapter 3: Deuterium and Tritium), Pergamon Press, Oxford.
- Moore, D.S. and Robinson, S.D. (1983) Hydrido complexes of the transition metals, *Chem. Soc. Rev.*, **12**, 415–452.
- Muetterties, E.L. (1971) *Transition Metal Hydrides*, Marcel Dekker, New York.
- Sharpe, A.G. (1981) *Inorganic Chemistry* (Chapter 9), Longmans, London.
- Stinson, S.C. (1980) Hydride reducing agents, use expanding, *Chem. Eng. News*, Nov 3, 18–20.
- Wiberg, E. and Amberger, E. (1971) *Hydrides*, Elsevier.

### The hydrogen economy

- McAuliffe, C.A. (1973) The hydrogen economy, *Chemistry in Britain*, **9**, 559–563.
- Marchetti, C. (1977) The hydrogen economy and the chemist, *Chemistry in Britain*, **13**, 219–222.
- Williams, L.O. (1980) *Hydrogen Power: An Introduction to Hydrogen Energy and Its Applications*, Pergamon Press, Oxford.

### Hydrogen bonding

- Coulson, C. A. (1979) *Valence*, Oxford University Press, Oxford. 3rd ed. by McWeeny, R. (This is an updated version of Coulson's 1952 book.)
- DeKock, R.L. and Gray, H.B. (1980) *Chemical Structure and Bonding*, Benjamin/Cummins, Menlo Park, California.
- Douglas, B., McDaniel, D.H. and Alexander, J.J. (1982) *Concepts and Models of Inorganic Chemistry*, 2nd ed (Chapter V: The Hydrogen Bond), John Wiley, New York.
- Emsley, J. (1980) Very strong hydrogen bonds, *Chem. Soc. Rev.*, **9**, 91–124.
- Joesten, M.D. and Schaad, L.J. (1974) *Hydrogen Bonding*, Marcel Dekker, New York.
- Pauling, L. (1960) *The Nature of the Chemical Bond* (Chapter 12), 3rd ed., Oxford University Press, London.
- Pimentel, G.C. and McClellan, A.L. (1960) *The Hydrogen Bond*, W.H. Freeman, San Francisco. (A well written monograph, with over 2200 references. Dated but thorough.)
- Vinogradov, S.N. and Linnell, R.H. (1971) *Hydrogen Bonding*, Van Nostrand Reinhold, New York. (Good general treatment.)
- Wells, A.F. (1984) *Structural Inorganic Chemistry*, 5th ed., Oxford University Press, Oxford.

### Acids and bases

- Bell, R.P. (1973) *The Proton in Chemistry*, 2nd ed., Chapman and Hall, London.
- Bronsted, J.N. (1923) *Rec. Trav. Chim.*, **42**, 718. (Original paper on the Bronsted theory.)
- Cady, H.P and Elsey, H.M. (1928) A general definition of acids, bases and salts, *J. Chem. Ed.*, **5**, 1425. (Original paper on the solvent system.)
- Drago, R.S. (1974) A Modern approach to acid–base chemistry, *J. Chem. Ed.*, **51**, 300.
- Finston, H.L and Rychtman, A.C. (1982) *A New View of Current Acid–Base Theories*, John Wiley, Chichester.
- Fogg, P.G.T. and Gerrard, W. (eds) (1990) *Hydrogen Halides in Non-Aqueous Solvents*, Pergamon, New York.
- Gillespie, R.J. (1973) The chemistry of the superacid system, *Endeavour*, **32**, 541.

- Gillespie, R J (1975) Proton acids, Lewis acids, hard acids, soft acids and super acids, Chapter 1 in *Proton Transfer Reactions* (ed Caldin E and Gold, V) Chapman and Hall, London
- Hand, C W and Blewitt, H L (1986) *Acid-Base Chemistry*, Macmillan, New York, Collier Macmillan, London
- Huheey, J E (1978) *Inorganic Chemistry*, 2nd ed (Chapter 7), Harper and Row New York
- Jensen, W B (1980) *The Lewis Acid-Base Concepts*, Wiley, New York and Chichester
- Koltoff I M and Elving, P J (1986) (eds), *Treatise on Analytical Chemistry*, 2nd ed Vol 2 Part 1, Wiley, Chichester, 157-440
- Olah G A Surya Prakask, G K, and Sommer, J (1985) *Superacids*, Wiley Chichester and Wiley-Interscience, New York
- Pearson, R G (1987) Recent advances in the concept of hard and soft acids and bases *J Chem Ed* 64, 561-567
- Smith, D W (1987) An acidity scale for binary oxides, *J Chem Ed*, 64, 480-481
- Vogel A I, Jeffery, G H, Bassett, J, Mendham, J and Denney, R C (1990) *Vogel's Textbook of Quantitative Chemical Analysis*, 5th ed, Halstead Press (Indicators acid-base titrations, weak acids and bases, buffers etc)

### Water and solutions

- Burgess, J (1988) *Ions in Solution*, Ellis Horwood, Chichester
- Franks, F (1984) *Water*, 1st revised ed, Royal Society for Chemistry, London
- Hunt J P and Friedman, H L (1983) Aquo complexes of metal ions, *Progr in Inorg Chem*, 30, 359-387
- Murrell J N and Boucher E A (1982) *Properties of Liquids and Solutions*, John Wiley, Chichester
- Nielson G W and Enderby, J E (eds) (1986) *Water and Aqueous Solutions* Colston Research Society 37th Symposium (University of Bristol), Adam Hilger, Bristol
- Symons M C R (1989) Liquid water - the story unfolds, *Chemistry in Britain* 25, 491-494

### Non-aqueous solvents

- Addison C C (1980) Dinitrogen tetroxide, nitric acid and their mixtures as media for inorganic reactions, *Chem Rev*, 80, 21-39
- Addison, C C (1984) *The Chemistry of the Liquid Alkali Metals*, John Wiley Chichester
- Burger, K (1983) *Ionic Solvation and Complex Formation Reactions in Non Aqueous Solvents*, Elsevier, New York
- Emeléus H J and Sharpe, A G (1973) *Modern Aspects of Inorganic Chemistry*, 4th ed (Chapter 7 Reactions in Non-Aqueous Solvents, Chapter 8 Hydrogen and the hydrides), Routledge and Kegan Paul, London
- Gillespie, R J and Robinson E A (1959) The sulphuric acid solvent system, *Adv Inorg Chem Radiochem*, 1, 385
- Lagowski, J (ed) (1978) *The Chemistry of Non aqueous Solvents*, Academic Press, New York
- Nicholls, D (1979) *Inorganic Chemistry in Liquid Ammonia* (Topics in Inorganic and General Chemistry, Monograph 17), Elsevier, Oxford
- Popovych, O and Tomkins, R P T (1981) *Non Aqueous Solution Chemistry* Wiley, Chichester
- Waddington T C (ed) (1969) *Non Aqueous Solvent Systems*, Nelson

## PROBLEMS

1. Suggest reasons for and against the inclusion of hydrogen in the main groups of the periodic table.
2. Describe four ways in which hydrogen is produced on an industrial scale. Give one convenient method of preparing hydrogen in the laboratory.
3. Give an account of the main uses of hydrogen.
4. Give equations to show the reaction of hydrogen with: (a) Na, (b) Ca, (c) CO, (d) N, (e) S, (f) Cl, (g) CuO.
5. Describe the different types of hydrides which are formed.
6. Give examples of six proton solvents other than water, and show how they self-ionize.
7. What species are characteristic of acids and of bases in the following solvents: (a) liquid ammonia, anhydrous acetic acid, (b) anhydrous nitric acid, (c) anhydrous HF, (d) anhydrous perchloric acid, (e) anhydrous sulphuric acid, (f) dinitrogen tetroxide.
8. Describe how the various physical properties of a liquid affect its usefulness as a solvent.
9. How are the properties of  $\text{H}_2\text{O}$ ,  $\text{NH}_3$  and HF affected by hydrogen bonding?
10. Explain the variation in boiling points of the hydrogen halides (HF  $20^\circ\text{C}$ , HCl  $-85^\circ\text{C}$ , HBr  $-67^\circ\text{C}$  and HI  $-36^\circ\text{C}$ ).
11. Discuss the theoretical background, practical uses and theoretical limitations of liquid hydrogen fluoride as a non-aqueous solvent. List materials which behave as acids and bases in this solvent, and explain what happens when  $\text{SbF}_5$  is dissolved in HF.
12. Discuss the theoretical background, practical uses and limitations of liquid ammonia non-aqueous solvent. Explain what happens when  $^{15}\text{NH}_4\text{Cl}$  is dissolved in unlabelled liquid ammonia and the solvent evaporated.

# The *s*-Block Elements

## Part Two

# Group 1 – the alkali metals

9

Table 9.1 Electronic structures

Element	Symbol	Electronic structure
Lithium	Li	$1s^2 2s^1$ or [He] $2s^1$
Sodium	Na	$1s^2 2s^2 2p^6 3s^1$ or [Ne] $3s^1$
Potassium	K	$1s^2 2s^2 2p^6 3s^2 3p^6 4s^1$ or [Ar] $4s^1$
Rubidium	Rb	$1s^2 2s^2 2p^6 3s^2 3p^6 3d^{10} 4s^2 4p^6 5s^1$ or [Kr] $5s^1$
Caesium	Cs	$1s^2 2s^2 2p^6 3s^2 3p^6 3d^{10} 4s^2 4p^6 4d^{10} 5s^2 5p^6 6s^1$ or [Xe] $6s^1$
Francium	Fr	[Rn] $7s^1$

## INTRODUCTION

The elements of Group 1 illustrate, more clearly than any other group of elements, the effects of increasing the size of atoms or ions on the physical and chemical properties. They form a closely related group, and probably have the least complicated chemistry of any group in the periodic table. The physical and chemical properties of the elements are closely related to their electronic structures and sizes. The elements are all metals, excellent conductors of electricity, and typically soft and highly reactive. They have one loosely held valence electron in their outer shell, and typically form univalent, ionic and colourless compounds. The hydroxides and oxides are very strong bases, and the oxosalts are very stable.

Lithium, the first element in the group, shows considerable differences from the rest of the group. In all of the main groups the first element shows a number of differences from the later elements in the group.

Sodium and potassium together make up over 4% by weight of the earth's crust. Their compounds are very common, and have been known and used from very early times. Some of their compounds are used in very large amounts. World production of NaCl was 183.5 million tonnes in 1992 (most was used to make NaOH and  $Cl_2$ ); 38.7 million tonnes of NaOH were produced in 1994. About 31.5 million tonnes/year of  $Na_2CO_3$  is used, and  $NaHCO_3$ ,  $Na_2SO_4$  and NaOCl are also of industrial importance. World production of potassium salts (referred to as 'potash' and measured as  $K_2O$ ) was 24.5 million tonnes in 1992. Much of it was used as fertilizer, but KOH,  $KNO_3$  and  $K_2O$  are also important. In addition

sodium and potassium are essential elements for animal life. The metals were first isolated by Humphrey Davy in 1807 by the electrolysis of KOH and NaOH.

### OCCURRENCE AND ABUNDANCE

Despite their close chemical similarity, the elements do not occur together mainly because their ions are of different size.

Lithium is the thirty-fifth most abundant element by weight and is

**Table 9.2** Abundance of the elements in the earth's crust, by weight

	Abundance in earth's crust		Relative abundance
	(ppm)	(%)	
Li	18	0.0018	35
Na	22 700	2.27	7
K	18 400	1.84	8
Rb	78	0.0078	23
Cs	2.6	0.00026	46

mainly obtained as the silicate minerals, spodumene  $\text{LiAl}(\text{SiO}_3)_2$ , and lepidolite  $\text{Li}_2\text{Al}_2(\text{SiO}_3)_3(\text{FOH})_2$ . World production of lithium minerals was 8900 tonnes in 1992. The main sources are the Soviet Union 36%, Australia 34%, China 12%, Zimbabwe 10%, Chile 9%, and Canada 8%.

Sodium and potassium are the seventh and eighth most abundant elements by weight in the earth's crust. NaCl and KCl occur in large amounts in sea water. The largest source of sodium is rock salt (NaCl). Various salts including NaCl,  $\text{Na}_2\text{B}_4\text{O}_7 \cdot 10\text{H}_2\text{O}$  (borax),  $\text{Na}_2\text{CO}_3$ ,  $\text{NaHCO}_3 \cdot 2\text{H}_2\text{O}$  (trona),  $\text{NaNO}_3$  (saltpetre) and  $\text{Na}_2\text{SO}_4$  (mirabilite) are obtained from deposits formed by the evaporation of ancient seas such as the Dead Sea and the Great Salt Lake at Utah, USA. Sodium chloride is extremely important and is used in larger tonnages than any other chemical. World production was 183.5 million tonnes in 1992. The main sources are the USA 19%, China 10%, the Soviet Union 9%, India 7%, Germany 8%, Canada 6%, the UK and Australia 5% each, and France and Mexico 4% each. In most places it is mined as rock salt. In the UK (the Cheshire salt field) about 75% is extracted in solution as brine, and similarly in Germany over 70% is extracted as brine. 'Solar' salt is obtained by evaporating sea water in some hot countries. Ninety-two per cent of the salt produced in India is by evaporation, and 26% of that from Spain and France. This method is also used in Australia.


Potassium occurs mainly as deposits of KCl (sylvite), a mixture of KCl and NaCl (sylvinites), and the double salt  $\text{KCl} \cdot \text{MgCl}_2 \cdot 6\text{H}_2\text{O}$  (carnallite). Soluble potassium salts are collectively called 'potash'. World production of potash was 34.5 million tonnes in 1992, measured as  $\text{K}_2\text{O}$ . The main



sources are from mined deposits (the Soviet Union 35%, Canada 25%, Germany 18%, France and the USA 5% each and Israel 4%). Large amounts are recovered from brines such as the Dead Sea (Jordan) and the Great Salt Lake (Utah USA), where the concentration may be 20–25 times higher than in sea water, but it is not economic to recover potassium salts from 'normal' sea water.

There is no convenient source of rubidium and only one of caesium and these elements are obtained as by-products from lithium processing.

All of the elements heavier than bismuth (atomic number 83)  $_{83}\text{Bi}$  are radioactive. Thus francium (atomic number 89) is radioactive, and as it has a short half life period of 21 minutes it does not occur appreciably in nature. Any that existed when the earth was formed will have disappeared, and any formed now from actinium will have a transitory existence.



## EXTRACTION OF THE METALS

The metals of this group are too reactive to be found in the free state. Their compounds are amongst the most stable to heat, so thermal decomposition is impractical. Since the metals are at the top of the electrochemical series they react with water, so displacement of one element from solution by another higher in the electrochemical series will be unsuccessful. The metals are the strongest chemical reducing agents known, and so cannot be prepared by reducing the oxides. Electrolysis of aqueous solutions in order to obtain the metal is also unsuccessful unless a mercury cathode is used, when it is possible to obtain amalgams, but recovery of the pure metal from the amalgam is difficult.

The metals may all be isolated by electrolysis of a fused salt, usually the fused halide, often with impurity added to lower the melting point.

Sodium is made by the electrolysis of a molten mixture of about 40% NaCl and 60%  $\text{CaCl}_2$  in a Downs cell (Figure 9.1). This mixture melts at about  $600^\circ\text{C}$  compared with  $803^\circ\text{C}$  for pure NaCl. The small amount of calcium formed during the electrolysis is insoluble in the liquid sodium, and dissolves in the eutectic mixture. There are three advantages to electrolysis of a mixture.

1. It lowers the melting point and so reduces the fuel bill.
2. The lower temperature results in a lower vapour pressure for sodium, which is important as sodium vapour ignites in air.
3. At the lower temperature the liberated sodium metal does not dissolve in the melt, and this is important because if it dissolved it would short-circuit the electrodes and thus prevent further electrolysis.

*continued overleaf*




Figure 9.1 Downs cell for the production of sodium

A Downs cell comprises a cylindrical steel vessel lined with firebrick measuring about 2.5 m in height and 1.5 m in diameter. The anode is a graphite rod in the middle and is surrounded by a cast steel cathode. A metal gauze screen separates the two electrodes and prevents the Na formed at the cathode from recombining with  $\text{Cl}_2$  produced at the anode. The molten sodium rises as it is less dense than the electrolyte, and it is collected in an inverted trough and removed and packed into steel drums.

A similar cell can be used to obtain potassium by electrolysis of fused KCl. However, the cell must be operated at a higher temperature because the melting point of KCl is higher, and this results in the vaporization of the liberated potassium. Since sodium is a more powerful reducing agent than potassium and is readily available, the modern method is to reduce molten KCl with sodium vapour at  $850^\circ\text{C}$  in a large fractionating tower. This gives K of 99.5% purity.



Rb and Cs are produced in a similar way by reducing the chlorides with Ca at  $750^\circ\text{C}$  under reduced pressure.

### USES OF GROUP 1 METALS AND THEIR COMPOUNDS

Lithium stearate  $\text{C}_{17}\text{H}_{35}\text{COOLi}$  is used in making automobile grease.  $\text{Li}_2\text{CO}_3$  is added to bauxite in the electrolytic production of aluminium as it lowers the melting point.  $\text{Li}_2\text{CO}_3$  is also used to toughen glass. It also has uses in medicine, as it affects the balance between  $\text{Na}^+$  and  $\text{K}^+$  and  $\text{Mg}^{2+}$  and  $\text{Ca}^{2+}$  in the body. Lithium metal is used to make alloys for example with lead to make 'white metal' bearings for motor engines, with aluminium to make aircraft parts which are light and strong, and with magnesium to make armour plate. There is great interest in lithium

for thermonuclear purposes, since when bombarded with neutrons it produces tritium (see the section on Nuclear Fusion in Chapter 31). Lithium is also used to make electrochemical cells (both primary and secondary batteries). Primary batteries produce electricity by a chemical change, and are discarded when they 'run down'. These have Li anodes, carbon cathodes and  $\text{SOCl}_2$  as the electrolyte. There is interest in Li/S batteries which could power battery cars in the future, and in secondary cells, which may provide a practical way of storing off-peak electricity. LiH is used to generate hydrogen, and LiOH to absorb  $\text{CO}_2$ .

Caustic soda NaOH is the most important alkali used in industry and is used for a wide variety of purposes including making many inorganic and organic compounds, paper making, neutralizations, and making alumina, soap and rayon. Soda ash  $\text{Na}_2\text{CO}_3$  may be used interchangeably with NaOH in many applications such as making paper, soap and detergents. Large amounts are used in making glass, phosphates, silicates, and cleaning preparations and removing  $\text{SO}_2$  pollution from the flue gases at coal-fired electricity generating stations. Large amounts of  $\text{Na}_2\text{SO}_4$  are used to make soap and detergents, paper, textiles and glass. NaOCl is used as a bleach and a disinfectant, and production was about 950 000 tonnes (chlorine equivalent) in 1990.  $\text{NaHCO}_3$  is used in baking powder. The use of sodium metal is declining, but about 80 000 tonnes were produced in 1994. The largest use of sodium is to make a Na/Pb alloy needed to make  $\text{PbEt}_4$  and  $\text{PbMe}_4$ . These organolead compounds are used as anti-knock additives to petrol, but this use of sodium continues to decrease as more cars use lead-free petrol. Another important use is to reduce  $\text{TiCl}_4$  and  $\text{ZrCl}_4$  to the metals. Other uses are making  $\text{Na}_2\text{O}_2$  and NaH, and in sodium street lights. Liquid sodium metal is used as a coolant in fast breeder nuclear reactors. It transfers heat from the reactor to turbines, where the heat produces steam which is used to generate electricity. A fast breeder reactor is still operational at Grenoble (France), but another at Dounray (Scotland) has now been decommissioned. These reactors operate at a temperature of about  $600^\circ\text{C}$ ; being a metal, sodium conducts heat very well, and as its boiling point is  $881^\circ\text{C}$  it is ideal for this purpose. Small amounts of the metal are used in organic synthesis, and for drying organic solvents.

Potassium is an essential element for life. Roughly 95% of potassium compounds are used as fertilizers for plants – KCl 90%,  $\text{K}_2\text{SO}_4$  9%,  $\text{KNO}_3$  1%. Potassium salts are always more expensive than sodium salts, usually by a factor of 10 or more. KOH (which is prepared by electrolysis of aqueous KCl) is used to make potassium phosphates and also soft soap, e.g. potassium stearate, both of which are used in liquid detergents.  $\text{KNO}_3$  is used in explosives.  $\text{KMnO}_4$  is used in the manufacture of saccharin, as an oxidizing agent and for titrations.  $\text{K}_2\text{CO}_3$  is used in ceramics, colour TV tubes and fluorescent light tubes. Potassium superoxide  $\text{KO}_2$  is used in breathing apparatus and in submarines, and KBr is used in photography. Not much potassium metal is produced, and most of it is used to make  $\text{KO}_2$ .

## ELECTRONIC STRUCTURE

Group 1 elements all have one valency electron in their outer orbital – an  $s$  electron which occupies a spherical orbital. Ignoring the filled inner shells the electronic structures may be written  $2s^1$ ,  $3s^1$ ,  $4s^1$ ,  $5s^1$ ,  $6s^1$  and  $7s^1$ . The single valence electron is a long distance from the nucleus, is only weakly held and is readily removed. In contrast the remaining electrons are closer to the nucleus, more tightly held, and are removed only with great difficulty. Because of similarities in the electronic structures of these elements many similarities in chemical behaviour would be expected.

## SIZE OF ATOMS AND IONS

Group 1 atoms are the largest in their horizontal periods in the periodic table. When the outer electron is removed to give a positive ion, the size decreases considerably. There are two reasons for this:

1. The outermost shell of electrons has been completely removed.
2. Having removed an electron, the positive charge on the nucleus is now greater than the charge on the remaining electrons, so that each of the remaining electrons is attracted more strongly towards the nucleus. This reduces the size further.

Positive ions are always smaller than the parent atom. Even so, the ions are very large, and they increase in size from  $\text{Li}^+$  to  $\text{Fr}^+$  as extra shells of electrons are added.

The  $\text{Li}^+$  is much smaller than the other ions. For this reason, Li only mixes with Na above  $380^\circ\text{C}$ , and it is immiscible with the metals K, Rb and Cs, even when molten, nor will Li form substitutional alloys with them. In contrast the other metals Na, K, Rb and Cs are miscible with each other in all proportions.

## DENSITY

The atoms are large, so Group 1 elements have remarkably low densities. Lithium metal is only about half as dense as water, whilst sodium and potassium are slightly less dense than water (see Table 9.3). It is unusual

Table 9.3 Size and density

	Metallic radius (Å)	Ionic radius $\text{M}^+$ six coordinate (Å)	Density ( $\text{g cm}^{-3}$ )
Li	1.52	0.76	0.54
Na	1.86	1.02	0.97
K	2.27	1.38	0.86
Rb	2.48	1.52	1.53
Cs	2.65	1.67	1.90

for metals to have low densities, and in contrast most of the transition metals have densities greater than  $5 \text{ g cm}^{-3}$ , for example iron  $7.9 \text{ g cm}^{-3}$ , mercury  $13.6 \text{ g cm}^{-3}$ , and osmium and iridium (the two most dense elements)  $22.57$  and  $22.61 \text{ g cm}^{-3}$  respectively.

## IONIZATION ENERGY

The first ionization energies for the atoms in this group are appreciably lower than those for any other group in the periodic table. The atoms are very large so the outer electrons are only held weakly by the nucleus: hence the amount of energy needed to remove the outer electron is not very large. On descending the group from Li to Na to K to Rb to Cs, the size of the atoms increases: the outermost electrons become less strongly held, so the ionization energy decreases.

The second ionization energy – that is the energy to remove a second electron from the atoms – is extremely high. The second ionization energy is always larger than the first, often by a factor of two, because it involves removing an electron from a smaller positive ion, rather than from a larger neutral atom. The difference between first and second ionization energies is much larger in this case since in addition it corresponds to removing an electron from a closed shell. A second electron is never removed under normal conditions, as the energy required is greater than that needed to ionize the noble gases. The elements commonly form  $M^+$  ions.

Table 9.4 Ionization energies

	First ionization energy ( $\text{kJ mol}^{-1}$ )	Second ionization energy ( $\text{kJ mol}^{-1}$ )
Li	520.1	7296
Na	495.7	4563
K	418.6	3069
Rb	402.9	2650
Cs	375.6	2420

## ELECTRONEGATIVITY AND BOND TYPE

The electronegativity values for the elements in this group are very small – in fact the smallest values of any element. Thus when these elements react with other elements to form compounds, a large electronegativity difference between the two atoms is probable, and ionic bonds are formed.

Na electronegativity	0.9
Cl electronegativity	<u>3.0</u>
Electronegativity difference	<u>2.1</u>

Table 9.5 Electronegativity values

	Pauling's electronegativity
Li	1.0
Na	0.9
K	0.8
Rb	0.8
Cs	0.7

An electronegativity difference of approximately 1.7–1.8 corresponds to 50% ionic character. The value 2.1 exceeds this, so the bonding in NaCl is predominantly ionic. Similar arguments apply to other compounds: for example, the electronegativity difference in LiF is 3.0, and in KBr is 2.0 and both compounds are ionic.

The chemistry of the alkali metals is largely that of their ions.

### BORN–HABER CYCLE: ENERGY CHANGES IN THE FORMATION OF IONIC COMPOUNDS

When elements react to form compounds,  $\Delta G$  (the free energy of formation) is negative. For a reaction to proceed spontaneously, the free energy of the products must be lower than that of the reactants.


Usually the energy changes are measured as enthalpy values  $\Delta H$ , and  $\Delta G$  is related to  $\Delta H$  by the equation

$$\Delta G = \Delta H - T\Delta S$$

In many cases enthalpy values are used instead of free energy values and the two are almost the same if the term  $T\Delta S$  is small. At room temperature  $T$  is almost 300 K, so  $\Delta G$  and  $\Delta H$  are only similar when the change in entropy  $\Delta S$  is very small. Entropy changes are large when there is a change in physical state, e.g. solid to liquid, or liquid to gas, but otherwise entropy changes are usually small.

A whole series of energy changes is involved when one starts from the elements and finishes with an ionic crystal. These changes are shown in the Born–Haber cycle (Figure 9.2). The cycle serves two purposes. First it explains how these various energy changes are related and second, if all but one of the terms can be measured, then the remaining value can be calculated. There is no direct way of obtaining electron affinity values and these have been calculated from this type of energy cycle.

Hess's law states that the energy change occurring during a reaction depends only on the energy of the initial reactants and the energy of the final products and not on the reaction mechanism, or the route taken. Thus, by Hess's law, the energy change for the reaction of solid sodium and chlorine gas to form a sodium chloride crystal by the direct route (measured as the enthalpy of formation) must be the same as the sum of


$$\Delta H_f = + \Delta H_s + I + \frac{1}{2}\Delta H_d + E + U$$

**Table 9.6** Enthalpy ( $\Delta H$ ) values for MCl (all values in  $\text{kJ mol}^{-1}$ )

	Sublimation energy $M_{(s)} - M_{(g)}$	$\frac{1}{2}$ enthalpy of dissociation $\frac{1}{2}Cl_2 - Cl$	Ionization energy $M - M^+$	Electron affinity $Cl - Cl^-$	Lattice energy	Total = enthalpy of formation
Li	161	121.5	520	-355	-845	-397.5
Na	108	121.5	496	-355	-770	-399.5
K	90	121.5	419	-355	-703	-427.5
Rb	82	121.5	403	-355	-674	-422.5
Cs	78	121.5	376	-355	-644	-423.5

the ionization energy) is used to produce the ions, so these terms are positive. Ionic solids are formed because an even larger amount of energy is evolved, mainly coming from the lattice energy and to a smaller extent from the electron affinity, resulting in a negative value for the enthalpy of formation  $\Delta H_f$ .

All the halides  $MX$  have negative enthalpies of formation, which indicates that thermodynamically (that is in terms of energy) it is feasible to form the compounds  $MX$  from the elements. The values are shown in Table 9.7. Several trends are apparent in these values.

1. The most negative enthalpies of formation occur with the fluorides. For any given metal, the values decrease in the sequence fluoride > chloride > bromide > iodide. Thus the fluorides are the most stable, and the iodides the least stable.
2. The enthalpies of formation for the chlorides, bromides and iodides become more negative on descending the group. This trend is observed with most salts, but the opposite trend is found in the fluorides.

Ionic compounds may also be formed in solution, when a similar cycle of energy changes must be considered, but the hydration energies of the positive and negative ions must be substituted for the lattice energy.

The energy cycle shown in Figure 9.3 is very similar to the Born–Haber cycle. The enthalpy of formation of hydrated ions from the elements in their natural state must be equal to the sum of all the other energy changes going round the cycle.




Figure 9.3 Energy cycle for the hydration of ions



**Table 9.7** Standard enthalpies of formation for Group 1 halides (all values in  $\text{kJ mol}^{-1}$ )

	MF	MCl	MBr	MI
Li	-612	-398	-350	-271
Na	-569	-400	-360	-288
K	-563	-428	-392	-328
Rb	-549	-423	-389	-329
Cs	-531	-424	-395	-337

## STRUCTURES OF THE METALS, HARDNESS AND COHESIVE ENERGY

At normal temperatures all the Group 1 metals adopt a body-centred cubic type of lattice with a coordination number of 8. However, at very low temperatures lithium forms a hexagonal close-packed structure with a coordination number of 12.

The metals are all very soft, and can be cut quite easily with a knife. Lithium is harder than the others, but is softer than lead. Bonding in metals is discussed in Chapters 2 and 5 in terms of delocalized molecular orbitals or bands, extending over the whole crystal.

The cohesive energy is the force holding the atoms or ions together in the solid. (This is the same in magnitude, but the opposite in sign, to the enthalpy of atomization, which is the energy required to break the solid up into gaseous atoms.) The cohesive energies of Group 1 metals are about half of those for Group 2, and one third of those for Group 13 elements. The magnitude of the cohesive energy determines the hardness, and it depends on the number of electrons that can participate in bonding and on the strength of the bonds formed. The softness, low cohesive energy and weak bonding in Group 1 elements are consequences of these metals having only one valency electron which can participate in bonding (compared with two or more electrons in most other metals), and of the large size and diffuse nature of the outer bonding electron. The atoms become larger on descending the group from lithium to caesium, so the bonds are weaker, the cohesive energy decreases and the softness of the metals increases.

**Table 9.8** Cohesive energy

	Cohesive energy (enthalpy of atomization) ( $\text{kJ mol}^{-1}$ )
Li	161
Na	108
K	90
Rb	82
Cs	78

## MELTING AND BOILING POINTS

The generally low values for cohesive energy are reflected in the very low values of melting and boiling points in the group. The cohesive energy decreases down the group, and the melting points decrease correspondingly.

The melting points range from lithium 181 °C to caesium 28.5 °C. These are extremely low values for metals, and contrast with the melting points of the transition metals, most of which are above 1000 °C.

The melting point of lithium is nearly twice as high (in °C) as that for sodium, though the others are close together. With many properties it is found that the first element in each group differs appreciably from the rest of the group. (Differences between lithium and the other Group 1 elements are discussed near the end of this chapter.)

Table 9.9 Melting and boiling points

	Melting point (°C)	Boiling point (°C)
Li	181	1347
Na	98	881
K	63	766
Rb	39	688
Cs	28.5	705

## FLAME COLOURS AND SPECTRA

A result of the low ionization energies is that when these elements are irradiated with light, the light energy absorbed may be sufficient to make an atom lose an electron. Electrons emitted in this way are called photoelectrons, and this explains the use of caesium and potassium as cathodes in photoelectric cells.

Electrons may also be quite readily excited to a higher energy level, for example in the flame test. To perform this test, a sample of the metal chloride, or any salt of the metal moistened with concentrated HCl, is heated on a platinum or nichrome wire in a Bunsen burner flame. The heat from the burner excites one of the orbital electrons to a higher energy

Table 9.10 Flame colours and wavelengths


	Colour	Wavelength (nm)	Wavenumber (cm <sup>-1</sup> )
Li	crimson	670.8	14 908
Na	yellow	589.2	16 972
K	lilac	766.5	13 046
Rb	red-violet	780.0	12 821
Cs	blue	455.5	21 954

level. When the excited electron drops back to its original energy level it gives out the extra energy it obtained. The energy  $E$  is related to the wave number  $\nu$  by the Einstein relationship:

$$E = h\nu \text{ (where } h \text{ is Planck's constant)}$$

For Group 1 metals, the energy emitted appears as visible light, thus giving the characteristic flame colorations.

The colour actually arises from electronic transitions in short-lived species which are formed momentarily in the flame. The flame is rich in electrons, and in the case of sodium the ions are temporarily reduced to atoms.



The sodium D-line (which is actually a doublet at 589.0 nm and 589.6 nm) arises from the electronic transition  $3s^1 \rightarrow 3p^1$  in sodium atoms formed in the flame. The colours from different elements do not all arise from the same transition, or from the same species. Thus the red line for lithium arises from a short-lived LiOH species formed in the flame.

These characteristic flame colorations of the *emission spectra* are used for the analytical determination of these elements by flame photometry. A solution of a Group 1 salt is aspirated into an oxygen–gas flame in a flame photometer. The energy from the flame excites an electron to a higher energy level, and when it falls back to the lower energy level the extra energy is given out as light. The intensity of the flame coloration is measured with a photoelectric cell. The intensity depends on the concentration of metal present. A calibration graph is produced by measuring intensities with known standard solutions, and the exact concentration of the unknown solution can be found by comparison with the standard graph.

Alternatively *atomic absorption spectroscopy* may be used to estimate Group 1 metals. Here a lamp that emits a wavelength appropriate for a particular electronic transition is used to irradiate the sample in the flame. Thus a sodium lamp is used to detect sodium in the sample; other lamps are used to detect other elements. The amount of light absorbed, this time by the ground state atoms, is measured, and is proportional to the amount of the particular element being tested for.

## COLOUR OF COMPOUNDS

Colour arises because the energy absorbed or emitted in electronic transitions corresponds to a wavelength in the visible region. The Group 1 metal ions all have noble gas configurations in which all the electrons are paired. Thus promoting an electron requires some energy to unpair an electron, some to break a full shell of electrons and some to promote the electron to a higher level. The total energy is large: hence there are no suitable transitions and the compounds are typically white. Any transitions which do occur will be of high energy, will appear in the ultraviolet region rather than in the visible region, and will be invisible to the human eye. Com-

pounds of Group 1 metals are typically white, except those where the anion is coloured, for example sodium chromate  $\text{Na}_2[\text{CrO}_4]$  (yellow), potassium dichromate  $\text{K}_2[\text{Cr}_2\text{O}_7]$  (orange), and potassium permanganate  $\text{K}[\text{MnO}_4]$  (deep purple). In these cases the colour comes from the anions  $[\text{CrO}_4]^-$ ,  $[\text{Cr}_2\text{O}_7]^{2-}$  or  $[\text{MnO}_4]^-$  and not from the Group 1 metal ion.

When Group 1 elements form compounds (usually ionic, but there are a few covalent compounds) all the electrons are paired. Because of this Group 1 compounds are diamagnetic. There is one notable exception – the superoxides, which are discussed later.

## CHEMICAL PROPERTIES




Table 9.11 Some reactions of Group 1 metals

Reaction	Comment
$\text{M} + \text{H}_2\text{O} \rightarrow \text{MOH} + \text{H}_2$	The hydroxides are the strongest bases known
with excess dioxygen	
$\text{Li} + \text{O}_2 \rightarrow \text{Li}_2\text{O}$	Monoxide is formed by Li and to a small extent by Na
$\text{Na} + \text{O}_2 \rightarrow \text{Na}_2\text{O}_2$	Peroxide formed by Na and to a small extent by Li
$\text{K} + \text{O}_2 \rightarrow \text{KO}_2$	Superoxide formed by K, Rb, Cs
$\text{M} + \text{H}_2 \rightarrow \text{MH}$	Ionic salt like hydrides
$\text{Li} + \text{N}_2 \rightarrow \text{Li}_3\text{N}$	Nitride formed only by Li
$\text{M} + \text{P} \rightarrow \text{M}_3\text{P}$	All the metals form phosphides
$\text{M} + \text{As} \rightarrow \text{M}_3\text{As}$	All the metals form arsenides
$\text{M} + \text{Sb} \rightarrow \text{M}_3\text{Sb}$	All the metals form stibnides
$\text{M} + \text{S} \rightarrow \text{M}_2\text{S}$	All the metals form sulphides
$\text{M} + \text{Se} \rightarrow \text{M}_2\text{Se}$	All the metals form selenides
$\text{M} + \text{Te} \rightarrow \text{M}_2\text{Te}$	All the metals form tellurides
$\text{M} + \text{F}_2 \rightarrow \text{MF}$	All the metals form fluorides
$\text{M} + \text{Cl}_2 \rightarrow \text{MCl}$	All the metals form chlorides
$\text{M} + \text{Br}_2 \rightarrow \text{MBr}$	All the metals form bromides
$\text{M} + \text{I}_2 \rightarrow \text{MI}$	All the metals form iodides
$\text{M} + \text{NH}_3 \rightarrow \text{MNH}_2$	All the metals form amides

### Reaction with water

Group 1 metals all react with water, liberating hydrogen and forming the hydroxides. The reaction becomes increasingly violent on descending the group. Thus lithium reacts gently, sodium melts on the surface of the

water and the molten metal skates about vigorously and may catch fire (especially if localized), and potassium melts and always catches fire.



The standard electrode potentials  $E^\circ$  are  $\text{Li}^+|\text{Li} = -3.05$  volts,  $\text{Na}^+|\text{Na} = -2.71$ ,  $\text{K}^+|\text{K} = -2.93$ ,  $\text{Rb}^+|\text{Rb} = -2.92$ ,  $\text{Cs}^+|\text{Cs} = -2.92$ . Lithium has the most negative standard electrode potential of any element in the periodic table, largely because of its high hydration energy. Standard electrode potentials  $E^\circ$  and Gibbs free energy  $\Delta G$  are related by the equation:

$$\Delta G = -nFE^\circ$$

where  $n$  is the number of electrons removed from the metal to produce the ion, and  $F$  is the Faraday constant.


The reaction  $\text{Li}^+ + \text{e} \rightarrow \text{Li}$  has the largest negative  $E^\circ$  value, and hence the largest positive  $\Delta G$  value. Thus the reaction does **not** occur. However, the reverse reaction  $\text{Li} \rightarrow \text{Li}^+ + \text{e}$  has a large negative value of  $\Delta G$ , so lithium liberates more energy than the other metals when it reacts with water. In view of this it is at first sight rather surprising that lithium reacts gently with water, whereas potassium, which liberates less energy, reacts violently and catches fire. The explanation lies in the kinetics (that is the rate at which the reaction proceeds), rather than in the thermodynamics (that is the total amount of energy liberated). Potassium has a low melting point, and the heat of reaction is sufficient to make it melt, or even vaporize. The molten metal spreads out, and exposes a larger surface to the water, so it reacts even faster, gets even hotter and catches fire.

### Reaction with air

Chemically, Group 1 elements are very reactive, and tarnish rapidly in dry air. Sodium, potassium, rubidium and caesium form oxides of various types, but lithium forms a mixture of the oxide and the nitride,  $\text{Li}_3\text{N}$ .

### Reaction with dinitrogen

Lithium is the only element in the group that reacts with dinitrogen to form a nitride. Lithium nitride,  $\text{Li}_3\text{N}$ , is ionic ( $3\text{Li}^+$  and  $\text{N}^{3-}$ ), and is ruby red. Two reactions of the nitride are of interest. First, on heating to a high temperature it decomposes to the elements, and second, it reacts with water, giving ammonia.



## OXIDES, HYDROXIDES, PEROXIDES AND SUPEROXIDES

## Reaction with air

The metals all burn in air to form oxides, though the the product varies depending on the metal. Lithium forms the monoxide  $\text{Li}_2\text{O}$  (and some peroxide  $\text{Li}_2\text{O}_2$ ), sodium forms the peroxide  $\text{Na}_2\text{O}_2$  (and some monoxide  $\text{Na}_2\text{O}$ ), and the others form superoxides of the type  $\text{MO}_2$ .

All five metals can be induced to form the normal oxide, peroxide or superoxide by dissolving the metal in liquid ammonia and bubbling in the appropriate amount of dioxygen.

## Normal oxides – monoxides

The monoxides are ionic, for example  $2\text{Li}^+$  and  $\text{O}^{2-}$ .  $\text{Li}_2\text{O}$  and  $\text{Na}_2\text{O}$  are pure white solids as expected, but surprisingly  $\text{K}_2\text{O}$  is pale yellow,  $\text{Rb}_2\text{O}$  is bright yellow and  $\text{Cs}_2\text{O}$  is orange. Metallic oxides are usually basic. The typical oxides  $\text{M}_2\text{O}$  are strongly basic oxides, and they react with water, forming strong bases.



The crystal structures of  $\text{Li}_2\text{O}$ ,  $\text{Na}_2\text{O}$ ,  $\text{K}_2\text{O}$  and  $\text{Rb}_2\text{O}$  are anti fluorite structures. The anti-fluorite structure is like that for fluorite  $\text{CaF}_2$ , except that the positions of the positive and negative ions are interchanged. Thus  $\text{Li}^+$  fill the sites occupied by  $\text{F}^-$ , and  $\text{O}^{2-}$  fill sites occupied by  $\text{Ca}^{2+}$ .  $\text{Cs}_2\text{O}$  has an anti  $\text{CdCl}_2$  layer structure.

## Hydroxides


Sodium hydroxide  $\text{NaOH}$  is often called caustic soda, and potassium hydroxide is called caustic potash, because of their corrosive properties (for example on glass or on skin). These caustic alkalis are the strongest bases known in aqueous solution. The hydroxides of Na, K, Rb and Cs are very soluble in water, but  $\text{LiOH}$  is much less soluble (see Table 9.12). At

Table 9.12 Solubility of Group 1 hydroxides


Element	Solubility (g/100 g $\text{H}_2\text{O}$ )
Li	13.0 (25°C)
Na	108.3 (25°C)
K	112.8 (25°C)
Rb	197.6 (30°C)
Cs	385.6 (15°C)

25°C a saturated solution of NaOH is about 27 molar, whilst saturated LiOH is only about 5 molar.

The bases react with acids to form salts and water, and are used for many neutralizations.




The bases also react with  $\text{CO}_2$ , even traces in the air, forming the carbonate. LiOH is used to absorb carbon dioxide in closed environments such as space capsules (where its light weight is an advantage in reducing the launching weight).




They also react with the amphoteric oxides,  $\text{Al}_2\text{O}_3$  forming aluminates,  $\text{SiO}_2$  (or glass) forming silicates,  $\text{SnO}_2$  forming stannates,  $\text{PbO}_2$  forming plumbates and  $\text{ZnO}$  forming zincates.


The bases liberate ammonia from both ammonium salts and coordination complexes where ammonia is attached to a transition metal ion (ammine complexes).




NaOH reacts with  $\text{H}_2\text{S}$  to form sulphides  $\text{S}^{2-}$ , and hydrogen sulphides  $\text{SH}^-$ , and it is used to remove mercaptans from petroleum products.



The hydroxides react with alcohols, forming alkoxides.



KOH resembles NaOH in all its reactions, but as KOH is much more expensive it is seldom used. However, KOH is much more soluble in alcohol, thus producing  $\text{OC}_2\text{H}_5^-$  ions by the equilibrium





This accounts for the use of alcoholic KOH in organic chemistry. Group 1 hydroxides are thermally stable, illustrating the strong electropositive nature of the metals. On heating, many hydroxides decompose, losing water and forming the oxide.

### Peroxides and superoxides


The peroxides all contain the  $[\text{—O—O—}]^{2-}$  ion. They are diamagnetic (all the electrons are paired), and are oxidizing agents. They may be regarded as salts of the dibasic acid  $\text{H}_2\text{O}_2$ , and they react with water and acid, giving hydrogen peroxide  $\text{H}_2\text{O}_2$ .



$\text{Na}_2\text{O}_2$  is pale yellow in colour. It is used industrially for bleaching wood pulp, paper and fabrics such as cotton and linen. It is a powerful oxidant, and many of its reactions are dangerously violent, particularly with materials that are reducing agents such as aluminium powder, charcoal, sulphur and many organic liquids. Because it reacts with  $\text{CO}_2$  in the air it has been used to purify the air in submarines and confined spaces, as it both removes  $\text{CO}_2$  and produces  $\text{O}_2$ . Potassium superoxide  $\text{KO}_2$  is even better for this purpose. Some typical reactions are



The industrial process for forming sodium peroxide is a two stage reaction in the presence of excess air





The superoxides contain the ion  $[\text{O}_2]^-$ , which has an unpaired electron, and hence they are paramagnetic and are all coloured ( $\text{LiO}_2$  and  $\text{NaO}_2$  yellow,  $\text{KO}_2$  orange,  $\text{RbO}_2$  brown and  $\text{CsO}_2$  orange).

$\text{NaO}_2$  has three different crystal structures, the marcasite structure at liquid air temperatures, the pyrites structure  $\text{FeS}_2$  between  $-77^\circ\text{C}$  and  $-50^\circ\text{C}$ , and a calcium carbide  $\text{CaC}_2$  structure at room temperature. Both the pyrites and calcium carbide structures are related to the  $\text{NaCl}$  structure in that the metal ions occupy the  $\text{Na}^+$  sites, and  $\text{O}_2^-$ ,  $\text{S}_2^{2-}$  and  $\text{C}_2^{2-}$  ions are centred on the  $\text{Cl}^-$  sites. Since the negative ions contain two atoms, their shape is an elongated rod rather than a sphere. In the  $\text{CaC}_2$  structure, the  $\text{C}_2^{2-}$  ions are all oriented along one of the cubic axes, and thus the unit cell is elongated in that direction, hence the unit cell is cubic in  $\text{NaCl}$  but tetragonal in  $\text{CaC}_2$ . The pyrites structure is similar, but the  $\text{C}_2^{2-}$  ions are not all in alignment, and the cubic structure is retained.

Superoxides are even stronger oxidizing agents than peroxides, and give both  $\text{H}_2\text{O}_2$  and  $\text{O}_2$  with either water or acids




$\text{KO}_2$  is used in space capsules, submarines, and breathing masks, because it both produces dioxygen and removes carbon dioxide. Both functions are important in life support systems






Sodium superoxide cannot be prepared by burning the metal in dioxygen at atmospheric pressure, but it is made commercially and in good yields by reacting sodium peroxide with dioxygen at a high temperature and pressure (450 °C and 300 atmospheres) in a stainless steel bomb.




The bonding in peroxides and superoxides is described in the examples of molecular orbital treatment in Chapter 4. The peroxide ion  $[\text{—O—O—}]^{2-}$  has 18 electrons, which occupy the molecular orbitals as shown:



Thus the bond order is one, corresponding to a single bond.


The superoxide ion  $[\text{O}_2]^-$  has only 17 electrons, which give a bond order of 1.5.






Generally, large atoms or ions form weaker bonds than small ones. The peroxide and superoxide ions are large, and it is noteworthy that the stability of the peroxides and superoxides increases as the metal ions become larger. This shows that large cations can be stabilized by large anions, since if both ions are similar in size the coordination number will be high, and this gives a high lattice energy.

## SULPHIDES


The metals all react with sulphur, forming sulphides such as  $\text{Na}_2\text{S}$ , and polysulphides  $\text{Na}_2\text{S}_n$  where  $n = 2, 3, 4, 5$  or  $6$ . The polysulphide ions are made from zig-zag chains of sulphur atoms.




Sodium sulphide can also be made by heating sodium sulphate with carbon, or by passing  $\text{H}_2\text{S}$  into  $\text{NaOH}$  solution.



Group 1 sulphides hydrolyse appreciably in water, giving strongly alkaline solutions:



$\text{Na}_2\text{S}$  is used to make organic sulphur dyestuffs and in the leather industry to remove hair from hides.  $\text{Na}_2\text{S}$  is readily oxidized by air to form sodium thiosulphate which is used in photography to dissolve silver halides and as a laboratory reagent for iodine titrations




## SODIUM HYDROXIDE

Sodium hydroxide is the most important alkali used in industry. It is produced on a large scale (38.7 million tonnes in 1994) by the electrolysis of an aqueous solution of  $\text{NaCl}$  (brine) using either a diaphragm cell or a mercury cathode cell. At one time it was also made from  $\text{Na}_2\text{CO}_3$  by the lime-caustic soda process but this is only used a little nowadays as other methods are cheaper. Details of the industrial methods, uses and tonnages are given in Chapter 10.

## SODIUM HYDROGENCARBONATE (SODIUM BICARBONATE)

About 900 000 tonnes of  $\text{NaHCO}_3$  were produced in 1991, of which 40% is used for baking powder, 15% to make other chemicals, 12% in pharmaceutical products including anti-acid preparations for indigestion and 10% in fire extinguishers. An increasing use is flue gas desulphurization.

$\text{NaHCO}_3$  can be used on its own to make cakes or bread rise since it decomposes between  $50^\circ\text{C}$  and  $100^\circ\text{C}$  giving bubbles of  $\text{CO}_2$ .



Baking powder is more commonly used and contains  $\text{NaHCO}_3$ ,  $\text{Ca}(\text{H}_2\text{PO}_4)_2$ , and starch. The  $\text{Ca}(\text{H}_2\text{PO}_4)_2$  is acidic and when moistened it reacts with  $\text{NaHCO}_3$  giving  $\text{CO}_2$ . The starch is a filler. An improved combination baking powder contains about 40% starch, 30%  $\text{NaHCO}_3$ , 20%  $\text{NaAl}(\text{SO}_4)_2$ , and 10%  $\text{Ca}(\text{H}_2\text{PO}_4)_2$ . The  $\text{NaAl}(\text{SO}_4)_2$  slows the reaction down so the  $\text{CO}_2$  is given off more slowly.

## SODIUM SULPHATE

About 4.3 million tonnes of  $\text{Na}_2\text{SO}_4$  were used in 1993. About 55% of this is made synthetically as a by-product from the manufacture of  $\text{HCl}$  and also from many neutralization processes that use  $\text{H}_2\text{SO}_4$ . About 45% mainly Glauber's salt  $\text{Na}_2\text{SO}_4 \cdot 10\text{H}_2\text{O}$  is mined.

The major use of  $\text{Na}_2\text{SO}_4$  – some 70% – is in the paper industry and about 10% is used in detergents and 10% in glass manufacture. In the Kraft paper making process a strong alkaline solution of  $\text{Na}_2\text{SO}_4$  is used to dissolve the lignin that holds the cellulose fibres together in wood chips.


The cellulose fibres are then turned into corrugated cardboard and brown paper.

## OXOSALTS – CARBONATES, BICARBONATES, NITRATES AND NITRITES

Group 1 metals are highly electropositive and thus form very strong bases, and have quite stable oxosalts.

The carbonates are remarkably stable, and will melt before they eventually decompose into oxides at temperatures above  $1000^{\circ}\text{C}$ .  $\text{Li}_2\text{CO}_3$  is considerably less stable and decomposes more readily.


Because Group 1 metals are so strongly basic, they also form solid bicarbonates (also called hydrogencarbonates). No other metals form solid bicarbonates, though  $\text{NH}_4\text{HCO}_3$  also exists as a solid. Bicarbonates evolve carbon dioxide and turn into carbonates on gentle warming. This is one test for bicarbonates in qualitative analysis. The crystal structures of  $\text{NaHCO}_3$  and  $\text{KHCO}_3$  both show hydrogen bonding, but are different. In  $\text{NaHCO}_3$  the  $\text{HCO}_3^-$  ions are linked into an infinite chain, whilst in  $\text{KHCO}_3$  a dimeric anion is formed.



Lithium is exceptional in that it does not form a solid bicarbonate, though  $\text{LiHCO}_3$  can exist in solution. All the carbonates and bicarbonates are soluble in water.


Over 50 000 tonnes of  $\text{Li}_2\text{CO}_3$  are produced annually. Most of it is added as an impurity to  $\text{Al}_2\text{O}_3$  to lower its melting point in the extraction of aluminium by electrolysis. Some is used to toughen glass (sodium in the glass is replaced by lithium).  $\text{Na}_2\text{CO}_3$  is used as washing soda to soften water in hard water areas, and  $\text{NaHCO}_3$  is used as baking powder.

The nitrates can all be prepared by the action of  $\text{HNO}_3$  on the corresponding carbonate or hydroxide, and they are all very soluble in water.  $\text{LiNO}_3$  is used for fireworks and red-coloured distress flares. Large deposits of  $\text{NaNO}_3$  are found in Chile, and are used as a nitrogenous fertilizer. Solid  $\text{LiNO}_3$  and  $\text{NaNO}_3$  are deliquescent, and because of this  $\text{KNO}_3$  is used in preference to  $\text{NaNO}_3$  in gunpowder (gunpowder is a mixture of  $\text{KNO}_3$ , sulphur and charcoal).  $\text{KNO}_3$  is usually obtained from synthetic nitric acid and  $\text{K}_2\text{CO}_3$ , but at one time it was made from  $\text{NaNO}_3$ :



Group 1 nitrates are fairly low melting solids, and are amongst the most stable nitrates known. However, on strong heating they decompose into

nitrites, and at higher temperatures to the oxide  $\text{LiNO}_3$  decomposes more readily than the others, forming the oxide



Alkali metal nitrates are widely used as molten salts as a solvent in which to carry out high temperature oxidations, and also as a heat transfer medium. They are used up to around  $600^\circ\text{C}$ , but molten salt baths are often used at much lower temperatures. For example, a 1 : 1 mixture of  $\text{LiNO}_3/\text{KNO}_3$  melts at the surprisingly low temperature of  $125^\circ\text{C}$ .



Nitrites are important in the manufacture of organonitrogen compounds, the most important being the azo dyes. Small amounts of  $\text{NaNO}_2$  are used in molten salt baths with  $\text{NaNO}_3$ , and some is used as a food preservative. Nitrites are easily recognized in the laboratory, because on treatment with dilute acids they produce brown fumes of  $\text{NO}_2$ .



$\text{NaNO}_2$  is manufactured by absorbing oxides of nitrogen in  $\text{Na}_2\text{CO}_3$  solution



They can also be made by thermal decomposition of nitrates and the chemical reduction of nitrates



or by reacting  $\text{NO}$  with a hydroxide




## HALIDES AND POLYHALIDES

Since  $\text{Li}^+$  is the smallest ion in the group, it would be expected to form hydrated salts more readily than the other metals.  $\text{LiCl}$ ,  $\text{LiBr}$  and  $\text{LiI}$  form trihydrates  $\text{LiX} \cdot 3\text{H}_2\text{O}$  but the other alkali metal halides form anhydrous crystals.

All the halides adopt a  $\text{NaCl}$  type of structure with a coordination number of 6 except for  $\text{CsCl}$ ,  $\text{CsBr}$  and  $\text{CsI}$ . The latter have a  $\text{CsCl}$  type of structure with a coordination number of 8. Rather more compounds adopt the  $\text{NaCl}$  type of structure than would be expected from the radius ratios of the ions  $r^+/r^-$ , and the reason for this structure being adopted is that it gives the highest lattice energy (see the sections on Ionic compounds of the type  $\text{AX}$ , and Lattice energy in Chapter 3).


The alkali metal halides react with the halogens and interhalogen compounds forming ionic polyhalide compounds:




## HYDRIDES

Group 1 metals all react with hydrogen, forming ionic or salt-like hydrides  $\text{M}^+\text{H}^-$ . However, the ease with which they do so decreases from lithium to caesium. These hydrides contain the  $\text{H}^-$  ion (which is not commonly found, since hydrogen usually forms  $\text{H}^+$  ions). It can be proved that  $\text{H}^-$  ions exist because on electrolysis hydrogen is liberated at the anode.


The hydrides react with water, liberating hydrogen, and lithium hydride is used as a source of hydrogen for military purposes and for filling meteorological balloons.




Lithium also forms a complex hydride  $\text{Li}[\text{AlH}_4]$ , called lithium aluminium hydride, which is a useful reducing agent. It is made from lithium hydride in dry ether solution.



Lithium aluminium hydride is ionic, and the  $[\text{AlH}_4]^-$  ion is tetrahedral.  $\text{Li}[\text{AlH}_4]$  is a powerful reducing agent and is widely used in organic chemistry, as it reduces carbonyl compounds to alcohols. It reacts violently with water, so it is necessary to use absolutely dry organic solvents, for example ether which has been dried over sodium.  $\text{Li}[\text{AlH}_4]$  will also reduce a number of inorganic compounds.




Sodium tetrahydridoborate (sodium borohydride)  $\text{Na}[\text{BH}_4]$  is another hydride complex. It is ionic, comprising tetrahedral  $[\text{BH}_4]^-$  ions. It is best obtained by heating sodium hydride with trimethyl borate:



Other tetrahydridoborates for Group 1 and 2 metals, aluminium and some transition metals can be made from the sodium salt. These tetrahydridoborates are used as reducing agents, and the alkali metal compounds (particularly those of Na and K) are becoming increasingly used as they are much less sensitive to water than  $\text{Li}[\text{AlH}_4]$ . Thus  $\text{Na}[\text{BH}_4]$  can be crystallized from cold water, and  $\text{K}[\text{BH}_4]$  from hot water, so they

have the advantage that they can be used in aqueous solutions. The others react with water (See Group 13)



### SOLUBILITY AND HYDRATION


All the simple salts dissolve in water, producing ions, and consequently the solutions conduct electricity. Since  $\text{Li}^+$  ions are small, it might be expected that solutions of lithium salts would conduct electricity better than solutions of the same concentration of sodium, potassium, rubidium or caesium salts. The small ions should migrate more easily towards the cathode, and thus conduct more than the larger ions. However, ionic mobility or conductivity measurements in aqueous solution (Table 9.13) give results in the opposite order  $\text{Cs}^+ > \text{Rb}^+ > \text{K}^+ > \text{Na}^+ > \text{Li}^+$ . The reason for this apparent anomaly is that the ions are hydrated in solution. Since  $\text{Li}^+$  is very small, it is heavily hydrated. This makes the radius of the hydrated ion large, and hence it moves only slowly. In contrast,  $\text{Cs}^+$  is the least hydrated, and the radius of the hydrated  $\text{Cs}^+$  ion is smaller than the radius of hydrated  $\text{Li}^+$ , and hence hydrated  $\text{Cs}^+$  moves faster and conducts electricity more readily.

Table 9.13 Ionic mobilities and hydration


	Ionic radius (Å)	Ionic mobility at infinite dilution	Approx. radius hydrated ion (Å)	Approx. hydration number	Hydration terms		
					$\Delta H^\circ$	$\Delta S^\circ$ (kJ mol <sup>-1</sup> )	$\Delta G^\circ$
$\text{Li}^+$	0.76	33.5	3.40	25.3	-544	-134	-506
$\text{Na}^+$	1.02	43.5	2.76	16.6	-435	-100	-406
$\text{K}^+$	1.38	64.5	2.32	10.5	-352	-67	-330
$\text{Rb}^+$	1.52	67.5	2.28	10.0	-326	-54	-310
$\text{Cs}^+$	1.67	68.0	2.28	9.9	-293	-50	-276

The hydration number is the average number of water molecules associated with the metal ion. The values need not be whole numbers and are obtained by measuring the transference of water in a conductivity cell.

Some water molecules touch the metal ion and bond to it, forming a complex. These water molecules constitute the *primary shell* of water. Thus  $\text{Li}^+$  is tetrahedrally surrounded by four water molecules. This may be explained by the oxygen atoms of the four water molecules using a lone pair to form a coordinate bond to the metal ion. With four electron pairs in the valence shell the VSEPR theory predicts a tetrahedral structure. Alternatively, using valence bond theory, the 2s orbital and the three 2p orbitals form four  $sp^3$  hybrid orbitals which are filled by the lone pairs from the oxygen atoms.



With the heavier ions, particularly Rb<sup>+</sup> and Cs<sup>+</sup>, the number of water molecules increases to six. VSEPR theory predicts an octahedral structure. Valence bond theory also indicates an octahedral arrangement using one s orbital, three p orbitals and two d orbitals for bonding.



A secondary layer of water molecules further hydrates the ions, though these are only held by weak ion–dipole attractive forces. The strength of such forces is inversely proportional to the distance, that is to the size of the metal ion. Thus the secondary hydration decreases from lithium to caesium, and accounts for Li<sup>+</sup> being the most heavily hydrated.



Note that the d orbitals comprise a group of three (called t<sub>2g</sub> orbitals), and a group of two (called e<sub>g</sub> orbitals). Only the group of two is used for bonding.

The size of the hydrated ions is an important factor affecting the passage of these ions through cell walls. It also explains their behaviour on cation-exchange columns, where hydrated Li<sup>+</sup> ions are attached less strongly, and hence eluted first.

The decrease in hydration from Li<sup>+</sup> to Cs<sup>+</sup> is also shown in the crystalline salts, for nearly all lithium salts are hydrated, commonly as trihydrates. In these hydrated Li salts Li<sup>+</sup> is coordinated to 6H<sub>2</sub>O, and the

octahedra share faces forming chains. Many sodium salts are hydrated e.g.  $\text{Na}_2\text{CO}_3 \cdot 10\text{H}_2\text{O}$ ,  $\text{Na}_2\text{CO}_3 \cdot 7\text{H}_2\text{O}$  and  $\text{Na}_2\text{CO}_3 \cdot \text{H}_2\text{O}$ . Few potassium salts and no rubidium or caesium salts are hydrated.

The simple salts are all soluble in water, and so in qualitative analysis these metals need to be precipitated as less common salts. Thus  $\text{Na}^+$  is precipitated by adding zinc (or copper) uranyl acetate solution and precipitating  $\text{NaZn}(\text{UO}_2)(\text{Ac})_9 \cdot \text{H}_2\text{O}$  sodium zinc uranyl acetate.  $\text{K}^+$  is precipitated by adding a solution of sodium cobaltinitrite and precipitating potassium cobaltinitrite  $\text{K}_3[\text{Co}(\text{NO}_2)_6]$  or by adding perchloric acid and precipitating potassium perchlorate  $\text{KClO}_4$ . Group 1 metals can be estimated gravimetrically, sodium as the uranylacetate, and potassium, rubidium and caesium as tetraphenylborates. However, modern instrumental methods such as flame photometry and atomic absorption spectrometry are much quicker and easier to use and are now used in preference to gravimetric analysis.



If a salt is insoluble its lattice energy is greater than the hydration energy.  $\text{K}[\text{B}(\text{C}_6\text{H}_5)_4]$  is insoluble because the hydration energy is very small as a result of the large size of its ions.

The solubility of most of the salts of Group 1 elements in water decreases on descending the group. For a substance to dissolve the energy evolved when the ions are hydrated (hydration energy) must be larger than the energy required to break the crystal lattice (lattice energy). Conversely, if the solid is insoluble the hydration energy is less than the lattice energy.

Strictly in the two cycles shown in Figure 9.4 we should use Gibbs free energy  $\Delta G$  values. In particular, the lattice energy is an enthalpy  $\Delta H^\circ$  term and we should use  $\Delta G^\circ$  the standard free energy for converting the crystalline salt into gaseous ions an infinite distance apart. However, the two terms differ only by a small term for the entropy of vaporization.

Table 9.14 Hydration and lattice energy values for Group 1 halides at 25°C

	Free energy of hydration $\Delta G^\circ$ (kJ mol <sup>-1</sup> )	Lattice energy (kJ mol <sup>-1</sup> )			
		MF	MCl	MBr	MI
$\text{Li}^+$	-506	-1035	-845	-800	-740
$\text{Na}^+$	-406	-908	-770	-736	-690
$\text{K}^+$	-330	-803	-703	-674	-636
$\text{Rb}^+$	-310	-770	-674	-653	-615
$\text{Cs}^+$	-276	-720	-644	-623	-590






Figure 9.4 Solubility related to lattice energy and hydration energy. (a) The solid dissolves, (b) the solid is insoluble.

of the ions. It should in principle be possible to predict solubilities from lattice energies and hydration energies. In practice there are difficulties in predicting solubilities because the values for the data are not known very accurately, and the result depends on a small difference between two large values.

The reason why the solubility of most Group 1 metals decreases on descending the group is that the lattice energy only changes slightly, but the free energy of hydration changes rather more. For example, the difference in lattice energy between NaCl and KCl is  $67 \text{ kJ mol}^{-1}$ , and yet the difference in  $\Delta G_{(hydration)}$  for  $\text{Na}^+$  and  $\text{K}^+$  is  $76 \text{ kJ mol}^{-1}$ . Thus KCl is less soluble than NaCl.

The Group 1 fluorides and carbonates are exceptional in that their solubilities increase rapidly on descending the group. The reason for this is that their lattice energies change more than the hydration energies on descending the group. The lattice energy depends on electrostatic attraction between ions, and is proportional to the distance between the ions, that is proportional to  $1/(r^+ + r^-)$ . It follows that the lattice energy will


Table 9 15 Solubilities of Group 1 halides

	Solubility (Molar value first, g/100 g H <sub>2</sub> O given in brackets)			
	MF	MCl	MBr	MI
Li	0.1 (0.27)	19.6 (830)	20.4 (177)	8.8 (165)
Na	1.0 (4.22)	6.2 (36)	8.8 (91)	11.9 (179)
K	15.9 (92.3)	4.8 (34.7)	7.6 (67)	8.7 (144)
Rb	12.5 (130.6)	7.5 (91)	6.7 (110)	7.2 (152)
Cs	24.2 (367.0)	11.0 (186)	5.1 (108)	3.0 (79)

vary most when  $r^-$  is small, that is with  $F^-$ , and will vary least when  $r^+$  is large (with  $I^-$ ). The weight of solute dissolving does not provide a very useful comparison of the solubilities, because the molecular weights differ. The easiest way to compare the number of ions is to compare the solubilities as molar quantities.

### SOLUTIONS OF METALS IN LIQUID AMMONIA

In the presence of impurities or catalysts such as Fe, the alkali metals react with liquid ammonia to form a metal amide and hydrogen.



If all catalysts and impurities are absent, then Group 1 metals, and to a lesser extent the elements Ca, Sr and Ba in Group 2 and the lanthanide elements Eu and Yb, dissolve directly in very high concentration in liquid ammonia. The metal can be recovered simply by allowing the ammonia to boil off.

Dilute solutions of alkali metals in liquid ammonia are dark blue in colour, and the main species present are solvated metal ions and solvated electrons. If the blue solution is allowed to stand, the colour slowly fades until it disappears owing to the formation of a metal amide. At concen

Table 9 16 Solubilities in liquid ammonia

Element	Solubility (g metal/100 g NH <sub>3</sub> )	
	-33.4°C	0°C
Li	10.9	11.3
Na	25.1	23.0
K	47.1	48.5




Note that -33.4°C is the boiling point of liquid ammonia at one atmosphere pressure. The 0°C data were measured under pressure.

trations above 3M, solutions are copper-bronze coloured and have a metallic lustre because metal ion clusters are formed.

These solutions of metals in liquid ammonia conduct electricity better than any salt in any liquid, and the conductivity is similar to that of pure metals (specific conductivity of  $\text{Hg} = 10^4 \text{ ohm}^{-1}$ ;  $\text{Na}/\text{NH}_3 = 0.5 \times 10^4 \text{ ohm}^{-1}$ ;  $\text{K}/\text{NH}_3 = 0.45 \times 10^4 \text{ ohm}^{-1}$ ). Conduction is due mainly to the presence of solvated electrons.



The metals are also soluble in other amines and these solutions are used in organic and inorganic syntheses. These solutions of metals in liquid ammonia act as powerful reducing agents for the elements of Groups 14, 15 and 16, for many compounds and coordination complexes, and they will even reduce an aromatic ring.

These reductions can be carried out in liquid ammonia, but not in water, because the alkali metals are stronger reducing agents than is hydrogen, and so will react with water and liberate hydrogen. The metals can exist for some time in liquid ammonia.




## COMPOUNDS WITH CARBON

If lithium is heated with carbon, an ionic carbide  $\text{Li}_2\text{C}_2$  is formed. The other metals do not react with carbon directly, but do form similar carbides when heated with ethyne (formerly called acetylene), or when ethyne is passed through a solution of the metal in liquid ammonia.



These compounds contain the carbide ion  $[\text{C}\equiv\text{C}]^{2-}$  or hydridocarbide ion  $[\text{C}\equiv\text{C}-\text{H}]^-$ . The most important reaction of carbides is with water, when they give ethyne (acetylene). Thus they are termed acetylides.




$\text{LiC}_2\text{H}$  is used in the industrial manufacture of vitamin A.

The metals potassium, rubidium and caesium react with graphite by invading the space between the layers of carbon in the graphite lattice. They form highly coloured interstitial carbides that are nonstoichiometric, (that is of variable composition), ranging from  $\text{C}_{60}\text{K}$  (grey), to  $\text{C}_{36}\text{K}$  (blue), to a maximum invasion corresponding to  $\text{C}_8\text{K}$  (bronze). (See Chapter 12.)

## ORGANIC AND ORGANOMETALLIC COMPOUNDS


The alkali metals replace hydrogen in organic acids, forming salts such as sodium acetate (sodium ethanoate)  $\text{CH}_3\text{COONa}$  and potassium benzoate

$\text{C}_6\text{H}_5\text{COOK}$  Soap is a mixture of the sodium salts of palmitic, oleic and stearic acids (Palmitic acid  $\text{C}_{15}\text{H}_{31}\text{COOH}$  occurs in palm oil oleic acid  $\text{C}_{17}\text{H}_{33}\text{COOH}$  occurs in olive oil and stearic acid  $\text{C}_{17}\text{H}_{35}\text{COOH}$  occurs in beef and mutton fat and tallow) Soap is made by the saponification (hydrolysis) of naturally occurring fats and oils. These fats and oils are esters of glycerol, and their hydrolysis with  $\text{NaOH}$  first breaks the ester to glycerol and fatty acids neutralizing the fatty acid to give the sodium salts i.e. the soap. World production of soap was 7.4 million tonnes in 1991.



Lithium stearate is also a 'soap', and is made from  $\text{LiOH}$  and some natural fat such as tallow. It is widely used to thicken hydrocarbon oils used as lubricants (the so called detergent oils), and it is also used to make greases for motor vehicles.

Lithium shows a stronger tendency to covalency than the other alkali metals. Lithium also shows a diagonal relationship with magnesium. Magnesium forms a number of alkyl and aryl compounds called Grignard compounds which are very important in making organometallic compounds. It is not surprising that lithium also forms a number of covalent alkyls and aryls which are of great importance in the preparation of organometallic compounds. For example,  $(\text{LiCH}_3)_4$  is typical of a range of compounds: it is covalent, soluble in organic solvents, and can be sublimed or distilled. These compounds are frequently tetrameric or hexameric. They are made from the alkyl or aryl halide, usually the chloride, in a solvent such as light petroleum, cyclohexane, toluene or ether.




The structure of the  $(\text{LiCH}_3)_4$  cluster is unusual. The four  $\text{Li}$  atoms occupy the corners of a tetrahedron. Each methyl  $\text{C}$  atom is above a face of the tetrahedron, and forms a triple bridge to the three  $\text{Li}$  atoms that make up the face of the tetrahedron. The intramolecular  $\text{Li}-\text{C}$  distance is  $2.31 \text{ \AA}$ . The  $\text{C}$  is bonded to the three  $\text{H}$  atoms in the methyl group. The  $\text{C}$  is also bonded to a  $\text{Li}$  atom in another tetrahedron (with an intermolecular  $\text{Li}-\text{C}$  distance of  $2.36 \text{ \AA}$ ). The coordination number for the  $\text{C}$  atom is therefore 7. This cannot be explained by classical bonding theories as the  $\text{C}$  atom has only one  $s$  and three  $p$  orbitals available for bonding. The simplest explanation involves a four centre two electron bond covering the three  $\text{Li}$  atoms at the corners of a face and the  $\text{C}$  atom above it. In a similar way the coordination number of  $\text{Li}$  is also 7, made up by three  $\text{Li}$

in the tetrahedron, three C at the centres of faces of the tetrahedron, and one Li in another tetrahedron.







Lithium ethyl is tetrameric in the solid  $(\text{LiEt})_4$ , but is hexameric  $(\text{LiEt})_6$  when dissolved in hydrocarbons. The solid is similar in structure to  $(\text{LiCH}_3)_4$ , and the hexamer is thought to comprise an octahedron of Li atoms with Et groups above six of the eight faces, involving multi-centre bonding.

n-Butyl lithium is also tetrameric in the solid  $(\text{LiBu})_4$ . It is commercially available. Production is about 1000 tonnes/year. The main uses are as a polymerization catalyst and for alkylation. It is a very versatile reagent in the laboratory for the synthesis of aromatic derivatives and unsaturated derivatives such as vinyl and allyl lithium. Many of these reactions are similar to those using Grignard reagents.




From these an extremely wide range of organometallic and organic compounds can be prepared.

(R = alkyl or aryl)



Alkyls of Na, K, Rb and Cs are usually prepared from the corresponding organomercury compound.



These compounds are ionic  $\text{M}^+\text{R}^-$ , and are extremely reactive. They catch fire in air, react violently with most compounds except dinitrogen and saturated hydrocarbons, and are consequently difficult to handle.

## COMPLEXES, CROWNS AND CRYPTS

Group 1 metals stand out from the other groups in their weak tendency to form complexes. This is predictable because the factors favouring complex

formation are small size, high charge, and empty orbitals of low energy for forming the bonds and Group 1 metal ions are very large and have a low charge (+1)

A number of aqua complexes are known such as  $[\text{Li}(\text{H}_2\text{O})_4]^+$  and a primary hydration shell of four  $\text{H}_2\text{O}$  molecules arranged tetrahedrally is found in various crystalline salts.  $\text{Na}^+$  and  $\text{K}^+$  also have the same primary hydration shell, but  $\text{Rb}^+$  and  $\text{Cs}^+$  coordinate six  $\text{H}_2\text{O}$  molecules. Stable complexes are formed with phosphine oxides, for example complexes of formula  $[\text{LiX} \cdot 4\text{Ph}_3\text{PO}]$ ,  $[\text{LiX} \cdot 5\text{Ph}_3\text{PO}]$  and  $[\text{NaX} \cdot 5\text{Ph}_3\text{PO}]$  are known where X is a large anion such as  $\text{ClO}_4^-$ ,  $\text{I}^-$ ,  $\text{NO}_3^-$  or  $\text{SbF}_6^-$ . There is a slight tendency to form ammine complexes such as  $[\text{Li}(\text{NH}_3)_4]\text{I}$ . Weak complexes of sulphates, peroxosulphates and thiosulphates and also hexacyanoferrates, are known in solution.

However, some organic chelating agents (particularly salicylaldehyde and  $\beta$  diketones) are extremely strong complexing agents and Group 1 ions form complexes with these. These ligands are very strong complexing agents because they are multidentate that is they have more than one donor group so they form more than one bond to the metal, and also because they form a ring or chelate compound by bonding to the metal. Examples include salicylaldehyde, acetylacetone, benzoylacetone, methyl salicylate, o-nitrophenol, and o-nitrocresol. The metal usually attains a coordination number of 4 or 6 (see Figure 9.5).

An important development in the chemistry of the alkali metals is the discovery of complexes with polyethers, and 'cryptate' complexes with macrocyclic molecules with nitrogen and oxygen.

The crown ethers are an interesting class of complexing agents first synthesized by Pedersen in 1967. An example is dibenzo 18-crown-6 (see Figure 9.6), and the name indicates that there are two benzene rings in the compound, 18 atoms make up a crown shaped ring, and six of the ring atoms are oxygen. These six oxygen atoms may complex with a metal ion, even with large ions like Group 1 ions that are not very good at forming complexes. The organic part of the molecule is puckered to give the crown arrangement, and the oxygen atoms with their lone pairs are nearly planar about the metal ion at the centre of the ring. The bonding of the metal ion to the polyether is largely electrostatic, and a close fit between the size of the metal ion and the size of the hole in the centre of the polyether is essential. Cyclic polyethers can have varying sizes of ring, for example, benzo 12-crown-4 has a ring of 12 atoms, four of which are oxygen. The polyethers form complexes selectively with the alkali metal ions. The size of the ring opening in the crown determines the size of the metal ion which may be accommodated. Thus a crown-4 (a cyclic polyether with four oxygens) is selective for  $\text{Li}^+$ ,  $\text{Na}^+$  prefers crown-5, and  $\text{K}^+$  prefers crown-6. It is possible to get complexes with the unusual coordination number of 10, for example  $\text{K}^+$  (dibenzo 30-crown-10). Crown ethers form a number of crystalline complexes, but more importantly they are sometimes added to organic solvents to make them dissolve inorganic salts which, being ionic, would not normally dissolve. Polyethers of this type act as ion carriers inside living




Figure 9.5 Salicaldehyde and acetylacetone complexes.

cells to transport ions across cell membranes, and thus maintain the balance between  $Na^+$  and  $K^+$  inside and outside cells.

The cryptates are three-dimensional equivalents of the crown ethers, but contain nitrogen atoms which provide branching and act as extra donor sites in addition to the oxygen atoms to bond to the metal ion. They are called cryptates because they wrap round and hide the cation. A typical crypt is the molecule  $N[CH_2CH_2OCH_2CH_2OCH_2CH_2]_3N$ . This is called (cryptand-222) and forms a complex  $[Rb(crypt)]CNS \cdot H_2O$  in which six oxygen atoms and two nitrogen atoms in the crypt molecule bond to the metal ion, giving the metal ion a coordination number of 8. The ligand completely wraps round the metal ion, hiding it: hence the name crypt. The complex presents a hydrocarbon exterior, and so is soluble in organic solvents. Such complexes are used for solvent extraction, stabilizing uncommon oxidation states, and promoting otherwise improbable reactions.

An unusual compound  $[Na(cryptand-222)]^+Na^-$  can be formed by




Figure 9 6 Structures of some crown ethers

cooling a solution of Na in ethylamine with cryptand 222. This is a golden yellow, diamagnetic solid which is only stable below  $-10^{\circ}\text{C}$ . The interesting feature is that it contains  $\text{Na}^+$ , the sodide ion. Crystallographic studies show that the radius of  $\text{Na}^+$  is about  $2.3 \text{ \AA}$ . Electron transfer has occurred between two sodium atoms, forming  $\text{Na}^+$  and  $\text{Na}^-$ . The large crypt ligand completely shields the  $\text{Na}^+$  ion and prevents it recombining with  $\text{Na}^-$ . Other alkali compounds containing  $\text{K}^+$  potasside,  $\text{Rb}^+$  rubidide and  $\text{Cs}^+$  caeside ions have been made in a similar way. They are all yellow-brown in colour, and are less stable.

If the reaction is carried out with an excess of cryptand, some unusual complexes called electrides are formed. These are black solids and are paramagnetic, so they contain unpaired electrons. They have formulae such as  $[\text{Cs}^+(\text{cryptand 222})][(\text{cryptand 222})\text{e}^-]$  in which an electron is trapped in a hole of radius approximately  $2.4 \text{ \AA}$ .

### BIOLOGICAL IMPORTANCE

Living organisms require at least 27 elements, of which 15 are metals. Metals required in major quantities are K, Mg, Na and Ca. Minor quantities of Mn, Fe, Co, Cu, Zn and Mo, and trace amounts of V, Cr, Sn, Ni and Al, are required by at least some organisms.

Bulk quantities of Group 1 and 2 metals are required, mainly to balance




Figure 9 7 Cryptand 222 ligand



the electrical charges associated with negatively charged organic macromolecules in the cell, and also to maintain the osmotic pressure inside the cell, to keep it turgid and prevent its collapse.

In view of the close similarity of chemical properties between Na and K, it is surprising that their biological functions are very different.  $\text{Na}^+$  are actively expelled from cells, whereas  $\text{K}^+$  are not. This ion transport is sometimes called a sodium pump, and it involves both the active expulsion of  $\text{Na}^+$  and the active take-up of  $\text{K}^+$ . Analysis of the fluids inside and outside animal cells shows that ion transport really does occur. In animal cells the concentration of  $\text{K}^+$  is about 0.15 M and the concentration of  $\text{Na}^+$  is about 0.01 M. In body fluids (lymph and blood) the concentrations of  $\text{K}^+$  and  $\text{Na}^+$  are about 0.003 M and 0.15 M respectively. The transport of ions requires energy, and this is obtained by the hydrolysis of ATP. It is estimated that hydrolysis of one ATP molecule to ADP provides enough energy to move three  $\text{Na}^+$  ions out of the cell, and two  $\text{K}^+$  and one  $\text{H}^+$  ions back in to the cell. The mechanism for ion transport involves polyethers natural to the organism.

The different ratio of  $\text{Na}^+$  to  $\text{K}^+$  inside and outside cells produces an electrical potential across the cell membrane, which is essential for the functioning of nerve and muscle cells. The movement of glucose into cells is associated with  $\text{Na}^+$  ions; they enter the cell together. This is favoured by a high concentration gradient. The  $\text{Na}^+$  ions entering the cell in this way must then be expelled. The movement of amino acids is similar.  $\text{K}^+$  ions inside the cell are essential for the metabolism of glucose, the synthesis of proteins, and the activation of some enzymes.

The 1987 Nobel Prize for Chemistry was awarded to C.J. Pedersen, J.M. Lehn and D. Cram for their work on the discovery and applications of crown ethers and cryptates.

## DIFFERENCES BETWEEN LITHIUM AND THE OTHER GROUP 1 ELEMENTS

The properties of lithium and its compounds differ far more from those of the other Group 1 elements than the other Group 1 elements and compounds differ among themselves. Apart from having the same oxidation number as the rest of Group 1, lithium compounds may show closer similarities with Group 2 elements (particularly magnesium) than they show towards their own group. Some of the differences are set out below:

1. The melting and boiling points of lithium metal are much higher than those for the other Group 1 elements.
2. Lithium is much harder than the other Group 1 metals.
3. Lithium reacts the least readily with oxygen, forming the normal oxide. It forms a peroxide only with great difficulty, and the higher oxides are unstable.
4. Lithium hydroxide is less basic than the other hydroxides in the group, and therefore many of its salts are less stable.  $\text{Li}_2\text{CO}_3$ ,  $\text{LiNO}_3$  and

$\text{LiOH}$  all form the oxide on gentle heating, though the analogous compounds of the rest of the group are stable. Another example of the less basic nature is that though lithium forms a bicarbonate in solution, it does not form a solid bicarbonate, whereas the others all form stable solid bicarbonates.


- 5 Lithium forms a nitride  $\text{Li}_3\text{N}$ . None of the other Group 1 elements forms a nitride, but Group 2 elements form nitrides.
- 6 Lithium reacts directly with carbon to form an ionic carbide. None of the other Group 1 elements do this, but Group 2 elements all react similarly with carbon.
- 7 Lithium has a greater tendency to form complexes than have the heavier elements, and ammoniated salts such as  $[\text{Li}(\text{NH}_3)_4]\text{I}$  exist as solids.
- 8  $\text{Li}_2\text{CO}_3$ ,  $\text{Li}_3\text{PO}_4$  and  $\text{LiF}$  are all insoluble in water, and  $\text{LiOH}$  is only sparingly soluble. The rest of Group 1 form soluble compounds, but the corresponding magnesium salts are insoluble or sparingly soluble.
- 9 The halides and alkyls of lithium are far more covalent than the corresponding sodium compounds, and because of this covalency they are soluble in organic solvents. Similarly, lithium perchlorate and to a lesser extent sodium perchlorate resemble magnesium perchlorate in their high solubility in acetone (propanone).
- 10 The lithium ion itself, and also its compounds, are more heavily hydrated than those of the rest of the group.

Several generalizations may be drawn from this apparently anomalous behaviour of lithium.

The first element in each of the main groups (Li, Be, B, C, N, O and F) differs from the rest of the group. This is partly because the first element is much smaller than the subsequent elements and consequently it is more likely to form covalent compounds (Fajans' rules) and complexes.

The first element in a group can form a maximum of four conventional electron pair bonds. This is because the outer shell of electrons contains only one  $s$  orbital and three  $p$  orbitals. The subsequent elements can use  $d$  orbitals for bonding; they can attain a coordination number of 6 by using one  $s$ , three  $p$  and two  $d$  orbitals. For this reason the coordination number attained by a complex or a covalent compound of the first element in a group is commonly 4 and for the subsequent elements the coordination number is commonly 6. This simple concept is based on a bond consisting of two electrons shared between two atoms. Exceptions occur when multi-centre bonds are formed (as in  $\text{Li}_4(\text{CH}_3)_4$ ).

The similarity between lithium (the first member of Group 1) and magnesium (the second element in Group 2) is called a diagonal relationship. Diagonal relationships also exist between other pairs of elements: Be and Al, B and Si as shown.



The diagonal relationship arises because of the effects of both size and charge. On descending a group, the atoms and ions increase in size. On moving from left to right in the periodic table, the size decreases. Thus on moving diagonally, the size remains nearly the same. For example, lithium is smaller than sodium, and magnesium is also smaller than sodium, and hence lithium and magnesium are similar in size. The sizes of  $\text{Li}^+ = 0.76 \text{ \AA}$  and  $\text{Mg}^{2+} = 0.72 \text{ \AA}$  are close, and so in situations where size is important their behaviour should be similar.

Beryllium and aluminium also show a diagonal relationship. In this case the sizes are not so close ( $\text{Be}^{2+} = 0.45 \text{ \AA}$  and  $\text{Al}^{3+} = 0.535 \text{ \AA}$ ), but the charge per unit area is similar ( $\text{Be}^{2+}$  2.36 and  $\text{Al}^{3+}$  2.50) because the charges are 2+ and 3+ respectively.

$$\text{Charge per unit area} = \frac{(\text{ionic charge})}{\frac{4}{3} \cdot \pi \cdot (\text{ionic radius})^2}$$

It is sometimes suggested that the diagonal relationship arises because of a diagonal similarity in electronegativity values.

Li	Be	B	C
1.0	1.5	2.0	2.5
Na	Mg	Al	Si
0.9	1.2	1.5	1.8

Since ionic size and electronegativity are closely related, this is part of the same picture.

## FURTHER READING

- Addison, C.C. (1984) *The Chemistry of the Liquid Alkali Metals*, John Wiley, Chichester.
- Bach, R.O. (ed.) (1985) *Lithium: Current Applications in Science, Medicine and Technology*, John Wiley, Chichester and New York (Conference proceedings).
- Cram, D.J. and Cram, J.M. (1995) *Container Molecules and their Guests*, Royal Society of Chemistry, Cambridge.
- Dietrich, B. (1985) Coordination chemistry of alkali and alkaline earth cations with macrocyclic ligands, *J. Chem. Ed.*, **62**, 954–964. (Crowns and crypts.)
- Gockel, G.W. (1991) *Crown Ethers and Cryptands* (one of a series on Supramolecular Chemistry, ed. Stoddart, J.F.), Royal Society of Chemistry, Cambridge.
- Hanusa, T.P. (1987) Re-examining the diagonal relationships, *J. Chem. Ed.*, **64**, 686–687.
- Hart, W.A. and Beumel, O.F. (1973) *Comprehensive Inorganic Chemistry*, Vol. I (Chapter 7: Lithium and its compounds), Pergamon Press, Oxford.
- Hughes, M.N. and Birch, N.J. (1982) IA and IIA cations in biology, *Chemistry in Britain*, **18**, 196–198.
- Jolly, W.L. (1972) *Metal Ammonia Solutions*, Dowden, Hutchinson and Row, Stroudsburg, PA.
- Lagowski, J. (ed.) (1967) *The Chemistry of Non-aqueous Solvents* (Chapter 6), Academic Press, New York. (Solutions of metals in liquid ammonia.)
- Lehn, J.M. (1973) Design of organic complexing agents, *Structure and Bonding*, **16**, 1–69.
- Lippard, S. (ed.) (1984) *Progress in Inorganic Chemistry*, Vol. 32 by Dye, J.L.,

- Electrides Negatively Charged Metal Ions and Related Phenomena* Wiley Interscience New York
- March N N (1990) *Liquid Metals* Cambridge University Press
- Parker D (1983) Alkali and alkaline earth cryptates *Adv Inorg and Rad o-chem* 27 1–26
- Pedersen C J (1967) *J Am Chem Soc* 89 2495 7017 7036 (Cyclic polyethers and their complexes with metals )
- Pedersen C J and Frensdorf H K (1972) *Angew Chem* 11 16–25 (Cyclic polyethers and their complexes with metals )
- Sargeson A M (1979) Caged metal ions *Chemistry in Britain* 15 23–27 (A straightforward account of crown ethers crypts etc )
- The Chemical Society (1967) *The Alkali Metals* (Special Publication No 22) London
- Waddington T C (ed ) (1969) *Non Aqueous Solvent Systems* (Chapter 1 by Jolly W L and Hallada C J ) Nelson (Solutions of metals in liquid ammonia )
- Wakefield B J (1976) *The Chemistry of Organolithium Compounds* Pergamon Press Oxford
- Whaley T P (1973) *Comprehensive Inorganic Chemistry* Vol 1 (Chapter 8 Sodium potassium rubidium caesium and francium) Pergamon Press Oxford

## PROBLEMS

- Why are Group 1 elements
  - univalent
  - largely ionic
  - strong reducing agents
  - poor complexing agents?
  - Why do they have the lowest first ionization energy values in their periods?
- Why are the Group 1 metals soft low melting and of low density? (Refer back to Chapter 5 )
- Lithium is the smallest ion in Group 1. It would therefore be expected to have the highest ionic mobility, and hence solutions of its salts would be expected to have a higher conductivity than solutions of caesium salts. Explain why this is not so
- What is the reason for lithium having a greater tendency to form covalent compounds than the other elements in the group?
- The atomic radius for lithium is  $1.23 \text{ \AA}$ . When the outermost  $2s$  electron is ionized off the ionic radius of  $\text{Li}^+$  is  $0.76 \text{ \AA}$ . Assuming that the difference in radii relates to the space occupied by the  $2s$  electron calculate what percentage of the volume of the lithium atom is occupied by the single valence electron. Is this assumption fair? (Volume of a sphere is  $\frac{4}{3} \pi r^3$ ) (Answer 76.4% )
- Why and in what ways does lithium resemble magnesium?
- What products are formed when each of the Group 1 metals is burnt in dioxygen? How do these products react with water? Use the molecular

orbital theory to describe the structure of the oxides formed by sodium and potassium.

8. Explain the difference in reactivity of the Group 1 metals with water.
9. The ionization energies of Group 1 elements suggest that caesium should be the most reactive, but the standard electrode potentials suggest that lithium is the most reactive. Reconcile these two observations.
10. Describe how you would make lithium hydride. Give equations to show two important properties of lithium hydride. The compound contains the isoelectronic ions  $\text{Li}^+$  and  $\text{H}^-$ . Which ion is the larger and why?
11. Give equations to show the reactions between sodium and: (a)  $\text{H}_2\text{O}$ , (b)  $\text{H}_2$ , (c) graphite, (d)  $\text{N}_2$ , (e)  $\text{O}_2$ , (f)  $\text{Cl}_2$ , (g)  $\text{Pb}$ , (h)  $\text{NH}_3$ .
12. Group 1 elements generally form very soluble compounds. Name some insoluble or sparingly soluble compounds. How are these elements detected and confirmed in qualitative analysis?
13. Describe the colour and nature of the solutions of Group 1 metals in liquid ammonia. Give an equation to show how these solutions decompose.
14. Draw the crystal structures of  $\text{NaCl}$  and  $\text{CsCl}$ . What is the coordination number of the metal ion in each case? Explain why these two salts adopt different structures.
15. Do the alkali metals form many complexes? Which of the metal ions in the group are best at forming complexes? Which are the best complexing agents?
16. Draw the complexes formed by  $\text{Li}^+$ ,  $\text{Na}^+$  and  $\text{K}^+$  with acetyl acetone and with salicylaldehyde. Why do the coordination numbers differ?
17. What is a crown ether, and what is a crypt? Draw examples of Group 1 complexes with these molecules. In what way is this type of complex of biological importance?
18. Which of the following methods would you use to extinguish a fire of lithium, sodium or potassium metals? Explain why some of these are unsuitable, and give the reactions involved.
  - (a) water
  - (b) dinitrogen
  - (c) carbon dioxide
  - (d) asbestos blanket
19. The four general methods of extracting metals are thermal decomposition, displacement of one element by another, chemical reduction, and electrolytic reduction. How are Group 1 metals obtained and why are the other methods unsuitable?


20. 0.347 g of a metal (A) was dissolved in dilute  $\text{HNO}_3$ . This solution gave a red coloration to a non-luminous Bunsen burner flame, and on evaporation gave 0.747 g of metal oxide (B). (A) also reacted with dinitrogen, forming a compound (C), and with hydrogen, forming (D). On reacting 0.1590 g of (D) with water, a gas (E) was evolved and a sparingly soluble compound (F) formed, which gave a strongly basic reaction and required 200 ml of 0.1000 M hydrochloric acid to neutralize it. Identify the substances (A) to (F) and explain the reactions involved.

# The chlor-alkali industry

10

The chlor-alkali industry includes the production of three main chemicals: sodium hydroxide (sometimes called caustic soda), chlorine, and sodium carbonate (sometimes called soda ash). All three chemicals are made from sodium chloride.

NaOH and Cl<sub>2</sub> are produced simultaneously by the electrolysis of an aqueous solution of NaCl. NaOH is the most important alkali used in industry, and Cl<sub>2</sub> is also an extremely important industrial chemical. Sodium carbonate is included with the other two chemicals for two reasons – first because in many applications such as making paper, soap and detergents it can be used interchangeably with sodium hydroxide, and second because Na<sub>2</sub>CO<sub>3</sub> can quite easily be converted into NaOH (or vice versa) using the lime–caustic soda process. In this process, the reaction is reversible, and depending on the relative demands and cost of sodium carbonate and sodium hydroxide it may be used in either direction. Before 1955 Na<sub>2</sub>CO<sub>3</sub> was used very extensively for water softening as it prevented the formation of scum when using soap in hard water. Soap is discussed under ‘Organic and organometallic compounds’ in Chapter 9, and hard water is discussed in Chapter 11. Thus before 1955 it was economic to make Na<sub>2</sub>CO<sub>3</sub> from NaOH. More recently the use of soap has declined as detergents have become more widely used, and with this the demand for Na<sub>2</sub>CO<sub>3</sub> has declined. Nowadays the reverse reaction is carried out on a limited scale, converting Na<sub>2</sub>CO<sub>3</sub> to NaOH.



All three chemicals are classed as ‘heavy inorganic chemicals’ because of the very large tonnages involved. A list of the chemicals produced in the largest quantities is shown in Table 10.1.

## LEBLANC PROCESS

C.W. Scheele discovered chlorine in 1774 by oxidizing hydrochloric acid with manganese dioxide.






Table 10.1 Some figures for tonnes of heavy chemicals produced in 1991, 1992, 1993 and 1994


Chemical	Millions of tonnes		
	World	USA	UK
1 H <sub>2</sub> SO <sub>4</sub>	145.5 <sup>b</sup>	42.3 <sup>b</sup>	1.7 <sup>b</sup>
2 CaO	127.9 <sup>c</sup>	18.4 <sup>c</sup>	2.5 <sup>b</sup>
3 NH <sub>3</sub>	110 <sup>b</sup>	17.3 <sup>c</sup>	1.2 <sup>c</sup>
4 O <sub>2</sub>	(100) <sup>b</sup>	23.3 <sup>c</sup>	2.5 <sup>c</sup>
5 NH <sub>4</sub> NO <sub>3</sub>	(75) <sup>b</sup>	8.4 <sup>c</sup>	—
6 N <sub>2</sub>	(60) <sup>b</sup>	32.6 <sup>c</sup>	—
7 ethene	47.5 <sup>d</sup>	20.6 <sup>c</sup>	1.8 <sup>a</sup>
8 NaOH	38.7 <sup>d</sup>	12.9 <sup>c</sup>	—
9 Cl <sub>2</sub>	35.3 <sup>d</sup>	12.0 <sup>c</sup>	0.88 <sup>a</sup>
10 Na <sub>2</sub> CO <sub>3</sub>	31.5 <sup>c</sup>	9.9 <sup>c</sup>	—
11 propylene	25.9 <sup>d</sup>	11.2 <sup>c</sup>	0.79 <sup>a</sup>
12 HNO <sub>3</sub>	24.7 <sup>a</sup>	8.5 <sup>c</sup>	—
13 methanol	20.6 <sup>c</sup>	5.3 <sup>c</sup>	0.40 <sup>a</sup>
14 benzene	20.4 <sup>a</sup>	6.2 <sup>c</sup>	0.91 <sup>a</sup>
15 H <sub>3</sub> PO <sub>4</sub>	20.3 <sup>a</sup>	11.5 <sup>b</sup>	—
16 ethanol	15.8 <sup>b</sup>	0.9 <sup>b</sup>	0.24 <sup>b</sup>
17 vinyl chloride	14.9 <sup>d</sup>	6.9 <sup>c</sup>	0.16 <sup>a</sup>
18 HCl	12.3 <sup>a</sup>	3.2 <sup>c</sup>	0.15 <sup>a</sup>

<sup>a</sup> 1991 value, <sup>b</sup> 1992 value, <sup>c</sup> 1993 value, <sup>d</sup> 1994 value



He also described the bleaching properties of chlorine, and these eventually led to demand for both chlorine and sodium hydroxide on an industrial scale for use in the textiles industry. At that time there was no chemical industry, so people had to make their own chemicals. The first problem was to make the HCl. This was produced by the Leblanc process. Though the process is now obsolete, it warrants description because it was the first large scale industrial process in Europe, it lasted for most of the nineteenth century, and it illustrates the need to consider what raw materials are needed, how they can be obtained, and the commercial need to sell everything produced. (At this time Europe led the world industrially and the process was imported into the USA from Europe.)



The HCl was then oxidized to give Cl<sub>2</sub>



The Na<sub>2</sub>SO<sub>4</sub> was used either to make glass, or to make Na<sub>2</sub>CO<sub>3</sub> and NaOH






In this process, the chemicals used are  $\text{H}_2\text{SO}_4$ ,  $\text{NaCl}$ ,  $\text{CaCO}_3$  and  $\text{C}$ , and the products are  $\text{NaOH}$  and  $\text{Cl}_2$  (and to a lesser extent  $\text{Na}_2\text{SO}_4$ ). The raw materials were obtained:



$\text{NaCl}$  – mined or extracted as brine solution

$\text{CaCO}_3$  – mined as limestone




In 1874 world production of  $\text{NaOH}$  was 525 000 tonnes, of which 94% was produced by the Leblanc process. Production of  $\text{NaOH}$  had risen to 1 800 000 tonnes by 1902, but by then only 8% was produced by the Leblanc process. The Leblanc process became obsolete because cheaper methods were found. It was replaced in turn by the Weldon process, the Deacon process, and eventually by electrolysis.

### WELDON AND DEACON PROCESSES

The Leblanc process used  $\text{MnO}_2$  to oxidize the  $\text{HCl}$ , but the  $\text{MnCl}_2$  formed was wasted. The Weldon process (1866) recycled the  $\text{MnCl}_2$ , and was therefore cheaper.

In the Deacon process (1868), air was used to oxidize the  $\text{HCl}$  instead of using  $\text{MnO}_2$ . A gas phase reaction was performed between  $\text{HCl}$  and air on the surface of bricks soaked in a solution of  $\text{CuCl}_2$ , which acted as a catalyst. The reaction is reversible, and a conversion of about 65% is possible.



Nowadays about 90% of the world supply of chlorine comes from the electrolysis of an aqueous solution of sodium chloride (brine). Most of the remainder is produced by the electrolysis of molten  $\text{NaCl}$  in the production of sodium metal, electrolysis of aqueous  $\text{KCl}$  in the production of  $\text{KOH}$ , and electrolysis of molten  $\text{MgCl}_2$  in the extraction of magnesium metal. However, a small amount is made by the oxidation of  $\text{HCl}$  with air, in a slightly modified Deacon process. This started in 1960, and uses a didymium promoted catalyst of  $\text{Dm}_2\text{O}_3$  and  $\text{CuCl}_2$  at a slightly lower temperature of  $400^\circ\text{C}$ . (Didymium is an old name and means 'twin'. It was once thought to be an element, but was later resolved into two lanthanide elements, praseodymium and neodymium. The catalyst is a finely powdered mixture of solids which flows like a liquid, and this is termed a fluidized bed.)

### ELECTROLYTIC PROCESSES


Electrolysis of brine was first described in 1800 by Cruickshank, but it was not until 1834 that Faraday put forward the Laws of Electrolysis. At that

time electrolysis was strictly limited because primary batteries were the only source of electricity. This changed in 1872 when Gramme invented the dynamo. The first commercial electrolytic plant was started in Frankfurt (Germany) in 1891, where the cell was filled, electrolysed, emptied then refilled and so on. This was therefore a *discontinuous or batch process*. Clearly a cell which could run continuously, and did not need emptying, would produce more and cost less to operate. Many developments and patents attempting to exploit the commercial possibilities appeared over the next twenty years. The first commercially operated plant to use a *continuous diaphragm cell* was probably that designed by Le Seur at Romford (Maine) in 1893, followed by Castner cells at Saltville (Virginia, USA) in 1896. The first in the UK was set up by Hargreaves and Bird in 1897 at Runcorn. In all of these (and also in many modern diaphragm cells), asbestos was used as the diaphragm to separate the anode and cathode compartments. Brine was constantly added, and NaOH and  $\text{Cl}_2$  were produced continuously.


About the same time, Castner (who was an American working in Birmingham, England) and Kellner (an Austrian working in Vienna) developed and patented similar versions of the *mercury cathode cell* in 1897. Their combined patents were used by the Castner Kellner Alkali Company, also at Runcorn, and also in 1897.

The same two types of cell, diaphragm and mercury cathode, still remain in use. The early electrolytic plants produced about 2 tonnes of chlorine per day, but modern plants produce 1000 tonnes per day.


In the electrolysis of brine, reactions occur at both the anode and the cathode.



Side reactions may also occur if the products mix



and also another reaction may occur to a small extent at the anode



## DIAPHRAGM CELL

A porous diaphragm of asbestos is used to keep the  $\text{H}_2$  and  $\text{Cl}_2$  gases (produced at the electrodes) separated from one another. If  $\text{H}_2$  and  $\text{Cl}_2$  gases mix they react and the reaction may be explosive. In daylight (and more so in sunlight) a photolytic reaction takes place which produces chlorine atoms. These lead to an explosive chain reaction with hydrogen.




Figure 10.1 A diaphragm cell.


The diaphragm also separates the anode and cathode compartments. This reduces the chance that NaOH produced in the cathode compartment can mix and react with  $\text{Cl}_2$  produced in the anode compartment. This reduces the chance of the side reaction producing sodium hypochlorite, NaOCl. However, some sodium hydroxide or  $\text{OH}^-$  may diffuse into the other compartment, and this is inhibited by maintaining the level of electrolyte higher in the anode compartment than in the cathode compartment, so there is a small positive flow from the anode to the cathode compartment. Traces of dioxygen are produced in a side reaction. This reacts with the carbon electrodes, gradually destroying them and forming  $\text{CO}_2$ .

There is considerable interest in using thin synthetic plastic membranes for the diaphragm instead of asbestos. These membranes are made of a polymer called nafion, supported on a teflon mesh. (Nafion is a copolymer of tetrafluoroethylene and a perfluorosulphonylethoxy ether.) Plastic membranes have a lower resistance than asbestos.

Less than half the NaCl is converted to NaOH, and a mixture of about 11% NaOH and 16% NaCl is usually obtained. This solution is concentrated in a steam evaporator, when a considerable amount of NaCl crystallizes out, giving a final solution containing 50% NaOH and 1% NaCl. *It is important to note that NaOH made in this way always contains some NaCl.* This may or may not matter, depending on how the NaOH is to be used. For most industrial purposes, the product is sold as a solution, as the cost of evaporating it to give the solid exceeds the increased cost of transporting the solution.

## MERCURY CATHODE CELL

During the electrolysis of brine,  $\text{Na}^+$  ions migrate towards the cathode, and when they get there the ions are discharged.



If the cathode is made of mercury, the Na atoms produced dissolve in the mercury and form an amalgam, or loose alloy. The amalgam is pumped to a different compartment called the denuder, where water trickles over




Figure 10 2 Commercial diaphragm cell for  $Cl_2$  and  $NaOH$

lumps of graphite (here acting as an inert solid) The water and the  $Na$  in the amalgam react and in this way *pure*  $NaOH$  at 50% strength is obtained



The clean mercury is recycled back to the electrolysis tank. Originally the anodes were made of graphite but because traces of dioxygen are produced in a side reaction they become pitted owing to the formation of  $CO_2$ . The anodes are now made of steel coated with titanium. Titanium is




Figure 10 3 Mercury cathode cell for  $Cl_2$  and  $NaOH$

very resistant to corrosion, and this not only overcomes the problem of pitting and forming  $\text{CO}_2$ , but also lowers the electrical resistance.

### QUANTITIES

In both electrolytic processes (diaphragm cell and mercury cathode cell) equimolar amounts of  $\text{Cl}$  and  $\text{NaOH}$  are produced. Since  $\text{Cl}$  has an atomic weight of 35.5, and  $\text{NaOH}$  has a molecular weight of 40, it follows that electrolysis yields 40 parts by weight of  $\text{NaOH}$  to 35.5 parts of  $\text{Cl}_2$ . This corresponds to 1.13 tonnes of  $\text{NaOH}$  for 1 tonne of  $\text{Cl}_2$ . In 1994 world production of  $\text{Cl}_2$  was 35.3 million tonnes.

Prior to 1965 demand for  $\text{NaOH}$  exceeded that for  $\text{Cl}_2$ , so  $\text{Cl}_2$  was cheap. Since then the position has reversed, largely due to the use of large amounts of  $\text{Cl}_2$  in making plastics such as polyvinyl chloride. (World production of PVC was 14.9 million tonnes in 1991.)

### SODIUM CARBONATE

World production of  $\text{Na}_2\text{CO}_3$  in 1993 was 31.5 million tonnes, and 49% of this was used in the glass industry. Smaller amounts were used to make various sodium phosphates and polyphosphates which are used for water

Table 10.2 Chlorine production (million tonnes/year)

World production	35.3
USA	12.0 (34%)
Soviet Union	8 (23%) approx.
Western Germany	3.5 (10%)
Canada	1.4 (4%)
France	1.4 (4%)
UK	1.0 (3%)
Japan	0.93 (2.6%)
Italy	0.92 (2.6%)
Spain	0.51 (1.4%)

Table 10.3 Major uses of chlorine

	EEC	USA
Vinyl chloride monomer ( $\text{CH}_2=\text{CHCl}$ )	31%	18%
Organic intermediates	16%	
Chlorinated solvents	14%	22%
( $\text{C}_2\text{H}_4\text{Cl}$ approx. 40 000 tonnes/year, $\text{CH}_2\text{Cl} \cdot \text{CH}_2\text{Cl}$ etc.)		
Propylene oxide	8%	5%
Bleaching wood pulp and paper		11%
Chloromethanes ( $\text{CCl}_4$ , $\text{CHCl}_3$ etc.)		10%
Inorganic materials		8%
(bleaching powder, sodium hypochlorite)		
Other uses	31%	26%

Table 10.4 Major uses of caustic soda


	USA
Inorganic chemicals	21%
Organic chemicals	17%
Wood pulp and paper making	14%
Neutralizations	12%
Alumina production	7%
Soap	4%
Rayon	4%
Other uses	21%

Table 10.5 Major uses of sodium carbonate

	USA
Glass – bottles	34%
Sodium phosphates	12%
Glass – sheets and glass fibre	11%
Sodium silicate	5%
Alkaline cleaners	5%
Wood pulp and paper making	4%
Other uses	29%

softening (being added to various cleaning powders), and in wood pulp and paper making. The increased awareness of the effect of 'acid rain' on plants and buildings has led to a new use for  $\text{Na}_2\text{CO}_3$  in treating the flue gases from coal- and oil fired power stations, to remove  $\text{SO}_2$  and  $\text{H}_2\text{SO}_4$ . This use may eventually account for a large tonnage of  $\text{Na}_2\text{CO}_3$ .

The main producing countries are the USA (30%), the Soviet Union (19%), China (8%), Western Germany (5%), Japan (4%), Bulgaria (4%) and Poland (4%). Most of the  $\text{Na}_2\text{CO}_3$  is produced synthetically by the Solvay (ammonia-soda) process. However, since prehistoric times a natural deposit called Trona,  $\text{Na}_2\text{CO}_3 \cdot \text{NaHCO}_3 \cdot 2\text{H}_2\text{O}$ , has been obtained from dried-up lake beds in Egypt. Large amounts are now mined, particularly in the USA and Kenya. In the USA 9.9 million tonnes of  $\text{Na}_2\text{CO}_3$  were used in 1993. About 6 million tonnes/year of  $\text{Na}_2\text{CO}_3$  is made from Trona. Trona is sometimes called sodium sesquicarbonate (sesqui means one and a half), and this is converted to sodium carbonate by heating:




In the description of the chlor-alkali industry it was mentioned that sodium carbonate (soda ash) can be used instead of  $\text{NaOH}$  in applications such as making paper, soap and detergents, and that sodium carbonate can be used to make  $\text{NaOH}$  by the lime-caustic soda process. However, as  $\text{NaOH}$  is at present cheap and plentiful, not much sodium carbonate is

used for these purposes. With the increased use of detergents, there has been a decline in the use of 'washing soda'  $\text{Na}_2\text{CO}_3 \cdot 10\text{H}_2\text{O}$  for water softening.






### THE SOLVAY (OR AMMONIA-SODA) PROCESS

There have been many attempts to make  $\text{Na}_2\text{CO}_3$  more cheaply than by the Leblanc process, by using the overall reaction:



The reaction was first studied by Freshnel in 1811, and several commercial plants were built but were quickly abandoned because they failed to make a profit, or they encountered technical problems such as corrosion of the plant, contamination of the product and blocked pipes. Ernest Solvay was the first to operate a commercial plant successfully, in Belgium (1869).

The process is much more complicated than the overall equation implies, and to make things worse the reaction is reversible and only 75% of the NaCl is converted. The first stage in the process is to purify saturated brine, and then react it with gaseous ammonia. The ammoniated brine is then carbonated with  $\text{CO}_2$ , forming  $\text{NaHCO}_3$ . This is insoluble in the brine solution because of the common ion effect and so can be filtered off, and on heating to  $150^\circ\text{C}$  it decomposes to anhydrous  $\text{Na}_2\text{CO}_3$  (called light soda ash in industry because it is a fluffy solid with a low packing density of about  $0.5\text{ g cm}^{-3}$ ). Next  $\text{CO}_2$  is stripped (removed) by heating the solution, and the  $\text{CO}_2$  is reused. Then the  $\text{NH}_3$  is driven off by adding alkali (a slurry of lime in water), and the ammonia is reused. Lime ( $\text{CaO}$ ) is obtained by heating limestone ( $\text{CaCO}_3$ ), and this also provides the  $\text{CO}_2$  required. When lime is mixed with water it gives  $\text{Ca}(\text{OH})_2$ .



Thus the materials consumed are NaCl and  $\text{CaCO}_3$ , and there is one useful product,  $\text{Na}_2\text{CO}_3$ , and one by-product,  $\text{CaCl}_2$ . There is little requirement for  $\text{CaCl}_2$ , so only a little is recovered from solution, and the rest is wasted. The largest use of  $\text{Na}_2\text{CO}_3$  is for glass making (Table 10.5), and this requires 'heavy ash', which is  $\text{Na}_2\text{CO}_3 \cdot \text{H}_2\text{O}$ . To obtain this, the 'light ash' produced in the Solvay process (which is anhydrous  $\text{Na}_2\text{CO}_3$ ) is recrystallized from hot water.

## FURTHER READING

- Adam D J (1980) Early industrial electrolysis *Education in Chemistry* 17 13–14–16
- Borgstedt H U and Mathews C K (1987) *Applied Chemistry of the Alkali Metals* Plenum London
- Boynton R S (1980) *Chemistry and Technology of Lime and Limestone* 2nd ed John Wiley Chichester
- Buchner W, Schleibs R, Winter G and Buchel K H (1989) *Industrial Inorganic Chemistry* VCH Publishers Weinheim
- Grayson M and Eckroth D (eds) *Kirk Othmer Concise Encyclopedia of Chemical Technology* John Wiley
- Kirk Othmer Encyclopedia of Chemical Technology* (1984) (26 volumes) 3rd ed Wiley Interscience
- Stephenson R M (1966) *Introduction to the Chemical Process Industries* Van Nostrand Reinhold New York
- Thompson R (ed) (1986) *The Modern Inorganic Chemicals Industry* (chapter by Purcell R W The Chlor Alkali Industry chapter by Campbell A Chlorine and Chlorination Special Publication No 31 The Chemical Society London
- Venkatesh S and Tilak S (1983) Chlor alkali technology *J Chem Ed* 60 276–278

Production figures for the top 50 chemicals produced in the USA each year are published in *Chemical and Engineering News* in one of the issues in June each year (see Appendix K)

## PROBLEMS

- 1 What chemicals are obtained industrially from sodium chloride? Outline the processes
- 2 Describe in detail the industrial electrolysis of sodium chloride. Comment on the purity of the products
- 3 What are the main uses of chlorine, sodium and caustic soda? Why has demand for chlorine increased dramatically?
- 4 What is  $\text{Na}_2\text{CO}_3$  used for? Why has its use declined? Explain how at different times NaOH has been converted into  $\text{Na}_2\text{CO}_3$  and at other times  $\text{Na}_2\text{CO}_3$  has been converted into NaOH



# Group 2 – the alkaline earth elements

11

Table 11.1 Electronic structures

Element	Symbol	Electronic structure
Beryllium	Be	$1s^2 2s^2$ or [He] $2s^2$
Magnesium	Mg	$1s^2 2s^2 2p^6 3s^2$ or [Ne] $3s^2$
Calcium	Ca	$1s^2 2s^2 2p^6 3s^2 3p^6 4s^2$ or [Ar] $4s^2$
Strontium	Sr	$1s^2 2s^2 2p^6 3s^2 3p^6 3d^{10} 4s^2 4p^6 5s^2$ or [Kr] $5s^2$
Barium	Ba	$1s^2 2s^2 2p^6 3s^2 3p^6 3d^{10} 4s^2 4p^6 4d^{10} 5s^2 5p^6 6s^2$ or [Xe] $6s^2$
Radium	Ra	[Rn] $7s^2$

## INTRODUCTION

The Group 2 elements show the same trends in properties as were observed with Group 1. However, beryllium stands apart from the rest of the group, and differs much more from them than lithium does from the rest of Group 1. The main reason for this is that the beryllium atom and  $\text{Be}^{2+}$  are both extremely small, and the relative increase in size from  $\text{Be}^{2+}$  to  $\text{Mg}^{2+}$  is four times greater than the increase between  $\text{Li}^+$  and  $\text{Na}^+$ . Beryllium also shows some diagonal similarities with aluminium in Group 13. Beryllium and barium compounds are all very toxic.

The elements form a well graded series of highly reactive metals, but are less reactive than Group 1. They are typically divalent, and generally form colourless ionic compounds. The oxides and hydroxides are less basic than those of Group 1: hence their oxosalts (carbonates, sulphates, nitrates) are less stable to heat. Magnesium is an important structural metal, and is used in large amounts (303 000 tonnes in 1993). Several compounds are used in vast quantities: limestone ( $\text{CaCO}_3$ ) is used to make quicklime  $\text{CaO}$  (127.9 million tonnes in 1993) and cement (1396 million tonnes in 1993), and 14.2 million tonnes of chalk are also used. Other compounds used on a large scale include gypsum  $\text{CaSO}_4$  (88.2 million tonnes in 1992), fluorite  $\text{CaF}_2$  (3.6 million tonnes in 1992), magnesite  $\text{MgCO}_3$  (10.8 million tonnes in 1992) and barytes  $\text{BaSO}_4$  (4.9 million tonnes in 1992).

$\text{Mg}^{2+}$  and  $\text{Ca}^{2+}$  are essential elements in the human body, and  $\text{Mg}^{2+}$  is an important constituent of chlorophyll.

## ELECTRONIC STRUCTURE

All Group 2 elements have two s electrons in their outer shell. Ignoring the filled inner orbitals, their electronic structures may be written  $2s^2$ ,  $3s^2$ ,  $4s^2$ ,  $5s^2$ ,  $6s^2$  and  $7s^2$ .

## OCCURRENCE AND ABUNDANCE

Beryllium is not very familiar, partly because it is not very abundant (2 ppm) and partly because it is difficult to extract. It is found in small quantities as

Table 11.2 Abundance of the elements in the earth's crust by weight

	ppm	Relative abundance
Be	2.0	51
Mg	27 640	6
Ca	46 600	5
Sr	384	15
Ba	390	14
Ra	$1.3 \times 10^{-6}$	

the silicate minerals beryl  $\text{Be}_3\text{Al}_2\text{Si}_6\text{O}_{18}$  and phenacite  $\text{Be}_2\text{SiO}_4$ . About 6700 tonnes of beryl were mined in 1993, mainly in the USA (73%), Kazakhstan (13%) and the former Soviet Union (12%). (The gemstone emerald has the same formula as beryl, but also contains small amounts of chromium which make it green in colour.)

Magnesium is the sixth most abundant element in the earth's crust (27 640 ppm or 2.76%). Magnesium salts occur to about 0.13% in sea water. Entire mountain ranges (e.g. the Dolomites in Italy) consist of the mineral dolomite  $[\text{MgCO}_3 \cdot \text{CaCO}_3]$ . Calcined dolomite is used as a refractory for lining furnaces, and dolomite is used for road making. There are also large deposits of magnesite  $\text{MgCO}_3$ ; 10.8 million tonnes were mined in 1992. The main sources are China 24%, North Korea 15%, Turkey 11% and the Soviet Union 10%. There are also deposits of sulphates such as epsomite  $\text{MgSO}_4 \cdot 7\text{H}_2\text{O}$  and kieserite  $\text{MgSO}_4 \cdot \text{H}_2\text{O}$ . Carnallite  $[\text{KCl} \cdot \text{MgCl}_2 \cdot 6\text{H}_2\text{O}]$  is mined as a source of potassium. Mg also occurs in a wide range of silicate minerals, including olivine  $(\text{Mg}, \text{Fe})_2\text{SiO}_4$ , talc  $\text{Mg}_3(\text{OH})_2\text{Si}_4\text{O}_{10}$ , chrysotile  $\text{Mg}_3(\text{OH})_4\text{Si}_2\text{O}_5$  (asbestos) and micas such as  $\text{K}^+[\text{Mg}_3(\text{OH})_2(\text{AlSi}_3\text{O}_{10})]$ .

Calcium is the fifth most abundant element in the earth's crust (46 600 ppm or 4.66%) and it occurs throughout the world in many common minerals. There are vast sedimentary deposits of  $\text{CaCO}_3$  existing as whole mountain ranges of limestone, marble and chalk (the white cliffs of Dover) and also as coral. These originated from the shells of marine life. Though limestone is typically white, in many places it is coloured yellow, orange or brown owing to traces of iron. There are two crystalline forms of  $\text{CaCO}_3$ , calcite and aragonite. Calcite is the more common; it

forms colourless rhombohedral crystals. Aragonite is orthorhombic, and is commonly red-brown or yellow in colour, and this accounts for the colour of the landscape of the Red Sea area, the Bahamas and the Florida keys. Limestone is commercially important as a source of lime  $\text{CaO}$ . Lime is produced on an enormous scale (127.9 million tonnes in 1993), second in volume only to  $\text{H}_2\text{SO}_4$ . Limestone chippings are also used for making roads.

Fluoroapatite  $[\text{3}(\text{Ca}_3(\text{PO}_4)_2) \cdot \text{CaF}_2]$  is commercially important as a source of phosphate. Gypsum  $\text{CaSO}_4 \cdot 2\text{H}_2\text{O}$  and anhydrite  $\text{CaSO}_4$  are major minerals. World production of gypsum was 88.2 million tonnes in 1992. The major sources were the USA 17%, China 14%, Iran 9%, Canada and Thailand 8% each, and France and Spain 6% each. A much smaller amount of anhydrite was mined. Gypsum is used in making Portland cement, plasterboard and plaster, and in glass making. Its use in plaster is not just recent, since in the Valley of the Kings in Egypt the walls of the ancient burial tombs of Tutankhamun and those of the other kings were plastered with  $\text{CaSO}_4$  and then engraved with hieroglyphics. The White Sands National Park and missile range in New Mexico, USA (where the first atomic bomb was tested) have an area of 100 miles by 40 miles of pure white sand dunes composed of gypsum. Fluorite  $\text{CaF}_2$  is important as the main source of fluorine.

Strontium (384 ppm) and barium (390 ppm) are much less abundant, but are well known because they occur as concentrated ores which are easy to extract. Strontium is mined as celestite  $\text{SrSO}_4$  and strontianite  $\text{SrCO}_3$ . World production of Sr minerals was 283 100 tonnes in 1993. The main producers are Mexico 30%, Turkey 25%, Spain 19%, China 12% and Iran 11%. Ba is mined as barytes  $\text{BaSO}_4$ . World production was 4.9 million tonnes in 1992. It is found throughout the world and the largest producers are China 21%, the former Soviet Union 11%, Mexico 8%, India 7%, Turkey 6% and USA 6%. Radium is extremely scarce and is radioactive. It was first isolated by Pierre and Marie Curie by processing many tons of the uranium ore pitchblende. It was used for radiotherapy treatment of cancer at one time: other forms of radiation are now used ( $^{60}\text{Co}$ , X-rays or a linear accelerator). Marie Curie was awarded the Nobel Prize for chemistry in 1911 for isolating and studying radium and polonium.

## EXTRACTION OF THE METALS


The metals of this group are not easy to produce by chemical reduction because they are themselves strong reducing agents, and they react with carbon to form carbides. They are strongly electropositive and react with water, and so aqueous solutions cannot be used for displacing them with another metal, or for electrolytic production. Electrolysis of aqueous solutions can be carried out using a mercury cathode, but recovery of the metal from the amalgam is difficult. All the metals can be obtained by electrolysis of the fused chloride, with sodium chloride added to lower the melting point, although strontium and barium tend to form a colloidal suspension.

*continued overleaf*

In older processes BeO is extracted from beryl  $\text{Be}_3\text{Al}_2\text{Si}_6\text{O}_{18}$  by heat treatment or fusion with alkali, followed by treatment with sulphuric acid to give soluble  $\text{BeSO}_4$ . Addition of  $\text{NH}_4\text{OH}$  gives  $\text{Be}(\text{OH})_2$  which on heating gives BeO. BeO has ceramic properties, and is used in nuclear reactors. Alternatively beryllium is extracted from the silicate minerals by treatment with HF, forming the soluble complex sodium tetrafluoroberyllate  $\text{Na}_2[\text{BeF}_4]$ , and converting this to the hydroxide and then to the oxide. Be itself is prepared by converting the hydroxide to  $\text{BeCl}_2$  by heating with C and  $\text{Cl}_2$ , followed by electrolysis of the fused chloride. Alternatively beryllium is obtained by reducing  $\text{BeF}_2$  with magnesium. Be is used to make alloys with other metals. Addition of about 2% Be to Cu metal increases its strength by a factor of 5 or 6. An alloy of Be with Ni is used to make springs and electrical contacts. Be has a very low cross-section for neutron capture, and is used in the nuclear energy industry. Both Be and BeO have been used in nuclear reactors, and for this purpose they must be of extremely high purity. High purity material is obtained by making basic beryllium acetate, purifying this by distilling it under reduced pressure, and then either decomposing it to the oxide by heating, or converting it to the chloride and then reducing the chloride with Ca or Mg to give the metal. The absorption of electromagnetic radiation by a solid depends on its electron density. Be has a very low electron density and has a smaller absorbing power than any other solid, and for this reason it is used to make the windows of X-ray tubes.


Magnesium is the only Group 2 metal to be produced on a large scale. World production was 303 000 tonnes in 1993. The largest producers were the USA 48%, the Soviet Union 12%, Canada 9% and Norway 8%. Mg is an extremely important lightweight structural metal because of its low density ( $1.74 \text{ g cm}^{-3}$  compared with steel  $7.8 \text{ g cm}^{-3}$  or aluminium  $2.7 \text{ g cm}^{-3}$ ). Mg forms many binary alloys, often containing up to 9% Al, 3% Zn and 1% Mn, traces of the lanthanides praseodymium Pr and neodymium Nd, and traces of thorium. The metal and its alloys can be cast, machined and welded quite easily. It is used to make the bodies of aircraft, aircraft parts and motor car engines. Up to 5% Mg is usually added to Al to improve its properties. Chemically it is important in Grignard reagents such as  $\text{C}_2\text{H}_5\text{MgBr}$ .

Mg was formerly prepared by heating MgO and C to  $2000^\circ\text{C}$ , at which temperature C reduces MgO. The gaseous mixture of Mg and CO was then cooled very rapidly to deposit the metal. This 'quenching' or 'shock-cooling' was necessary as the reaction is reversible, and if cooled slowly the reaction will come to equilibrium further to the left.



Magnesium is now produced by high temperature reduction, and by electrolysis.



- 1 In the Pidgeon process Mg is produced by reducing calcined dolomite with ferrosilicon at  $1150^\circ\text{C}$  under reduced pressure.



2. Electrolysis may be carried out either on fused  $\text{MgCl}_2$ , or on partially hydrated  $\text{MgCl}_2$ . The  $\text{MgCl}_2$  is produced in two ways.


#### Dow sea water process

Sea water contains about 0.13%  $\text{Mg}^{2+}$  ions, and the extraction of magnesium depends on the fact that  $\text{Mg}(\text{OH})_2$  is very much less soluble than  $\text{Ca}(\text{OH})_2$ . Slaked lime  $\text{Ca}(\text{OH})_2$  is added to sea water, and the calcium ions dissolve and  $\text{Mg}(\text{OH})_2$  is precipitated. This is filtered off, treated with  $\text{HCl}$  to produce magnesium chloride, and electrolysed.



#### Dow natural brine process

Dolomite  $[\text{MgCO}_3 \cdot \text{CaCO}_3]$  is calcined (heated strongly) to give calcined dolomite  $\text{MgO} \cdot \text{CaO}$ . This is treated with  $\text{HCl}$ , giving a solution of  $\text{CaCl}_2$  and  $\text{MgCl}_2$ . This is treated with more calcined dolomite and  $\text{CO}_2$  is bubbled in.  $\text{CaCO}_3$  is precipitated, leaving a solution of  $\text{MgCl}_2$  which is then electrolysed.



Ca metal is used to make alloys with Al for bearings. It is used in the iron and steel industry to control carbon in cast iron and as a scavenger for P, O and S. Other uses are as a reducing agent in the production of other metals – Zr, Cr, Th and U – and for removing traces of  $\text{N}_2$  from argon. Chemically  $\text{CaH}_2$  is sometimes used as a source of  $\text{H}_2$ . World production of Ca is about 1000 tonnes/year. The metal is obtained by electrolysis of the fused  $\text{CaCl}_2$ , which is obtained either as a waste product from the Solvay process, or from  $\text{CaCO}_3$  and  $\text{HCl}$ .

The remaining metals Sr and Ba are produced on a very much smaller scale by electrolysis of their fused chlorides, or from their oxides by reduction with aluminium (a thermite reaction).

## SIZE OF ATOMS AND IONS

Group 2 atoms are large, but are smaller than the corresponding Group 1 elements as the extra charge on the nucleus draws the orbital electrons in. Similarly the ions are large, but are smaller than those of Group 1, especially because the removal of two orbital electrons increases the effective nuclear charge even further. Thus, these elements have higher densities than Group 1 metals.

Table 11.3 Size and density

	Metallic radius (Å)	Ionic radius $M^{2+}$ six coordinate (Å)	Density ( $g\ cm^{-3}$ )
Be	1.12	0.31*	1.85
Mg	1.60	0.72	1.74
Ca	1.97	1.00	1.55
Sr	2.15	1.18	2.63
Ba	2.22	1.35	3.62
Ra		1.48	5.5

\* Four coordinate radius six coordinate value = 0.45 Å

Group 2 metals are silvery white in colour. They have two valency electrons which may participate in metallic bonding compared with one electron for Group 1 metals. Consequently Group 2 metals are harder, have higher cohesive energy and have much higher melting points and boiling points than Group 1 elements (see Table 11.4) but the metals are relatively soft. The melting points do not vary regularly mainly because the metals adopt different crystal structures (see the section on Metallic bonds and metallic structures in Chapter 2).

Table 11.4 Melting and boiling points of Group 1 and 2 elements

	Melting point (°C)	Boiling point (°C)		Melting point (°C)	Boiling point (°C)
Be	1287	(2500)	Li	181	1347
Mg	649	1105	Na	98	881
Ca	839	1494	K	63	766
Sr	768	1381	Rb	39	(85)
Ba	727	(1850)	Cs	28.5	705
Ra	(700)	(1700)			

Figures in brackets are approximate

## IONIZATION ENERGY

The third ionization energy is so high that  $M^{3+}$  ions are never formed. The ionization energy for  $Be^{2+}$  is high and its compounds are typically covalent. Mg also forms some covalent compounds. However the compounds formed by Mg, Ca, Sr and Ba are predominantly divalent and ionic. Since the atoms are smaller than those in Group 1, the electrons are more tightly held so that the energy needed to remove the first electron (first ionization energy) is greater than for Group 1. Once one electron has been removed, the ratio of charges on the nucleus to orbital electrons is increased so that the remaining electrons are more tightly held. Hence the energy needed to remove a second electron is nearly double that required

for the first. The total energy required to produce gaseous divalent ions for Group 2 elements (first ionization energy + second ionization energy) is over four times greater than the energy required to produce  $M^+$  from Group 1 metals. The fact that ionic compounds are formed shows that the energy given out when a crystal lattice is formed more than offsets that used in producing ions.

Table 11.5 Ionization energies and electronegativity

	Ionization energy (kJ mol <sup>-1</sup> )			Pauling's electronegativity
	1st	2nd	3rd	
Be	899	1757	14 847	1.5
Mg	737	1450	7 731	1.2
Ca	590	1145	4 910	1.0
Sr	549	1064		1.0
Ba	503	965		0.9
Ra	509	979	(3 281)	

Estimated value in brackets.

## ELECTRONEGATIVITY

The electronegativity values of Group 2 elements are low, but are higher than the values for Group 1. When Mg, Ca, Sr and Ba react with elements such as the halogens and dioxygen at the right hand side of the periodic table, the electronegativity difference is large and the compounds are ionic.

The value for Be is higher than for the others.  $\text{BeF}_2$  has the biggest electronegativity difference for a compound of Be and so is the most likely compound of Be to be ionic.  $\text{BeF}_2$  has a very low conductivity when fused, and is regarded as covalent.

## HYDRATION ENERGIES

The hydration energies of the Group 2 ions are four or five times greater than for Group 1 ions. This is largely due to their smaller size and increased charge, and  $\Delta H_{\text{hydration}}$  decreases down the group as the size of the ions increases. In the case of Be a further factor is the very strong complex  $[\text{Be}(\text{H}_2\text{O})_4]^{2+}$  that is formed. The crystalline compounds of Group 2 contain more water of crystallization than the corresponding Group 1 compounds. Thus NaCl and KCl are anhydrous but  $\text{MgCl}_2 \cdot 6\text{H}_2\text{O}$ ,  $\text{CaCl}_2 \cdot 6\text{H}_2\text{O}$  and  $\text{BaCl}_2 \cdot 2\text{H}_2\text{O}$  all have water of crystallization. Note that the number of molecules of water of crystallization decreases as the ions become larger.

Since the divalent ions have a noble gas structure with no unpaired electrons, their compounds are diamagnetic and colourless, unless the acid radical is coloured.

Table 11.6 Hydration energies

	Ionic radius (Å)	$\Delta H$ hydration (kJ mol <sup>-1</sup> )
Be <sup>2+</sup>	0.31*	-2494
Mg <sup>2+</sup>	0.72	-1921
Ca <sup>2+</sup>	1.00	-1577
Sr <sup>2+</sup>	1.18	-1443
Ba <sup>2+</sup>	1.35	-1305

\* Four coordinate radius


## ANOMALOUS BEHAVIOUR OF BERYLLIUM

Be differs from the rest of the group for three reasons


- 1 It is extremely small and Fajans' rules state that small highly charged ions tend to form covalent compounds
- 2 Be has a comparatively high electronegativity. Thus when beryllium reacts with another atom, the difference in electronegativity is seldom large, which again favours the formation of covalent compounds. Even BeF<sub>2</sub> (electronegativity difference 2.5) and BeO (electronegativity difference 2.0) show evidence of covalent character.
- 3 Be is in the second row of the periodic table and the outer shell can hold a maximum of eight electrons. (The orbitals available for bonding are one 2s and three 2p orbitals.) Thus Be can form a maximum of four conventional electron pair bonds and in many compounds the maximum coordination number of Be is 4. The later elements can have more than eight outer electrons and may attain a coordination number of 6 using one s, three p and two d orbitals for bonding. Exceptions occur if multi-centre bonding occurs, as for example in basic beryllium acetate, when higher coordination numbers are obtained.


Thus we should expect Be to form mainly covalent compounds and commonly have a coordination number of 4. Anhydrous compounds of Be are predominantly two covalent and BeX<sub>2</sub> molecules should be linear.

Electronic structure of beryllium atom in the ground state



Electronic structure of beryllium atom in excited state




  
 two unpaired electrons can form bonds  
 with two X atoms – linear molecule  
 (sp hybridization)

In fact linear molecules exist only in the gas phase, as this electronic arrangement has not filled the outer shell of electrons. In the solid state four fold coordination is always achieved. There are several ways by which this can be achieved.




1. Two ligands that have a lone pair of electrons may form coordinate bonds using the two unfilled orbitals in the valence shell of Be. Thus two  $F^-$  ions might coordinate to  $BeF_2$ , forming  $[BeF_4]^{2-}$ . Similarly diethyl ether can coordinate to  $Be(+II)$  in  $BeCl_2$ , forming  $[BeCl_2(OEt_2)_2]$ .
2. The  $BeX_2$  molecules may polymerize to form chains, containing bridging halogen groups, for example  $(BeF_2)_n$ ,  $(BeCl_2)_n$ . Each halogen forms one normal covalent bond, and uses a lone pair to form a coordinate bond (Figure 11.3c).
3.  $(BeMe_2)_n$  has essentially the same structure as  $(BeCl_2)_n$ , but the bonding in the methyl compound is best regarded as three-centre two-electron bonds covering one Me and two Be atoms.
4. A covalent lattice may be formed with a zinc blende or wurtzite structure (coordination number 4), for example by  $BeO$  and  $BeS$ .


In water beryllium salts are extensively hydrolysed to give a series of hydroxo complexes of unknown structure. They may be polymeric and of the type:



If alkali is added to these solutions the polymers break down to give the simple mononuclear beryllate ion  $[Be(OH)_4]^{2-}$ , which is tetrahedral. Many beryllium salts contain the hydrated ion  $[Be(H_2O)_4]^{2+}$  rather than  $Be^{2+}$ , and the hydrated ion too is a tetrahedral complex ion. Note that the coordination number is 4. Forming a hydrated complex increases the effective size of the beryllium ion, thus spreading the charge over a larger area. Stable ionic salts such as  $[Be(H_2O)_4]SO_4$ ,  $[Be(H_2O)_4](NO_3)_2$  and  $[Be(H_2O)_4]Cl_2$  are known.



Beryllium salts are acidic when dissolved in pure water because the hydrated ion hydrolyses producing  $\text{H}_3\text{O}^+$ . This happens because the  $\text{Be}-\text{O}$  bond is very strong, and so in the hydrated ion this weakens the  $\text{O}-\text{H}$  bonds, and hence there is a tendency to lose protons. The initial reaction is



but this may be followed by further polymerization involving hydroxo-bridged structures  $[\text{Be}_2\text{OH}]^{1+}$ ,  $[\text{Be}_3(\text{OH})_4]^{3+}$ . In alkaline solutions  $[\text{Be}(\text{OH})_4]^{2-}$  is formed. The other Group 2 salts do not interact so strongly with water, and do not hydrolyse appreciably.

Beryllium salts rarely have more than four molecules of water of crystallization associated with the metal ion because there are only four orbitals available in the second shell of electrons whereas magnesium can have a coordination number of 6 by using some 3d orbitals as well as 3s and 3p orbitals.

### SOLUBILITY AND LATTICE ENERGY

The solubility of most salts decreases with increased atomic weight though the usual trend is reversed with the fluorides and hydroxides in this group. Solubility depends on the lattice energy of the solid and the hydration energy of the ions as explained below.

Some lattice energy values for Group 2 compounds are listed in Table 11.7. The lattice energies are much higher than the values for Group 1 compounds because of the effect of the increased charge on the ions in the Born-Landé equation (See Chapter 3). Taking any one particular negative ion the lattice energy decreases as the size of the metal increases.

Table 11.7 Lattice energies of some compounds ( $\text{kJ mol}^{-1}$ )

	MO	$\text{MCO}_3$	$\text{MF}_2$	$\text{MCl}_2$
Mg	-3923	-3178	-2906	-2292
Ca	-3517	-2986	-2610	-2058
Sr	-3312	-2718	-2459	
Ba	-3120	-2614	-2367	

The hydration energy also decreases as the metal ions become larger (Table 11.8). For a substance to dissolve the hydration energy must ex-


Table 11.8 Enthalpies of hydration

	$\Delta H$ ( $\text{kJ mol}^{-1}$ )
$\text{Be}^{2+}$	-2494
$\text{Mg}^{2+}$	-1921
$\text{Ca}^{2+}$	-1577
$\text{Sr}^{2+}$	-1443
$\text{Ba}^{2+}$	-1305

ceed the lattice energy. Consider a related group of compounds, such as the chlorides of all the Group 2 metals. On descending the group the metal ions become larger and so both the lattice energy and the hydration energy decrease. A decrease in lattice energy favours increased solubility, but a decrease in hydration energy favours decreased solubility. These two factors thus change in opposite directions, and the overall effect depends on which of the two has changed most. With most compounds, on descending the group, the hydration energy decreases more rapidly than the lattice energy: hence the compounds become less soluble as the metal gets larger. However, with fluorides and hydroxides the lattice energy decreases more rapidly than the hydration energy, and so their solubility increases on descending the group.

### SOLUTIONS OF THE METALS IN LIQUID AMMONIA

The metals all dissolve in liquid ammonia as do the Group 1 metals. Dilute solutions are bright blue in colour due to the spectrum from the solvated electron. These solutions decompose very slowly, forming amides and evolving hydrogen, but the reaction is accelerated by many transition metals and their compounds.



Evaporation of the ammonia from solutions of Group 1 metals yields the metal, but with Group 2 metals evaporation of ammonia gives hexamoniates of the metals. These slowly decompose to give amides.



Concentrated solutions of the metals in ammonia are bronze coloured, due to the formation of metal clusters.

### CHEMICAL PROPERTIES

#### Reaction with water

The reduction potential of beryllium is much less than those for the rest of the group. (Standard electrode potentials  $E^\circ$  of  $\text{Be}^{2+}|\text{Be}$   $-1.85$ ,  $\text{Mg}^{2+}|\text{Mg}$   $-2.37$ ,  $\text{Ca}^{2+}|\text{Ca}$   $-2.87$ ,  $\text{Sr}^{2+}|\text{Sr}$   $-2.89$ ,  $\text{Ba}^{2+}|\text{Ba}$   $-2.91$ ,  $\text{Ra}^{2+}|\text{Ra}$   $-2.92$  volts.) This indicates that beryllium is much less electropositive (less metallic) than the others, and beryllium does not react with water. There is some doubt whether it reacts with steam to form the oxide  $\text{BeO}$ , or fails to react at all.

Ca, Sr and Ba have reduction potentials similar to those of the corresponding Group 1 metals, and are quite high in the electrochemical series. They react with cold water quite readily, liberating hydrogen and forming metal hydroxides.






Table 11 9 Some reactions of Group 2 elements

Reaction	Comment
$M + 2H_2O \rightarrow M(OH)_2 + H_2$	Be probably reacts with steam Mg with hot water and Ca Sr and Ba react rapidly with cold water
$M + 2HCl \rightarrow MCl_2 + H_2$	All the metals react with acids liberating hydrogen
$Be + NaOH \rightarrow Na_2[Be(OH)_4] + H_2$	Be is amphoteric
$2M + O_2 \rightarrow 2MO$ with excess dioxygen $Ba + O_2 \rightarrow BaO_2$	Normal oxide formed by all group members Ba also forms the peroxide
$M + H_2 \rightarrow MH_2$	Ionic salt like hydrides formed at high temperatures by Ca Sr and Ba
$3M + N_2 \rightarrow M_3N_2$	All form nitrides at high temperatures
$3M + 2P \rightarrow M_3P_2$	All the metals form phosphides at high temperatures
$M + S \rightarrow MS$ $M + Se \rightarrow MSe$ $M + Te \rightarrow MTe$	All the metals form sulphides All the metals form selenides All the metals form tellurides
$M + F_2 \rightarrow MF_2$ $M + Cl_2 \rightarrow MCl_2$ $M + Br_2 \rightarrow MBr_2$ $M + I_2 \rightarrow MI_2$	All the metals form fluorides All the metals form chlorides All the metals form bromides All the metals form iodides
$3M + 2NH_3 \rightarrow 2M(NH_2)_2$	All the metals form amides at high temperatures

Magnesium has an intermediate value, and it does not react with cold water but it decomposes hot water



or




Mg forms a protective layer of oxide, so despite its favourable reduction potential it does not react readily unless the oxide layer is removed by amalgamating with mercury. In the formation of the oxide film it resembles aluminium.

## HYDROXIDES

$Be(OH)_2$  is amphoteric but the hydroxides of Mg, Ca, Sr and Ba are basic. The basic strength increases from Mg to Ba, and Group 2 shows

the usual trend that basic properties increase on descending a group.

Solutions of  $\text{Ca}(\text{OH})_2$  and  $\text{Ba}(\text{OH})_2$  are called lime water and baryta water respectively, and are used to detect carbon dioxide. When  $\text{CO}_2$  is bubbled through these solutions, they become 'turbid' or 'milky' due to the formation of a suspension of solid particles of  $\text{CaCO}_3$  or  $\text{BaCO}_3$ . If excess  $\text{CO}_2$  is passed through these 'milky' solutions then the turbidity disappears as soluble bicarbonates form with the excess  $\text{CO}_2$ . Baryta water is rather too sensitive as it gives a positive test for  $\text{CO}_2$  by exhaling breath on it, whereas with lime water, breath (or other gas) must be blown through the solution as bubbles.




The bicarbonates of Group 2 metals are only stable in solution. Caves in limestone regions often have stalactites growing down from the roof, and stalagmites growing up from the floor. Water percolating through the limestone contains some  $\text{Ca}^{2+}(\text{HCO}_3^-)_2$  in solution. The soluble bicarbonate decomposes slowly into the insoluble carbonate, and this results in the slow growth of the stalactites and stalagmites.




## HARDNESS OF WATER

Hard water contains dissolved salts such as magnesium and calcium carbonates, bicarbonates or sulphates. It is difficult to produce lather from soap with hard water, and an insoluble scum is formed. The metal ions  $\text{Ca}^{2+}$  and  $\text{Mg}^{2+}$  react with the stearate ions from the soap, forming an insoluble scum of calcium stearate before any lather is produced. Hard water also produces scale (insoluble deposits) in water pipes, boilers, and kettles.

'Temporary hardness' is due to the presence of  $\text{Mg}(\text{HCO}_3)_2$  and  $\text{Ca}(\text{HCO}_3)_2$ . It is called 'temporary' because it can be removed by boiling, which drives off  $\text{CO}_2$  and upsets the equilibrium.




Thus the bicarbonates decompose into carbonates, and calcium carbonate is precipitated. If this is filtered off, or allowed to settle, the water is free from hardness. Temporary hardness can also be removed by adding slaked lime to precipitate calcium carbonate. This is called 'lime softening', and by operating at pH 10.5, temporary hardness due to  $\text{HCO}_3^-$  can be almost completely removed.





'Permanent hardness' is not removed by boiling, and is due mainly to  $\text{MgSO}_4$  or  $\text{CaSO}_4$  in solution. Small quantities of pure water are prepared

in the laboratory either by distilling the water, or by passing it through an ion-exchange resin, when the  $\text{Ca}^{2+}$  and  $\text{Mg}^{2+}$  ions are replaced by  $\text{Na}^+$ . The sodium salts do not affect the lathering power. Ion-exchange methods are widely used in industry. Water may also be softened by adding various phosphates, such as trisodium phosphate  $\text{Na}_3\text{PO}_4$ , sodium pyrophosphate  $\text{Na}_4\text{P}_2\text{O}_7$ , sodium tripolyphosphate  $\text{Na}_5\text{P}_3\text{O}_{10}$ , or Grahams salt (Calgon)  $(\text{NaPO}_3)_n$ . These form a complex with the calcium and magnesium ions and 'sequester' them, that is keep them in solution. At one time large quantities of sodium carbonate were used in the lime-soda process to soften water. The effect of adding  $\text{Na}_2\text{CO}_3$  is to precipitate  $\text{CaCO}_3$ .



### REACTION WITH ACIDS AND BASES

The metals all react with acids and liberate  $\text{H}_2$ , although Be reacts slowly. Be is rendered passive by concentrated  $\text{HNO}_3$ , i.e. it does not react. This is because concentrated  $\text{HNO}_3$  is a strong oxidizing agent and it forms a very thin layer of oxide on the surface of the metal, which protects it from further attack by the acid. Be is amphoteric, as it also reacts with  $\text{NaOH}$ , giving  $\text{H}_2$  and sodium beryllate. Mg, Ca, Sr and Ba do not react with  $\text{NaOH}$ , and are purely basic. This illustrates that basic properties increase on descending the group.




### OXIDES AND PEROXIDES

All the elements in this group burn in  $\text{O}_2$  to form oxides  $\text{MO}$ . Be metal is relatively unreactive in the massive form, and does not react below  $600^\circ\text{C}$ , but the powder is much more reactive and burns brilliantly. The elements also burn in air, forming a mixture of oxide and nitride. Mg burns with dazzling brilliance in air, and evolves a lot of heat. This is used to start a thermite reaction with aluminium, and also to provide light in flash photography using light bulbs, not electronics.



$\text{BeO}$  is usually made by ignition of the metal, but the other metal oxides are usually obtained by thermal decomposition of the carbonates  $\text{MCO}_3$ . Other oxysalts such as  $\text{M}(\text{NO}_3)_2$  and  $\text{MSO}_4$ , and also  $\text{M}(\text{OH})_2$ , all decompose to the oxide on heating. The oxosalts are less stable to heat than the corresponding Group 1 salts because the metals and their hydroxides are less basic than those of Group 1.

$\text{CaO}$  (quicklime) is made in enormous quantities (127.9 million tonnes in 1993) by roasting  $\text{CaCO}_3$  in a lime kiln.




MgO is not very reactive, especially if it has been ignited at high temperatures, and for this reason it is used as a refractory. BeO is also used as a refractory. They combine a number of properties that make them useful for lining furnaces. These factors are:

1. High melting points (BeO approx. 2500°C, MgO approx. 2800°C).
2. Very low vapour pressures.
3. Very good conductors of heat.
4. Chemical inertness.
5. Electrical insulators.

All Be compounds should be used with care as they are toxic and dust or smoke cause berylliosis.

CaO, SrO and BaO react exothermically with water, forming hydroxides.



Mg(OH)<sub>2</sub> is extremely insoluble in water (approx.  $1 \times 10^{-4} \text{ g l}^{-1}$  at 20°C) but the other hydroxides are soluble and the solubility increases down the group (Ca(OH)<sub>2</sub> approx.  $2 \text{ g l}^{-1}$ ; Sr(OH)<sub>2</sub> approx.  $8 \text{ g l}^{-1}$ ; Ba(OH)<sub>2</sub> approx.  $39 \text{ g l}^{-1}$ ). Be(OH)<sub>2</sub> is soluble in solutions containing an excess of OH<sup>-</sup>, and is therefore amphoteric. Mg(OH)<sub>2</sub> is weakly basic, and is used to treat acid indigestion. The other hydroxides are strong bases. Ca(OH)<sub>2</sub> is called slaked lime.


BeO is covalent and has a 4:4 zinc sulphide (wurtzite) structure, but all the others are ionic and have a 6:6 sodium chloride structure.

Attempts to predict the structure using the sizes of the ions and the radius ratio are only partly successful (Table 11.10). The correct structure is predicted for BeO, MgO and CaO, but for SrO and BaO the predicted coordination number is 8, though the structures found are six-coordinate. Crystals adopt the structure that has the most favourable lattice energy, and the failure of the radius ratio concept in this case leads us to examine the assumptions on which it is based. (See Chapter 3 under 'A more critical look at radius ratios'.) Ionic radii are not known with great accuracy and they change with different coordination numbers. Also, ions are not necessarily spherical, or inelastic.

Table 11.10 Radius ratios and coordination numbers

Oxide	Radius ratio $\text{M}^{2+}/\text{O}^{2-}$	Predicted coordination number	Coordination number found
BeO	0.32	4	4
MgO	0.51	6	6
CaO	0.71	6	6
SrO	0.84	8	6
BaO	0.96	8	6

As the atoms get larger, the ionization energy decreases and the elements also become more basic. BeO is insoluble in water but dissolves in acids to give salts and in alkalis to give beryllates which on standing precipitate as the hydroxide. BeO is therefore amphoteric. MgO reacts with water, forming  $\text{Mg(OH)}_2$ , which is weakly basic. CaO reacts very readily with water, evolving a lot of heat and forming  $\text{Ca(OH)}_2$ , which is a moderately strong base.  $\text{Sr(OH)}_2$  and  $\text{Ba(OH)}_2$  are even stronger bases. The oxides are usually prepared by thermal decomposition of the carbonates, nitrates or hydroxides. The increase in basic strength is illustrated by the temperatures at which the carbonates decompose:



The carbonates are all ionic but  $\text{BeCO}_3$  is unusual because it contains the hydrated ion  $[\text{Be(H}_2\text{O)}_4]^{2+}$  rather than  $\text{Be}^{2+}$ .

$\text{CaCO}_3$  occurs as two different crystalline forms: calcite and aragonite. Both forms occur naturally as minerals. Calcite is the more stable; each  $\text{Ca}^{2+}$  is surrounded by six oxygen atoms from  $\text{CO}_3^{2-}$  ions. Aragonite is a metastable form, and its standard enthalpy of formation is about  $5 \text{ kJ mol}^{-1}$  higher than that of calcite. In principle aragonite should decompose to calcite but a high energy of activation prevents this happening. Aragonite can be made in the laboratory by precipitating from a hot solution. Its crystal structure has  $\text{Ca}^{2+}$  surrounded by nine oxygen atoms. This is a rather unusual coordination number.

Calcium oxide (lime) is prepared on a large scale (127.9 million tonnes in 1993) by heating  $\text{CaCO}_3$  in lime kilns:



Lime is used:

- 1 In steel making to remove phosphates and silicates as slag
- 2 By mixing with  $\text{SiO}_2$  and alumina or clay to make cement
- 3 For making glass
- 4 In the lime-soda process, which is part of the chlor-alkali industry converting  $\text{Na}_2\text{CO}_3$  to NaOH or vice versa
- 5 For 'softening' water
- 6 To make  $\text{CaC}_2$
- 7 To make slaked lime  $\text{Ca(OH)}_2$  by treatment with water

Bleaching powder is made by passing  $\text{Cl}_2$  into slaked lime, and about 150 000 tonnes a year are produced. Though bleaching powder is often written as  $\text{Ca(OCl)}_2$  it is really a mixture:




Soda lime is a mixture of NaOH and  $\text{Ca(OH)}_2$  and is made from quicklime ( $\text{CaO}$ ) and aqueous sodium hydroxide. It is much easier to handle than NaOH.

Peroxides are formed with increasing ease and increasing stability as the




metal ions become larger. Barium peroxide  $\text{BaO}_2$  is formed by passing air over  $\text{BaO}$  at  $500^\circ\text{C}$ .  $\text{SrO}_2$  can be formed in a similar way but this requires a high pressure and temperature.  $\text{CaO}_2$  is not formed in this way, but can be made as the hydrate by treating  $\text{Ca(OH)}_2$  with  $\text{H}_2\text{O}_2$  and then dehydrating the product. Crude  $\text{MgO}_2$  has been made using  $\text{H}_2\text{O}_2$ , but no peroxide of beryllium is known. The peroxides are white ionic solids containing the  $[\text{O—O}]^{2-}$  ion and can be regarded as salts of the very weak acid hydrogen peroxide. Treating peroxides with acid liberates hydrogen peroxide.




## SULPHATES


The solubility of the sulphates in water decreases down the group,  $\text{Be} > \text{Mg} \gg \text{Ca} > \text{Sr} > \text{Ba}$ . Thus  $\text{BeSO}_4$  and  $\text{MgSO}_4$  are soluble, but  $\text{CaSO}_4$  is sparingly soluble, and the sulphates of  $\text{Sr}$ ,  $\text{Ba}$  and  $\text{Ra}$  are virtually insoluble. The significantly higher solubilities of  $\text{BeSO}_4$  and  $\text{MgSO}_4$  are due to the high enthalpy of solvation of the smaller  $\text{Be}^{2+}$  and  $\text{Mg}^{2+}$  ions. Epsom salt  $\text{MgSO}_4 \cdot 7\text{H}_2\text{O}$  is used as a mild laxative. Calcium sulphate can exist as a hemihydrate  $\text{CaSO}_4 \cdot \frac{1}{2}\text{H}_2\text{O}$  which is important in the building trade as plaster of Paris. This is made by partially dehydrating gypsum.




When powdered plaster of Paris  $\text{CaSO}_4 \cdot \frac{1}{2}\text{H}_2\text{O}$  is mixed with the correct amount of water it sets into a solid mass of  $\text{CaSO}_4 \cdot 2\text{H}_2\text{O}$  (gypsum). Plaster of Paris is used for plastering walls, and also to make plaster casts (moulds) for a variety of purposes, industrial, sculptural, and in hospitals to encase limbs so that broken bones are set straight. Alabaster is a fine grained form of  $\text{CaSO}_4 \cdot 2\text{H}_2\text{O}$  which is shiny like marble, and is used to make ornaments.  $\text{CaSO}_4$  is slightly soluble in water (2 g per litre), so objects made from alabaster or gypsum cannot be kept outdoors.  $\text{BaSO}_4$  is both insoluble in water and opaque to X-rays, and is used as a 'barium meal' to provide a shadow of the stomach or duodenum on an X-ray picture, which is useful in diagnosing stomach or duodenal ulcers. The sulphates all decompose on heating, giving the oxides:



In the same way as with the stability and thermal decomposition of the carbonates, the more basic the metal is, the more stable the sulphate is. This is shown by the temperatures at which decomposition occurs:




Heating the sulphates with C reduces them to sulphides. Most barium compounds are made from barium sulphide.



Group II elements also form perchlorates  $\text{MClO}_4$  which have very similar structures to the sulphates, and the  $\text{ClO}_4^-$  ion is tetrahedral and similar in size to the  $\text{SO}_4^{2-}$  ion. However, they differ chemically, since perchlorates are strong oxidizing agents. Magnesium perchlorate is used as a drying agent called anhydron. Anhydron should not be used with organic materials because it is a strong oxidizing agent, and accidental contact with organic material could cause an explosion.

### NITRATES


Nitrates of the metals can all be prepared in solution and can be crystallized as hydrated salts by the reaction of  $\text{HNO}_3$  with carbonates, oxides or hydroxides. Heating the hydrated solids does not give the anhydrous nitrate because the solid decomposes to the oxide. Anhydrous nitrates can be prepared using liquid dinitrogen tetroxide and ethyl acetate. Beryllium is unusual in that it forms a basic nitrate in addition to the normal salt.



Basic beryllium nitrate is covalent and has an unusual structure (Figure 11.1b). Four Be atoms are located at the corners of a tetrahedron, with six  $\text{NO}_3^-$  groups along the six edges of the tetrahedron, and the (basic) oxygen at the centre. The structure is of interest partly because beryllium is unique in forming a series of stable covalent molecules of formula  $[\text{Be}_4\text{O}(\text{R})_6]$  where R may be  $\text{NO}_3^-$ ,  $\text{HCOO}^-$ ,  $\text{CH}_3\text{COO}^-$ ,  $\text{C}_2\text{H}_5\text{COO}^-$ ,  $\text{C}_6\text{H}_5\text{COO}^-$  etc. Thus basic beryllium nitrate is one of a series of similar molecules (cf. basic beryllium acetate (Figure 11.5b)). The structure is also of interest because the  $\text{NO}_3^-$  groups act as bidentate ligands in forming a bridge between two Be atoms. (See 'Chelates' in Chapter 7 for a discussion of multidentate groups.)

### HYDRIDES

The elements Mg, Ca, Sr and Ba all react with hydrogen to form hydrides  $\text{MH}_2$ . Beryllium hydride is difficult to prepare, and less stable than the others. Impure  $\text{BeH}_2$  (contaminated with various amounts of ether) was first made by reducing  $\text{BeCl}_2$  with lithium aluminium hydride  $\text{Li}[\text{AlH}_4]$ . Pure samples can be obtained by reducing  $\text{BeCl}_2$  with lithium borohydride  $\text{Li}[\text{BH}_4]$  to give  $\text{BeB}_2\text{H}_4$ , then heating  $\text{BeB}_2\text{H}_4$  in a sealed tube with triphenylphosphine  $\text{PPh}_3$ .






Figure 11.1 (a) A bridging  $\text{NO}_3^-$  group. (b) Basic beryllium nitrate.







Figure 11.2 Polymeric  $\text{BeH}_2$  structure with three-centre bonds.



The hydrides are all reducing agents and are hydrolysed by water and dilute acids with the evolution of hydrogen.




$\text{CaH}_2$ ,  $\text{SrH}_2$  and  $\text{BaH}_2$  are ionic, and contain the hydride ion  $\text{H}^-$ . Beryllium and magnesium hydrides are covalent and polymeric.  $(\text{BeH}_2)_n$  presents an interesting structural problem. In the gas phase it seems probable that several species may be present comprising polymeric chains and rings. The solid exists in both amorphous and crystalline forms. Both are thought to be polymeric and to contain hydrogen bridges between beryllium atoms.

Be is bonded to four H atoms, and the H atoms appear to be forming two bonds. Since Be has two valency electrons, and H only one, it is apparent that there are not enough electrons to form the usual electron pair bonds in which two electrons are shared between two atoms. Instead of this, three-centre bonds are formed in which a 'banana-shaped' molecular orbital (or three-centre bond) covers three atoms  $\text{Be} \dots \text{H} \dots \text{Be}$ , and contains two electrons. (This is called a three-centre two-electron bond.) This is an example of a cluster compound, where the monomeric molecule  $\text{BeH}_2$  (formed with normal bonds) would result in only four electrons in




the outer shell of the beryllium atom. This situation is termed 'electron deficient', and, by clustering, each atom shares its electrons with several neighbours and receives a share in their electrons. Clustering is important in metals (Chapter 5) and the boron hydrides (Chapter 12), and in the halides of the second and third row transition metals (Chapter 18).

## HALIDES

Halides  $\text{MX}_2$  can be made by heating the metals with the halogen or by the action of halogen acid on either the metal or the carbonate. The beryllium halides are covalent, hygroscopic and fume in air due to hydrolysis. They sublime, and they do not conduct electricity. Anhydrous beryllium halides cannot be obtained from materials made in aqueous solutions because the hydrated ion  $[\text{Be}(\text{H}_2\text{O})_4]^{2+}$  is formed, e.g.  $[\text{Be}(\text{H}_2\text{O})_4]\text{Cl}_2$  or  $[\text{Be}(\text{H}_2\text{O})_4]\text{F}_2$ . Attempts to dehydrate result in hydrolysis.



The anhydrous halides are best prepared by the following reactions. Reaction with  $\text{CCl}_4$  is a standard method for making anhydrous chlorides which cannot be obtained by dehydrating hydrates. (See Chapter 16.)



The anhydrous halides are polymeric. Beryllium chloride vapour contains  $\text{BeCl}_2$  and  $(\text{BeCl}_2)_2$ , but the solid is polymerized. Though the structure of the  $(\text{BeCl}_2)_n$  polymer is similar to that for  $(\text{BeH}_2)_n$ , the bonding is different. Both show clustering, but the hydride has three centre bonding whereas the halides have halogen bridges in which a halogen atom bonded to one beryllium atom uses a lone pair of electrons to form a coordinate bond to another beryllium atom.





Figure 11.3  $\text{BeCl}_2$  structures (a) monomer (b) dimer and (c) polymer

Beryllium fluoride is very soluble in water, owing to the high solvation energy of Be in forming  $[\text{Be}(\text{H}_2\text{O})_4]^{2+}$ . The other fluorides  $\text{MF}_2$  are all almost insoluble.

Fluorides of the other metals are ionic, have high melting points, and are insoluble in water.  $\text{CaF}_2$  is a white, insoluble, high melting solid. It is very important industrially, and is the main source of both  $\text{F}_2$  and  $\text{HF}$ .




World production of fluorite  $\text{CaF}_2$  was 3.6 million tonnes in 1992. The main sources are China 42%, the Soviet Union, Mexico and Mongolia 8% each, and South Africa 7%.  $\text{CaF}_2$  is also used to make prisms and cell windows for spectrophotometers.

The chlorides, bromides and iodides of Mg, Ca, Sr and Ba are ionic, have much lower melting points than the fluorides, and are readily soluble in water. The solubility decreases somewhat with increasing atomic number. The halides all form hydrates, and they are hygroscopic (absorb water vapour from the air). Several million tonnes of  $\text{CaCl}_2$  are produced each year. Large amounts are discarded in solution as a waste product from the Solvay process because it is not economic to recover the solid and demand is low.  $\text{CaCl}_2$  is widely used for treating ice on roads, particularly in very cold countries, because a 30% eutectic mixture of  $\text{CaCl}_2/\text{H}_2\text{O}$  freezes at  $-55^\circ\text{C}$ , compared with  $\text{NaCl}/\text{H}_2\text{O}$  at  $-18^\circ\text{C}$ .  $\text{CaCl}_2$  is also used to make concrete set more quickly and to improve its strength, and as 'brine' in refrigeration plants. A minor use is in laboratories as a desiccant (drying agent). Anhydrous  $\text{MgCl}_2$  is important in the electrolytic method for extracting magnesium.


## NITRIDES

The alkaline earth elements all burn in dinitrogen and form ionic nitrides  $\text{M}_3\text{N}_2$ . This is in contrast to Group I where  $\text{Li}_3\text{N}$  is the only nitride formed.




Because the  $\text{N}_2$  molecule is very stable, it requires a lot of energy to convert  $\text{N}_2$  into  $\text{N}^{3-}$  nitride ions. The large amount of energy required comes from the very large amount of lattice energy evolved when the crystalline solid is formed. The lattice energy is particularly high because of the high charges on the ions  $\text{M}^{2+}$  and  $\text{N}^{3-}$ . Li is alone in Group I in forming a nitride, and here the very small size of  $\text{Li}^+$  results in a high lattice energy. (See Born-Landé equation, Chapter 3.)

$\text{Be}_3\text{N}_2$  is rather volatile in accord with the greater tendency of Be to covalency, but the other nitrides are not volatile. All the nitrides are all crystalline solids which decompose on heating and react with water, liberating ammonia and forming either the metal oxide or hydroxide, e.g.





## CARBIDES (see also Chapter 13)

When BeO is heated with C at 1900–2000 °C a brick red coloured carbide of formula Be<sub>2</sub>C is formed. This is ionic and has an anti fluorite structure i.e. like the CaF<sub>2</sub> structure except that the positions of the metal ions and anions are interchanged. It is unusual because it reacts with water forming methane and is thus called a methanide.




Group 2 metals typically form ionic carbides of formula MC<sub>2</sub>. The metals Mg, Ca, Sr and Ba form carbides of formula MC<sub>2</sub>, either when the metal is heated with carbon in an electric furnace or when their oxides are heated with carbon. CaC<sub>2</sub> made in this way is a grey coloured solid but is colourless when pure. BeC<sub>2</sub> is made by heating Be with ethyne.

On heating MgC<sub>2</sub> changes into Mg<sub>2</sub>C<sub>3</sub>. This contains C<sub>3</sub><sup>4-</sup> and it reacts with water to form propyne CH<sub>3</sub>C≡CH (methyl acetylene).




The MC<sub>2</sub> carbides all have a distorted sodium chloride type of structure. M<sup>2+</sup> replaces Na<sup>+</sup> and C≡C<sup>2-</sup> replaces Cl<sup>-</sup>. The C<sub>2</sub><sup>2-</sup> ions are elongated not spherical like Cl<sup>-</sup>. Thus the axis along which the C<sub>2</sub><sup>2-</sup> ions lie is lengthened compared with the other two axes and this is called tetragonal distortion. The structure is shown in Chapter 3 Figure 3.12. At temperatures above 450 °C the C<sub>2</sub><sup>2-</sup> ions adopt random positions rather than being aligned in this way and the unit cell then becomes cubic rather than tetragonal.

Calcium carbide is the best known. It reacts with water liberating ethyne (formerly called acetylene) and is thus called an acetylides.




At one time this reaction was the main source of ethyne for oxy acetylene welding. Production of CaC<sub>2</sub> peaked at 7 million tonnes/year in 1960 but had declined to 4.9 million tonnes in 1991 because ethyne is now obtained from processing oil.

CaC<sub>2</sub> is an important chemical intermediate. When CaC<sub>2</sub> is heated in an electric furnace with atmospheric dinitrogen at 1100 °C, calcium cyanamide CaNCN is formed. This is an important reaction because it is one method of fixing atmospheric dinitrogen. (The Haber process for NH<sub>3</sub> is another method of fixing dinitrogen.)








The cyanamide ion [N=C=N]<sup>2-</sup> is isoelectronic with CO<sub>2</sub> and has the same linear structure. CaNCN is produced on a large scale, particularly in locations where there is cheap electricity. At one time about 1.3 million tonnes/year was produced though this is now increasing. Cyanamide is

widely used (particularly in SE Asia and the Far East) as a slow acting nitrogenous fertilizer, as it hydrolyses slowly over a period of months.  $\text{CaNCN}$  has the advantage over more soluble nitrogenous fertilizers such as  $\text{NH}_4\text{NO}_3$  or urea, in that it is not washed away with the first rainstorm.



Other important industrial uses of  $\text{CaNCN}$  are the manufacture of cyanamide  $\text{H}_2\text{NCN}$  which is used to make urea and thiourea, and of melamine which forms hard plastics with formaldehyde.



It is interesting that  $\text{BaC}_2$  also reacts with  $\text{N}_2$ , but it forms a cyanide  $\text{Ba}(\text{CN})_2$ , not a cyanamide  $(\text{NCN})^{2-}$

## INSOLUBLE SALTS

The sulphates of calcium, strontium and barium are insoluble, and the carbonates, oxalates, chromates and fluorides of the whole group are insoluble. This is a useful factor in qualitative analysis.

## ORGANOMETALLIC COMPOUNDS

Both Be and Mg form an appreciable number of compounds with  $\text{M}-\text{C}$  bonds, but only a few have been isolated for Ca, Sr and Ba.

Victor Grignard, a Frenchman, won the Nobel Prize for Chemistry in 1912 for his work on organomagnesium compounds which are now called Grignard reagents. These are probably the most versatile reagents in organic chemistry, and can be used to make a wide variety of alcohols, aldehydes, ketones, carboxylic acids, esters, amides and alkenes. The use of Grignard reagents and lithium alkyls provide the two general methods for making organometallic compounds, and hence Grignard compounds are very important in inorganic chemistry too.

Grignard reagents are made by the slow addition of an alkyl or aryl halide (Cl, Br or I) to a continuously stirred mixture of magnesium turnings in an absolutely dry organic solvent such as diethyl ether. Water and air must be rigorously excluded. The reaction often has an induction period before it starts, and may require the addition of a crystal of iodine to penetrate the oxide film on the metal to make it start. Very reactive magnesium can be prepared by reducing magnesium halides with potassium in the presence of KI, and the use of this makes it easier to prepare Grignard reagents, and extends their uses.



Grignard reagents are all very reactive. Iodides are the most reactive, and chlorides the least reactive. Alkyl Grignard compounds are usually more reactive than aryl Grignard compounds.

All Grignard reagents are rapidly hydrolysed by water to give the parent hydrocarbon.



Grignard reagents are not stored, but are made and used when required without isolating them. They are normally solvated or polymerized with halogen bridges. Their structures have long been the subject of controversy. X-ray structures of solid  $\text{PhMgBr} \cdot 2\text{Et}_2\text{O}$  and  $\text{EtMgBr} \cdot 2\text{Et}_2\text{O}$  show that the magnesium is tetrahedrally coordinated by bromine, the organic group, and oxygen atoms from ether molecules, but in solution several species may be present.















Figure 11.4 Structures of some Grignard compounds

Some typical reactions are










alkyl and aryl chlorosilanes


The alkyl and aryl chlorosilanes are commercially important in the manufacture of silicones (see Group 14).

$\text{BeCl}_2$  reacts with Grignard compounds, forming reactive alkyls and aryls. The compound  $\text{Be}(\text{Me})_2$  is dimerized in the vapour state, and polymerized in the solid. The structure formed is a chain structure which resembles that in  $\text{BeCl}_2$ . The bonding is, however, very different. The bonding in  $\text{Be}-\text{Me}-\text{Be}$  is best described as two electrons forming a three-centre bridge bond involving both Be atoms and the  $\text{CH}_3$  group, similar to the three-centre bonds in  $(\text{BeH}_2)_n$ . This is different from the halogen bridging in  $(\text{BeCl}_2)_n$  where the bridging chlorine atom forms two normal two-electron bonds.

Though much less studied than Grignard compounds, the other Group 2 metals also form dialkyl and diaryl compounds. These may be prepared using Grignard compounds, lithium alkyls/aryl or mercury alkyls/aryl.



Similar reactions may be used to make dialkyls and diaryls of Mg, Ca, Sr and Ba. The Ca, Sr and Ba compounds are much more reactive than the corresponding magnesium compound. The beryllium alkyls react with  $\text{BeCl}_2$  to form 'beryllium Grignard' compounds.







These are less reactive than the corresponding magnesium (Grignard) compounds.

## COMPLEXES

Group 2 metals are not noted for their ability to form complexes. The factors favouring complex formation are small highly charged ions with suitable empty orbitals of low energy which can be used for bonding. All the elements in the group form divalent ions, and these are smaller than the corresponding Group 1 ions: hence Group 2 elements are better at forming complexes than Group 1 elements. Be is appreciably smaller than the others, and so Be forms many complexes. Of the others, only Mg and Ca show much tendency to form complexes in solution, and these are usually with oxygen-donor ligands.

Beryllium fluoride  $\text{BeF}_2$  readily coordinates two extra  $\text{F}^-$  ions, forming the  $[\text{BeF}_4]^{2-}$  complex. The tetrafluoroberyllates  $\text{M}_2[\text{BeF}_4]$  are well known complex ions, and resemble the sulphates in properties. In most cases beryllium is four-coordinate in complexes and the tetrahedral arrangement adopted correlates with the orbitals available for complex formation.

Electronic structure of beryllium atom in the ground state	$1s$ 	no unpaired electrons so form no covalent bonds
Electronic structure of beryllium atom in excited state	$1s$ 	two unpaired electrons, so can form two covalent bonds
Electronic structure of beryllium atom in gaseous $\text{BeF}_2$ molecule	$1s$  <p>two electron pairs – linear molecule (<math>sp</math> hybridization)</p>	two fluorine atoms share electrons with the unpaired electrons
Electronic structure of beryllium atom in $[\text{BeF}_4]^{2-}$ complex ion	$1s$  <p>four electron pairs from two covalent and two coordinate bonds – tetrahedral molecule (<math>sp^3</math> hybridization)</p>	two $\text{F}^-$ ions each donate an electron pair into an empty orbital forming two coordinate bonds

In a similar way complexes of the type  $\text{BeCl}_2 \cdot \text{D}_2$  are formed (where  $\text{D}$  is an ether, aldehyde or ketone with an oxygen atom which has a lone pair of electrons that can be donated). These complexes, like  $[\text{Be}(\text{H}_2\text{O})_4]^{2+}$  are tetrahedral.

Many stable chelate complexes of  $\text{Be}$  are known, including beryllium oxalate  $[\text{Be}(\text{ox})_2]^{2-}$ , with  $\beta$ -diketones such as acetylacetone, and with catechol. In all of these the  $\text{Be}^{2+}$  ion is tetrahedrally coordinated (see Figure 11.5b).

A complex with an unusual structure called basic beryllium acetate  $[\text{Be}_4\text{O}(\text{CH}_3\text{COO})_6]$  is formed if  $\text{Be}(\text{OH})_2$  is evaporated with acetic acid. The structure comprises a central oxygen atom surrounded by four beryllium atoms located at the corners of a tetrahedron, with six acetate groups arranged along the six edges of the tetrahedron (see Figure 11.5a). This structure is one of a series with different organic acids replacing the acetate





Figure 11.5 (a) Basic beryllium acetate  $\text{Be}_4\text{O}(\text{CH}_3\text{COO})_6$ . (b) Beryllium oxalate complex  $[\text{Be}(\text{ox})_2]^{2-}$

group, and it is the same as the structure of basic beryllium nitrate (Figure 11.1b). Basic beryllium acetate is soluble in organic solvents. It is covalent, and thus has a fairly low melting point ( $285^\circ\text{C}$ ) and boiling point ( $330^\circ\text{C}$ ). These are low enough for it to be distilled, which is useful in the purification of beryllium.

Be compounds are said to taste sweet, but do **not** test this for yourself as they are extremely toxic. This is due to their very high solubility and their ability to form complexes with enzymes in the body. Be displaces Mg from some enzymes because it has a stronger complexing ability. Contact with the skin causes dermatitis, and inhaling dust or smoke causes a disease called berylliosis which is rather like silicosis.

Magnesium forms a few halide complexes such as  $[\text{NEt}_4]_2[\text{MgCl}_4]$ , but Ca, Sr and Ba do not.

From the viewpoint of life on this planet the most important complex formed by magnesium is chlorophyll. The magnesium is at the centre of a flat heterocyclic organic ring system called a porphyrin, in which four nitrogen atoms are bonded to the magnesium (see Figure 11.6). Chlorophyll is the green pigment in plants which absorbs light in the red region from sunlight, and makes the energy available for photosynthesis. In this process  $\text{CO}_2$  is converted into sugars.





Almost all life ultimately depends on chlorophyll and photosynthesis. The dioxygen in the atmosphere is a by-product of photosynthesis, and food-stuffs are either parts of plants, or animals which feed on plants. Though photosynthesis is commonly associated with higher plants, about half actually occurs in algae, and certain green, brown, red and purple bac-

teria. The photosynthetic bacteria are anaerobic and are poisoned by  $O_2$ . These bacteria oxidize  $H_2S$  to  $S$ , or oxidize an organic molecule instead of the usual reaction where  $H_2O$  is oxidized to  $O_2$ .

Calcium and the rest of the group only form complexes with strong complexing agents. Examples include acetylacetone,  $CH_3 \cdot CO \cdot CH_2 \cdot CO \cdot CH_3$  (which has two donor oxygen atoms), and ethylenediaminetetraacetic acid, EDTA, which has four donor oxygen atoms and two donor nitrogen atoms in each molecule. The free acid  $H_4EDTA$  is insoluble, and the disodium salt  $Na_2H_2EDTA$  is the most used reagent.



EDTA will form six-coordinate complexes with most metal ions in solution provided that the pH is suitably adjusted. Since Be is invariably four-coordinate it does not complex appreciably with EDTA. In contrast, calcium and magnesium complex with EDTA, and titrations are performed using EDTA in buffered solutions to estimate the amounts of  $Ca^{2+}$  and  $Mg^{2+}$  present to determine the 'hardness' of the water. EDTA



(\* = donor atom)

Figure 11.6 (a) Chlorophyll a (b) Ethylenediaminetetraacetic acid EDTA

titrations of  $\text{Ca}^{2+}$  and  $\text{Mg}^{2+}$  are carried out at higher pH than those of many other metals (e.g.  $\text{Zn}^{2+}$ ,  $\text{Cd}^{2+}$  and  $\text{Pb}^{2+}$ ) as their complexes are less stable, and at lower pH values the EDTA is protonated instead of the Ca or Mg complex forming. EDTA is sometimes added to detergents to soften the water. Various polyphosphate ions also form complexes in solution, and this is also important in water softening.

Stable solid complexes with crown ethers and crypts have been isolated. Details of these are given in 'Complexes crowns and crypts' in Chapter 9.

### BIOLOGICAL ROLE OF $\text{Mg}^{2+}$ AND $\text{Ca}^{2+}$

$\text{Mg}^{2+}$  ions are concentrated in animal cells, and  $\text{Ca}^{2+}$  are concentrated in the body fluids outside the cell, in much the same way that  $\text{K}^{+}$  concentrates inside the cell and  $\text{Na}^{+}$  outside.  $\text{Mg}^{2+}$  ions form a complex with ATP, and are constituents of phosphohydrolases and phosphotransferases, which are enzymes for reactions involving ATP and energy release. They are also essential for the transmission of impulses along nerve fibres.  $\text{Mg}^{2+}$  is important in chlorophyll, in the green parts of plants.  $\text{Ca}^{2+}$  is important in bones and teeth as apatite  $\text{Ca}_3(\text{PO}_4)_2$ , and the enamel on teeth as fluoroapatite  $[\text{3}(\text{Ca}_3(\text{PO}_4)_2) \cdot \text{CaF}_2]$ .  $\text{Ca}^{2+}$  ions are important in blood clotting, and are required to trigger the contraction of muscles and to maintain the regular beating of the heart.

### DIFFERENCES BETWEEN BERYLLIUM AND THE OTHER GROUP 2 ELEMENTS

Beryllium is anomalous in many of its properties and shows a diagonal relationship to aluminium in Group 13:

1. Be is very small and has a high charge density so by Fajans' rules it has a strong tendency to covalency. Thus the melting points of its compounds are lower ( $\text{BeF}_2$  m.p.  $800^\circ\text{C}$  whilst the fluorides of the rest of group melt about  $1300^\circ\text{C}$ ). The Be halides are all soluble in organic solvents and hydrolyse in water rather like the aluminium halides. The other Group 2 halides are ionic.
2. Beryllium hydride is electron deficient and polymeric, with multi-centre bonding, like aluminium hydride.
3. The halides of beryllium are electron deficient, and are polymeric, with halogen bridges.  $\text{BeCl}_2$  usually forms chains but also exists as the dimer.  $\text{AlCl}_3$  is dimeric.
4. Be forms many complexes – not typical of Groups 1 and 2.
5. Be is amphoteric, liberating  $\text{H}_2$  with  $\text{NaOH}$  and forming beryllates. Al forms aluminates.
6.  $\text{Be}(\text{OH})_2$ , like  $\text{Al}(\text{OH})_3$ , is amphoteric.
7. Be, like Al, is rendered passive by nitric acid.
8. The standard electrode potentials for Be and Al,  $-1.85$  volts and  $-1.66$  volts respectively, are much closer than the value for Be is to the values for Ca, Sr and Ba ( $-2.87$ ,  $-2.89$  and  $-2.90$  volts) respectively.

- 9 Be salts are extensively hydrolysed
- 10 Be salts are among the most soluble known
- 11 Beryllium forms an unusual carbide  $\text{Be}_2\text{C}$ , which like  $\text{Al}_4\text{C}_3$  yields methane on hydrolysis

There is plainly a diagonal similarity between beryllium in Group II and aluminium in Group III. Just as was the case with lithium and magnesium the similarity in atomic and ionic sizes is the main factor underlying this relationship.

### FURTHER READING

- Bell N A (1972) Beryllium halides and complexes *Adv Inorg Radiochem* 14 225
- Dietrich B (1985) Coordination chemistry of alkali and alkaline earth cations with macrocyclic ligands *J Chem Ed* 62 954–964 (Crowns and crypts)
- Everest D A (1973) Beryllium *Comprehensive Inorganic Chemistry* Vol I Pergamon Press Oxford
- Goodenough R D and Stenger V A (1973) Magnesium calcium strontium barium and radium *Comprehensive Inorganic Chemistry* Vol I Pergamon Press Oxford
- Hanusz T P (1987) Re-examining the diagonal relationships *J Chem Ed* 64 686–687
- Hughes M N (1972) *The Inorganic Chemistry of Biological Processes* (Chapter 8) John Wiley London (Group I and II metals in biology)
- Hughes M N and Birch N J (1982) IA and IIA cations in biology *Chemistry in Britain* 18 196–198
- Parker D (1983) Alkali and alkaline earth cryptates *Adv Inorg Radiochem* 27 1–26
- Sargeson A M (1979) Caged metal ions *Chemistry in Britain* 15 23–27 (A straightforward account of crown ethers, crypts etc.)
- Schubert J (1973) Readings from *Scientific American in Chemistry of the Environment* (Chapter 34 Beryllium and berylliosis) W H Freeman San Francisco
- Skilleter D N (1990) To be or not to be – the story of beryllium toxicity *Chemistry in Britain* 26 26–30
- Spiro T G (ed) (1983) *Calcium in Biology* Wiley Interscience New York
- Waker W E C (1980) *Magnesium and Man* Harvard University Press London

### PROBLEMS

- 1 Why are Group II elements smaller than their Group I counterparts?
- 2 Why are Group II metals harder and why do they have higher melting points than Group I metals?
- 3 What is the reason why compounds of Be are much more covalent than other Group II compounds?
- 4 What is the structure of  $\text{BeCl}_2$  in the gaseous state and as a solid? Why is  $\text{BeCl}_2$  acidic when dissolved in water?
- 5 Describe the difference in structure between  $\text{BeH}_2$  and  $\text{CaH}_2$ .
- 6 Why do the halides and hydrides of Be polymerize?

7. What precautions are necessary when handling beryllium compounds?
8. What are the usual coordination numbers for  $\text{Be}^{2+}$  and  $\text{Mg}^{2+}$ ? What is the reason for the difference?
9. Compare the extent of hydration of Group 1 and Group 2 halides. Why do Be salts seldom contain more than four molecules of water of crystallization?
10. Give equations to show the reactions between Ca and: (a)  $\text{H}_2\text{O}$ , (b)  $\text{H}_2$ , (c) C, (d)  $\text{N}_2$ , (e)  $\text{O}_2$ , (f)  $\text{Cl}_2$ , (g)  $\text{NH}_3$ .
11. Compare the reaction with water of Group 1 and Group 2 metals. How does the basic strength of Group 2 hydroxides vary within the group? Is this trend typical of the rest of the periodic table?
12. The hardness of water may be 'temporary' or 'permanent'.
  - (a) What causes each of these conditions, and how is each treated?
  - (b) Find (from other literature sources) how naturally occurring zeolites, synthetic ion-exchange resins and polyphosphates may be used for softening water.
13. Do the alkaline earth metal ions form many complexes? Are Group 2 better or worse than Group 1 at forming complexes? What is the reason for the difference? Which of the metal ions in the group are best at forming complexes? Which are the best complexing agents? Name one complex of a Group 2 metal which is of biological importance.
14. Outline the preparation, properties, structure and use of basic beryllium acetate.
15. Under what conditions do the Group 2 metal ions form stable complexes with EDTA? How are the amounts of  $\text{Ca}^{2+}$  and  $\text{Mg}^{2+}$  present in water estimated by titration with EDTA? (Consult a practical textbook, e.g. Vogel). Are the EDTA complexes more or less stable than those of most other metal ions? Why is the titration performed at a high pH? What indicator is used?
16. Describe how you would prepare a Grignard reagent from Mg, and list five different uses of the reagent in preparative reactions. (Refer also to the section on silicones.)
17. The four general methods of extracting metals are thermal decomposition, displacement of one element by another, chemical reduction, and electrolytic reduction. How are Group 2 metals obtained and why are the other methods unsuitable?
18. On treatment with cold water, an element (A) reacted quietly, liberating a colourless, odourless gas (B), and a solution (C). Lithium reacted with (B) yielding a solid product (D) which effervesced with water to give a strongly basic solution (F). When carbon dioxide was

bubbled through solution (C) an initial white precipitate (G) was formed but this re dissolved forming solution (H) when more carbon dioxide was added. Precipitate (G) effervesced when moistened with concentrated hydrochloric acid and gave a deep red coloration to a Bunsen burner flame. When (G) was heated with carbon at  $1000^{\circ}\text{C}$  a caustic white compound (I) was formed which when heated with carbon at  $1000^{\circ}\text{C}$  gave a solid (J) of some commercial importance. Name the substances (A) to (J) and give balanced chemical equations for each of the reactions.

- 19 When a white substance (A) was treated with dilute hydrochloric acid a colourless gas (B) was evolved which turned moist litmus paper red. On bubbling (B) through lime water a precipitate (C) was formed but passage of further gas resulted in a clear solution (D). A small sample of (A) was moistened with concentrated hydrochloric acid and placed on a platinum wire and introduced into a Bunsen burner flame where it caused a green flame coloration. On strong heating (A) decomposed giving a white solid (E) which turned red litmus paper blue. 1.9735 g of (A) was heated strongly and gave 1.5334 g of (E). The sample of (E) was dissolved in water and made up to 250 ml in a standard flask. 25 ml aliquots were titrated with acid and required 20.30 ml of 0.0985 M hydrochloric acid. Name the compounds (A) to (E) inclusive and give equations for all the reactions. Calculate the gram molecular weight of (A).



# The *p*-Block Elements

## Part Three

# The group 13 elements

12

Table 12.1 Electronic structures and oxidation states

Element	Symbol	Electronic configuration	Oxidation states*
Boron	B	[He] $2s^2 2p^1$	<b>III</b>
Aluminium	Al	[Ne] $3s^2 3p^1$	(I) <b>III</b>
Gallium	Ga	[Ar] $3d^{10} 4s^2 4p^1$	I <b>III</b>
Indium	In	[Kr] $4d^{10} 5s^2 5p^1$	I <b>III</b>
Thallium	Tl	[Xe] $4f^{14} 5d^{10} 6s^2 6p^1$	I <b>III</b>

\*The most important oxidation states (generally the most abundant and stable) are shown in bold. Other well-characterized but less important states are shown in normal type. Oxidation states that are unstable, or in doubt, are given in parentheses.

## GENERAL PROPERTIES

Boron is a non-metal, and always forms covalent bonds. Normally it forms three covalent bonds at  $120^\circ$  using  $sp^2$  hybrid orbitals. There is no tendency to form univalent compounds. All  $BX_3$  compounds are electron deficient, and may accept an electron pair from another atom, thus forming a coordinate bond.  $BF_3$  is commercially important as a catalyst. Boron also forms a large number of compounds in which the boron atoms form an open basket type of structure, and some which are a closed polyhedron. Other atoms such as carbon may be included in the polyhedron. The bonding in these compounds is of considerable theoretical interest, and involves multi-centre bonds.

The four elements Al, Ga, In and Tl all form trivalent compounds. The heavier members show the 'inert pair effect', and univalent compounds become increasingly important in the order  $Ga \rightarrow In \rightarrow Tl$ . These four elements (Table 12.1) are more metallic, and more ionic, than B. They are moderately reactive metals. Their compounds are on the borderline between ionic and covalent. Many of their compounds are covalent when anhydrous, but they form ions in solution.

## OCCURRENCE AND ABUNDANCE

Boron is a fairly rare element, but it is well known because it occurs as concentrated deposits of borax  $\text{Na}_2[\text{B}_4\text{O}_5(\text{OH})_4] \cdot 8\text{H}_2\text{O}$  and kernite  $\text{Na}_2[\text{B}_4\text{O}_5(\text{OH})_4] \cdot 2\text{H}_2\text{O}$ . The largest deposits are in the Mojave desert (in California), and in Death Valley (in Utah). These are desert regions. Over a long period of time, any rain has leached these alkaline salts from the hills into lakes in the valleys. These lakes have long since dried up leaving solid deposits on the surface from 10 to 50 metres deep. The amount of crude borate minerals mined in 1993 – was 5.3 million tonnes. The largest producers are the Soviet Union 53%, and the USA and Turkey 19% each.

Aluminium is the most abundant metal, and the third most abundant element (after oxygen and silicon) by weight in the earth's crust. It is well known and is commercially important. Aluminium metal is produced on a vast scale. Primary production was 19.4 million tonnes in 1992, and an additional 5 million tonnes is recycled. The most important ore of aluminium is bauxite. This is a generic name for several minerals with formulae varying between  $\text{Al}_2\text{O}_3 \cdot \text{H}_2\text{O}$  and  $\text{Al}_2\text{O}_3 \cdot 3\text{H}_2\text{O}$ . World production of bauxite was 108.6 million tonnes in 1992. Aluminium also occurs in large amounts in aluminosilicate rocks such as feldspars, and micas. When these rocks weather they form clay minerals or other metamorphic rocks. There is no easy or economical method of extracting aluminium from feldspars, micas or clays.

Table 12.2 Abundance of the elements in the earth's crust by weight

	ppm	Relative abundance
B	9	38
Al	83 000	3
Ga	19	33 =
In	0.24	63
Tl	0.5	60


Gallium is twice as abundant as boron, but indium and thallium are much less common. All three elements, Ga, In and Tl, occur as sulphides. Ga, In and Tl are not very well known. This is partly because they do not occur as concentrated ores, and partly because there are no major uses for them. Small amounts of Ga are found in the ores of the elements adjacent to it in the periodic table (Al, Zn and Ge). Traces of In and Tl are found in ZnS and PbS ores. Production of In was 145 tonnes, Ga 28 tonnes, and Tl 14.5 tonnes in 1993.

## EXTRACTION AND USES OF THE ELEMENTS

### Extraction of boron




Amorphous boron of low purity (called Moissan boron) is obtained by

reducing  $B_2O_3$  with Mg or Na at a high temperature. It is 95–98% pure (being contaminated with metal borides), and is black in colour.



It is difficult to obtain pure crystalline boron, as it has a very high melting point ( $2180^\circ\text{C}$ ), and the liquid is corrosive. Small amounts of crystalline boron may be obtained:

1. By reducing  $BCl_3$  with  $H_2$ . This is done on the kilogram scale.
2. Pyrolysis of  $BI_3$  (Van Arkel method).
3. Thermal decomposition of diborane or other boron hydrides.



#### Uses of boron

An important use of boron is to make boron steel or boron carbide control rods for nuclear reactors. Boron has a very high cross-section for capturing neutrons. Control rods made of boron steel or boron carbide may be lowered into a reactor to absorb neutrons and thus slow the reactor down. Boron carbide is also used as an abrasive. Boron is used to make impact resistant steel, as it increases the hardenability (that is the depth to which it will harden) of steel.

Borax  $Na_2[B_4O_5(OH)_4] \cdot 8H_2O$ , orthoboric acid  $H_3BO_3$  and boron sesquioxide  $B_2O_3$  find many uses. The most important uses are making fibreglass for insulation and textiles (50% of use in USA) and perborates for detergents (35% in Europe). World production of borax was roughly 2.2 million tonnes in 1992 (USA 45%, Turkey 42%). Borax is used as a flame retardant for fabric and wood, and mixed with NaOH and sold as 'Polybor' and 'Timbor' for treating timber and hardboard against attack by wood-boring insects. Borax is used as a flux in brazing and in silver soldering. The borax reacts with oxides (such as  $Cu_2O$  on the surface of hot brass), the borates so formed melt, and a clean metal surface is exposed to the solder. Borax is also used in making enamel, and in leather tanning.

Orthoboric acid is made by treating borate ores with sulphuric acid. About 211 000 tonnes were made in 1992. Reaction of  $H_3BO_3$  with  $H_2O_2$  gives the mono peroxoboric acid, which probably has the structure  $[(HO)_3B(OOH)]$ . Sodium peroxoborate  $Na_2[B_2(O_2)_2(OH)_4] \cdot 6H_2O$  is a constituent of many detergents and washing powders, particularly in Europe, where washing powders may contain 20% of sodium peroxo-

*continued overleaf*

borate. It is used less in the USA. World production is 550 000 tonnes/year. Peroxoborates act as brighteners, because they absorb UV light and emit visible light. This makes both white and coloured fabrics appear extra bright. If used at temperatures over 80 °C, peroxoborates decompose to hydrogen peroxide  $\text{H}_2\text{O}_2$ , which acts as a bleach.


Boron sesquioxide  $\text{B}_2\text{O}_3$  is used in making borosilicate (heat resistant) glass (e.g. Pyrex which contains 14%  $\text{B}_2\text{O}_3$ ). Borosilicate glass has a lower coefficient of thermal expansion and is easier to work than normal 'soda glass'.  $\text{H}_3\text{BO}_3$ ,  $\text{B}_2\text{O}_3$  and calcium borate are used to make soda-free glass fibre, which is used for thermal insulation in houses.

### Extraction of aluminium

Aluminium is obtained from the ore bauxite which may be  $\text{AlO}(\text{OH})$  ( $\text{Al}_2\text{O}_3 \cdot \text{H}_2\text{O}$ ) or  $\text{Al}(\text{OH})_3$  ( $\text{Al}_2\text{O}_3 \cdot 3\text{H}_2\text{O}$ ). One hundred and eight million tonnes were mined in 1992. The largest sources are Australia 37%, Guinea 15%, Jamaica 10% and Brazil 9%.

The first step is to purify the ore. In the *Bayer process*, waste materials (mainly iron and silicon compounds) are removed because these would spoil the properties of the product.  $\text{NaOH}$  is added to the ore, and as Al is amphoteric it dissolves forming sodium aluminate.  $\text{SiO}_2$  also dissolves as silicate ions. Any insoluble waste materials, particularly iron oxide, are removed by filtering. Next aluminium hydroxide is precipitated from the strongly alkaline aluminate solution. This may be done either by bubbling in some  $\text{CO}_2$  (an acidic oxide which lowers the pH), or by seeding the solution with  $\text{Al}_2\text{O}_3$ . The silicate ions remain in solution. The  $\text{Al}(\text{OH})_3$  precipitate is calcined (heated strongly) which converts it to purified  $\text{Al}_2\text{O}_3$ .

Aluminium is usually extracted by the *Hall-Héroult process*.  $\text{Al}_2\text{O}_3$  is melted with cryolite  $\text{Na}_3[\text{AlF}_6]$ , and electrolysed in a graphite lined steel tank, which serves as the cathode. The anodes are also made of graphite. The cell runs continuously, and at intervals molten aluminium (m.p. 660 °C) is drained from the bottom of the cell and more bauxite is added. Some cryolite is mined as a mineral in Greenland, but this is insufficient to meet the demand for it, and most is made synthetically.



Cryolite improves the electrical conductivity of the cell as  $\text{Al}_2\text{O}_3$  is a poor conductor. In addition, the cryolite serves as an added impurity and lowers the melting point of the mixture to about 950 °C. Other impurities such as  $\text{CaF}_2$  and  $\text{AlF}_3$  may also be added. (A typical electrolyte mixture is 85%  $\text{Na}_3[\text{AlF}_6]$ , 5%  $\text{CaF}_2$ , 5%  $\text{AlF}_3$  and 5%  $\text{Al}_2\text{O}_3$ .) Various products are formed at the anodes, including  $\text{O}_2$ ,  $\text{CO}_2$ ,  $\text{F}_2$  and carbon compounds of fluorine. These erode the anodes, which must be replaced periodically. The traces of fluorine formed cause serious corrosion. Large amounts of  $\text{Li}_2\text{CO}_3$  are now used as an alternative impurity, because this reduces corrosion. Energy consumption is very high, and the process is only econ

omic where there is a source of cheap electricity, usually hydroelectric power.

### Uses of aluminium

Aluminium metal is moderately soft and weak when pure, but is much stronger when alloyed with other metals. Its main advantage is its lightness (low density  $2.73 \text{ g cm}^{-3}$ ). Some alloys are used for special purposes: duralumin which contains about 4% Cu, and several aluminium bronzes (alloys of Cu and Al with other metals such as Ni, Sn and Zn). The metal produced in the largest quantity is iron/steel (712 million tonnes in 1992) but production of aluminium is the second largest. (Total production of Al was 24.4 million tonnes in 1991, made up of 19.4 million tonnes primary production and 5 million tonnes recycled.) The largest producers of Al metal are the USA 21%, the Soviet Union 17%, Canada 10%, and Australia, Brazil and China 6% each. There are many uses for aluminum and its alloys:

1. As structural metals in aircraft, ships, cars, and heat exchangers.
2. In buildings (doors, windows, cladding panels and mobile homes).
3. Containers such as cans for drinks, tubes for toothpaste etc. and metal foil.
4. For cooking utensils.
5. To make electric power cables (on a weight for weight basis they conduct twice as well as copper).
6. Finely divided aluminium powder is called 'aluminium bronze', and is used in preparing aluminium paint.

It has been assumed for many years that  $\text{Al}^{3+}$  is completely harmless and non-toxic to humans.  $\text{Al}(\text{OH})_3$  is widely used as an anti-acid treatment for indigestion.  $\text{Al}_2(\text{SO}_4)_3$  is used to treat drinking water, and cooking utensils are made of aluminium. However, there are indications that aluminium may not be as harmless as was once thought. Aluminium is acutely toxic to people with kidney failure, who are unable to excrete the element. Patients suffering from Alzheimer's disease (which causes senility) have deposits of aluminium salts in the brain. This element, though toxic, is normally excreted very efficiently. Any abundant element will inevitably be taken up by plants and then by animals, and in general the biosphere either makes use of elements (in which case they are classed as essential) or positively rejects them. Elements are hardly ever toxicologically neutral.

### Gallium, indium and thallium

Traces of gallium are found in bauxite, and the ratio of Ga to Al is about 1/5000. During the Bayer process for purifying alumina the concentration of Ga in the alkaline solution gradually increases to about 1/250. Ga is extracted by electrolysis of this solution. Indium and thallium occur in minute quantities in ZnS and PbS ores. These sulphide ores are roasted

*continued overleaf*

with air in a smelter, to convert them to ZnO and PbO. The Ga and In are recovered from the flue dust, and they are extracted by electrolysis of aqueous solutions of their salts.

*The metals are soft, silver coloured and reactive. They dissolve in acids.* There are no large scale uses for Ga, In or Tl, but small amounts of Ga are used to dope crystals to make transistors. Semiconductor manufacture requires ultra-high purity Ga. This is obtained by zone refining. Gallium is also used in other semiconductor devices. Gallium arsenide GaAs is iso-electronic with Ge, and is used in light emitting diodes (LEDs) and laser diodes. There is a lot of research into using GaAs to make memory chips for computers, since these work 5 to 10 times faster than those made from silicon. Indium is used to dope crystals to make *p-n-p* transistors, and in thermistors (InAs and InSb). It is also used in low melting point solder (commonly used to solder semiconductor chips) and other low melting alloys.

## OXIDATION STATES AND TYPE OF BONDS

### The (+III) oxidation state

The elements all have three outer electrons. Apart from Tl they normally use these to form three bonds, giving an oxidation state of (+III). Are the bonds ionic or covalent? Covalency is suggested by the following:

- 1 Fajans' rules – small size of the ions and their high charge of 3+ favours the formation of covalent bonds.
- 2 The sum of the first three ionization energies is very large, and this also suggests that bonds will be largely covalent.
- 3 The electronegativity values are higher than for Groups 1 and 2, and when reacting with other elements the difference is not likely to be large.

Boron is considerably smaller than the other elements and thus has a higher ionization energy than the others. The ionization energy is so high that B is always covalent.

Many simple compounds of the remaining elements, such as  $\text{AlCl}_3$  and  $\text{GaCl}_3$ , are covalent when anhydrous. However, Al, Ga, In and Tl all form metal ions in solution. The type of bonds formed depends on which is most favourable in terms of energy. This change from covalent to ionic happens because the ions are hydrated, and the amount of hydration energy evolved exceeds the ionization energy. Consider  $\text{AlCl}_3$ : 5137 kJ mol<sup>-1</sup> are required to convert Al to  $\text{Al}^{3+}$ ,  $\Delta H_{\text{hydration}}$  for  $\text{Al}^{3+}$  is -4665 kJ mol<sup>-1</sup> and  $\Delta H_{\text{hydration}}$  for  $\text{Cl}^-$  is -381 kJ mol<sup>-1</sup>. Thus the total hydration energy is

$$-4665 + (3 \times -381) = -5808 \text{ kJ mol}^{-1}$$

This exceeds the ionization energy, so  $\text{AlCl}_3$  ionizes in solution.

The hydrated metal ions have six molecules of water which are held very strongly in an octahedral structure  $[\text{M}(\text{H}_2\text{O})_6]^{3+}$ . The metal–oxygen bonds are very strong. This weakens the  $\text{O—H}$  bonds, and protons are released to neighbouring water molecules, forming  $\text{H}_3\text{O}^+$  (hydrolysis).



### The (+I) oxidation state – the ‘inert pair effect’

In the *s*-block, Group 1 elements are univalent, and Group 2 elements are divalent. In Group 13 we would expect the elements to be trivalent. In most of their compounds this is the case, but some of the elements show lower valency states as well. There is an increasing tendency to form univalent compounds on descending the group. Compounds with  $\text{Ga}(\text{I})$ ,  $\text{In}(\text{I})$  and  $\text{Tl}(\text{I})$  are known. With Ga and In the (+I) oxidation state is less stable than the (+III) state. However, the stability of the lower oxidation state increases on descending the group.  $\text{Tl}(\text{I})$  thallos compounds are more stable than  $\text{Tl}(\text{III})$  thallic compounds.

How and why does monovalency occur? The atoms in this group have an outer electronic configuration of  $s^2p^1$ . Monovalency is explained by the *s* electrons in the outer shell remaining paired, and not participating in bonding. This is called the ‘inert pair effect’. If the energy required to unpair them exceeds the energy evolved when they form bonds, then the *s* electrons will remain paired. The strength of the bonds in  $\text{MX}_3$  compounds decreases down the group. The mean bond energy for chlorides are  $\text{GaCl}_3 = 242$ ,  $\text{InCl}_3 = 206$  and  $\text{TlCl}_3 = 153 \text{ kJ mol}^{-1}$ . Thus the *s* electrons are most likely to be inert in thallium.

*The inert pair effect is not the explanation of why monovalency occurs in Group 13. It merely describes what happens, i.e. two electrons do not participate in bonding. The reason that they do not take part in bonding is energy. The univalent ions are much larger than the trivalent ions, and (+I) compounds are ionic, and are similar in many ways to Group 1 elements.*

The inert pair effect is not restricted to Group 13, but also occurs among the heavier elements in other groups in the *p*-block. Examples from Group 14 are  $\text{Sn}^{2+}$  and  $\text{Pb}^{2+}$ , and examples from Group 15 are  $\text{Sb}^{3+}$  and  $\text{Bi}^{3+}$ . The lower oxidation state becomes more stable on descending the group. Thus  $\text{Sn}^{2+}$  is a reducing agent but  $\text{Pb}^{2+}$  is stable and  $\text{Sb}^{3+}$  is a reducing agent but  $\text{Bi}^{3+}$  is stable. When the *s* electrons remain paired, the oxidation state is always two lower than the usual oxidation state for the group.

Thus in the *s*-block, Groups 1 and 2 show only the group valency. Groups in the *p*-block show variable valency, differing in steps of two. Variable valency also occurs with elements in the *d*-block. This arises from using different numbers of *d* electrons for bonding, so in this case the valency can change in steps of one (e.g.  $\text{Cu}^+$  and  $\text{Cu}^{2+}$ ,  $\text{Fe}^{2+}$  and  $\text{Fe}^{3+}$ ).



### The (+II) oxidation state

Gallium is *apparently* divalent in a few compounds, such as  $\text{GaCl}_2$ . However, Ga is not really divalent, as the structure of  $\text{GaCl}_2$  has been shown to be  $\text{Ga}^+[\text{GaCl}_4]^-$  which contains Ga(I) and Ga(III).

### MELTING POINTS, BOILING POINTS AND STRUCTURES

The melting points of the Group 13 elements do not show a regular trend as did the metals of Groups 1 and 2. The Group 13 values are not strictly comparable because B and Ga have unusual crystal structures.

Boron has an unusual crystal structure which results in the melting point being very high. There are at least four different allotropic forms. Boron has insufficient electrons to fill the valence shell even after forming bonds. The variety and complexity of the allotropic forms illustrates the number of ways in which boron attempts to solve this problem. Other elements solve this problem by metallic bonding, but small size and high ionization energy make this impossible for boron. All four allotropic forms contain icosahedral units with boron atoms at all 12 corners. (Note that an icosahedron is a regular shape with 12 corners and 20 faces.) In these units twelve B atoms form a regular shape, and each B atom is bonded to five equivalent neighbours (at a distance of  $1.77 \text{ \AA}$ ). The difference between the allotropic forms arises in the way the icosahedra are bonded together. The simplest form is  $\alpha$ -rhombohedral boron. In this, half the atoms are bonded to one atom in another icosahedron (at a distance of  $1.71 \text{ \AA}$ ), and half the atoms are bonded to atoms in two different icosahedra (at a distance of  $2.03 \text{ \AA}$ ). Plainly this is neither a regular structure nor a metallic structure. Only 37% of space is occupied by the atoms, compared with 74% for a close-packed arrangement. This shows that icosahedra fill up space ineffectively. The other allotropes have even more complicated structures.

The elements Al, In and Tl all have close-packed metal structures. Gallium has an unusual structure. Each metal atom has one close neighbour at a distance of  $2.43 \text{ \AA}$ , and six more distant neighbours at distances between  $2.70 \text{ \AA}$  and  $2.79 \text{ \AA}$ . This remarkable structure tends towards discrete diatomic molecules rather than a metallic structure. This accounts for the incredibly low melting point of gallium of  $30^\circ\text{C}$ . Ga is also unusual because the liquid expands when it forms the solid, i.e. the solid is




Figure 12.1 (a)  $\text{B}_{12}$  icosahedron (b) Structure of  $\alpha$ -rhombohedral boron.

Table 12.3 Melting and boiling points<sup>1</sup>

	Melting point ( $^\circ\text{C}$ )	Boiling point ( $^\circ\text{C}$ )
B	2180	3650
Al	660	2467
Ga	30	2403
In	157	2080
Tl	303	1457

less dense than the liquid. This property is unique to Ga, Ge and Bi.

Though the melting points decrease from Al to In as expected on descending a group, it increases again for Tl. The boiling point of B is unusually high, but the values for Ga, In and Tl decrease on descending the group as expected. Note that the boiling point for Ga is in line with the others, whereas its melting point is not. The very low melting point is due to the unusual crystal structure, but the structure no longer exists in the liquid.

## SIZE OF ATOMS AND IONS

The metallic radii of the atoms do not increase regularly on descending the group (Table 12.4). However, the values are not strictly comparable. Boron is not a metal, and the radius given is half the closest approach in the structure. Ga has an unusual structure, and the value given is half the closest approach. The others have close-packed metal structures.

The ionic radii for  $M^{3+}$  increase down the group, though not in the regular way observed in Groups 1 and 2. There are two reasons for this:

1. There is no evidence for the existence of  $B^{3+}$  under normal conditions, and the value is an estimate.
2. The electronic structures of the elements are different. Ga, In and Tl follow immediately after a row of ten transition elements. They therefore have ten  $d$  electrons, which are less efficient at shielding the nuclear charge than the  $s$  and  $p$  electrons. (Shielding is in the order  $s > p > d > f$ .) Poor shielding of the nuclear charge results in the outer electrons being more firmly held by the nucleus. Thus atoms with a  $d^{10}$  inner shell are smaller and so have higher ionization energies than would otherwise be expected. This contraction in size is sometimes called the  $d$ -block contraction. In a similar way Tl follows immediately after 14  $f$ -block elements. The size and ionization energy of Tl are affected even more by the presence of 14  $f$  electrons, which shield the nuclear charge even less effectively. The contraction in size from these  $f$ -block elements is called the *lanthanide contraction*.

**Table 12.4** Ionic and covalent radii and electronegativity values

	Metallic radius (Å)	Ionic radius		Pauling's electronegativity
		$M^{3+}$ (Å)	$M^+$ (Å)	
B	(0.885)	(0.27)	—	2.0
Al	1.43	0.535	—	1.5
Ga	(1.225)	0.620	1.20	1.6
In	1.67	0.800	1.40	1.7
Tl	1.70	0.885	1.50	1.8

For values in brackets see text.


Table 12.5 Standard reduction potentials (volts)

Oxidation states								
+III	Acid solution			0	+III	Basic solution		0
	+II	+I				+II	+I	
Al <sup>3+</sup>	-1.66			Al	Al(OH) <sub>3</sub>	-2.31		Al
Ga <sup>3+</sup>	-0.44		-0.79	Ga	H <sub>2</sub> GaO <sub>2</sub> <sup>-</sup>	-1.22		Ga
	-0.56							
In <sup>3+</sup>	-0.44		-0.18	In	In(OH) <sub>3</sub>	-1.0		In
	-0.34							
Tl <sup>3+</sup>	+2.06		-0.34	Tl	Tl(OH) <sub>3</sub>	-0.05		Tl(OH)
	+1.26							

The large difference in size between B and Al results in many differences in properties. Thus B is a non metal, has a very high melting point, always forms covalent bonds and forms an acidic oxide. In contrast, Al is a metal, has a much lower melting point, and its oxide is amphoteric. (It is safe to generalize in this way, but unsafe to argue quantitatively that  $\text{Al}^{3+}$  is twice the size of  $\text{B}^{3+}$  or that the metallic radii differ by a factor of 1.6 as  $\text{B}^{3+}$  does not exist, and B is not a metal.)

### ELECTROPOSITIVE CHARACTER

The electropositive or metallic nature of the elements increases from B to Al, but then decreases from Al to Tl. This is shown by the standard electrode potentials for the reaction



The increase in metallic character from B to Al is the usual trend on descending a group associated with increasing size. However, Ga, In and Tl do not continue the trend. The elements are less likely to lose electrons (and are thus less electropositive) because of the poor shielding by *d* electrons described previously.


Table 12.6 Standard electrode potentials  $E^\circ$ 

	$M^{3+}   M$ (volts)	$M^+   M$ (volts)
B	(-0.87*)	
Al	-1.66	+0.55
Ga	-0.56	-0.79 <sup>†</sup>
In	-0.34	-0.18
Tl	+1.26	-0.34

\* For  $H_3BO_3 + 3H^+ + 3e^- \rightarrow B + 3H_2O$ <sup>†</sup> Value in acidic solution.

The standard electrode potentials  $E^\circ$  for  $M^{3+}|M$  become less negative from Al to Ga to In and the potential becomes positive for Tl. Since  $\Delta G = -nFE^\circ$  it follows that  $\Delta G$ , the free energy of formation of the metal, e.g.  $Al^{3+} + 3e^- \rightarrow Al$ , is positive. Thus it is difficult to make this reaction work. (The reverse reaction  $Al \rightarrow Al^{3+} + 3e^-$  occurs spontaneously.) The standard potential becomes less negative on descending the group so it becomes less difficult for the reaction  $M^{3+} \rightarrow M$  to occur. Thus the (+III) oxidation state becomes less stable in aqueous solution on descending the group. In a similar way, the  $E^\circ$  values for  $M^+|M$  show that the (+I) state increases in stability. With Tl, the (+I) state is more stable than the (+III) state.

It should be remembered that in this type of argument  $E^\circ$  and  $\Delta G$  refer to the reaction with  $H_2$ :



## IONIZATION ENERGY

The ionization energies increase as expected (first ionization energy < second ionization energy < third ionization energy). The sum of the first three ionization energies for each of the elements is very high. Thus boron

Table 12.7 Ionization energies

	Ionization energy (kJ mol <sup>-1</sup> )			
	1st	2nd	3rd	Sum of three
B	801	2427	3659	6887
Al	577	1816	2744	5137
Ga	579	1979	2962	5520
In	558	1820	2704	5082
Tl	589	1971	2877	5437

has no tendency to form ions, and always forms covalent bonds. The other elements normally form covalent compounds except in solution.

The ionization energy values do not decrease smoothly down the group. The decrease from B to Al is the usual trend on descending a group associated with increased size. The poor shielding by *d* electrons and the resulting *d*-block contraction affect the values for the later elements.

### REACTIONS OF BORON

Pure crystalline boron is very unreactive. However, it is attacked at high temperatures by strong oxidizing agents such as a mixture of hot concentrated  $\text{H}_2\text{SO}_4$  and  $\text{HNO}_3$ , or by sodium peroxide. In contrast, finely divided amorphous boron (which contains between 2% and 5% of impurities) is more reactive. It burns in air or dioxygen, forming the oxide. It also burns at white heat in dinitrogen, forming the nitride BN. This is a slippery white solid with a layer structure similar to graphite. Boron also burns in the halogens, forming trihalides. It reacts directly with many elements, forming borides, which are hard and refractory. It reduces strong  $\text{HNO}_3$  and  $\text{H}_2\text{SO}_4$  slowly, and also liberates  $\text{H}_2$  from fused  $\text{NaOH}$ .




Figure 12.2 Structure of boron nitride

Table 12.8 Some reactions of amorphous boron


Reaction	Comment
$4\text{B} + 3\text{O}_2 \rightarrow 2\text{B}_2\text{O}_3$	At high temperature
$2\text{B} + 3\text{S} \rightarrow \text{B}_2\text{S}_3$	At $1200^\circ\text{C}$
$2\text{B} + \text{N}_2 \rightarrow 2\text{BN}$	At very high temperature
$2\text{B} + 3\text{F}_2 \rightarrow 2\text{BF}_3$ $2\text{B} + 3\text{Cl}_2 \rightarrow 2\text{BCl}_3$ $2\text{B} + 3\text{Br}_2 \rightarrow 2\text{BBr}_3$ $2\text{B} + 3\text{I}_2 \rightarrow 2\text{BI}_3$	At high temperature
$2\text{B} + 6\text{NaOH} \rightarrow 2\text{Na}_3\text{BO}_3 + 3\text{H}_2$	When fused with alkali
$2\text{B} + 2\text{NH}_3 \rightarrow 2\text{BN} + 3\text{H}_2$	At very high temperature
$\text{B} + \text{M} \rightarrow \text{M}_x\text{B}_y$	Many metals form borides (not Group 1) often nonstoichiometric

### REACTIONS OF THE OTHER ELEMENTS

#### Reaction with water and air


The metals Al, Ga, In and Tl are silvery white. Thermodynamically Al should react with water and with air, but in fact it is stable in both. The

Reaction	Comment
$4M + 3O_2 \rightarrow M_2O_3$	All react at high temperature Al very strongly exothermic Ga only superficially oxidized Tl forms some $Tl_2O$ as well
$2Al + N_2 \rightarrow 2AlN$	Only Al at high temperature
$2M + 3F_2 \rightarrow 2MF_3$ $2M + 3Cl_2 \rightarrow 2MCl_3$ $2M + 3Br_2 \rightarrow 2MBr_3$ $2M + 3I_2 \rightarrow 2MI_3$ $TlI + I_2 \rightarrow Tl^+[I_3]^-$	All the metals } $Tl^+$ also formed form trihalides Al, Ga, In only thallium(I) triiodide formed
$2M + 6HCl \rightarrow 2MCl_3 + 3H_2$	All react with dilute mineral acids, Al passivated by $HNO_3$ particularly when concentrated
$Al + NaOH + H_2O \rightarrow NaAlO_2 + H_2$ $Na_3AlO_3 + H_2$	Al and Ga only
$M + NH_3 \rightarrow MNH_2$	All the metals form amides




### Reaction with dioxygen

Aluminium burns readily in air or dioxygen, and the reaction is strongly exothermic. This is known as the *Thermite reaction*.



The *Thermite reaction* evolves so much energy that it can be dangerous. The aluminium becomes white hot, and often causes fires. For this precise reason mixtures of Al and an oxide such as  $\text{Fe}_2\text{O}_3$  or  $\text{SiO}_2$  (to provide the oxygen) were used to make incendiary bombs during World War II. Warships are sometimes made of aluminium alloys to reduce their weight. A thermite reaction can be started if the ship is hit by a missile. Such fires on ships caused considerable casualties in the Falklands Islands conflict. The very strong affinity of Al for oxygen is used in the metallurgical extraction of other metals from their oxides.



### Reaction with the halogens and sulphate

Aluminium reacts with the halogens quite readily, even when cold, forming trihalides.

Aluminium sulphate is used in large amounts (3.7 million tonnes in 1991). It is made by treating bauxite with  $\text{H}_2\text{SO}_4$ . It is used as a coagulant and precipitant in treating both drinking water and sewage. It is also used in the paper industry, and as a mordant in dyeing.

### Alums

Aluminium ions may crystallize from aqueous solutions, forming double salts. These are called *aluminium alums* and have the general formula  $[\text{M}^I(\text{H}_2\text{O})_6][\text{Al}(\text{H}_2\text{O})_6](\text{SO}_4)_2$ .  $\text{M}^I$  is a singly charged cation such as  $\text{Na}^+$ ,  $\text{K}^+$  or  $\text{NH}_4^+$ . The crystals are usually large octahedra, and are extremely pure. Purity is especially important in some applications. Potash alum  $[\text{K}(\text{H}_2\text{O})_6][\text{Al}(\text{H}_2\text{O})_6](\text{SO}_4)_2$  is used as a mordant in dyeing. In this application  $\text{Al}^{3+}$  is precipitated as  $\text{Al}(\text{OH})_3$  on cloth to help the dyes bind to the cloth as aluminium complexes. It is essential that  $\text{Fe}^{3+}$  is absent in order to obtain the 'true' bright colours. Double salts break up in solution, into their constituent ions. Crystals are made up of  $[\text{M}^I(\text{H}_2\text{O})_6]^+$ ,  $[\text{Al}(\text{H}_2\text{O})_6]^{3+}$  and two  $\text{SO}_4^{2-}$  ions. The ions are simply the right size and charge to crystallize together. Some  $\text{M}^{3+}$  ions other than  $\text{Al}^{3+}$  also form alums of formula  $[\text{M}^I(\text{H}_2\text{O})_6][\text{M}^{III}(\text{H}_2\text{O})_6](\text{SO}_4)_2$ . The most common trivalent ions are  $\text{Fe}^{3+}$  and  $\text{Cr}^{3+}$ , but others include  $\text{Ti}^{3+}$ ,  $\text{V}^{3+}$ ,  $\text{Mn}^{3+}$ ,  $\text{Co}^{3+}$ ,  $\text{In}^{3+}$ ,  $\text{Rh}^{3+}$ ,  $\text{Ir}^{3+}$  and  $\text{Ga}^{3+}$ .

### Cement

Aluminium compounds, particularly tricalcium aluminate  $\text{Ca}_3\text{Al}_2\text{O}_6$ , are very important as constituents of Portland and high alumina cements. The formula of tricalcium aluminate is better written  $\text{Ca}_9[\text{Al}_6\text{O}_{18}]$ , because it contains 12-membered rings of  $\text{Si—O—Si—O}$  made by joining six  $\text{AlO}_4$  tetrahedra. Portland cement is made by heating the correct mixture of limestone ( $\text{CaCO}_3$ ) with sand ( $\text{SiO}_2$ ) and clay (aluminosilicate) at a temperature of  $1450\text{--}1600^\circ\text{C}$  in a rotary kiln. When mixed with sand and water Portland cement sets to give concrete, a hard whitish insoluble solid, similar in appearance to Portland stone. (Portland stone is limestone quarried on Portland Bill in Dorset, England.) Between 2% and 5% of gypsum  $\text{CaSO}_4 \cdot 2\text{H}_2\text{O}$  is added to slow down the setting process, as slow setting greatly increases the strength. The composition of cement is usually given in terms of the oxides. A typical composition for Portland cement is  $\text{CaO}$  70%,  $\text{SiO}_2$  20%,  $\text{Al}_2\text{O}_3$  5%,  $\text{Fe}_2\text{O}_3$  3%,  $\text{CaSO}_4 \cdot 2\text{H}_2\text{O}$  2%. Total world production of cement was 1396 million tonnes in 1993, about 70% of which was Portland cement.

High alumina cement is made by fusing limestone and bauxite with small amounts of  $\text{SiO}_2$  and  $\text{TiO}_2$  at  $1400\text{--}1500^\circ\text{C}$  in either an open hearth furnace or a rotary kiln. High alumina cement is more expensive than is Portland cement, but has one major advantage over Portland cement – it sets much quicker and develops high strength within one day. It is used to make beams for bridges and buildings. High alumina cement has good resistance to sea water and dilute mineral acids. It withstands temperatures up to  $1500^\circ\text{C}$  and so may be used with refractory bricks in furnaces. A typical analysis of high alumina cement is  $\text{CaO}$  40%,  $\text{Al}_2\text{O}_3$  40%,  $\text{SiO}_2$  10%,  $\text{Fe}_2\text{O}_3$  10%. There has been much publicity over structural failures of beams made of high alumina cement. Failure is due to prolonged exposure to hot wet conditions, or using too much water when mixing the sand and cement. This latter results in it setting too quickly and thus not having time to crystallize properly.

### Reactions of Ga, In and Tl

Gallium and indium are stable in air and are not attacked by water unless free oxygen is present. Thallium is a little more reactive and is superficially oxidized by air. All three metals dissolve in dilute acids, liberating hydrogen. Gallium is amphoteric like aluminium, and it dissolves in aqueous  $\text{NaOH}$ , liberating  $\text{H}_2$  and forming gallates. The oxides and hydroxides of Al and Ga are also amphoteric. In contrast, the oxides and hydroxides of In and Tl are purely basic.

All three metals react with the halogens on gentle warming.

### SOME PROPERTIES OF THALLIUM(I)

Thallium(I) or thallos compounds are well known. They are typically colourless. They are also extremely poisonous. When ingested, traces turn




the hair very black, but larger doses cause loss of hair and death. They are toxic because they upset the enzyme systems in the body.

In aqueous solution the  $Tl^+$  ion is much more stable than  $Tl(III)$ . The ionic radius of  $Tl^+$  ( $1.50 \text{ \AA}$ ) is between that of  $K^+$  ( $1.38 \text{ \AA}$ ) and  $Rb^+$  ( $1.52 \text{ \AA}$ ). For this reason  $Tl^+$  resembles Group 1 ions in a number of ways.  $TlOH$  and  $Tl_2O$  are both soluble in water, and are strongly basic. They absorb  $CO_2$  from the air, forming  $Tl_2CO_3$ . The solubility of most of the salts is slightly lower than for potassium salts.  $Tl^+$  can replace  $K^+$  in some enzymes, and can thus be used as a biological tracer in the body. There are some differences.  $TlOH$  is yellow, and on heating to  $100^\circ\text{C}$  it turns into black  $Tl_2O$ . The coordination number of  $Tl^+$  is usually 6 or 8, compared with 6 for Group 1 ions.  $TlF$  is soluble in water, but the other halides are almost insoluble. There is also some similarity with  $Ag^+$ , as  $TlCl$  is sensitive to light. It darkens when exposed to light rather like  $AgCl$ , but  $TlCl$  is not soluble in  $NH_4OH$  whilst  $AgCl$  is soluble.


## COMPOUNDS OF BORON AND OXYGEN

### Boron sesquioxide and the borates


These are the most important compounds of boron. Sesqui means one and a half, so the oxide should have a formula  $MO_{1\frac{1}{2}}$ , or  $M_2O_3$ . All the elements in the group form sesquioxides when heated in dioxygen.  $B_2O_3$  is made more conveniently by dehydrating boric acid:






$B_2O_3$  is a typical non-metallic oxide and is acidic in its properties. It is the anhydride of orthoboric acid, and it reacts with basic (metallic) oxides, forming salts called borates or metaborates. In the borax bead test,  $B_2O_3$  or borax  $Na_2[B_4O_5(OH)_4] \cdot 8H_2O$  is heated in a Bunsen burner flame with metal oxides on a loop of platinum wire. The mixture fuses to give a glass-like metaborate bead. Metaborate beads of many transition metals have characteristic colours, and so this reaction provides a means of identifying the metal. This simple test provided the first proof that vitamin  $B_{12}$  contained cobalt.





However, it is possible to force  $B_2O_3$  to behave as a basic oxide by reacting with very strongly acidic compounds. Thus with  $P_2O_5$  or  $As_2O_5$ , boron phosphate or boron arsenate are formed.



Orthoboric acid  $\text{H}_3\text{BO}_3$  is soluble in water, and behaves as a weak monobasic acid. It does not donate protons like most acids, but rather it accepts  $\text{OH}^-$ . It is therefore a Lewis acid, and is better written as  $\text{B}(\text{OH})_3$ .




Polymeric metaborate species are formed at higher concentrations, for example:




#### Acidic properties of $\text{H}_3\text{BO}_3$ or $\text{B}(\text{OH})_3$

Since  $\text{B}(\text{OH})_3$  only partially reacts with water to form  $\text{H}_3\text{O}^+$  and  $[\text{B}(\text{OH})_4]^-$ , it behaves as a weak acid. Thus  $\text{H}_3\text{BO}_3$  or  $(\text{B}(\text{OH})_3)$  cannot be titrated satisfactorily with  $\text{NaOH}$ , as a sharp end point is not obtained. If certain organic polyhydroxy compounds such as glycerol, mannitol or sugars are added to the titration mixture, then  $\text{B}(\text{OH})_3$  behaves as a strong monobasic acid. It can now be titrated with  $\text{NaOH}$ , and the end point is detected using phenolphthalein as indicator (indicator changes at pH 8.3–10.0).




The added compound must be a *cis*-diol, to enhance the acidic properties in this way. (This means that it has  $\text{OH}$  groups on adjacent carbon atoms in the *cis* configuration.) The *cis*-diol forms very stable complexes with the

$[\text{B}(\text{OH})_4]^-$  formed by the forward reaction above, thus effectively removing it from solution. The reaction is reversible. Thus removal of one of the products at the right hand side of the equation upsets the balance, and the reaction proceeds completely to the right. Thus all the  $\text{B}(\text{OH})_3$  reacts with  $\text{NaOH}$  in effect it acts as a strong acid in the presence of the *cis* diol



### Structures of borates

In the simple borates, each B atom is bonded to three oxygen atoms, arranged at the corners of an equilateral triangle. This would be predicted from the orbitals used for bonding



Thus orthoboric acid contains triangular  $\text{BO}_3^{3-}$  units. In the solid the  $\text{B}(\text{OH})_3$  units are hydrogen bonded together into two-dimensional sheets with almost hexagonal symmetry (See Figure 12.3). The layers are quite a large distance apart ( $3.18 \text{ \AA}$ ), and thus the crystal breaks quite easily into very fine particles. At one time orthoboric acid was used as a mildly antiseptic talcum powder for babies, because it forms a fine powder. It is no longer used since it sometimes caused a rash.

The orthoborates contain discrete  $\text{BO}_3^{3-}$  ions, and examples include




Figure 12.3 Hydrogen bonded structure of orthoboric acid.

$\text{Mg}_3(\text{BO}_3)_2$  and the lanthanide orthoborates  $\text{Ln}^{\text{III}}\text{BO}_3$ . In the metaborates simple units ( $\text{BO}_3$  planar triangular units or  $\text{BO}_4$  tetrahedra) join together to form a variety of polymeric chain and ring structures (see Figure 12.4).


Thus two triangular units join by sharing one corner in  $\text{Mg}_2[\text{B}_2\text{O}_5]$  and  $\text{Co}^{\text{II}}[\text{B}_2\text{O}_5]$ . These are called pyroborates by analogy with pyrophosphates. Three triangular units share corners and form a ring in sodium and potassium metaborates  $\text{NaBO}_2$  and  $\text{KBO}_2$  (Figure 12.4b) which are better written  $\text{Na}_3[\text{B}_3\text{O}_6]$  and  $\text{K}_3[\text{B}_3\text{O}_6]$ . Many triangular units may polymerize into an infinite chain, e.g. as calcium metaborate  $[\text{Ca}(\text{BO}_2)_2]_n$  (Figure 12.4a).

In a similar way discrete tetrahedral units are found in  $\text{Na}_2[\text{B}(\text{OH})_4]\text{Cl}$  and  $\text{Ta}^{\text{V}}\text{BO}_4$ . Two tetrahedra may join by sharing one corner, as in  $\text{Mg}[(\text{HO})_3\text{B} \cdot \text{O} \cdot \text{B}(\text{OH})_3]$ . Other structures form rings, chains, sheets and three-dimensional polymers.

Some interesting structures including both triangular and tetrahedral units are formed when polymerization occurs. The spiro compound  $\text{K}[\text{B}_5\text{O}_6(\text{OH})_4]$  (Figure 12.4c) contains one tetrahedral unit and four triangular units. Borax is usually written as  $\text{Na}_2\text{B}_4\text{O}_7 \cdot 10\text{H}_2\text{O}$  but is actually made from two tetrahedra and two triangular units joined as shown (Figure 12.4d) and should be written  $\text{Na}_2[\text{B}_4\text{O}_5(\text{OH})_4] \cdot 8\text{H}_2\text{O}$ .

### Borax

The most common metaborate is borax  $\text{Na}_2[\text{B}_4\text{O}_5(\text{OH})_4] \cdot 8\text{H}_2\text{O}$ . It is a useful primary standard for titrating against acids.




**Figure 12.4** Structures of some borates (a) Metaborate chain  $[\text{Ca}(\text{BO}_2)_2]_n$  made up of triangular  $\text{BO}_3$  units (b) Metaborate ring  $\text{K}_3[\text{B}_3\text{O}_6]$  made up of triangular  $\text{BO}_3$  units (c) Complex metaborate  $\text{K}[\text{B}_5\text{O}_6(\text{OH})_4]$  called the spiro anion is made up of four triangular  $\text{BO}_3$  units and one tetrahedral  $\text{BO}_4$  unit (d) Borax ( $\text{Na}_2[\text{B}_4\text{O}_5(\text{OH})_4] \cdot 8\text{H}_2\text{O}$ ) is made up of two triangular and two tetrahedral units. This ion is  $[\text{B}_4\text{O}_5(\text{OH})_4]^{2-}$ , and the other water molecules are associated with the metal ions.




One of the products  $\text{H}_3\text{BO}_3$  is itself a weak acid. Thus the indicator used to detect the end point of this reaction must be one that is unaffected by  $\text{H}_3\text{BO}_3$ . Methyl orange is normally used, which changes in the pH range 3.1–4.4.

One mole of borax reacts with two moles of acid. This is because when borax is dissolved in water both  $\text{B}(\text{OH})_3$  and  $[\text{B}(\text{OH})_4]^-$  are formed, but only the  $[\text{B}(\text{OH})_4]^-$  reacts with  $\text{HCl}$ .



Large amounts of sodium peroxoborate are produced, and world production is about 550 000 tonnes/year. There are two main preparative methods:

- $$\underset{\text{sodium metaborate}}{2\text{NaBO}_2} + 2\text{H}_2\text{O}_2 + 6\text{H}_2\text{O} \rightarrow \underset{\text{sodium peroxoborate}}{\text{Na}_2[(\text{OH})_2\text{B}(\text{O}-\text{O})_2\text{B}(\text{OH})_2]} \cdot 6\text{H}_2\text{O}$$



1. B often forms triangular  $\text{BO}_3$  units. Sometimes these remain monomeric, but they may form polynuclear ions by sharing the O atoms at corners. This links the triangular units together into chains, rings and two-dimensional flat sheet-like structures
2. B sometimes forms tetrahedral  $\text{BO}_4$  units. More complex polynuclear borates contain both triangular  $\text{BO}_3$  units and tetrahedral  $\text{BO}_4$  units linked together by sharing corners. These structures are not flat.


- 3 Hydrated borates may accept protons. These are added in the following order: (i)  $O^{2-}$  ions are converted to  $OH^-$ , (ii) tetrahedral O are protonated, (iii) the O in planar triangles are protonated and (iv) any free  $OH^-$  groups are converted to  $H_2O$ .
- 4 Hydrated borates may polymerize by eliminating  $H_2O$ . This may be followed by breaking or rearranging B—O bonds.
- 5  $H_3BO_3$  often exists in the presence of more complex polyanions.

These polymeric borate structures tend to break up when dissolved in water.


In contrast, the structures of phosphates and silicates are always based on tetrahedral  $PO_4$  and  $SiO_4$  units. The tetrahedra may polymerize into chains, rings and three-dimensional structures. These structures are rather more stable and do not break up in solution.

### Qualitative analysis of boron compounds

When borates are treated with HF (or with concentrated  $H_2SO_4$  and  $CaF_2$ ) the volatile compound  $BF_3$  is formed. If the  $BF_3$  gas produced is introduced into a flame (for example a Bunsen flame) the flame gives a characteristic green coloration.




An alternative test is to make the ester methyl borate  $B(OCH_3)_3$ . The suspected borate sample is mixed with concentrated  $H_2SO_4$  to form  $H_3BO_3$ , and warmed with methyl alcohol in a small evaporating basin.



The concentrated  $H_2SO_4$  removes the water formed. The mixture is then set on fire. Methyl borate is volatile, and colours the flame green.

### Fluoboric acid

$H_3BO_3$  dissolves in aqueous HF, forming fluoboric acid  $HBF_4$ .



Fluoboric acid is a strong acid, and commercial solutions contain 40% acid. The  $[BF_4]^-$  ion is tetrahedral and fluoborates resemble perchlorates  $ClO_4^-$  and sulphates in crystal structure and solubility ( $KClO_4$  and  $KBF_4$  are both not very soluble in water). The  $[BF_4]^-$  and  $[ClO_4]^-$  ions have a very low tendency to form complexes in aqueous solution, though a few complexes are formed in non-aqueous media.


### Borides

There are over 200 binary compounds between metals and boron. There are many different stoichiometries. The most common are  $M_2B$ ,  $MB$ .

$\text{MB}_2$ ,  $\text{MB}_4$  and  $\text{MB}_6$ , though formulae as diverse as  $\text{M}_5\text{B}$  and  $\text{MB}_{66}$  are known. Some of the compounds are nonstoichiometric. The formulae of some of the compounds cannot be rationalized by the application of simple valency rules, and are best explained by multi-centre bonding.

They may be prepared by heating the metal with boron, and by a variety of other methods. The metal-rich borides are mostly with transition metals. They are hard, and have very high melting points:  $\text{ZrB}_2$ ,  $\text{HfB}_2$ ,  $\text{NbB}_2$  and  $\text{TaB}_2$  all melt over  $3000^\circ\text{C}$ . The melting points and the electrical conductivities are often higher than for the parent metals. Thus  $\text{TiB}_2$  conducts five times as well as Ti metal. Borides are often chemically inert, and they have several uses:

1. Boron carbide is commonly written as  $\text{B}_4\text{C}$ . It is produced in quantities of tonnes by reducing  $\text{B}_2\text{O}_3$  with C at  $1600^\circ\text{C}$ . It is a useful source of B, and is also used as an abrasive for polishing. It is used in brake linings for cars. Fibres of  $\text{B}_4\text{C}$  have an enormous tensile strength, and are used to make bullet-proof clothing. These fibres are made as follows:



Boron carbide should be written  $\text{B}_{13}\text{C}_2$ , but its composition varies and may approach  $\text{B}_{12}\text{C}_3$ . The structure comprises a series of  $\text{B}_{12}$  icosahedra. Each icosahedron is linked to six others through either four B—C—B linkages and two B—B linkages, or through six B—C—B linkages. The structure is a cluster compound, and can only be explained by multi-centre bonding.

2. Powder fabrication techniques are used to fabricate parts such as turbine blades and rocket nozzles from powdered borides such as  $\text{CrB}_2$ ,  $\text{TiB}_2$ , and  $\text{ZrB}_2$ .
3. Boron steel is used in the nuclear industry for shielding and for control rods in reactors because  $^{10}\text{B}$  has a very high absorption cross-section for thermal neutrons.

## THE OTHER GROUP 13 OXIDES

Alumina  $\text{Al}_2\text{O}_3$  exists principally in two crystalline forms called  $\alpha\text{-Al}_2\text{O}_3$  or corundum, and  $\gamma\text{-Al}_2\text{O}_3$ , and in addition there is a fibrous form which is made commercially.

Corundum is found as a mineral, and  $\alpha\text{-Al}_2\text{O}_3$  is also made by heating  $\text{Al}(\text{OH})_3$  or  $\gamma\text{-Al}_2\text{O}_3$  above  $1000^\circ\text{C}$ . Corundum is extremely hard (9 on Moh's scale) and is used as 'jewellers' rouge' to polish glass. (See Appendix N). An impure form of corundum, contaminated with iron oxide and silica, is called emery. This is used to make emery paper ('sandpaper' used to polish metals). Corundum is unaffected by acids. It has a high melting point of over  $2000^\circ\text{C}$ . It is used as a refractory to line furnaces and to make containers for high temperature reactions. The crystal structure of corundum is hexagonally close-packed oxygen atoms, with two thirds of the octahedral holes filled by  $\text{Al}^{3+}$  ions.



$\gamma$   $\text{Al}_2\text{O}_3$  is made by dehydrating  $\text{Al}(\text{OH})_3$  below  $450^\circ\text{C}$  and in contrast to  $\alpha$   $\text{Al}_2\text{O}_3$  it dissolves in acids absorbs water and is used for chromatography

Fibrous  $\text{Al}_2\text{O}_3$  is made commercially by ICI and Du Pont. Fibres of  $\text{Al}_2\text{O}_3$  and  $(\text{ZrO}_2)$  are sold under the trade name *Saffil*. These fibres feel like silk are 2–5 cm in length and are 1/20th the diameter of a human hair. The fibres are hollow and are flexible though they have a high tensile strength. In addition they are chemically inert and withstand prolonged heating up to  $1400^\circ\text{C}$ . The fibres can be woven into ropes or fabric and are also used for making chemically inert paper and a support for catalysts. Fibres are also used to strengthen certain metals (Mg, Al and Pb) for example Al reinforced by 50% fibre is five times stiffer than pure Al. Fibres also have excellent thermal and electrical insulating properties.

Alumina is white but it can be coloured by the addition of  $\text{Cr}_2\text{O}_3$  or  $\text{Fe}_2\text{O}_3$ . White sapphires are gem quality corundum. Synthetic rubies can be made by strongly heating a mixture of  $\text{Al}_2\text{O}_3$  and  $\text{Cr}_2\text{O}_3$  for example in an oxy hydrogen flame. Rubies are very hard and are used for jewellery and to make bearings in watches and instruments. Thus ruby is a mixed oxide. Blue sapphires are another mixed oxide containing traces of  $\text{Fe}^{2+}$ ,  $\text{Fe}^{3+}$  and  $\text{Ti}^{4+}$ . The mineral spinel  $\text{MgAl}_2\text{O}_4$  is another mixed oxide. It gives its name to the structure adopted by many  $\text{M}^{\text{II}}\text{M}^{\text{III}}\text{O}_4$  compounds.

Aluminium has a very strong affinity for oxygen. The enthalpy of formation of  $\text{Al}_2\text{O}_3$  is  $-1670 \text{ kJ mol}^{-1}$ , higher (more negative) than for practically all other metal oxides. Thus Al may be used in the thermite reduction of less stable metal oxides.




### Qualitative analysis of aluminium

In qualitative analysis  $\text{Al}(\text{OH})_3$  is precipitated as a white gelatinous substance when  $\text{NH}_4\text{OH}$  is added to the solution (after previously removing acid insoluble sulphides with  $\text{H}_2\text{S}$ ).  $\text{Fe}(\text{OH})_3$ ,  $\text{Cr}(\text{OH})_3$  and  $\text{Zn}(\text{OH})_2$  are also precipitated but  $\text{Fe}(\text{OH})_3$  is brown,  $\text{Cr}(\text{OH})_3$  grey-green or grey-blue,  $\text{Zn}(\text{OH})_2$  is white like  $\text{Al}(\text{OH})_3$  but it is not gelatinous.  $\text{Zn}(\text{OH})_2$  dissolves in excess  $\text{NH}_4\text{OH}$  whereas  $\text{Al}(\text{OH})_3$  does not. A confirmatory test for aluminium is the formation of a red precipitate from  $\text{Al}(\text{OH})_3$  and the dye aluminon.

### Amphoteric behaviour – aluminates

$\text{Al}(\text{OH})_3$  is amphoteric. It reacts principally as a base i.e. it reacts with acids to form salts that contain the  $[\text{Al}(\text{H}_2\text{O})_6]^{3+}$  ion. However  $\text{Al}(\text{OH})_3$  shows some acidic properties when it dissolves in  $\text{NaOH}$  forming sodium aluminate. (However,  $\text{Al}(\text{OH})_3$  is reprecipitated by the addition of carbon dioxide showing that the acidic properties are very weak.)



The formula of aluminates is often written as  $\text{NaAlO}_2 \cdot 2\text{H}_2\text{O}$  (which is equivalent to  $[\text{Al(OH)}_4]^-$ ). Raman spectra suggest that the structure of the aluminate ion is more complicated than this implies, and the structure changes with both pH and concentration:


1. Between pH 8 and 12 the ions polymerize using OH bridges and each aluminium is octahedrally coordinated.
2. In dilute solutions above pH values of 13, a tetrahedral  $[\text{Al(OH)}_4]^-$  ion exists.
3. In concentrated solutions above 1.5 M and at pH values greater than 13 the ion exists as a dimer:  $[(\text{HO})_3\text{Al}-\text{O}-\text{Al(OH)}_3]^{2-}$

$\text{Ga}_2\text{O}_3$  and  $\text{Ga(OH)}_3$  are both amphoteric like the corresponding Al compounds.  $\text{Ga(OH)}_3$  is white and gelatinous and dissolves in alkali, forming gallates.  $\text{Tl}_2\text{O}_3$  and  $\text{In}_2\text{O}_3$  are completely basic, and form neither hydrates nor hydroxides. In contrast, thallos hydroxide  $\text{TlOH}$  is a strong base, and is soluble in water. Thus  $\text{TlOH}$  differs from the trivalent hydroxides and resembles the Group 1 hydroxides. Where an element can exist in more than one valency state, there is a general tendency for the lowest valency state to be the most basic.


Thallium(III) acetate and trifluoroacetate can be made by dissolving the oxide in the appropriate acid. They are used in the synthesis of organo-metallic thallium compounds.

## TETRAHYDRIDOBORATES (BOROHYDRIDES)

Stable complexes containing the group  $[\text{BH}_4]^-$  are well known. These should be called tetrahydridoborates, though the old name borohydride is still widely used. The tetrahydridoborate ion  $[\text{BH}_4]^-$  is tetrahedral, and the sodium salt  $\text{Na}[\text{BH}_4]$  is the most important compound. It is usually prepared from trimethylborate. It is ionic, and has a sodium chloride structure.




Other tetrahydridoborates are made by treating  $\text{Na}[\text{BH}_4]$  with the appropriate metal chloride. The alkali metal tetrahydridoborates are white ionic solids and react with water with varying ease. Thus  $\text{Li}[\text{BH}_4]$  reacts violently with water, but  $\text{Na}[\text{BH}_4]$  may be recrystallized from cold water with only slight decomposition, and  $\text{K}[\text{BH}_4]$  is quite stable.



The alkali metal tetrahydridoborates are valuable reducing agents in both inorganic and organic chemistry.  $\text{Na}[\text{BH}_4]$  is stable in alcoholic and

aqueous solutions. This makes it a useful reagent for reducing aldehydes to primary alcohols, and ketones to secondary alcohols. It is a nucleophilic reagent, and attacks sites of low electron density. Thus other functional groups such as  $C=C$ ,  $COOH$  and  $NO_2$  are not normally attacked.



Not all tetrahydridoborates are ionic. The beryllium, aluminium and transition metal borohydrides become increasingly covalent and volatile. In these the  $[BH_4]^-$  group acts as a ligand and forms covalent compounds with metal ions. One or more H atoms in a  $[BH_4]^-$  act as a bridge and bond to the metal, forming a three-centre bond with two electrons shared by three atoms. The  $[BH_4]^-$  ligand is unusual in that it may form one, two or three such three-centre bonds to the metal ion. Thus  $Be(BH_4)_2$ ,  $Al(BH_4)_3$  and  $Zr(BH_4)_4$  are covalent, and react strongly with water. In the Al and Zr compounds, each  $BH_4^-$  forms two hydrogen bridges, whilst in the Be compound two of the three  $BH_4^-$  form three hydrogen bridges.





Figure 12.5 Structures of  $Al(BH_4)_3$  and  $Be(BH_4)_2$  (After H. J. Emeléus and A. G. Sharpe *Modern Aspects of Inorganic Chemistry*, 4th ed., 1973, Routledge and Kegan Paul.)

The other elements in the group also form electron-deficient hydrides.  $(AlH_3)_n$  is a white involatile solid. It is a reducing agent and reacts violently with water. It is extensively polymerised by 3-centre hydrogen bridges similar to those in diborane. (The structure of  $\alpha$ - $AlH_3$  is known and each Al participates in six bridges.) Aluminium hydride is best made from  $Li[AlH_4]$  and  $AlCl_3$ . It can be made from  $LiH$  and  $AlCl_3$  in either solution, but with excess  $LiH$  lithium aluminium hydride  $Li[AlH_4]$  is formed instead.





$\text{Li}[\text{AlH}_4]$  is a most useful organic reducing agent because it will reduce functional groups, but in general it does not attack double bonds. It is analogous to the borohydrides but cannot be used in aqueous solutions.

Gallium forms compounds analogous to the borohydrides, e.g.  $\text{Li}[\text{GaH}_4]$ . Indium forms a polymeric hydride  $(\text{InH}_3)_n$ , but there is some doubt about the existence of a hydride of thallium.


## TRIHALIDES

All the elements form trihalides. The boron halides are covalent.  $\text{BF}_3$  is gaseous,  $\text{BCl}_3$  liquid and  $\text{BI}_3$  is solid.  $\text{BF}_3$  is by far the most important. It is a colourless gas, boiling point  $-101^\circ\text{C}$ , and is made in large quantities:



Both  $\text{BF}_3$  gas and its complex with diethyl ether  $(\text{C}_2\text{H}_5)_2\text{O} \rightarrow \text{BF}_3$  (a viscous liquid) are commercially available.

The shape of the  $\text{BF}_3$  molecule is a planar triangle with bond angles of  $120^\circ$ . This is predicted by VSEPR theory as the most stable shape for three outer electron pairs round B. The valence bond theory also predicts a planar triangle with hybridization of one  $s$  and two  $p$  orbitals used for bonding. However, the B atom only has six electrons in its outer shell and this is termed *electron deficient*.



The bond lengths in  $\text{BF}_3$  are  $1.30 \text{ \AA}$ , and are significantly shorter than the sum of the covalent radii ( $\text{B} = 0.80 \text{ \AA}$ ,  $\text{F} = 0.72 \text{ \AA}$ ). The bond energy is very high:  $646 \text{ kJ mol}^{-1}$ , which is higher than for any single bond. The shortness and strength of the bonds is interpreted in terms of a  $p\pi-p\pi$  interaction, that is the bonds possess some double bond character. The empty  $2p_z$  atomic orbital on B which is not involved in hybridization is perpendicular to the triangle containing the  $sp^2$  hybrid orbitals. This  $p_z$  orbital may accept an electron pair from a full  $p_z$  orbital on any one of the three fluorine atoms. Thus a dative  $\pi$  bond is formed, and the B atom attains an octet of electrons. If one localized double bond existed, then

there would be one short bond and two longer ones. However, all measurements show that the three bond lengths are identical. The old valence bond explanation of this was resonance between three structures with the double bond in different positions. The modern explanation is that the double bond is delocalized. The four  $p_z$  atomic orbitals from B and the three F atoms form a four-centre  $\pi$  molecular orbital covering all four atoms which contains two bonding electrons. Delocalized  $\pi$  bonding is described more fully in Chapter 4.





Figure 12.6 Structure of  $\text{BF}_3$

The empty  $2p_z$  orbital on the boron atom in  $\text{BF}_3$  can also be filled by a lone pair of electrons from donor molecules such as  $\text{Et}_2\text{O}$ ,  $\text{NH}_3$ ,  $(\text{CH}_3)_3\text{N}$  or by ions such as  $\text{F}^-$ . When this occurs, a tetrahedral molecule or ion is formed.




Once a tetrahedral complex has been formed, the possibility for  $\pi$  bonding no longer exists. In  $\text{H}_3\text{N} \rightarrow \text{BF}_3$  the B—F distance is  $1.38 \text{ \AA}$ , and in  $\text{Me}_3\text{N} \rightarrow \text{BF}_3$  the distance is  $1.39 \text{ \AA}$ , much longer than the  $1.30 \text{ \AA}$  in  $\text{BF}_3$ . Since the boron halides will accept electron pairs from numerous atoms and ions such as  $\text{F}^-$ , O, N, P and S, they are acting as strong Lewis acids.

The trihalides are important industrial chemicals, particularly  $\text{BF}_3$ , and to a lesser extent  $\text{BCl}_3$ . They are used to prepare elemental boron. They are also very useful for promoting certain organic reactions. In some cases  $\text{BF}_3$  is used up in the reaction, and in others it acts as a catalyst by forming a  $\text{BF}_3$  complex with one or both reactants. Forming an 'intermediate compound' in this way lowers the activation energy. Examples include

- 1 Friedel-Crafts reactions such as alkylations and acylations. In these the  $\text{BF}_3$  is used up in the reaction, and so is not strictly catalytic.





- 2 It acts as a catalyst in several reactions




3. Considerable quantities of  $\text{BF}_3$  are also used as a polymerization catalyst in the production of polyisobutenes (used to make viscostatic lubricating oils), coumarone-indene resins, and butadiene-styrene rubbers.


About 4000 tonnes a year of  $\text{BF}_3$  are produced in the USA from  $\text{B}_2\text{O}_3$  or borax:



The boron halides are all hydrolysed by water.  $\text{BF}_3$  hydrolyses incompletely and forms fluoborates. This is because the HF first formed reacts with the  $\text{H}_3\text{BO}_3$ .



The other halides hydrolyse completely, giving boric acid.



The fluorides of Al, Ga, In and Tl are ionic and have high melting points. The other halides are largely covalent when anhydrous.  $\text{AlCl}_3$ ,  $\text{AlBr}_3$  and  $\text{GaCl}_3$  exist as dimers, thus attaining an octet of electrons. The dimeric formula is retained when the halides dissolve in non-polar solvents such as benzene. However, when the halides dissolve in water, the high enthalpy of hydration is sufficient to break the covalent dimer into  $[\text{M} \cdot 6\text{H}_2\text{O}]^{3+}$  and  $3\text{X}^-$  ions. At low temperatures  $\text{AlCl}_3$  exists as a close packed lattice of  $\text{Cl}^-$  with  $\text{Al}^{3+}$  occupying octahedral holes. On heating  $\text{Al}_2\text{Cl}_6$  species are formed and the volume of the solid greatly increases. This illustrates how close the bonding in this compound is to the ionic/covalent border.

Group 13 elements have only three valency electrons. When these are used to form three covalent bonds, the atom has a share in only six electrons. The compounds are therefore electron deficient. The  $\text{BX}_3$  halides attain an octet by  $\pi$  bonding. The other elements in the group have larger atoms and cannot get effective  $\pi$  overlap, so they polymerize to remedy the electron deficiency.

$\text{AlCl}_3$  is an important industrial chemical. Production is about 25 000 tonnes/year in the USA alone. Anhydrous  $\text{AlCl}_3$  (and to a lesser extent  $\text{AlBr}_3$ ) is used as the 'catalyst' in a variety of Friedel-Crafts type of reactions for alkylations and acylations. Large amounts of ethylbenzene are made in this way and are used to make styrene. (Polystyrene production was 8.2 million tonnes in 1991.)









Figure 12.7 Structure of  $\text{Al}_2\text{Cl}_6$  dimer.




(a)  $B_4Cl_4$ (b)  $B_5Cl_9$ (c)  $B_9Cl_9$ 


◊ B

○ Cl


Figure 12.8 Boron monochloride structures  $(BCl)_n$  showing polyhedral boron cages (After A G Missey *The Typical Elements* Penguin 1972)



This is not true 'catalytic' action, as the  $AlCl_3$  is used up, and the formation of  $[AlCl_4]^-$  or  $[AlBr_4]^-$  is an essential part of the reaction. Acylations are similar



$AlCl_3$  is also used to catalyse the reaction to make ethyl bromide (which is used to make the petrol additive  $PbEt_4$ )




$AlCl_3$  is also used in the manufacture of anthraquinone (used in the dyestuffs industry), and dodecylbenzene (used to make detergents), and in the isomerization of hydrocarbons (petroleum industry)


$TlI_3$  is an unusual compound. It is isomorphous with  $CsI_3$  and  $NH_4I_3$ , and contains the linear triiodide ion  $I_3^-$ . Thus the metal is present as  $Tl^+$ , in the oxidation state (+I) not (+III)

## DIHALIDES

Boron forms halides of formula  $B_2X_4$ . These decompose slowly at room temperature.  $B_2Cl_4$  can be made as follows



There is free rotation about the B—B bond and in the gaseous and liquid states the molecule adopts a non eclipsed conformation. In the solid state the molecule is planar because of crystal forces and ease of packing. Gallium and indium also form 'dihalides' see diagram on page 387




g.s.

These are more properly written  $Ga^+[GaCl_4]^-$  and  $In^+[InCl_4]^-$  and contain M(I) and M(III) rather than Ga(II) and In(II)

## MONOHALIDES


Boron forms several stable polymeric monohalides  $(BX)_n$



The compounds  $B_2Cl_4$ ,  $B_xCl_x$  and  $B_4Cl_4$  are crystalline solids and their

structures (Figure 12.8) have a closed cage or polyhedron of B atoms, where each B atom is bonded to three other B atoms and to one Cl atom. Since B has only three valency electrons there are not enough electrons to form normal electron pair bonds. It is probable that multi-centre  $\sigma$  bonds cover all the B atoms in the cage.

Al, Ga and In all form monohalides MX in the gas phase at elevated temperatures, e.g.




These compounds are not very stable, and are covalent.


Thallium forms univalent thallos halides which are more stable than the thallium trihalides. This illustrates the inert pair effect, and TlF is ionic.

## COMPLEXES


Group 13 elements form complexes much more readily than the s-block elements, because of their smaller size and increased charge. Tetrahedral hydride and halide complexes such as  $\text{Li}[\text{AlH}_4]$  and  $\text{H}[\text{BF}_4]$  have already been mentioned. In addition many octahedral complexes such as  $[\text{GaCl}_6]^{3-}$ ,  $[\text{InCl}_6]^{3-}$  and  $[\text{TlCl}_6]^{3-}$  are known. The most important octahedral complexes are those with chelate groups, for example  $\beta$ -diketones such as acetylacetone, oxalate ions, dicarboxylic acids, pyrocatechol, and also 8-hydroxyquinoline. (See Figure 12.9.) The latter complex has been used in the gravimetric determination of aluminium.



acetylacetonate complex



oxalate complex



8-hydroxyquinoline complex

Figure 12.9 Some complexes

## DIFFERENCES BETWEEN BORON AND THE OTHER ELEMENTS

Boron differs significantly from the other elements in Group 13, mainly because the atoms are very small. It is always covalent, and it is non-metallic. In addition, boron shows a diagonal relationship with silicon in Group 14.

1.  $\text{B}_2\text{O}_3$  is an acidic oxide; like  $\text{SiO}_2$ . This is in contrast to  $\text{Al}_2\text{O}_3$ , which is amphoteric.
2.  $\text{H}_3\text{BO}_3$ , which may be written  $\text{B}(\text{OH})_3$ , is acidic, whilst  $\text{Al}(\text{OH})_3$  is amphoteric.
3. Simple borates and silicate ions can polymerize, forming isopolyacids. Both are built on similar structural principles, namely by sharing oxygen atoms. Complicated chains, rings, sheets and other structures are formed in this way. Aluminium forms no analogous compounds.
4. The hydrides of B are gaseous, readily hydrolysed and spontaneously inflammable. In contrast aluminium hydride is a polymeric solid  $(\text{AlH}_3)_n$ .  $\text{SiH}_4$  is gaseous, readily hydrolysed and inflammable.
5. Apart from  $\text{BF}_3$ , the halides of B and Si hydrolyse readily and vigorously. The aluminium halides are only partly hydrolysed in water.



## BORON HYDRIDES

## Compounds known

None of the Group 13 elements react directly with hydrogen but several interesting hydrides are known. The boron hydrides are sometimes called boranes by analogy with the alkanes (hydrocarbons). Almost 20 boranes have been reported, and 11 are well characterized. They fall into two series.

- 1  $B_nH_{(n+4)}$  (called *nido* boranes)
- 2 A less stable series  $B_nH_{(n+6)}$  (called *arachno* boranes)

In cases where the nomenclature is ambiguous, as for example for penta-borane, it is usual to include the number of hydrogen atoms in the name.



Table 12.10 The two series of boranes

<i>Nido</i> boranes $B_nH_{(n+4)}$	m.p. (°C)	b.p. (°C)	<i>Arachno</i> boranes $B_nH_{(n+6)}$	m.p. (°C)	b.p. (°C)
$B_2H_6$ diborane	-165	-93	$B_4H_{10}$ tetraborane	-120	18
$B_5H_9$ pentaborane 9	-47	60	$B_5H_{11}$ pentaborane 11	-122	65
$B_6H_{10}$ hexaborane 10	-62	108	$B_6H_{12}$ hexaborane 12	-82	
$B_8H_{12}$ octaborane 12	dec		$B_8H_{14}$ octaborane 14	dec	
			$B_9H_{15}$ (nonaborane or enneaborane)	3	
$B_{10}H_{14}$ decaborane	-100	213			

dec = decomposes


## Preparation

Diborane is the simplest and most studied of the hydrides. It is used to prepare the higher boranes, and is an important reagent in synthetic organic chemistry. For the latter purpose it is normally generated *in situ*. It is a versatile reagent for the production of organoboranes which are useful intermediates in organic synthesis. Alternatively diborane is used as a powerful electrophilic reducing agent for certain functional groups. It attacks sites with a high electron density such as N in cyanides and nitrites and O in carbonyl compounds.





Diborane may be prepared by a variety of methods. Boranes were first prepared by Alfred Stock, who pioneered this branch of chemistry.

between 1912 and 1936. He heated Mg and B to give magnesium boride  $\text{Mg}_3\text{B}_2$ , and then treated this with orthophosphoric acid. The reaction gives a mixture of products. There were enormous difficulties with this early work because the compounds were highly reactive, flammable, and hydrolysed by water. Stock developed vacuum line techniques, which were previously unknown, to handle these reactive compounds. This preparative method has now been superseded except for making  $\text{B}_6\text{H}_{10}$ .




Many other methods have been used:




There are several convenient laboratory preparations:


1. Reducing the etherate complexes of the boron halides with  $\text{Li}[\text{AlH}_4]$ .



2. Reacting  $\text{Na}[\text{BH}_4]$  and iodine in the solvent diglyme. Diglyme is a polyether  $\text{CH}_3\text{OCH}_2\text{CH}_2\text{OCH}_2\text{CH}_2\text{OCH}_3$ .




3. Reducing  $\text{BF}_3$  with  $\text{Na}[\text{BH}_4]$  in diglyme.



Method (3) is particularly useful when diborane is required as a reaction intermediary. It is produced in situ, and used without the need to isolate or purify it.


Diborane is a colourless gas, and must be handled with care as it is highly reactive. It catches fire spontaneously in air and explodes with dioxygen. The heat of combustion is very high. In the laboratory it is handled in a vacuum frame. Since it reacts with the grease used to lubricate taps, special taps must be used. It is instantly hydrolysed by water, or aqueous alkali. At red heat the boranes decompose to boron and hydrogen.




Most syntheses of higher boranes involve heating  $\text{B}_2\text{H}_6$ , sometimes with hydrogen. A complex reaction occurs when  $\text{B}_2\text{H}_6$  is heated in a sealed

tube Various higher boranes are formed ( $B_4H_{10}$ ,  $B_5H_{11}$ ,  $B_6H_{12}$  and  $B_{10}H_{14}$ ) The  $B_2H_6$  molecule probably breaks into the very reactive intermediate  $\{BH_3\}$  which has only a transient existence and reacts with  $B_2H_6$ , giving another intermediate  $\{B_3H_9\}$  This loses hydrogen forming  $\{B_3H_7\}$ , which reacts with more  $\{BH_3\}$  to give  $B_4H_{10}$  In a similar way a variety of higher boranes are formed depending on the exact conditions For example


(5 h at 80–90 °C, 200 atmospheres)



(rapid at 200–250 °C)



(slow pyrolysis in sealed tube 150 °C)




Most of the higher boranes are liquids, but  $B_6H_{10}$  and  $B_{10}H_{14}$  are solids As the molecular weight increases, they gradually become more stable in air, and less sensitive to water  $B_{10}H_{14}$  is inert in air and can be recovered from aqueous solutions At one time the boranes were considered as possible high energy rocket fuels The aim was to replace hydrocarbon fuels in military aircraft and missiles Over a tonne of  $B_{10}H_{14}$  was made for this purpose Interest in this use disappeared when it was found that combustion to  $B_2O_3$  was incomplete Because of this the exhaust nozzles of the rocket became partly blocked with an involatile BO polymer

## REACTIONS OF THE BORANES

### Hydroboration


A very important reaction occurs between  $B_2H_6$  (or  $BF_3 + NaBH_4$ ) and alkenes and alkynes







The reactions are carried out in dry ether under an atmosphere of dinitrogen because  $B_2H_6$  and the products are very reactive The alkylborane products  $BR_3$  are not usually isolated They may be converted as follows

- 1 to hydrocarbons by treatment with carboxylic acids,
- 2 to alcohols by reaction with alkaline  $H_2O_2$ , or
- 3 to either ketones or carboxylic acids by oxidation with chromic acid

The complete process is called hydroboration, and results in *cis* hydrogenation, or *cis* hydration Where the organic molecule is not symmetrical, the reaction follows the anti Markovnikov rule, that is B attaches to the least substituted C atom









Hydroboration is a simple and useful process for two main reasons:

1. The mild conditions required for the initial hydride addition.
2. The variety of products which can be produced using different reagents to break the B—C bond.

H.C. Brown won the Nobel Prize for Chemistry in 1979 for work on these organoboron compounds.

### Reaction with ammonia

All the boranes act as Lewis acids and can accept electron pairs. Thus they react with amines, forming simple adducts. They also react with ammonia, but the products depend on the conditions:



The compound  $\text{B}_2\text{H}_6 \cdot 2\text{NH}_3$  is ionic, and comprises  $[\text{H}_3\text{N} \rightarrow \text{BH}_2 \leftarrow \text{NH}_3]^+$  and  $[\text{BH}_4]^-$  ions. On heating, it forms borazine.

Boron nitride is a white slippery solid. One B atom and one N atom together have the same number of valency electrons as two C atoms. Thus boron nitride has almost the same structure as graphite, with sheets made up of hexagonal rings of alternate B and N atoms joined together. The sheets are stacked one on top of the other, giving a layer structure (Figure 12.10).






Figure 12.10 Similarity in structure between (a) boron nitride and graphite, (b) borazine and benzene.

Borazine B<sub>3</sub>N<sub>3</sub>H<sub>6</sub> is sometimes called 'inorganic benzene' because its structure shows some formal similarity with benzene, with delocalized electrons and aromatic character. Their physical properties are also similar.

Borazine and substituted borazines are now made:










Borazine forms  $\pi$  complexes such as B<sub>3</sub>N<sub>3</sub>H<sub>6</sub>—Cr(CO)<sub>3</sub> with transition metal compounds. Borazine is considerably more reactive than benzene, and addition reactions occur quite readily:



If heated with water, borazine hydrolyses slowly.



Some other reactions of boranes



## STRUCTURES OF THE BORANES

The bonding and structures of the boranes are of great interest. They are different from all other hydrides. There are not enough valency electrons to form conventional two-electron bonds between all of the adjacent pairs of atoms, and so these compounds are termed electron deficient.

In diborane there are 12 valency electrons, three from each B atom and six from the H atoms. Electron diffraction results indicate the structure shown in Figure 12.11.

The two bridging H atoms are in a plane perpendicular to the rest of the molecule and prevent rotation between the two B atoms. Specific heat measurements confirm that rotation is hindered. Four of the H atoms are in a different environment from the other two. This is confirmed by Raman spectra and by the fact that diborane cannot be methylated beyond  $\text{Me}_4\text{B}_2\text{H}_2$  without breaking the molecule into  $\text{BMe}_3$ .

The terminal B—H distances are the same as the bond lengths measured in non-electron-deficient compounds. These are assumed to be normal covalent bonds, with two electrons shared between two atoms. We can describe these bonds as two-centre two-electron bonds (2c-2e).

Thus the electron deficiency must be associated with the bridge groups. The nature of the bonds in the hydrogen bridges is now well established. Obviously they are abnormal bonds as the two bridges involve only one electron from each boron atom and one from each hydrogen atom, making a total of four electrons. An  $sp^3$  hybrid orbital from each boron atom overlaps with the 1s orbital of the hydrogen. This gives a delocalized molecular orbital covering all three nuclei, containing one pair of electrons and making up one of the bridges (see Figure 12.12). This is a three-centre two-electron bond (3c-2e). A second three-centre bond is also formed.




Figure 12.11 The structure of diborane.




Figure 12.12 Overlap of approximately  $sp^2$  hybrid orbitals from B with an  $s$  orbital from H to give a 'banana-shaped' three-centre two-electron bond.

The higher boranes have an open cage structure (Figure 12.13). Both normal and multi-centre bonds are required to explain these structures:

1. Terminal B—H bonds. These are normal covalent bonds, that is two-centre two-electron (2c-2e) bonds.
2. B—B bonds. These are also normal 2c-2e bonds.





Figure 12.13 Structures of some boranes (a) Diborane  $B_2H_6$ , with two three-centre B...H...B bonds. (b) Tetraborane  $B_4H_{10}$ , with four three-centre B...H...B bonds and one B—B bond. (c) Pentaborane-9  $B_5H_9$ , where the boron atoms form a square-based pyramid with four three-centre B...H...B bonds, and multi-centre bonds from the apical B atom to the four B atoms in the square. (d) Pentaborane-11  $B_5H_{11}$ , where the boron atoms form a distorted square-based pyramid, with three three-centre B...H...B bonds and three-centre B...B...B bonds in two of the triangular faces. (e) Decaborane-14. (After A. G. Massey, *The Typical Elements*, Penguin, 1972.)


3. Three-centre bridge bonds including B...H...B as in diborane. These are 3c-2e bonds.
4. Three-centre bridge bonds including B...B...B, similar to the hydrogen bridge in (3). These are called 'open boron bridge bonds', and are of the type 3c-2e.
5. Closed 3c-2e bonds between three B atoms.



Decaborane-14 has ten B atoms. This number is two short of being able to form a regular icosahedron. An icosahedron has 12 corners and 20 faces. It is a closed cage structure, and is particularly stable. The two extra atoms required to complete the cage may be added by reacting  $B_{10}H_{14}$  with an ethyne, forming a carborane (Figure 12.14).




Alternatively two B atoms may be added to complete the cage by reacting  $B_{10}H_{14}$  with  $Me_3N \rightarrow BH_3$ .



## ORGANOMETALLIC COMPOUNDS

Besides the carboranes and the alkylboranes discussed earlier, all the Group 13 trihalides will react with Grignard reagents and organolithium reagents, forming trialkyl or triaryl compounds:




The aluminium compounds are unusual because they have dimeric structures, and appear to have three-centre bonds involving  $sp^3$  hybrid orbitals on Al and C in Al—C—Al bridges (Figure 2.15).


Another important route to organoaluminium compounds is from aluminium metal and  $H_2$ . The two elements do not react directly to give  $AlH_3$ . However, aluminium does take up hydrogen in the presence of aluminium alkyl catalysts (Ziegler catalysts).



Alkenes may be added to Al—H bonds.




**Figure 12.14** Structure of orthocarborane, one of the isomeric forms of the icosahed carborane  $B_{10}C_2H_{10}R_2$ . (After A.G. Massey, *The Typical Elements*, Penguin, 1972.)



**Figure 12.15** Structure of aluminium trimethyl dimer.




At 90–120°C and 100 atmospheres pressure, ethene molecules are slowly inserted into the Al—C bonds



Long chains up to  $\text{C}_{200}$  may be grown. Hydrolysis of these longish-chain aluminium alkyls gives straight chain hydrocarbons called polyethylene or polythene. Formed in this way these are low molecular weight polymers (or oligomers), and are of no commercial use. If a transition metal catalyst such as  $\text{TiCl}_4$  (Natta catalyst) is used then polymerization is much quicker. Furthermore the reaction does not require a high pressure and a much higher molecular weight polymer is produced. These high molecular weight polymers are very important as one route to commercial polythene (see Chapter 20 under 'Organometallic compounds').

Alcohols with chain lengths of about  $\text{C}_{14}$  are produced from ethene by growing suitable aluminium alkyls, oxidizing with air and then hydrolysing with water. Reaction of these alcohols with  $\text{SO}_3$  gives sulphonates  $\text{R}-\text{SO}_3\text{H}$  which are then neutralized to make biodegradable detergents  $\text{CH}_3-(\text{CH}_2)_n-\text{OSO}_3^- \text{Na}^+$  (Detergents are discussed in Group 16 under  $\text{SO}_3$ ).

Aluminium alkyls catalyse the dimerization of propene in the formation of isoprene



The use of aluminium alkyls in producing alcohols and isoprene is of considerable industrial importance. (Commercial polythene is made in two ways, either using titanium catalysts or by a peroxide-induced free radical polymerization, rather than with aluminium alkyls.)

### FURTHER READING

- Borax Review* (1987) Borax Holdings Ltd  
 Brown H C (1972) *Boranes in Organic Chemistry* Cornell University Press  
 Brown, H C (1975) *Organic Synthesis via Boranes* Wiley New York  
 Brown H C (1979) Hydride reductions. A 40-year revolution in organic chemistry *Chem Eng News* March 5 24–29  
 Callahan K P and Hawthorn M F (1976) Ten years of metallocarboranes *Adv Organometallic Chem*, 14 145–186  
 Christ C L and Clark J R (1977) A crystal classification of borate structures with emphasis on hydrated borates *Phys Chem Minerals* 2 59

- Greenwood, N.N. (1963) The chemistry of gallium, *Adv. Inorg. Chem. Radiochem.*, **5**, 91.
- Greenwood, N.N. (1973) *Comprehensive Inorganic Chemistry*, Vol. I (Chapter 11: Boron), Pergamon Press, Oxford.
- Greenwood, N.N. (1975) *Boron*, Pergamon Press, Oxford and Elmsford, NY.
- Greenwood, N.N. (1977) The synthesis, structure and chemical reactions of metalloboranes, *Pure Appl. Chem.*, **49**, 791–802.
- Greenwood, N.N. and Ward, I.M. (1974) Metalloboranes and metal–boron bonding, *Chem Soc. Rev.*, **3**, 231–271.
- Grimes, R.N. (1971) *Carboranes*, Academic Press, New York.
- Grimes, R.N. (ed.) (1982) *Metal Interactions with Boron Clusters* (Modern Inorganic Chemistry Series), Plenum Publishing Corp., London.
- Grimes, R.N. (1983) Carbon-rich carboranes and their metal derivatives, *Adv. Inorg. Chem. Radiochem.*, **26**, 55–118.
- Haupin, W.E. (1983) Electrochemistry of the Hall–Heroult process for aluminium *J. Chem. Ed.*, **60**, 279–282.
- Iversen, S. (1988) The chemistry of dementia, *Chemistry in Britain*, **24**, 338–342, 364. (Effects of aluminium in the body.)
- James, B.D. and Wallbridge, M.G.H. (1970) Metal tetrahydroborates, *Progr. Inorg. Chem.*, **11**, 97–231. (A comprehensive review with over 600 references.)
- Johnson, B.G.F. (ed.) (1980) *Transition Metal Clusters*, Wiley, New York. (Chapters by various leading workers in this field.)
- Johnson, B.G.F. and Lewis, J. (1981) *Adv. Inorg. Chem. Radiochem.*, **24**, 225. (A good review of cluster compounds.)
- Kennedy, J.D. (1984, 1986) The Polyhedral Metalloboranes, Parts I and II, *Progr. Inorg. Chem.*, **32**, 519–679; **34**, 211–434.
- Lancashire, R. (1982) Bauxite and aluminium production, *Education in Chemistry*, **19**, 74–77.
- Lee, A.G. (1971) *The Chemistry of Thallium*, Elsevier, Amsterdam.
- Lee, A.G. (1972) Coordination chemistry of thallium(I), *Coordination Chem. Rev.*, **8**, 289.
- Liebman, J.F., Greenberg, A. and Williams, R.E. (eds) (1988) *Avances in Boron and the Boranes*, VCH, New York.
- Massey, A.G., Boron subhalides (1980) *Chemistry in Britain*, **16**, 588–598.
- Massey, A.G. (1983) The sub-halides of boron, *Adv. Inorg. Chem. Radiochem.*, **26**, 1–54.
- Massey, R.C. (1989) *Aluminium in Food and the Environment* (Special Publication No. 73), Royal Society of Chemistry, London.
- Muetterties, E.L. (ed.) (1975) *Boron Hydride Chemistry*, Academic Press, New York.
- Sanderson, R.T. (1997) More on complex hydrides, *Chem. Eng. News*, **29**, 3. (Li[AlH<sub>4</sub>] etc.)
- Stinson, S.C. (1980) Hydride reducing agents, use expanding, *Chem. Eng. News*, Nov 3, 18–20.
- Thompson, R. (ed.) (1981) *Speciality Inorganic Chemicals* (Chapter by Wade, K., Sodium borohydride and its uses, Royal Society for Chemistry, London, 1981.
- Thompson, R. (ed.) (1986) *The Modern Inorganic Chemicals Industry* (Chapter by Thompson, R., Production and Uses of Inorganic Boron Compounds, (Special Publication No. 31), The Chemical Society, London.
- Wade, K. and Bannister, A.J. (1973) *Comprehensive Inorganic Chemistry*, Vol. I (Chapter 12: Aluminium, gallium, indium and thallium), Pergamon Press, Oxford.
- Wade, K. (1976) Structural and bonding patterns in cluster chemistry, *Adv. Inorg. Chem. Radiochem.*, **18**, 1–66.
- Wade, K. (1971) *Electron Deficient Compounds*, Nelson, London.

- Walton R A (1971) Coordination complexes of the thallium(III) halides and their behaviour in non aqueous media *Coordination Chem Rev* 6 1-25
- Wiberg E and Amberger E (1971) *Hydrides of the Elements of Main Groups I-IV* (Chapters 5 and 6) Elsevier Amsterdam

### PROBLEMS

- 1 The first element in each of the main groups in the periodic table shows anomalous properties when compared with other members of the same group. Discuss this statement with particular reference to the elements Li, Be and B.
- 2 What is the main source of boron? Outline the steps in the extraction of boron.
- 3 Draw the structure of the  $B_{12}$  unit found in the solid structure of boron. What is this shape called?
- 4 (a) List features which make borax a useful primary standard and give a balanced equation to show its use in titrations.  
(b) Work out the shape of the  $BO_3^{3-}$  ion and explain why it has this structure.
- 5 Orthoboric acid may be written as  $H_3BO_3$  or  $B(OH)_3$ . How does it ionize in water and which way of writing the formula is the most helpful? How strong an acid is it? Why does glycerol enhance its acidic properties? Write a balanced equation for a neutralization reaction with boric acid.
- 6 Give an account of isopolyacids with special reference to borates.
- 7 Give one method for the preparation of diborane,  $B_2H_6$ . Why is it called an electron deficient compound? Draw the structure of diborane and give the bond lengths. What is unusual about the bonding in this compound?
- 8 How does diborane react with (a) ammonia, (b) boron tribromide and (c) trimethylboron?
- 9 Describe the use of diborane in hydroboration.
- 10 Give the preparation, structure and uses of sodium borohydride.
- 11 Compare the structures of  $BF_3$  gas,  $AlCl_3$  gas and  $AlCl_3$  in aqueous solution.
- 12 Explain the following:  
(a)  $BF_3$  has no dipole moment but  $PF_3$  has a substantial dipole.  
(b)  $BF_3$  and  $BrF_3$  molecules have different shapes.
- 13 Describe the preparation and give the structures of the dihalides of B, Ga and In.
- 14 What is the principal ore of aluminium? How is the ore purified and

how is the metal extracted? What is the process called? What is the function of cryolite in the process? What is aluminium used for?

15. From the position of Al in the electrochemical series, would you expect it to be stable in water? Why is it stable in air and water?
16. Give equations to show the reactions between Al and: (a)  $H_{(aq)}^+$ , (b) NaOH, (c)  $N_2$ , (d)  $O_2$ , (e)  $Cl_2$ .
17. Give two examples of alums. What species are present when these materials dissolve in water?
18. How is aluminium chloride prepared? What is its structure when anhydrous and when dissolved in water? Give an example of the use of  $AlCl_3$  as a Friedel–Crafts catalyst.
19. How would you prepare LiH and  $LiAlH_4$ . What are they used for?
20. Give two different preparations for  $Et_3Al$  and describe its use as a catalyst for polymerizing  $C_2H_4$ . Compare the products formed with those described in the section on titanium in Chapter 20.
21. Compare and contrast the chemistry of boron and aluminium.
22. Give reasons for trivalency and monovalency in Group 13 elements, and comment on the validity of divalent compounds such as  $GaCl_2$ .
23. Write notes on the chemistry of thallium in the (+I) oxidation state.
24. Substance (A) is a yellowish-white deliquescent solid which sublimes and has a vapour density of 133. (A) reacted violently with water, forming solution (B). A sample of (B) gave a curdy white precipitate (C) on addition of dilute  $HNO_3$  and  $AgNO_3$  solution, but this readily dissolved on the addition of dilute  $NH_4OH$ , though a gelatinous white precipitate was formed in its place. (D) was filtered off and dissolved in excess NaOH, forming a clear solution (E). When  $CO_2$  was passed into (E), compound (D) was reprecipitated.  
Substance (A) dissolved unchanged in dry ether, and when this solution was reacted with LiH one of two products (F) or (G) was formed, depending on whether the LiH was in excess or not.  
Qualitative analysis of solution (B) gave a white gelatinous precipitate in Group III. When 0.1333 g of (A) was dissolved in water and treated with 8-hydroxyquinoline, 0.4594 g of precipitate was obtained.  
Identify the compounds (A) to (G) and give equations for all of the reactions.

Table 13.1 Electronic structures and oxidation states

Element		Electronic structure		Oxidation states*	
Carbon	C	[He]	$2s^2 2p^2$		<b>IV</b>
Silicon	Si	[Ne]	$3s^2 3p^2$	(II)	<b>IV</b>
Germanium	Ge	[Ar]	$3d^{10} 4s^2 4p^2$	II	<b>IV</b>
Tin	Sn	[Kr]	$4d^{10} 5s^2 5p^2$	II	<b>IV</b>
Lead	Pb	[Xe]	$4f^{14} 5d^{10} 6s^2 6p^2$	II	<b>IV</b>

\* The most important oxidation states (generally the most abundant and stable) are shown in bold. Other well characterized but less important states are shown in normal type. Oxidation states that are unstable or in doubt, are given in parentheses.

## INTRODUCTION

Carbon is extremely widespread in nature. It is an essential constituent of all living matter, as proteins, carbohydrates and fats. Carbon dioxide is essential in photosynthesis, and is evolved in respiration. Organic chemistry is devoted to the chemistry of carbon containing compounds. Inorganic compounds produced on a large scale include carbon black, coke, graphite, carbonates, carbon dioxide, carbon monoxide (as a fuel gas), urea, calcium carbide, calcium cyanamide and carbon disulphide. There is great interest in organometallic compounds, carbonyls and  $\pi$  bonding complexes.

The discovery that flint (hydrated  $\text{SiO}_2$ ) had a sharp cutting edge was very important in the development of human technology. Nowadays silicon is important in a number of materials produced in high tonnages. These include cement, ceramics, clays, bricks, glass and the silicone polymers. The very pure element is important in the microelectronics industries (transistors and computer chips).

Germanium is little known, but tin and lead are very well known and have been used as metals since before Biblical times. Lead sheet was used on the floor in the Hanging Gardens of Babylon (one of the wonders of the ancient world) to prevent the water escaping.

## OCCURRENCE OF THE ELEMENTS

The elements are all well known, apart from germanium. Carbon is the seventeenth, and silicon the second most abundant element by weight in the earth's crust (Table 13.2). Germanium minerals are very rare. Ge occurs as traces in the ores of other metals and in coal, but it is not well known. Both Si and Ge are important for making semiconductors and transistors. Though the abundances of tin and lead are comparatively low, they occur as concentrated ores which are easy to extract, and both metals have been well known since before Biblical times.

Carbon occurs in large quantities combined with other elements and compounds mainly as coal, crude oil, and carbonates in rocks such as calcite  $\text{CaCO}_3$  and magnesite  $\text{MgCO}_3$  and dolomite  $[\text{MgCO}_3 \cdot \text{CaCO}_3]$ .

Table 13.2 Abundance of the elements in the earth's crust by weight

	ppm	Relative abundance
C	180	17
Si	272 000	2
Ge	1.5	54
Sn	2.1	49 =
Pb	13	36

Carbon is also found in the native form: large amounts of graphite are mined, and extremely small quantities (in tonnage terms) of diamonds are mined too! Both  $\text{CO}_2$  and CO are important industrially.  $\text{CO}_2$  occurs in small amounts in the atmosphere, but this is important as  $\text{CO}_2$  has a vital role in the carbon cycle with photosynthesis and respiration. CO is an important fuel, and forms some interesting carbonyl complexes. Silicon occurs very widely, as silica  $\text{SiO}_2$  (sand and quartz), and in a wide variety of silicate minerals and clays. Germanium is only found as traces in some silver and zinc ores, and in some types of coal. Tin is mined as cassiterite  $\text{SnO}_2$ , and lead is found as the ore galena  $\text{PbS}$ .

## EXTRACTION AND USES OF THE ELEMENTS

### Carbon


Carbon black (soot) is produced in large amounts (4.5 million tonnes in 1991). It is made by the incomplete combustion of hydrocarbons from natural gas or oil. The particle size is very small. Over 90% is used in the rubber industry to make car tyres. Its other main use is in newspaper ink.

Coke is produced in very large amounts (390 million tonnes in 1991). Three hundred and thirty-nine million tonnes were produced by high temperature carbonization of coal, in which coal is heated in large ovens in the absence of air. Fifty-one million tonnes were produced by distilling heavier petroleum oils. Coke is extremely important in the metallurgical

*continued overleaf*

extraction of iron and many other metals. The distillation of coal also provides a valuable source of organic chemicals.

In 1992, 930 000 tonnes of natural graphite were mined (China 59%, South Korea 17%, the Soviet Union 7% and India 5%). This is usually found as a mixture with mica, quartz and silicates, which contains 10–60% C. Graphite is separated from most of the impurities by flotation. Finally it is purified by heating with HCl and HF in a vacuum to remove the last traces of silicon compounds as  $\text{SiF}_4$ . Sedimentary deposits of carbon are mined in Mexico. This was once thought to be amorphous carbon, but is now regarded as microcrystalline (very finely divided) graphite. Nearly as much graphite is made synthetically as is mined.



Graphite is used for making electrodes in steel making and metal foundries, for crucibles as a lubricant, and in pencils, brake linings and brushes for electric motors. It is also used as the moderator in the cores of gas-cooled nuclear reactors, where it slows down neutrons.

Activated charcoal is made by heating or chemically oxidizing sawdust or peat. World production was 864 200 tonnes in 1991. Active carbon has an enormous surface area, and is used to purify and decolorize sugar and other chemicals. It is also used to absorb poisonous gases in gas masks, in filter beds at sewage plants and as a catalyst for some reactions.

The largest sources of diamonds are Australia 41%, Botswana 16%, Zaire 14%, the Soviet Union 11%, and South Africa 10%. World production of natural diamonds was 98 400 000 carats or 19.68 tonnes in 1992. Large diamonds are cut as gemstones, and their size is measured in carats (1 g = 5 carats). About 30% are used as gemstones, and 70% are used for industrial purposes, mainly for making drills or as an abrasive powder for cutting and polishing, as diamond is very hard (10 on Mohs' scale) – see Appendix N. It is economic to make small industrial quality diamonds synthetically, by high temperature and pressure treatment of graphite.




### Silicon

More than a million tonnes of Si are produced annually. Most of it is added to steel to deoxidize it. This is important in the manufacture of high silicon corrosion resistant steels. For this purpose it is convenient to use ferro-silicon. This is an alloy of Fe and Si. In 1991, 3.5 million tonnes of ferro-silicon were produced. It is made by reducing  $\text{SiO}_2$  and scrap iron with coke.




The element Si is obtained by reducing  $\text{SiO}_2$  with high purity coke. There must be an excess of  $\text{SiO}_2$  to prevent the formation of the carbide  $\text{SiC}$ . Si is a shiny blue-grey colour and has an almost metal-like lustre, but it is a semiconductor, not a metal. High purity Si (for the semiconductor

industry) is made by converting Si to  $\text{SiCl}_4$ , purifying this by distillation, and reducing the chloride with Mg or Zn.



The electronics industry requires small quantities of ultrapure silicon and germanium (with a purity better than  $1 : 10^9$ ). These materials are insulators when pure, but become *p*-type or *n*-type semiconductors when doped with a Group 15 or Group 13 element respectively. These are used as transistors and semiconductor devices. Very pure Si is also used to make computer chips (see Chapter 3 under 'Micro-minaturised semiconductor devices'). To obtain ultrapure Si or Ge, the materials are first purified as much as possible, for example by careful fractional distillation of  $\text{SiCl}_4$  to get pure Si. For the final stage of purification a process called zone refining is used. This is an excellent method for small quantities. A rod of the element, which has already been purified extensively, is placed in a long quartz tube filled with an inert gas. A heating coil melts a thin disc of the rod. The heater moves slowly from one end to the other, and pure Si or metal crystallizes from the melt. The impurities are more soluble in the liquid, and are carried to the end of the rod, where they are cut off and discarded. Semiconductor quality Si can also be made by sodium reduction of  $\text{Na}_2[\text{SiF}_6]$ , which is a by-product from making phosphate fertilizers from fluoroapatite.



### Germanium

Ge has been recovered from coal ash, but it is now recovered from the flue dust from smelting Zn ores. A number of steps are required in the recovery of Ge from flue dust to concentrate and purify it. These give pure  $\text{GeO}_2$  which is reduced by  $\text{H}_2$  to Ge at  $500^\circ\text{C}$ . Transistor grade (ultrapure) material is obtained by zone refining. World production was about 50 tonnes in 1993 (20% of it from the USA). It is used mainly for making transistors and semiconductor devices. It is transparent to infra-red light and is therefore also used for making prisms and lenses and windows in infra-red spectrophotometers and scientific apparatus.

### Tin

The only important ore is cassiterite  $\text{SnO}_2$ . Mine production was 177 000 tonnes (metal content) in 1992. The main supplies now come from China 25%, Indonesia 17%, and Brazil 15%. In the UK, tin was mined in Cornwall from Roman times until this century, but these mines are now uneconomic.

$\text{SnO}_2$  is reduced to the metal using carbon at  $1200\text{--}1300^\circ\text{C}$  in an electric

*continued overleaf*




furnace. The product often contains traces of Fe, which make the metal hard. Fe is removed by blowing air through the molten mixture to oxidize the iron to FeO, which then floats to the surface.

The main uses of Sn are electroplating steel to make tin-plate, and making alloys. Tin-plate is extensively used for making cans for food and drinks. The most important alloy is solder (Sn/Pb), but there are many others, including bronze (Cu/Sn), gun metal (Cu/Sn/Pb/Zn) and pewter (Sn/Sb/Cu). SnO<sub>2</sub> is used as a glaze in ceramics, and is often mixed with other metal oxides as pigments for pottery. SnCl<sub>4</sub> and Me<sub>2</sub>SnCl<sub>2</sub> are used to produce very thin films of SnO<sub>2</sub> on glass. This toughens the glass, so bottles can be made with thinner walls and glass can be made scratch resistant (useful for spectacles). Slightly thicker films are put on glass windows, to reduce heat losses. The film allows visible light to pass through, but reflects IR radiation, and thus keeps heat inside a room. A film of SnO<sub>2</sub> is put onto aircraft windows. This conducts electricity and thus produces heat, and prevents the window from frosting up. Large amounts of organotin compounds are used (estimated to be over 40 000 tonnes/year). Compounds R<sub>2</sub>SnX<sub>2</sub> (where R is an alkyl group such as n-octyl and X is an organic acid residue such as laurate) are used to stabilize halogenated plastics such as PVC. Without a stabilizer, the plastic degrades in sunlight, air or on heating and becomes brittle and discoloured. The butyl compound Bu<sub>2</sub>SnX<sub>2</sub> is used to 'cure' or vulcanize silicone rubber at room temperature. Inorganic tin compounds are used as flame retardants and smoke suppressants. Triorgano compounds such as Bu<sub>3</sub>SnOH or Ph<sub>3</sub>SnOAc are extensively used in agriculture to control fungi such as potato blight (*Botrytis infestans*) and similar fungal attack of vines, rice and sugar beet. Similar compounds kill red spider mites which attack fruit crops such as apples and pears, and other insects and larvae. They are also used to preserve wood. They make very effective and long lasting antifouling paint for boats, preventing the build-up of barnacles. This use has now been banned because the heavy metal Sn seems to have entered the food chain.

### Lead


The main ore is galena PbS. This is black, shiny and very dense. The main sources are the USSR 17%, Australia 14%, the USA 10%, Canada 9%, and Peru, Mexico and China 6% each. Galena is mined and separated from other minerals by froth flotation. There are two methods of extracting the element.

1. Roast in air to give PbO and then reduce with coke or CO in a blast furnace.



2. PbS is partially oxidized by heating and blowing air through it. After

some time the air is turned off and heating is continued, and the mixture undergoes self-reduction.




The metal contains a number of metallic impurities: Cu, Ag, Au, Sn, As, Sb, Bi and Zn. These are removed by cooling to near the freezing point of Pb, when first Cu and then Zn containing most of the Ag and Au solidify. Preferential oxidation converts As, Sb and Sn to  $\text{As}_2\text{O}_3$ ,  $\text{Sb}_2\text{O}_3$ , and  $\text{SnO}_2$  which float on the surface of the molten metal and may be skimmed off. World production of Pb was 5.3 million tonnes in 1992. Of this, 3.1 million tonnes was primary production from PbS. The main sources of ores are Australia 19%, the USA 13%, Canada 11% and China 10%. The recycling of scrap lead yielded 2.2 million tonnes. About 55% of the Pb produced is used to make lead/acid storage batteries. More than 158 million car batteries were produced in 1985. In these the supporting grid for the electrodes is made of an alloy of 91% Pb and 9% Sb. The active anode material is  $\text{PbO}_2$ , and the cathode material is spongy Pb. Over 80% of 'battery lead' is recovered from worn-out batteries and recycled. About 15% of lead production is used for lead sheets, lead pipes and solder. The manufacture of  $\text{PbEt}_4$  as an additive to petrol at one time used 10–20%, but this is declining rapidly. About 10% is used in paints and pigments. Red lead paint containing  $\text{Pb}_3\text{O}_4$  is used for rustproofing metal and white lead  $(\text{PbCO}_3)_2 \cdot \text{Pb}(\text{OH})_2$  was at one time widely used as an opacifier in paint. Their use has declined because lead is toxic, and  $\text{TiO}_2$  is a good alternative opacifier. Calcium plumbate  $\text{Ca}_2\text{PbO}_4$  is used for rustproofing corrugated steel sheets, and  $\text{PbCrO}_4$  is used as a strong yellow pigment for road signs and markings. Lead compounds are also included in crown glass and cut glass, and in ceramic glazes.

## STRUCTURE AND ALLOTROPY OF THE ELEMENTS

Carbon exists in a large number of allotropic forms. These include diamond,  $\alpha$ - and  $\beta$ -graphite, a rare hexagonal form of diamond, and a variety of discrete molecules such as  $\text{C}_{60}$ , which are really clusters of carbon atoms, and are called collectively fullerenes.

Si, Ge and Sn also have a diamond type of structure, though Sn exists as a metallic form. Pb exists only in the metallic form. Ge is unusual because the liquid expands when it forms the solid. This property is unique to Ga, Ge and Bi.



Diamond is extremely unreactive, and in contrast graphite is quite reactive.

Diamonds are typically colourless, though industrial diamonds are often black. Most naturally occurring diamonds contain a trace of nitrogen, but 'blue diamonds' contain a trace of Al instead. In diamond each C atom is tetrahedrally surrounded by four other C atoms, each at a distance of  $1.54 \text{ \AA}$ . The tetrahedra are linked together into a three-dimensional giant molecule. The unit cell is cubic. Strong covalent bonds extend in all directions. Thus the melting point is abnormally high (about  $3930^\circ\text{C}$ ) and the structure is very hard (see Figure 13.1). (In a rare modification of diamond, the tetrahedra are arranged differently to give a wurtzite like structure and a hexagonal unit cell.)




Figure 13.1 The crystal structure of diamond (Wells, A F, *Structural Inorganic Chemistry*, Clarendon Press, Oxford)




Figure 13.2 (a) The structure of a graphite sheet (b) Structure of  $\alpha$  graphite

Graphite is composed of flat two-dimensional sheets of carbon atoms. Each sheet is a hexagonal net of C atoms, and may be regarded as a fused system of benzene rings (Figure 13.2). The layers are held together by relatively weak van der Waals forces. In  $\alpha$ -graphite the layers are arranged in the sequence ABAB... with the third layer exactly above the first layer. In  $\beta$  graphite the order of layers is ABCABC... The two forms are interconvertible. Heating turns  $\beta$  into  $\alpha$ , and grinding turns  $\alpha$  into  $\beta$ . In both forms the C—C bond lengths within a sheet are  $1.41 \text{ \AA}$  (similar to the C—C distance of  $1.40 \text{ \AA}$  in benzene). The distance between layers is  $3.35 \text{ \AA}$ . This interlayer distance is large – appreciably more than twice the covalent radius of carbon ( $2 \times 1.54 \text{ \AA} = 3.08 \text{ \AA}$ ). Thus bonding between layers is weak. Graphite cleaves easily between the layers, which accounts for the remarkable softness of the crystals ( $>1$  on Mohs' scale). (See Appendix N for Mohs' scale.) Graphite is used as a lubricant, either on its own or in graphited oil. In contrast, diamond is hard (10 on Mohs' scale) and has abrasive properties. The wide spacing of sheets in graphite also means that the atoms do not pack together to fill space very effectively. Thus the density of graphite ( $2.22 \text{ g cm}^{-3}$ ) is lower than that of diamond ( $3.51 \text{ g cm}^{-3}$ ).

In graphite only three of the valency electrons of each carbon atom are involved in forming  $\sigma$  bonds (using  $sp^2$  hybrid orbitals). The fourth

electron forms a  $\pi$  bond. The  $\pi$  electrons are delocalized over the whole sheet, and as they are mobile, graphite conducts electricity. Conduction can occur in a sheet, but not from one sheet to another.

Graphite is thermodynamically more stable than diamond, and its free energy of formation is  $1.9 \text{ kJ mol}^{-1}$  lower at room temperature and ordinary pressure. Thermodynamically it is favourable for diamonds to turn into graphite. They do not normally do so because there is a high energy of activation for the process. If this activation energy is available, the change does occur, and diamond tipped drills do burn out and form graphite if they get too hot. The reverse process is not thermodynamically possible, and it requires very forcing high energy conditions to convert graphite to diamond. Graphite can be converted to synthetic diamonds at  $1600^\circ\text{C}$  by a pressure of 50 000–60 000 atmospheres.

When an electric spark is struck between graphite electrodes, soot is produced. (An atmosphere of argon is required to prevent the formation of  $\text{CO}_2$  and  $\text{CO}$ .) This soot is mainly carbon black, but contains significant amounts of a  $\text{C}_{60}$  carbon cluster compound sometimes called buckminster fullerene. Smaller amounts of other similar fullerenes  $\text{C}_{32}$ ,  $\text{C}_{50}$ ,  $\text{C}_{70}$ ,  $\text{C}_{76}$  and  $\text{C}_{84}$  may also be produced. The fullerenes are easily extracted from the soot by dissolving them in benzene or hydrocarbon solvents, giving a wine red solution and finally mustard-coloured crystals. The different compounds are separated chromatographically.

This isomer of carbon differs from diamond and graphite (which form lattices), in that the fullerenes form discrete molecules. The  $\text{C}_{60}$  molecule looks rather like a soccer ball, and is sometimes called 'a bucky ball'. It consists of a fused system of five- and six-membered rings (Figure 13.3). Fullerenes are covalent; hence their solubility in organic solvents. However, they can easily be reduced electrochemically, and react with Group 1 metals, forming solids such as  $\text{K}_3\text{C}_{60}$ . This compound behaves as a superconductor below 18 K, which means that it carries an electric current with zero resistance.  $\text{C}_{60}$  reacts with  $\text{OsO}_4$ , which adds across one of the double bonds in the cage. It also forms platinum complexes.




Figure 13.3 Structure of buckminster fullerene.

## DIFFERENCES BETWEEN CARBON, SILICON AND THE REMAINING ELEMENTS

In general, the first element in a group differs from the rest of the group because of its smaller size and higher electronegativity. These result in the first element having a higher ionization energy, being more covalent, and being less metallic.

Using the classical theory of bonding, the first atom is limited to forming a maximum of four covalent bonds, because only  $s$  and  $p$  orbitals are available for bonding. This would limit the coordination number to 4 in these compounds. The majority of carbon compounds are either three- or four-coordinate. However, multi-centre bonds are now well established, and a number of compounds are known where carbon has higher coordination numbers, as shown in Table 13.3.

Table 13.3 Some carbon compounds with higher coordination numbers

Compound	Coordination number
$\text{Al}_2(\text{CH}_3)_6$	5
$\text{B}_{10}\text{C}_2\text{H}_{12}\text{R}_2$	6
$\text{Li}_4(\text{CH}_3)_4$	7
$[\text{Co}_3\text{C}(\text{CO})_{18}]^2$	8

In addition carbon differs from the other elements in its unique ability to form  $p\pi-p\pi$  multiple bonds such as  $\text{C}=\text{C}$ ,  $\text{C}\equiv\text{C}$ ,  $\text{C}=\text{O}$ ,  $\text{C}=\text{S}$  and  $\text{C}\equiv\text{N}$ . The later elements do not form  $p\pi-p\pi$  bonds principally because the atomic orbitals are too large and diffuse to obtain effective overlap but they can use  $d$  orbitals in multiple bonding, particularly between Si and N or O. Thus  $\text{N}(\text{SiH}_3)_3$  is planar and has  $p\pi-d\pi$  bonding but  $\text{N}(\text{CH}_3)_3$  is pyramidal and has no  $\pi$  bonding (see Figure 13.18).

Carbon also differs from the others in its marked ability to form chains (catenation). This is because the C—C bonds are very strong and the bonds Si—Si, Ge—Ge and Sn—Sn decrease progressively in strength (Table 13.4).


Table 13.4 Bond energies

Bond	Bond energy (kJ mol <sup>-1</sup> )	Remarks
C—C	348	Forms many chains of great length
Si—Si	297	Forms a few chains up to $\text{Si}_{18}\text{H}_{18}$ in hydrides and $\text{Si}_{16}\text{F}_{34}$ , $\text{Si}_6\text{Cl}_{14}$ , $\text{Si}_4\text{Br}_{10}$ with halogens
Ge—Ge	260	Forms a few chains up to $\text{Ge}_6\text{H}_{14}$ in hydrides and $\text{Ge}_2\text{Cl}_6$ with Cl
Sn—Sn	240	Forms dimer $\text{Sn}_2\text{H}_6$ in hydrides

Carbon and silicon have only  $s$  and  $p$  electrons but the other elements follow a completed transition series with ten  $d$  electrons. Thus some differences are expected and carbon and silicon differ both from one another and from the rest of the group while germanium, tin and lead form a graded series.

### CARBON DATING

The technique of carbon dating can be used to measure the age of archeological objects. Carbon occurs largely as the isotope  $^{12}\text{C}$  but there is a small amount of  $^{13}\text{C}$  which leads to the average atomic weight of 12.011. In the atmosphere, dinitrogen is bombarded by cosmic neutrons, which produces the isotope  $^{14}\text{C}$ .



This carbon reacts with dioxygen, forming  $\text{CO}_2$ , which is eventually used by green plants in photosynthesis to make glucose sugar. The glucose may be used by the plant to build starch, proteins, cellulose and other materials in the plant. All plant tissues thus contain traces of  $^{14}\text{C}$ . Animals eat plants, so they too contain traces of  $^{14}\text{C}$ . This isotope of carbon is weakly radioactive. It undergoes  $\beta$ -decay, and has a half life of 5668 years. While the plant or animal is alive, a natural balance exists between the intake of radiocarbon and that lost by decay. This steady state gives  $15.3 \pm 0.1$  disintegrations per minute per gram of carbon. When the plant or animal dies the intake of radiocarbon ceases, but  $\beta$ -decay continues. Thus a very old sample of wood, cloth, paper, leather etc. will be less radioactive than a recent sample. A very small sample is burnt in dioxygen, and the  $\text{CO}_2$  produced is introduced into a suitable radiation counter. By carefully measuring the present radioactive decay rate, it is possible to calculate how long ago the plant or animal died. This provides an absolute scale for dating objects of plant or animal origin between 1000 and 10 000 years old. The technique has recently been used to determine the age of the Turin shroud, and many other objects. W.F. Libby was awarded the Nobel Prize for Chemistry in 1960 for developing this technique.

## PHYSICAL PROPERTIES

### Covalent radii

The covalent radii increase down the group. The difference in size between Si and Ge is less than might be otherwise expected because Ge has a full 3d shell which shields the nuclear charge rather ineffectively. In a similar way the small difference in size between Sn and Pb is because of the filling of the 4f shell.

Table 13.5 Radii, melting points and electronegativity values

	Covalent radius (Å)	Ionization energies (kJ mol <sup>-1</sup> )				Melting point (°C)	Boiling point (°C)	Pauling's electro- negativity values
		1st	2nd	3rd	4th			
C	0.77	1086	2354	4622	6223	4100		2.5
Si	1.17	786	1573	3232	4351	1420	3280	1.8
Ge	1.22	760	1534	3300	4409	945	2850	1.8
Sn	1.40	707	1409	2943	3821	232	2623	1.8
Pb	1.46	715	1447	3087	4081	327	1751	1.8

### Ionization energy

The ionization energies decrease from C to Si, but then change in an irregular way because of the effects of filling the *d* and *f* shells. The amount

of energy required to form  $M^{4+}$  ions is extremely large and hence simple ionic compounds are rare. The only elements which will give a large enough electronegativity difference to give ionic character are F and O. The compounds  $SnF_2$ ,  $PbF_2$ ,  $SnF_4$ ,  $PbF_4$ ,  $SnO_2$ , and  $PbO_2$  are significantly ionic, but the only significant metal ion is  $Pb^{2+}$ .

### Melting points

C has an extremely high melting point. Si melts appreciably lower than C, but the values for Si and Ge are still high. They all have the very stable diamond type of lattice. Melting involves breaking the strong covalent bonds in this lattice, and so requires a lot of energy. The melting points decrease on descending the group because the M—M bonds become weaker as the atoms increase in size (Table 13.4). Sn and Pb are metallic, and have much lower melting points. They do not use all four outer electrons for metallic bonding.


### Metallic and non-metallic character

The change from non metal to metal with increasing atomic number is well illustrated in Group 14, where C and Si are non metals, Ge has some metallic properties, and Sn and Pb are metals. The increase in metallic character shows itself in the structures and appearance of the elements, in physical properties such as malleability and electrical conductivity, and in chemical properties such as the increased tendency to form  $M^{2+}$  ions and the acidic or basic properties of the oxides and hydroxides.

### Four covalent compounds

The majority of the compounds are four covalent. In this case all four outer electrons take part in bonding. In the valence bond theory this is explained by promoting electrons from the ground state to an excited state. The energy needed to unpair and promote the electron is more than repaid by the energy released on forming two extra covalent bonds. The distribution of the four orbitals results in a tetrahedral structure, consistent with  $sp^3$  hybridization.

Electronic structure of  
carbon atom –  
ground state



two unpaired electrons thus can only  
form two covalent bonds

Carbon atom –  
excited state



four unpaired electrons thus can now form  
four covalent bonds giving a tetrahedral  
structure

## CHEMICAL REACTIVITY

The elements in this group are relatively unreactive, but reactivity increases down the group. The  $M^{II}$  oxidation state becomes increasingly stable on descending the group. Pb often appears more noble (unreactive) than expected from its standard electrode potential of  $-0.13$  volts. The unreactiveness is partly due to a surface coating of oxide, and partly due to the high overpotential for the reduction of  $H^+$  to  $H_2$  at a Pb surface. The production of  $H_2$  from  $H^+$  at a lead electrode is kinetically unfavourable, so a much larger potential is required than the standard reduction potential.

C, Si and Ge are unaffected by water. Sn reacts with steam to give  $SnO_2$  and  $H_2$ . Pb is unaffected by water, probably because of a protective oxide film.

C, Si and Ge are unaffected by dilute acids. Sn dissolves in dilute  $HNO_3$ , forming  $Sn(NO_3)_2$ . Pb dissolves slowly in dilute  $HCl$ , forming the sparingly soluble  $PbCl_2$  and quite readily in dilute  $HNO_3$ , forming  $Pb(NO_3)_2$  and oxides of nitrogen. Pb also dissolves in organic acids (e.g. acetic, citric and oxalic acids). Pb does not dissolve in dilute  $H_2SO_4$  because a surface coating of  $PbSO_4$  is formed.

Diamond is unaffected by concentrated acids, but graphite reacts with hot concentrated  $HNO_3$ , forming mellitic acid, and with a mixture of hot concentrated  $HF/HNO_3$ , forming graphite oxide. Si is oxidized and fluorinated by concentrated  $HF/HNO_3$ . Ge dissolves slowly in hot concentrated  $H_2SO_4$  and in  $HNO_3$ . Sn dissolves in several concentrated acids. Pb does not dissolve in concentrated  $HCl$  because a surface coating of  $PbCl_2$  is formed.

C is unaffected by alkalis. Si reacts slowly with cold aqueous solutions of  $NaOH$ , and readily with hot solutions, giving solutions of silicates  $[SiO_4]^{4-}$ . Sn and Pb are slowly attacked by cold alkali, and rapidly by hot alkali, giving stannates  $Na_2[Sn(OH)_6]$  and plumbates  $Na_2[Pb(OH)_6]$ . Thus Sn and Pb are amphoteric.

Diamond does not react with the halogens, but graphite reacts with  $F_2$  at  $500^\circ C$ , forming intercalation compounds or graphite fluoride  $(CF)_n$ . Si and Ge react readily with all the halogens, forming volatile halides  $SiX_4$  and  $GeX_4$ . Sn and Pb are less reactive. Sn reacts with  $Cl_2$  and  $Br_2$  in the cold, and with  $F_2$  and  $I_2$  on warming, giving  $SnX_4$ . Pb reacts with  $F_2$  in the cold, forming  $PbF_2$ , and with  $Cl_2$  on heating, giving  $PbCl_2$ .

## INERT PAIR EFFECT

The inert pair effect shows itself increasingly in the heavier members of the group. There is a decrease in stability of the (+IV) oxidation state and an increase in the stability of the (+II) state on descending the group.  $Ge(+II)$  is a strong reducing agent whereas  $Ge(+IV)$  is stable.  $Sn(+II)$  exists as simple ions which are strongly reducing but  $Sn(+IV)$  is covalent and stable.  $Pb(+II)$  is ionic, stable and more common than  $Pb(+IV)$ ,



which is oxidizing. The lower valencies are more ionic because the radius of  $M^{2+}$  is greater than that of  $M^{4+}$  and according to Fajans' rules the smaller the ion the greater the tendency to covalency.


#### STANDARD REDUCTION POTENTIALS (VOLTS)

Acid solution			Basic solution		
Oxidation state					
+IV	+II	0	+IV	+II	0
$\text{Sn}^{4+}$	$\xrightarrow{+0.15}$ $\text{Sn}^{2+}$	$\xrightarrow{+0.14}$ $\text{Sn}$	$[\text{Sn}(\text{OH})_6]^{2-}$	$\xrightarrow{+0.90}$ $\text{HSnO}_2^-$	$\xrightarrow{+0.91}$ $\text{Sn}$
$\text{PbO}_2$	$\xrightarrow{+1.46}$ $\text{Pb}^{2+}$	$\xrightarrow{+0.13}$ $\text{Pb}$	$\text{PbO}_2$	$\xrightarrow{+0.28}$ $\text{PbO}$	$\xrightarrow{+0.44}$ $\text{Pb}$

#### GRAPHITE COMPOUNDS

The distance between layers in graphite is large, hence the bonding between layers is weak. Thus a large number of substances can invade the space between sheets forming intercalation compounds of varying composition. When atoms, molecules or ions invade the space between the layers, they cause an increase in the interlayer distance. Provided that the graphite sheets remain flat, the new compound retains its graphite-like character; the  $\pi$  electrons continue to be delocalized over the whole layer and are thus able to conduct electricity. If the invading atoms add electrons to the  $\pi$  system, the electrical conductivity is increased. Reactions of this kind (i.e. intercalation reactions) are often reversible.

When graphite is heated to about  $300^\circ\text{C}$  with the vapours of the heavier Group 1 metals K, Rb and Cs, it absorbs metal, forming a bronze coloured compound  $\text{C}_x\text{M}$ . The bronze colour is due to the formation of metal atom clusters at these relatively high metal concentrations, in the same way as clusters are formed in solutions of these metals in liquid ammonia. If  $\text{C}_x\text{M}$  is heated to  $350^\circ\text{C}$  under reduced pressure, metal is lost and a series of intercalation compounds are formed ranging from steel blue to blue or black in colour, depending on the number of layers invaded by the metal (see Table 13.6).



Intercalation compounds of Li and Na are more difficult to make, but a series of compounds is known:  $\text{C}_6\text{Li}$ ,  $\text{C}_{12}\text{Li}$ ,  $\text{C}_{16}\text{Li}$ ,  $\text{C}_{18}\text{Li}$  and  $\text{C}_{40}\text{Li}$ .

The crystal structure of  $\text{C}_8\text{K}$  is known. The graphite sheets remain intact, but the gap between the sheets increases because of the presence of metal atoms. The C atoms in one sheet are arranged vertically above those

in the sheet below, rather than in the ABAB... arrangement found in  $\alpha$ -graphite. Since the sheets remain flat, they retain their delocalized  $\pi$  electron system. Thus  $C_8K$  can conduct electricity, but the electrical resistance is appreciably lower than for  $\alpha$ -graphite, i.e.  $C_8M$  conducts better than graphite (resistance at 285 K:  $\alpha$ -graphite 28.4 ohm cm;  $C_8K$  1.02 ohm cm). Graphite is diamagnetic, and  $C_8K$  is paramagnetic. This suggests that bonding between metal and graphite layers involves the transfer of an electron from the alkali metal atom to the  $\pi$  system (that is to the conduction band) of the graphite sheets ( $K \rightarrow K^+ + e$ ). The presence of the invading species forces the graphite sheets apart from their usual distance of 3.35 Å up to a distance as great as 10 Å. These alkali metal graphite compounds are highly reactive. They may explode in water, and react vigorously in air.

$FeCl_3$  reacts with graphite and forms a different type of intercalation compound. Similar behaviour is found with.

1. the halogens  $Cl_2$  and  $Br_2$ ;
2.  $HF$ ;

Table 13.6 Idealized representation of graphite compounds showing different numbers of layers invaded by metal

$C_8M$ bronze	$C_{24}M$ steel-blue	$C_{36}M$ blue	$C_{48}M$ black	$C_{60}M$ black
every layer invaded	every second layer invaded	every third layer invaded	every fourth layer invaded	every fifth layer invaded
-C	-C	-C	-C	-C
-M	-M	-M	-M	-M
-C	-C	-C	-C	-C
-M				
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M	-M	
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M	-M		
-C	-C	-C	-C	-C
-M				-C
-C	-C	-C	-C	-C
-M	-M			
-C	-C	-C	-C	-C
-M				-C</

- 3 a large number of halides including  $\text{CdCl}_2$ ,  $\text{CuBr}_2$ ,  $\text{FeCl}_3$ ,  $\text{AlCl}_3$ ,  $\text{ClF}_3$ ,  $\text{TiF}_4$ ,  $\text{MoCl}_5$ ,  $\text{SbF}_5$ ,  $\text{UCl}_6$  and  $\text{XeF}_6$ ,
- 4 a number of oxides  $\text{CrO}_3$ ,  $\text{MoO}_3$ ,  $\text{SO}_3$ ,  $\text{N}_2\text{O}_5$  and  $\text{Cl}_2\text{O}_7$ ,
- 5 and some sulphides  $\text{FeS}_2$ ,  $\text{PdS}$ ,  $\text{V}_2\text{S}_3$

Some of the invading compounds can act as electron pair acceptors. In others, for example  $\text{FeCl}_3$ , the compound  $\text{C}_6\text{FeCl}_3$  is formed in which the  $\text{FeCl}_3$  forms a layer lattice within the host lattice of graphite. This is almost the same as the layer lattice formed by  $\text{FeCl}_3$  itself. The presence of this kind of invading species increases the electrical conductivity of graphite by a factor of up to ten times. There seems to be a transfer of electrons from graphite to the invading atoms. With  $\text{Cl}_2$  and  $\text{Br}_2$  the halogen may remove bonding electrons from graphite ( $\text{Cl} + e \rightarrow \text{Cl}^-$ ) thus leaving a 'positive hole' in the valence band. The positive hole can migrate, and therefore can carry current. It is not known how conduction occurs in the halide intercalation compounds.

A third class of compounds is formed between O and F with graphite. These compounds are non conducting. Graphite oxide is formed when graphite is oxidized with strong reagents such as concentrated  $\text{HNO}_3$ ,  $\text{HClO}_4$  or  $\text{KMnO}_4$ . Graphite oxide is unstable, pale lemon coloured and nonstoichiometric. It decomposes slowly at  $70^\circ\text{C}$ , and catches fire at  $200^\circ\text{C}$ , forming  $\text{H}_2\text{O}$ ,  $\text{CO}_2$ ,  $\text{CO}$  and  $\text{C}$ . The O/C ratio approaches 1/2, but is often short of oxygen and frequently contains hydrogen. The interlayer spacing is increased to  $6\text{--}7\text{ \AA}$ . The oxide absorbs water, alcohols, acetone and a variety of molecules. This may increase the interlayer spacing up to  $19\text{ \AA}$ . X ray diffraction shows a layer structure with puckered sheets made up of a hexagonal network of atoms. The  $\text{C}_6$  units are mostly in the chair conformation, but a few  $\text{C}=\text{C}$  bonds remain. The oxygen forms bridging (ether-like) linkages  $\text{C}-\text{O}-\text{C}$  and  $\text{C}-\text{OH}$  groups which may undergo keto-enol tautomerism  $\equiv\text{C}-\text{OH}$  to  $\text{>C}=\text{O}$ . The sheets are buckled because all four electrons on a C atom are now involved in  $\sigma$  bonding. This destroys the delocalized system of mobile  $\pi$  electrons found in the flat sheets in graphite, and this explains the loss of electrical conductivity.

Graphite fluoride is formed by heating graphite in  $\text{F}_2$  at  $450^\circ\text{C}$ . The reaction proceeds at a lower temperature in the presence of  $\text{HF}$ . This can happen in cells producing  $\text{F}_2$  and not only will it destroy the electrode, but it may also cause an explosion. The product,  $\text{CF}_n$ , is nonstoichiometric, and  $n$  varies from 0.7 to 0.98. The colour varies from black through grey to silver and white with increasing fluorine content. The interlayer spacing is about  $8\text{ \AA}$ . The structure is thought to be a layer structure with buckled sheets. It involves tetrahedral bonding by C atoms.  $\text{CF}$  is non conducting, and very unreactive.

### CARBIDES

Compounds of carbon and a less electronegative element are called carbides. This excludes compounds with N, P, O, S and the halogens from this section. Carbides are of three main types

1. ionic or salt-like
2. interstitial or metallic
3. covalent


The formulae of some of the compounds cannot be rationalized by the application of simple valency rules. All three types are prepared by heating the metal or its oxide with carbon or a hydrocarbon at temperatures of 2000°C.

### Salt-like carbides


It is convenient to group these depending on whether the structure contains C, C<sub>2</sub> or C<sub>3</sub> 'anions'.

Beryllium carbide Be<sub>2</sub>C is a red solid and may be made by heating C and BeO at 2000°C. Aluminium carbide Al<sub>4</sub>C<sub>3</sub> is a pale yellow solid formed by heating the elements in an electric furnace. Be<sub>2</sub>C contains individual C atoms/ions, but the structure of Al<sub>4</sub>C<sub>3</sub> is complex. It is misleading to formulate the structure as 4Al<sup>3+</sup> and 3C<sup>4-</sup> as such a high charge separation is unlikely. Both Be<sub>2</sub>C and Al<sub>4</sub>C<sub>3</sub> are called *methanides* because they react with H<sub>2</sub>O, yielding methane.


Carbides with a C<sub>2</sub> unit are well known. They are formed mainly by the elements in Group 1 (M<sub>2</sub>C<sub>2</sub>); Group 2 (M<sup>II</sup>C<sub>2</sub>); the coinage metals (Cu, Ag, Au); Zn and Cd; and some of the lanthanides (LnC<sub>2</sub> and Ln<sub>4</sub>(C<sub>2</sub>)<sub>3</sub>). These are all colourless ionic compounds and contain the carbide ion (—C≡C—)<sup>2-</sup>. By far the most important compound is CaC<sub>2</sub>. This is made commercially by strongly heating lime and coke:



The reaction is endothermic, and a temperature of 2200°C is required. These carbides react exothermically with water, liberating ethyne (formerly called acetylene), so they are called *acetylides*.



Production of CaC<sub>2</sub> reached a maximum of 7 million tonnes/year in 1960, but has since declined to 4.9 million tonnes in 1991. At one time it was the major source of acetylene for oxy-acetylene welding, but ethyne is now obtained mainly from oil. CaC<sub>2</sub> is an important chemical intermediate and is used on an industrial scale to produce calcium cyanamide. Cyanamide is used as a nitrogenous fertilizer, and to make urea and melamine. (See Chapter 11, under 'Carbides'.)



The acetylides have a NaCl type of lattice, with Ca<sup>2+</sup> replacing Na<sup>+</sup> and C<sub>2</sub><sup>2-</sup> replacing Cl<sup>-</sup>. In CaC<sub>2</sub>, SrC<sub>2</sub> and BaC<sub>2</sub> the elongated shape of the (C≡C)<sup>2-</sup> ion causes tetragonal distortion of the unit cell, that is it elongates the unit cell in one direction – see Chapter 3 Figure 3.12.

One of the two carbides of magnesium Mg<sub>2</sub>C<sub>3</sub> contains a C<sub>3</sub> unit, and on hydrolysis with water it yields propyne CH<sub>3</sub>—C≡CH.

### Interstitial carbides

These are formed mostly by transition elements, and some of the lanthanides and actinides. The Cr, Mn, Fe, Co and Ni groups form a large number of carbides with a wide range of stoichiometries. They are typically infusible or are very high melting, and are very hard. For example, TaC has a melting point of 3900°C, and is very hard (9–10 on Mohs' scale of hardness), and WC is also very hard. Both are used to make cutting tools for lathes. Interstitial carbides retain many of the properties of metals. They conduct electricity by metallic conduction, and have a lustre like a metal.


In these compounds, C atoms occupy octahedral holes in the close-packed metal lattice, and so do not affect the electrical conductivity of the metal. Provided that the size of the metal is greater than 1.35 Å, the octahedral holes are large enough to accommodate C atoms without distorting the metal lattice. (Since we are considering a metal lattice, 12-coordinate radii must be used.) If all the octahedral holes are occupied the formula is MC. Interstitial carbides are generally unreactive. They do not react with H<sub>2</sub>O like ionic carbides. Most react slowly with concentrated HF or HNO<sub>3</sub>.

Some metals, including Cr, Mn, Fe, Co and Ni, have radii below 1.35 Å, hence the metal lattice is distorted. Thus the structures are more complicated, for compounds such as V<sub>2</sub>C, Mn<sub>5</sub>C<sub>2</sub>, Fe<sub>3</sub>C, V<sub>4</sub>C<sub>3</sub> and others. Cementite Fe<sub>3</sub>C is an important constituent of steel. These carbides are more reactive, and are hydrolysed by dilute acids, and in some cases by water, giving a mixture of hydrocarbons and H<sub>2</sub>.



Some carbides are based on the NaCl structure, with C occupying all of the Cl<sup>−</sup> positions. These include carbides of some of the early transition metals TiC, ZrC, HfC, VC, NbC, TaC, CrC and MoC, and those of some actinides such as ThC, UC and PuC.

### Covalent carbides

SiC and B<sub>4</sub>C are the most important. Silicon carbide is hard (9.5 on Mohs' scale), infusible and chemically inert. It is widely used as an abrasive called carborundum, and about 300 000 tonnes are produced annually by heating quartz or sand with an excess of coke in an electric furnace at 2000–2500°C.



SiC is very unreactive. It is unaffected by acids (except H<sub>3</sub>PO<sub>4</sub>), but it does react with NaOH and air, and with Cl<sub>2</sub> at 100°C.



SiC is often dark purple, black or dark green due to traces of Fe and other impurities, but pure samples are pale yellow to colourless. SiC has a three-dimensional structure of Si and C atoms, each atom tetrahedrally surrounded by four of the other kind. There are a large number of different crystal forms based on either the diamond or wurtzite structures. Boron carbide is even harder than silicon carbide and is used both as an abrasive and as a shield from radiation. It is manufactured in tonne quantities. Its formula is more correctly represented by  $B_{13}C_2$  (see Chapter 12, under 'Borides').

## OXYGEN COMPOUNDS



Carbon forms more oxides than the other elements, and these oxides differ from those of the other elements because they contain  $p\pi-p\pi$  multiple bonds between C and O. Two of these oxides, CO and  $CO_2$ , are extremely stable and important. Three are less stable:  $C_3O_2$ ,  $C_5O_2$  and  $C_{12}O_9$ . Others which are even less stable include graphite oxide,  $C_2O$  and  $C_2O_3$ .

### Carbon monoxide CO

CO is a colourless, odourless, poisonous gas. It is formed when C is burned in a limited amount of air. In the laboratory it is prepared by dehydrating formic acid with concentrated  $H_2SO_4$ .



CO can be detected because it burns with a blue flame. It also reduces an aqueous  $PdCl_2$  solution to metallic Pd, and when passed through a solution of  $I_2O_5$  it liberates  $I_2$ , i.e. it reduces  $I_2O_5$  to  $I_2$ . The latter reaction is used to estimate CO quantitatively. The  $I_2$  is titrated with  $Na_2S_2O_3$ .



CO is toxic because it forms a complex with haemoglobin in the blood, and this complex is more stable than oxy-haemoglobin. This prevents the haemoglobin in the red blood corpuscles from carrying oxygen round the body. This causes an oxygen deficiency, leading to unconsciousness and then death. CO is sparingly soluble in water and is a neutral oxide. CO is an important fuel, because it evolves a considerable amount of heat when it burns in air.




The following are all important industrial fuels:

1. *Water gas*: an equimolecular mixture of CO and  $H_2$ .
2. *Producer gas*: a mixture of CO and  $N_2$ .
3. *Coal gas*: a mixture of CO,  $H_2$ ,  $CH_4$  and  $CO_2$ , produced at a gasworks by distilling coal, and stored in large gas holders. This was the 'town gas'


supplied to peoples' homes for cooking and heating. In the UK it has now been replaced by natural gas ( $\text{CH}_4$ ), but town gas is still used in some countries.

Water gas is made by blowing steam through red or white hot coke




The water gas reaction is strongly endothermic ( $\Delta G = \Delta H - T\Delta S$ ). Thus the coke cools down, and at intervals the steam must be turned off and air blown through to reheat the coke. It is a particularly good fuel, i.e. it has a high calorific value, because both CO and  $\text{H}_2$  burn and evolve heat.

Producer gas is made by blowing air through red hot coke




The overall reaction is exothermic, so the coke does not cool down as with water gas.



Producer gas is a less efficient fuel than water gas, i.e. it has a lower calorific value, as only part of the gas will burn. The approximate composition of producer gas is 70%  $\text{N}_2$ , 25% CO, 4%  $\text{CO}_2$  with traces of  $\text{CH}_4$ ,  $\text{H}_2$  and  $\text{O}_2$ .

CO is a good reducing agent and can reduce many metal oxides to the metal. (See 'The occurrence and isolation of the elements' and 'Thermodynamics of reduction processes' Chapter 6.)







CO is an important ligand. It can donate an electron pair to many transition metals, forming carbonyl compounds. The number of CO molecules bonded to the metal in this way is generally in accordance with the effective atomic number rule (see Chapter 7). However, the bonding is more complicated than this implies. A number of different stoichiometries are formed (Table 13.7).

Table 13.7 Binary metal carbonyls formed by the first row transition elements


Sc	Ti	V	Cr	Mn	Fe	Co	Ni	Cu	Zn
		$\text{V}(\text{CO})_6$	$\text{Cr}(\text{CO})_6$	$\text{Mn}_2(\text{CO})_{10}$	$\text{Fe}(\text{CO})_5$	$\text{Co}_2(\text{CO})_8$	$\text{Ni}(\text{CO})_4$		
					$\text{Fe}_3(\text{CO})_{12}$	$\text{Co}_4(\text{CO})_{12}$			
					$\text{Fe}_5(\text{CO})_{14}$	$\text{Co}_6(\text{CO})_{16}$			

Carbonyl compounds may be made by a variety of reactions:




In the Mond process (now obsolete) for purifying nickel, nickel carbonyl  $\text{Ni}(\text{CO})_4$  was made from Ni and CO at  $50^\circ\text{C}$ . (Water gas was used as the source of CO.)  $\text{Ni}(\text{CO})_4$  is a gas and can be separated from other metals and impurities. The  $\text{Ni}(\text{CO})_4$  gas was then decomposed at  $230^\circ\text{C}$ . Though the original process is obsolete, a modified process is used in Canada.

The bonding in CO may be represented as three electron pairs shared between the two atoms:



It is better represented using the molecular orbital theory (see Chapter 4).



The carbon-metal bond in carbonyls may be represented as the donation of an electron pair from carbon to the metal  $\text{M} \leftarrow \text{C} \equiv \text{O}$ . This original  $\sigma$  bond is weak. A stronger second bond is formed by back bonding, sometimes called dative  $\pi$  bonding. This arises from sideways overlap of a full  $d_{xy}$  orbital on the metal with the empty antibonding  $\pi^* 2p_y$  orbital of the carbon, thus forming a  $\pi \text{M} \rightarrow \text{C}$  bond. The total bonding is thus  $\text{M}=\text{C}=\text{O}$ . The filling, or partial filling, of the antibonding orbital on C reduces the bond order of the C—O bond from the triple bond in CO towards a double bond. This is shown by the increase in C—O bond length from  $1.128 \text{ \AA}$  in CO to about  $1.15 \text{ \AA}$  in many carbonyls.

CO is the most studied organometallic ligand. Because of the back bonding it is sometimes called a  $\pi$  acceptor ligand. The drift of  $\pi$  electron density from M to C makes the ligand more negative, which in turn enhances its  $\sigma$  donating power. Thus CO forms weak bonds to Lewis acids (electron pair acceptors) such as  $\text{BF}_3$  as only  $\sigma$  bonding is involved. In contrast CO forms strong bonds to transition metals where both  $\sigma$  and  $\pi$  bonding can occur. Other  $\pi$  acceptor ligands include  $\text{CN}^-$ ,  $\text{RNC}$ , and  $\text{NO}^+$ . Comparing these ligands, the strengths of the  $\sigma$  bonds are in the order  $\text{CN}^- > \text{RNC} > \text{CO} > \text{NO}^+$ , whilst their  $\pi$  acceptor properties are in the reverse order.






Figure 13.4 Schematic of orbital overlaps in metal carbonyls (After N N Greenwood and A Earnshaw, *Chemistry of the Elements*, Pergamon, 1984, p 351)

CO is a very versatile ligand. It may act as a bridging group between the two metal atoms, for example in di iron enneacarbonyl  $\text{Fe}_2(\text{CO})_9$ . CO may stabilize metal clusters by the C forming a multi centre bond with three metal atoms, and the  $\pi^*$  orbitals in CO may be involved in bonding to other metal atoms.







Figure 13.5 Structure of  $\text{Fe}_2(\text{CO})_9$

Carbon monoxide is quite reactive, and combines readily with O, S and the halogens F, Cl and Br




The carbonyl halides are readily hydrolysed by water, and react with ammonia to form urea





Carbonyl chloride is extremely toxic, and was used as a poisonous gas in World War I. Nowadays it is produced in quite large quantities to make tolylene diisocyanate which is an intermediate in the manufacture of polyurethane plastics.

### Carbon dioxide $\text{CO}_2$


$\text{CO}_2$  is a colourless, odourless gas. It is a major industrial chemical, with 5.3 million tonnes produced in the USA and 10 million tonnes worldwide in 1993. The main industrial source is as a by-product from the manufacture of hydrogen for making ammonia.




It is also recovered from fermentation processes in breweries, from the gases evolved from calcining limestone in lime kilns and from the flue gases from coal-burning electric power stations. The  $\text{CO}_2$  is recovered by absorbing it in either aqueous  $\text{Na}_2\text{CO}_3$  or ethanolamine.




It is obtained in small amounts by the action of dilute acids on carbonates. It can also be made by burning carbon in excess of air.



### Recovery of $\text{CO}_2$



### Girbotol process




$\text{CO}_2$  gas can be liquified under pressure between  $-57^\circ\text{C}$  and  $+31^\circ\text{C}$ . About 80% is sold in liquid form, and 20% as solid. The solid is produced



a bidentate ligand with one C atom and one O atom bonded to the metal, and the  $\text{CO}_2$  molecule is bent.

The structure of  $\text{CO}_2$  is linear  $\text{O}=\text{C}=\text{O}$ . Both  $\text{C}=\text{O}$  bonds are the same length. In addition to  $\sigma$  bonds between C and O, there is a three-centre four-electron  $\pi$  bond covering all three atoms. This adds two  $\pi$  bonds to the structure in addition to the two  $\sigma$  bonds. Thus the  $\text{C}=\text{O}$  bond order is two. This is described in more detail in Chapter 4.

Biologically, carbon dioxide is important in the processes of photosynthesis, where the green parts of plants manufacture glucose sugar. Ultimately all animal and plant life depends on this process.




The reverse reaction occurs during the process of respiration, where animals and plants release energy.




### Carbon suboxides

Carbon suboxide  $\text{C}_3\text{O}_2$  is a foul-smelling gas, boiling point  $6^\circ\text{C}$ . It is made by dehydrating malonic acid with  $\text{P}_4\text{O}_{10}$ .



It is stable at  $-78^\circ\text{C}$  and the molecule is linear. At room temperature the gas polymerizes to a yellow solid, and at higher temperatures to red and purple solids. The oxide reacts with  $\text{H}_2\text{O}$ , giving malonic acid, and with  $\text{HCl}$  and  $\text{NH}_3$  as follows:




There are disputed reports that  $\text{C}_5\text{O}_2$  is formed by thermolysis of  $\text{C}_3\text{O}_2$ . The only other stable suboxide is  $\text{C}_{12}\text{O}_9$ . This is a white solid, and is the anhydride of mellitic acid  $\text{C}_6(\text{COOH})_6$ .

### CARBONATES

There are two series of salts from carbonic acid  $\text{H}_2\text{CO}_3$ , namely carbonates  $\text{CO}_3^{2-}$  and hydrogencarbonates  $\text{HCO}_3^-$ . The  $\text{CO}_3^{2-}$  ion is flat. The  $\text{CO}_4^{4-}$  ion does not exist, even though  $\text{SiO}_4^{4-}$  does. This is probably because C is too small, and the situation is analogous to the formation of  $\text{NO}_3^-$  and

$\text{PO}_4^{3-}$  in Group 15 The structure of the  $\text{CO}_3^{2-}$  ion may be represented as follows




The  $\pi$  bonding in the  $\text{CO}_3^{2-}$  ion is best described using a delocalized  $\pi$  molecular orbital covering all four atoms (See Chapter 4)

Many carbonates of formula  $\text{M}^{\text{II}}\text{CO}_3$  have the same structure as calcite but others have the aragonite structure. The structure adopted is related to the size of the metal ions

$\text{Mn}^{2+}$	$\text{Mg}^{2+}$	$\text{Co}^{2+}$	$\text{Zn}^{2+}$	$\text{Fe}^{2+}$	$\text{Cd}^{2+}$	$\text{Ca}^{2+}$	$\text{Sr}^{2+}$	$\text{Pb}^{2+}$	$\text{Ba}^{2+}$
0.67	0.72	0.74	0.74	0.78	0.97	1.00	1.18	1.21	1.35
← calcite structure →						← aragonite structure →			

Some carbonates are produced in very large amounts: 31.5 million tonnes/year of  $\text{Na}_2\text{CO}_3$ , 900 000 tonnes/year  $\text{NaHCO}_3$ , and 50 000 tonnes/year of  $\text{Li}_2\text{CO}_3$  (see Chapters 9 and 10)

Carbonate ions are colourless and hence the carbonates of Group 1 and 2 metals are white. Though  $\text{Ag}^+$  salts are typically white,  $\text{Ag}_2\text{CO}_3$  is yellow due to the strong polarizing effect of  $\text{Ag}^+$ .  $(\text{NH}_4)_2\text{CO}_3$  and Group 1 carbonates are readily soluble in water, except  $\text{Li}_2\text{CO}_3$  which is only slightly soluble.  $\text{Ti}_2\text{CO}_3$  is moderately soluble, but the other Group 13 carbonates are sparingly soluble or insoluble. Carbonates all react with acids, liberating  $\text{CO}_2$ .



Group 1 carbonates are stable to heat, and melt without decomposing. Group 2 carbonates all decompose if heated sufficiently strongly. Their stability increases as the size of the metal ion increases. Most other carbonates decompose easily.

	$\text{CaCO}_3 \xrightarrow{\text{heat}} \text{CaO} + \text{CO}_2$				
	$\text{BeCO}_3$	$\text{MgCO}_3$	$\text{CaCO}_3$	$\text{SrCO}_3$	$\text{BaCO}_3$
Decomposition temperature	<100°C	540°C	900°C	1290°C	1360°C

The only solid bicarbonates known are those of the Group 1 metals and of  $\text{NH}_4^+$ . These are colourless solids, and are somewhat less soluble than the corresponding carbonates. They decompose easily on heating. The

solid structures of these contain polymeric chains of  $\text{HCO}_3^-$  groups hydrogen bonded together.


## THE CARBON CYCLE

Though carbon is the seventeenth most abundant element in the earth's crust, and totals about  $2 \times 10^{16}$  tonnes, most of this is in the form of coal, oil and various carbonates (limestone and dolomite) which are immobilized.

In contrast there is a rapid turnover of  $\text{CO}_2$  in the atmosphere, carbon compounds in living matter,  $\text{CO}_2$  dissolved in the oceans, and more slowly with carbonate minerals formed on the sea bed. An equilibrium exists between them. The proportion of  $\text{CO}_2$  in the atmosphere is approximately 0.046% by weight, and 0.031% by volume. Though only a small percentage,  $\text{CO}_2$  is essential for life, and amounts to 2500 billion tonnes ( $2500 \times 10^9$  tonnes).

Photosynthesis by the green parts of plants and some brown and blue algae removes about 360 billion tonnes of  $\text{CO}_2$  from the atmosphere a year – roughly 15%. Glucose sugar is the first product formed. This may be used for respiration and energy release by the plant, or incorporated into plant cells. These may be eaten by animals, and used for respiration or for producing animal cells. Eventually the same amount of  $\text{CO}_2$  is returned to the atmosphere either by respiration of the plant or animal, or by death and putrefaction of plant or animal remains.

Combustion of fossil fuels, mainly coal, oil and natural gas, and burning tropical rain forests adds about 25 billion tonnes of  $\text{CO}_2$  to the atmosphere each year. (Coal production in 1992 was 4545 million tonnes, crude oil 3034 million tonnes, natural gas  $2.1 \times 10^{12} \text{ m}^3$ . Important amounts of  $\text{CO}_2$  are released by burning limestone to make lime for making cement. Lime production in 1992 was 127.9 million tonnes so about 100 million tonnes of  $\text{CO}_2$  was produced.




It is estimated that in 1992 the USA added 1.2 billion tonnes of  $\text{CO}_2$  to the atmosphere, the USSR 1 billion tonnes and western Europe 0.8 billion tonnes. If all of this  $\text{CO}_2$  remained in the atmosphere, it is estimated that the  $\text{CO}_2$  content will double by the year 2020. With the ever increasing use of fossil fuels the amount of  $\text{CO}_2$  could double even sooner.

The  $\text{CO}_2$  molecule absorbs strongly in the infrared region, and its presence in the atmosphere decreases the loss of heat from the earth by radiation. This global warming is called the 'greenhouse effect'. (Other gases, including the oxides of nitrogen from car exhausts, Freons from aerosols and refrigerators and methane from bacteria in the soil and in the rumen of cows, also add to the greenhouse effect.) The magnitude of this effect, and whether it exists at all are controversial. The concentration of atmospheric  $\text{CO}_2$  has increased by 10% since 1958, and on the basis of measurements of  $\text{CO}_2$  from ice cores is some 25% higher than before the

industrial revolution. This corresponds to about half the  $\text{CO}_2$  produced from burning fossil fuels, and most of the remainder has been absorbed by the oceans. A United Nations report suggests that if nothing is done the mean temperature of the earth will rise by  $2.5^\circ\text{C}$  in the next 30 years. This is an average, varying from  $2^\circ\text{C}$  at the equator to  $4^\circ\text{C}$  at the poles. This could have dramatic effects on the climate. Some fertile areas like the grain belt in the USA would become desert and crops would not grow. The increased temperature would cause more evaporation of water and hence more rain, flooding and tropical storms in certain parts of the world. Part of the polar ice caps would melt, and this together with the thermal expansion of the sea would flood vast areas of land.

It is by no means certain that these catastrophic changes will occur. It must be emphasized that there is a long timescale for the expected warming due to greenhouse gases. Furthermore in nature one change in the biosphere is usually balanced by another with the opposite effect. Biological and other feedbacks are likely to affect the future concentrations of greenhouse gases. More  $\text{CO}_2$  in the atmosphere may enhance plant growth which will use it up. A whole forest can grow in 30 years. Since large amounts of  $\text{CO}_2$  dissolve in the sea, this should make the pH of the sea decrease. In the extreme this increase in acidity might dissolve the calcareous shells of molluscs and other sea life, thus destroying them. This is far from certain, since if global warming does occur, the solubility of  $\text{CO}_2$  in water will decrease. However, an increase in  $\text{CO}_2$  in the surface waters could well lead to an increase in plankton – small marine plants which use  $\text{CO}_2$  in photosynthesis. In addition slow reactions occur on the ocean floor




The silicate sediments on the ocean floor play an important role in fixing the composition and pH of the water. An increase in pH is compensated by the dissolution of certain minerals and the precipitation of others. Thus silicate rocks may change to carbonates and  $\text{SiO}_2$ . If the pH subsequently changes the other way then these processes are reversed.

The greenhouse debate is a reminder of the limited evidence, uncertainty and long timescale of the problems of global warming. The author's opinion is that it must be prudent to conserve energy, to improve efficiency and to reduce wasteful practices, since there is no immediate alternative in sight to using fossil fuels. Nuclear power is the only major alternative energy source, and at present many people find it unacceptable. The hydrogen economy is a long way off, and solar power and the power of wind and waves can at best provide only a very small fraction of our energy requirements.

## SULPHIDES


Carbon disulphide  $\text{CS}_2$  is the most important sulphide of carbon. It is a colourless volatile liquid, b.p.  $46^\circ\text{C}$ . It is dangerous to handle because

it is very flammable, it has a very low flash point (30°C) and it ignites spontaneously at 100°C. It is very poisonous, affecting the brain and central nervous system. Pure samples smell like ether, but organic impurities frequently give it an extremely foul smell. It is a commercially important chemical, and world production was 280 400 tonnes in 1991. At one time it was produced by heating charcoal and S vapour at about 850°C. Nowadays it is produced mainly from a gas phase reaction between natural gas and sulphur, catalysed by  $\text{Al}_2\text{O}_3$  or silica gel.



The main uses of  $\text{CS}_2$  are as follows:

1. The manufacture of viscose rayon (artificial silk) and cellophane.  $\text{CS}_2$  reacts with cellulose and NaOH to form sodium cellulose dithiocarbonate (cellulose xanthate).




This is dissolved in lye (aqueous alkali) to give a viscous solution called 'viscose'. On acidification, 'viscose' is converted back to cellulose in the form of fibres (either rayon or cellulose wool), or as a thin film (cellophane).

2. The manufacture of  $\text{CCl}_4$  (see later under 'Halides').
3. Smaller amounts are used as a solvent for S in the cold vulcanization of rubber.

$\text{CS}_2$  reacts with aqueous NaOH, giving a mixture of sodium carbonate and sodium trithiocarbonate:



$\text{CS}_2$  reacts with  $\text{NH}_3$ , giving ammonium dithiocarbamate:



$\text{CS}_2$  is a linear molecule with a similar structure to  $\text{CO}_2$ .  $\text{CS}_2$  forms complexes more readily than  $\text{CO}_2$ . The complex  $[\text{Pt}(\text{CS}_2)(\text{PPh}_3)]$  is structurally similar to  $[\text{Co}(\text{CO})_2(\text{PPh}_3)_3]$ . The  $\text{CS}_2$  acts as a bidentate ligand with one C atom and one S atom bonded to the metal, and the  $\text{CS}_2$  molecule is bent. The S atoms may bond to other metal atoms, giving more complicated complexes. The bonding cannot be explained by classical localized bonds.


Sunlight changes  $\text{CS}_2$  to CS, which is why  $\text{CS}_2$  is stored in dark coloured bottles. A high frequency electric charge also converts  $\text{CS}_2$  vapour to CS. CS is unlike CO, and is a highly reactive radical even at the temperature of




liquid air. Passing an arc through  $\text{CS}_2$  gives  $\text{C}_3\text{S}_2$ . This is thought to have the structure  $\text{S}=\text{C}=\text{C}=\text{C}=\text{S}$ . It is a red liquid that polymerizes slowly (as does  $\text{C}_3\text{O}_2$ ).

### OXIDES OF SILICON

Two oxides of silicon,  $\text{SiO}$  and  $\text{SiO}_2$ , have been reported. Silicon monoxide is thought to be formed by high temperature reduction of  $\text{SiO}_2$  with  $\text{Si}$ , but its existence at room temperature is in doubt.




Silicon dioxide  $\text{SiO}_2$  is commonly called silica, and it is widely found as sand and quartz. Group 14 elements typically form four bonds. Carbon can form  $p\pi-p\pi$  double bonds and hence  $\text{CO}_2$  is a discrete molecule and is a gas. Silicon cannot form double bonds in this way using  $p\pi-p\pi$  orbitals. (A substantial number of silicon compounds are now known to contain  $p\pi-d\pi$  bonds in which the silicon atom appears to use  $d$  orbitals for bonding.) Thus  $\text{SiO}_2$  forms an infinite three dimensional structure, and  $\text{SiO}_2$  is a high melting solid.  $\text{SiO}_2$  exists in at least 12 different forms. The main ones are quartz, tridymite and cristobalite, each of which has different structures at high and low temperatures.  $\alpha$ -Quartz is by far the most common and is a major constituent of granite and sandstone. Pure  $\text{SiO}_2$  is colourless, but traces of other metals may colour it, giving semi-precious gemstones such as amethyst (violet), rose quartz (pink), smoky quartz (brown), citrine (yellow), and non-precious materials such as flint (often black due to C), agate and onyx (banded).




In all of these forms each Si is tetrahedrally surrounded by four O atoms. Each corner is shared with another tetrahedron, thus giving an infinite array. The difference between these structures is the way in which the tetrahedral  $\text{SiO}_4$  units are arranged.  $\alpha$ -Quartz is the most stable form at room temperature and in this the tetrahedra form helical chains. These are interlinked. Since the helix may be left or right handed, they cannot be superimposed, so it exists as  $d$  and  $l$  optical isomers. Individual crystals can be separated by hand. In cristobalite the Si atoms have the same arrangement as the C atoms in diamond, with O atoms midway between them. The relation between tridymite and cristobalite is the same as that between wurtzite and zinc blende. Heating any solid form of  $\text{SiO}_2$  to its softening temperature, or slow cooling of molten  $\text{SiO}_2$ , gives a glass like solid. This is

amorphous, and contains a disordered mixture of rings, chains and three-dimensional units.


Silica in any form is unreactive. It is an acidic oxide and so does not react with acids. However, it does react with HF, forming silicon tetrafluoride  $\text{SiF}_4$ . This reaction is used in qualitative analysis to detect silicates: when the  $\text{SiF}_4$  comes into contact with a drop of water it is hydrolysed to silicic acid. This can be seen as a white solid forming on the surface of the drop of water.



$\text{SiO}_2$  is an acidic oxide: it dissolves slowly in aqueous alkali, and more rapidly in fused alkalis MOH or fused carbonates  $\text{M}_2\text{CO}_3$ , forming silicates.



This reaction accounts for ground glass stoppers sticking in reagent bottles containing NaOH. Of the halogens, only fluorine attacks  $\text{SiO}_2$ .



Quartz is important as a piezo-electric material for the crystals in gramophone pickups, for cigarette and gas lighters and for making crystal oscillators for radios and computers. There is insufficient natural quartz of high enough purity, and so it is made synthetically by hydrothermal growth of seed crystals from aqueous NaOH and vitreous silica at  $400^\circ\text{C}$  under pressure.

Vitreous silica has a low coefficient of expansion, is quite resistant to shock, and is very transparent to visible and ultraviolet light. It is used for laboratory glassware, and for optical components such as lenses and prisms and cells to hold samples in UV-visible spectrophotometers.

Silica gel is amorphous and very porous. It is obtained by dehydrating silicic acid, and contains about 4% water. It is widely used as a drying agent, a catalyst, and in chromatography. The mineral opal, which is used as a white or pearl-like gemstone, is hard (amorphous) silica gel. The beginnings of ordered structures are shown by various minerals, many of which are cut and polished as gemstones:

- agate (often banded colours)
- onyx (often white and black bands)
- carnelian (yellow or red)
- bloodstone (green with red spots)
- jasper (usually red or brown but sometimes green, blue or yellow)
- flint (colourless or black if C present)

These are best written  $\text{SiO}_2 \cdot n\text{H}_2\text{O}$ .

Kieselguhr is another form of  $\text{SiO}_2$ . It is a fine white powder, and about 2 million tonnes/year are obtained by open cast mining in Europe and North America. It is used in filtration plants, as an abrasive, and as an inert

filler (Gelignite is a mixture of the explosive nitrobenzene (liquid) and inert kieselguhr (solid) )

### OXIDES OF GERMANIUM, TIN AND LEAD

The dioxides  $\text{GeO}_2$ ,  $\text{SnO}_2$  and  $\text{PbO}_2$  normally adopt a  $\text{TiO}_2$  structure with 6 3 coordination. The basicity of the oxides increases down the group; this is the usual trend. Thus  $\text{CO}_2$  and  $\text{SiO}_2$  are purely acidic.  $\text{GeO}_2$  is not as strongly acidic as  $\text{SiO}_2$ , and  $\text{SnO}_2$  and  $\text{PbO}_2$  are amphoteric.  $\text{GeO}_2$ ,  $\text{SnO}_2$  and  $\text{PbO}_2$  dissolve in alkali to form germanates, stannates and plumbates respectively. The germanates have complicated structures similar to the silicates, but the stannates and plumbates contain  $[\text{Sn}(\text{OH})_6]^{2-}$  and  $[\text{Pb}(\text{OH})_6]^{2-}$  complex ions. There is no evidence of the existence of  $\text{Ge}(\text{OH})_4$ ,  $\text{Sn}(\text{OH})_4$  and  $\text{Pb}(\text{OH})_4$  and these are better represented as  $\text{MO}_2(\text{H}_2\text{O})_n$ , where  $n$  is about two. All three oxides are insoluble in acids except when a complexing agent such as  $\text{F}^-$  or  $\text{Cl}^-$  is present, when complex ions such as  $[\text{GeF}_6]^{2-}$  and  $[\text{SnCl}_6]^{2-}$  are formed.

The lower oxides  $\text{GeO}$ ,  $\text{SnO}$  and  $\text{PbO}$  have layer lattices rather than the typical ionic structures. They are slightly more basic and ionic than the corresponding higher oxides.  $\text{GeO}$  is distinctly acidic, whilst  $\text{SnO}$  and  $\text{PbO}$  are amphoteric and dissolve in both acids and bases. The increased stability of the lower valence states on descending a group is illustrated by the fact that  $\text{Ge}^{\text{II}}$  and  $\text{Sn}^{\text{II}}$  are quite strong reducing agents whereas  $\text{Pb}^{\text{II}}$  is stable.

$\text{PbO}$  is commercially important. It exists as a red form called litharge and a yellow form called massicot. Litharge is used in large amounts to make lead glass, and in ceramic glazes. World production is about 250 000 tonnes/year. 'Black oxide' of lead is a mixture of  $\text{PbO}$  and  $\text{Pb}$ , and is extensively used to make the plates in electric storage batteries for motor cars. The anode is oxidized to  $\text{PbO}_2$  and the cathode is reduced to spongy lead. About 700 000 tonnes/year are used worldwide.

Lead also forms a mixed oxide  $\text{Pb}_3\text{O}_4$ . This is called red lead and may be represented as  $2\text{PbO} \cdot \text{PbO}_2$ ; clearly it contains  $\text{Pb}(\text{II})$  and  $\text{Pb}(\text{IV})$ .  $\text{Pb}_3\text{O}_4$  is used in paint to prevent the rusting of iron and steel. It is also used to colour and vulcanize plastic and artificial rubber. Smaller amounts are used in ceramics and glassmaking. World production is about 18 000 tonnes/year.

$\text{PbO}_2$  is used as a strong oxidizing agent, and is produced in situ in lead storage batteries.

### SILICATES

#### Occurrence in the earth's crust

About 95% of the earth's crust is composed of silicate minerals, aluminosilicate clays or silica. These make up the bulk of all rocks, sands and their breakdown products, clays and soil. Many building materials are silicates: granite, slates, bricks, and cement. Ceramics and glass are also silicates.

first	olivine	$M_2^{II}SiO_4$
	pyroxenes	$M_2^{II}(SiO_3)_2$
	amphiboles	$M_7^{II}(Al, Si)_4O_{11} \cdot (OH)_2$
	biotite micas	$(K, H)_2(Mg, Fe^{II})_2(Al, Fe^{III})_2(SiO_4)_3$
	orthoclase feldspars	$KAlSi_3O_8$
	muscovite micas	$KAl_2(AlSi_3O_{10}) \cdot (OH)_2$
	quartz	$SiO_2$
last	zeolites	$Na_2(Al_2Si_3O_{10})2H_2O$

(Leaving a small amount of water,  $SO_2$ , S, Pb, Cu, Ag, Sn, As, Sb, Bi and other transition metals in solution under a very high temperature and pressure)

Figure 13.6 Sequence in which minerals are thought to have crystallized.

The three most abundant elements are O, Si and Al. Together they make up 81% of the earth's crust, that is four out of five atoms are one of these. This is a much higher abundance than in the earth as a whole or in the universe. During the cooling of the earth the lighter silicate materials crystallized and floated to the surface, resulting in the concentration of silicates in the earth's crust.


N.L. Bowen has summarized the sequence in which these crystalline minerals appeared as the magma cooled, and this is called Bowen's Reaction Series (Figure 13.6).

Several points arise:

1. The simpler silicate units crystallized first.
2. Hydroxyl groups appear in the later minerals, and F may be substituted instead of OH.
3. Isomorphous replacement, i.e. changing one metal for another without changing the structure, occurs particularly in the later minerals.
4. The orthoclase feldspars, muscovite mica and quartz are the major minerals of granite.
5. As the silicates cooled further, they shrank and cracked. The hydrothermal (hot water) solution moved through the cracks nearer the surface to regions of lower temperature and pressure where the elements precipitated and then combined with S, forming veins of sulphides.

### Soluble silicates

Silicates can be prepared by fusing an alkali metal carbonate with sand in an electric furnace at about 1400°C.



The product is a soluble glass of sodium or potassium silicate. It is dissolved in hot water under pressure, and is filtered from any insoluble material. The composition of the product varies, but is approximately  $Na_2Si_2O_5 \cdot 6H_2O$ . In 1991, 2.6 million tonnes of soluble sodium silicates were produced (measured in terms of  $SiO_2$  content). They are used in

liquid detergent preparations to keep the pH high, so that grease and fat can be dissolved by forming a soap. Soluble silicates must not be used if the water is hard, or they will react with  $\text{Ca}^{2+}$  to form insoluble calcium silicate. Sodium silicate is also used as an adhesive (for example for pasting paper, bonding paper pulp and corrugated cardboard), in asbestos roof tiles, in fireproof paint and putty, and in making silica gel.

### Principles of silicate structures

The majority of silicate minerals are very insoluble, because they have an infinite ionic structure and because of the great strength of the Si—O bond. This made it difficult to study their structures and physical properties such as cleavage and the hardness of rocks were originally studied. The structural principles in silicate structures have only become apparent since the structures have been solved by X ray crystallographic methods.

- 1 The electronegativity difference between O and Si,  $3.5 - 1.8 = 1.7$  suggests that the bonds are almost 50% ionic and 50% covalent.
- 2 The structure may therefore be considered theoretically by both ionic and covalent methods. The radius ratio  $\text{Si}^{4+} \text{O}^{2-}$  is 0.29 which suggests that Si is four coordinate and is surrounded by four O atoms at the corners of a tetrahedron. This can also be predicted from the use of the 3s and three 3p orbitals by Si for bonding. Thus silicates are based on  $(\text{SiO}_4)^{4-}$  tetrahedral units.
- 3 The  $\text{SiO}_4$  tetrahedra may exist as discrete units, or may polymerize into larger units by sharing corners—that is by sharing O atoms.
- 4 The O atoms are often close packed or nearly close packed. Close packed structures have tetrahedral and octahedral holes and metal ions may occupy either octahedral or tetrahedral sites depending on their size. Most metal ions are the right size to fit one type of hole though  $\text{Al}^{3+}$  can fit into either. Thus Al can replace either a metal in one of the holes, or a silicon atom in the lattice. This is particularly important in the aluminosilicates.

Occasionally Li may occupy sites with a coordination number of 6 rather than the usual 4, and K and Ca may have a coordination number of 8 rather than the usual 6. The radius ratio principle is a useful guide, but it is only strictly applicable to ionic compounds and silicates are partly covalent. In these compounds the full charge separation to give  $\text{Si}^{4+}$  and  $\text{O}^{2-}$  does not occur, and empirical 'effective ionic radii' may be used instead of normal ionic radii (see Further Reading, R. D. Shannon).

### CLASSIFICATION OF SILICATES

The way in which the  $(\text{SiO}_4)^{4-}$  tetrahedral units are linked together provides a convenient classification of the many silicate minerals.

**Orthosilicates (neso-silicates)**

A wide variety of minerals contain discrete  $(\text{SiO}_4)^{4-}$  tetrahedra, that is they share no corners (see Figure 13.7). They have the formula  $\text{M}_2^{\text{II}}[\text{SiO}_4]$ , where M may be Be, Mg, Fe, Mn or Zn, or  $\text{M}^{\text{IV}}[\text{SiO}_4]$ , for example  $\text{ZrSiO}_4$ . Different structures are formed depending on the coordination number adopted by the metal.

In willemite  $\text{Zn}_2[\text{SiO}_4]$ , and phenacite  $\text{Be}_2[\text{SiO}_4]$ , the Zn and Be atoms have a coordination number of 4, and occupy tetrahedral holes.


In forsterite  $\text{Mg}_2[\text{SiO}_4]$ , the Mg has a coordination number of 6 and

**Table 13.8** Types of holes occupied in close-packed structures

Oxide	Radius ratio	Coordination number	Type of hole occupied
$\text{Be}^{2+} : \text{O}^{2-}$	0.25	4	Tetrahedral
$\text{Si}^{4+} : \text{O}^{2-}$	0.29	4	Tetrahedral
$\text{Al}^{3+} : \text{O}^{2-}$	0.42	4 or 6	{ Tetrahedral or Octahedral
$\text{Mg}^{2+} : \text{O}^{2-}$	0.59	6	Octahedral
$\text{Fe}^{2+} : \text{O}^{2-}$	0.68	6	Octahedral

occupies octahedral holes. When octahedral sites are occupied, it is quite common to get isomorphous replacement of one divalent metal ion by another of similar size, without changing the structure. The mineral olivine  $(\text{Mg}, \text{Fe})_2[\text{SiO}_4]$  has the same structure as forsterite, but about one tenth of the  $\text{Mg}^{2+}$  ions in forsterite are replaced by  $\text{Fe}^{2+}$  ions. The ions have the same charge and similar radii ( $\text{Mg}^{2+}$  0.72 Å,  $\text{Fe}^{2+}$  0.78 Å), and occupy the same type of hole. Thus substitution of one metal for another does not change the structure. This mineral may also have  $\text{Mn}^{\text{II}}$  in some octahedral sites, thus giving  $(\text{Mg}, \text{Fe}, \text{Mn})_2[\text{SiO}_4]$ . These structures are all related to hexagonal close-packing.

Zircon  $\text{ZrSiO}_4$  is used as a gemstone as it can be cut to look like a



**Figure 13.7** Structure of orthosilicates. (After T. Moeller.)

diamond but is much cheaper. Zircon is much softer than diamond, and the cut edges which make the gem attractive eventually wear and spoil the look of the stone. Zircon has a coordination number of 8. The structure is not close packed.

The garnets are another important group of minerals with discrete tetrahedra. Large crystals of garnet are cut and polished and used as a red gemstone. Much larger amounts (106 099 tonnes in 1993) are used to make 'sandpaper'. The formula is  $M_3^{II}M_2^{III}[(SiO_4)_3]$ .  $M^{II}$  may be Mg, Ca or  $Fe^{II}$ , and these are six coordinate.  $M^{III}$  may be  $Fe^{III}$ , Cr or Al and these are eight coordinate.

### Pyrosilicates (soro-silicates, disilicates)

Two tetrahedral units are joined by sharing the O at one corner, thus giving the unit  $(Si_2O_7)^{6-}$ . This is the simplest of the condensed silicate ions. The name pyro comes from the similarity in structure with pyrophosphates such as  $Na_4P_2O_7$ , and these were named because they can be made by heating orthophosphates (see Figure 13.8).

Pyrosilicates are rare. One example is thortveitite  $Sc_2[Si_2O_7]$ . A number of lanthanide disilicates have similar formulae  $Ln_2[Si_2O_7]$ . These are not quite the same, as the Si—O—Si angle is not  $180^\circ$  as in the Sc compound, but varies down to  $133^\circ$ , and the coordination number of the metal changes from 6 to 7 and then to 8 as the size of the metal increases. Hemimorphite  $Zn_4(OH)_2[Si_2O_7] \cdot H_2O$  is another example, but structural studies show no difference in the lengths of the bridging and terminal Si—O bonds. Thus the representation as a disilicate ion may be misleading and the structure may be better considered as  $[SiO_4]$  and  $[ZnO_3(OH)]$  tetrahedra linked to give a three-dimensional network.




Figure 13.8 Structure of pyrosilicates  $Si_2O_7^{6-}$  (After T. Moeller)

### Cyclic silicates

If two oxygen atoms per tetrahedron are shared, ring structures may be formed of general formula  $(Si_3O_8)^{2-}_n$  (Figure 13.9). Rings containing three, four, six and eight tetrahedral units are known, but those with three and six are the most common. The cyclic ion  $Si_3O_8^{6-}$  occurs in wollastonite  $Ca_3[Si_3O_9]$  and in benitoite  $BaTi[Si_3O_9]$ . The  $Si_6O_{18}^{12-}$  unit occurs in beryl.




Figure 13.9 Structure of cyclic silicates  $\text{Si}_3\text{O}_9^{6-}$  and  $\text{Si}_6\text{O}_{18}^{12-}$ . (After T. Moeller.)

$\text{Be}_3\text{Al}_2[\text{Si}_6\text{O}_{18}]$ . In beryl the  $\text{Si}_6\text{O}_{18}$  units are aligned one above the other, leaving channels.  $\text{Na}^+$ ,  $\text{Li}^+$  and  $\text{Cs}^+$  are commonly found in these channels, and because of the channels the mineral is permeable to gases consisting of small atoms or molecules, e.g. helium. Beryl and emerald are both gemstones. Beryl is found with granite and usually forms pale green crystals which are six-sided prisms. Emerald has the same formula as beryl except that it contains 1–2% Cr which gives it a strong green colour.

### Chain silicates

Simple chain silicates or pyroxenes are formed by the sharing of the O atoms on two corners of each tetrahedron with other tetrahedra. This gives the formula  $(\text{SiO}_3)_n^{2n-}$  (see Figures 13.10 and 13.11). A large number of important minerals form chains, but there are a variety of different structures formed because the arrangement of the tetrahedra in space may vary and thus affect the repeat distance along the chain. The most common arrangement repeats after every second tetrahedron, for example in spodumene  $\text{LiAl}[(\text{SiO}_3)_2]$  (which is the main source of Li), enstatite  $\text{Mg}_2[(\text{SiO}_3)_2]$ , and diopside  $\text{CaMg}[(\text{SiO}_3)_2]$ . Wollastonite  $\text{Ca}_3[(\text{SiO}_3)_3]$  has a repeat unit of three tetrahedra, and others are known with repeat units of 4, 5, 6, 7, 9 and 12.

Double chains can be formed when two simple chains are joined together by shared oxygens. These minerals are called amphiboles, and they are well known. There are several ways of forming double chains, giving formulae  $(\text{Si}_2\text{O}_5)_n^{2n-}$ ,  $(\text{Si}_4\text{O}_{11})_n^{6n-}$ ,  $(\text{Si}_6\text{O}_{17})_n^{10-}$  and others. (See Figure 13.12.)






Figure 13.10 Structure of various single chains




Figure 13.11 Structure of pyroxenes  $(\text{SiO}_3)_{2n}^{2n-}$ . (After T. Moeller.)

The most numerous and best known amphiboles are the asbestos minerals. These are based on the structural unit  $(\text{Si}_4\text{O}_{11})_n^{6n-}$ . In this structure (Figure 13.12) some tetrahedra share two corners, whilst others share three corners. Examples include tremolite,  $\text{Ca}_2\text{Mg}_5[(\text{Si}_4\text{O}_{11})_2(\text{OH})_2]$ , and crocidolite  $\text{Na}_2\text{Fe}^{\text{II}}\text{Fe}_2^{\text{III}}[(\text{Si}_4\text{O}_{11})_2(\text{OH})_2]$ . Amphiboles always contain hydroxyl groups, which are attached to the metal ions.

The Si—O bonds in the chains are strong and directional. Adjacent chains are held together by the metal ions present. Thus pyroxenes and amphiboles cleave readily parallel to the chains, forming fibres. For this reason they are called fibrous minerals. The cleavage angle for pyroxenes is  $89^\circ$ , and for amphiboles  $56^\circ$ . This is used as a means of identifying the minerals. These angles are related to the size of the cross-sectional tra-




Figure 13.12 Structure of various double chains.




Figure 13.13 Structure of amphiboles  $(\text{Si}_4\text{O}_{11})_n^{6n-}$ . (After T. Moeller.)

pezium of the chains and the way in which they are packed together (see Figure 13.14).

Asbestos is of considerable commercial importance, and 2.8 million tonnes were mined in 1993 (Soviet Union 36%, Canada 19%, Kazakhstan 14%, and China and Brazil 9% each). It is useful because it is strong, cheap, resistant to heat and flames, and also resistant to acids and alkalis. Most is used to make asbestos reinforced cement and roofing sheets. Smaller amounts are used for brake linings, clutch linings, asbestos paper, adding to vinyl floor coverings, and thermal insulation for pipes, and fibres may be woven into asbestos cloth to make fire fighting suits.

Asbestos minerals come from two different groups of silicates:

1. The amphiboles.
2. The sheet silicates.

The amphiboles include crocidolite  $\text{Na}_2\text{Fe}_3^{II}\text{Fe}_2^{III}[\text{Si}_8\text{O}_{22}](\text{OH})_2$ , which is called blue asbestos, and others derived from it by isomorphous replace-




Figure 13 14 Cleavage angles in pyroxenes and amphiboles

ment, for example amosite or brown asbestos  $(\text{Mg}, \text{Fe}^{II})_7[\text{Si}_8\text{O}_{22}](\text{OH})_2$ . Together these make up about 5% of the asbestos used.

The mineral chrysotile  $\text{Mg}_3(\text{OH})_4[\text{Si}_2\text{O}_5]$  is called white asbestos, and this is derived from serpentine, and is a sheet silicate. This constitutes 95% of the asbestos used.

Though asbestos is chemically inert, it presents a serious health hazard. Inhaling asbestos dust causes asbestosis or scarring of the lungs. It also causes lung cancer. Blue asbestos appears to be the worst hazard. The disease may have a latent period of 20–30 years. The best control is to minimize asbestos dust, and to handle asbestos wet if possible.

### Sheet silicates (phyllo silicates)

When  $\text{SiO}_4$  units share three corners the structure formed is an infinite two dimensional sheet of empirical formula  $(\text{Si}_2\text{O}_5)^{2n-}$  (see Figure 13 15). There are strong bonds within the Si—O sheet, but much weaker forces hold each sheet to the next one. Thus these minerals tend to cleave into thin sheets.

Structures with simple planar sheets are rare. A large number of sheet silicates are important and well known. These have slightly more complicated structures, and are made up of either two or three layers joined together. These include

- 1 Clay minerals (kaolinite, pyrophyllite, talc)
- 2 White asbestos (chrysotile, biotite)
- 3 Micas (muscovite and margarite)
- 4 Montmorillonites (Fullers earth, bentonite and vermiculite)

Consider how a two layer structure may be formed. If we start with a simple silicate sheet then one side of the sheet contains all the unshared (singly bound) O atoms. The pure hydroxides  $\text{Al}(\text{OH})_3$  and  $\text{Mg}(\text{OH})_2$  both crystallize with layer structures (and Al and Mg are six coordinate and occupy octahedral sites). The unshared O in a silicate sheet have almost




Figure 13.15 Structure of sheet silicates  $(\text{Si}_2\text{O}_5)_n^{2n-}$ . (After T. Moeller.)

the same relative positions as two thirds of the OH groups on each side of these hydroxide layers. If a  $\text{Si}_2\text{O}_5$  layer is placed alongside a layer of  $\gamma$ -gibbsite  $\text{Al}(\text{OH})_3$ , then many of the O atoms will coincide. The OH groups in  $\text{Al}(\text{OH})_3$  can be removed and an electrically neutral two-layer structure is formed. These double layers stacked parallel give the mineral kaolinite, which has the formula  $\text{Al}_2(\text{OH})_4[\text{Si}_2\text{O}_5]$ . It is a white solid and is formed by the decomposition of granite. Large amounts are used for filling paper, and as a refractory. World production of kaolinite was 22.5 million tonnes in 1992 (USA 41%, UK 11%, and South Korea 8%). China clay or kaolin is mined in Cornwall. It is a high grade of kaolinite, and when small amounts of  $\text{SiO}_2$  and mica are removed it can be mixed with water to give a white or nearly white plastic clay. Small amounts are used for making porcelain, china cups and plates, sanitary ware, and other ceramics, and for chromatography, as treatment for indigestion and for poultices.

One  $\text{Al}(\text{OH})_3$  layer has two equivalent sides. A  $\text{Si}_2\text{O}_5$  layer was combined with one side in kaolinite, but a second  $\text{Si}_2\text{O}_5$  sheet can combine with the other side thus giving a three-layer structure. This is made up of silicate,  $\text{Al}(\text{OH})_3$ , silicate. Pyrophyllite  $\text{Al}_2(\text{OH})_2[(\text{Si}_2\text{O}_5)_2]$  has this three-layer structure (Figure 13.16).

A layer of brucite  $\text{Mg}(\text{OH})_2$  may be combined with a  $\text{Si}_2\text{O}_5$  layer to form a two-layer structure. This gives the mineral chrysotile  $\text{Mg}_3(\text{OH})_4[\text{Si}_2\text{O}_5]$  (white asbestos), which is of considerable commercial importance. Alter-




Figure 13.16 Two and three layer structures

natively brucite may combine with two  $\text{Si}_2\text{O}_5$  layers forming a triple sheet structure called talc or soapstone  $\text{Mg}_3(\text{OH})_2[(\text{Si}_2\text{O}_5)_3]$ . These triple sheets are electrically neutral and there are no metal ions holding one sheet to the next so the structure breaks very easily, and is very soft. Soapstone has a slippery feeling (hence its name). It acts as a dry lubricant. World production of talc was 8.4 million tonnes in 1992. It is used mainly in making ceramics, paper and paint. Small amounts are used in cosmetics, as talc can be ground into a fine powder and used as talcum powder.

Substitution of atoms may occur in the triple-layer structures of the pyrophyllite types. If Si is partly replaced by Al (in tetrahedral holes) then the sheet becomes negatively charged. These charges are balanced by positively charged metal ions which are placed between the layers. This gives rise to the mica minerals. These are a group of minerals characterized by the fact that they are readily split into glistening transparent flexible sheets of varied colour. Muscovite has the formula  $\text{KAl}_2(\text{OH})_2[\text{AlSi}_3\text{O}_{10}]$  and is called white mica. Margarite has the formula  $\text{CaAl}_2(\text{OH})_2[\text{AlSi}_3\text{O}_{10}]$ . Substitution of atoms may also occur in talc  $\text{Mg}_3(\text{OH})_2[\text{Si}_4\text{O}_{10}]$ . Replacing Si by Al + K gives a mica called phlogopite  $\text{KMg}_3(\text{OH})_2[\text{AlSi}_3\text{O}_{10}]$ . Partial replacement of Mg by  $\text{Fe}^{II}$  gives the common mineral biotite  $\text{K}(\text{MgFe}^{II})_3(\text{OH})_2[\text{AlSi}_3\text{O}_{10}]$  or black mica. Micas are much harder than talc and the other minerals in this section because of the electrostatic attraction between the negatively charged triple sheets and the positive metal ions. However, this is still a point of weakness in the structure, and micas cleave between the layers quite readily. World production of mica was 214 000 tonnes in 1992. The main sources are the USA 40%, Soviet Union 16% and Canada 8%. Sheet mica is used as an electrical insulator and as a former on which to wind electric heating elements (e.g. in electric irons). It is also used in electrical capacitors and for windows in furnaces. Finely ground mica is used as a filler in plastics and rubber, in insulating board, and in polychromatic and glitter paint (e.g. for motor cars).

The clay minerals are formed from other silicates by weathering, or by hydrothermal processes, i.e. by the action of water under heat and pressure. They contain electrically neutral layers, e.g. kaolinite, and pyrophyllite. The clay minerals also include the montmorillonites which have negatively charged layers but the number of charges is much lower than in the micas.

Some, but not all, of the octahedral  $\text{Al}^{III}$  in pyrophyllite  $\text{Al}_2(\text{OH})_2[(\text{Si}_2\text{O}_5)_2]$  are replaced by  $\text{Mg}^{II}$ , giving  $(\text{Mg}_{0.33}, \text{Al}_{1.67})(\text{OH})_2[(\text{Si}_2\text{O}_5)_2]^{0.33-}$ . The triple sheets thus have a small negative charge, and  $1/3 \text{ M}^+$  or  $1/6 \text{ M}^{2+}$  must be incorporated between the layers. These metal ions can be hydrated, and the minerals are sometimes called hydromicas. Finely divided particles suspended in water have thixotropic properties. The particles are small plates with negative charges on the surface, and positive charges on the edge. The particles are free to move in water, and they arrange themselves  $+$  to  $-$  and thus give a semi-solid gel-like mass. If stirred the  $+/-$  attractions are broken, and the suspension becomes watery, that is of lower viscosity. They are used in thixotropic non-drip emulsion paints. These minerals can also act as ion exchangers. Fuller's Earth is a calcium montmorillonite. It is very absorbant: about 4.2 million tonnes were produced in 1992, mainly to decolorize and deodorize vegetable and mineral oils, fats and waxes. It is also used to mop up oil spills, and as litter for pet animals. It can act as an ion exchanger for  $\text{Ca}^{2+}$ , and replacement of  $\text{Ca}^{2+}$  by  $\text{Na}^+$  gives the mineral bentonite. This has marked thixotropic properties and is used as drilling mud, and in water-based emulsion paints (9.2 million tonnes of bentonite were produced in 1992).

If in talc  $\text{Mg}_3(\text{OH})_2[(\text{Si}_2\text{O}_5)_2]$  substitution of  $\text{Mg}^{2+}$  in the brucite sheet occurs, and if also replacement of  $\text{Si}^{4+}$  with  $\text{Al}^{3+}$  occurs in the silicate sheet, then vermiculites are formed. A typical formula is  $\text{Na}_x(\text{Mg}, \text{Al}, \text{Fe})_3(\text{OH})_2[(\text{Si}, \text{Al})_2\text{O}_5)_2] \cdot \text{H}_2\text{O}$ . If vermiculites are heated they dehydrate in an unusual way by extruding little worms: hence the name. These materials are porous and light in weight, and are used for packing and insulation, and as 'soil' for growing plants by ring culture. About half a million tonnes are produced each year.

### Three-dimensional silicates

Sharing all four corners of a  $\text{SiO}_4$  tetrahedron results in a three-dimensional lattice of formula  $\text{SiO}_2$  (quartz, tridymite, cristobalite etc.). These contain no metal ions, but three-dimensional structures can form the basis of silicate structures if there is isomorphous replacement of some of the  $\text{Si}^{4+}$  by  $\text{Al}^{3+}$  plus an additional metal ion. This gives an infinite three-dimensional lattice, and the additional cations occupy holes in the lattice. Replacing one quarter of the  $\text{Si}^{4+}$  in  $\text{SiO}_2$  with  $\text{Al}^{3+}$  gives a framework ion  $\text{AlSi}_3\text{O}_8^-$ . The cations are usually the larger metal ions such as  $\text{K}^+$ ,  $\text{Na}^+$ ,  $\text{Ca}^{2+}$  or  $\text{Ba}^{2+}$ . The smaller ions  $\text{Fe}^{3+}$ ,  $\text{Cr}^{3+}$  and  $\text{Mn}^{2+}$  which were common in the chain and sheet silicates do not occur in the three-dimensional silicates because the cavities in the lattice are too large. Replacements of one quarter or one half of the Si atoms are quite common, giving structures  $\text{M}^I[\text{AlSi}_3\text{O}_8]$  and  $\text{M}^{II}[\text{Al}_2\text{Si}_2\text{O}_8]$ . Such replacements result in three groups of minerals:

1. feldspars
2. zeolites
3. ultramarines.

The feldspars are the most important rock forming minerals and constitute two thirds of the igneous rocks. For example, granite is made up of feldspars with some micas and quartz. Feldspars are divided into two classes

<i>Orthoclase feldspars</i>		<i>Plagioclase feldspars</i>	
orthoclase	$K[AlSi_3O_8]$	albite	$Na[AlSi_3O_8]$
celsian	$Ba[Al_2Si_2O_8]$	anorthite	$Ca[Al_2Si_2O_8]$

The orthoclases are more symmetrical than are plagioclases as  $K^+$  and  $Ba^{2+}$  are just the right size to fit into the lattice whilst  $Na^+$  and  $Ca^{2+}$ , being smaller, allow distortion.

Zeolites have a much more open structure than the feldspars. The anion skeleton is penetrated by channels, giving a honeycomb-like structure. These channels are large enough to allow them to exchange certain ions. They can also absorb or lose water and other small molecules without the structure breaking down. Zeolites are often used as ion exchange materials, and as molecular sieves. Natrolite  $Na_2[Al_2Si_3O_{10}] \cdot 2H_2O$  is a natural ion exchanger. Permutit water softeners use sodium zeolites. Zeolites take  $Ca^{2+}$  ions from hard water and replace them by  $Na^+$ , thereby softening the water. The sodium zeolite natrolite gradually becomes a calcium zeolite, and eventually has to be regenerated by treatment with a strong solution of  $NaCl$  when the reverse process takes place. In addition to naturally occurring minerals, many synthetic zeolites have been made. Zeolites also act as molecular sieves by absorbing molecules which are small enough to enter the cavities, but not those which are too big to enter. They can absorb water,  $CO_2$ ,  $NH_3$  and  $EtOH$ , and they are useful for separating straight chain hydrocarbons from branched chain compounds. Some other zeolites are heulandite  $Ca[Al_2Si_7O_{18}] \cdot 6H_2O$ , chabazite  $Ca[Al_2Si_4O_{12}] \cdot 6H_2O$  and analcite  $Na[AlSi_3O_8] \cdot H_2O$ . Molecular sieves can be made with pores of appropriate size to remove small molecules selectively.

The mineral lapis lazuli is a splendid blue colour and was highly prized as a pigment for oil paintings in the middle ages. It contains ultramarine  $Na_8[(AlSiO_4)_6]S_2$ , in which the colour is produced by the polysulphide ion. The ultramarines are a group of related compounds, which contain no water, but do contain cations such as  $Cl^-$ ,  $SO_4^{2-}$  and  $S_2^{2-}$ . Some examples of ultramarines are

ultramarine	$Na_8[(AlSiO_4)_6]S_2$
sodalite	$Na_8[(AlSiO_4)_6]Cl_2$
noesan	$Na_8[(AlSiO_4)_6]SO_4$

The ultramarines are now produced synthetically. Ultramarine itself is made by igniting kaolinite, sodium carbonate and sulphur in the absence of air. The product may be green, blue or red depending on the particular polysulphide species present. Typically it is used as a blue pigment in oil based paints and ceramics. Before the days of detergents with artificial

brighteners, synthetic ultramarine was used as a blueing agent (called dolly blue) to make domestic washing appear white by masking any yellowness.

## SILICATES IN TECHNOLOGY

Many silicates are used as a direct result of their physical properties. For example, clay minerals are used for absorbing chemicals, micas are used for electrical insulation, asbestos is used for thermal insulation, agate and flint are used as hard or sharp surfaces, and a variety of gemstones are used for ornaments and jewellery.

Silicates are extremely important because the cement, ceramic and glass industries are based on their chemistry. Metallurgical extraction processes often produce silicates as waste products or slag, either because the minerals are silicates, or because the minerals contain silicate impurities. Some of the main technological applications are as follows.

### Alkali silicates

These are used mainly as glue, as described earlier.

### Cement

Both Portland and high alumina cement are described in Chapter 12.

### Ceramics

Ceramics are inorganic materials that can be made into a paste and shaped at normal temperatures: the shape is then 'fired' at a high temperature. Firing gives the product strength, either by sintering the crystallites together, or partly melting the paste. A number of carbides, oxides, and, in particular, clays, are treated in this way. The process is important for making bricks, tiles and pottery.

On heating, kaolinite  $\text{Al}_2(\text{OH})_4[\text{Si}_2\text{O}_5]$  loses water at  $500\text{--}600^\circ\text{C}$ , giving  $\text{Al}_2\text{O}_3 \cdot 2\text{SiO}_2$ , and at about  $950^\circ\text{C}$  forms a solid solution of mullite (approximate formula  $3\text{Al}_2\text{O}_3 \cdot 2\text{SiO}_2$ ) and  $\text{SiO}_2$ . This remains solid till at least  $1595^\circ\text{C}$ , and then softens only slowly. Since this is an iron-free clay, the product is white.

The porosity of the product depends on the temperature reached. If the firing temperature is high, the product does not absorb liquids. The presence of  $\text{Fe}^{3+}$  in the clay imparts a red or purple colour, and clays with a high proportion of  $\text{CaO}$  give a yellow or buff coloured product. Most ceramics except bricks and floor tiles are covered with a glassy coating called a glaze. This is done by dipping the article in an aqueous suspension of a heavy metal oxide such as  $\text{SnO}_2$  or  $\text{PbO}_2$  before firing. Pigments may be applied either before glazing (underglaze colour), or after firing and on top of the glaze, when a second firing is required.



### Glass

A small amount of glass is made of silica. This has excellent properties, but very high temperatures are needed to produce it. *Silica glass* is too expensive for general use, but is used in scientific instruments.

The temperature required for melting can be reduced by adding various oxides to the melt, thus obtaining *silicate glass*. A number of oxides may be used including  $\text{Na}_2\text{O}$ ,  $\text{K}_2\text{O}$ ,  $\text{MgO}$ ,  $\text{CaO}$ ,  $\text{BaO}$ ,  $\text{B}_2\text{O}_3$ ,  $\text{Al}_2\text{O}_3$ ,  $\text{PbO}$  and  $\text{ZnO}$ . Glass is a solid solution, and so its composition may vary. The amount of oxide added is not very large, and so the  $\text{SiO}_4$  tetrahedra have a significant role in the structure. If only  $\text{Na}_2\text{O}$  or  $\text{K}_2\text{O}$  were used, the glass would be water soluble. Normal domestic glass for windows is a *calcium alkali silicate glass* made by fusing the alkali metal carbonate,  $\text{CaCO}_3$  and  $\text{SiO}_2$ . (The carbonates decompose to oxides on heating.) If  $\text{Na}_2\text{CO}_3$  is used we obtain *soda glass*, which is also used for cheap laboratory glassware. Using  $\text{K}_2\text{CO}_3$  gives *potash glass*. Most of the  $\text{CaO}$  may be replaced by  $\text{PbO}$ , giving *lead glass*, which has a higher refractive index, and is used for making optical parts and glass ornaments. If  $\text{Al}_2\text{O}_3$  is used,  $\text{Al}^{3+}$  may be present in the structure as a free metal ion, or it may replace  $\text{Si}^{4+}$  in  $\text{SiO}_4$  tetrahedra. If  $\text{B}_2\text{O}_3$  is used  $\text{B}^{3+}$  replaces some  $\text{Si}^{4+}$  in the tetrahedral skeleton. *Borosilicate glasses* containing B, and sometimes Al as well, are important. They have a low coefficient of expansion, and can withstand heat changes without cracking. They contain less alkali and so are less prone to chemical attack. Such glasses are widely used for laboratory equipment as in Pyrex glassware.

Glass is produced in very large amounts. In 1991, 26.4 million tonnes of glass for bottles was produced, and in addition 7 million tonnes of sheet glass was produced. This was used mainly as windows.

Additives for fining, for decolorizing and for colouring may be used when making glass. Fining agents such as  $\text{NaNO}_3$  or  $\text{As}_2\text{O}_3$  are added to remove bubbles. The fining agent decomposes and gives off large bubbles of gases in the melt, which sweep out the small bubbles that are always formed. Decolorizing agents may be added to eliminate impurities and to obtain colourless glass.  $\text{Fe}^{3+}$  gives a yellow-brown colour, a mixture of  $\text{Fe}^{3+}$  and  $\text{Fe}^{2+}$  gives a green colour and  $\text{Fe}^{2+}$  gives a light blue colour. Other colouring agents may be added –  $\text{Co}^{2+}$  gives a deep blue and colloidal particles of Cu give ruby-red colours.  $\text{CaF}_2$  is sometimes added as a clouding agent to make *opal glass*.

## ORGANOSILICON COMPOUNDS AND THE SILICONES

### Organosilicon compounds


$\text{Si}-\text{C}$  bonds are almost as strong as  $\text{C}-\text{C}$  bonds. Thus silicon carbide  $\text{SiC}$  is extremely hard and stable. Many thousands of organosilicon compounds containing  $\text{Si}-\text{C}$  bonds have been made, most since 1950. Many of these are inert, and stable to heat (e.g.  $\text{SiPh}_4$  can be distilled in air at  $428^\circ\text{C}$ ). However, the vast range of organic compounds is not replicated by silicon for three main reasons.

1. Silicon has little tendency to bond to itself (catenate) whilst carbon has a strong tendency to do so. The largest chains formed by Si are contained in  $\text{Si}_{16}\text{F}_{34}$  and  $\text{Si}_8\text{H}_{18}$ , but these compounds are exceptional. This is related to the weakness of Si—Si bonds in contrast to the strength of C—C bonds (see Table 13.4).
2. Silicon does not form  $p\pi-p\pi$  double bonds, whilst carbon does so readily. (Note that a disilene  $\text{Me}_2\text{Si}=\text{SiMeH}$  has been isolated, but only by using matrix isolation methods with solid argon. Various transient reaction species with Si=C and Si=N bonds are known, and  $(\text{Me}_3\text{Si})_2\text{Si}=\text{C}(\text{OSiMe}_3)(\text{C}_{10}\text{H}_{15})$  exists as crystals at room temperature, and is stable in the absence of air. These are rare exceptions.)
3. Silicon forms a number of compounds containing  $p\pi-d\pi$  double bonds in which the silicon atom uses  $d$  orbitals (see later).

### Preparation of organosilicon compounds


There are several ways of forming Si—C bonds:

1. By a Grignard reaction




This is useful in the laboratory, or on a small scale.

2. Using an organolithium compound



This also is useful in the laboratory, and R may be alkyl or aryl.

3. By the Rochow 'Direct Process'. Alkyl or aryl halides react directly with a fluidized bed of silicon in the presence of large amounts (10%) of a copper catalyst.



This is the main industrial method for making methyl and phenyl chlorosilanes which are of considerable commercial importance in the production of silicones. The yield is about 70%, with varying amounts of other products:  $\text{MeSiCl}_3$  (10%) and  $\text{Me}_3\text{SiCl}$  (5%), and smaller amounts of  $\text{Me}_4\text{Si}$  and  $\text{SiCl}_4$  and others such as  $\text{MeSiHCl}_2$ . Both Grignard and direct methods yield a mixture of products, and very careful fractionation is important as the boiling points are close:  $\text{Me}_3\text{SiCl}$  ( $57.7^\circ\text{C}$ ),  $\text{MeSiCl}_3$  ( $66.4^\circ\text{C}$ ) and  $\text{Me}_2\text{SiCl}_2$  ( $69.6^\circ\text{C}$ ).


4. Catalytic addition of Si—H to an alkene. This is a useful general method, but is not applicable to making the methyl and phenyl silanes required by the silicone industry.

Except for  $\text{Ph}_3\text{SiCl}$  which is solid the products are volatile liquids. They are highly reactive and flammable and the reaction with water is strongly exothermic.


### Silicones

The silicones are a group of organosilicon polymers. They have a wide variety of commercial uses as fluids, oils, elastomers (rubbers) and resins. Annual production is estimated as about 300 000 tonnes/year. They are now produced on a larger scale than any other group of organometallic compounds.


The complete hydrolysis of  $\text{SiCl}_4$  yields  $\text{SiO}_2$ , which has a very stable three dimensional structure. The fundamental research of F. S. Kipping on the hydrolysis of alkyl substituted chlorosilanes led, not to the expected silicon compound analogous to a ketone but to long chain polymers called silicones.




The starting materials for the manufacture of silicones are alkyl or aryl substituted chlorosilanes. Methyl compounds are mainly used, though some phenyl derivatives are used as well. Hydrolysis of dimethyldichlorosilane  $(\text{CH}_3)_2\text{SiCl}_2$  gives rise to straight chain polymers and as an active OH group is left at each end of the chain polymerization continues and the chain increases in length.  $(\text{CH}_3)_2\text{SiCl}_2$  is therefore a chain building unit. Normally, high polymers are obtained.



Hydrolysis under carefully controlled conditions can produce cyclic structures, with rings containing three, four, five or six Si atoms:




tris cyclo-dimethylsiloxane




tetrakis cyclo-dimethylsiloxane

Hydrolysis of trimethylmonochlorosilane  $(\text{CH}_3)_3\text{SiCl}$  yields  $(\text{CH}_3)_3\text{SiOH}$  trimethylsilanol as a volatile liquid, which can condense, giving hexamethyldisiloxane. Since this compound has no OH groups, it cannot polymerize any further.




hexamethyldisiloxane

If some  $(\text{CH}_3)_3\text{SiCl}$  is mixed with  $(\text{CH}_3)_2\text{SiCl}_2$  and hydrolysed, the  $(\text{CH}_3)_3\text{SiCl}$  will block the end of the straight chain produced by  $(\text{CH}_3)_2\text{SiCl}_2$ . Since there is no longer a functional OH group at this end of the chain, it cannot grow any more at this end. Eventually the other end will be blocked in a similar way. Thus  $(\text{CH}_3)_3\text{SiCl}$  is a chain stopping unit, and the ratio of  $(\text{CH}_3)_3\text{SiCl}$  and  $(\text{CH}_3)_2\text{SiCl}_2$  in the starting mixture will determine the average chain size.



The hydrolysis of methyl trichlorosilane  $\text{RSiCl}_3$  gives a very complex cross linked polymer



In a similar way addition of a small amount of  $\text{CH}_3\text{SiCl}_3$  to the hydrolysis mixture produces a few cross links or provides a site for attaching other molecules. By controlled mixing of the reactants any given type of polymer can be produced.

Silicones are fairly expensive but have many desirable properties. They were originally developed as electrical insulators because they are more stable to heat than are organic polymers and if they do break down they do not produce conducting materials as carbon does. They are resistant to heat, oxidation and most chemicals. They are strongly water repellent, are good electrical insulators and have non stick properties and anti foaming properties. Their strength and inertness are related to two factors:

1. Their stable silica like skeleton of  $\text{Si}-\text{O}-\text{Si}-\text{O}-\text{Si}$ . The  $\text{Si}-\text{O}$  bond energy is very high ( $502 \text{ kJ mol}^{-1}$ )
2. The high strength of the  $\text{Si}-\text{C}$  bond

Their water repellency arises because a silicone chain is surrounded by organic side groups and looks like an alkane from the outside. Silicones may be liquids, oils, greases, elastomers (rubbers) or resins.

Straight chain polymers of 20 to 500 units are used as silicone fluids. They make up 63% of the silicones used. If they are made by hydrolysing a mixture of  $(\text{CH}_3)_2\text{SiCl}_2$  and  $(\text{CH}_3)_3\text{SiCl}$  then the chain lengths vary considerably. Commercially they are made by treating a mixture of tetrakis cyclo dimethylsiloxane  $(\text{Me}_2\text{SiO})_4$  and hexamethyl disiloxane  $(\text{Me})_3\text{SiOSi}(\text{Me})_3$  with 100%  $\text{H}_2\text{SO}_4$ . The cyclo compound provides chain building units and the hexamethylsiloxane provides chain stopping groups. The average chain length is determined by the ratio of these reactants. The  $\text{H}_2\text{SO}_4$  splits  $\text{Si}-\text{O}-\text{Si}$  bonds forming  $\text{Si}-\text{O}-\text{SO}_3\text{H}$  esters and  $\text{Si}-\text{OH}$ . The esters hydrolyse back to give  $\text{Si}-\text{O}-\text{Si}$  bonds. This process goes on repeatedly and results in the size of chains all becoming similar. The boiling point and viscosity increase with chain length giving compounds ranging from watery liquids to viscous oils and greases. The fluids are used as water repellents for treating masonry and buildings, glassware and fabrics. They are also included in car polish and shoe polish. Silicone fluids are non toxic and have a low surface tension. Addition of a few parts per million of a

silicone greatly reduces foaming in sewage disposal, textile dyeing, beer making (fermentation) and frothing of cooking oil in making potato crisps or chips. Silicone oils are used as dielectric insulating material in high voltage transformers. They are also used as hydraulic fluids. Methyl silicones can be used as light duty lubricating oil, but are not suitable for heavy duty applications like gearboxes, because the oil film breaks down under high pressure. Silicones with some phenyl groups are better lubricants. These oils can be mixed with lithium stearate soaps to give greases.

Silicone rubbers are made of long, straight chain polymers, (dimethylpolysiloxanes) between 6000 and 600 000 Si units long, mixed with a filler – usually finely divided  $\text{SiO}_2$  or occasionally graphite. They are usually produced by hydrolysis of dimethyldichlorosilane with KOH. Great care must be taken to exclude chain blocking and cross-linking groups. Rubbers make up about 25% of the silicones produced. Silicone rubbers are useful because they retain their elasticity from  $-90^\circ\text{C}$  to  $+250^\circ\text{C}$ , which is a much wider range than for natural rubber. They are also good electrical insulators. They may be vulcanized to give hard rubber as follows:

1. By oxidizing with a small amount of benzoyl peroxide which produces occasional cross-links (up to 1% of the Si atoms may be cross-linked).
2. By building a cross-linking unit into the chain.

The most heat-stable side groups are phenyl groups, followed by the methyl, ethyl and propyl groups in descending order of stability. On heating in air to  $350-400^\circ\text{C}$ , silicones are rapidly oxidized and cross-links are formed. The polymer becomes brittle and cracks, and low molecular weight polymers and cyclic structures are evolved. Strong heating in the absence of air causes silicones to soften and form volatile products, but oxidation and cross-linking do not occur.

Silicone resins are rigid polymers rather like bakelite. They are made by dissolving a mixture of  $\text{PhSiCl}_3$  and  $(\text{Ph})_2\text{SiCl}_2$  in toluene and hydrolysing with water. The partly polymerized product is washed to remove HCl, and can then be shaped or moulded. Finally the product is heated with a quaternary ammonium salt as catalyst to condense any remaining OH groups in the structure. The final product is extensively cross-linked. About 12% of silicones produced are resins. These resins are used as electrical insulators, often mixed with glass fibre for additional strength. They are used to make printed circuit boards and to encapsulate integrated circuit chips and resistors. They are also used as non-stick coatings for pans, and for moulds for car tyres and bread.

## HYDRIDES

All the elements form covalent hydrides, but the number of compounds formed and the ease with which they form differs greatly. Carbon forms a vast number of chain and ring compounds including:




1. The alkanes (paraffins)  $\text{C}_n\text{H}_{2n+2}$
2. The alkenes (olefines)  $\text{C}_n\text{H}_{2n}$

3 The alkynes (acetylenes)  $C_nH_{2n-2}$ 


## 4 Aromatic compounds

These are the basis of organic chemistry. There is a strong tendency to catenation (forming chains) because the C—C bond is very strong.


Silicon forms a limited number of saturated hydrides,  $Si_nH_{2n+2}$ , called the silanes. These may exist as straight chains or branched chains, containing up to eight Si atoms. Ring compounds are very rare. No analogues of alkenes or alkynes are known. Monosilane  $SiH_4$  is the only silicon hydride of importance.  $SiH_4$  and  $SiHCl_3$  were first made by treating an Al/Si alloy with dilute HCl. A mixture of silanes was prepared by hydrolysing magnesium silicide,  $Mg_2Si$ , with sulphuric or phosphoric acid. These compounds are colourless gases or volatile liquids. They are highly reactive and catch fire or explode in air. Apart from  $SiH_4$  they are thermally unstable. It only became possible to study them when A. Stock invented a method of handling reactive gases in a vacuum frame.




More recently monosilane has been prepared by reducing  $SiCl_4$  with  $Li[AlH_4]$ ,  $LiH$  or  $NaH$  in ether solution at low temperatures. This is a much better method, as it gives one product rather than a mixture and it gives a quantitative yield.




Silanes may also be prepared by direct reaction by heating Si or ferrosilicon with anhydrous  $HX$  or  $RX$  in the presence of a copper catalyst.



The silanes are much more reactive than the alkanes. The alkanes are chemically unreactive apart from reaction with the halogens, and burning in air. In contrast the silanes are strong reducing agents, ignite in air and explode in  $Cl_2$ . Pure silanes do not react with dilute acids or pure water in silica apparatus, but they hydrolyse readily in alkaline solutions, or even with the trace of alkali which leaches out from glass apparatus.




Compounds with Si—H bonds undergo an important hydrosilation reaction with alkenes, in the presence of a platinum catalyst. The reaction is similar to hydroboration, and the products may be used to make silicones.





The difference in behaviour between alkanes and silanes is attributed to several factors:

1. Pauling's electronegativity values are: C = 2.5, Si = 1.8, and H = 2.1. Thus the bonding electrons between C and H or Si and H are not equally shared, leaving a  $\delta^-$  charge on C and a  $\delta^+$  charge on Si. Thus Si is vulnerable to attack by nucleophilic reagents.



2. The larger size of Si makes it easier to attack.
3. Si has low energy *d* orbitals which may be used to form an intermediate compound, and thus lower the activation energy of the process.



Several germanium hydrides or germanes  $\text{Ge}_n\text{H}_{2n+2}$  are known up to  $n = 5$ . They are straight chain compounds and are colourless gases or volatile liquids. They are similar to the silanes, but are less volatile, less flammable and are unaffected by water or aqueous acids or alkalis.  $\text{GeH}_4$  can be made:



Stannane  $\text{SnH}_4$  is much less stable. It can be made by reducing  $\text{SnCl}_4$  with  $\text{Li}[\text{AlH}_4]$  or  $\text{Na}[\text{BH}_4]$ . It is a strong reducing agent. It is unaffected by water and dilute acids and alkali, but it reacts slowly with concentrated solutions. Distannane  $\text{Sn}_2\text{H}_6$  is known and is even less stable. No higher stannanes are known. Plumbane  $\text{PbH}_4$  is even less stable and even more difficult to prepare. The preparative methods used for the other hydrides fail. It has been made in trace amounts and at low concentrations by cathodic reduction and detected using a mass spectrometer.


## CYANIDES

The alkali metal cyanides, particularly NaCN, are made in quantity, about 120 000 tonnes/year. Until about 1965 it was made by the *Castner process* by high temperature reactions from sodamide.









Since 1965 hydrogen cyanide HCN has become commercially available (currently 300 000 tonnes/year) NaCN is made from this HCN was formerly prepared by acidification of NaCN or  $\text{Ca}(\text{CN})_2$



In the modern industrial processes a gas phase reaction occurs between  $\text{CH}_4$  and  $\text{NH}_3$  at about  $1200^\circ\text{C}$  in the presence of a catalyst





HCN is extremely poisonous. It has an abnormally high boiling point of  $26^\circ\text{C}$  because of hydrogen bonding. It is one of the weakest acids known weaker than HF. Over half the HCN produced is used to make the polymer methyl methacrylate and the remainder is used to make NaCN  $(\text{ClCN})_3$  and various cyanide complexes such as  $\text{K}_4[\text{Fe}(\text{CN})_6]$  and  $\text{K}_3[\text{Fe}(\text{CN})_6]$  and in the extraction of Ag and Au




HCN has been used as a non aqueous ionizing solvent

The cyanide ion is important in forming stable complexes particularly with the metals of the Cr Mn Fe Co Ni Cu and Zn groups. Two common complexes are ferrocyanides  $[\text{Fe}(\text{CN})_6]^{4-}$  and ferricyanides  $[\text{Fe}(\text{CN})_6]^{3-}$ . The later transition elements form stable cyanide complexes because they can use filled  $d$  orbitals for  $d\pi-p\pi$  backbonding in addition to the original  $\sigma$  coordinate bond  $\text{M} \leftarrow (\text{CN})^-$ . The bonding is similar to that in the carbonyls, and the  $\text{CN}^-$  ion acts as a  $\pi$  acceptor. The negative charge on  $\text{CN}^-$  makes it a stronger  $\sigma$  donor than CO, but the charge also weakens the effectiveness of  $\text{CN}^-$  as a  $\pi$  acceptor.


The extreme toxicity of cyanides is due to  $\text{CN}^-$  complexing with metals in enzymes and haemoglobin in the body, thus preventing normal metabolism. Besides forming many complexes analogous to halide complexes the cyanide ion often brings out the maximum coordination number of a metal. Thus  $\text{Fe}^{3+}$  forms  $[\text{FeCl}_4]^-$  with chloride ions but  $[\text{Fe}(\text{CN})_6]^{3-}$  with cyanide ions. Many metal ions such as  $\text{Cu}^+$ ,  $\text{Ni}^+$ ,  $\text{Mn}^+$ ,  $\text{Au}^+$  and  $\text{Mn}^{3+}$  which are too unstable to exist in solution, are quite stable when complexed with cyanide ions. The formation of complexes is important in the extraction of silver and gold, as the metals dissolve in a solution of NaCN in the presence of air, and form sodium argentocyanide or sodium aurocyanide, from which the metal is recovered by reduction with zinc



Cyanide ions may act as both complexing and reducing agents



In this reaction the cyanide ion is itself oxidized to cyanogen  $(\text{CN})_2$  in much the same way as  $\text{I}^-$  is oxidized to  $\text{I}_2$  by  $\text{Cu}^{2+}$ . In alkaline solution, cyanogen disproportionates into cyanide and cyanate ions.




The cyanate ion is isoelectronic with carbon dioxide; hence they have similar structures and are both linear.




## COMPLEXES


The ability to form complexes is favoured by a high charge, small size and availability of empty orbitals of the right energy. Carbon is in the second period and has a maximum of eight electrons in its outer shell. In four-covalent compounds of carbon, the second shell contains the maximum of eight electrons. Because this structure resembles that of a noble gas, these compounds are stable, and carbon does not form complexes. Four-covalent compounds of the subsequent elements can form complexes due to the availability of  $d$  orbitals, and they generally increase their coordination number from 4 to 6.



The VSEPR theory suggests that because there are six outer electron pairs these complexes will be octahedral. The valence bond theory requires that four covalent and two coordinate bonds are formed and give an octahedral structure. For example,  $[\text{SiF}_6]^{2-}$ :




The arguments over hybridizing  $d$  orbitals have been discussed in Chapter 4. The  $[\text{SiF}_6]^{2-}$  ion is usually formed from  $\text{SiO}_2$  and aqueous  $\text{HF}$



The  $[\text{SiF}_6]^{2-}$  complex is stable in water and alkali, but the others in the group are less stable.  $[\text{GeF}_6]^{2-}$  and  $[\text{SnF}_6]^{2-}$  are hydrolysed by alkali, and  $[\text{PbF}_6]^{2-}$  is hydrolysed by both alkali and water. Ge, Sn and Pb also form chloride complexes such as  $[\text{PbCl}_6]^{2-}$ , and oxalate complexes such as  $[\text{Pb}(\text{ox})_3]^{2-}$ .


Lead tetraacetate  $\text{Pb}(\text{CH}_3\text{COO})_4$  can be obtained as a colourless, solid by treating  $\text{Pb}_3\text{O}_4$  with glacial acetic acid. It is water sensitive, and is widely used as a selective oxidizing agent in organic chemistry. Its best known application is in the cleavage of 1,2-diols (glycols), as present, for example, in carbohydrates.



### INTERNAL $\pi$ BONDING USING $d$ ORBITALS

The compounds trimethylamine  $(\text{CH}_3)_3\text{N}$  and trisilylamine  $(\text{SiH}_3)_3\text{N}$  have similar formulae, but have totally different structures (Figure 13.17). In trimethylamine, the arrangement of electrons is as follows:

Electronic structure of nitrogen atom – ground state



three unpaired electrons form bonds with  $\text{CH}_3$  groups – tetrahedral arrangement of three bond pairs and one lone pair ( $sp^3$  hybridization)

In trisilylamine, three  $sp^2$  orbitals are used for  $\sigma$  bonding, giving a plane triangular structure. The lone pair of electrons occupy a  $p$  orbital at right angles to the plane triangle. This overlaps with empty  $d$  orbitals on each of the three silicon atoms, and results in  $\pi$  bonding, more accurately described as  $p\pi-d\pi$  bonding, because it is from a full  $p$  orbital to an empty  $d$  orbital. This shortens the bond lengths  $\text{N}-\text{Si}$ . Since the nitrogen no longer has a lone pair of electrons, the molecule has no donor properties. Similar  $p\pi-d\pi$  bonding is impossible in  $(\text{CH}_3)_3\text{N}$  because C does not possess  $d$  orbitals and hence this molecule is pyramidal. About 200 compounds are now thought to contain  $p\pi-d\pi$  bonds (Figure 13.18) (see Further Reading, Raabe and Michl).





Figure 13.17 Trimethylamine  $(\text{CH}_3)_3\text{N}$  and trisilylamine  $(\text{SiH}_3)_3\text{N}$







Figure 13.18  $p\pi-d\pi$  bonding in trisilylamine. (From Mackay and Mackay, *Introduction to Modern Inorganic Chemistry*, 4th ed., Blackie, 1989.)

## TETRAHALIDES

All the tetrahalides are known except  $PbI_4$ . They are typically covalent, tetrahedral, and very volatile. The exceptions are  $SnF_4$  and  $PbF_4$ , which have three-dimensional structures and are high melting ( $SnF_4$  sublimes at  $705^\circ C$ ,  $PbF_4$  melts at  $600^\circ C$ ). The elements after C have  $d$  orbitals available, and the Si-F, Si-Cl and Si-O bonds are stronger than the corresponding bonds with C. This is thought to be due to the donation of electrons from F, Cl or O to Si, giving rise to  $p\pi-d\pi$  bonding.

### Carbon

Tetrafluoromethane (carbon tetrafluoride)  $CF_4$  is an exceptionally unreactive gas. It can be made as follows:



Other fluorine compounds such as hexafluoroethane  $C_2F_6$  and tetrafluoroethylene  $C_2F_4$  are known. Under pressure  $C_2F_4$  polymerizes to  $(C_2F_4)_n$ , giving polytetrafluoroethylene or PTFE. This is a hard, white solid plastic with a greasy feel to the touch, and is much heavier (more dense) than one would expect. It is a good electrical insulator, and is chemically inert. It is expensive, and is used in the laboratory because of its inertness. It has a very low coefficient of friction and is used for coating non-stick pans and razor blades. Fluorocarbons are useful lubricants, solvents and insulators.








Figure 13.19  $p\pi-d\pi$  overlap in  $SiF_4$ .


Tetrachloromethane (carbon tetrachloride)  $\text{CCl}_4$  is manufactured mainly from carbon disulphide



$\text{CCl}_4$  is extensively used as a solvent, and for the preparation of Freons. It is also used in fire extinguishers, where the heavy vapour excludes dioxygen and thus puts the fire out



The carbon halides are not hydrolysed *under normal conditions* because they have no *d* orbitals, and cannot form a five coordinate hydrolysis intermediate. In contrast the silicon halides hydrolyse readily. Silicon has 3*d* orbitals available, and these may be used to coordinate  $\text{OH}^-$  ions or water as a first step in hydrolysis. In any atom there are always empty orbitals, but these are usually too high in energy to be used. If sufficient energy is provided by using superheated steam then  $\text{CCl}_4$  will hydrolyse



Phosgene is highly toxic, and was used as a poisonous gas in World War I. It is now made by combining CO and  $\text{Cl}_2$  with a C catalyst in sunlight, and is used to make isocyanates for the manufacture of polyurethanes


### Freons

Mixed chlorofluorocarbons (sometimes called CFCs) such as  $\text{CFCl}_3$ ,  $\text{CF}_2\text{Cl}_2$  and  $\text{CF}_3\text{Cl}$  are known as Freons. They are unreactive and non-toxic and are widely used as refrigeration fluids, as the propellant in aerosols, and for washing computer boards. At one time, nearly 700 000 tonnes of Freons were produced annually, though production had fallen to 100 000 tonnes in 1992. Despite being inert they cause environmental damage. Their use in aerosols was banned in the USA in 1980, and in Europe from 1990. They are still used in refrigerators, and a total ban on Freons in Europe is planned by the year 2000.

Freons are very much more effective 'greenhouse gases' in the atmosphere than is  $\text{CO}_2$ , though the amount of Freons present is extremely small. Much more seriously, the Freons have penetrated the upper atmosphere (5–20 miles high), and are causing damage to the ozone layer. There has been a loss of about 6% of the ozone between 1980 and 1990. A hole in the ozone layer has appeared over the South Pole, and a similar hole seems to be developing over the North Pole. The ozone layer is important as it filters the radiation from the sun and prevents most of the harmful UV

radiation from reaching the earth. Excessive exposure to UV radiation should be avoided as it causes skin cancer (melanoma) in humans.

In the upper atmosphere Freons undergo a photolytic reaction and produce free chlorine atoms (which are radicals). These react readily with ozone. The ClO radicals formed decompose slowly, re-forming chlorine radicals, which react with more ozone. . . and so on. The chlorine radicals do not recombine to form Cl<sub>2</sub>, because they need a three-body collision to dissipate the energy, and such collisions are extremely rare in the upper atmosphere. There is no effective sink for chlorine radicals. Once formed they are used again and again, so a small number of radicals make a very effective scavenger for ozone.



Overall reaction:  $2\text{O}_3 \rightarrow 3\text{O}_2$


Several less harmful aerosol propellants are now in use. Hydrofluorocarbons (HFCs) such as CH<sub>2</sub>FCF<sub>3</sub> and hydrochlorofluorocarbons (HCFCs) such as CHCl<sub>2</sub>CF<sub>3</sub> are being used as substitutes. They are also greenhouse gases, and may damage the ozone layer, but they do less damage than CFCs because they do not remain in the atmosphere for so long. The H atoms are attacked by hydroxyl radicals in the upper atmosphere, forming trifluoroacetic acid. The latter is not very toxic, and is eventually decomposed by bacteria in the soil. CO<sub>2</sub> is an alternative propellant, but when cold it has a low vapour pressure and is therefore no use for windscreen de-icers. Butane also gives difficulties, since it is flammable, and cannot be used with food.

### Silicon


The silicon halides can be prepared by heating either Si or SiC with the appropriate halogen. In marked contrast to the inertness of CF<sub>4</sub>, CCl<sub>4</sub> and the Freons, SiF<sub>4</sub> is readily hydrolysed by alkali.



The silicon halides are rapidly hydrolysed by water to give silicic acid.




In the case of the tetrafluoride, a secondary reaction occurs between the resultant HF and the unchanged SiF<sub>4</sub>, forming the hexafluorosilicate ion [SiF<sub>6</sub>]<sup>2-</sup>



$\text{SiCl}_4$  is commercially important. Small amounts are used to make ultra pure Si for transistors. Large quantities of  $\text{SiCl}_4$  are hydrolysed at a high temperature (in an oxy hydrogen flame) giving very finely powdered  $\text{SiO}_2$  rather than  $\text{Si(OH)}_4$ . This ultrafine  $\text{SiO}_2$  is used as a thixotropic agent in polyester and epoxy paints and resins, and as an inert filler in silicone rubber.

Other members of the series  $\text{Si}_n\text{X}_{2n+2}$  can be produced by pyrolysis (strong heating). These are either volatile liquids or solids. The longest chains known are  $\text{Si}_{16}\text{F}_{34}$ ,  $\text{Si}_6\text{Cl}_{14}$  and  $\text{Si}_4\text{Br}_{10}$ . The chains are longer than those formed in the hydrides. This is due to  $p\pi-d\pi$  bonding from full halogen  $p$  orbitals with  $d$  orbitals on Si.




### Germanium, tin and lead

Ge, Sn and Pb form two series of halides,  $\text{MX}_4$  and  $\text{MX}_2$ . With Ge the (+IV) oxidation state is the most stable, but with Pb the (+II) state is the most stable.

The tetrahalides are all colourless volatile liquids except for  $\text{GeI}_4$  and  $\text{SnI}_4$  which are bright orange solids. Compounds formed by the main group elements are normally white. Colour is associated with electrons being promoted from one energy level to another, and absorbing or emitting the energy difference between the two levels. This is common in the transition elements, where there are often unfilled energy levels in the  $d$  shell allowing promotion from one  $d$  level to another. In the main groups, the  $s$  and  $p$  electron shells are normally filled when a compound is formed, so promotion within the same shell is not possible. Promotion from one shell to another, for example from the  $2p$  to the  $3p$  level, involves so much energy that absorption lines would appear in the ultraviolet rather than in the visible region. Thus the tetrahalides would be expected to be white in colour. The orange colour of  $\text{SnI}_4$  is caused by the absorption of blue light, the reflected light thus containing a higher proportion of red and orange. The energy absorbed in this way causes the transfer of an electron from I to Sn. (This corresponds to the temporary reduction of Sn(IV) to Sn(III)). Since transferring an electron to another atom is transferring a charge such spectra are called *charge transfer spectra*. This occurs in  $\text{SnI}_4$  and  $\text{GeI}_4$  because the atoms have similar energy levels. This would be expected because they are close in the periodic table, and have similar sizes. Charge transfer spectra do not occur with the other halides.

$\text{GeCl}_4$  and  $\text{GeBr}_4$  are hydrolysed less readily.  $\text{SnCl}_4$  and  $\text{PbCl}_4$  hydrolyse in dilute solutions, but hydrolysis is often incomplete and can be repressed by the addition of the appropriate halogen acid.



In the presence of excess acid, halides of Si, Ge, Sn and Pb increase their coordination number from 4 to 6, and form complex ions, such as  $[\text{SiF}_6]^{2-}$ ,  $[\text{GeF}_6]^{2-}$ ,  $[\text{SnCl}_6]^{2-}$  and  $[\text{SnCl}_5]^-$ .  $\text{PbI}_4$  is not known, probably because of the oxidizing power of  $\text{Pb}(+IV)$  and the reducing power of  $\text{I}^-$ , which results in  $\text{PbI}_2$  always being formed.

### Catenated halides

Carbon forms a number of catenated halides, perhaps the best known being Teflon or polytetrafluoroethylene, which is described above. The polymers formed have chain lengths of several hundred carbon atoms.

Silicon forms polymers  $(\text{SiF}_2)_n$  and  $(\text{SiCl}_2)_n$  by passing the tetrahalide over heated silicon. These polymers decompose on heating into low molecular weight polymers (or oligomers) of formula  $\text{Si}_n\text{X}_{2n+2}$ . The longest chains known are  $\text{Si}_{16}\text{F}_{34}$ ,  $\text{Si}_6\text{Cl}_{14}$  and  $\text{Si}_4\text{Br}_{10}$ .


Germanium forms the dimer  $\text{Ge}_2\text{Cl}_6$ , but Sn and Pb do not form any catenated halides.

### DIHALIDES



There is a steady increase in the stability of dihalides:



$\text{SiF}_2$  can be made by high temperature reactions, and can be trapped by cooling in liquid  $\text{N}_2$ . When the product warms up, polymerization occurs giving a range of compounds up to  $\text{Si}_{16}\text{F}_{34}$ .




$\text{GeF}_2$  is a white solid made either by heating Ge with anhydrous HF, or from  $\text{GeF}_4$  and Ge. It has an unusual fluorine-bridged polymeric structure, based on a trigonal bipyramid.  $\text{GeF}_3$  units share two F atoms (giving the formula  $\text{GeF}_2$ ), and the Ge also forms a weaker interaction to another F, with a lone pair in the fifth position. These units are linked into infinite spiral chains.  $\text{SnF}_2$  and  $\text{SnCl}_2$  are white solids, and are obtained by heating Sn or SnO with gaseous HF or HCl. Stannous fluoride  $\text{SnF}_2$  was used together with tin pyrophosphate  $\text{Sn}_2\text{P}_2\text{O}_7$  in the original 'Crest' fluoride toothpaste. This is surprising as Sn is toxic, and NaF is now used instead. The crystal structure of  $\text{SnF}_2$  is made of  $\text{Sn}_4\text{F}_8$  tetramers. These form an eight-membered puckered ring  $-\text{Sn}-\text{F}-\text{Sn}-\text{F}-$ , with weaker interactions linking the rings together.  $\text{SnCl}_2$  partly hydrolyses in water, forming the basic chloride  $\text{Sn}(\text{OH})\text{Cl}$ .  $\text{SnF}_2$  and  $\text{SnCl}_2$  both dissolve in solutions containing halide ions.



$\text{Sn}^{2+}$  ions do occur in perchlorate solutions, but the stannous ion is readily oxidized by air to  $\text{Sn}^{IV}$  unless precautions are taken.  $\text{Sn}^{2+}$  ions are



hydrolysed by water mainly to  $[\text{Sn}_3(\text{OH})_4]^{2+}$  with small amounts of  $[\text{SnOH}]^+$  and  $[\text{Sn}_2(\text{OH})_2]^{2+}$ . The  $[\text{Sn}_3(\text{OH})_4]^{2+}$  ion is probably cyclic and the compounds  $[\text{Sn}_3(\text{OH})_4]\text{SO}_4$  and  $[\text{Sn}_3(\text{OH})_4](\text{NO}_3)_3$  are known. The compounds  $\text{PbX}_2$  are much more stable than  $\text{PbX}_4$ . Pb is the only element in the group with well defined cations. The salts  $\text{PbX}_2$  can all be made from a water soluble  $\text{Pb}^{2+}$  salt and the corresponding halide ion or halogen acid. The plumbous ion is partially hydrolysed by water



## CLUSTER COMPOUNDS

There is a well established tendency for the heavier members of Groups 14, 15 and 16 to form polyatomic ions. These may be chains, rings or clusters.

Reduction of Ge, Sn and Pb by Na in liquid ammonia gives metal ions containing several atoms. These have been shown to be metal clusters. Crystalline compounds containing such ions can be isolated by forming complexes with ethylenediamine or with cryptand 222 ligands. Examples include  $[\text{Na}(\text{cryptand } 222)]^+ [\text{Sn}_5]^-$ ,  $[\text{Na}(\text{cryptand } 222)]_2^+ [\text{Pb}_5]^-$ ,  $[\text{Na}_4(\text{en})_5\text{Ge}_9]$  and  $[\text{Na}_4(\text{en})_5\text{Sn}_9]$ . The shape of  $\text{M}_5$  clusters is a trigonal bipyramid and  $\text{M}_9$  clusters are uncapped square anti prisms. (The latter consists of a square anti prism i.e. a cube with the top face with four corners rotated  $45^\circ$  relative to the bottom face. Uncapped means an extra atom projects from one of the faces.)

## REACTION MECHANISMS

Many inorganic reactions such as double decomposition involve only ions and these occur virtually instantaneously. Typically organic reactions are slower because they involve breaking covalent bonds and they occur either by substituting one group for another or by adding on an extra group to give an intermediate which then eliminates another group to give the product.

The hydrolysis of  $\text{SiCl}_4$  is rapid because Si can use a  $d$  orbital to form a five coordinate intermediate and the reaction occurs by an  $\text{S}_\text{N}2$  mechanism (Figure 13.20). A lone pair of electrons from the oxygen is donated to an empty  $d$  orbital on Si forming a five coordinate intermediate which has a trigonal bipyramidal structure.





Figure 13.20 Hydrolysis of  $\text{SiCl}_4$



If the hydrolysis is performed on an asymmetrically substituted, and consequently optically active, silicon compound such as  $\text{MeEtPhSi}^*\text{Cl}$ , then Walden inversion will occur, resulting in inversion of the structure from *d* to *l* or vice versa (Figure 13.21). In a similar way, the reduction of  $\text{R}_1\text{R}_2\text{R}_3\text{Si}^*\text{Cl}$  with  $\text{Li}[\text{AlH}_4]$  to give  $\text{R}_1\text{R}_2\text{R}_3\text{Si}^*\text{H}$  also involves inversion of structure.

Other mechanisms are possible because the conversion of  $\text{R}_1\text{R}_2\text{R}_3\text{Si}^*\text{H}$






Figure 13.21 Walden inversion of structure.

to  $\text{R}_1\text{R}_2\text{R}_3\text{Si}^*\text{Cl}$  occurs with the retention of structure. If  $\text{R}_1\text{R}_2\text{R}_3\text{Si}^*\text{Cl}$  is dissolved in ether or  $\text{CCl}_4$  it is recovered unchanged, but dissolving in  $\text{CH}_3\text{CN}$  results in racemization.


## ORGANIC DERIVATIVES

The elements of this group have an extensive organometallic chemistry. The divalent state becomes increasingly stable and important on descending the group (the inert pair effect), yet rather surprisingly the organometallic derivatives of Sn and Pb all contain  $\text{M}^{\text{IV}}$  and not  $\text{M}^{\text{II}}$ .

The alkyl silicon chlorides are important as the starting materials for the manufacture of silicones. The silicone polymers have already been described. Tetra organic derivatives of Si, Ge, Sn and Pb may be prepared from the halides using Grignard or organolithium reagents.



Tetraethyl lead is produced in large amounts and used as an 'anti knock' additive to increase the octane number of petrol. The commercial preparation uses a sodium/lead alloy



Lead is poisonous to man, and burning petrol containing  $\text{PbEt}_4$  releases lead into the atmosphere. In 1974 about 230 000 tonnes of  $\text{PbEt}_4$  was produced in the USA, 55 000 tonnes in the UK, and an estimated total of 500 000 tonnes worldwide. At that time,  $\text{PbEt}_4$  was produced in larger tonnage than any other organometallic compound. Production in 1992 was 150 000 tonnes and is still declining as a result of legislation requiring that new cars must run on lead free petrol.

About 40 000 tonnes/year of organotin compounds  $\text{R}_2\text{SnX}_2$  and  $\text{R}_3\text{SnX}$  are used. About two thirds are used to stabilize PVC plastics and the remainder are used in agriculture to control fungi, and pests such as insects and larvae.

## FURTHER READING

- Abel, E. W. (1973) *Comprehensive Inorganic Chemistry*, Vol. 2. (Chapter 17 Tin, Chapter 18 Lead) Pergamon Press, Oxford.
- Abel, E. W. and Stone, F. G. (1969–1970) The chemistry of transition metal carbonyls. *Q. Rev. Chem. Soc.* Part I – Structural considerations, **23**, 325, Part II – Synthesis and reactivity, **24**, 498.
- Acc. Chem. Res.* (1992) **25**, 98–174 (the whole issue is devoted to articles on fullerenes).
- Ainscough, E. W. and Brodie, A. M. (1984) Asbestos – structures, uses and biological activities. *Education in Chemistry*, **21**, 173–175.
- Barrer, R. M. (1978) *Zeolites and Clay Minerals as Sorbents and Molecular Sieves*, Academic Press, London.
- Beaton, J. M. (1992) A paper pattern system for the construction of fullerene molecular models, *J. Chem. Ed.*, **69**, 610–612.
- Bode, H. (1977) *Lead Acid Batteries*, Wiley, New York.
- Bolin, B. (1970) The carbon cycle, *Scientific American*, September.
- Boo, W. O. J. (1992) An introduction to Fullerene structures, *J. Chem. Ed.*, **69**, 605–609.
- Breck, D. W. (1973) *Molecular Sieves*, Wiley, New York.
- Curl, R. F. and Smalley, R. E. (1991) Fullerenes, *Scientific American*, **265**(4), 32–41.
- Cusack, P. A. (1986) *Investigations Into Tin Based Flame Retardants and Smoke Suppressants*, International Tin Institute, London.
- Donovan, R. J. (1978) Chemistry and pollution of the stratosphere, *Education in Chemistry*, **15**, 110–113.
- Drake, J. E. and Riddle, C. (1970) Volatile compounds of the hydrides of silicon and germanium with the elements of Group V and VI, *Q. Rev. Chem. Soc.*, **24**, 263.
- Ebsworth, E. A. V. (1963) *Volatile Silicon Compounds*, Pergamon Press, Oxford.
- Elliott, S. and Rowland, F. S. (1987) Chlorofluorocarbons and stratospheric ozone, *J. Chem. Ed.*, **64**, 387–390.
- Emeleus, H. J. and Sharpe, A. G. (1973) *Modern Aspects of Inorganic Chemistry*, 4th ed. (Complexes of Transition Metals Chapter 20 Carbonyls) Routledge and Kegan Paul.
- Fleming, S. (1976) *Dating in Archaeology – a Guide to Scientific Techniques*, Dent London (Carbon dating etc.).
- Glasser, L. S. D. (1982) Sodium silicates. *Chemistry in Britain*, **33**–39.

- Greniger, D. *et al.* (1976) *Lead Chemicals*, International Lead Zinc Research Organization, New York. (Comprehensive data on lead and its compounds.)
- Griffith, W.P. (1973) *Comprehensive Inorganic Chemistry*, Vol. 4 (Chapter 46: Carbonyls, cyanides, isocyanides and nitrosyls), Pergamon Press, Oxford.
- Harrison, P.G. (ed.) (1989) *Chemistry of Tin*, Blackie, Glasgow.
- Harrison, R.M. and Laxen, D.P.H. (1981) *Lead Pollution*, Chapman and Hall, London.
- Hawkins, J.M., Meyer, A., Lewis, T.A., Loren, S. and Hollander, S.R. (1991) Crystal structure of osmylated C<sub>60</sub>: confirmation of the soccer ball framework, *Science*, **252**, 312–313.
- Hedberg, K., Berg, L., Bethune, D.S., Brown, C.S., Dorn, D.R., Johnson R.D., and de Vries, M. (1991) Bond lengths in free molecules of Buckminsterfullerene C<sub>60</sub>, from gas phase electron diffraction, *Science*, **254**, 410–412.
- Holliday, A.K., Hughes, G. and Walker, S.M. (1973) *Comprehensive Inorganic Chemistry*, Vol. I (Chapter 13: Carbon), Pergamon Press, Oxford.
- Hunt, C. (1987) Silicones reinvestigated – 50 years ago, *Education in Chemistry*, **24**, 7–11.
- Johansen, H.H. (1977) Recent developments in the chemistry of transition metal carbides and nitrides, *Survey Progr. Chem.*, **8**, 57–81.
- Johnson, B.F.G. (1976) The structures of simple binary carbonyls, *JCS Chem. Commun.*, 211–213.
- Kratschmer, W., Lamb, L.D., Fostiropoulos, K. and Huffman, D.R. (1990) Solid C<sub>60</sub>: a new form of carbon, *Nature*, **347**, 354–358.
- Kroto, H.W., Allaf, A.W. and Balm, S.P. (1991) C<sub>60</sub>: Buckminsterfullerene, *Chem. Rev.*, **91**, 1213–1235.
- Lu, S., Lü, Y., Kappes, M.M. and Ibers, J.A. (1991) The structure of the C<sub>60</sub> molecule. X-ray crystal structure determination of a twin at 110 K, *Science*, **254**, 408–410.
- Molina, M.J. and Rowland, F.S. (1974) Stratospheric sink for chlorofluoromethanes: chlorine catalyzed destruction of ozone, *Nature*, **249**, 810–812.
- Nicholson, J.W. (1989) The early history of organotin chemistry, *J. Chem. Ed.*, **66**, 621–622.
- Noll, W. with contributions by Glenz, O. and Hecht, G. (1968) *Chemistry and Technology of Silicones*. Academic Press, New York.
- Pearce, C.A. (1972) *Silicon Chemistry and Applications* (Monograph for Teachers, No. 20). Chemical Society, London.
- Pizey, J.S. (ed.) (1977) *Synthetic Reagents* (Chapter 4 by Butler R.N., Lead tetraacetate), John Wiley, Chichester.
- Raabe, G. and Michl, J. (1985) Multiple bonding to silicon, *Chem. Rev.*, **85**, 419–509.
- Rochow, E.G. (1973) *Comprehensive Inorganic Chemistry*, Vol. I (Chapter 15: Silicon), Pergamon Press, Oxford.
- Segal, D. (1989) Making advanced ceramics, *Chemistry in Britain*, **25**, 151, 154–156.
- Selig, H. and Ebert, L.B. (1980) Graphite intercalation compounds, *Adv. Inorg. Chem. Radiochem.*, **23**, 281–327. (A comprehensive review with over 300 references.)
- Shannon R.D. (1976) Revised effective ionic radii, *Acta Cryst.*, **A32**, 751–767. (The most up to date and generally accepted values for ionic radii.)
- Sharpe, A.G. (1976) *Chemistry of Cyano Complexes of the Transition Metals*, Academic Press, London.
- Thompson, R. (ed.) (1986) *The Modern Inorganic Chemicals Industry* (Chapter by Farmer, J.B., Inorganic cyanogen compounds; chapter by Barby, D., Soluble silicates and their derivatives), Special Publication No. 31, The Chemical Society, London.
- Thrush, B.A. (1977) The chemistry of the stratosphere and its pollution, *Endeavour*, **1**, 3–6.
- Toth, L.E. (1971) *Transition Metal Carbides and Nitrides*, Academic Press,

London

- Turner D (1980) Lead in petrol, *Chemistry in Britain* 16 312–314  
 Wells A F (1984) *Structural Inorganic Chemistry*, 5th ed (Chapter 23 Silicon), Oxford University Press Oxford  
 Wiberg, E and Amberger E (1971) *Hydrides of the Elements of Main Groups I–IV*, (Chapter 7 Silicon hydrides, Chapter 10 Lead hydrides), Elsevier, Amsterdam (Comprehensive review, over 700 references)  
 Woolf, A A (1993) Modelling molecular footballs, *Ed Chem*, 30, 76–77  
 Zuckerman, J J (ed) (1976) Organotin compounds New chemistry and applications, *Advances in Chemistry Series*, No 157, American Chemical Society

## PROBLEMS

- 1 What are the most common oxidation states of carbon and tin? Why is there any difference?
- 2 (a) Draw the structures of diamond and graphite  
 (b) Explain the difference in density between diamond and graphite  
 (c) Explain the difference in electrical conductivity between diamond and graphite  
 (d) Which allotropic form of C has the lowest energy?  
 (e) Why does the less stable form exist when the other form is thermodynamically favoured?
- 3 List as many ways as possible of making CO and CO<sub>2</sub>. What are they used for, and how are they detected?
- 4 Explain the bonding in CO and CO<sub>2</sub>
- 5 List the advantages and limitations of CO as a reducing agent in the extraction of metals from their oxides
- 6 Give equations to explain what reaction occurs when the following are heated (a) CaCO<sub>3</sub>, (b) CaCO<sub>3</sub> and SiO<sub>2</sub>, (c) CaCO<sub>3</sub> and C, (d) CaC<sub>2</sub> and N<sub>2</sub>
- 7 Explain what happens when CO<sub>2</sub> is passed into a solution of Ca(OH)<sub>2</sub>. What happens with excess CO<sub>2</sub>?
- 8 Give equations to show what reactions occur between CO and (a) O<sub>2</sub>, (b) S, (c) Cl<sub>2</sub>, (d) Ni, (f) Fe, (g) Fe<sub>2</sub>O<sub>3</sub>
- 9 Write the formulae for the mononuclear carbonyls formed by V, Cr, Fe and Ni. What is the effective atomic number rule? Which of these complexes obey the rule?
- 10 Explain with the aid of suitable diagrams how CO forms  $\sigma$  and  $\pi$  bonds in Ni(CO)<sub>4</sub>
- 11 Draw the structures of the polynuclear carbonyls Mn<sub>2</sub>(CO)<sub>10</sub>, Fe<sub>3</sub>(CO)<sub>9</sub>, Ru<sub>3</sub>(CO)<sub>12</sub> and Rh<sub>4</sub>(CO)<sub>12</sub>
- 12 Why does CaCO<sub>3</sub> dissolve slightly when excess CO<sub>2</sub> is passed into an aqueous slurry? Write equations to explain the effect of a small amount of CO<sub>2</sub> on lime water, and of an excess of CO<sub>2</sub>
- 13 Give reasons why CO<sub>2</sub> is a gas and SiO<sub>2</sub> is a solid
- 14 Explain the  $\pi$  bonding in CO<sub>2</sub>, CO<sub>3</sub><sup>2-</sup>, SO<sub>2</sub> and SO<sub>3</sub>

15. Why is  $\text{CCl}_4$  unaffected by water whilst  $\text{SiCl}_4$  is rapidly hydrolysed? Is  $\text{CCl}_4$  unreactive towards superheated steam?
16. Compare the shapes of the following pairs of molecules or ions, and suggest reasons for the differences in each pair:
  - (a)  $\text{CCl}_4$  and  $\text{TeCl}_4$
  - (b)  $\text{CO}_2$  and  $\text{NO}_2$
  - (c)  $\text{SiF}_4$  and  $\text{ICl}_4^-$
17. Why is  $\text{SnI}_4$  an orange coloured solid when  $\text{CCl}_4$  and  $\text{SiBr}_4$  are colourless liquids?
18. Starting with labelled  $\text{BaCO}_3$  (containing  $^{14}\text{C}$ ), how would you prepare labelled  $\text{Na}_2\text{CO}_3$ ,  $\text{CaCO}_3$ ,  $\text{CaC}_2$ ,  $\text{CaNCN}$ ,  $\text{C}_2\text{H}_2$ ,  $\text{CH}_3\text{OH}$ ,  $\text{CS}_2$  and  $\text{Ni}(\text{CO})_4$ .
19. How is  $\text{CS}_2$  made, and what is it used for?
20. How are  $\text{NaCN}$  and  $(\text{CN})_2$  made? What is  $\text{NaCN}$  used for?
21. Give two preparations for monosilane and compare its chemical properties with those of  $\text{CH}_4$ . Explain any differences.
22. Give three examples of Freons. How are they made, what are they used for, and how do they damage the environment?
23. Compare and contrast the structures of trimethylamine and tri-silylamine.
24. Draw the structures of six different types of silicate and give the name and formula of one example of each type.
25. Describe the uses of soluble sodium silicates.
26. Describe the use of zeolites as water softeners.
27. How are silicate impurities removed in the extraction of Al and Fe?
28. Describe two commercial methods for manufacturing alkyl substituted chlorosilanes. How are the reaction products separated and how may polymers with almost any specified properties be prepared from them?
29. How can silicates be detected in qualitative analysis?
30. What are the main ores of Sn and Pb, and how are the metals extracted?
31. Give equations to show the reactions between Sn and: (a)  $\text{H}_{(\text{aq})}^+$ , (b)  $\text{NaOH}$ , (c)  $\text{HNO}_3$ , (d)  $\text{O}_2$ , (e)  $\text{Cl}_2$ .
32. What are the main uses of lead?
33. What is red lead, and what is it used for?
34. What are the main sources of lead pollution, what can be done about them, and what are the effects of lead on humans?
35. How would you make lead tetra-acetate? What is its structure, and what is it used for?
36. Describe the changes in physical and chemical properties which may be observed in the elements C, Si, Ge, Sn and Pb. Give reasons for these changes.

Table 14.1 Electronic structures and oxidation states

Element	Electronic structure			Oxidation states*									
Nitrogen	N	[He]	2s <sup>2</sup> 2p <sup>3</sup>	-III	-II	-I	0	I	II	III	IV	V	
Phosphorus	P	[Ne]	3s <sup>2</sup> 3p <sup>3</sup>							III	V		
Arsenic	As	[Ar]	3d <sup>10</sup> 4s <sup>2</sup> 4p <sup>3</sup>							III	V		
Antimony	Sb	[Kr]	4d <sup>10</sup> 5s <sup>2</sup> 5p <sup>3</sup>							III	V		
Bismuth	Bi	[Xe]	4f <sup>14</sup> 5d <sup>10</sup> 6s <sup>2</sup> 6p <sup>3</sup>							III	V		

\* The most important oxidation states (generally the most abundant and stable) are shown in bold. Other well characterized but less important states are shown in normal type. Oxidation states that are unstable or in doubt are given in parentheses.

### ELECTRONIC STRUCTURE AND OXIDATION STATES

The elements of this group all have five electrons in their outer shell. They exhibit a maximum oxidation state of five towards oxygen by using all five outer electrons in forming bonds. The tendency for the pair of *s* electrons to remain inert (the inert pair effect) increases with increasing atomic weight. Thus only the *p* electrons are used in bonding and trivalency results. Valencies of three and five are shown with the halogens and with sulphur. The hydrides are trivalent. Nitrogen exhibits a very wide range of oxidation states: (-III) in ammonia NH<sub>3</sub>, (-II) in hydrazine N<sub>2</sub>H<sub>4</sub>, (-I) in hydroxylamine NH<sub>2</sub>OH, (0) in dinitrogen N<sub>2</sub>, (+I) in nitrous oxide N<sub>2</sub>O, (+II) in nitric oxide NO, (+III) in nitrous acid HNO<sub>2</sub>, (+IV) in nitrogen dioxide NO<sub>2</sub>, and (+V) in nitric acid HNO<sub>3</sub>. The negative oxidation states arise because the electronegativity of H = 2.1 and that for N = 3.0.

### OCCURRENCE, EXTRACTION AND USES

#### Nitrogen

Though dinitrogen comprises 78% of the earth's atmosphere, it is not a very abundant element in the earth's crust (only the thirty-third equal). Nitrates are all very soluble in water so they are not widespread in the

earth's crust, though deposits are found in a few desert regions. The largest is a 450-mile-long belt along the coast of northern Chile, where  $\text{NaNO}_3$  (Chile saltpetre) is found together with small amounts of  $\text{KNO}_3$ ,  $\text{CaSO}_4$  and  $\text{NaIO}_3$  under a thin layer of sand or soil. This provided the main source of nitrates prior to World War I, when synthetic processes were developed for the manufacture of nitrates from atmospheric dinitrogen. A major deposit of saltpetre  $\text{KNO}_3$  occurs in India.

Nitrogen is an essential constituent of proteins and amino acids. (An average composition of a protein is C = 50%, O = 25%, N = 17%, H = 7%, S = 0.5%, P = 0.5% by weight.) Nitrates and other nitrogen compounds are extensively used in fertilizers and explosives. Earlier this century  $\text{NaNO}_3$  was very important as a fertilizer. Bat guano was also

**Table 14.2** Abundance of the elements in the earth's crust, by weight

	ppm	Relative abundance
N	19	33 =
P	1120	11
As	1.8	52
Sb	0.20	64
Bi	0.008	71

important. (This is bat droppings, which were found in large amounts in limestone caverns in Kentucky, Tennessee and Carlsbad, New Mexico.) In the last 50 years these sources have largely been replaced by  $\text{NH}_3$  and  $\text{NH}_4\text{NO}_3$  from the huge synthetic ammonia and nitric acid industries.

Dinitrogen gas is used in large amounts as an inert atmosphere. This is mainly in the iron and steel and other metallurgical industries, and in oil refineries for purging catalytic cracking vessels, re-forming vessels and pipes. Liquid nitrogen is used as a refrigerant. Large amounts of  $\text{N}_2$  are used in the manufacture of ammonia and calcium cyanamide.  $\text{N}_2$  is obtained commercially by condensing air to the liquid state, and then fractionally distilling the liquid air.  $\text{N}_2$  has a lower boiling point than  $\text{O}_2$  and distils off first. Six industrial gases are obtained in this way:  $\text{N}_2$ ,  $\text{O}_2$ , Ne, Ar, Kr and Xe. A typical analysis of air is shown in Table 14.3.

World production of  $\text{N}_2$  is growing rapidly and exceeds 60 million tonnes/year. (This is largely because liquid  $\text{O}_2$  is essential for modern steel making processes, and  $\text{N}_2$  is produced at the same time.) About two thirds of the  $\text{N}_2$  is sold as gas. This may either be compressed in steel cylinders, or piped to where it is used. One third is sold as liquid  $\text{N}_2$ . Dinitrogen obtained in this way always contains traces of dioxygen and the noble gases. Commercial  $\text{N}_2$  normally contains up to 20 ppm of  $\text{O}_2$ , 'oxy-free'  $\text{N}_2$  contains up to 2 ppm  $\text{O}_2$ , and ultrapure  $\text{N}_2$  has no  $\text{O}_2$  but may have up to 10 ppm Ar.

A cylinder of  $\text{N}_2$  is the usual source of  $\text{N}_2$  in the laboratory, but samples of the gas may be obtained by making ammonium nitrite and then warming it.  $\text{N}_2$  is also obtained by oxidizing ammonia, for example with calcium




*continued overleaf*



Table 14.3 Abundance of different gases in dry air

	% by volume	b p of gas (°C)
N <sub>2</sub>	78.08	-195.8
O <sub>2</sub>	20.95	-183.1
Ar	0.934	-186.0
CO <sub>2</sub>	0.025–0.050	-78.4 (sublimes)
Ne	0.0015	-246.0
H <sub>2</sub>	0.0010	-253.0
He	0.00052	-269.0
Kr	0.00011	-153.6
Xe	0.0000087	-108.1

hypochlorite, bromine water or CuO. Small quantities of very pure N<sub>2</sub> may be obtained by carefully warming sodium azide NaN<sub>3</sub> to about 300°C. Thermal decomposition of NaN<sub>3</sub> is used to inflate the air bags used as safety devices in some cars.



### Phosphorus

Phosphorus is the eleventh most abundant element in the earth's crust. Phosphorus is essential for life, both as a structural material in higher animals, and in the essential metabolism of both plants and animals. About 60% of bones and teeth are Ca<sub>3</sub>(PO<sub>4</sub>)<sub>2</sub> or [3Ca<sub>3</sub>(PO<sub>4</sub>)<sub>2</sub> · CaF<sub>2</sub>], and an average person has 8 lbs (3.5 kg) of calcium phosphate in his body. Nucleic acids such as DNA and RNA contain the genetic material for each cell. These nucleic acids are made up of polyester chains of phosphates and sugars with organic bases (adenine, cytosine, thymine and guanine). Phosphorus, in the form of adenosine triphosphate ATP and adenosine diphosphate ADP, is of vital importance for the production of energy in cells. When water splits a phosphate group off ATP, forming ADP, 33 kJ mole<sup>-1</sup> of energy is released.

Vast amounts of phosphates are used in fertilizers. World production of phosphate rock was 145 million tonnes in 1992 (USA 32%, China 18%, Soviet Union 15%, and Morocco 13%). Most is mined as fluoroapatite [3Ca<sub>3</sub>(PO<sub>4</sub>)<sub>2</sub> · CaF<sub>2</sub>], but some is found as hydroxyapatite [3Ca<sub>3</sub>(PO<sub>4</sub>)<sub>2</sub> · Ca(OH)<sub>2</sub>] and chloroapatite [3Ca<sub>3</sub>(PO<sub>4</sub>)<sub>2</sub> · CaCl<sub>2</sub>] where OH<sup>-</sup> and Cl<sup>-</sup> are substituted for F<sup>-</sup> in the crystal structure. About 90% of phosphate rock is used directly to make fertilizers, and the remainder is used to make phosphorus and phosphoric acid.








Figure 14.1 Structure of adenosine triphosphate ATP.

World production of elemental P is about one million tonnes/year, but is declining. It is obtained by the reduction of calcium phosphate with C in an electric furnace at 1400–1500 °C. Sand (silica  $\text{SiO}_2$ ) is added to remove the calcium as a fluid slag (calcium silicate) and to drive off the phosphorus as  $\text{P}_4\text{O}_{10}$ . The  $\text{P}_4\text{O}_{10}$  is reduced to phosphorus by C. At this temperature gaseous phosphorus distils off, mainly as  $\text{P}_4$  but with some  $\text{P}_2$ . This is condensed to white phosphorus  $\text{P}_4$  by passing the gas through water.



About 85% of the elemental P produced is used to make very pure phosphoric acid  $\text{H}_3\text{PO}_4$ . About 10% is used to make  $\text{P}_4\text{S}_{10}$  (used making organo P—S compounds) and  $\text{P}_4\text{S}_3$  (which is used to make matches).




Other uses are for making  $\text{POCl}_3$  and phosphor bronze.

### Arsenic, antimony and bismuth

The elements As, Sb and Bi are not very abundant. Their most important source is as sulphides occurring as traces in other ores. They are well known because they are obtained as metallurgical by-products from roasting sulphide ores in a smelter. Care should be taken since As and Sb compounds are poisonous. The colours of the sulphide ores are distinctive.


Arsenic is obtained as  $\text{As}_2\text{O}_3$  in the flue dust from roasting  $\text{CuS}$ ,  $\text{PbS}$ ,  $\text{FeS}$ ,  $\text{CoS}$  and  $\text{NiS}$  in air. World production of  $\text{As}_2\text{O}_3$  was 47 000 tonnes in 1992. The oxide may be converted to As by reduction with C. The only common ores are arsenopyrites  $\text{FeAsS}$  (white–grey colour with metallic lustre), realgar  $\text{As}_4\text{S}_4$  (red–orange colour) and orpiment  $\text{As}_2\text{S}_3$  (yellow colour). The last two are found in volcanic areas. The element As is obtained commercially by heating arsenides such as  $\text{NiAs}$ ,  $\text{NiAs}_2$  or  $\text{FeAs}_2$ , or arsenopyrites  $\text{FeAsS}$ , to about 700 °C in the absence of air, when the As sublimes out.

*continued overleaf*



There are few uses for As metal, but it is used to alloy with lead to make the lead harder. Small amounts are used to dope semiconductors and make light emitting diodes. Arsenic compounds are generally made from  $\text{As}_2\text{O}_3$ . Their main uses, e.g. rat poison, in medicine to kill parasites, and for preventing wood rot, arise from their poisonous nature.

Antimony is obtained as  $\text{Sb}_2\text{O}_3$  in the flue dust from roasting  $\text{ZnS}$  ores. This is easily reduced to the metal with carbon. The most important ore is stibnite  $\text{Sb}_2\text{S}_3$  (indescent metal-like needles). The metal is obtained by fusing with iron:



Antimony metal is used in alloys with Sn and Pb. It is also used to electroplate steel to prevent rusting. World production of Sb was 84 000 tonnes in 1992. Antimony compounds are used as fire retardants in foam fillings for furniture and mattresses.

$\text{Bi}_2\text{O}_3$  is obtained from the flue dust from roasting  $\text{PbS}$ ,  $\text{ZnS}$  and  $\text{CuS}$ , and can be reduced to the metal with carbon. It also occurs as the minerals bismuthinite  $\text{Bi}_2\text{S}_3$  and bismite  $\text{Bi}_2\text{O}_3$ . Because of its low melting point bismuth metal can be cast in much the same way as lead. As, Sb and Bi metals are all too brittle to work. Bi is used in low melting alloys. (One use of these alloys is as a low melting plug for automatic fire sprinkler systems.) Other uses are in batteries, bearings, solder and ammunition. World production was 3600 tonnes in 1992.

## GENERAL PROPERTIES AND STRUCTURES OF THE ELEMENTS

### Nitrogen

The first element differs from the rest as was the case in the previous groups. Thus dinitrogen is a colourless, odourless, tasteless gas which is diamagnetic and exists as diatomic molecules  $\text{N}_2$ . The other elements are solids and exist as several allotropic forms. The  $\text{N}_2$  molecule contains

Table 14.4 Melting and boiling points

	Melting point (°C)	Boiling point (°C)
$\text{N}_2$	-210	-195.8
$\text{P}_4$	44	281
$\alpha\text{-As}$	816*	615 (sublimes)
$\alpha\text{-Sb}$	631	1587
$\alpha\text{-Bi}$	271	1564

\* At 38.6 atmospheres pressure


a triple bond  $\text{N}\equiv\text{N}$  with a short bond length of  $1.09 \text{ \AA}$ . This bond is very stable, and the dissociation energy is consequently very high ( $945.4 \text{ kJ mol}^{-1}$ ). Thus  $\text{N}_2$  is inert at room temperature, though it does react with Li, forming the nitride  $\text{Li}_3\text{N}$ . Other isoelectronic species such as CO,  $\text{CN}^-$  and  $\text{NO}^+$  are much more reactive than  $\text{N}_2$ , and this is because the bonds are partly polar, whilst in  $\text{N}_2$  they are not. At elevated temperatures  $\text{N}_2$  becomes increasingly reactive, and reacts directly with elements from Groups 2, 13 and 14, with  $\text{H}_2$  and with some of the transition metals.

Active nitrogen can be made by passing an electric spark through  $\text{N}_2$  gas at a low pressure. This forms atomic nitrogen, and the process is associated with a yellow–pink afterglow. Active nitrogen will react with a number of elements, and breaks many normally stable molecules.

### The nitrogen cycle

There is a continual turnover of nitrogen between the atmosphere, the soil, the sea and living organisms, which is estimated to be between  $10^8$  and  $10^9$  tonnes/year. This is called the nitrogen cycle. Consider the combined nitrogen in the soil: this is present as nitrates, nitrites and ammonium compounds. Losses of combined nitrogen from the soil occur for several reasons:

1. Plants absorb these compounds, and use them to make protoplasm, in order to grow. Plants may be eaten by animals, and animals may eat animals. Animals excrete nitrogenous wastes usually as urea or uric acid, which is returned to the soil. Death and decay eventually return all the nitrogen to the soil.
2. A group of denitrifying bacteria called *Denitrificans* convert nitrates into  $\text{N}_2$  or  $\text{NH}_3$  gases, which escape into the atmosphere. (Horse stables often smell of ammonia for this reason.)  $\text{NH}_3$  is returned to the soil by the first rainstorm, but  $\text{N}_2$  is not. Examples of denitrifying bacteria include *Pseudomonas* and *Achromobacter*.



3. A net loss of nitrogen compounds in the soil occurs through the drainage of surface water into the sea. There it supports marine plant life.
4. There is a small loss of NO and  $\text{NO}_2$  into the atmosphere from the burning of plants and coal, and from car exhausts. Though this may be unpleasant and produce smog locally, the amounts are small, and the nitrogen is returned to the soil when it rains.

There are net gains to the supply of combined nitrogen in the soil:

1. The largest gain is from nitrifying bacteria which fix  $\text{N}_2$  gas and turn it into nitrates or ammonium salts. This produces over 60% of the nitrogen gain. It is estimated that approximately 175 million tonnes of  $\text{N}_2$  are fixed annually by bacteria. This may be compared with 110

million tonnes of  $\text{NH}_3$  produced in 1992 by man (mainly by the Haber-Bosch process, but some from the distillation of coal) The most important genus of bacteria is *Rhizobium* These live symbiotically in the nodules of roots of plants in the family Leguminosae, i.e. peas, beans, clover and alder trees Other nitrifying bacteria live free in the soil, for example the blue-green bacteria *Anabena* and *Nostoc*, aerobic bacteria such as *Azotobacter* and *Beyerinckia*, and anaerobic bacteria such as *Clostridium pastorianum* These bacteria require traces of certain transition metals such as Mo, Fe, Co and Cu from the soil, and also B The nitrogen fixing enzyme 'nitrogenase' was isolated from *Clostridium pastorianum* in 1960 the same enzyme system is responsible for nitrogen fixation in the other bacteria too

Nitrogenase contains two components One is a Mo-Fe protein of molecular weight 220 000, containing 24-32 Fe, two Mo and a labile sulphide group, and the other is an Fe protein of molecular weight 60 000, containing four Fe and four S Nitrogenase reduces  $\text{N}_2$  to  $\text{NH}_3$  and the  $\text{N}_2$  is thought to form a complex with the Mo-Fe protein Bonding in  $\text{N}_2$  complexes favours end on coordination to the metal  $\sigma$  donation from N to the metal is more important than  $\pi$  back bonding from the metal to N Nitrogenase also reduces  $\text{N}_2\text{O}$ ,  $\text{RCN}$  and  $\text{N}_3^-$  to  $\text{NH}_3$  and it also reduces ethyne  $\text{C}_2\text{H}_2$  to ethene  $\text{C}_2\text{H}_4$

Blue-green bacteria can also fix  $\text{N}_2$ , and this is important in growing rice

The number of kilograms of nitrogen fixed in one acre of fertile soil in one year by different organisms is *Rhizobium* 120, blue-green bacteria 10, *Azotobacter* 0.1, *Clostridium* 0.1

- 2 About 20% comes from  $\text{NH}_4\text{NO}_3$ , which is used in vast quantities as an artificial fertilizer The Haber-Bosch process is used to fix atmospheric  $\text{N}_2$  and to make  $\text{NH}_3$ , and the Ostwald process is used to convert  $\text{NH}_3$  to  $\text{HNO}_3$  Reacting  $\text{NH}_3$  and  $\text{HNO}_3$  gives  $\text{NH}_4\text{NO}_3$
- 3 Relatively small amounts come from deposits such as Chile saltpetre  $\text{NaNO}_3$  which is mined and used as fertilizer
- 4 Minor gains come from the effects of lightning, and from photochemical changes Lightning may cause  $\text{N}_2$  and  $\text{O}_2$  in the air to form  $\text{NO}$  and  $\text{NO}_2$  This is essentially similar to the obsolete Birkeland-Eyde process The strong UV radiation in the upper atmosphere may cause similar photochemical changes, giving oxides of nitrogen The  $\text{NO}_2$  formed forms a very dilute solution of  $\text{HNO}_3$  in rain water.

### Phosphorus

Phosphorus is solid at room temperature White phosphorus is soft, waxy and reactive It reacts with moist air and gives out light (chemiluminescence) It ignites spontaneously in air at about  $35^\circ\text{C}$ , and is stored under water to prevent this It is highly toxic It exists as tetrahedral  $\text{P}_4$  molecules, and the tetrahedral structure remains in the liquid and gaseous states Above  $800^\circ\text{C}$   $\text{P}_4$  molecules in the gas begin to dissociate into  $\text{P}_2$




Figure 14.2 The structure of black phosphorus. The atoms are arranged in corrugated planes in crystalline black phosphorus (Van Wazer, J.R., *Phosphorus and Its Compounds*, Vol.I, Interscience, New York – London, 1958, p.121).

molecules, which have a bond energy of  $489.6 \text{ kJ mol}^{-1}$ . (This is only half the value for  $\text{N}_2$  because the orbitals in the third shell are much larger and give relatively poor  $p\pi-p\pi$  overlap.) If white phosphorus is heated to about  $250^\circ\text{C}$ , or a lower temperature in the presence of sunlight, then red phosphorus is formed. This is a polymeric solid, which is much less reactive than white phosphorus. It is stable in air and does not ignite unless it is heated to  $400^\circ\text{C}$ . It need not be stored under water. It is insoluble in organic solvents. Heating white phosphorus under high pressure results in a highly polymerized form of P called black phosphorus. This is thermodynamically the most stable allotrope. It is inert and has a layer structure (Figure 14.2). Other more doubtful allotropes have been reported.

#### Arsenic, antimony and bismuth

Solid As, Sb and Bi each exist in several allotropic forms. Arsenic vapour contains tetrahedral  $\text{As}_4$  molecules. A reactive yellow form of the solid resembles white phosphorus and is thought to contain tetrahedral  $\text{As}_4$  units. Sb also has a yellow form. All three elements have much less reactive metallic or  $\alpha$ -forms. These have layer structures, but the layers are

Table 14.5 Radii, ionization energies and electronegativity

	Covalent radius (Å)	Ionization energies ( $\text{kJ mol}^{-1}$ )			Pauling's electronegativity
		1st	2nd	3rd	
N	0.74	1403	2857	4578	3.0
P	1.10	1012	1897	2910	2.1
As	1.21	947	1950	2732	2.0
Sb	1.41	834	1590	2440	1.9
Bi	1.52	703	1610	2467	1.9

puckered. Another allotrope of Sb that is formed at high pressure has a hexagonal close packed structure. A high pressure form of Bi has a body centred cubic structure. Bismuth is unusual because the liquid expands when it forms the solid. This unusual behaviour is also found with Ga and Ge.





Figure 14.3 Layer structure of bismuth

## BOND TYPE

The majority of compounds formed by this group are covalent.



A coordination number of 4 is obtained if the lone pair is donated (that is used to form a coordinate bond) to another atom or ion. An example is the ammonium ion  $[\text{H}_3\text{N} \rightarrow \text{H}]^+$  (Figure 14.4).






Figure 14.4 Structure of ammonia

It requires too much energy to remove all five outer electrons so  $\text{M}^{5+}$  ions are not formed. However, Sb and Bi can lose just three electrons

forming  $M^{3+}$  ions, but the ionization energy is too high for the other elements to do so. Both  $SbF_3$  and  $BiF_3$  exist as ionic solids. The  $M^{3+}$  ions are not very stable in solution. They can exist in fairly strong acid solutions, but are rapidly hydrolysed in water to give the antimony oxide ion or bismuth oxide ion  $SbO^+$  and  $BiO^+$ . This change is reversed by adding 5M HCl.



Nitrogen atoms may gain three electrons and so attain a noble gas configuration, forming ionic nitrides containing the  $N^{3-}$  ion. It takes  $2125 \text{ kJ mol}^{-1}$  of energy to form  $N^{3-}$ . Thus ionic nitrides are formed only by metals which have low ionization energies and can form nitrides with high lattice energies ( $Li_3N$ ,  $Be_3N_2$ ,  $Mg_3N_2$ ,  $Ca_3N_2$ ). Though compounds such as  $Na_3P$  and  $Na_3Bi$  are known, these are not ionic.

Nitrogen cannot extend its coordination number beyond 4 because there are only four orbitals available in the second shell of electrons. Thus nitrogen cannot form complexes by accepting electron pairs from other ligands, but the subsequent elements can form such complexes. Thus the other elements may have coordination numbers of 5 or 6 as, for example, in  $PCl_5$  gas and  $[PCl_6]^-$ . The formation of complexes may be explained by involving one or two  $d$  orbitals in bonding. Thus  $sp^3d$  or  $sp^3d^2$  hybridization may occur. The  $3d$  orbitals of an isolated phosphorus atom are much larger than the  $3s$  and  $3p$  orbitals. This might at first sight suggest that the use of the  $3d$  orbitals for bonding is improbable. However, when electronegative ligands are placed round the phosphorus atom, the  $3d$  orbitals contract to nearly the same size as the  $3s$  and  $3p$  orbitals. (The extent of  $d$  orbital participation in  $\sigma$  bonding is controversial and is discussed in Chapter 4.)

Nitrogen also differs from the other elements in that it can form strong  $p\pi-p\pi$  multiple bonds. Because of this it forms several compounds which have no counterparts in the other elements. These include nitrates  $NO_3^-$ , nitrites  $NO_2^-$ , azides  $N_3^-$ , dinitrogen  $N_2$ , oxides of nitrogen  $N_2O$ ,  $NO$ ,  $NO_2$ ,  $N_2O_4$ , cyanides  $CN^-$ , and azo and diazo compounds. Because nitrogen can form multiple bonds, the oxides  $N_2O_3$  and  $N_2O_5$  are monomeric, whilst the trioxides and pentoxides of the other elements are dimeric.

## METALLIC AND NON-METALLIC CHARACTER

Group 15 shows the usual trend, that metallic character increases on descending the group. Thus N and P are non-metals, As and Sb are metalloids, which show many metallic properties, and Bi is a true metal. The increasing metallic character is shown by the following:



- 1 In the appearance and structures of the elements
- 2 By their tendency to form positive ions
- 3 By the nature of their oxides. Metallic oxides are typically basic, and non metallic oxides are acidic. Thus the normal oxides of N and P are strongly acidic, whereas those of As and Sb are amphoteric and that of Bi is largely basic
- 4 The electrical resistivity of the metallic forms ( $\alpha$ -As 33,  $\alpha$  Sb 39 and  $\alpha$ -Bi 106  $\mu\text{ohm cm}$ ) are much lower than for white phosphorus ( $1 \times 10^{17} \mu\text{ohm cm}$ ), indicating an increase in metallic properties. However, the resistivity values are higher than the values for a good conductor such as Cu, 1.67  $\mu\text{ohm cm}$ , and higher than Sn, 11, and Pb, 20  $\mu\text{ohm cm}$  in the adjacent group (See Appendix J)

## REACTIVITY

Dinitrogen is relatively unreactive, which is why it has accumulated in such large amounts in the atmosphere

White phosphorus catches fire when exposed to air, burning to form  $\text{P}_4\text{O}_{10}$ . It is stored under water to prevent this. Red phosphorus is stable in air at room temperature, though it reacts on heating.

Arsenic is stable in dry air, but tarnishes in moist air, giving first a bronze then a black tarnish. When heated in air it sublimes at  $615^\circ\text{C}$  and forms  $\text{As}_4\text{O}_6$ , not  $\text{As}_4\text{O}_{10}$ . Strong heating in dioxygen can give either of these oxides, depending on the amount of dioxygen present. This reluctance to attain the maximum oxidation state for the group is found in the elements Ga, As, Se and Br, that is in the elements immediately following the filling of the first  $d$  shell.  $\text{As}_4\text{O}_{10}$  and  $\text{H}_3\text{AsO}_4$  are used as oxidizing agents in volumetric analysis.

Sb is less reactive, and is stable towards water and to air at room temperature. On heating in air it forms  $\text{Sb}_4\text{O}_6$ ,  $\text{Sb}_4\text{O}_8$  or  $\text{Sb}_4\text{O}_{10}$ . Bi forms  $\text{Bi}_2\text{O}_3$  on heating.


## HYDRIDES

The elements all form volatile hydrides of formula  $\text{MH}_3$ , which are all poisonous, foul smelling gases. On descending the group from  $\text{NH}_3$  to  $\text{BiH}_3$ ,



- 1 The hydrides become increasingly difficult to prepare
- 2 Their stability decreases
- 3 Their reducing power increases
- 4 The ease of replacing the hydrogen atoms by other groups such as Cl or Me decreases
- 5 Their ability to act as electron donors, using the lone pair of electrons for coordinate bond formation, decreases

**Ammonia NH<sub>3</sub>**




NH<sub>3</sub> is a colourless gas with a pungent odour. The gas is quite poisonous. It dissolves very readily in water with the evolution of heat. At 20°C and one atmosphere pressure 53.1 g NH<sub>3</sub> dissolves in 100 g water. This corresponds to 702 volumes of NH<sub>3</sub> dissolving in 1 volume of H<sub>2</sub>O. In solution ammonia forms ammonium hydroxide NH<sub>4</sub>OH, and behaves as a weak base.




NH<sub>3</sub> and NH<sub>4</sub>OH both react with acids, forming ammonium salts. These salts resemble potassium salts in solubility and in their crystal structures. Like the Group 1 salts, ammonium salts are typically colourless. There are some differences. Ammonium salts are usually slightly acidic if they have been formed with strong acids such as HNO<sub>3</sub>, HCl and H<sub>2</sub>SO<sub>4</sub>, since NH<sub>4</sub>OH is only a weak base. Ammonium salts decompose quite readily on heating. If the anion is not particularly oxidizing (e.g. Cl<sup>-</sup>, CO<sub>3</sub><sup>2-</sup> or SO<sub>4</sub><sup>2-</sup>) then ammonia is evolved:



If the anion is more oxidizing (e.g. NO<sub>2</sub><sup>-</sup>, NO<sub>3</sub><sup>-</sup>, ClO<sub>4</sub><sup>-</sup>, Cr<sub>2</sub>O<sub>7</sub><sup>2-</sup>) then NH<sub>4</sub><sup>+</sup> is oxidized to N<sub>2</sub> or N<sub>2</sub>O.




NH<sub>3</sub> burns in dioxygen with a pale yellow flame:



The same reaction occurs in air, but the heat of reaction is insufficient to maintain combustion unless heat is supplied, for example in a gas flame. Certain mixtures of NH<sub>3</sub>/O<sub>2</sub> and NH<sub>3</sub>/air are explosive.


NH<sub>3</sub> is prepared in the laboratory by heating an ammonium salt with NaOH. This is a standard test in the laboratory for NH<sub>4</sub><sup>+</sup> compounds.



The NH<sub>3</sub> evolved may be detected:

1. By its characteristic smell.
2. By turning moist litmus paper blue.
3. By forming dense white clouds of NH<sub>4</sub>Cl with the stopper from a bottle of HCl.
4. By forming a yellow–orange–brown precipitate with Nessler's solution.

World production of  $\text{NH}_3$  was 110 million tonnes in 1992. Most was manufactured synthetically from  $\text{H}_2$  and  $\text{N}_2$  by the Haber–Bosch process (see later) but some was obtained from coal gas purification and during coke production from coal. Ammonia can also be obtained from the hydrolysis of calcium cyanamide,  $\text{CaNCN}$ . Calcium cyanamide is usually used as a fertilizer, and this reaction occurs slowly in the soil



( $\text{CaNCN}$  is also used to make melamine, urea and thiourea – See Chapter 11.) In the past when town gas was made as a fuel by dry distilling coal in the absence of air, any nitrogenous compounds in coal were converted into  $\text{NH}_3$ . This  $\text{NH}_3$  was obtained as a by-product

### Ammonium salts


Ammonium salts are all very soluble in water. They all react with  $\text{NaOH}$ , liberating  $\text{NH}_3$ . The  $\text{NH}_4^+$  ion is tetrahedral. Several ammonium salts are important.

$\text{NH}_4\text{Cl}$  is well known. At one time it was obtained by heating camel dung.  $\text{NH}_4\text{Cl}$  is easily purified by sublimation. It can be recovered as a by-product from the Solvay process. It is used in 'dry batteries' of the Leclanché type. It is also used as a flux when tinning or soldering metals, since many metal oxides react with  $\text{NH}_4\text{Cl}$  forming volatile chlorides, thus leaving a clean metal surface.

$\text{NH}_4\text{NO}_3$  is used in enormous amounts as a nitrogenous fertilizer. It is deliquescent. Because it can cause explosions it is often mixed with  $\text{CaCO}_3$  or  $(\text{NH}_4)_2\text{SO}_4$  to make it safe. It is also used as an explosive, since on strong heating (above  $300^\circ\text{C}$ ) or with a detonator, very rapid decomposition occurs. The solid has almost zero volume and it produces seven volumes of gas; this causes the explosion.




Smaller amounts of  $(\text{NH}_4)_2\text{SO}_4$  are also used as a fertilizer. At one time  $(\text{NH}_4)_2\text{SO}_4$  was obtained as a by-product from making coal gas (town gas). Since natural gas has become available in developed countries, town gas is no longer made.  $(\text{NH}_4)_2\text{SO}_4$  is made by passing  $\text{NH}_3$  and  $\text{CO}_2$  gases into a slurry of  $\text{CaSO}_4$  in water.




Small amounts of diammonium hydrogen phosphate  $(\text{NH}_4)_2\text{HPO}_4$  and ammonium dihydrogen phosphate  $\text{NH}_4\text{H}_2\text{PO}_4$  are used as fertilizers. They are also used for fireproofing wood, paper and textiles.  $\text{NH}_4\text{ClO}_4$  is used as an oxidizing agent in solid fuel rocket propellants.

**Phosphine  $\text{PH}_3$** 

Phosphine  $\text{PH}_3$  is a colourless and extremely toxic gas, which smells slightly of garlic or bad fish. It is highly reactive. It can be formed either by hydrolysing metal phosphides such as  $\text{Na}_3\text{P}$  or  $\text{Ca}_3\text{P}_2$  with water, or by hydrolysing white phosphorus with  $\text{NaOH}$  solution.



$\text{PH}_3$ , unlike  $\text{NH}_3$ , is not very soluble in water: aqueous solutions are neutral. It is more soluble in  $\text{CS}_2$  and other organic solvents. Phosphonium salts such as  $[\text{PH}_4]^+\text{Cl}^-$  can be formed, but require  $\text{PH}_3$  and anhydrous  $\text{HCl}$  (in contrast to the ready formation of  $\text{NH}_4\text{X}$  in aqueous solution). Pure  $\text{PH}_3$  is stable in air, but it catches fire when heated to about  $150^\circ\text{C}$ .




$\text{PH}_3$  frequently contains traces of diphosphine  $\text{P}_2\text{H}_6$  which cause it to catch fire spontaneously. This is the origin of the flickering light called will-o'-the-wisp, which is sometimes seen in marshes.

**Arsine  $\text{AsH}_3$ , stibine  $\text{SbH}_3$  and bismuthine  $\text{BiH}_3$** 

The bond energy (Table 14.6) and the stability of the hydrides both decrease on descending the group. Consequently, arsine  $\text{AsH}_3$ , stibine  $\text{SbH}_3$  and bismuthine  $\text{BiH}_3$  are only obtained in small amounts.  $\text{AsH}_3$  and  $\text{SbH}_3$  are both very poisonous gases.  $\text{AsH}_3$ ,  $\text{SbH}_3$  and  $\text{BiH}_3$  can be prepared by hydrolysing binary metal compounds such as  $\text{Zn}_3\text{As}_2$ ,  $\text{Mg}_3\text{Sb}_2$  or  $\text{Mg}_3\text{Bi}_2$  with water or dilute acid.  $\text{AsH}_3$  and  $\text{SbH}_3$  are formed in Marsh's test for As and Sb compounds. Before the use of instruments for analysis, this test was used as a forensic test. Practically all As or Sb compounds can be reduced with Zn and acid, forming  $\text{AsH}_3$  or  $\text{SbH}_3$ . The gaseous hydrides are passed through a glass tube heated with a Bunsen burner.  $\text{SbH}_3$  is less stable than  $\text{AsH}_3$ : hence it decomposes before passing through the flame, and gives a metallic mirror on the glass tube.  $\text{AsH}_3$  is more stable, and requires stronger heating to make it decompose. Thus  $\text{AsH}_3$  gives a mirror after the flame.

**Structure of the hydrides**

The structure of ammonia may either be described as pyramidal, or tetrahedral with one position occupied by a lone pair (Figure 14.4). This shape is predicted using the VSEPR theory since there are four electron pairs in the outer shell. These comprise three bonding pairs and one lone pair. The repulsion between a lone pair and a bond pair of electrons always exceeds that between two bond pairs. Thus the bond angles are reduced from  $109^\circ 27'$  to  $107^\circ 48'$ , and the regular tetrahedral shape is slightly distorted.



The hydrides  $\text{PH}_3$ ,  $\text{AsH}_3$  and  $\text{SbH}_3$  would be expected to be similar. However, the bond pairs of electrons are much further away from the central atom than they are in  $\text{NH}_3$ . Thus the lone pair causes even greater distortion in  $\text{PH}_3$ ,  $\text{AsH}_3$  and  $\text{SbH}_3$ . The bond angle decreases to  $91^\circ 18'$  (Table 14.6). These bond angles suggest that in  $\text{PH}_3$ ,  $\text{AsH}_3$ ,  $\text{SbH}_3$  and  $\text{BiH}_3$  the orbitals used for bonding are close to pure  $p$  orbitals.

The melting and boiling points of the hydrides increase from  $\text{PH}_3$  through  $\text{AsH}_3$  to  $\text{SbH}_3$ . The values for  $\text{NH}_3$  seem out of line with this trend: one might have expected the boiling point of  $\text{NH}_3$  to be  $-110^\circ\text{C}$  or  $-120^\circ\text{C}$ . The reason why  $\text{NH}_3$  has a higher boiling point and is much less volatile than expected is that it is hydrogen bonded in the liquid state. The other hydrides do not form hydrogen bonds.

These hydrides are strong reducing agents and react with solutions of metal ions to give phosphides, arsenides and stibnides. They are flammable and extremely poisonous.

Table 14.6 Some properties of the hydrides

	m.p. ( $^\circ\text{C}$ )	b.p. ( $^\circ\text{C}$ )	Bond energy ( $\text{kJ mol}^{-1}$ )	Bond angle	Bond length ( $\text{\AA}$ )
$\text{NH}_3$	-77.8	-34.5	N-H = 389	H-N-H = $107^\circ 48'$	1.017
$\text{PH}_3$	-133.5	-87.5	P-H = 318	H-P-H = $93^\circ 36'$	1.419
$\text{AsH}_3$	-116.3	-62.4	As-H = 247	H-As-H = $91^\circ 48'$	1.519
$\text{SbH}_3$	-88	-18.4	Sb-H = 255	H-Sb-H = $91^\circ 18'$	1.707

### Donor properties

$\text{NH}_3$  can donate its lone pair of electrons quite strongly to form complexes. Thus ammonia forms ammonium  $\text{NH}_4^+$  salts, and also coordination complexes with metal ions from the Co, Ni, Cu and Zn groups, for example the  $[\text{Co}(\text{NH}_3)_6]^{3+}$  ion, very readily.

$\text{PH}_3$  acts as an electron donor and forms numerous complexes such as  $[\text{F}_3\text{B} \leftarrow \text{PH}_3]$ ,  $[\text{Cl}_3\text{Al} \leftarrow \text{PH}_3]$  and  $[\text{Cr}(\text{CO})_3(\text{PH}_3)_3]$ . A variety of other

trivalent phosphorus compounds such as  $\text{PF}_3$ ,  $\text{PCl}_3$ ,  $\text{PEt}_3$ ,  $\text{P(OR)}_3$  and  $\text{PPh}_3$  also form complexes, which in some ways resemble complexes with CO. Thus the lone pair on P is used to form the coordinate bond to an empty orbital on the B or metal (a  $\sigma$  bond). In the case of metals, this original coordinate bond may be reinforced by back bonding from  $\pi$  overlap of a filled  $d$  orbital on the metal with an empty  $d$  orbital on P.

The donor properties of the other hydrides are very weak, and they have little or no tendency to form coordinate bonds.

In  $\text{NH}_3$  the lone pair occupies an  $sp^3$  hybrid orbital. In  $\text{AsH}_3$  and  $\text{SbH}_3$  the bond angles become close to  $90^\circ$  which suggests that the orbitals used for M—H bonding are almost pure  $p$  orbitals. If the three  $p$  orbitals are used for M—H bonding, the lone pair must occupy a spherical  $s$  orbital. This is larger, and less directional, and hence less effective for forming a coordinate bond. This means that any  $\sigma$  bond will be very weak. In addition the  $4d$  and  $5d$  orbitals are too large for effective  $\pi$  back bonding. These two factors account for the difference in complexing power between the hydrides.


Nitrogen forms several hydrides (see Table 14.7).

Table 14.7 Hydrides of nitrogen

Formula	Name	Oxidation state
$\text{NH}_3$	Ammonia	−III
$\text{N}_2\text{H}_4$	Hydrazine	−II
$\text{NH}_2\text{OH}$	Hydroxylamine	−I


#### Hydrazine $\text{N}_2\text{H}_4$

Hydrazine is a covalent liquid, which fumes in air, and smells similar to  $\text{NH}_3$ . Pure hydrazine burns readily in air with the evolution of a large amount of heat.




The methyl derivatives  $\text{MeNHNH}_2$  and  $\text{Me}_2\text{NNH}_2$  are mixed with  $\text{N}_2\text{O}_4$  and used as a rocket fuel in the space shuttle, in guided missiles, and (earlier) in the Apollo lunar modules.


$\text{N}_2\text{H}_4$  is a weak base and reacts with acids, forming two series of salts. The salts are white ionic crystalline solids, and are soluble in water.



When dissolved in water (in neutral or basic solutions) hydrazine or its salts are powerful reducing agents. They are used to produce silver and copper mirrors and to precipitate the platinum metals. Hydrazine also reduces  $\text{I}_2$  and  $\text{O}_2$ .




In acidic solutions, hydrazine usually behaves as a mild reducing agent, though powerful reducing agents can reduce  $\text{N}_2\text{H}_4$  to  $\text{NH}_3$ , thus causing  $\text{N}_2\text{H}_4$  to be oxidized




Hydrazine may act as an electron donor. The N atoms have a lone pair of electrons, which can form coordinate bonds to metal ions such as  $\text{Ni}^{2+}$  and  $\text{Co}^{2+}$ .


World production of hydrazine is nearly 20 000 tonnes/year. Most is used as rocket fuel. Other uses are the manufacture of 'blowing agents' (for producing blown plastics), as agricultural chemicals, and to treat the boiler feed water in power stations to prevent oxidation of the boiler and pipes. In the laboratory phenylhydrazine is used to characterize carbonyl compounds and sugars by forming crystalline derivatives called osazones. Osazones can be identified by microscopic examination of the shape of the crystals, or by melting point determination.




Hydrazine is still manufactured by the Raschig process, in which ammonia is oxidized by sodium hypochlorite in dilute aqueous solution



A side reaction between chloramine and hydrazine may destroy some or all of the product




This reaction is catalysed by heavy metal ions present in solution. For this reason distilled water is used (rather than tap water), and glue or gelatin is added to mask (i.e. complex with) the remaining metal ions. The use of excess of ammonia reduces the incidence of chloramine reacting with hydrazine. The use of a dilute solution of the reactants is necessary to minimize another side reaction



The modern industrial process runs continuously rather than as a batch process. A dilute aqueous solution containing a 30-1 ratio of  $\text{NH}_4\text{OH}$  and  $\text{NaOCl}$  and gelatin is passed rapidly at high pressure through a reactor at  $150^\circ\text{C}$ . Conversion is about 60%, and a 0.5% solution of hydrazine is obtained. The excess  $\text{NH}_3$  is stripped off and recycled. The hydrazine is concentrated by distillation yielding  $\text{N}_2\text{H}_4 \cdot \text{H}_2\text{O}$ , or by adding  $\text{H}_2\text{SO}_4$  to precipitate the salt  $\text{N}_2\text{H}_4 \cdot \text{H}_2\text{SO}_4$ .

Electron diffraction and infrared data indicate that the structure of hydrazine is related to that of ethane. Each N atom is tetrahedrally surrounded by one N, two H and a lone pair. The two halves of the molecule are rotated  $95^\circ$  about the N—N bond and adopt a gauche (non-eclipsed) conformation. The N—N bond length is  $1.45 \text{ \AA}$ .



Phosphorus forms an unstable hydride  $\text{P}_2\text{H}_4$ , which has very little chemical similarity to  $\text{N}_2\text{H}_4$ .




### Hydroxylamine $\text{NH}_2\text{OH}$

Hydroxylamine forms colourless crystals that melt at  $33^\circ\text{C}$ . It is thermally unstable and decomposes into  $\text{NH}_3$ ,  $\text{N}_2$ ,  $\text{HNO}_2$  and  $\text{N}_2\text{O}$  easily. It explodes if heated strongly. It is usually handled in aqueous solution, or as one of its salts, since these are more stable than free  $\text{NH}_2\text{OH}$ .


Hydroxylamine is a weaker base than is ammonia or hydrazine. Salts contain the hydroxylammonium ion  $[\text{NH}_3\text{OH}]^+$ .



The appropriate reduction potentials (see page 490) suggest that hydroxylamine should disproportionate. It disproportionates slowly in acidic solutions:





and rapidly in alkaline solutions:



Both  $\text{NH}_2\text{OH}$  and its salts are very poisonous, and they are also strong reducing agents.

Hydroxylamine is manufactured by reducing nitrites, or from nitromethane:



Hydroxylamine has donor properties (like  $\text{NH}_3$  and  $\text{N}_2\text{H}_4$ ): the N atom can form coordinate bonds, and can complex with metals. In addition it adds



easily to double bonds in organic molecules, and thus provides an easy way of introducing N atoms into molecules

$\text{NH}_2\text{OH}$  is manufactured in large quantities to make cyclohexanone oxime, which is converted to caprolactam and then polymerized to give nylon 6





Figure 14.5 Nylon-6


### LIQUID AMMONIA AS A SOLVENT

Ammonia gas is easily condensed (boiling point  $-33^\circ\text{C}$ ) to give liquid ammonia. Liquid ammonia is the most studied non aqueous solvent and it resembles the aqueous system quite closely. Liquid ammonia, like water, will dissolve a wide variety of salts. Both water and ammonia undergo self ionization




Thus, substances which produce  $\text{H}_3\text{O}^+$  ions in water are acids, and ammonium salts are acids in liquid ammonia. Similarly, substances producing  $\text{OH}^-$  in water or  $\text{NH}_2^-$  in liquid ammonia are bases in that solvent.

Thus acid-base neutralization reactions occur in both solvents, and phenolphthalein may be used to detect the end point in either





In a similar way, precipitation reactions occur in both solvents. However, the direction of the reaction is a function of the solvent




Amphoteric behaviour is observed in both solvents, for example,


$\text{Zn}(\text{OH})_2$  is amphoteric in water and  $\text{Zn}(\text{NH}_2)_2$  is amphoteric in ammonia:




Liquid ammonia is an extremely good solvent for the alkali metals and the heavier Group 2 metals Ca, Sr and Ba. The metals are very soluble and solutions in liquid ammonia have a conductivity comparable to that of pure metals. The ammonia solvates the metal ions, but is resistant to reduction by the free electrons. These solutions of metals in liquid ammonia are very good reducing agents because of the presence of free electrons.



Solutions of ammonium salts in liquid ammonia are used to clean the cooling systems in some nuclear reactors. Liquid sodium is used to cool fast breeder nuclear reactors, such as that at Dounreay in Scotland. Liquid ammonia is a good solvent for metals, but the surfaces are left wet with  $\text{NH}_3$ . When this evaporates it may leave a trace of finely divided sodium which is pyrophoric. Thus it is necessary to destroy the sodium by using an acid such as an ammonium salt in liquid ammonia.



Because liquid ammonia accepts protons readily, it enhances the ionization of so-called weak acids such as acetic acid.



The  $\text{NH}_3$  removes  $\text{H}^+$  and thus causes the reaction to proceed in the forward direction. Thus acetic acid has a  $\text{p}K_a$  value of 5 in water but is almost completely ionized in liquid ammonia. Ammonia thus reduces the difference between the strengths of acids. In this respect ammonia is called a levelling solvent (see Chapter 8, under Acids and bases).


## HYDROGEN AZIDE AND THE AZIDES

Hydrogen azide  $\text{HN}_3$  (formerly called hydrazoic acid) is a colourless liquid b.p.  $37^\circ\text{C}$ , which is highly poisonous and has an irritating odour. Both the liquid and the gas explode on heating or with a violent shock.





$\text{HN}_3$  is slightly more stable in aqueous solution, but should be treated with care. It dissociates slightly in aqueous solution ( $\text{p}K_a \cong 5$ ). It behaves as a weak acid, of similar strength to acetic acid. It reacts with electropositive

metals, forming salts called azides, but unlike other acid + metal reactions, no hydrogen is evolved



Covalent azides are used as detonators and explosives. Ionic azides are usually much more stable, and some are used as organic intermediates and dyestuffs.

The most important method of making azides is by passing nitrous oxide gas into fused sodamide at 190°C under anhydrous conditions. The water vapour produced reacts with more sodamide. Alternatively nitrous oxide can be passed into a solution of sodamide in liquid ammonia as a solvent.



The sodium azide so obtained may be converted to hydrogen azide by treatment with  $\text{H}_2\text{SO}_4$  followed by distillation. Lead azide  $\text{Pb}(\text{N}_3)_2$  can be precipitated from a solution of sodium azide and a soluble lead salt such as  $\text{Pb}(\text{NO}_3)_2$ .  $\text{Pb}(\text{N}_3)_2$  is sensitive to shock and is used as a detonator to set off a high explosive charge. It is particularly reliable, and works even in damp conditions. Numerous other metal azides are known.

Cyanuric triazide is a powerful explosive (Figure 14.6)





Figure 14.6 Structure of cyanuric triazide.

The  $(\text{N}_3)^-$  ion is considered as a pseudohalide ion (see Chapter 16). It forms the extremely unstable and explosive compounds fluorazide  $\text{FN}_3$ , chlorazide  $\text{ClN}_3$ , bromazide  $\text{BrN}_3$  and iodazide  $\text{IN}_3$ , but the dimer  $\text{N}_3-\text{N}_3$  is unknown.


Analysis of  $\text{N}_3^-$  is by reduction with  $\text{H}_2\text{S}$ .



The  $\text{N}_3^-$  ion has 16 outer electrons and is isoelectronic with  $\text{CO}_2$ . The  $\text{N}_3^-$  ion is linear ( $\text{N}-\text{N}-\text{N}$ ) as is  $\text{CO}_2$ . Four electrons are used for the two  $\sigma$  bonds. Each of the end N atoms has one non bonding pair of electrons. This leaves  $16 - 4 - (2 \times 2) = 8$  electrons for  $\pi$  bonding. If the bonding

and non-bonding electrons are assumed to occupy the  $2s$  and  $2p_x$  orbitals, this leaves six atomic orbitals for  $\pi$  bonding. These are three  $2p_y$  AOs and three  $2p_z$  AOs. The three  $2p_y$  orbitals form three three-centre  $\pi$  molecular orbitals. The lowest MO in energy is bonding, the highest is antibonding, and the remaining MO is non-bonding. In a similar way the three  $2p_z$  atomic orbitals give bonding, non-bonding and antibonding MOs. The eight  $\pi$  electrons fill both of the bonding MOs and both of the non-bonding MOs. Thus there is a total of two  $\sigma$  and two  $\pi$  bonds, giving  $\text{N}=\text{N}=\text{N}$  and a bond order of 2. Both  $\text{N}-\text{N}$  bonds are the same length,  $1.16 \text{ \AA}$ .

The hydrogen azide molecule has a bent structure. The addition of the extra electron from H means that one electron must now occupy an antibonding MO, and hence the two  $\text{N}-\text{N}$  bond lengths are different:



The bond angle  $\text{H}-\text{N}-\text{N}$  is  $112^\circ$ , and the two  $\text{N}-\text{N}$  bonds are of significantly different lengths, and the bond orders are probably 1.5 and 2 respectively.

## FERTILIZERS

Plant fertilizers normally contain three main ingredients:

1. *Nitrogen* in a combined form (commonly as ammonium nitrate, other ammonium salts or nitrates, or as urea). Nitrogen is essential for plant growth, particularly of leaves, since it is a constituent of amino acids and proteins, which must be made to make new cells.
2. *Phosphorus* for root growth, usually as a slightly soluble form of phosphate such as 'superphosphate' or 'triple superphosphate'. These are made from phosphate rocks such as fluoroapatite  $[\text{3Ca}_3(\text{PO}_4)_2 \cdot \text{CaF}_2]$  which are mined. Basic slag, which is a by-product from the steel industry, is also used as a phosphate fertilizer.
3. *Potassium ions* for flowering, often provided as  $\text{K}_2\text{SO}_4$ .


## NITROGEN FIXATION

There is a large amount of  $\text{N}_2$  gas in the atmosphere, but plants are unable to utilize this because  $\text{N}_2$  gas is so stable and unreactive. Fertile soil contains combined nitrogen, mainly in the form of nitrates, nitrites, ammonium salts or urea  $\text{CO}(\text{NH}_2)_2$ . These compounds are absorbed from the soil water by the roots of the plants. This reduces the fertility of the soil, though much of the nitrogen is eventually returned to the soil due to death and decay of the plants. It has long been known that using a plot of land to grow different crops in rotation gives a better yield than growing the same crop repeatedly. Furthermore, growing clover one year greatly



### STANDARD REDUCTION POTENTIALS (


[illegible]

Though plants require nitrates, bacteria in the soil will readily convert other nitrogenous compounds into nitrates.




There is considerable research interest into finding transition metal catalysed systems which will absorb dinitrogen and produce ammonia for fertilizers cheaply and without the necessity for high temperatures or pressure. The first dinitrogen complex, the pentaammine(dinitrogen)ruthenium cation, was made in 1965 by reducing ruthenium trichloride with hydrazine. Other methods have now been found, e.g. replacement of a labile ligand in a complex by  $N_2$ . Dinitrogen complexes have now been made for almost all the transition elements.






### Cyanamide process

Production of calcium cyanamide exceeds 1.3 million tonnes/year, and is rising. It is used in large amounts as a nitrogenous fertilizer, and as a source of organic chemicals such as melamine.



### Haber–Bosch process

The most important commercial process is the Haber–Bosch process. Fritz Haber discovered how to make  $\text{N}_2$  and  $\text{H}_2$  combine directly in the laboratory. He was awarded the Nobel Prize for Chemistry in 1918. Carl Bosch was a chemical engineer who developed the plant to make ammonia using this reaction on an industrial scale. He too was awarded the Nobel Prize for Chemistry in 1931 for his work on high pressure reactions.





The reaction is reversible, and Le Chatelier's principle suggests that a high pressure and low temperature are required to drive the reaction to the right, and thus form  $\text{NH}_3$ . A low temperature gives a higher percentage conversion to  $\text{NH}_3$ , but the reaction is slow in reaching equilibrium, and a catalyst is required. In practice the conditions used are 200 atmospheres pressure, a temperature of 380–450°C and a catalyst of *promoted iron*. It is more economic to use a higher temperature, so that equilibrium will be reached much faster, even though this gives a lower percentage conversion. At a temperature of about 400°C a 15% conversion is obtained with a single pass over the catalyst. The gas mixture is cooled to condense liquid  $\text{NH}_3$ , and the unchanged mixture of  $\text{N}_2$  and  $\text{H}_2$  gases is recycled. The plant is made of steel alloyed with Ni and Cr.


The catalyst is made by fusing  $\text{Fe}_3\text{O}_4$  with KOH and a refractory material such as  $\text{MgO}$ ,  $\text{SiO}_2$  or  $\text{Al}_2\text{O}_3$ . This is broken into small lumps and put into the ammonia converter, where the  $\text{Fe}_3\text{O}_4$  is reduced to give small crystals of iron in a refractory matrix. This is the active catalyst.

The actual plant is more complicated than this one stage reaction implies, since the  $\text{N}_2$  and  $\text{H}_2$  must be made before they can be converted to  $\text{NH}_3$ . The cost of  $\text{H}_2$  is of great importance for the economy of the process. Originally the  $\text{H}_2$  required was produced by electrolysis of water. This was expensive, and a cheaper method using coke and water was then used (water gas, producer gas). Nowadays the  $\text{H}_2$  is produced from hydro


carbons, either naphtha or  $\text{CH}_4$ , by reacting with steam at  $750^\circ\text{C}$  with a Ni catalyst. All traces of S must be removed since these poison the catalyst.



Some air is added. The  $\text{O}_2$  burns with some of the  $\text{H}_2$ , thus leaving  $\text{N}_2$  to give the required reaction ratio  $\text{N}_2 : \text{H}_2$  of 1 : 3.



CO must also be removed as it too poisons the catalyst.



Finally the  $\text{CO}_2$  is removed in a scrubber by means of a concentrated solution of  $\text{K}_2\text{CO}_3$ , or ethanolamine.

World production of  $\text{NH}_3$  has risen from about 1 million tonnes/year in 1950 to 110 million tonnes in 1992. This is not quite the largest tonnage of any chemical produced, but since  $\text{NH}_3$  has a very low molecular weight it constitutes a larger amount of substance (moles) than any other chemical. The largest producers are the USSR 27%, China 21%, the USA 18%, Canada 4%, Romania 4%, the Netherlands 3%, Mexico 3%, West Germany, Poland, Italy and East Germany 2% each.

About 75% of the ammonia is used as a fertilizer (30% direct application of  $\text{NH}_3$  gas or  $\text{NH}_4\text{OH}$  to the soil, 20%  $\text{NH}_4\text{NO}_3$ , urea 15%, ammonium phosphate 10%,  $(\text{NH}_4)_2\text{SO}_4$  3%). Other uses include the following:

1. Making  $\text{HNO}_3$ , which can be used to make  $\text{NH}_4\text{NO}_3$  (fertilizer), or explosives such as nitroglycerine, nitrocellulose and TNT.  $\text{HNO}_3$  can be used for many other purposes.
2. Making caprolactam, which on polymerization forms nylon-6 (see hydroxylamine).
3. Making hexamethylenediamine which is used in making nylon-6-6, polyurethanes and polyamides.
4. Making hydrazine and hydroxylamine.
5. Liquid  $\text{NH}_3$  is often used as a cheaper and more convenient way of transporting  $\text{H}_2$  than cylinders of compressed  $\text{H}_2$  gas. The  $\text{H}_2$  is obtained from  $\text{NH}_3$  by heating over a catalyst of finely divided Ni or Fe.
6. Ammonia has been used as the cooling liquid in refrigerators. It has a very high heat of vaporization, and convenient boiling and freezing points. With the environmental concern over using Freons in refrigerators, this use of  $\text{NH}_3$  could increase.

The widespread use of nitrates as fertilizers greatly boosts crop yields. Since nitrates are soluble, the run-off water into lakes and rivers also contains nitrates. This causes several problems.

1. It produces increased growth of algae and other aquatic plants, which may clog up rivers and lakes, and may make mudbanks in estuaries turn green.




- 2 There is concern that nitrates are harmful in drinking water. They cause a disease in babies called methaemoglobinaemia, which reduces the amount of oxygen in the baby's blood. In extreme forms this causes the 'blue baby syndrome'. There is also concern that nitrates could be linked with stomach cancer. Because of this, the EEC have set a safety limit of 25 ppm for nitrates in drinking water.
- 3 There is some concern that denitrification to oxides of nitrogen, particularly  $N_2O$ , may harm the ozone layer.

## UREA

Urea is widely used as a nitrogenous fertilizer. It is very soluble, and hence quick acting, but it is easily washed away. It has a very high nitrogen content (46%). It is manufactured from  $NH_3$ , and the reaction proceeds in two stages:




In the soil, urea slowly hydrolyses to ammonium carbonate:




## PHOSPHATE FERTILIZERS

Phosphate rocks such as fluoroapatite [ $3Ca_3(PO_4)_2 \cdot CaF_2$ ] are very insoluble, and thus are of no use to plants. Superphosphate is made by treating phosphate rock with concentrated  $H_2SO_4$ . The acid salt  $Ca(H_2PO_4)_2$  is more soluble, and over a period of weeks the superphosphate will dissolve in the soil water:



The  $CaSO_4$  is an insoluble waste product, and is of no value to plants, but is not removed from the product sold.

'Triple superphosphate' is made in a similar way, using  $H_3PO_4$  to avoid the formation of the waste product  $CaSO_4$ :



## HALIDES



### Trihalides

All the possible trihalides of N, P, As, Sb and Bi are known. The nitrogen compounds are the least stable. Though  $NF_3$  is stable,  $NCl_3$  is explosive.

It was formerly sold as 'agene' to bleach flour to make white bread. This use declined rapidly when it was suspected that bread made from flour bleached in this way sent dogs mad!  $\text{NBr}_3$  and  $\text{NI}_3$  are known only as their unstable ammoniates  $\text{NBr}_3 \cdot 6\text{NH}_3$  and  $\text{NI}_3 \cdot 6\text{NH}_3$ . The latter compound can be made by dissolving  $\text{I}_2$  in  $0.880 \text{ NH}_4\text{OH}$ . It detonates unless excess ammonia is present, and students are warned not to prepare this compound. The other 16 trihalides are stable.

The trihalides are predominantly covalent and, like  $\text{NH}_3$ , have a tetrahedral structure with one position occupied by a lone pair. The exceptions are  $\text{BiF}_3$  which is ionic and the other halides of Bi and  $\text{SbF}_3$  which are intermediate in character.

The trihalides typically hydrolyse readily with water, but the products vary depending on the element:



They also react with  $\text{NH}_3$ .



$\text{NF}_3$  behaves differently from the others. It is unreactive, rather like  $\text{CF}_4$ , and does not hydrolyse with water, dilute acids or alkali. It does react if sparked with water vapour.

$\text{PF}_3$  is rather less reactive towards water and is more easily handled than the other halides. The trihalides, particularly  $\text{PF}_3$ , can act as donor molecules using their lone pair to form a coordinate bond, for example in  $\text{Ni}(\text{PF}_3)_4$ . In addition to this  $\sigma$  bond, there is  $\pi$  backbonding from a filled orbital on the metal to an empty  $d$  orbital on P, similar to the way CO acts as a ligand.  $\text{Ni}(\text{PF}_3)_4$  can be made from nickel carbonyl  $\text{Ni}(\text{CO})_4$ .




Many trifluorophosphine complexes of the transition metals are known. Much of the work was done by J. Chatt and his group at ICI. Though most of the trihalides are made from the elements,  $\text{PF}_3$  is made by the action of  $\text{CaF}_2$  (or other fluoride) on  $\text{PCl}_3$ .  $\text{PF}_3$  is a colourless, odourless gas, which is very toxic because it forms a complex with haemoglobin in the blood, thus starving the body of oxygen.

$\text{NF}_3$  has little tendency to act as a donor molecule. The molecule is tetrahedral with one position occupied by a lone pair, and the bond angle  $\text{F—N—F}$  is  $102^\circ 30'$ . However, the dipole moment is very low (0.23 Debye units) compared with 1.47D for  $\text{NH}_3$ . The highly electronegative F atoms attract electrons, and these moments partly cancel the moment from the lone pair, and this reduces both the dipole moment and its donor power.

The trihalides also show acceptor properties, and can accept an electron

pair from another ion such as  $F^-$ , forming complex ions such as  $[SbF_6]^{2-}$  and  $[Sb_2F_7]^-$ . They also react with a variety of organometallic reagents forming compounds  $MR_3$ .



$PCl_3$  is the most important trihalide and 250 000 tonnes/year are produced commercially from the elements. Some  $PCl_3$  is used to make  $PCl_5$ .





$PCl_3$  is widely used in organic chemistry to convert carboxylic acids to acid chlorides and alcohols to alkyl halides.



$PCl_3$  can be oxidized by  $O_2$  or  $P_4O_{10}$  to give phosphorus oxochloride  $POCl_3$ .



$POCl_3$  is used in large amounts in the manufacture of trialkyl and triaryl phosphates  $(RO)_3PO$ .




Several of these phosphate derivatives are commercially important.

- 1 Triethyl phosphate is used in producing systemic insecticides.
- 2 Tritolyl phosphate is a petrol additive.
- 3 Triaryl phosphates and trioctyl phosphate are used as plasticizers for polyvinyl chloride.
- 4 Tri n butyl phosphate is used for solvent extraction.


### Pentahalides

Nitrogen is unable to form pentahalides because the second shell contains a maximum of eight electrons i.e. four bonds. The subsequent elements have suitable *d* orbitals and form the following pentahalides.



$\text{AsCl}_5$  is highly reactive and unstable, and has only a temporary existence.  $\text{BiF}_5$  is highly reactive, and explodes with water, forming  $\text{O}_3$  and  $\text{F}_2\text{O}$ . It oxidizes  $\text{UF}_4$  to  $\text{UF}_6$ , and  $\text{BrF}_3$  to  $\text{BrF}_5$ , and fluorinates hydrocarbons.

The pentahalides are prepared as follows:



These molecules have a trigonal bipyramid shape in the gas phase (see Figure 14.7), as expected from the VSEPR theory for five pairs of electrons.





Figure 14.7 Structure of gaseous phosphorus pentachloride.

The valence bond explanation of the shape is:




The trigonal bipyramid is not a regular structure. Electron diffraction on  $\text{PF}_5$  gas shows that some bond angles are  $90^\circ$  and others are  $120^\circ$ , and the axial P—F bond lengths are  $1.58 \text{ \AA}$  whilst the equatorial P—F lengths are  $1.53 \text{ \AA}$ . In contrast nmr studies suggest that all five F atoms are equivalent. This paradox may be explained quite simply. Electron diffraction gives an instantaneous picture of the molecule, whilst nmr gives the picture averaged over several milliseconds. The axial and equatorial F atoms are thought to interchange their positions in less time than that needed to take the nmr. The interchange of axial and equatorial positions is called 'pseudorotation'.


$\text{PF}_5$  remains covalent and keeps this structure in the solid state.

However,  $\text{PCl}_5$  is close to the ionic-covalent borderline, and it is covalent in the gas and liquid states, but is ionic in the solid state.  $\text{PCl}_5$  solid exists as  $[\text{PCl}_4]^+$  and  $[\text{PCl}_6]^-$  the ions have tetrahedral and octahedral structures respectively. In the solid,  $\text{PBr}_5$  exists as  $[\text{PBr}_4]^+\text{Br}^-$ , and  $\text{PI}_5$  appears to be  $[\text{PI}_4]^+$  and  $\text{I}^-$  in solution.

$\text{PCl}_5$  is the most important pentahalide, and it is made by passing  $\text{Cl}_2$  into a solution of  $\text{PCl}_3$  in  $\text{CCl}_4$ . World production is about 20 000 tonnes/year. Complete hydrolysis of the pentahalides yields the appropriate acid. Thus  $\text{PCl}_5$  reacts violently with water:




If equimolar amounts are used, the reaction is more gentle and yields phosphorus oxochloride  $\text{POCl}_3$ :





$\text{PCl}_5$  is used in organic chemistry to convert carboxylic acids to acid chlorides, and alcohols to alkyl halides:



It reacts with  $\text{P}_4\text{O}_{10}$ , forming  $\text{POCl}_3$  and with  $\text{SO}_2$ , forming thionyl chloride  $\text{SOCl}_2$ :



$\text{PCl}_5$  also reacts with  $\text{NH}_4\text{Cl}$ , forming a variety of phosphonitric chloride polymers (see later):



Despite the existence of pentahalides, no hydrides  $\text{MH}_5$  are known. To attain the five-valent state,  $d$  orbitals must be used. Hydrogen is not sufficiently electronegative to make the  $d$  orbitals contract sufficiently, though  $\text{PHF}_4$  and  $\text{PH}_2\text{F}_3$  have been isolated.

## OXIDES OF NITROGEN

The oxides and oxoacids of nitrogen all exhibit  $p\pi-p\pi$  multiple bonding between the nitrogen and oxygen atoms. This does not occur with the heavier elements in the group, and consequently nitrogen forms a number of compounds which have no P, As, Sb or Bi analogues. Nitrogen forms a very wide range of oxides, exhibiting all the oxidation states from (+I) to (+VI). The lower oxides are neutral, and the higher ones are acidic (Table 14.8).

Table 14.8 Oxides of nitrogen

Formula	Oxidation number	Name
N <sub>2</sub> O	+I	Nitrous oxide
NO	+II	Nitric oxide
N <sub>2</sub> O <sub>3</sub>	+III	Nitrogen sesquioxide
NO <sub>2</sub> , N <sub>2</sub> O <sub>4</sub>	+IV	Nitrogen dioxide, dinitrogen tetroxide
N <sub>2</sub> O <sub>5</sub>	+V	Dinitrogen pentoxide
(NO <sub>3</sub> , N <sub>2</sub> O <sub>6</sub> ) very unstable	+VI	Nitrogen trioxide, dinitrogen hexoxide

### Nitrous oxide N<sub>2</sub>O

N<sub>2</sub>O is a stable, relatively unreactive colourless gas. It is prepared by careful thermal decomposition of molten ammonium nitrate at about 280°C. If heated strongly it explodes. N<sub>2</sub>O can also be made by heating a solution of NH<sub>4</sub>NO<sub>3</sub> acidified with HCl.




N<sub>2</sub>O is a neutral oxide and does not form hyponitrous acid H<sub>2</sub>N<sub>2</sub>O<sub>2</sub> with water nor hyponitrites with alkali. It is important in the preparation of sodium azide, and hence also of the other azides:



The largest use of N<sub>2</sub>O is as a propellant for whipped ice-cream. Because it has no taste, and is non-toxic, it meets the strict food and health regulations.

N<sub>2</sub>O is used as an anaesthetic, particularly by dentists. It is sometimes called 'laughing gas', because small amounts cause euphoria. It requires a partial pressure of 760 mm Hg of N<sub>2</sub>O to anaesthetize a patient completely. Thus if dioxygen is also supplied, the patient may not be completely unconscious. If deprived of dioxygen for long, the patient will die. Plainly N<sub>2</sub>O is unsuitable for long operations. Usually N<sub>2</sub>O is administered to put the patient 'to sleep', and O<sub>2</sub> to make him recover consciousness.


The molecule is linear as would be expected for a triatomic molecule with 16 outer shell electrons (see also N<sub>3</sub><sup>-</sup> and CO<sub>2</sub>). However, CO<sub>2</sub> is symmetrical (O—C—O), whereas in N<sub>2</sub>O the orbital energies favour the formation of the asymmetrical molecule N—N—O rather than the symmetrical molecule N—O—N. The bond lengths are short, and the bond orders have been calculated as N—N 2.73 and N—O 1.61.



### Nitric oxide NO

NO is a colourless gas and is an important intermediate in the manufacture of nitric acid by the catalytic oxidation of ammonia (Ostwald process). It

was also important in the obsolete Birkeland–Eyde process which involved sparking dinitrogen and dioxygen. NO is prepared in the laboratory by the reduction of dilute  $\text{HNO}_3$  with Cu, or reduction of  $\text{HNO}_2$  with  $\text{I}^-$




NO is a neutral oxide and is not an acid anhydride


NO has 11 valency electrons. It is impossible for them all to be paired and hence this is an odd electron molecule and the gas is paramagnetic. It is diamagnetic in the liquid and solid states, because the molecule dimerizes forming  $\text{O}=\text{N}-\text{N}=\text{O}$ . The asymmetrical dimer  $\text{O}=\text{N}-\text{O}-\text{N}$  has been observed to be formed as a red solid in the presence of HCl or other Lewis acids.

The bond length  $\text{N}-\text{O}$  is  $1.15 \text{ \AA}$ , which is intermediate between a double and a triple bond. Bonding is best described using the molecular orbital theory (see Chapter 4). The bonding is similar to that in  $\text{N}_2$  and  $\text{CO}$  which both have 10 outer electrons. NO has 11 outer electrons, and the extra unpaired electron occupies an antibonding  $\pi^*2p$  orbital. This reduces the bond order from 3 in  $\text{N}_2$  to  $2\frac{1}{2}$  in NO. If this electron is removed by oxidizing NO, the nitrosonium ion  $\text{NO}^+$  is formed. In  $\text{NO}^+$  the bond order is 3, and the  $\text{N}-\text{O}$  bond length contracts from  $1.15 \text{ \AA}$  in NO to  $1.06 \text{ \AA}$  in  $\text{NO}^+$ .

Odd electron molecules are usually highly reactive and tend to dimerize. NO is unusually stable for an odd electron molecule. Nevertheless it reacts instantly with dioxygen to give  $\text{NO}_2$ , and with the halogens it gives nitrosyl halides, e.g.  $\text{NOCl}$ .




NO readily forms coordination complexes with transition metal ions. These complexes are called nitrosyls.  $\text{Fe}^{2+}$  and NO form the complex  $[\text{Fe}(\text{H}_2\text{O})_5\text{NO}]^{2+}$ , which is responsible for the colour in the 'brown ring test' for nitrates. Most nitrosyl complexes are coloured. Another example is sodium nitroprusside  $\text{Na}_2[\text{Fe}(\text{CN})_5\text{NO}] \cdot 2\text{H}_2\text{O}$ . NO often acts as a three electron donor, in contrast to most ligands which donate two electrons. Thus three CO groups may be replaced by two NO groups:




In these complexes the  $\text{M}-\text{N}-\text{O}$  atoms are linear, or close to linear. However, in 1968 the  $\text{M}-\text{N}-\text{O}$  angle in  $[\text{Ir}(\text{CO})(\text{Cl})(\text{PPh}_3)(\text{NO})]^+$  was found to be  $123^\circ$ , and since then a number of other complexes have been found with bond angles in the range  $120-130^\circ$ . These bent bonds, which are weaker than straight bonds, are of considerable theoretical interest. NO may also act as a bridging ligand between two or three metal atoms in a similar way to CO.

### Nitrogen sesquioxide $\text{N}_2\text{O}_3$


$\text{N}_2\text{O}_3$  can only be obtained at low temperatures. It can be made by condensing equimolar amounts of  $\text{NO}$  and  $\text{NO}_2$  together, or by reacting  $\text{NO}$  with the appropriate amount of  $\text{O}_2$ . This gives a blue liquid or solid, which is unstable and dissociates into  $\text{NO}$  and  $\text{NO}_2$  at  $-30^\circ\text{C}$ .




It is an acidic oxide and is the anhydride of nitrous acid  $\text{HNO}_2$ . With alkali it forms nitrites.



$\text{N}_2\text{O}_3$  reacts with the concentrated acids, forming nitrosyl salts:




The oxide exists in two different forms. These may be interconverted by irradiation with light of the appropriate wavelength. The  $\text{N}-\text{N}$  bond length from microwave spectra is  $1.864 \text{ \AA}$  in the asymmetrical form. This is exceptionally long and thus the bond is exceptionally weak compared with the  $\text{N}-\text{N}$  bond found in hydrazine (length of  $1.45 \text{ \AA}$ ).




### Nitrogen dioxide $\text{NO}_2$ and dinitrogen tetroxide $\text{N}_2\text{O}_4$

$\text{NO}_2$  is a red-brown poisonous gas and is produced on a large scale by oxidizing  $\text{NO}$  in the Ostwald process for the manufacture of nitric acid. In the laboratory it is prepared by heating lead nitrate:




The gaseous products  $\text{O}_2$  and  $\text{NO}_2$  are passed through a U-tube cooled in ice. The  $\text{NO}_2$  (b.p.  $21^\circ\text{C}$ ) condenses. The  $\text{Pb}(\text{NO}_3)_2$  must be carefully dried, since  $\text{NO}_2$  reacts with water. The  $\text{NO}_2$  is obtained as a brown liquid which turns paler on cooling, and eventually becomes a colourless solid. This is because  $\text{NO}_2$  dimerizes into colourless  $\text{N}_2\text{O}_4$ .  $\text{NO}_2$  is an odd electron molecule, and is paramagnetic and very reactive. It dimerizes to  $\text{N}_2\text{O}_4$ , pairing the previously unpaired electrons.  $\text{N}_2\text{O}_4$  has no unpaired electrons and is diamagnetic.






$\text{N}_2\text{O}_4$  is a mixed anhydride, because it reacts with water to give a mixture of nitric and nitrous acids




The  $\text{HNO}_2$  formed decomposes to give NO




Thus moist  $\text{NO}_2$  or  $\text{N}_2\text{O}_4$  gases are strongly acidic

The  $\text{NO}_2$  molecule is angular with an O—N—O angle of  $132^\circ$ . The bond length O—N of  $1.20 \text{ \AA}$  is intermediate between a single and a double bond. X ray diffraction on solid  $\text{N}_2\text{O}_4$  shows the structure to be planar




The N—N bond is very long ( $1.64 \text{ \AA}$ ), and is therefore weak. It is much longer than the single bond N—N distance of  $1.47 \text{ \AA}$  in  $\text{N}_2\text{H}_4$ , but there is no satisfactory explanation of why it is long.

Liquid  $\text{N}_2\text{O}_4$  is useful as a non-aqueous solvent. It self-ionizes






In  $\text{N}_2\text{O}_4$  substances containing  $\text{NO}^+$  are acids and those containing  $\text{NO}_2^-$  are bases. A typical acid-base reaction is



Liquid  $\text{N}_2\text{O}_4$  is particularly useful as a solvent for preparing anhydrous metal nitrates and also nitrate complexes







The  $\text{NO}_2$ – $\text{N}_2\text{O}_4$  system is a strong oxidizing agent.  $\text{NO}_2$  reacts with fluorine and chlorine, forming nitryl fluoride  $\text{NO}_2\text{F}$  and nitryl chloride  $\text{NO}_2\text{Cl}$ . It oxidizes HCl to  $\text{Cl}_2$  and CO to  $\text{CO}_2$ ,




Dinitrogen pentoxide  $\text{N}_2\text{O}_5$ 

$\text{N}_2\text{O}_5$  is prepared by carefully dehydrating  $\text{HNO}_3$  with  $\text{P}_2\text{O}_5$  at low temperatures. It is a colourless deliquescent solid, which is highly reactive, is a strong oxidizing agent, and is light sensitive. It is the anhydride of  $\text{HNO}_3$ .



In the gas phase  $\text{N}_2\text{O}_5$  decomposes into  $\text{NO}_2$ ,  $\text{NO}$  and  $\text{O}_2$ . Nitrogen trioxide  $\text{NO}_3$  may be formed by treating  $\text{N}_2\text{O}_5$  with  $\text{O}_3$ .


X-ray diffraction shows that solid  $\text{N}_2\text{O}_5$  is ionic  $\text{NO}_2^+ \text{NO}_3^-$ ; it should in reality be called nitronium nitrate. It is covalent in solution and in the gas phase, and probably has the structure:





## OXOACIDS OF NITROGEN

Nitrous acid  $\text{HNO}_2$ 

Nitrous acid is unstable except in dilute solution. It is easily made by acidifying a solution of a nitrite. Barium nitrite is often used with  $\text{H}_2\text{SO}_4$ , since the insoluble  $\text{BaSO}_4$  can be filtered off easily.




Group 1 metal nitrites can be made by heating nitrates, either on their own or with Pb.




Nitrous acid and nitrites are weak oxidizing agents and will oxidize  $\text{Fe}^{2+}$  to  $\text{Fe}^{3+}$ , and  $\text{I}^-$  to  $\text{I}_2$ ; they themselves are reduced to  $\text{N}_2\text{O}$  or  $\text{NO}$ . However,  $\text{HNO}_2$  and nitrites are oxidized by  $\text{KMnO}_4$  and  $\text{Cl}_2$ , forming nitrates  $\text{NO}_3^-$ .

Large amounts of nitrites are used to make diazo compounds, which are converted into azo dyes, and also pharmaceutical products.



Nitrites are important in the manufacture of hydroxylamine:



Sodium nitrite is used as a food additive in cured meat, sausages, hot dogs, bacon and tinned ham. Though an approved additive, its use is controversial.  $\text{NaNO}_2$  is slightly poisonous. The tolerance limit for humans is 5–10 g per day depending on body weight.  $\text{NO}_2^-$  ions inhibit the growth of bacteria, particularly *Clostridium botulinum*, which causes botulism (a particularly unpleasant form of food poisoning). Reductive decomposition of  $\text{NO}_2^-$  gives  $\text{NO}$ , which forms a red complex with haemoglobin and improves the look of meat. There is concern that during the cooking of meat, the nitrites may react with amines and be converted into nitrosamines  $\text{R}_2\text{N}-\text{N}=\text{O}$ , which are thought to cause cancer. Certainly secondary and tertiary aliphatic amines form nitrosamines with nitrites.



The nitrite ion is a good ligand and forms many coordination complexes. Since lone pairs of electrons are present on both N and O atoms, either N or O can form a coordinate bond. This gives rise to isomerism between nitro complexes  $\text{M} \leftarrow \text{NO}_2$  and nitrito complexes  $\text{M} \leftarrow \text{ONO}$ , for example  $[\text{Co}(\text{NH}_3)_5(\text{NO}_2)]^{2+}$  and  $[\text{Co}(\text{NH}_3)_5(\text{ONO})]^{2+}$ . This is discussed in Chapter 7, under 'Isomerism'. If a solution of  $\text{Co}^{2+}$  ions is treated with  $\text{NO}_2^-$  ions, first  $\text{Co}^{2+}$  ions are oxidized to  $\text{Co}^{3+}$ , then  $\text{NO}_2^-$  ions form the complex  $[\text{Co}(\text{NO}_2)_6]^{3-}$ . Precipitation of potassium cobaltinitrite  $\text{K}_3[\text{Co}(\text{NO}_2)_6]$  is used to detect  $\text{K}^+$  qualitatively. The  $\text{NO}_2^-$  ion may act as a chelating ligand, and bond to the same metal twice, or it may act as a bridging ligand joining two metal atoms.

The nitrite ion  $\text{NO}_2^-$  has a plane triangular structure, with N at the centre, two corners occupied by O atoms, and the third corner occupied by the lone pair. A three centre bond covers the N and the two O atoms and the bond order is 1.5 for the N—O bonds, which have bond lengths in between those for a single and double bond. (More details are given in Chapter 4, under 'Examples of molecular orbital treatment involving delocalised  $\pi$  bonding'.)

### Nitric acid $\text{HNO}_3$

$\text{HNO}_3$  is the most important oxoacid of nitrogen. (The three most important industrial acids in order of tonnages produced are (1)  $\text{H}_2\text{SO}_4$ , (2)  $\text{HNO}_3$  and (3)  $\text{HCl}$ .) Pure nitric acid is a colourless liquid, but on exposure to light it turns slightly brown because of slight decomposition into  $\text{NO}_2$  and  $\text{O}_2$ .




It is a strong acid and is 100% dissociated in dilute aqueous solutions into  $\text{H}_3\text{O}^+$  and  $\text{NO}_3^-$ . It forms a large number of salts called nitrates which are typically very soluble in water.


The shape of the  $\text{NO}_3^-$  ion is a planar triangle, like the  $\text{CO}_3^{2-}$  ion. The later elements in both groups form tetrahedral oxoacid ions such as  $\text{PO}_4^{3-}$  and  $\text{SiO}_4^{4-}$ . This difference in shape is probably due to the small size of the N and C atoms and their restriction to eight electrons in their outer shell.

$\text{HNO}_3$  is an excellent oxidizing agent particularly when hot and concentrated.  $\text{H}^+$  ions are oxidizing, but the  $\text{NO}_3^-$  ion is an even stronger oxidizing agent in acid solution. Thus metals like copper and silver which are insoluble in  $\text{HCl}$  dissolve in  $\text{HNO}_3$ . Some metals such as gold are insoluble even in  $\text{HNO}_3$ , but will dissolve in aqua regia, a mixture of 25% concentrated  $\text{HNO}_3$  and 75% concentrated  $\text{HCl}$ . The enhanced ability to dissolve metals shown by aqua regia arises from the oxidizing power of  $\text{HNO}_3$  coupled with the ability of  $\text{Cl}^-$  to form complexes with the metal ions.



$\text{HNO}_3$  was originally made from  $\text{NaNO}_3$  or  $\text{KNO}_3$  and concentrated  $\text{H}_2\text{SO}_4$ . The first synthetic method was the Birkeland–Eyde process. This sparked  $\text{N}_2$  and  $\text{O}_2$  together in an electric arc furnace, and passed the gas into water. The process was started in Norway in 1903, but is now obsolete, because of the high cost of electricity.



The Ostwald process depends on the catalytic oxidation of ammonia to  $\text{NO}$ , followed by oxidation of  $\text{NO}$  to  $\text{NO}_2$ , and conversion of  $\text{NO}_2$  with water to  $\text{HNO}_3$ . The first plant was set up in Germany in 1908, and Ostwald was awarded the Nobel Prize in 1909. The method is still used and about 24.7 million tonnes/year of  $\text{HNO}_3$  are produced. The overall process is:



The  $\text{NO}$  and air are cooled and the mixture of gases is absorbed in a countercurrent of water.



This gives a  $\text{HNO}_3$  solution of concentration 60% by weight. Distillation only increases the concentration to 68% since a constant boiling mixture is formed. 'Concentrated'  $\text{HNO}_3$  contains 98% acid and is produced by dehydrating with concentrated sulphuric acid, or by mixing with a 72% magnesium nitrate solution, followed by distillation.

When nitric acid is mixed with concentrated sulphuric acid, the nitronium ion  $\text{NO}_2^+$  is formed. This is the active species in the nitration of

aromatic organic compounds. This is an important step in making explosives, or the nitro compounds may be reduced to aniline and used for making dyestuffs.





Figure 14.8 Nitration of benzene and toluene

Covalent nitrates are less stable than ionic nitrates. (This is a similar behaviour to that of the azides.) Nitroglycerine, nitrocellulose, trinitrotoluene (TNT) and fluorine nitrate ( $\text{FNO}_3$ ) are all explosive (Figure 14.9).

World production of explosives is quoted as 2.5 million tonnes for 1991, but the true value may be higher than this.

$\text{HNO}_3$  is a strong oxidizing agent, and is used to oxidize cyclohexanol/cyclohexanone mixtures to adipic acid (which reacts with hexamethylenediamine in the manufacture of nylon-66).



$\text{HNO}_3$  is also used to oxidize *p*-xylene to terephthalic acid for the manufacture of terylene.

The structure of the nitrate ion is a planar triangle. All three oxygen









Figure 14.9 Some explosives.

atoms are equivalent. In addition to the  $\sigma$  bonds, four-centre  $\pi$  molecular orbitals cover the N and the three O atoms. Each of the N—O bonds has a bond order of  $1\frac{1}{3}$ , 1 from the  $\sigma$  bond and  $\frac{1}{3}$  from the  $\pi$  bond. (This is described more fully in Chapter 4, under 'Examples of molecular orbital treatment involving delocalised  $\pi$  bonding'.)

Reduction of nitrates in acid solution gives either  $\text{NO}_2$  or  $\text{NO}$ , but in alkaline solutions with metals such as Devarda's alloy (Cu/Al/Zn), ammonia is produced.



## OXIDES OF PHOSPHORUS, ARSENIC AND BISMUTH


The oxides of the rest of the group are listed in Table 14.9. They form fewer oxides than does nitrogen, presumably because of the inability of these elements to form  $p\pi-p\pi$  double bonds.

Table 14.9 Oxides and their oxidation states


$P_4O_6$	III		$As_4O_6$	III	$Sb_4O_6$	III	$Bi_2O_3$	III
$P_4O_7$	III	V			$(SbO_2)_n$	III	V	
$P_4O_8$	III	V						
$P_4O_9$	III	V						
$P_4O_{10}$		V	$As_4O_{10}$	V	$Sb_4O_{10}$		V	

## Trioxides

Phosphorus trioxide is dimeric and should be written  $P_4O_6$ , not  $P_2O_3$ .  $P_4O_6$  has four P atoms at the corners of a tetrahedron, with six O atoms along the edges, each O being bonded to two P atoms. The structures of  $As_4O_6$  and  $Sb_4O_6$  are similar to this.  $Bi_2O_3$  is ionic. The structure of  $P_4O_{10}$  is shown in Figure 14.10. Since the  $P-O-P$  angle is  $127^\circ$  the O atoms are strictly above the edges, but it is more convenient to draw them on the edges.

Figure 14.10 Structure of phosphorus trioxide  $P_4O_6$ .

Because yellow phosphorus is more reactive than is  $N_2$ , phosphorus oxides (unlike nitrogen oxides) can all be obtained by burning phosphorus in air.




$P_4O_6$  is formed by burning phosphorus in a limited supply of air. It is a soft white solid (m.p.  $24^\circ\text{C}$ , b.p.  $175^\circ\text{C}$ ). It is removed from the reaction mixture and is purified by distillation. (Higher oxides are formed in a plentiful supply of air.)  $P_4O_6$  will burn in air, forming  $P_4O_{10}$ .



$\text{As}_4\text{O}_6$  and  $\text{Sb}_4\text{O}_6$  are obtained by burning the metals in air or dioxygen, since they have less tendency to form higher oxides. Heating the sulphide minerals  $\text{As}_4\text{S}_4$  (realgar) or  $\text{As}_2\text{S}_3$  (orpiment) in air also gives  $\text{As}_4\text{O}_6$ . Both  $\text{As}_4\text{O}_6$  and  $\text{Sb}_4\text{O}_6$  are very poisonous.  $\text{Bi}_2\text{O}_3$  is not dimeric like the others.

The basicity of oxides and hydroxides usually increases on descending a group.  $\text{P}_4\text{O}_6$  is acidic and hydrolyses in water, forming phosphorous acid. (This is considered in more detail later.) Arsenious oxide  $\text{As}_4\text{O}_6$  is sparingly soluble in water, and  $\text{Sb}_4\text{O}_6$  is insoluble.  $\text{As}_4\text{O}_6$  and  $\text{Sb}_4\text{O}_6$  are both amphoteric since they react with alkali, forming arsenites and antimonites, and with concentrated  $\text{HCl}$ , forming arsenic and antimony trichlorides. In the past, various copper arsenites were used as brilliant green pigments. The best known are Scheele's green  $\text{Cu}_2\text{As}_2\text{O}_5$  and Paris green  $[(\text{CH}_3\text{COO})\text{Cu}_2(\text{AsO}_3)]$ . They are seldom used nowadays because they are toxic, and, even worse, in damp places bacteria and moulds can produce poisonous volatile substances such as  $\text{AsH}_3$  and  $\text{As}(\text{CH}_3)_3$ .  $\text{Bi}_2\text{O}_3$  is wholly basic.



### Pentoxides

Phosphorus pentoxide is the most important oxide, and is quite common. It is dimeric and has the formula  $\text{P}_4\text{O}_{10}$ , not  $\text{P}_2\text{O}_5$ . Its structure is derived from that of  $\text{P}_4\text{O}_6$ . Each P atom in  $\text{P}_4\text{O}_6$  forms three bonds to O atoms. There are five electrons in the outer shell of a P atom. Three electrons have been used in bonding, and the other two comprise a lone pair, which is situated on the outside of the tetrahedral unit. In  $\text{P}_4\text{O}_{10}$  the lone pairs on each of the four P atoms form a coordinate bond to an oxygen atom (Figure 14.11a).


Measurement of the P—O bond lengths shows that the bridging bonds on the edges are 1.60 Å but the coordinate bonds on the corners are 1.43 Å. The bridging bonds compare with those in  $\text{P}_4\text{O}_6$  (1.65 Å) and are normal single bonds. The bonds on the corners are much shorter than a single bond, and are in fact double bonds. These double bonds are different in origin from the 'usual' double bonds such as that in ethene which arises from  $p\pi-p\pi$  overlap with one electron coming from each C atom. The second bond in  $\text{P}=\text{O}$  is formed by  $p\pi-d\pi$  back bonding. A full  $p$  orbital on the O atom overlaps sideways with an empty  $d$  orbital on the P atom. Thus it differs from the double bond in ethene in two respects:

1. A  $p$  orbital overlaps with a  $d$  orbital, rather than  $p$  with  $p$ .
2. Both electrons come from one atom, and hence the bond is a 'dative bond'.

A similar type of back bonding is found in the carbonyls.

$\text{As}_4\text{O}_{10}$  has a similar structure to  $\text{P}_4\text{O}_{10}$  in the gas phase. However, the





**Figure 14.11** Structure of phosphorus pentoxide  $P_4O_{10}$  (a) Formation of  $\sigma$  bonds (b) Orbitals involved in back bonding


crystal contains equal numbers of  $[AsO_4]$  tetrahedra and  $[AsO_6]$  octahedra joined together by sharing corners.  $As_4O_{10}$  is a strong oxidizing agent, and oxidizes  $HCl$  to  $Cl_2$ . It is deliquescent, and very soluble in water.

$P_4O_{10}$  is formed by burning  $P$  in an excess of air or dioxygen, but  $As$  and  $Sb$  require more drastic oxidation by concentrated  $HNO_3$  to form the pentoxides.  $As_4O_{10}$  and  $Sb_4O_{10}$  lose dioxygen when they are heated, and form the trioxides.

$P_4O_{10}$  absorbs water from the air or from other compounds and becomes sticky. Because of this strong affinity for water,  $P_4O_{10}$  is used as a drying agent. Finely powdered  $P_4O_{10}$  is sometimes spread over glass wool and used for drying purposes. This provides a large drying surface, which is not easily covered by solid hydrolysis products.  $P_4O_{10}$  hydrolyses violently in water, forming phosphoric acid  $H_3PO_4$ . The manufacture of pure  $H_3PO_4$  by this route is the largest use of  $P_4O_{10}$ .



$P_4O_{10}$  reacts with alcohols and ethers, forming phosphate esters. (The relation of these esters to phosphoric acid is shown by writing  $H_3PO_4$  as  $O=P(OH)_3$ .)




$As_4O_{10}$  dissolves slowly in water, forming arsenic acid  $H_3AsO_4$ . This is tribasic, and is a much stronger acid than is arsenious acid. Salts such as lead arsenate  $PbHAsO_4$  and calcium arsenate  $Ca_3(AsO_4)_2$  are used as

insecticides against locusts, cotton weevils, and fruit moths.  $\text{Sb}_4\text{O}_{10}$  is insoluble in water and antimononic acid is not known. Antimonates containing  $[\text{Sb}(\text{OH})_6]^-$ , however, are known.

Bi does not form a pentoxide, showing that the stability of the highest oxidation states decreases on descending the group. The usual trend that higher oxidation states are more acidic is also observed.

### Other oxides

The oxides  $\text{P}_4\text{O}_7$ ,  $\text{P}_4\text{O}_8$  and  $\text{P}_4\text{O}_9$  are very uncommon. In these oxides one molecule contains P atoms in both the oxidation states (+III) and (+V).  $\text{P}_4\text{O}_7$  is best made by dissolving  $\text{P}_4\text{O}_6$  in tetrahydrofuran and reacting it with the correct amount of dioxygen. Heating  $\text{P}_4\text{O}_6$  under vacuum in a sealed tube gives a mixture of red phosphorus and the oxides  $\text{P}_4\text{O}_7$ ,  $\text{P}_4\text{O}_8$  and  $\text{P}_4\text{O}_9$ . These oxides have structures in between those of  $\text{P}_4\text{O}_6$  and  $\text{P}_4\text{O}_{10}$ , in that they have one, two or three apical O atoms attached to P atoms. Hydrolysis with water thus yields a mixture of oxoacids in both oxidation states, phosphoric acid P(+V) and phosphorous acid P(+III).



## OXOACIDS OF PHOSPHORUS

Phosphorus forms two series of oxoacids:


1. The phosphoric series of acids, in which the oxidation state of P is (+V), and in which the compounds have oxidizing properties.
2. The phosphorous series of acids, which contain P in the oxidation state (+III), and which are reducing agents.

In all of these, P is four-coordinate and tetrahedrally surrounded wherever possible.  $p\pi-p\pi$  back bonding gives rise to  $\text{P}=\text{O}$  bonds. The hydrogen atoms in OH groups are ionizable and are acidic, but the P—H bonds found in the phosphorous acids have reducing, not acidic, properties. Simple phosphate ions can condense (polymerize) together to give a wide range of more complicated isopolyacids or their salts.

## THE PHOSPHORIC ACID SERIES

### Orthophosphoric acids

The simplest phosphoric acid is  $\text{H}_3\text{PO}_4$  orthophosphoric acid (Figure 14.12). The acid contains three replaceable H atoms, and is tribasic. It undergoes stepwise dissociation:




Three series of salts can be formed

- 1 Dihydrogen phosphates, for example sodium dihydrogen phosphate  $\text{NaH}_2\text{PO}_4$ , which is slightly acidic in water
- 2 Monohydrogen phosphates, for example disodium hydrogen phosphate  $\text{Na}_2\text{HPO}_4$ , which is slightly basic in water
- 3 Normal phosphates such as trisodium phosphate  $\text{Na}_3\text{PO}_4$ , which are appreciably basic in solution

$\text{NaH}_2\text{PO}_4$  and  $\text{Na}_2\text{HPO}_4$  are made industrially by neutralizing  $\text{H}_3\text{PO}_4$  with 'soda ash' ( $\text{Na}_2\text{CO}_3$ ), but  $\text{NaOH}$  is required to make  $\text{Na}_3\text{PO}_4$ . All three salts exist in the anhydrous state and also in a number of hydrated forms and they are used extensively

Phosphoric acid also forms esters with alcohols



Phosphates are detected analytically by mixing a solution of the salt with dilute  $\text{HNO}_3$  and ammonium molybdate solution. A yellow precipitate of a complex ammonium 12-molybdophosphate forms slowly, confirming the presence of phosphates. Arsenates form a similar precipitate, but only on heating the mixture.

The orthophosphates of Group 1 metals (except Li) and  $\text{NH}_4^+$  are soluble in water. Most of the other metal orthophosphates are soluble in dilute  $\text{HCl}$  or acetic acids. Titanium, zirconium and thorium phosphates are insoluble even in acids. Thus in qualitative analysis a solution of zirconyl nitrate is commonly added to remove any phosphate present in solution.

Phosphates can be estimated quantitatively by adding a solution containing  $\text{Mg}^{2+}$  and  $\text{NH}_4\text{OH}$  solution to a solution of the phosphate. Magnesium ammonium phosphate is precipitated quantitatively, and this is filtered, washed, ignited, and weighed as magnesium pyrophosphate  $\text{Mg}_2\text{P}_2\text{O}_7$ .









Figure 14.12 Structure of orthophosphoric acid  $\text{H}_3\text{PO}_4$

Impure orthophosphoric acid  $\text{H}_3\text{PO}_4$  is prepared in large amounts by treating phosphate rock with  $\text{H}_2\text{SO}_4$ . This is called the 'wet process'. The  $\text{CaSO}_4$  is hydrated to gypsum  $\text{CaSO}_4 \cdot 2\text{H}_2\text{O}$ , which is filtered off, and the  $\text{F}^-$  is converted to  $\text{Na}_2[\text{SiF}_6]$  and removed. The  $\text{H}_3\text{PO}_4$  is concentrated by evaporation. Most of the  $\text{H}_3\text{PO}_4$  made in this way is used to make fertilizer.




Pure  $\text{H}_3\text{PO}_4$  is made by the 'furnace process'. Molten P is burnt in a furnace with air and steam. First  $\text{P}_4\text{O}_{10}$  is formed by reaction between P and O, and then this is immediately hydrolysed.




Phosphoric acid is hydrogen bonded in aqueous solution, and because of this the 'concentrated acid' is syrupy and viscous. Concentrated acid is widely used and contains about 85% by weight of  $\text{H}_3\text{PO}_4$  (100% pure (anhydrous)  $\text{H}_3\text{PO}_4$  is seldom used, but it can be prepared as colourless deliquescent crystals by evaporation at low pressure). Most of the acid (solution) made in this way is used in the laboratory, and in food (Kraft cheese  $\text{Na}_2\text{HPO}_4$ ) and pharmaceutical preparations.

$\text{H}_3\text{PO}_4$  may also be made by the action of concentrated  $\text{HNO}_3$  on P.




Orthophosphoric acid loses water steadily on heating:



### Polyphosphates

A very large number of polyphosphoric acids and their salts, the polyphosphates, arise by polymerizing acidic  $[\text{PO}_4]$  units forming isopolyacids. These consist of chains of tetrahedra, each sharing the O atoms at one or two corners of the  $[\text{PO}_4]$  tetrahedron, giving simple unbranched chains, in a similar way to the formation of pyroxenes by the silicates.

The hydrolysis of  $\text{P}_4\text{O}_{10}$  proceeds in stages, and an understanding of these stages leads to an understanding of the wide range of phosphoric acids (Figure 14.14).



Polyphosphates are straight chain compounds. The basicity of the various acids, that is the number of replaceable H atoms, can be found by drawing the structure and counting the number of OH groups. Thus




Figure 14.13 Pyrophosphoric acid  $\text{H}_4\text{P}_2\text{O}_7$  and tripolyphosphoric acid  $\text{H}_5\text{P}_3\text{O}_{10}$

orthophosphoric acid is tribasic, pyrophosphoric acid is tetrabasic, tripolyphosphoric acid is pentabasic, tetrapolyphosphoric acid is hexabasic, and tetrametaphosphoric acid is tetrabasic





Figure 14.14 Scheme for the hydrolysis of  $\text{P}_4\text{O}_{10}$

Many polyphosphates are known. Chains of different lengths with up to ten  $[\text{PO}_4]$  units have been isolated, but the first four in the series are well known.

$\text{H}_3\text{PO}_4$	orthophosphoric acid
$\text{H}_4\text{P}_2\text{O}_7$	dipolyphosphoric acid (pyrophosphoric acid)
$\text{H}_5\text{P}_3\text{O}_{10}$	tripolyphosphoric acid
$\text{H}_6\text{P}_4\text{O}_{13}$	tetrapolyphosphoric acid

Some very long chain polymers called Graham's salt, Kurrol salt and Maddrell's salt are also known. These are named after the person who first reported them, and they are discussed later.


Disodium dihydrogenpyrophosphate  $\text{Na}_2\text{H}_2\text{P}_2\text{O}_7$  is mixed with  $\text{NaHCO}_3$  and used in bread making to leaven the bread, that is to make it rise. They react and evolve  $\text{CO}_2$  when heated together. This is an easier way of making batches of bread than using yeast, and is used commercially.




$\text{Ca}_2\text{P}_2\text{O}_7$  is used as the abrasive/polishing agent in fluoride toothpaste, and  $\text{Na}_4\text{P}_2\text{O}_7$  is mixed with starch and flavouring to make 'instant pudding' mixtures.

At one time sodium pyrophosphate  $\text{Na}_4\text{P}_2\text{O}_7$  was added to soap powders and solutions as a water softener, to prevent the formation of scum in hard water. For many purposes detergents, e.g. anionic and non-ionic surfactants (surface active agents), have replaced soap. Also  $\text{Na}_4\text{P}_2\text{O}_7$  has been replaced by sodium tripolyphosphate  $\text{Na}_5\text{P}_3\text{O}_{10}$ . Between 20% and 45% of  $\text{Na}_5\text{P}_3\text{O}_{10}$  is added to solid detergent powders and liquid detergents (washing up fluids etc.) used in the home and in industry. (The lower figure applies to the USA, where there have been bad experiences of extensive pollution of rivers and lakes.) Sodium tripolyphosphate is called a 'filler' because it increases the quantity of material in the packet. Its main usefulness, however, is in serving as a water softener. It does this by forming a stable soluble complex with  $\text{Ca}^{2+}$  and  $\text{Mg}^{2+}$ . This is called sequestration, and results in the effective removal (masking) of these ions which are responsible for hardness in water. Thus  $\text{Ca}^{2+}$  and  $\text{Mg}^{2+}$  ions do not form precipitates with  $\text{CO}_3^{2-}$  ions or with soap in its presence.  $\text{Na}_5\text{P}_3\text{O}_{10}$  also makes the solution alkaline which helps dissolve grease and improves the action of the detergent.  $\text{Na}_5\text{P}_3\text{O}_{10}$  can be prepared in the following ways:

1. The most common method of preparation is to fuse the correct quantities of  $\text{Na}_2\text{HPO}_4$  and  $\text{NaH}_2\text{PO}_4$ . Recrystallization from water gives the hexahydrate  $\text{Na}_5\text{P}_3\text{O}_{10} \cdot 6\text{H}_2\text{O}$ :



2. In Germany it is largely made by fusing  $\text{Na}_2\text{O}$  and  $\text{P}_4\text{O}_{10}$ . On cooling, the pyrophosphate  $\text{Na}_2\text{P}_2\text{O}_7$  crystallizes out first, but with slow cooling this changes into  $\text{Na}_5\text{P}_3\text{O}_{10}$ :



### Long chain polyphosphates – linear metaphosphates

The very long chain polyphosphates have caused confusion in the past since they were originally called metaphosphates – a name used for ring compounds. When the number of units in the polymer  $n$  becomes very large, the formula of a chain polyphosphate  $(\text{PO}_3)_n$ ,  $\text{PO}_4$  becomes indistinguishable from that of a true metaphosphate, that is a ring compound with a formula  $(\text{PO}_3)_n$ . The long chains are sometimes called linear metaphosphates.

Graham's salt is the best known of these long chain polyphosphates and is formed by quenching molten  $\text{NaPO}_3$ . It forms a glassy solid instead of crystallizing. In industry it is incorrectly called sodium hexametaphosphate. This is wrong because it does not contain six  $[\text{PO}_4]$  units and is a high molecular weight polymer  $(\text{NaPO}_3)_n$ , which usually has a mean molecular weight of 12000–18000, and up to 200  $[\text{PO}_4]$  units in the chain. Though mainly made up of long chains, it does contain up to 10% of ring metaphosphates and a little cross linked material. (Molecular weights of these long chain polymeric species can be determined by titrating the end groups, and also from osmotic pressure, diffusion, viscosity, electrophoresis, and ultracentrifuge measurements.) Graham's salt is soluble in water. These solutions give precipitates with metal ions such as  $\text{Pb}^{2+}$  and  $\text{Ag}^+$  but not with  $\text{Ca}^{2+}$  and  $\text{Mg}^{2+}$ . Graham's salt is sold commercially under the trade name Calgon. It is widely used for softening water. It sequesters  $\text{Ca}^{2+}$  and  $\text{Mg}^{2+}$  in a similar way to  $\text{Na}_5\text{P}_3\text{O}_{10}$ . Many of these polyphosphates are used for water softening and also for descaling boilers and pipes.

Heating  $\text{Na}_2\text{H}_2\text{P}_2\text{O}_7$  results in dehydration but three different products are formed depending on the vapour pressure of water. If heated in air (an open system), where water can escape then cyclic sodium trimetaphosphate is formed. Heating in a closed system where the water cannot escape, yields either Maddrell's high temperature or low temperature salt. These are crystalline, as is Kurrol's salt. They consist of chains of tetrahedral  $[\text{PO}_4]$  units, and they differ in the way the tetrahedra are oriented in the chains. Thus Kurrol's salt is made up of helical chains of  $[\text{PO}_4]$  units and the structure contains an equal number of left handed and right handed helices. Thus chains may differ in their length and they may also have different repeat units, as was found in the chain silicates.

These and other relationships are shown in (Figure 14.15).

When (cyclic) sodium trimetaphosphate melts at about  $625^\circ\text{C}$  long chain polyphosphates are formed. If the liquid is cooled rapidly these chains remain (Graham's salt). Annealing Graham's salt above  $550^\circ\text{C}$  gives Kurrol's salt. This exists in two forms – one fibrous and the other plate like. They have different densities. The two different forms are





Figure 14.15 Relation of various polyphosphates.

similar to the asbestos minerals in the silicates, some of which are made of chains, and others of sheets. Annealing one form of Kurrol salt at 400°C gives sodium trimetaphosphate, and the other gives Maddrell's high temperature salt. All forms of sodium polyphosphate revert to (cyclic) sodium trimetaphosphate near the melting point 625°C, or on annealing (prolonged heating) at 400°C. This is presumably because the trimetaphosphate has the most stable crystal structure.

### Metaphosphates – cyclophosphates

The metaphosphates form a family of ring compounds. The old name of metaphosphates is still widely used even though according to IUPAC nomenclature cyclo- should be used to indicate the formation of rings. They can be prepared by heating orthophosphates:



There is no evidence for the existence of free monometaphosphate ions  $\text{PO}_3^-$ , or of dimetaphosphate ions. The latter would involve the sharing of







Figure 14 16 Some polyphosphate ions

two corners, that is an edge between two  $[\text{PO}_4]$  tetrahedra and would impose a great deal of strain on the structure. In contrast tri and tetra metaphosphates are well known. A few larger rings have been isolated with up to eight  $[\text{PO}_4]$  units that is up to  $\text{Na}_8[\text{P}_8\text{O}_{24}]$ . These are obtained as mixtures and are conveniently separated by paper chromatography or thin layer chromatography.

Sodium trimetaphosphate  $\text{Na}_3\text{P}_3\text{O}_9$  is made by heating  $\text{NaH}_2\text{PO}_4$  to  $640^\circ\text{C}$  and holding the melt at  $500^\circ\text{C}$  for some time to allow the condensation to take place and the water to be evolved. The ring structure has been established by X ray analysis of several salts. Hydrolysis of the ring compound sodium trimetaphosphate by alkali gives the chain compound sodium tripolyphosphate.



Sodium tetrametaphosphate  $\text{Na}_4\text{P}_4\text{O}_{12} \cdot 4\text{H}_2\text{O}$  is formed when  $\text{P}_4\text{O}_{10}$  is treated with a solution of cold  $\text{NaOH}$  or  $\text{NaHCO}_3$ .

### Hypophosphoric acid $\text{H}_4\text{P}_2\text{O}_6$

This contains P in the oxidation state (+IV) and has one less O atom than pyrophosphoric acid  $\text{H}_4\text{P}_2\text{O}_7$ . It is prepared by hydrolysis and oxidation of





Figure 14 17 Hydrolysis and oxidation of yellow phosphorus


red phosphorus by NaOCl, or yellow phosphorus by water and air. There are no P—H bonds, and so this acid is not a reducing agent. There are four acidic hydrogens, and hence the acid is tetrabasic and can form four series of salts, though usually two hydrogens are replaced. It is unusual in that it contains a P—P bond. This is much stronger than the P—O—P bond, so hydrolysis is slow.



### THE PHOSPHOROUS ACID SERIES


The phosphorous acids are less well known. They all contain phosphorus in the oxidation state (+III). They have P—H bonds and are therefore reducing agents.

Hydrolysis of  $\text{P}_4\text{O}_6$  in a manner analogous to the hydrolysis of  $\text{P}_4\text{O}_{10}$  already described yields pyro- and orthophosphorous acids, which are both dibasic and reducing agents.



#### Orthophosphorous acid $\text{H}_3\text{PO}_3$

$\text{H}_3\text{PO}_3$  contains two acidic H atoms (the OH groups), and one reducing H (the P—H hydrogen atom). Consequently only two of the three H atoms can ionize, and the acid is dibasic.



Thus  $\text{H}_3\text{PO}_3$  can form two series of salts:

1. Dihydrogen phosphites, for example  $\text{NaH}_2\text{PO}_3$ .
2. Monohydrogen phosphites, for example  $\text{Na}_2\text{HPO}_3$ .

The phosphites are very strong reducing agents in basic solutions. In acid solutions they are converted to  $\text{H}_3\text{PO}_3$ , which is still a moderately strong reducing agent.

**Metaphosphorous acid ( $\text{HPO}_2$ )<sub>n</sub>**

This can be prepared from phosphine at low pressure



If the formula were  $\text{HPO}_2$  the P atom would only form three bonds or else form double bonds. In fact it polymerizes rather than form double bonds. The structure is not known but by analogy with metaphosphoric acid it may well be a ring structure.

**Hypophosphorous acid  $\text{H}_3\text{PO}_2$** 

$\text{H}_3\text{PO}_2$  contains P in the oxidation state (+1) and has one O atom less than the orthophosphorous acid. It is prepared by alkaline hydrolysis of phosphorus.



The acid is monobasic and a very strong reducing agent. Salts of this acid are called hypophosphites and sodium hypophosphite  $\text{NaH}_2\text{PO}_2$  is used industrially to bleach wood and to make paper.




Figure 14.18 Alkaline hydrolysis of phosphorus

**MAJOR USES OF PHOSPHATES**

Phosphate rock is mined on a vast scale (145 million tonnes in 1992). The minerals vary both in purity and in composition. Industry expresses the production of phosphates in terms of the  $\text{P}_2\text{O}_5$  content. On this basis world production of phosphates is about 34 million tonnes per year (This is equivalent to 46.9 million tonnes of  $\text{H}_3\text{PO}_4$ ). The major commercial uses are as follows:


- 85% For fertilizers such as superphosphate, triple superphosphate and ammonium phosphate. These do not need to be especially pure.
- 5% Added to detergents (builders i.e. fillers) mainly sodium triphosphates in powders and sodium pyrophosphate in liquid preparations.

- 3% Used in the food industry to give the acid taste in drinks such as cola (pH 2), sarsaparilla and root beer, and as an emulsifier in processed cheese, dried milk, sausages etc.
- 2½% For treating metals.
- Rustproofing, by dipping the hot metal into phosphoric acid, or heating the acid to 90–95 °C (sometimes with  $\text{Zn}^{2+}$ ,  $\text{Mn}^{2+}$   $\text{Cu}^{2+}$  or other ions present) in processes such as Parkerizing and Bonderizing. Small metal parts such as nuts, bolts and screws are treated in this way, and also motor car bodies, refrigerators etc. before they are painted.
  - Pickling metals, that is removing scale and oxide from the surface of iron and steel by dipping in an acid bath.
  - 'Bright dipping' of aluminium parts. The parts are connected to the anode and electrolysed in a bath of  $\text{H}_3\text{PO}_4$  with a small amount of  $\text{HNO}_3$  and a trace of  $\text{Cu}(\text{NO}_3)_2$ . This gives a highly polished Al surface protected by a clear layer of  $\text{Al}_2\text{O}_3$ .
- 1% For industrial uses such as water softening (particularly calgon, and trisodium phosphate  $\text{Na}_3\text{PO}_4$ ), buffers ( $\text{NaH}_2\text{PO}_4$  and  $\text{Na}_2\text{HPO}_4$ ), paint strippers ( $\text{Na}_3\text{PO}_4$ ), and removing  $\text{H}_2\text{S}$  from gases particularly in the petroleum industry ( $\text{K}_3\text{PO}_4$ ).
- 1% For making phosphorus sulphides (for matches).
- 1% For making organophosphorus compounds: plasticizers (triaryl phosphates), insecticides (triethyl phosphate) and petrol additives (tritoyl phosphate).
- 1% For pharmaceutical products such as toothpaste ( $\text{CaHPO}_4 \cdot 2\text{H}_2\text{O}$ , or  $\text{Ca}_2\text{P}_2\text{O}_7$  in fluoride toothpaste), and combined baking powder ( $\text{Ca}(\text{H}_2\text{PO}_4)_2$  which is slightly acidic, mixed with  $\text{NaHCO}_3$ ).
- ½% Flameproofing fabrics (ammonium phosphates and urea phosphate  $\text{NH}_2\text{CONH}_2 \cdot \text{H}_3\text{PO}_4$ ).


The excessive use of phosphates as water softeners is criticized by environmentalists, since it contributes to water pollution. The phosphates in domestic waste water pass through sewage disposal systems into rivers and lakes. There they nourish bacteria, which grow excessively and deplete the water of dissolved dioxygen, thus killing the fish. The phosphates may also produce a massive overgrowth of water plants. When this crop of plants dies, there will be excessive decay and putrefaction which may also kill the fish. The tendency of the acidic ions of P to condense and give isopolyacids is quite strong. The phosphates and phosphites are similar to the arsenates and arsenites. Condensed As anions are much less stable than the corresponding P polyanions and they are rapidly hydrolysed in water. Antimonates and antimonites are known, but Sb has a coordination number of 6, and these salts contain the octahedral  $[\text{Sb}(\text{OH})_6]^-$  ion.

## SULPHIDES OF PHOSPHORUS


When P and S are heated together to a temperature over 100 °C,  $\text{P}_4\text{S}_3$ ,  $\text{P}_4\text{S}_6$ ,  $\text{P}_4\text{S}_7$  and  $\text{P}_4\text{S}_{10}$  may be formed depending on the relative amounts of




Tetra phosphorus  
trisulphide  $P_4S_3$



Tetra phosphorus  
pentasulphide  $P_4S_5$



Tetra phosphorus  
heptasulphide  $P_4S_7$



Tetra phosphorus  
decasulphide  $P_4S_{10}$

Figure 14 19 Structures of phosphorus sulphides

reactants present. Two more compounds  $P_4S_4$  and  $P_4S_9$  have been made using other reactions.


$P_4S_{10}$  is structurally the same as  $P_4O_{10}$ , but the absence of  $P_4S_6$  is surprising. The structures of the other sulphides have no counterparts in the oxides. They are loosely related to the structures of the oxides  $P_4O_6$  and  $P_4O_{10}$  with a tetrahedron of P atoms, with some S atoms bridging between P atoms and others occupying apical positions attached to P atoms.

### $P_4S_3$

Phosphorus trisulphide  $P_4S_3$  is the most stable sulphide. It is made by heating red phosphorus and a limited amount of sulphur to  $180^\circ\text{C}$  in an inert atmosphere. It is soluble in organic solvents such as toluene and carbon disulphide. Traces of unreacted P can be removed either by recrystallization from toluene or by distillation.  $P_4S_3$  is used commercially for making matches. Matches contain  $P_4S_3$ ,  $\text{KClO}_3$ , fillers and glue. The friction between the match and the sandpaper on the side of the box initiates a violent reaction between the  $P_4S_3$  and  $\text{KClO}_3$ . This generates enough heat to make the match burst into flame.

$P_4S_{10}$ 

$P_4S_{10}$  is the most important sulphide. It is made by reacting liquified white phosphorus at  $300^\circ\text{C}$  with a slight excess of sulphur. World production is about 250 000 tonnes/year. It hydrolyses in water, forming phosphoric acid in a similar way to  $P_4O_{10}$ .



The most important reaction of  $P_4S_{10}$  is hydrolysis by alcohols and phenols to give dialkyl or diaryl dithiophosphoric acids.






Figure 14.20 Structures of thiophosphoric acids.

The Zn salts of dialkyl and diaryl thiophosphates  $[(RO)_2 \cdot P \cdot (S)]_2Zn$  are used as extreme pressure additives in high pressure lubricants such as gearbox oil.  $(EtO)_2 \cdot P \cdot (S) \cdot Na$  and  $(EtO)_2 \cdot P \cdot (S) \cdot NH_4$  are used as flotation agents for concentrating sulphide ores such as  $PbS$  and  $ZnS$  before smelting. The methyl and ethyl derivatives are used in the manufacture of pesticides such as malathion and parathion.




These organophosphorus esters are very effective insecticides. They prevent the nervous system of insects from working properly, thus killing the insects very rapidly. Acetylcholine is a chemical neurotransmitter, produced to transmit nerve impulses across a synaptic junction. Normally the enzyme acetylcholinesterase destroys the acetylcholine once the im-

pulse has been transmitted. These organophosphorus esters inhibit the action of acetylcholinesterase. Malathion and parathion are not toxic if eaten by mammals, since the digestive system breaks the molecule down before it enters the body.


### PHOSPHAZENES AND CYCLOPHOSPHAZENES (PHOSPHONITRILIC COMPOUNDS)

Nitrogen and phosphorus show only a slight tendency to catenate by themselves. The maximum chain length for nitrogen is three in the azide  $\text{N}_3^-$  ion and two for phosphorus in a few compounds such as  $\text{P}_2\text{H}_4$  and  $(\text{Me}_2)(\text{S})\text{P}-\text{P}(\text{S})(\text{Me}_2)$ . A few ring compounds exist with four, five or six P or As atoms joined together.


In contrast to this, N and P may bond together, forming a large number of phosphazenes. In these the P atom is in the oxidation state (+V) and N is in the (+III) state. The compounds are formally unsaturated. Thus monophosphazenes may be made by reacting an azide with  $\text{PCl}_5$ ,  $\text{POR}_3$  or  $\text{P}(\text{C}_6\text{H}_5)_3$ .



Diphosphazenes can be made as follows



However, N and P catenate together forming an interesting series of polymers



This reaction produces a mixture of ring compounds  $(\text{NPCl}_2)_n$  where  $n = 3, 4, 5, 6, \dots$ , and fairly short linear chains. The most common rings ( $n = 3$  and 4) contain six or eight atoms. The former are flat and the latter exist in 'chair' and 'boat' conformations.

A large number of chain compounds are known. These range from short chains  $\text{P}_2\text{NCl}_7$ ,  $\text{P}_3\text{N}_2\text{Cl}_9$ ,  $\text{P}_4\text{N}_3\text{Cl}_{11}$  to those with up to  $10^4$  units.




Figure 14.21 Some cyclophosphazene compounds

$[-N=PCl_2-]$  linked together. These compounds were originally called phosphonitrilic halides, but are now named systematically poly(chlorophosphazenes).








Figure 14.22 Some polyphosphazene chain compounds.

The chlorine atoms are reactive, and most reactions of chlorophosphazenes involve replacement of Cl by groups such as alkyl, aryl, OH, OR, NCS or  $NR_2$ . Alkyl or aryl groups may be introduced using lithium or Grignard reagents. Substitution may be complete, or partial, and in the latter case many different isomers are possible.



Similar compounds are formed with Br and F. The largest rings formed contain 34 atoms in the chlorides and 12 atoms in the bromides. Some of the long chain polymers are rubber-like, and those with perfluoroalkoxy side groups  $[NP(OCH_2CF_3)_2]_n$  resemble polythene.

There are many potential uses for the high molecular weight phosphazenes, as rigid plastics, expanded foam, and fibres, since they are waterproof and fireproof, and are unaffected by petrol, oil, and solvents. They also form flexible plastics which are useful for fuel hoses and gaskets since they retain their elasticity at low temperatures. The phosphazenes are at present far too expensive for general use. Thin films of poly(aminophosphazene) are used in hospitals to cover severe burns and other extensive wounds since they prevent the loss of body fluids and keep germs out.

There are two main points of interest in these P—N compounds:

1. The nature of the bonding is not understood. In all of these phosphazene compounds the (apparent) P—N and P=N bonds are equivalent. Their bond lengths are 1.56–1.59 Å, which is much shorter than the usual single bond distance of 1.77 Å. Thus the bonding in these compounds is not adequately represented by a system of alternate single



and double bonds, nor can it be explained by  $p\pi-p\pi$  bonding and delocalization similar to that in benzene or graphite. It has been suggested that a coordinate bond is formed between a filled  $sp^2$  orbital on N and the empty  $3d_{x^2-y^2}$  orbital on P. This is similar to the  $p\pi-d\pi$  bonding in the oxides of phosphorus except that in the phosphazenes the  $\pi$  bonds are delocalized over the whole molecule, giving pseudo-aromatic character. There are objections to this because of the size and energy of the  $d$  orbitals. Alternatively the singly occupied  $p_z$  orbital on N may form a three centre bond with the  $d_{xz}$  and  $d_{yz}$  orbitals on the two adjacent P atoms.



- 2 The polyphosphazenes form a very extensive series of polymers. Carbon based polymers are the most extensive, then the silicones then the phosphazenes.

## ORGANOMETALLIC COMPOUNDS



Nitrogen forms primary, secondary and tertiary amines  $RNH_2$ ,  $R_2NH$  and  $R_3N$  which are described fully in organic chemistry texts.

Many organophosphorus compounds are toxic. Some have been used as pesticides, herbicides, and nerve gases. Others play an essential part in life.

The halides of P, As, Sb and Bi react readily with lithium reagents and Grignard reagents, forming alkyl and aryl compounds. The best known are the tertiary phosphine compounds such as triphenyl phosphine.






The trimethyl derivatives of P, As, Sb and Bi are all attacked by air, but the triaryl compounds are stable. It is not necessary to substitute all three halogen atoms, and mixed halo organo species can be made either by using an excess of  $PCl_3$  or by using a weaker alkylating or arylating agent.



The structures of  $MR_3$  derivatives are pyramidal (tetrahedral with one position occupied by a lone pair) like  $NH_3$ . The trialkyls of P and As possess strong donor properties and consequently form many complexes with transition metals. In these a  $\sigma$  bond is formed using the lone pair of electrons and a  $\pi$  bond is formed by 'back bonding', arising from the donation of electrons from a full  $d$  orbital on the transition metal to an empty  $d$  orbital on P or As. This 'back bonding' is similar to that discussed under the oxides of phosphorus, but since it involves two  $d$  orbitals it is called  $d\pi-d\pi$  bonding.


Some  $MR_3$  derivatives can be made in a similar way, and their structures

are similar to that of  $\text{PCl}_5$ ; that is a trigonal bipyramidal structure. It is rare to have five organic groups bonded to P.



Several ions  $\text{NR}_4^+$ ,  $\text{PR}_4^+$ ,  $\text{AsR}_4^+$  and  $\text{SbR}_4^+$  exist which are tetrahedral like the ammonium ion.

Treatment of  $\text{POCl}_3$  with lithium or Grignard reagents yields trialkyl and triaryl phosphine oxides.



Phosphate esters play a vital role in many life processes:

1. The release of energy in living matter by adenosine triphosphate ( $\text{ATP} \rightarrow \text{ADP} + \text{energy}$ ) has been described earlier. Nicotinamide adenine dinucleotide (NAD) is important in the degradation of citric acid in the Krebs' cycle for the release of energy. Another ester, phosphocreatine, is important in the regeneration of ATP, and others control the synthesis and storage of carbohydrates such as glycogen in animals.
2. Phosphate esters are also important in the synthesis of proteins and nucleic acids. Deoxyribonucleic acids, DNA, are responsible for the storage and transfer of genetic information. The sequence of organic bases is specific for each nucleic acid. The DNA molecules comprise two strands which are hydrogen bonded together and form a double helix. Ribonucleic acids, RNA, are similar, but are usually single strands, and form a single helix. Their function is to act as a template to produce identical nucleic acids, with the same sequence of bases, and the same orientation in space.
3. Phosphate esters also play a part in photosynthesis, and the conversion of surplus sugar into starch in plants.
4. Phosphate esters are also involved in dinitrogen fixation.

## FURTHER READING

- Addison, C.C. (1980) Dinitrogen tetroxide, nitric acid, and their mixtures as media for inorganic reactions, *Chem. Rev.*, **80**, 21–39.
- Addison, C.C., Logan, N., Wallwork, S.C. and Garner, C.D. (1971) Structural aspects of coordinated nitrate groups, *Q. Rev. Chem. Soc.*, **25**, 289–322.
- Allcock, H.R. (1972) *Phosphorus Nitrogen Compounds*, Academic Press, London.
- Allcock, H.R. (1985) Inorganic macromolecules, *Chem. Eng. News*, March 18 issue, 22–36.
- Arena, B.J. (1986) Ammonia: confronting a primal trend, *J. Chem. Ed.*, **63**, 1040–1043.
- Aylett, B.J. (1979) Arsenic, antimony and bismuth, *Organometallic Compounds*, 4th ed., Vol. I, Part 2, Chapman and Hall, London.
- Baudler, M. (1987) Polyphosphorus compounds – new results and new perspectives, *Angewandte Chemie*, International Edition, **26**, 419–441.

- Bergersen, F J and Postgate, J R (eds) (1987) *A Century of Nitrogen Fixation Research*, Royal Society, London
- Bossard, G E *et al* (1983) Reactions of coordinated dinitrogen, *Inorg Chem*, **22**, 1968-1970
- Bottomley, F and Burns, R C (1979) *Treatise on Dinitrogen Fixation*, Wiley, New York
- Broughton, W J and Phler, A (1986) *Nitrogen Fixation*, Clarendon, Oxford
- Cardulla, F (1983) Hydrazine *J Chem Ed*, **60**, 505-508
- Chatt, J, Dilworth, J R and Richards, R L (1978) Recent advances in the chemistry of nitrogen fixation, *Chem Rev*, **78**, 589-625
- Chatt, J, da C Pina, L M and Richards, R L (eds) (1980) *New Trends in the Chemistry of Nitrogen Fixation*, Academic Press, London and New York (Conference papers)
- Coates, G E and Wade, K (1967) Antimony and bismuth *Organometallic Compounds*, 3rd ed, Vol 1 (Chapter 5), Methuen, London
- Colburn, C B (ed) (1966) *Developments in Inorganic Nitrogen Chemistry*, Vol 1 (Chapter 2 by Yoffe, A D, The Inorganic Azides Chapter 5 by Nielsen, M L, Phosphorus nitrogen compounds), Elsevier, Amsterdam
- Corbridge, D E (1985) *Phosphorus: An Outline of Its Chemistry, Biochemistry and Technology*, 3rd ed (No 6, Studies in Inorganic Chemistry), Elsevier, Oxford
- Emsley, J and Hall, D (1976) *The Chemistry of Phosphorus*, Harper and Row, New York
- Evans, H J, Bottomley, P J and Newton, W E (eds) (1985) *6th International Symposium on Nitrogen Fixation* (held at Corvallis, Or) Dordrecht, Lancaster, Nijhoff
- Lysseltov, J and Dirkse, T P (eds) (1988) *Alkali Metal Orthophosphates*, Pergamon
- Gallon, J R and Chaplin, A E (1987) *An Introduction to Nitrogen Fixation*, Cassell
- Glidewell, C (1990) The nitrate/nitrite controversy, *Chemistry in Britain* **26**, 26-30 (On the harmful effects of nitrates in drinking water)
- Goldwhite, H (1981) *Introduction to Phosphorus Chemistry* (Cambridge texts in Chemistry and Biochemistry), Cambridge University Press, Cambridge
- Griffith, E J (1975) The chemical and physical properties of condensed phosphates, *Pure Appl Chem*, **44**, 173-200
- Griffith, W P (1968) Organometallic nitrosyls *Adv Organometallic Chem* **7**, 211
- Griffith, W P (1973) *Comprehensive Inorganic Chemistry*, Vol 4 (Chapter 46, Carbonyls, cyanides, isocyanides and nitrosyls), Pergamon Press, Oxford
- Hamilton, C L (ed) (1973) *Chemistry in the Environment* (Chapter 5 by Delwiche, C C, The Nitrogen Cycle) Readings from Scientific American, W H Freeman, San Francisco
- Heal, H G (1980) *The Inorganic Heterocyclic Chemistry of Sulphur, Nitrogen and Phosphorus*, Academic Press, London
- Henderson, R A, Leigh, G J and Pickett, C J (1983) The chemistry of nitrogen fixation and models for the reactions of nitrogenase, *Adv Inorg Chem Radiochem*, **27**, 197-292
- Hoffmann, H and Becke-Goehring, M (1976) Phosphorus sulphides, *Topics Phosphorus Chem*, **8**, 193-271 (A comprehensive review with over 400 references)
- Holm, R H (1981) Metal clusters in biology: quest for synthetic representation of the catalytic site of nitrogenase, *Chem Soc Rev*, **10**, 455-490
- Jander, J (1976) Recent chemistry and structure investigation of  $\text{Ni}_3$ ,  $\text{NbF}_3$ ,  $\text{NCl}_3$  and related compounds, *Adv Inorg Chem Radiochem*, **19**, 1-63
- Johnson, B F G and McCleverty, J A (1966) Nitric oxide compounds of transition metals, *Progr Inorg Chem*, **7**, 277
- Jolly, W L (1972) *Metal Ammonia Solutions*, Dowden, Hutchinson and Row, Stroudburg, PA

- Jones, K. (1973) *Comprehensive Inorganic Chemistry*, Vol. II (Chapter 19: Nitrogen), Pergamon Press, Oxford.
- Kanazawa, T. (ed.) (1989) *Inorganic Phosphate Materials*, Kodansha, Tokyo.
- Kulaev, I.S. (1980) *The Biochemistry of Inorganic Polyphosphates*, John Wiley, Chichester.
- Lagowski, J. (ed.) (1967) *The Chemistry of Non-aqueous Solvents* (Chapter 4 by Lee, W.H., Nitric Acid; Chapter 7 by Lagowski, J.J. and Moczygamba, G.A., Liquid ammonia, Academic Press, New York.
- Lee, J.A., Rorison, I.H. and McNeill, S. (eds) (1983) *Nitrogen as an Ecological Factor* (22nd symposium of the British Ecological Society, Oxford, 1981), Blackwell Scientific Publications, Oxford.
- Lieu, N.H. et al. (1984) Reduction of molecular nitrogen in molybdenum (III–V) hydroxide/titanium(III), *Inorg. Chem.*, **23**, 2772–2777.
- McAuliffe, C.A. and Levason, W. (1979) *Phosphine, Arsine and Stibine Complexes of the Transition Metals*, Elsevier, Amsterdam.
- Nicholls, D. (1979) *Inorganic Chemistry in Liquid Ammonia* (Topics in Inorganic and General Chemistry, Monograph 17), Elsevier.
- Postgate, J.R. (1982) *The Fundamentals of Nitrogen Fixation*, Cambridge University Press, Cambridge.
- Richards, R.L. (1979) Nitrogen fixation, *Education in Chemistry*, **16**, 66–69.
- Richards, R.L. (1988) Biological nitrogen fixation, *Chemistry in Britain*, **24**, 133–134, 136.
- Schmidt, E.W. (1984) *Hydrazine and its Derivatives: Preparation, Properties Applications*, John Wiley, New York and Chichester.
- Smith, J.D. (1973) *Comprehensive Inorganic Chemistry*, Vol. II (Chapter 21: Nitrogen), Pergamon Press, Oxford.
- Toy, A.D.F. (1973) *Comprehensive Inorganic Chemistry*, Vol. II (Chapter 20: Chemistry of phosphorus), Pergamon Press, Oxford.
- Toy, A.D.F. (1975) *Chemistry of Phosphorus*, Pergamon Press, New York.
- Thompson, R. (ed.) (1986) *The Modern Inorganic Chemicals Industry* Chapter by Grant, W.J. and Redfearn, S.L., Industrial gases; chapter by Andrew, S.P., Modern processes for the production of ammonia, nitric acid and ammonium nitrate; chapter by Childs, A.F., Phosphorus, phosphoric acid and inorganic phosphates), Special Publication No. 31, The Chemical Society, London.
- Waddington, T.C. (ed.) (1965) *Non Aqueous Solvent Systems* (Chapter 1 by Jolly, W.L. and Hallida, C.J., Liquid ammonia), Nelson.
- Wright, A.N. and Winkler, C.A. (1968) *Active Nitrogen*, Academic Press, New York.
- Yamabe, T., Hori, K., Minato, T. and Fukui, K. (1980) Theoretical study on the bonding nature of transition metal complexes of molecular nitrogen, *Inorg. Chem.*, **19**, 2154–2159.

## PROBLEMS

1. Use the molecular orbital theory to describe the bonding in  $\text{N}_2$  and  $\text{NO}$ . What is the bond order in each case?
2. Explain why nitrogen molecules have the formula  $\text{N}_2$ , whilst phosphorus has the formula  $\text{P}_4$ .
3. Outline how nitrogen and phosphorus are obtained commercially.
4. Write balanced equations to show the effect of heat on (a)  $\text{NaNO}_3$ , (b)  $\text{NH}_4\text{NO}_3$ , (c) a mixture of  $\text{NH}_4\text{Cl}$  and  $\text{NaNO}_2$ , (d)  $\text{Cu}(\text{NO}_3)_2 \cdot 2\text{H}_2\text{O}$ , (e)  $\text{Pb}(\text{NO}_3)_2$  and (f)  $\text{NaN}_3$ .

- 5 Give equations to show how the following materials react with water  
(a)  $\text{Li}_3\text{N}$ , (b)  $\text{CaNCN}$ , (c)  $\text{AlN}$ , (d)  $\text{NO}_2$ , (e)  $\text{N}_2\text{O}_5$ , (f)  $\text{NCl}_3$
- 6 Describe the commercial methods for manufacturing  $\text{NH}_3$  and  $\text{HNO}_3$   
How are the starting materials obtained? What are their main uses?  
How is  $\text{HNO}_3$  concentrated?
- 7 Explain the  $\pi$  bonding in  $\text{NO}_3^-$
- 8 Write an account of the chemistry of the oxides of nitrogen. Describe and give equations for the preparation of each, and discuss their properties, reactivity structures and bonding
- 9 Describe the conditions under which the following react, and give the products in each case
  - (a) copper and nitric acid
  - (b) nitrous oxide and sodamide
  - (c) calcium carbide and nitrogen
  - (d) cyanide ions and cupric sulphate
  - (e) ammonia and an acidified solution of sodium hypochlorite
  - (f) nitrous acid and iodide ions
- 10 Describe the production of hydrazine and hydrazine sulphate. What practical difficulties are involved? What are they used for?
- 11 Explain what happens and give equations for the reaction of an aqueous solution of hydrazine sulphate with
  - (a) an aqueous solution of  $\text{I}_2$  in  $\text{KI}$
  - (b) an alkaline solution of copper sulphate
  - (c) an aqueous solution of potassium ferricyanide  $\text{K}_3[\text{Fe}(\text{CN})_6]$
  - (d) an ammoniacal solution of silver nitrate
- 12 Why is  $\text{NF}_3$  stable whilst  $\text{NCl}_3$  and  $\text{NI}_3$  are explosive?
- 13 Why is it that  $\text{NF}_3$  has no donor properties, but  $\text{PF}_3$  forms many complexes with metals? Give examples of such complexes
- 14 Give a preparation of  $\text{NH}_2\text{OH}$  and describe one of its major uses
- 15 What are the main ingredients in fertilizers? How are they made and what use do the plants make of them?
- 16 Compare the oxides of nitrogen and phosphorus
- 17 Substance (A) is a gas of vapour density 8.5. On oxidation at high temperature with a platinum catalyst it gave a colourless gas (B), which rapidly turned brown in air, forming a gas (C). (B) and (C) were condensed together to give substance (D), which reacted with water, forming an acid (E). On treatment of (E) with an acidified solution of  $\text{KI}$ , gas (B) was evolved, but when (E) was treated with a solution of  $\text{NH}_4\text{Cl}$ , a stable colourless gas (F) was evolved. (F) did not support combustion, but magnesium continued to burn in it. However, (F) reacted with calcium carbide in an electric furnace, forming a solid

- (G), which was slowly hydrolysed by water, forming a solution of substance (A), which turned Nessler's reagent yellow. Identify substances (A) to (G) and explain the reactions involved.
18. Compare the structures of the oxides and sulphides of phosphorus.
  19. Give equations for the reactions of the following compounds with water: (a)  $\text{P}_4\text{O}_6$ , (b)  $\text{P}_4\text{O}_{10}$ , (c)  $\text{PCl}_3$ , (d)  $\text{PCl}_5$ , (e)  $\text{Na}_3\text{P}$ .
  20. What do you understand by  $p\pi-d\pi$  bonding in the oxides and oxoacids of phosphorus? Give examples to show how this may explain some of the differences in the chemistry of nitrogen and phosphorus?
  21. Explain why the P—O bond length in  $\text{POCl}_3$  is  $1.45 \text{ \AA}$  whereas the sum of the single bond covalent radii of phosphorus and oxygen is  $1.83 \text{ \AA}$ .
  22. Discuss the uses of phosphates in analysis and in industry.
  23. Compare and contrast the structures and behaviour of phosphates, silicates and borates.
  24. Suggest reasons why  $\text{PF}_5$  is known but  $\text{NF}_5$  is not.
  25. Give examples of phosphazenes. How are they made, and what are their structures?
  26. Give equations for the reactions of the following compounds with water: (a)  $\text{As}_4\text{O}_6$ , (b)  $\text{As}_4\text{O}_{10}$ , (c)  $\text{SbCl}_3$ , (d)  $\text{Mg}_3\text{Bi}$ , (e)  $\text{Na}_3\text{As}$ .

Table 15.1 Electronic structures and oxidation states

Elements		Electronic structure		Oxidation states*			
Oxygen	O	[He]	$2s^2 2p^4$	<b>-II</b>	(-I)		
Sulphur	S	[Ne]	$3s^2 3p^4$	<b>-II</b>		(II)	IV VI
Selenium	Se	[Ar]	$3d^{10} 4s^2 4p^4$	<b>(-II)</b>		II	IV VI
Tellurium	Te	[Kr]	$4d^{10} 5s^2 5p^4$			II	IV VI
Polonium	Po	[Xe]	$4f^{14} 5d^{10} 6s^2 6p^4$			II	IV

\* The most important oxidation states (generally the most abundant and stable) are shown in bold. Other well characterized but less important states are shown in normal type. Oxidation states that are unstable or in doubt are given in parentheses.

## GENERAL PROPERTIES

The first four elements are non metals. Collectively they are called 'the chalcogens' or ore forming elements, because a large number of metal ores are oxides or sulphides.

Several chemicals in this group are industrially important.  $H_2SO_4$  is the most important chemical in the chemical industry. A staggering figure of 146 million tonnes was produced in 1992. One hundred million tonnes/year of  $O_2$  is produced and most is used in iron and steel making. In 1992, 54 million tonnes of S were produced, most of which is used to make  $H_2SO_4$ . One million tonnes/year of  $Na_2SO_3$  is used, mostly to bleach wood pulp and paper. Worldwide, 1 018 200 tonnes of  $H_2O_2$  were produced in 1991.

The elements show the usual increase in metallic character on descending the group. This is shown by their reactions, the structures of the elements, and an increased tendency to form  $M^{2+}$  ions together with a decrease in stability of  $M^{2-}$  ions. O and S are totally non metallic. Non metallic character is weaker in Se and Te. Po is markedly metallic, and is also radioactive and short lived.

Oxygen is a very important element in inorganic chemistry, since it reacts

with almost all the other elements. Most of its compounds are covered under the other elements.

S, Se and Te are moderately reactive and burn in air to form dioxides. They combine directly with most elements, both metals and non-metals, though less readily than with O. As expected for non-metals, S, Se and Te are not attacked by acids except those which are oxidizing agents. Po shows metallic properties since it dissolves in  $\text{H}_2\text{SO}_4$ , HF, HCl and  $\text{HNO}_3$ , forming pink solutions of  $\text{Po}^{\text{II}}$ . However, Po is strongly radioactive, and the  $\alpha$ -emission decomposes the water, and the  $\text{Po}^{\text{II}}$  solution is quickly oxidized to yellow solutions of  $\text{Po}^{\text{IV}}$ .

Oxygen shows several differences from the rest of the group. These are associated with its smaller size, higher electronegativity, and the lack of suitable  $d$  orbitals. Oxygen can use  $p\pi$  orbitals to form strong double bonds. The other elements can also form double bonds, but these become weaker as the atomic number increases. Thus  $\text{CO}_2$  ( $\text{O}=\text{C}=\text{O}$ ) is stable,  $\text{CS}_2$  less stable,  $\text{CSe}_2$  polymerizes rather than form double bonds and  $\text{CTe}_2$  is unknown. Oxygen also forms strong hydrogen bonds which greatly affect the properties of water and other compounds.

Sulphur shows a much greater tendency to form chains and rings than the other elements (see Allotropic Forms). Sulphur forms an extensive and unusual range of compounds with nitrogen which are not matched by the other elements.

Whereas O and S have only  $s$  and  $p$  electrons, Se follows after the first transition series and has  $d$  electrons too. The filling of the  $3d$  shell affects the properties of Ge, As, Se and Br. The atoms are smaller, and the electrons are held more tightly. This is the reason why Se is reluctant to attain the highest oxidation state of (+VI) shown by S. Thus  $\text{HNO}_3$  oxidizes S to  $\text{H}_2\text{SO}_4$  (S +VI) but only oxidizes Se to  $\text{H}_2\text{SeO}_3$  (Se +IV).

All compounds of Se, Te and Po are potentially toxic, and should be handled with care. Organo derivatives, and volatile compounds such as  $\text{H}_2\text{Se}$  and  $\text{H}_2\text{Te}$ , are 100 times more toxic than HCN.

## ELECTRONIC STRUCTURE AND OXIDATION STATES

The elements all have the electronic structure  $s^2p^4$ . They may attain a noble gas configuration either by gaining two electrons, forming  $\text{M}^{2-}$  ions, or by sharing two electrons, thus forming two covalent bonds. The electronegativity of O is very high – second only to F. The electronegativity difference between M and O is large. Thus most metal oxides are ionic and contain  $\text{O}^{2-}$  ions, and the oxidation state of O is (–II). Sulphides, selenides and tellurides are formed with the more electronegative metals in Groups 1 and 2 and the lanthanides, and these compounds are some of the most stable formed. Compounds are often written as containing  $\text{S}^{2-}$ ,  $\text{Se}^{2-}$  and  $\text{Te}^{2-}$ . The electronegativity differences suggest that these compounds are close to the 50% ionic, 50% covalent borderline. In the same way as for  $\text{PCl}_5$ , these compounds may be covalent in the solid but ionic in aqueous solution.




The elements also form compounds containing two covalent (electron pair) bonds such as  $\text{H}_2\text{O}$ ,  $\text{F}_2\text{O}$ ,  $\text{Cl}_2\text{O}$ ,  $\text{H}_2\text{S}$  and  $\text{SCl}_2$ . Where the chalcogen atom is the least electronegative atom in the molecule (e.g. in  $\text{SCl}_2$  where the electronegativity of S = 2.5 and Cl = 3.5) the S shows an oxidation state of (+II).

In addition, the elements S, Se and Te show oxidation states of IV and VI, and these are more stable than the +II state.

### ABUNDANCE OF THE ELEMENTS

Oxygen is the most abundant of all elements. It exists in the free form as dioxygen molecules  $\text{O}_2$  and makes up 20.9% by volume and 23% by weight of the atmosphere. Most of this has been produced by photosynthesis, the process where the chlorophyll in the green parts of plants uses the sun's energy to make foodstuffs such as glucose sugar.



Oxygen makes up 46.6% by weight of the earth's crust, where it is the major constituent of silicate minerals. Oxygen also occurs as many metal oxide ores, and as deposits of oxosalts such as carbonates, sulphates, nitrates and borates. Oceans cover three quarters of the earth's surface and oxygen makes up 89% by weight of the water in the oceans. Ozone  $\text{O}_3$  exists in the upper atmosphere, and is of great importance. This is discussed later.

Sulphur is the sixteenth most abundant element and constitutes 0.034% by weight of the earth's crust. It occurs mainly in the combined form as numerous sulphide ores and as sulphates (particularly gypsum  $\text{CaSO}_4 \cdot 2\text{H}_2\text{O}$ ). It is not economic to mine these to obtain S, although gypsum is mined for other uses. The native element can be obtained from volcanic sources in many places, but these sources are little used now except in Japan and Mexico. From Biblical times up till the present century volcanic sources provided the major source of S. In early times S in the form of brimstone (burning rock) was used for fumigation. From the thirteenth century until the middle of the nineteenth century it was used to make gunpowder. In the present century the major use has been to make  $\text{H}_2\text{SO}_4$ .

The other elements Se, Te and Po are very scarce.


Table 15.2 Abundance of the elements in the earth's crust by weight

	ppm	Relative abundance
O	455 000	1
S	340	16
Se	0.05	68
Te	0.001	74 =
Po	trace	


## EXTRACTION AND USES OF THE ELEMENTS

## Extraction and separation of dioxygen

Dioxygen is produced industrially by the fractional distillation of liquid air. (See Chapter 14, under 'Occurrence, extraction and uses of Nitrogen'.) Most of the  $O_2$  is used in the steel making industry. Gas produced in this way commonly contains traces of  $N_2$  and the noble gases, particularly Ar. Steel cylinders of compressed  $O_2$  are used for many purposes, including oxy-acetylene welding, and in the laboratory.  $O_2$  is administered together with an anaesthetic for surgical operations. It is sometimes prepared on a small scale in the laboratory by thermal decomposition of  $KClO_3$  (with  $MnO_2$  as catalyst), though the product often contains traces of  $Cl_2$  or  $ClO_2$ . Small amounts of  $O_2$  as an emergency breathing supply in aircraft are produced by heating  $NaClO_3$ :



$O_2$  can also be made by the catalytic decomposition of hypochlorites:




or by the electrolysis of water with a trace of  $H_2SO_4$  or barium hydroxide solution.

## Uses of dioxygen

Practically all the elements react with dioxygen either at room temperature or on heating. (The only exceptions are a few noble metals such as Pt, Au and W, and the noble gases.) Even though the bond energy of  $O_2$  is high ( $493 \text{ kJ mol}^{-1}$ ) the reactions are generally strongly exothermic, and once started often continue spontaneously.

Dioxygen is essential for respiration (for the release of energy in the body) by both animals and plants. It is therefore essential for life.



The complex formed between dioxygen and haemoglobin (the red pigment in blood) is of vital importance since it is the method by which higher animals transport dioxygen round the body to the cells which actually use it.

World production of liquid and gaseous  $O_2$  is about 100 million tonnes/year. By far the largest consumption of dioxygen (60–80%) is in the iron and steel industry. Here pure dioxygen is used to convert pig iron into steel in the *basic oxygen process* which originated as the *Kaldo* and *LD* processes. Since the late 1950s these have replaced the Bessemer process (which used air). Plants to produce dioxygen are frequently located adjacent to, or are part of, modern steel making plants, and the  $O_2$  is piped from one plant to the other. There are three advantages to the modern methods using  $O_2$ :

*continued overleaf*

- 1 The conversion to steel is quicker
- 2 Larger ingots of pig iron can be used (Bessemer 6 tonnes, BOP 100 tonnes)
- 3 The metal does not form nitrides, which can occur when air is used

In some places dioxygen is introduced with air into blast furnaces used for the reduction of iron oxides to impure pig iron by coke. The reason for using dioxygen is largely to allow the use of some heavy hydrocarbons (naphtha) as fuels as a partial replacement for expensive metallurgical coke. Dioxygen is also used for oxy-acetylene welding and metal cutting. Other important chemical uses of dioxygen include the following

- 1 The preparation of  $\text{TiO}_2$  from  $\text{TiCl}_4$ .  $\text{TiO}_2$  is used as a white pigment in paint and paper and as a filler in plastics
- 2 To oxidize  $\text{NH}_3$  in the manufacture of  $\text{HNO}_3$
- 3 In the manufacture of oxirane (ethylene oxide) from ethene
- 4 As the oxidant in rockets



#### Extraction of sulphur

World production of S was 57 million tonnes in 1992. The main producers are the USA 20%, the former Soviet Union 15%, Canada 13%, China 11% and Japan and the former Czechoslovakia 5% each. There are several methods of extracting S

Recovered from natural gas and petroleum	48%
Mined by the Frasch process	19%
From pyrites	17%
Recovered from smelter gases	12%
Mined as sulphur ore	4%
Made from $\text{CaSO}_4$	0.03%

Large amounts of sulphur are obtained from natural gas plants. In Canada these plants are the major source (90%) of S since the natural gas there may contain up to 20%  $\text{H}_2\text{S}$ . It is essential that all traces of sulphur compounds are removed from natural gas, since  $\text{H}_2\text{S}$  has an objectionable smell. Furthermore, burning sulphur compounds forms  $\text{SO}_2$  which has an acrid smell and is corrosive. In a similar way, large amounts of S are obtained from oil refineries (60% of the USA total and 37% of the USSR total). After cracking long chain hydrocarbons,  $\text{H}_2\text{S}$  and other sulphur derivatives are removed because of their objectionable smell. About a third of the  $\text{H}_2\text{S}$  is oxidized in air to give  $\text{SO}_2$ , which is subsequently reacted with the remaining  $\text{H}_2\text{S}$ . This provides a second major source of S in the USA and Japan. With the enormous increase in the use of natural gas and oil, more S is now obtained from gas and petroleum than is mined by the Frasch process (see later).

Major deposits of native S are found in the USA (the Gulf of Mexico States Louisiana, Texas and Mexico), and in the upper Vistula region of Poland and the Ukraine. These deposits of S were formed by anaerobic bacteria which metabolize  $\text{CaSO}_4$  to form  $\text{H}_2\text{S}$  and S.



These underground deposits of S are mined by the Frasch process, and yield S in a very high state of purity. In this process, three concentric pipes are sunk in a borehole down to the underground deposit. Superheated steam is passed down the outer pipe, and this melts the sulphur. Compressed air is blown down the inner pipe and forces molten sulphur up the middle pipe. One bore hole can cover an area of about half an acre. This technique was developed to overcome difficulties of mining in swamp areas or through quicksand, and for offshore mining in Louisiana. Mining in the USA started in the 1890s, and in Poland in the 1950s.


$\text{SO}_2$  is obtained as a by-product in the extraction of metals from sulphide ores. The most important metal sulphide is iron pyrites (fool's gold)  $\text{FeS}_2$ . This is mined in large amounts in the USSR, Spain, Portugal, Japan and many other places. Non-ferrous metals such as wurtzite  $\text{ZnS}$ , galena  $\text{PbS}$ , several forms of copper sulphide and  $\text{NiS}$  all yield  $\text{SO}_2$  in smelters. The  $\text{SO}_2$  is used to make  $\text{H}_2\text{SO}_4$ . Because there are a large number of metal production processes, this method of producing S currently yields more S than the other two methods. However, it is produced as  $\text{SO}_2$  rather than S. The metals in the *p*-block and about half of the transition metals form sulphide minerals: all these metals are collectively called chalcophiles. Some of the most important sulphide minerals are listed in Table 15.3.

There are vast amounts of S in the form of sulphates dissolved in the oceans, and as mineral deposits such as  $\text{CaSO}_4$ . There are smaller deposits of other metals such as  $\text{FeSO}_4$  and  $\text{Al}_2(\text{SO}_4)_3$ . In Poland  $\text{SO}_2$  is obtained by heating  $\text{CaSO}_4$  with coke in a rotary kiln. Production is about 20 000 tonnes/year. The  $\text{SO}_2$  is used for the Contact process for the manufacture of  $\text{H}_2\text{SO}_4$ . Production of elemental S from sulphates is not much used since other sources of S are at present cheaper.

Table 15.3 Some important sulphide ores

$\text{MoS}_2$	Molybdenite
$\text{FeS}_2$	Pyrites (fool's gold)
$\text{FeS}_2$	Marcasite
$\text{FeAsS}$	Arsenopyrites
$(\text{Fe}, \text{Ni})_9\text{S}_8$	Pentlandite
$\text{Cu}_2\text{S}$	Copper glance or chalcocite
$\text{CuFeS}_2$	Copper pyrites or chalcopyrite
$\text{Cu}_5\text{FeS}_4$	Bornite or peacock mineral
$\text{Ag}_2\text{S}$	Silver glance or argentite
$\text{ZnS}$	Zinc blende or sphalerite
$\text{ZnS}$	Wurtzite
$\text{HgS}$	Cinnabar
$\text{PbS}$	Galena or lead glance
$\text{As}_2\text{S}_3$	Orpiment
$\text{As}_4\text{S}_4$	Realgar
$\text{Sb}_2\text{S}_3$	Stibnite
$\text{Bi}_2\text{S}_3$	Bismuthinite

*continued overleaf*



At one time elemental S was obtained in large amounts as a by-product in the production of coal gas. Since natural gas has replaced coal gas (town gas) in many developed areas, this source has largely disappeared except in less developed areas.



### Acid rain and SO<sub>2</sub>

Coal typically contains 2% S, and may contain up to 4%. This represents a huge potential source of S, which could be extracted as SO<sub>2</sub> from the flue gases. Worldwide about 4530 million tonnes of coal were produced in 1992. The largest use is in coal burning electricity generating plants. Worldwide this produces about 90 million tonnes of S, that is 180 million tonnes of SO<sub>2</sub>. (In the UK 85 million tonnes of coal are used in power stations producing about 2.4 million tonnes per year of S or 4.8 million tonnes of SO<sub>2</sub>.) Because it is uneconomic to remove the SO<sub>2</sub>, only about 1% of this total tonnage is recovered as H<sub>2</sub>SO<sub>4</sub>. The majority is discharged into the atmosphere where it causes acid rain.

The atmospheric chemistry of acid rain is not fully understood. SO<sub>2</sub> is oxidized by ozone or hydrogen peroxide to SO<sub>3</sub>. This reacts with water or hydroxyl radicals to give H<sub>2</sub>SO<sub>4</sub>. Ammonium sulphate is also formed, and can be seen as an atmospheric haze (sometimes described as an aerosol of fine particles). *Wet deposition* occurs after raindrops become nucleated with aerosol particles of SO<sub>3</sub> or (NH<sub>4</sub>)<sub>2</sub>SO<sub>4</sub>, but SO<sub>2</sub> does not dissolve in significant amounts. Instead SO<sub>2</sub> is deposited by *dry deposition* and is absorbed directly on both solid and liquid ground surfaces. In 1982 UK deposition was about 50 units (kg hectare<sup>-1</sup> year<sup>-1</sup>) of dry and 5 units of wet. The name 'acid rain' is misleading since it refers to both wet and dry deposition.

Inevitably power stations are located (and SO<sub>2</sub> is emitted) in densely populated regions. Using high chimney stacks to disperse the gas merely moves the problem on to someone else. For example, 10% of SO<sub>2</sub> pollution in Sweden actually comes from Sweden, but 80% comes from the industrial regions of Europe (East and West Germany, Poland, Czechoslovakia) and 10% from Britain. Acid rain causes damage to trees, plants, fish and buildings, and causes respiratory ailments in man and animals. About 60% of atmospheric SO<sub>2</sub> comes from coal fired power stations. Most of the rest comes from oil refineries, oil fired power stations and smelters.

Total elimination of SO<sub>2</sub> pollution is not possible for both economic and technical reasons. However, we have the technology to reduce pollution to a low figure. The methods used are scrubbing the flue gases with a slurry of Ca(OH)<sub>2</sub>, or reducing the SO<sub>2</sub> to S using H<sub>2</sub>S and an activated alumina catalyst.



### Uses of sulphur

S is an essential though minor constituent of certain proteins. It is present in the amino acids cystine, cysteine and methionine.

World production of S was 57 million tonnes in 1992. Almost 90% of this is converted to  $\text{SO}_2$ , then to  $\text{SO}_3$  and finally to  $\text{H}_2\text{SO}_4$ . Sixty per cent of the  $\text{H}_2\text{SO}_4$  produced is used to make fertilizers. The remainder is used to make a variety of other chemicals. Sulphites  $\text{SO}_3^{2-}$ , hydrogen sulphites  $\text{HSO}_3^-$  and  $\text{SO}_2$  are important for bleaching.

The 10% of S for non-acid purposes is used as elemental S. Some is used to make carbon disulphide  $\text{CS}_2$ , which is used to make  $\text{CCl}_4$  and viscose rayon. Sulphur reacts with alkenes and forms sulphur cross-links between molecules. This is important in the vulcanizing of rubber. Sulphur and selenium will dehydrogenate saturated hydrocarbons. Other uses of sulphur are in the manufacture of fungicides, insecticides and gunpowder. Gunpowder is an intimate mixture of saltpetre  $\text{NaNO}_3$  (75%), charcoal (15%) and sulphur (10%). It was discovered by Roger Bacon in 1245, and was the first explosive which could propel a bullet or cannon ball. It was first used for this purpose at the Battle of Crécy in 1346. It was then used in land and sea warfare for 500 years until better explosives such as gun-cotton, nitroglycerine and cordite were discovered.

### Extraction and uses of selenium and tellurium

Se and Te occur among sulphide ores and are obtained in concentrated form from anode sludge after the electrolytic refining of copper. This sludge also contains the platinum metals, and Ag and Au. Se and Te are also obtained from flue dust produced during the roasting of sulphide ores such as  $\text{PbS}$ ,  $\text{CuS}$  or  $\text{FeS}_2$ . The dust is trapped by means of an electrostatic precipitator. Both elements also occur in the native form together with S.

World production of Se metal was 1670 tonnes in 1992. Most is used to decolorize glass, though  $\text{Cd(S,Se)}$  is used to make pink and red coloured glass. Se is used in Xerox-type photocopiers to make the photoreceptor to capture the image. The photoreceptor is a thin film of Se on an Al support. The photoreceptor is sensitized electrostatically by a high voltage, and then an image is focussed on it as on the film in a camera. Areas exposed to light lose their electrostatic charge. Toner powder sticks to the areas still charged, and the powder is transferred to a sheet of paper and heated to fuse the powder to the paper. Thus a copy of the original image is obtained. The photoreceptor is then wiped clean, sensitized again, and reused. Selenium is an essential element in the body in trace amounts, and is a component in a number of important enzymes, e.g. glutathione peroxidase, which protects cells against attack by peroxide. However, Se is toxic in larger quantities.


*continued overleaf*

World production of Te metal was 152 tonnes in 1992. The major part of this is used in making steel and non ferrous alloys for example to harden lead.

Both Se and Te compounds are absorbed by the human body and are excreted as foul smelling organic derivatives in breath and sweat.

### Discovery and production of polonium

Polonium was discovered by Marie Curie by processing very large amounts of thorium and uranium minerals and separating the decay products. Polonium is one of the decay products (see Radioactive decay series in Chapter 31). The separation was observed by studying the radioactivity.



Marie Curie shared the award of a Nobel Prize for Physics with H. A. Becquerel and Pierre Curie in 1903 for work on radioactivity which was then a new technique. In 1911 she was awarded a second Nobel Prize (this time for Chemistry) for the discovery of polonium and radium. Polonium is named after Marie Curie's home country Poland. Polonium is now made artificially in gram quantities from bismuth by neutron irradiation in a nuclear reactor. The metal is extracted by sublimation.



All isotopes of polonium are highly radioactive. The most stable isotope is  ${}^{210}_{84}\text{Po}$  but this is an intense  $\alpha$  emitter and has a half life of 138 days. The  $\alpha$  emission decomposes water which complicates any studies of polonium compounds in aqueous solutions. Thus the chemistry of polonium is not well known.

## STRUCTURE AND ALLOTROPY OF THE ELEMENTS

All the elements except Te are polymorphic that is they exist in more than one allotropic form.

### Oxygen

Oxygen occurs as two non metallic forms dioxygen  $\text{O}_2$  and ozone  $\text{O}_3$ . Dioxygen  $\text{O}_2$  is stable as a diatomic molecule which accounts for it being a gas. (S, Se, Te and Po have more complicated structures e.g.  $\text{S}_8$  and are solids at normal temperatures.) The bonding in the  $\text{O}_2$  molecule is not as simple as it might at first appear. If the molecule had two covalent bonds then all the electrons would be paired and the molecule should be diamagnetic.




Dioxygen is paramagnetic and therefore contains unpaired electrons. The explanation of this phenomenon was one of the early successes of the

molecular orbital theory. The structure is described (see 'Examples of molecular orbital treatment' in Chapter 4).

Liquid dioxygen is pale blue in colour, and the solid is also blue. The colour arises from electronic transitions which excite the ground state (a triplet state) to a singlet state. This transition is 'forbidden' in gaseous dioxygen. In liquid or solid dioxygen a single photon may collide with two molecules simultaneously and promote both to excited states, absorbing red-yellow-green light, so  $O_2$  appears blue. The origin of the excited singlet states in  $O_2$  lies in the arrangement of electrons in the antibonding  $\pi^*2p_y$  and  $\pi^*2p_z$  molecular orbitals, and is shown below.

Second excited state (electrons have opposite spins)	$\pi^*p_y \pi^*p_z$ 	singlet	State $^1\Sigma_g^+$	Energy/kJ 157
First excited state (electrons paired)		singlet	$^1\Delta_g$	92
Ground state (electrons have parallel spins)		triplet	$^3\Sigma_g^-$	0


Singlet  $O_2$  is excited, and is much more reactive than normal ground state triplet dioxygen. Singlet dioxygen can be generated photochemically by irradiating normal dioxygen in the presence of a sensitizer such as fluorescein, methylene blue or some polycyclic hydrocarbons. Singlet dioxygen can also be made chemically:



Singlet dioxygen can add to a diene molecule in the 1,4 positions, rather like a Diels-Alder reaction. It may add 1,2 to an alkene which can be cleaved into two carbonyl compounds.

Singlet dioxygen may be involved in biological oxidations.

Ozone  $O_3$  is the triatomic allotrope of oxygen. It is unstable, and decomposes to  $O_2$ . The structure of  $O_3$  is angular, with an O—O—O bond angle of  $116^\circ 48'$ . Both O—O bond lengths are  $1.28 \text{ \AA}$ , which is intermediate between a single bond ( $1.48 \text{ \AA}$  in  $H_2O_2$ ) and a double bond ( $1.21 \text{ \AA}$  in  $O_2$ ). (The structure of  $O_3$  is described near the end of Chapter 4.) The older valence bond representation as resonance hybrids is now seldom used. The structure is described as the central O atom using  $sp^2$  hybrid orbitals to bond to the terminal O atoms. The central atom has one lone pair, and the terminal O atoms have two lone pairs. This leaves four electrons for  $\pi$  bonding. The  $p_z$  atomic orbitals from the three atoms form three delocalized molecular orbitals covering all three atoms. One MO is bonding, one non-bonding, and one antibonding. The four  $\pi$  electrons fill the bonding and non-bonding MOs and thus contribute one delocalized  $\pi$  bond to the molecule in addition to the two  $\sigma$  bonds. Thus the bond order is 1.5, and the  $\pi$  system is described as a four-electron three-centre bond.



## Sulphur


Sulphur has more allotropic forms than any other element. These different forms arise partly from the extent to which S has polymerized, and partly





from the crystal structures adopted. The two common crystalline forms are  $\alpha$  or rhombic sulphur which is stable at room temperature, and  $\beta$  or monoclinic sulphur which is stable above 95.5°C. These two forms change reversibly with slow heating or slow cooling. Rhombic sulphur occurs naturally as large yellow crystals in volcanic areas. A third modification known as  $\gamma$  monoclinic sulphur is nacreous (looks like mother of pearl). It can be made by chilling hot concentrated solutions of S in solvents such as CS<sub>2</sub>, toluene or EtOH. All three forms contain puckered S<sub>8</sub> rings with a crown conformation (Figure 15.2), and differ only in the overall packing of the rings in the crystal. This affects their densities.

$\alpha$ rhombic	2.069 g cm <sup>-3</sup>
$\beta$ monoclinic	1.94–2.01 g cm <sup>-3</sup>
$\gamma$ monoclinic	2.19 g cm <sup>-3</sup>

Engel's sulphur ( $\epsilon$  sulphur) is unstable and contains S<sub>6</sub> rings arranged in the chair conformation. It is made by pouring Na<sub>2</sub>S<sub>2</sub>O<sub>3</sub> solution into concentrated HCl and extracting the S with toluene. It can also be made as follows:



Several other rings S<sub>7</sub>, S<sub>9</sub>, S<sub>10</sub>, S<sub>11</sub>, S<sub>12</sub>, S<sub>18</sub> and S<sub>20</sub> have been made by Schmidt and his group. They are usually obtained by 1:1 reactions in dry ether between hydrogen polysulphides and polysulphur dichlorides with the required number of S atoms, for example:



In all of these ring compounds the S—S distance is 2.04–2.06 Å and the bond angle S—S—S is in the range 102–108°. They are all soluble in CS<sub>2</sub>.

Plastic or  $\chi$  sulphur is obtained by pouring liquid sulphur into water. Several other forms can be produced by quenching molten S. These may be fibrous, laminar or rubber-like, and a commercial form is called Crystex. These are all metastable and revert to the  $\alpha$  (cyclo S<sub>8</sub>) form on standing. Their structures contain spiral chains, and sometimes S<sub>8</sub> and other rings.

Sulphur melts to form a mobile liquid. As the temperature is raised the colour darkens. At 160°C the S<sub>8</sub> rings break, and the diradicals so formed polymerize, forming long chains of up to a million atoms. This makes all the physical properties change discontinuously. The viscosity increases sharply, and continues to rise up to 200°C. At higher temperatures chains break, and shorter chains and rings are formed, which makes the viscosity decrease up to 444°C, the boiling point. The vapour at 200°C consists mostly of S<sub>8</sub> rings, but contains 1–2% of S<sub>2</sub> molecules. At 600°C the gas mainly consists of S<sub>2</sub> molecules.

The S<sub>2</sub> molecule is paramagnetic and blue coloured like O<sub>2</sub>, and pre-




Figure 15.2 Structure of S<sub>8</sub> molecule

sumably has similar bonding.  $S_2$  gas is stable up to  $2200^\circ\text{C}$ . The stability of  $S_2$  is used in the quantitative analysis of S compounds. They are burnt in a reducing flame, and the colour from excited  $S_2$  is measured spectrophotometrically.  $S_3$  and  $S_4$  are also known.

### Selenium, tellurium and polonium

Six allotropes of selenium are known. Interest in these is because Se is used in electronic devices. These include capturing the image in Xerox-type photocopiers, as rectifiers (to convert alternating current into direct current), and as light emitting diodes (LEDs). There are four red forms. Three different red non-metallic forms are known containing  $Se_8$  rings. They differ in the way the rings are packed in the crystal. An 'amorphous' red form contains polymeric chains. There are in addition two grey forms. The most stable is the grey metallic form, which contains infinite spiral chains of Se atoms with weak metallic interaction between adjacent chains. A black vitreous form of Se is commercially available, and is made of large irregular rings with up to 1000 atoms.

Tellurium has only one crystalline form, which is silvery white and semi-metallic. This is similar to grey Se, but has stronger metallic interaction.

Polonium is a true metal. It exists as an  $\alpha$ -form which is cubic and a  $\beta$ -form which is rhombohedral. Both forms are metallic.

Thus there is a marked decrease in the number of allotropic forms from S to Se to Te. There is an increase in metallic character down the group. The electrical properties also change from insulators (O and S), to semiconductors (Se and Te), to metallic conduction (Po). The structures change from simple diatomic molecules, to rings and chains, to a simple metallic lattice.

Sulphur dissolves in oleum, giving brightly coloured solutions, which may be yellow, deep blue or bright red. These contain cations  $[S_n]^{2+}$ .  $[S_4]^{2+}$  is bright yellow, and the X-ray structure shows it is square planar. It is isoelectronic with  $S_2N_2$ .  $[S_8]^{2+}$  is deep blue and the structure is cyclic. The red colour was thought to be due to  $[S_{16}]^{2+}$ , but has recently been shown to be due to  $[S_{19}]^{2+}$ . Selenium and tellurium also dissolve in oleum, forming  $[Se_4]^{2+}$ ,  $[Te_4]^{2+}$ ,  $[Se_8]^{2+}$  and, in addition,  $[Se_{10}]^{2+}$  and  $[Te_6]^{4+}$ .

### CHEMISTRY OF OZONE

$O_3$  is an unstable, dark blue diamagnetic gas, b.p.  $-112^\circ\text{C}$ . The colour is due to intense absorption of red light ( $\lambda$  557 and 602 nm). It also absorbs strongly in the UV region ( $\lambda$  255 nm). This is particularly important since there is a layer of  $O_3$  in the upper atmosphere which absorbs harmful UV radiation from the sun, thus protecting people on the earth. The use of chlorofluorocarbons in aerosols and refrigerators, and their subsequent escape into the atmosphere, is blamed for making holes in the ozone layer over the Antarctic and Arctic. It is feared that this will allow an excess-

Square plana  
 $S_4^{2+}$ ,  $Se_4^{2+}$ ,  $Te_4^{2+}$

...  
 $S_8^{2+}$ ,  $Se_8^{2+}$

$Se_{10}^{2+}$




Figure 15.3 Various cations.


ive amount of UV light to reach the earth which will cause skin cancer (melanoma) in humans. Oxides of nitrogen (from car exhausts) and the halogens can also damage the  $O_3$  layer (See Chapter 13).

$O_3$  has a characteristic sharp smell, often associated with sparking electrical equipment. The gas is toxic, and continuous exposure to concentrations of 0.1 ppm must be avoided.


$O_3$  is usually prepared by the action of a silent electric discharge upon dioxygen between two concentric metallized tubes in an apparatus called an ozonizer. Concentrations of up to 10% of  $O_3$  are obtained in this way. Higher concentrations or pure  $O_3$  can be obtained by fractional liquifaction of the mixture. The pure liquid is dangerously explosive. Low concentrations of  $O_3$  can be made by UV irradiation of  $O_2$ . This occurs in the atmosphere when photochemical smog is formed over some cities, for example over Los Angeles or Tokyo. The photochemical change is useful for producing low concentrations to sterilize food, particularly for cold storage.  $O_3$  can also be made by heating  $O_2$  to over  $2500^\circ\text{C}$  and quenching. In all of these preparations oxygen atoms are produced, and these react with  $O_2$  molecules to form  $O_3$ .

$O_3$  is also used as a disinfectant. For example, it is used to purify drinking water, since it destroys bacteria and viruses. Its advantage over chlorine for this purpose is that it avoids the unpleasant smell and taste of chlorine, since any excess  $O_3$  soon decomposes to  $O_2$ . For similar reasons it is used to treat water in swimming pools.



The amount of  $O_3$  in a gas mixture may be determined by passing the gas into a KI solution buffered with a borate buffer (pH 9.2). The iodine that is liberated is titrated with sodium thiosulphate.



Alternatively the gas may be decomposed catalytically, and the change in volume measured.



$O_3$  is thermodynamically unstable, and decomposes to  $O_2$ . The decomposition is exothermic, and is catalysed by many materials. The solid and liquid often decompose explosively. The gas decomposes slowly, even when warmed, *providing catalysts and UV light are absent*.  $O_3$  is an extremely powerful oxidizing agent, second only to  $F_2$  in oxidizing power, and reacts much more readily than dioxygen.



Potassium ozonide  $KO_3$  is an orange coloured solid and contains the paramagnetic  $O_3^-$  ion.  $O_3$  adds to unsaturated organic compounds at room

Table 15.4 Physical properties of the elements


	Covalent radius (Å)	Ionic radius M <sup>2-</sup> (Å)	First ionization energy (kJ mol <sup>-1</sup> )	Pauling's electro- negativity	Melting point (°C)	Boiling point (°C)
O	0.74	1.40	1314	3.5	-229	-183
S	1.04	1.84	999	2.5	114	445
Se	1.14	1.98	941	2.4	221	685
Te	1.37	2.21	869	2.1	452	1087
Po			813	2.0	254	962

Values for covalent radii are for two-coordination.

### STANDARD REDUCTION POTENTIALS (VOLTS)

### Acid solution

### Oxidation state

$$+VI \quad +V \quad +IV \quad +III \quad +II\frac{1}{2} \quad +II \quad +I \quad 0 \quad -I \quad -II$$



\* Disproportionates

The difference in free energy between the different oxidation states of S is not very great.  $\text{PoO}_3$  ( $\text{Po}(+\text{VI})$ ) is appreciably more oxidizing than the  $(+\text{VI})$  states of the other elements, and selenate  $\text{SeO}_4^{2-}$  and tellurate

$\text{FeO}_3^2$  have a much greater oxidizing power than  $\text{SO}_4^2$ . The differences between the oxidizing power of the (+IV) states of polonite, tellurite, selenite and sulphite are smaller. The potentials also show the decrease in stability from  $\text{H}_2\text{O}$  to  $\text{H}_2\text{S}$  to  $\text{H}_2\text{Se}$  to  $\text{H}_2\text{Te}$  to  $\text{H}_2\text{Po}$  the last three are thermodynamically unstable.

### OXIDATION STATES (+II), (+IV) AND (+VI)

Oxygen is never more than divalent because when it has formed two covalent bonds it has attained a noble gas configuration, and there are no low energy orbitals which can be used to form further bonds. However, the elements S, Se, Te and Po have empty  $d$  orbitals which may be used for bonding, and they can form four or six bonds by unpairing electrons.




Compounds of S, Se and Te with O are typically tetravalent. The (+IV) state shows both oxidizing and reducing properties. Fluorine brings out the maximum oxidation state of (+VI). Compounds in the (+VI) state show oxidizing properties. The higher oxidation states become less stable on descending the group. These compounds are typically volatile because they are covalent.

### BOND LENGTHS AND $p\pi-d\pi$ BONDING

The bonds between S and O, or Se and O, are much shorter than might be expected for a single bond. In some cases they may be formulated as localized double bonds. A  $\sigma$  bond is formed in the usual way. In addition a  $\pi$  bond is formed by the sideways overlap of a  $p$  orbital on the oxygen with a  $d$  orbital on the sulphur giving a  $p\pi-d\pi$  interaction. This  $p\pi-d\pi$  bonding is similar to that found in the oxides and oxo acids of phosphorus and is in contrast to the more common  $p\pi-p\pi$  type of double bond found in ethene (Figure 15.4).

To obtain effective  $p\pi-d\pi$  overlap the size of the  $d$  orbital must be

similar to the size of the  $p$  orbital. Thus sulphur forms stronger  $\pi$  bonds than the larger elements in the group. On crossing a period in the periodic table, the nuclear charge is increased and more  $s$  and  $p$  electrons are added. Since these  $s$  and  $p$  electrons shield the nuclear charge incompletely, the size of the atom and the size of the  $d$  orbitals decreases from Si to P to S to Cl. The decrease in the size of the  $3d$  orbitals in this series of elements leads to progressively stronger  $p\pi-d\pi$  bonds. Thus in the silicates there is hardly any  $p\pi-d\pi$  bonding. Thus  $\text{SiO}_4$  units polymerize into an enormous variety of structures linked by  $\text{Si}-\text{O}-\text{Si}$   $\sigma$  bonds. In the phosphates,  $\pi$  bonding is stronger, but a large number of polymeric phosphates exist. In the oxoacids of sulphur,  $\pi$  bonding is even stronger and has become a dominant factor. Thus only a small amount of polymerization occurs, and only a few polymeric compounds are known with  $\text{S}-\text{O}-\text{S}$  linkages. For chlorine,  $p\pi-d\pi$  bonding is so strong that no polymerization of oxoanions occurs.

Figure 15.4  $p\pi-d\pi$  o

In cases where there is more than one  $\pi$  bond in the molecule it may be more appropriate to explain the  $\pi$  bonding in terms of delocalized molecular orbitals covering several atoms.

### DIFFERENCES BETWEEN OXYGEN AND THE OTHER ELEMENTS

Oxygen differs from the rest of the group in that it is more electronegative and therefore more ionic in its compounds.

Hydrogen bonding is very important for O compounds, but it is only recently that weak hydrogen bonds involving S have been proved to exist.

The absence of higher valency states and the limitation to a coordination number of 4 are a consequence of the limitation of the second shell to eight electrons. The other elements can have a coordination number of 6 by using  $d$  orbitals.

Oxygen can use  $p\pi$  orbitals to form strong double bonds. The other elements can also form double bonds, but these become weaker as the atomic number increases.

### GENERAL PROPERTIES OF OXIDES


Practically all of the elements react with dioxygen to form oxides. There are several ways in which oxides may be classified, depending on their structure or their chemical properties. First consider the classification according to their geometric structure. In this way oxides are classified as normal oxides, peroxides or suboxides.

#### Normal oxides


In these, the oxidation number of M can be deduced from the empirical formula  $\text{M}_x\text{O}_y$ , taking the oxidation number of oxygen as  $(-II)$ . These oxides, for example  $\text{H}_2\text{O}$ ,  $\text{MgO}$  and  $\text{Al}_2\text{O}_3$ , contain only  $\text{M}-\text{O}$  bonds.

### Peroxides

These contain more oxygen than would be expected from the oxidation number of M. Some are ionic and contain the peroxide ion  $O_2^{2-}$ , for example those of Group 1 and 2 metals ( $Na_2O_2$  and  $BaO_2$ ). Others are covalently bound and contain  $-O-O-$  in the structure, for example  $H_2O_2$  ( $H-O-O-H$ ) peroxomonosulphuric acid and peroxodisulphuric acid



Peroxo compounds are strong oxidizing agents, and are hydrolysed by water to give  $H_2O_2$



Superoxides, e.g.  $KO_2$ , contain more oxygen than would be expected (see Chapter 9)

### Suboxides

Here the formula contains less oxygen than would be expected from the oxidation number of M. They involve  $M-M$  bonds in addition to  $M-O$  bonds, for example  $O=C=C=C=O$

A second method of classifying oxides depends on their acid-base properties. Thus oxides may be acidic, basic, amphoteric or neutral, depending on the products formed when they react with water.




### Basic oxides

Metallic oxides are generally basic. Most metal oxides are ionic and contain the  $O^{2-}$  ion. The oxides of the more electropositive metals, Groups 1 and 2, and the lanthanides are typical. A large amount of energy is required to form an ionic oxide. This is because the  $O_2$  molecule must first be broken into atoms, and then the energy (the electron affinity) required to add two electrons to form  $O^{2-}$  is also large. Thus ionic oxides are formed by compounds with a high lattice energy to offset this. Thus ionic oxides typically have high melting points ( $Na_2O$  1275°C,  $MgO$  2800°C,  $La_2O_3$  2315°C). When they react with water the  $O^{2-}$  ion is converted into  $OH^-$






However, many metal oxides with formulae  $M_2O_3$  and  $MO_2$ , though ionic, do not react with water. Examples include  $Ti_2O_3$ ,  $Bi_2O_3$  and  $ThO_2$ . These react with acids to form salts, and so are basic. Where a metal can exist

from the most basic to the most acidic, then the further apart two oxides are in the series, the more stable the compound formed when they react together. This can be put on a quantitative basis by considering the changes in standard free energy




From the  $\Delta G$  values,  $\text{Na}_2\text{O}$  is the most basic and  $\text{Al}_2\text{O}_3$  the least basic. In fact  $\text{Na}_2\text{O}$  is strongly basic and  $\text{Al}_2\text{O}_3$  is amphoteric. From the free energy values for the hydroxides,  $\text{NaOH}$  is chemically the most reactive and  $\text{Al(OH)}_3$  the most stable. This is also true in the following reactions



From the  $\Delta G$  values,  $\text{SO}_3$  is the most strongly acidic oxide,  $\text{N}_2\text{O}_5$  is the next strongest, and  $\text{CO}_2$  is the weakest. From the free energy values of the salts formed,  $\text{Ca(NO}_3)_2$  is the least stable and the most reactive, whilst  $\text{CaSO}_4$  is the most stable and the least reactive.


The order of acidic strength of oxides can be obtained as follows



It is possible to predict if a reaction is possible or impossible. If  $\text{CaO}$  is added to a mixture of  $\text{H}_2\text{O}$  and  $\text{SO}_3$  ( $\text{H}_2\text{SO}_4$ ), the more stable  $\text{CaO} \cdot \text{SO}_3$  ( $\text{CaSO}_4$ ) will form, that is



but



Free energy data and acidic power are clearly related. Thermodynamics allows us to predict if a reaction is possible in terms of energy. This use of  $\Delta G$  values is not limited to oxides, but applies to all reactions. Thermodynamics does not allow us to predict the rate of a reaction. For example, the reaction below is thermodynamically possible



The reaction is very slow at normal temperatures, though it is more rapid at high temperatures in a blast furnace.

Much inorganic chemistry consists of remembering which compounds



react, and comparing the different stabilities of hydroxides, silicates, carbonates, nitrates, sulphates etc. The use of a series such as the one above minimizes this memory work.

For comprehensive lists of standard free energy data see Bard, A.J., Parsons, R. and Jordan, J.; and Latimer, W.M. in Further Reading.

### OXIDES OF SULPHUR, SELENIUM, TELLURIUM AND POLONIUM

Table 15.5 Oxides

Element	MO <sub>2</sub>	MO <sub>3</sub>	Other oxides
S	SO <sub>2</sub>	SO <sub>3</sub>	S <sub>2</sub> O (S <sub>2</sub> O <sub>2</sub> ) (SO) (S—O—O) (SO <sub>4</sub> ) S <sub>6</sub> O, S <sub>7</sub> O, S <sub>8</sub> O, S <sub>9</sub> O, S <sub>10</sub> O
Se	SeO <sub>2</sub>	SeO <sub>3</sub>	
Te	TeO <sub>2</sub>	TeO <sub>3</sub>	TeO
Po	PoO <sub>2</sub>		PoO

#### Dioxides MO<sub>2</sub>


SO<sub>2</sub> is produced commercially on a vast scale:

1. By burning S in air.
2. By burning H<sub>2</sub>S in air.
3. By roasting various metal sulphide ores with air in smelters (particularly FeS<sub>2</sub>, and to a smaller extent CuS and ZnS).
4. Large amounts are produced as a waste product by burning coal and, to a lesser extent, other fossil fuels, oil and gas. This undoubtedly harms the environment.


SO<sub>2</sub> is a colourless gas (b.p.  $-10^{\circ}\text{C}$ , m.p.  $-75.5^{\circ}\text{C}$ ), which has a choking smell, and is very soluble in water ( $39\text{ cm}^{-3}$  of SO<sub>2</sub> gas will dissolve in  $1\text{ cm}^{-3}$  of water). The SO<sub>2</sub> in solution is almost completely present as various hydrated species such as SO<sub>2</sub>·6H<sub>2</sub>O and the solution contains only a minute amount of sulphurous acid H<sub>2</sub>SO<sub>3</sub>. SO<sub>2</sub> levels above 5 ppm are poisonous to man, but plants are harmed at appreciably lower levels.

SO<sub>2</sub> may be detected in the laboratory:

1. By its smell.
2. Because it turns a filter paper moistened with acidified potassium dichromate solution green, due to the formation of Cr<sup>3+</sup>.



3. Because it turns starch iodate paper blue (due to starch and I<sub>2</sub>).



Quantitative methods for measuring SO<sub>2</sub> in the atmosphere are highly developed because of environmental concern over 'acid rain'. Methods include:

1. Oxidation to  $\text{H}_2\text{SO}_4$ , followed by determination of the  $\text{H}_2\text{SO}_4$  by titration (or conductimetric titration)



2. Reaction with  $\text{K}_2[\text{HgCl}_4]$  to give a mercury complex which reacts with the dye pararosaniline, and is estimated colorimetrically






3. Burning in a hydrogen flame in a flame photometer, and measuring the spectrum of  $\text{S}_2$  (See also the discussion of singlet dioxygen)

Most of the  $\text{SO}_2$  produced is oxidized to  $\text{SO}_3$  by the Contact process, and used to manufacture  $\text{H}_2\text{SO}_4$ . Smaller amounts of  $\text{SO}_2$  are used to make sulphites  $\text{SO}_3^{2-}$ , for bleaching, and for preserving food and wine




The forward reaction is exothermic, and is favoured by a low temperature. Since there is a decrease in the number of moles of gas, the process is favoured by a high pressure. In practice the reaction is carried out at atmospheric pressure. The formation of  $\text{SO}_3$  is favoured by an excess of  $\text{O}_2$ , and removing the  $\text{SO}_3$  from the reaction mixture. A catalyst is used to obtain a reasonable conversion in a reasonable time. In the Contact process a platinum gauze and platinized asbestos were both used at one time. Pt is an excellent catalyst, and it works at moderately low temperatures. However, it is very expensive and is susceptible to poisoning, particularly by metals such as As. Nowadays a  $\text{V}_2\text{O}_5$  catalyst activated with  $\text{K}_2\text{O}$  is used instead, and is supported on kieselguhr or silica. This is much cheaper, and is resistant to poisoning. The catalyst is inactive below  $400^\circ\text{C}$  and breaks down between  $600^\circ\text{C}$  and  $650^\circ\text{C}$ . Dust may clog the catalyst surface, and impair its efficiency. To prevent this the gases are passed through an electrostatic precipitator. The catalyst may last for over 20 years. Most commercial plants are four-stage convertors. The gases are passed over four beds of catalyst in turn, and are cooled in between each catalyst bed.  $\text{SO}_3$  is removed after passing over the first three beds, and again after the fourth bed.

$\text{SO}_2$  is used to make other products



$\text{SO}_2$  has also been used as a non-aqueous solvent. A wide range of covalent compounds, both inorganic and organic, are soluble in liquid  $\text{SO}_2$ , and it is a useful reaction medium. At one time it was thought that  $\text{SO}_2$  underwent self-ionization, with a system of 'acid-base' reactions in this solvent, but this is now known to be incorrect.



$\text{SO}_2$  gas forms discrete V-shaped molecules, and this structure is retained in the solid state (Figure 15.5). The bond angle is  $119^\circ 30'$ . The bonding in  $\text{SO}_2$  is described in Chapter 4.

The dioxides  $\text{SeO}_2$ ,  $\text{TeO}_2$  and  $\text{PoO}_2$  are made by burning the element in air.  $\text{SeO}_2$  is solid at room temperature. The gas has the same structure as  $\text{SO}_2$ , but the solid forms infinite chains which are not planar (Figure 15.6).  $\text{TeO}_2$  and  $\text{PoO}_2$  both crystallize in two ionic forms.





Figure 15.4 Structure of  $\text{SeO}_2$ .

The reaction of the dioxides with water also differs.  $\text{SO}_2$  is very soluble, but largely forms hydrated  $\text{SO}_2$  with only minute amounts of sulphurous acid  $\text{H}_2\text{SO}_3$ . (Dissolving  $\text{SO}_2$  in alkali gives sulphites – salts of  $\text{H}_2\text{SO}_3$ .) Pure  $\text{H}_2\text{SO}_3$  cannot be isolated.  $\text{SeO}_2$  reacts with water and forms selenious acid,  $\text{H}_2\text{SeO}_3$ , which may be obtained in a crystalline state.  $\text{TeO}_2$  is almost insoluble in water, but dissolves in alkali to form tellurites. It also dissolves in acids to form basic salts: this illustrates the amphoteric character of  $\text{TeO}_2$ . Thus there is the usual increase in basic character on descending a group.  $\text{SeO}_2$  is used to oxidize aldehydes and ketones.



### Trioxides $\text{MO}_3$

$\text{SO}_3$  is the only important trioxide. It is manufactured on a huge scale by the Contact process in which  $\text{SO}_2$  reacts with  $\text{O}_2$  in the presence of a catalyst (Pt or  $\text{V}_2\text{O}_5$ ). (See under  $\text{SO}_2$ ) The  $\text{SO}_3$  is not usually isolated, and practically all of it is converted to  $\text{H}_2\text{SO}_4$ .  $\text{SO}_3$  reacts vigorously with water, evolving a large amount of heat and forming  $\text{H}_2\text{SO}_4$ . Commercially it is not possible just to react  $\text{SO}_3$  with water. The  $\text{SO}_3$  reacts with water vapour and causes the formation of a dense mist of  $\text{H}_2\text{SO}_4$  droplets, which are difficult to condense and pass out of the absorber into the atmosphere. To avoid this, it has been found best to dissolve  $\text{SO}_3$  in 98–99%  $\text{H}_2\text{SO}_4$  in ceramic packed towers, to give oleum or fuming sulphuric acid. This is mainly pyrosulphuric acid  $\text{H}_2\text{S}_2\text{O}_7$ . Water is continuously added to keep the concentration of  $\text{H}_2\text{SO}_4$  constant.



In the gas phase  $\text{SO}_3$  has a plane triangular structure (Figure 15.7). The bonding is best described as S forming three  $\sigma$  bonds, giving rise to a plane triangle, and three delocalized  $\pi$  bonds. (See Chapter 4.)

At room temperature  $\text{SO}_3$  is solid and exists in three distinct forms.  $\gamma$ - $\text{SO}_3$  is ice-like and is a cyclic trimer  $(\text{SO}_3)_3$ , m.p.  $16.8^\circ\text{C}$ . If  $\text{SO}_3$  is kept




Figure 15.5 Structure of  $\text{SO}_2$ .




Figure 15.7 Structure of  $\text{SO}_3$





Figure 15.8 Structure of  $\text{SO}_3$  chains and  $\text{SO}_3$  cyclic trimer

for a long time, or if a trace of water is present, either  $\beta \text{SO}_3$  or  $\alpha \text{SO}_3$  is formed. Both look like asbestos, and comprise bundles of white silky needles.  $\beta \text{SO}_3$  (m.p.  $32.5^\circ\text{C}$ ) is made up of infinite helical chains of tetrahedral  $[\text{SO}_4]$  units each sharing two corners. This structure is similar to that of chain phosphates.  $\alpha \text{SO}_3$  (m.p.  $62.2^\circ\text{C}$ ) is the most stable form and is made of chains cross-linked into sheets (Figure 15.8).

$\text{SO}_3$  is a powerful oxidizing agent, especially when hot. It oxidizes  $\text{HBr}$  to  $\text{Br}_2$  and  $\text{P}$  to  $\text{P}_4\text{O}_{10}$ .


Commercially  $\text{SO}_3$  is important in the manufacture of  $\text{H}_2\text{SO}_4$  and also for sulphonating long chain alkylbenzene compounds. The sodium salts of these alkylbenzene sulphonates are anionic surface active agents and are the active ingredients of detergents.

$\text{SO}_3$  is used to make sulphamic acid  $\text{NH}_2\text{SO}_3\text{H}$



Sulphamic acid is the only strong acid that exists as a solid at room temperature. It is used for cleaning the plant at sugar refineries and breweries for desalination evaporators, and for destroying any excess nitrites present after dyeing with diazo dyestuffs.

$\text{SeO}_3$  is formed by the action of a silent electric discharge on  $\text{Se}$  and  $\text{O}_2$  gases, and  $\text{TeO}_3$  is formed from telluric acid  $\text{H}_6\text{TeO}_6$  by strong heating. Both trioxides are acid anhydrides.



### Other oxides


$\text{S}_2\text{O}$  is formed when  $\text{S}$  and  $\text{SO}_2$  are subjected to a silent electric discharge. It is very reactive, attacks metals and  $\text{KOH}$ , and will polymerize. It can exist for a few days at low pressures. It is of interest spectroscopically because of its similarity in structure to  $\text{O}_2$ . Until recently it was incorrectly formulated as  $\text{SO}$ .

A range of oxides from  $\text{S}_6\text{O}$  to  $\text{S}_{10}\text{O}$  have been made by dissolving the cyclo forms of  $\text{S}_6$ ,  $\text{S}_7$ ,  $\text{S}_8$ ,  $\text{S}_9$  and  $\text{S}_{10}$  in  $\text{CS}_2$  or  $\text{CH}_2\text{Cl}_2$  and oxidizing with trifluoroperoxoacetic acid at  $-10^\circ\text{C}$  to  $-30^\circ\text{C}$ .



These compounds are all orange-yellow in colour, and retain the original ring of  $\text{S}$  atoms, but have an oxygen atom double bonded to one of the ring  $\text{S}$  atoms.

$\text{TeO}$  and  $\text{PoO}$  are obtained by thermal decomposition of a sulphite.




### Detergents


Soap is the original detergent. It is excellent for cleaning and is 100% biodegradable (i.e. it is completely broken down by bacteria in sewage).

disposal plants or rivers). It has a typical formula of  $C_{17}H_{35}COO^-Na^+$ . It has two disadvantages:

1. It forms an insoluble precipitate or 'scum' when hard water containing  $Ca^{2+}$  or  $Mg^{2+}$  is used.
2. It cannot be used for industrial purposes in acidic solutions, since the fatty acids are precipitated.



Detergents are surface active agents. They consist of molecules with a non-polar organic part, and a polar group. If a non-polar material is placed in an ionic solvent containing a detergent, then the detergent molecules will arrange themselves on the surface so that the non-polar part of the molecule points towards the non-polar material, and the polar group points towards the solvent. Thus particles of dirt become surrounded by detergent molecules, forming a micelle. This effectively 'dissolves' the dirt. The first new detergents, introduced in about 1950, were branched chain alkylbenzene sulphonates (ABS). They are called 'hard detergents' and a typical formula is:



These are excellent detergents, with good surface active and cleaning properties. The problem is that waste water containing the detergent passes through the drains to the sewage treatment plants. The detergents cause problems with frothing in the sewage plants. Bacteria in the treatment plant break down various waste products, both sewage and the detergents. However, the detergent is only about 50–60% biodegradable. The bacteria cannot degrade the benzene ring, and they have difficulty and are slow at degrading branched chains. Thus much of the detergent is discharged into rivers and foams badly, especially if protein is present in the water.

'Soft' detergents also contain a non-polar and a polar part of the molecule, but they are linear alkylbenzene sulphonates (LAS) and have an unbranched aliphatic chain. They are 90% biodegradable. The straight alkyl chain is completely degraded, but the aromatic ring is not. Thus soft detergents cause considerably less pollution than do hard detergents.

If straight chain alcohols such as lauryl alcohol (available from coconut oil or tallow) are sulphonated, the product is an excellent detergent, which is rapidly and completely biodegraded. Alcohols of chain length  $C_{14}$  can be produced by the Ziegler–Natta process (see under 'Organometallic

compounds', Chapter 12) and are useful for making biodegradable detergents such as Teepol

At first sight it seems highly desirable to use biodegradable detergents. However, their use can create other problems. The bacteria responsible for degrading will grow rapidly, feeding on the degradable detergent. In growing they may use up all the dioxygen dissolved in the water. The lack of dioxygen kills all other forms of aquatic life such as fish or plants. Under extreme anaerobic conditions  $\text{SO}_4^{2-}$  ions may be reduced to  $\text{H}_2\text{S}$ , giving unpleasant smells.




### OXOACIDS OF SULPHUR

The oxoacids of sulphur are more numerous and more important than those of Se and Te. Many of the oxoacids of sulphur do not exist as free acids, but are known as anions and salts. Acids ending in -ous have S in the oxidation state (+IV), and form salts ending in -ite. Acids ending in -ic have S in the oxidation state (+VI) and form salts ending in -ate.


As discussed previously under bond lengths and  $p\pi-d\pi$  bonding, the oxoanions have strong  $\pi$  bonds and so they have little tendency to polymerize compared with the phosphates and silicates. To emphasize structural similarities the acids are listed in four series.



- 1 sulphurous acid series
- 2 sulphuric acid series
- 3 thionic acid series
- 4 peroxyacid series

#### 1 Sulphurous acid series





#### 2 Sulphuric acid series







### 3. Thionic acid series




### 4. Peroxoacid series





### Sulphurous acid series

Though  $\text{SO}_2$  is very soluble in water, most is present as hydrated  $\text{SO}_2$  ( $\text{SO}_2 \cdot \text{H}_2\text{O}$ ). Sulphurous acid  $\text{H}_2\text{SO}_3$  may exist in the solution in minute amounts, or not at all, though the solution is acidic. Its salts, the sulphites  $\text{SO}_3^{2-}$ , form stable crystalline solids. Many sulphites are insoluble or are sparingly soluble in water, e.g.  $\text{CaSO}_3$ ,  $\text{BaSO}_3$  or  $\text{Ag}_2\text{SO}_3$ . However, those of the Group 1 metals and ammonium are soluble in water, and in dilute solutions the hydrogen sulphite (bisulphite) ion  $\text{HSO}_3^-$  is the predominant species. Crystals of hydrogen sulphites have only been formed with a few large metal ions, e.g.  $\text{RbHSO}_3$  and  $\text{CsHSO}_3$ . Most attempts to isolate hydrogen sulphites lead to internal dehydration with the formation of disulphites  $\text{S}_2\text{O}_5^{2-}$ :




$\text{Na}_2\text{SO}_3$  is an important industrial chemical, and world production exceeds 1 million tonnes/year. It is made by passing  $\text{SO}_2$  into an aqueous solution of  $\text{Na}_2\text{CO}_3$  to give aqueous  $\text{NaHSO}_3$ , then treating the solution with more  $\text{Na}_2\text{CO}_3$ .



The main use of  $\text{Na}_2\text{SO}_3$  is as a bleach for wood pulp in the paper making industry. Some is used to treat boiler feed water (it removes  $\text{O}_2$  and thus reduces corrosion of pipes and boilers). Small amounts are used in photographic developer.

Sulphites and hydrogen sulphites liberate  $\text{SO}_2$  on treatment with dilute acids.



Sulphites and hydrogen sulphites both contain S in the oxidation state (+IV) and are moderately strong reducing agents. Sulphites are determined by reaction with  $\text{I}_2$ , and determination of the excess  $\text{I}_2$  with sodium thiosulphate.



The sulphite ion exists in crystals and has a pyramidal structure, that is tetrahedral with one position occupied by a lone pair. The bond angles  $\text{O}-\text{S}-\text{O}$  are slightly distorted ( $106^\circ$ ) due to the lone pair, and the bond lengths are  $1.51 \text{ \AA}$ . The  $\pi$  bond is delocalized, and hence the  $\text{S}-\text{O}$  bonds have a bond order of 1.33.






Fig. 15.9 Structure of sulphite ion  $\text{SO}_3^{2-}$

Electronic structure of sulphur atom – excited state



three unpaired electron form  $\sigma$  bonds forms  $\pi$  bond with three oxygen atoms  
four electron pairs hence tetrahedral  
with one position occupied by a lone pair

On heating solid hydrogen sulphites, or treating their solutions with  $\text{SO}_2$ , disulphites are formed. These contain an  $\text{S}-\text{S}$  linkage.




$\text{Na}_2\text{S}_2\text{O}_5$  is called sodium disulphite, but in the past it has been called sodium pyrosulphite and sodium metabisulphite. The free acid  $\text{H}_2\text{S}_2\text{O}_5$  is not known. Adding acid to disulphites gives  $\text{SO}_2$ .







On oxidation sulphites form sulphates, and with sulphur they form thio-sulphates.





Reduction of sulphite solution plus  $\text{SO}_2$  with Zn dust, or electrolytically, yields dithionites. These contain S in the oxidation state (+III).



The dithionite ion has an eclipsed conformation, with a very long S—S bond (2.39 Å) and S—O bond lengths of 1.51 Å. Sodium dithionite  $\text{Na}_2\text{S}_2\text{O}_4$  crystallizes out on adding NaCl to the mixture. The parent acid does not exist.  $\text{Na}_2\text{S}_2\text{O}_4$  is a powerful reducing agent, which has a variety of industrial uses. These include bleaching paper pulp and making dye-stuffs. It is used to treat water since it reduces many heavy metal ions ( $\text{Pb}^{2+}$ ,  $\text{Cu}^+$ ,  $\text{Bi}^{3+}$ ) to the metal. In NaOH solution  $\text{Na}_2\text{S}_2\text{O}_4$  is used to absorb dioxygen in gas analysis. It is also used to preserve foodstuffs and fruit squashes.

### Sulphuric acid series

$\text{H}_2\text{SO}_4$  is the most important acid used in the chemical industry. World production was 146 million tonnes in 1992. The main producers in millions tonnes/year are: USA 42%, China 14%, Morocco 7% and Japan 6%. By far the most important commercial process for its manufacture is the Contact process, in which  $\text{SO}_2$  is oxidized by air to  $\text{SO}_3$ , using a catalytic surface. Formerly a platinum gauze or platinized asbestos was used as catalyst. This has now been replaced by vanadium pentoxide, which is slightly less efficient but is cheaper and less easily poisoned. The  $\text{SO}_3$  could be mixed with water to give  $\text{H}_2\text{SO}_4$ , but the reaction is violent and produces a dense chemical mist which is difficult to condense. Instead, the  $\text{SO}_3$  is passed into 98%  $\text{H}_2\text{SO}_4$ , forming pyrosulphuric acid  $\text{H}_2\text{S}_2\text{O}_7$ , sometimes called oleum or fuming sulphuric acid. (Some trisulphuric acid  $\text{H}_2\text{S}_3\text{O}_{10}$  is also formed.) This solution may be sold as oleum, or diluted with water to give concentrated sulphuric acid which is a 98% mixture with water (an 18M solution).




(The older lead chamber process is now obsolete. This used  $\text{NO}_2$  as a homogeneous catalyst, to oxidize  $\text{SO}_2$  in the presence of water. The NO formed reacts with air to reform  $\text{NO}_2$ .)



dehydrates  $\text{HNO}_3$ , forming the nitronium ion  $\text{NO}_2^+$ , which is very important in the nitration of organic compounds.



$\text{H}_2\text{SO}_4$  can also remove the elements of water, for example in the preparation of ethers.




It removes water so strongly from some organic compounds that they char, and only the carbon remains. Paper and cloth are completely destroyed.



In dilute aqueous solution  $\text{H}_2\text{SO}_4$  acts as a strong acid. The first proton dissociates very readily, and hence hydrogen sulphates  $\text{HSO}_4^-$  formed. The second proton dissociates much less readily, to form sulphates  $\text{SO}_4^{2-}$ . Because of this, solutions of hydrogen sulphates are acidic.

The  $\text{SO}_4^{2-}$  ion is tetrahedral. The bond lengths are all equal (1.49 Å) and are all rather short. The bond order of the S—O bonds is approximately 1.5. The bonding is best explained as four  $\sigma$  bonds between S and the O atoms, with two  $\pi$  bonds delocalized over the S and the four O atoms.

Thiosulphuric acid  $\text{H}_2\text{S}_2\text{O}_3$  cannot be formed by adding acid to a thiosulphate because the free acid decomposes in water into a mixture of S,  $\text{H}_2\text{S}$ ,  $\text{H}_2\text{S}_n$ ,  $\text{SO}_2$  and  $\text{H}_2\text{SO}_4$ . It can be made in the absence of water (e.g. in ether) at low temperatures ( $-78^\circ\text{C}$ ).




In contrast, the salts which are called thiosulphates are stable and numerous. Thiosulphates are made by boiling alkaline or neutral sulphite solutions with S, and also by oxidizing polysulphides with air.



The thiosulphate ion is structurally similar to the sulphate ion (Figure 15.10).

Hydrated sodium thiosulphate  $\text{Na}_2\text{S}_2\text{O}_3 \cdot 5\text{H}_2\text{O}$  is called 'hypo'. It forms very large colourless hexagonal crystals, m.p.  $48^\circ\text{C}$ . It is readily soluble in water and solutions are used for iodine titrations in volumetric analysis. Iodine very rapidly oxidizes thiosulphate ions  $\text{S}_2\text{O}_3^{2-}$  to tetrathionate ions  $\text{S}_4\text{O}_6^{2-}$ , and the  $\text{I}_2$  is reduced to  $\text{I}^-$  ions.



$\text{Na}_2\text{S}_2\text{O}_3$  is used in the bleaching industry to destroy any excess  $\text{Cl}_2$  on fabrics after they have been through a bleach bath. Similarly  $\text{Na}_2\text{S}_2\text{O}_3$  is sometimes used to remove the taste from heavily chlorinated drinking





Figure 15.10 Structure of sulphate and thiosulphate ion


water. Since  $\text{Cl}_2$  is a stronger oxidizing agent than  $\text{I}_2$ , hydrogensulphate ions are formed rather than tetrathionate ions



Hypo is used in photography for 'fixing' films and prints. Photographic emulsions are made of  $\text{AgNO}_3$ ,  $\text{AgCl}$  and  $\text{AgBr}$ . Parts of the film exposed to light begin to decompose to  $\text{Ag}$ , thus forming a negative image. The process is enhanced by the developer solution. After developing, the film or print is put in a solution of hypo ( $\text{Na}_2\text{S}_2\text{O}_3$ ). This forms a soluble complex with silver salts, thus dissolving any unchanged silver salts in the photographic emulsion. When there is no photographic emulsion left, the film or print can safely be exposed to light.




Pyrosulphates can be made by heating hydrogen sulphates strongly, or by dissolving  $\text{SO}_3$  in  $\text{H}_2\text{SO}_4$ . Some trisulphuric acid  $\text{H}_2\text{S}_3\text{O}_{10}$  is also formed, but polysulphuric acids higher than this are not known.





### Thionic acid series

Dithionic acid  $\text{H}_2\text{S}_2\text{O}_6$  is known only in solution. The acid is dibasic, and salts called dithionates are known, e.g.  $\text{Na}_2\text{S}_2\text{O}_6$ . No acid salts exist. The acid and its salts contain S in the oxidation state (+V). Dithionates can be made by oxidizing a sulphite, but on a larger scale they are made by oxidizing a cooled aqueous solution of  $\text{SO}_2$  with  $\text{MnO}_2$  or  $\text{Fe}_2\text{O}_3$ .




Most dithionates are readily soluble in water. They can be isolated as  $\text{BaS}_2\text{O}_6$ , and converted into other salts by double decomposition reactions. Dithionates are stable to mild oxidizing agents, though strong oxidizing agents, such as  $\text{KMnO}_4$  or the halogens, oxidize them to sulphate. Similarly, mild reducing agents have no effect but strong reducing agents reduce dithionates to dithionites and sulphites.



The dithionate ion has a structure similar to that of ethane, but the two  $\text{SO}_3$  groups adopt an almost eclipsed conformation. The S—S length is

2.15 Å and the S—O bonds are 1.43 Å – again rather short. The bond angles S—S—O are close to tetrahedral (103°).


A range of polythionates have been known as salts since the early work of Wackenroder on the effect of H<sub>2</sub>S on aqueous solutions of SO<sub>2</sub>. Ions such as trithionate S<sub>3</sub>O<sub>6</sub><sup>2-</sup>, tetrathionate S<sub>4</sub>O<sub>6</sub><sup>2-</sup>, pentathionate S<sub>5</sub>O<sub>6</sub><sup>2-</sup> and hexathionate S<sub>6</sub>O<sub>6</sub><sup>2-</sup> are named according to the total number of S atoms present. It is only in recent times that the parent acids have been made.




### Peroxoacid series

The name peroxo indicates that the compound contains an —O—O— linkage. Two peroxoacids of sulphur are known: peroxomonosulphuric acid H<sub>2</sub>SO<sub>5</sub> and peroxodisulphuric acid H<sub>2</sub>S<sub>2</sub>O<sub>8</sub>. No peroxoacids of Se and Te are known. H<sub>2</sub>S<sub>2</sub>O<sub>8</sub> is a colourless solid, m.p. 65°C. It is obtained by electrolysis of sulphates at high current density. It is soluble in water, and is a powerful and useful oxidizing agent. It will convert Mn<sup>2+</sup> to permanganate and Cr<sup>3+</sup> to chromate. The most important salts are (NH<sub>4</sub>)<sub>2</sub>S<sub>2</sub>O<sub>8</sub> and K<sub>2</sub>S<sub>2</sub>O<sub>8</sub>. (NH<sub>4</sub>)<sub>2</sub>S<sub>2</sub>O<sub>8</sub> is used to initiate the polymerization of vinyl acetate in the production of synthetic rayon, and of tetrafluoroethylene in the formation of PTFE. K<sub>2</sub>S<sub>2</sub>O<sub>8</sub> is used as an initiating agent in the polymerization of vinyl chloride to PVC and styrene—butadiene copolymer rubbers.

Hydrolysis of peroxodisulphuric acid gives peroxomonosulphuric acid, H<sub>2</sub>SO<sub>5</sub>, which is often called Caro's acid.



H<sub>2</sub>SO<sub>5</sub> can also be made from chlorosulphuric acid:



It forms colourless crystals, m.p. 45°C, but must be handled with care since it may explode.

### OXOACIDS OF SELENIUM AND TELLURIUM

Selenium forms two oxoacids, selenious acid H<sub>2</sub>SeO<sub>3</sub> and selenic acid H<sub>2</sub>SeO<sub>4</sub>. Selenious acid is formed when SeO<sub>2</sub> dissolves in water. The solid acid can be isolated and two series of salts (the normal and acid selenites)

containing  $\text{SeO}_3^{2-}$  and  $\text{HSeO}_3^-$  are known. The acid is converted to selenic acid by refluxing with  $\text{H}_2\text{O}_2$ . Pyroselenates containing  $\text{Se}_2\text{O}_7^{2-}$  can be made by heating selenates, but the free acid is not known.


$\text{H}_2\text{SeO}_4$ , like  $\text{H}_2\text{SO}_4$ , is a strong acid and selenates are isomorphous with sulphates. Both  $\text{H}_2\text{SeO}_4$  and  $\text{H}_2\text{SeO}_3$  are moderately strong oxidizing agents.

$\text{TeO}_2$  is almost insoluble in water so that tellurous acid has not been characterized. The dioxide does react with strong bases and forms tellurites, acid tellurites and various polytellurites. Telluric acid  $\text{H}_6\text{TeO}_6$  is quite different from sulphuric and selenic acids and exists as octahedral  $\text{Te}(\text{OH})_6$  molecules in the solid. It is a fairly strong oxidizing agent, but a weak dibasic acid and forms two series of salts, examples of which are  $\text{NaTeO}(\text{OH})_5$  and  $\text{Li}_2\text{TeO}_2(\text{OH})_4$ . The acid is prepared by the action of powerful oxidizing agents such as  $\text{KMnO}_4$  on Te or  $\text{TeO}_2$ .


## OXOHALIDES

### Thionyl compounds


Only S and Se form oxohalides. These are called thionyl and selenyl halides, and the following are known




Thionyl chloride  $\text{SOCl}_2$  is a colourless fuming liquid, b.p.  $78^\circ\text{C}$ , and is usually prepared as follows



Most thionyl compounds are readily hydrolysed by water, though  $\text{SOF}_2$  only reacts slowly



$\text{SOCl}_2$  is used by organic chemists to convert carboxylic acids to acid chlorides and it is also used to make anhydrous metal chlorides




Thionyl bromide is prepared from the chloride and  $\text{HBr}$ , and thionyl fluoride is obtained from the chloride by reacting with  $\text{SbF}_3$ .


The structure of these oxohalides is tetrahedral with one position occupied by a lone pair.

### Sulphuryl compounds

The following sulphuryl halides are known







Sulphuryl chloride  $\text{SO}_2\text{Cl}_2$  is a colourless fuming liquid, b.p.  $69^\circ\text{C}$ , and is made by direct reaction of  $\text{SO}_2$  and  $\text{Cl}_2$  in the presence of a catalyst. It is used as a chlorinating agent. Sulphuryl fluoride is a gas and is not hydrolysed by water, but the chloride fumes in moist air and is hydrolysed by water. The sulphuryl halides have a distorted tetrahedral structure. They may be regarded as derivatives of  $\text{H}_2\text{SO}_4$ , where both OH groups have been replaced by halogens. If only one group is replaced, halosulphuric acids are obtained.



Fluorosulphuric acid forms many salts, but chlorosulphuric acid forms none and is used as a chlorinating agent in organic chemistry.


## HYDRIDES

The elements all form covalent hydrides. These are water  $\text{H}_2\text{O}$ , hydrogen sulphide  $\text{H}_2\text{S}$ , hydrogen selenide  $\text{H}_2\text{Se}$ , hydrogen telluride  $\text{H}_2\text{Te}$  and hydrogen polonide  $\text{H}_2\text{Po}$ . Water is liquid at room temperature, but the others are all colourless, foul smelling toxic gases. All but  $\text{H}_2\text{Te}$  can be made from the elements. It is easier to make  $\text{H}_2\text{S}$ ,  $\text{H}_2\text{Se}$  and  $\text{H}_2\text{Te}$  by the action of mineral acids on metal sulphides, selenides and tellurides, or hydrolysis:





$\text{H}_2\text{Te}$  can also be made by electrolysis cooled dilute  $\text{H}_2\text{SO}_4$  with a Te cathode.  $\text{H}_2\text{Po}$  has only been obtained in trace amounts from a mixture of Mg, Po and dilute acid.


$\text{H}_2\text{S}$ ,  $\text{H}_2\text{Se}$  and  $\text{H}_2\text{Te}$  are all soluble in water and all burn in air with a blue flame.



$\text{H}_2\text{S}$  is about twice as soluble in water as  $\text{CO}_2$ , and 1 volume of water can absorb 4.6 volumes of  $\text{H}_2\text{S}$  at  $0^\circ\text{C}$  and 2.6 volumes at  $20^\circ\text{C}$ . A saturated solution is used as a laboratory reagent, but it does not keep well since air slowly oxidizes it and sulphur is deposited.  $\text{H}_2\text{S}$  is a very weak dibasic acid. Most metal sulphides can be regarded as salts of  $\text{H}_2\text{S}$ , and since it is dibasic two series of salts can be derived from it, the hydrogen sulphides, e.g.  $\text{NaHS}$ , and the normal sulphides, e.g.  $\text{Na}_2\text{S}$ .



The alkali metal sulphides are all soluble in water and hydrolyse strongly (a 1 M solution is about 90% hydrolysed), so they are strongly basic.



Most of the sulphides of the heavy metals are insoluble in water and so do not hydrolyse. If a dilute solution of ammonia is saturated with  $\text{H}_2\text{S}$  then ammonium hydrogen sulphide  $\text{NH}_4\text{HS}$  is formed, not  $(\text{NH}_4)_2\text{S}$ . The latter only exists at low temperatures in the absence of water. Solutions of  $\text{NH}_4\text{HS}$  are colourless, and when mixed with an equimolar amount of  $\text{NH}_3$  it is used as a laboratory reagent. More commonly 'yellow ammonium sulphide' is used as a laboratory reagent for example to precipitate metal sulphides in qualitative analysis. Yellow ammonium sulphide is really a mixture of ammonium polysulphides, and is made by dissolving sulphur in colourless  $\text{NH}_4\text{HS}/\text{NH}_3$  solution.

### Water


Water is the most abundant chemical compound and the oceans cover almost 71% of the earth's surface. For this reason we have no need to prepare water. However, sea water contains many dissolved salts, and less than 3% of the earth's water is fresh water, and most of that is present as polar ice. The preparation of pure water for drinking and laboratory use is a major industry. The human body is more tolerant of some impurities than is industry. The EEC have set limits for impurities in drinking water.

Table 15.7 EEC limits for contaminants in drinking water


	( $\mu\text{g litre}^{-1}$ )	Source of contaminant and suspected problems
Al	200	$\text{Al}_2(\text{SO}_4)_3$ is added to water in some places to clarify it. Al may be related to Alzheimer's disease (senile dementia).
Pb	50	Water pipes made of lead are the problem. Pb damages the brains of children.
$\text{NO}_3^-$	50	Nitrates are added as fertilizers to make crops grow. This gets into the water supply. Nitrates affect the level of $\text{O}_2$ in the blood of babies and cause blue baby syndrome. Nitrates may be related to stomach cancer.
Trihalomethanes	100	Water supplies are treated with chlorine to kill bacteria. Over-chlorination may allow chloroform to be formed by reaction with peat. This is a possible cause of cancer of the gut and bladder.
Pesticides	0.1 0.5	For individual pesticides For all pesticides together DDT is now banned in many places. Its harmful effects occur because it accumulates and undergoes biological amplification in the food chain and UV light converts DDT into polychlorinated biphenyls which are toxic.



Very pure water is required for laboratory and industrial use. The only way to remove all solid solutes is distillation. This is expensive since water has a high boiling point and high latent heat of evaporation. During distillation the water tends to dissolve appreciable amounts of  $\text{CO}_2$  from the atmosphere, which make it acidic. A cheaper method is to produce deionized water. This is done by passing the water down two different ion-exchange columns one after the other. (Alternatively a 'mixed bed' may be used, i.e. a single column made up of two different ion-exchange materials.) Ion-exchange resins are insoluble polymeric solids, containing a reactive group. They are manufactured in bead form, and are permeable to water. The first column contains a sulphonic acid resin, that is an organic resin with acidic groups  $-\text{SO}_3\text{H}$ . This removes all metal ions from solution and replaces them with  $\text{H}^+$ :



The second column contains a resin with basic groups  $-\text{NR}_4^+\text{OH}^-$ , which removes negative ions.



Water produced in this way usually contains soluble silicates and  $\text{CO}_2$ . When all the reactive sites on the resin have been used, the resins can be regenerated by treating the first one with dilute  $\text{H}_2\text{SO}_4$ , and the second one with a  $\text{Na}_2\text{CO}_3$  solution.

Drinking water is usually much less pure, and water with no dissolved salts does not taste very nice. The World Health Organization recommends a maximum desirable content of not more than 0.5 grams of dissolved solids per litre, though the maximum permissible level is three times this. If the fresh water source contains silt, this is allowed to settle out. Light suspended particles and colloidal particles which discolour the water are removed by treating with  $\text{Al}(\text{OH})_3$  or  $\text{Fe}(\text{OH})_3$ . These coagulate suspended particles, thus clarifying the water. (Alum is the most widely used coagulating agent.) If necessary some water softening may be performed by ion-exchange, or by mixing water from different sources. The water is then chlorinated, or treated with ozone to kill bacteria. These are present because of drainage from fields into rivers and lakes, and also from the disposal of partly treated and untreated sewage. Failure to treat drinking water is the major cause of enteritis. In some underdeveloped parts of the world up to half the children under the age of five die from this cause or other waterborne diseases.

Sea water has a high salt content. The production of drinking water and water for crops from sea water is called desalination. It requires a large amount of energy, and is therefore expensive. It is only carried out when the shortage of fresh water is severe, but it has become increasingly important in arid regions like the Persian Gulf. Distillation, ion-exchange, electrodialysis, reverse osmosis and the freezing out of ice have all been used.

Table 15.8 Some properties of  $\text{H}_2\text{O}$ ,  $\text{H}_2\text{S}$ ,  $\text{H}_2\text{Se}$  and  $\text{H}_2\text{Te}$ 

	Enthalpies of formation ( $\text{kJ mol}^{-1}$ )	Bond angle	Boiling point ( $^{\circ}\text{C}$ )
$\text{H}_2\text{O}$	-242	$\text{H}-\text{O}-\text{H} = 104^{\circ}28'$	100
$\text{H}_2\text{S}$	-20	$\text{H}-\text{S}-\text{H} = 92^{\circ}$	-60
$\text{H}_2\text{Se}$	+81	$\text{H}-\text{Se}-\text{H} = 91^{\circ}$	-42
$\text{H}_2\text{Te}$	+154		-2.3

Apart from water, the other hydrides are all poisonous and have unpleasant odours. The hydrides decrease in stability from  $\text{H}_2\text{O}$  to  $\text{H}_2\text{S}$  to  $\text{H}_2\text{Se}$  to  $\text{H}_2\text{Te}$  (This is shown by the decrease in their enthalpies of formation – Table 15.8). They become less stable because the bonding orbitals become larger and more diffuse, hence overlap with the hydrogen 1s orbital is less effective.

The  $\text{H}-\text{O}-\text{H}$  bond angle in water is  $104^{\circ}28'$ , in accordance with the VSEPR prediction of slightly less than tetrahedral due to the presence of lone pairs of electrons. Thus the orbitals used for bonding by O are close to  $sp^3$  hybrids. In  $\text{H}_2\text{S}$ ,  $\text{H}_2\text{Se}$  and  $\text{H}_2\text{Te}$  the bond angles become close to  $90^{\circ}$ . This suggests that almost pure  $p$  orbitals on Se and Te are used for bonding to hydrogen.

In a series of similar compounds, the boiling points usually increase as the atoms become larger and heavier. If the boiling points increase, then the volatility decreases. This trend is shown by the boiling points of  $\text{H}_2\text{S}$ ,  $\text{H}_2\text{Se}$ ,  $\text{H}_2\text{Te}$  and  $\text{H}_2\text{Po}$ , but the boiling point of water is anomalous.

Water has an abnormally low volatility because its molecules are associated with each other by means of hydrogen bonds in both the solid and liquid states. The structure of liquid water is not known for certain, but probably consists of groups of two or three molecules hydrogen bonded together. The structure of ordinary hexagonal ice is known. At high pressures other more dense structures are formed. A total of nine different forms of ice are known. X-ray studies do not often reveal the positions of H atoms. In this case the H positions were found by neutron diffraction on solid deuterium oxide  $\text{D}_2\text{O}$ . The structure is similar to wurtzite  $\text{ZnS}$  (see Chapter 3), with O atoms occupying both the  $\text{Zn}^{2+}$  and the  $\text{S}^{2-}$  positions. The H atoms are located just off the line joining two O atoms, and the  $\text{O}-\text{H} \cdots \text{O}$  angle is  $104^{\circ}28'$ . The strength of a hydrogen bond is about  $20 \text{ kJ mol}^{-1}$ . This association is responsible for the abnormally high boiling point and melting point of water.

The H bonding is the main reason why covalent compounds have a very low solubility in water. When two substances mix there is an increase in entropy since the order decreases. Thus mixing is always favoured. However, in the case of water, dissolving something means that hydrogen bonds must be broken. Unless there is an interaction between the dissolved material and water greater than the energy lost through breaking hydrogen bonds, then the material will not dissolve. Covalent materials have little


interaction with water, and so are insoluble. Ionic materials become hydrated, and polar materials take part in the hydrogen bonding, so they are soluble.

A unique property of water is that the solid is less dense than the liquid. This is why lakes and the sea freeze from the top downwards. The ice at the top makes it difficult to cool the water underneath, so even at the North Pole there is water underneath the ice. But for this the sea would freeze solid and the polar ice-caps would cover much more of the earth's surface. The maximum density of water occurs at 4°C. On melting, the hydrogen bonded network in the solid partly breaks down. Ice has a rather open structure, with quite large cavities. On partial melting some 'free' water molecules occupy some of these cavities, and hence the density increases. This effect outweighs the effect of thermal expansion up to 4°C, but above this temperature expansion is the larger effect so the density decreases.

An unusual form of water called 'polywater' was reported and extensively studied between 1966 and 1973. Polywater was reported to have a freezing point of -40°C and a very high density of 1.4 g cm<sup>-3</sup>. It was obtained when water was formed in glass or quartz capillary tubes. This caused excitement at first because polywater was thought to comprise a larger number of water molecules polymerized together. It is now known to be a colloidal mixture of silicates, and a variety of ions Na<sup>+</sup>, K<sup>+</sup>, Ca<sup>2+</sup>, BO<sub>3</sub><sup>3-</sup>, NO<sub>3</sub><sup>-</sup>, SO<sub>4</sub><sup>2-</sup> and Cl<sup>-</sup> which had been leached from the glass!

### Other hydrides

The hydrides dissociate to a varying degree, forming H<sup>+</sup> ions. They are all very weak acids and there is an increase in acidic strength from H<sub>2</sub>O to H<sub>2</sub>Te. The large difference in electronegativity taken in conjunction with Fajans' rules (the larger the negative ion the greater the tendency to covalency) suggest that H<sub>2</sub>Te *gas* should be the most covalent. Acidic behaviour *in solution* is discussed for the halogen acids (see Chapter 16) and depends on the enthalpy of formation of the molecule, the ionization energy, electron affinity and enthalpies of hydration. In the compounds H<sub>2</sub>O, H<sub>2</sub>S, H<sub>2</sub>Se and H<sub>2</sub>Te the most important factor is the enthalpy of formation, the values being -120, -10, +43 and +77 kJ mol<sup>-1</sup>. The stability decreases (the last two are in fact thermodynamically unstable), thus accounting for the greater dissociation of H<sub>2</sub>Te.




The more acidic the hydrogen atom in the hydrides, the more stable will be the salts formed from them, i.e. oxides, sulphides, selenides and tellurides.

### Peroxides and polysulphides



Oxygen, and to a greater extent sulphur, differ from the remainder in their ability to catenate and form polyoxides and polysulphides, which are less

stable than the normal salts. Unbranched polysulphane chains containing up to eight sulphur atoms have been prepared




$\text{H}_2\text{O}_2$  and  $\text{H}_2\text{S}_2$  have similar 'skew' structures. The dimensions of  $\text{H}_2\text{O}_2$  gas are shown in Figure 15.11.  $\text{H}_2\text{O}_2$  is the smallest molecule known to show restricted rotation, in this case about the O—O bond, and this is presumably due to repulsion between the OH groups. A similar structure is retained in the liquid and solid, but the bond lengths and angles are slightly changed because of hydrogen bonding.

$\text{H}_2\text{O}_2$  and  $\text{H}_2\text{S}_2$  can be prepared by the addition of acid to a peroxide or a persulphide salt






In most of its reactions  $\text{H}_2\text{O}_2$  acts as a strong oxidizing agent. In acidic solutions these reactions are often slow, but in basic solution they are usually fast.  $\text{H}_2\text{O}_2$  will oxidize  $\text{Fe}^{2+}$  to  $\text{Fe}^{3+}$ ,  $[\text{Fe}^{\text{II}}(\text{CN})_6]^{4-}$  (ferrocyanide) to  $[\text{Fe}^{\text{III}}(\text{CN})_6]^{3-}$  (ferricyanide),  $\text{NH}_2\text{OH}$  to  $\text{HNO}_3$  and  $\text{SO}_3^{2-}$  to  $\text{SO}_4^{2-}$ .

Ionic peroxides such as  $\text{Na}_2\text{O}_2$  give  $\text{H}_2\text{O}_2$  with water or dilute acids.  $\text{Na}_2\text{O}_2$  reacts with gaseous  $\text{CO}_2$





Heating  $\text{Na}_2\text{O}_2$  with many organic compounds results in their oxidation to carbonates. Fusing  $\text{Na}_2\text{O}_2$  with  $\text{Fe}^{2+}$  salts gives sodium ferrate  $\text{Na}_2[\text{FeO}_4]$  which contains  $\text{Fe}(+\text{VI})$ .

With stronger oxidizing agents  $\text{H}_2\text{O}_2$  is oxidized, that is  $\text{H}_2\text{O}_2$  is forced to act as a reducing agent, and in such cases  $\text{O}_2$  is always evolved



$\text{H}_2\text{S}_2$  is not oxidizing.  $\text{H}_2\text{O}_2$  is fairly stable and decomposes only slowly in the absence of catalysts.  $\text{H}_2\text{S}_2$  is less stable, and its decomposition is catalysed by hydroxyl ions



Hydrogen polyselenides and polytellurides do not exist, but some of their salts are known

### Hydrogen peroxide

Pure  $\text{H}_2\text{O}_2$  is a colourless liquid which resembles water quite closely. It is more hydrogen bonded than is water and so has a higher boiling






Figure 15.11 Structure of  $\text{H}_2\text{O}_2$  in the gas phase

point (b.p. 152°C, m.p. -0.4°C). It is more dense than water (density 1.4 g cm<sup>-3</sup>). Though it has a high dielectric constant, it is of little use as an ionizing solvent because it is decomposed by many metal ions, and it oxidizes many compounds.




H<sub>2</sub>O<sub>2</sub> is a major industrial chemical, and 1 018 200 tonnes were produced in 1991. It is used extensively as a mild bleaching agent for textiles and paper/wood pulp. It is used for several environmental purposes: to restore aerobic conditions in sewage waters, and to oxidize cyanides and sulphides. It is an important rocket fuel. It is also used for making other chemicals, particularly sodium peroxoborate Na<sub>2</sub>[B<sub>2</sub>(O<sub>2</sub>)<sub>2</sub>(OH)<sub>4</sub>] · 6H<sub>2</sub>O (annual production 700 000 tonnes/year), which is used as a brightener in washing powders (see Chapter 12). Organic peroxides are used to initiate addition polymerization reactions (PVC, polyurethanes and epoxy resins), and sodium chlorite NaClO<sub>2</sub> is used for bleaching. Smaller amounts of H<sub>2</sub>O<sub>2</sub> are used to bleach hair, feathers, fats and waxes. It is used as an oxidizing agent in the laboratory, and as an antiseptic to treat wounds. It is useful to counteract chlorine, and in this reaction H<sub>2</sub>O<sub>2</sub> behaves as a reducing agent.



H<sub>2</sub>O<sub>2</sub> is unstable, and the rate at which it decomposes (disproportionates) depends on the temperature and concentration. Many impurities catalyse the decomposition, which may become very violent, especially in concentrated solutions. Catalysts include metal ions Fe<sup>2+</sup>, Fe<sup>3+</sup>, Ni<sup>2+</sup>, metal surfaces such as Pt or Ag, MnO<sub>2</sub>, charcoal or alkali – even the small amount leached from glass.




At one time H<sub>2</sub>O<sub>2</sub> was obtained by electrolysis of H<sub>2</sub>SO<sub>4</sub> or (NH<sub>4</sub>)<sub>2</sub>SO<sub>4</sub> at a high current density to form peroxosulphates, which were then hydrolysed.



H<sub>2</sub>O<sub>2</sub> is now produced on an industrial scale by a cyclic process (Figure 15.12). 2-Ethyl anthroquinol is oxidized by air to the corresponding quinone and H<sub>2</sub>O<sub>2</sub>. The anthraquinone is reduced back to anthraquinol with hydrogen at a moderate temperature using platinum, palladium or Raney nickel as catalyst. The cycle is then repeated. The reaction is carried out in a mixture of organic solvents (ester/hydrocarbon or octanol/methylnaphthalene). The solvent must:

1. dissolve the quinol and quinone
2. resist oxidation
3. be immiscible with water.

Figure 15.12 Production of  $\text{H}_2\text{O}_2$ 

The  $\text{H}_2\text{O}_2$  is extracted with water as a 1% solution. This is concentrated by distillation under reduced pressure, and sold as a 30% (by weight) solution which has a pH of about 4.0 (85% solutions are also produced).  $\text{H}_2\text{O}_2$  solutions are stored in plastic or wax coated glass vessels, often with negative catalysts such as urea or sodium stannate added as stabilizers. Solutions keep quite well, but must be handled with care since they may explode with traces of organic material or specs of dust.

### HALIDES

Compounds with the halogens are listed in Table 15.9. Since F is more electronegative than O, binary compounds are oxygen fluorides, whereas similar chlorine compounds are chlorine oxides. Some of these compounds including the oxides of iodine, are therefore described in Chapter 16 under 'Halogens oxides'.

Fluorine brings out the maximum valency of six with S, Se and Te, and


Table 15.9 Compounds with the halogens

	$\text{MX}_6$	$\text{MX}_4$	$\text{MX}_2$	$\text{M}_2\text{X}_2$	$\text{M}_2\text{X}$	Others
O			$\text{OF}_2$ $\text{Cl}_2\text{O}$ $\text{Br}_2\text{O}$	$\text{O}_2\text{F}_2$	$\text{ClO}_2$ $\text{BrO}_2$	$\text{O}_3\text{F}_2$ , $\text{O}_4\text{F}_2$ $\text{Cl}_2\text{O}_6$ , $\text{Cl}_2\text{O}_7$ $\text{BrO}_3$ $\text{I}_2\text{O}_4$ , $\text{I}_4\text{O}_9$ , $\text{I}_2\text{O}_5$
S	$\text{SF}_6$	$\text{SF}_4$ $\text{SCl}_4$	$\text{SF}_2$ $\text{SCl}_2$	$\text{S}_2\text{F}_2$ $\text{S}_2\text{Cl}_2$ $\text{S}_2\text{Br}_2$		$\text{SSF}_2$ , $\text{S}_2\text{F}_4$ , $\text{S}_2\text{F}_{10}$
Se	$\text{SeF}_6$	$\text{SeF}_4$ $\text{SeCl}_4$ $\text{SeBr}_4$		$\text{Se}_2\text{Cl}_2$ $\text{Se}_2\text{Br}_2$		
Te	$\text{TeF}_6$	$\text{TeF}_4$ $\text{TeCl}_4$ $\text{TeBr}_4$ $\text{TeI}_4$	$\text{TeCl}_2$ $\text{TeBr}_2$ $\text{TeI}_2$			
Po		$\text{PoCl}_4$ $\text{PoBr}_4$ $\text{PoI}_4$	$\text{PoCl}_2$ $\text{PoBr}_2$ $(\text{PoI}_2)$			

Compounds shown in parentheses are unstable.


$\text{SF}_6$ ,  $\text{SeF}_6$  and  $\text{TeF}_6$  are all formed by direct combination. They are all colourless gases and have an octahedral structure as predicted by the VSEPR theory. The low boiling point indicates a high degree of covalency.

Electronic structure of sulphur – excited state







six unpaired electrons form bonds with six fluorine atoms, hence octahedral shape

$\text{SF}_6$  is a colourless, odourless, non-flammable gas, which is insoluble in water and extremely inert. It is used as a gaseous dielectric (insulator) in high voltage transformers and switchgear.  $\text{SeF}_6$  is slightly more reactive and  $\text{TeF}_6$  is hydrolysed by water. This is possibly due to the larger size of Te which permits the larger coordination number necessary in the first stage of hydrolysis.




Coordination numbers greater than 6 are not common, but  $\text{TeF}_6$  does add  $\text{F}^-$  ions, forming  $[\text{TeF}_7]^-$  and  $[\text{TeF}_8]^{2-}$


Many tetrahalides are known. It is difficult to prepare tetrafluorides by direct combination even with diluted  $\text{F}_2$ , because they readily change to hexafluorides.  $\text{SF}_4$  is gaseous,  $\text{SeF}_4$  liquid and  $\text{TeF}_4$  solid. They have been prepared:






$\text{SF}_4$  is highly reactive, but is more stable than the lower fluorides. In contrast to the relatively stable hexafluorides, the tetrahalides are very sensitive to water.




$\text{SF}_4$  is a powerful fluorinating agent.




It is a useful selective fluorinating agent for organic chemicals, for example:



Figure 15 13 Structure of  $\text{TeCl}_4$ 


S, Se, Te and Po form tetrachlorides by direct reaction with chlorine.  $\text{SCl}_4$  is a rather unstable liquid, but the other tetrachlorides are solids. The structure of  $\text{TeCl}_4$  is a trigonal bipyramid with one equatorial position occupied by a lone pair (Figure 15 13). It is probable that the other tetrahalides are similar.

Electronic structure of tellurium atom – excited state




four unpaired electrons can form bonds with four chlorine atoms  
five electron pairs hence trigonal bipyramid with one position occupied by a lone pair

$\text{TeCl}_4$  reacts with hydrochloric acid and gives the complex ion  $[\text{TeCl}_6]^{2-}$  which is isomorphous with  $[\text{SiF}_6]^{2-}$  and  $[\text{SnCl}_6]^{2-}$





Po also forms complex halide ions and a series of compounds  $(\text{NH}_4)_2[\text{PoX}_6]$  and  $\text{Cs}[\text{PoX}_6]$  and  $\text{Cs}_2[\text{PoX}_6]$  are known where X is Cl, Br or I

Tetrabromides of Se, Te and Po are known but  $\text{SeBr}_4$  is unstable and hydrolyses readily




Te and Po are the only elements which form tetraiodides

$\text{SCl}_2$  is the best known dihalide. It is a foul smelling red liquid (m.p.  $-122^\circ\text{C}$ , b.p.  $59^\circ\text{C}$ ). Heating S and  $\text{Cl}_2$  gives  $\text{S}_2\text{Cl}_2$ , and if this is saturated with chlorine  $\text{SCl}_2$  is formed. Reacting  $\text{SCl}_2$  with hydrogen polysulphides at low temperatures yields a range of dichlorosulphanes



$\text{SCl}_2$  is commercially important since it readily adds across double bonds in alkenes. It has been used to produce the notorious 'mustard gas', first used in World War I, and more recently in 1988 in the Iran-Iraq war




Mustard gas is not a gas but a volatile liquid (m.p.  $13^\circ\text{C}$ , b.p.  $215^\circ\text{C}$ ). It was sprayed as a mist that stayed close to the ground, and was blown by gentle winds onto the enemy. It causes severe blistering of the skin and death. In living cells it is converted into the divinyl compound  $(\text{CH}_2\text{CH})_2\text{S}$  which reacts with and disrupts proteins in the cell.





The dihalides form angular molecules, based on a tetrahedron with two positions occupied by lone pairs. The lone pairs distort the tetrahedral angle of  $109^{\circ}28'$  to  $103^{\circ}$  in  $\text{SCl}_2$ ,  $101.5^{\circ}$  in  $\text{F}_2\text{O}$  and  $98^{\circ}$  in  $\text{TeBr}_2$ .

Electronic structure of sulphur atom – ground state




two unpaired electrons can form bonds with two chlorine atoms  
four electron pairs, hence structure is tetrahedral with two lone pairs


Dimeric monohalides such as  $\text{S}_2\text{F}_2$ ,  $\text{S}_2\text{Cl}_2$ ,  $\text{Se}_2\text{Cl}_2$  and  $\text{Se}_2\text{Br}_2$  are formed by direct action between S and Se and the halogens. These monohalides are hydrolysed slowly and tend to disproportionate.



$\text{S}_2\text{Cl}_2$  is a toxic yellow liquid (m.p.  $-76^{\circ}\text{C}$ , b.p.  $138^{\circ}\text{C}$ ), with a revolting smell. It is commercially important in vulcanizing rubber, and in preparing chlorohydrins. The use of  $\text{S}_2\text{Cl}_2$  has been described earlier for making rings of sulphur atoms with 7–20 atoms.




It can also be used to make dichlorosulphuranes.



The structure of  $\text{S}_2\text{Cl}_2$  and the other monohalides is similar to that of  $\text{H}_2\text{O}_2$ , with a bond angle of  $104^{\circ}$  which is due to distortion by two lone pairs.


$\text{S}_2\text{F}_2$  is an unstable compound. It is formed by the action of a mild fluorinating agent such as  $\text{AgF}$  on S. (Direct reaction of S with F gives  $\text{SF}_6$ , and even when the F is diluted with  $\text{N}_2$  it gives  $\text{SF}_4$ .)  $\text{S}_2\text{F}_2$  exists in two different isomeric forms,  $\text{F}-\text{S}-\text{S}-\text{F}$  (like  $\text{Cl}-\text{S}-\text{S}-\text{Cl}$  and  $\text{H}-\text{O}-\text{O}-\text{H}$ ), and thiothionyl fluoride  $\text{S}=\text{SF}_2$ .

The compound  $\text{S}_2\text{F}_{10}$  has an unusual structure, of two octahedra joined together.





## COMPOUNDS OF SULPHUR AND NITROGEN

A number of ring and chain compounds containing S and N exist. The elements N and S are diagonally related in the periodic table, and have similar charge densities. Their electronegativities are close (N 3.0, S 2.5) so covalent bonding is expected. The compounds formed have unusual structures which cannot be explained by the usual bonding theories. Attempting to work out oxidation states is unhelpful or misleading.

Figure 15 14 Structure of  $N_4S_4$ 


The best known is tetrasulphur tetranitride  $S_4N_4$ , and this is the starting point for many other S—N compounds.  $S_3N_3$  may be made as follows



$S_4N_4$  is a solid, m.p.  $178^\circ C$ . It is *thermochromic* that is it changes colour with temperature. At liquid nitrogen temperatures it is almost colourless, but at room temperature it is orange-yellow, and at  $100^\circ C$  it is red. It is stable in air, but may detonate with shock, grinding or sudden heating. The structure is a heterocyclic ring. This is cradle shaped and differs structurally from the  $S_8$  ring which is crown shaped. The X-ray structure (Figure 15 14) shows that the average S—N bond length is  $1.62 \text{ \AA}$ . Since the sum of the covalent radii for S and N is  $1.78 \text{ \AA}$ , the S—N bonds seem to have some double bond character. The fact that the bonds are of equal length suggests that this is delocalized. The S—S distances at the top and bottom of the cradle are  $2.58 \text{ \AA}$ . The van der Waals (non bonded) distance S—S is  $3.30 \text{ \AA}$ , and the single bond distance S—S is  $2.08 \text{ \AA}$ . This indicates weak S—S bonding, and  $S_4N_4$  is thus a cage structure.

Many different sizes of rings exist, for example  $\text{cyclo } S_2N_2$ ,  $\text{cyclo } S_4N_2$ ,  $\text{cyclo } S_4N_3Cl$ ,  $\text{cyclo } S_4N_4Cl_2$ . In addition bicyclo compounds  $S_{11}N_2$ ,  $S_{14}N_2$ ,  $S_{16}N_2$ ,  $S_{17}N_2$  and  $S_{19}N_2$  are known. The last four may be regarded as two heterocyclic  $S_7N$  rings, with the N atoms joined through a chain of 1–5 S atoms.


$S_4N_4$  is very slowly hydrolysed by water but reacts rapidly with warm NaOH with the break-up of the ring



If  $S_4N_4$  is treated with  $AgF$  in  $CCl_4$  solution then  $S_4N_4F_4$  is formed. This has an eight-membered S—N ring with the F atoms bonded to S. This results from breaking the S—S bonds across the ring. Similarly the formation of adducts such as  $S_4N_4 \cdot BF_3$  or  $S_4N_4 \cdot SbF_5$  (in which the extra group is bonded to N) breaks the S—S bonds and increases the mean S—N distance from  $1.62 \text{ \AA}$  to  $1.68 \text{ \AA}$ . This is presumably because the electron attracting power of  $BF_3$  or  $SbF_5$  withdraws some of the  $\pi$  electron density.

Reduction of  $S_4N_4$  with  $SnCl_2$  in MeOH gives tetrasulphur tetraimide  $S_4(NH)_4$ . Several imides can be made by reacting  $S_4N_4$  with S, or  $S_2Cl_2$  with  $NH_3$ . These imides are related to an  $S_x$  ring in which one or more S atoms have been replaced by imide NH groups, for example in  $S_7NH$ ,  $S_8(NH)_2$ ,  $S_8(NH)_3$  and  $S_4(NH)_4$ .

If  $S_4N_4$  is vaporized under reduced pressure and passed through silver wool then disulphur dinitrogen  $S_2N_2$  is formed




$S_2N_2$  is a crystalline solid, which is insoluble in water but soluble in many organic solvents. It explodes with shock or heat. The structure is cyclic and the four atoms are very nearly square planar.

The most important reaction of  $S_2N_2$  is the slow polymerization of the solid or vapour to form polythiazyl  $(SN)_x$ . This is a bronze coloured shiny solid that looks like a metal. It conducts electricity and conductivity increases as the temperature decreases, which is typical of a metal. It becomes a superconductor at 0.26 K. The crystal structure shows that the four-membered rings in  $S_2N_2$  have opened and polymerized into a long chain polymer. The atoms have a zig-zag arrangement, and the chain is almost flat. Conductivity is much greater along the chains than in other directions, and so the polymer behaves as a one-dimensional metal. The resistivity is quite high at room temperature (about  $1 \times 10^9 \mu\text{ohm cm}$  along a chain), but this falls to about  $1 \times 10^6 \mu\text{ohm cm}$  at 4 K. (See Appendix J for values for other elements.)

## ORGANO DERIVATIVES

Oxygen forms many organo derivatives  $R_2O$ , which are called ethers. Similar derivatives of S, Se and Te may be prepared using Grignard or organolithium reagents:



Dialkyl sulphides  $R_2S$  have a similar structure to water (tetrahedral with two positions occupied by lone pairs), and the lone pairs make them useful donor molecules.

Haemoglobin is the pigment in the blood of most animals. It is red when dioxygen is present and blue when there is no dioxygen. Haemoglobin is essential for absorbing molecular dioxygen in the lungs, where it forms oxyhaemoglobin. Oxyhaemoglobin releases the dioxygen in the parts of the body where it is needed, forming (reduced) haemoglobin. Haemoglobin






Figure 15.15 Structure of haem.

has a molecular weight of about 65000. It is made up of four haem groups, which are flat heterocyclic porphyrin ring systems containing iron and a globular protein (Figure 15.15). (See 'Bioinorganic chemistry of iron', Chapter 24.) Haemoglobin reacts with  $O_2$  and forms oxyhaemoglobin. In this complex the O-O axis of the  $O_2$  molecule lies parallel to the plane of the porphyrin ring, with two equal Fe-O distances. It is thought that molecular dioxygen is  $\pi$  bonded to the iron.

A few transition metal complexes can also form  $\pi$  bonded complexes with molecular oxygen.



### FURTHER READING

- Bagnall, K. W. (1973) *Comprehensive Inorganic Chemistry*, Vol. II (Chapter 24. Selenium, tellurium and polonium), Pergamon Press, Oxford.
- Bailey, P. S. (1978) *Ozonation in Organic Chemistry*, Academic Press, New York.
- Bard, A. J., Parsons, R. and Jordan, J. (1985) *Standard Potentials in Aqueous Solution* (Monographs in Electroanalytical Chemistry and Electrochemistry Series, Vol. 6), Marcel Dekker. (Commissioned by IUPAC to replace the earlier values in Latimer's book.)
- Bevan, D. J. M. (1973) *Comprehensive Inorganic Chemistry*, Vol. 3 (Chapter 49. Nonstoichiometric compounds), Pergamon Press, Oxford. (A good introduction to nonstoichiometric compounds.)
- Bland, W. J. (1984) Sulphuric acid - modern manufacture and uses, *Education in Chemistry*, 21, 7-10.
- Campbell, I. M. (1977) *Energy and the Atmosphere*, Wiley, London. (Acid rain etc.)
- Clive, D. L. J. (1978) *Modern Organo Selenium Chemistry*, Pergamon Press, New York.
- Cocks, A. and Kallend, T. (1988) The chemistry of atmospheric pollution. *Chemistry in Britain*, 24, 884-885.
- Cooper, W. C. (1972) *Tellurium*, Van Nostrand-Reinhold, New York.
- Donovan, R. J. (1978) Chemistry and pollution of the stratosphere, *Education in Chemistry*, 15, 110-113.
- Dotto, L. and Schiff, H. (1978) *The Ozone War*, Doubleday, New York.
- Emeleus, H. J. and Sharpe, A. G. (1973) *Modern Aspects of Inorganic Chemistry*, 4th ed. (Chapter 12. Peroxides and peroxy acids), Routledge and Kegan Paul, London.
- Fogg, P. G. T. and Young, C. L. (eds) (1988) *Hydrogen Sulfide, Deuterium Sulfide and Hydrogen Selenide*, Pergamon.
- Greenwood, G. and Hill, H. O. A. (1982) Oxygen and life. *Chemistry in Britain*, 18, 194.
- Govindjee, R. (1977) Photosynthesis. *McGraw Hill Encyclopedia of Science and Technology*, 4th ed., Vol. 10. (An introductory article.)

- Heal, H.G. (1980) *The Inorganic Heterocyclic Chemistry of Sulphur, Nitrogen and Phosphorus*, Academic Press, London.
- Heicklen, J. (1976) *Atmospheric Chemistry*, Academic Press, New York. (Acid rain etc.)
- Holloway, J.H. and Laycock, D. (1983) Preparations and reactions of inorganic main-group oxide fluorides, *Adv. Inorg. Chem. Radiochem.*, **27**, 157–195.
- Horvath, M., Bilitzky, L. and Huttner, J. (1985) *Ozone* (Topics in Inorganic and General Chemistry Series No. 20), Elsevier.
- Hynes, H.B.N. (1973) *The Biology of Polluted Waters*, Liverpool University Press. (A good textbook on water pollution.)
- Lagowski, J. (ed.) (1967) *The Chemistry of Non-aqueous Solvents*, Vol. III (Chapter by Burow, D.F., Liquid sulphur dioxide), Academic Press, New York.
- Latimer, W.M. (1959) *The Oxidation States of the Elements and Their Potentials in Aqueous Solution*, 2nd ed., Prentice Hall. (Old, but until very recently the standard source of oxidation potential data.)
- Murphy, J.S. and Orr, J.R. (1975) *Ozone Chemistry and Technology*, Franklin Institute Press, Philadelphia.
- Nickless, G. (ed.) (1968) *Inorganic Sulfur Chemistry*, Elsevier, Amsterdam.
- Ochiai, E.I. (1975) Bioinorganic chemistry of oxygen, *J. Inorg. Nuclear Chem.*, **37**, 1503–1509.
- Ogryzlo, E.A. (1965) Why liquid oxygen is blue, *J. Chem. Ed.*, **42**, 647–648.
- Oxygen in the Metal and Gaseous Fuel Industries* (1978) Special Publication No. 32, Royal Society for Chemistry, London. (Proceedings of first BOC Priestley Conference.)
- Oxygen and Life* (1981) Special Publication No. 39, Royal Society for Chemistry, London. (Proceedings of second BOC Priestley Conference.)
- Patai, S. (ed.) (1983) *The Chemistry of Peroxides*, John Wiley Chichester.
- Phillips, A. (1977) The modern sulphuric acid process, *Chemistry in Britain*, **13**, 471.
- Roesky, H.W. (1979) Cyclic sulphur–nitrogen compounds, *Adv. Inorg. Chem. Radiochem.*, **22**, 240–302.
- Roy, A.B. and Trudinger, P.A. (1970) *The Biochemistry of Inorganic Compounds of Sulphur*, Cambridge University Press, Cambridge.
- Schaap, A.P. (ed.) (1976) *Singlet Molecular Oxygen*, Wiley, New York.
- Schmidt, M. and Siebert, W. (1973) *Comprehensive Inorganic Chemistry*, Vol. II (Chapter 23: Oxyacids of sulfur), Pergamon Press, Oxford.
- Thompson, R. (ed.) (1976) *The Modern Inorganic Chemicals Industry* (Chapter by Grant, W.J. and Redfearn, S.L., Industrial gases; chapter by Arden, T.V., Water purification and recycling; chapter by Crampton, C.A. *et al.*, Manufacture, properties and uses of hydrogen peroxide and inorganic peroxy compounds; chapter by Phillips, A., The modern sulphuric acid process), Special Publication No. 31, The Chemical Society, London.
- Thrush, B.A. (1977) The chemistry of the stratosphere and its pollution, *Endeavour*, **1**, 3–6.
- Vaska, L. (1976) Dioxygen–metal complexes: towards a unified view, *Acc. Chem. Res.*, **9**, 175–183.
- Waddington, T.C. (ed.) (1965) *Non Aqueous Solvents* (Chapter 4 by Gillespie, R.J. and Robinson, E.A., Sulfuric acid; chapter 6 by Waddington, T.C., Liquid sulfur dioxide), Nelson.
- Wasserman, H.H. and Murray, R.W. (eds) (1979) *Singlet Oxygen*, Academic Press, New York.
- West, J.R. (1975) *New Uses of Sulfur*, ACS Advances in Chemistry series, No. 140, American Chemical Society.
- Zurer, P.S. (1987) The Antarctic ozone-hole, *Chem. Eng. News*, 7 August, 7–13; 2 November, 22–26.

## PROBLEMS

- Write equations for the preparation of oxygen from (a)  $\text{H}_2\text{O}$  (b)  $\text{H}_2\text{O}_2$  (c)  $\text{Na}_2\text{O}$  (d)  $\text{NaNO}_3$  (e)  $\text{KClO}_3$  (f)  $\text{HgO}$
- How is oxygen obtained commercially and what are its main uses?
- Compare the oxides of Na and Ca with those of S and N. Comment on their melting points, the nature of the bonding and their reactions with water, acids and bases.
- In what ways and on what basis may oxides be classified?
- Use the molecular orbital theory to describe the bonding in each of the following and give the bond order and magnetic properties (paramagnetic or diamagnetic) in each case: (a)  $\text{O}_2$ , (b) superoxide ion  $\text{O}_2^-$ , (c) peroxide ion  $\text{O}_2^{2-}$ .
- Explain the following facts:
  - Liquid oxygen sticks to the poles of a magnet but liquid nitrogen does not.
  - The  $\text{N}-\text{O}^+$  ion has a shorter bond length than does  $\text{NO}$  even though the latter has an extra electron.
- How is ozone prepared in the laboratory? What is its structure and what are its main uses? There is a layer of ozone in the upper atmosphere: why is this important to man?
- Give equations for the reaction between  $\text{O}_3$  and (a) Li (b) Na (c) K (d) C (e)  $\text{CH}_4$  (f)  $\text{N}_2$  (g) S (h) Cl (i)  $\text{PbS}$  (j)  $\text{CuS}$ .
- Why have oxygen molecules the formula  $\text{O}_2$  whilst sulphur is  $\text{S}_8$ ?
- Describe one method by which hydrogen peroxide is prepared. Give the structure of  $\text{H}_2\text{O}_2$  in the gas phase. Write balanced equations for the reaction of  $\text{H}_2\text{O}_2$  with:
  - an acidified solution of  $\text{KMnO}_4$
  - aqueous HI
  - an acidic solution of potassium hexacyanoferrate(II)
- What are the main sources of sulphur? Which are the two most common allotropic forms?
- Describe the Frasch process for mining sulphur.
- Describe the changes which occur on heating sulphur.
- Explain the differences in bond angles and boiling points of  $\text{H}_2\text{O}$  and  $\text{H}_2\text{S}$ .
- Explain how  $\pi$  bonding occurs in  $\text{O}_2$ ,  $\text{O}_3$ ,  $\text{SO}_2$  and  $\text{SO}_3$ .
- Describe how sulphuric acid is manufactured on an industrial scale. List its main uses.

17. Describe the preparation, properties and structure of  $\text{SO}_2$ ,  $\text{SO}_3$ ,  $\text{H}_2\text{SO}_5$ ,  $\text{H}_2\text{S}_2\text{O}_8$ .
18. (a) Describe the differences in structure between gaseous and solid  $\text{SO}_3$ .  
(b) What reaction occurs between  $\text{SO}_3$  and  $\text{H}_2\text{SO}_4$ ? Give the structure of the product.  
(c) Describe the action of heat on  $\text{NaHSO}_3$ .  
(d) Compare the structures of the  $\text{SO}_4^{2-}$  and  $\text{S}_2\text{O}_3^{2-}$  ions.  
(e) What reaction occurs between  $\text{Na}_2\text{S}_2\text{O}_3$  and  $\text{I}_2$ ?  
(f) Why are sulphurous acid and sulphites reducing?
19. Compare and contrast sulphuric acid, selenic acid and telluric acid.
20. How is  $\text{Na}_2\text{S}_2\text{O}_3$  made? Explain its uses in photography and volumetric analysis.
21. What are the main fluorides of sulphur? How are they made, what are their structures and what are their uses?
22. Explain why  $\text{SF}_6$  is unreactive towards water but  $\text{TeF}_6$  reacts.
23. Suggest reasons why  $\text{SF}_6$  is known but  $\text{OF}_6$  is not.

Table 16.1 Electronic structures and oxidation states

Element		Electronic configuration	Oxidation states*
Fluorine	F	[He] 2s <sup>2</sup> 2p <sup>5</sup>	-1
Chlorine	Cl	[Ne] 3s <sup>2</sup> 3p <sup>5</sup>	-1 +1 +III +IV +V +VI +VII
Bromine	Br	[Ar] 3d <sup>10</sup> 4s <sup>2</sup> 4p <sup>5</sup>	-1 +1 +III +IV +V +VI
Iodine	I	[Kr] 4d <sup>10</sup> 5s <sup>2</sup> 5p <sup>5</sup>	-1 +1 +III +V +VII
Astatine	At	[Xe] 4f <sup>14</sup> 5d <sup>10</sup> 6s <sup>2</sup> 6p <sup>5</sup>	

\* The most important oxidation states (generally the most abundant and stable) are shown in bold. Other well characterized but less important states are shown in normal type. Oxidation states that are unstable or in doubt are given in parentheses.

## INTRODUCTION

The name halogen comes from the Greek, and means salt former. The elements all react directly with metals to form salts, and they are also very reactive with non-metals. Fluorine is the most reactive element known.

The elements all have seven electrons in their outer shell. The  $s^2p^5$  configuration is one  $p$  electron less than that of the next noble gas. Thus atoms complete their octet either by acquiring an electron (i.e. through forming an ionic bond, giving  $X^-$ ) or by sharing an electron with another atom (thus forming a covalent bond). Compounds with metals are typically ionic, whilst those with non-metals are covalent.

The halogens show very close group similarities. Fluorine (the first element in the group) differs in several ways from the rest of the group. The first element of each of the main groups all show differences from the subsequent elements. The reasons for the difference are

1. The first element is smaller than the rest, and holds its electrons more firmly.
2. It has no low-lying  $d$  orbitals which may be used for bonding.

The properties of chlorine and bromine are closer than those between the other pairs of elements because their sizes are closer. The ionic radius




of  $\text{Cl}^-$  is 38% larger than that of  $\text{F}^-$ , but the radius of  $\text{Br}^-$  is only 6.5% larger than that of  $\text{Cl}^-$ . The relatively small change in size occurs because  $\text{Br}^-$  contains ten  $3d$  electrons, which shield the nuclear charge ineffectively. This also results in the electronegativity values being particularly close for these two elements. Thus there is little difference in polarity of the bonds formed by Cl and Br with other elements.

The oxidation states ( $\pm 1$ ) are by far the most common. Whether it is ( $-1$ ) or ( $+1$ ) depends on whether the halogen is the most electronegative element. Higher oxidation states exist for all of the elements except F. The lack of low-lying empty  $d$  orbitals in the second shell prevents F from forming more than one normal covalent bond.

Fluorine is a very strong oxidizing agent, and this together with its small size allows it to form compounds that bring out the highest oxidation state of other elements. Examples include  $\text{IF}_7$ ,  $\text{PtF}_6$ ,  $\text{SF}_6$  and many hexafluorides,  $\text{BiF}_5$ ,  $\text{SF}_5$ ,  $\text{TbF}_4$ ,  $\text{AgF}_2$ , and  $\text{K}[\text{Ag}^{\text{III}}\text{F}_4]$ .

The elements all exist as diatomic molecules, and they are all coloured. Gaseous  $\text{F}_2$  is light yellow,  $\text{Cl}_2$  gas is yellow-green,  $\text{Br}_2$  gas and liquid are dark red-brown, and  $\text{I}_2$  gas is violet. The colours arise from the absorption of light on promoting an electron from the ground state to a higher state. On descending the group the energy levels become closer, so the promotion energy becomes less and the wavelength of the band becomes longer.

$\text{I}_2$  solid crystallizes as black flakes, and has a slightly metallic lustre. Though the X-ray structure shows discrete  $\text{I}_2$  molecules, the colour is reminiscent of charge transfer compounds, and the properties are different from those of other molecular solids. The solid conducts electricity to a small extent, and the conductivity increases when the temperature is raised. This behaviour is like that of an intrinsic semiconductor, and different from metals. However, liquid  $\text{I}_2$  conducts very slightly. This is ascribed to self-ionization:



The stable isotopes of the halogens all have a nuclear spin. This is used in nmr spectroscopy. Chemical shifts are conveniently measured using the isotope  $^{19}\text{F}$ .

Several chemicals are of commercial importance and are produced on a vast scale. These include  $\text{Cl}_2$  (35.3 million tonnes in 1994), anhydrous  $\text{HCl}$  and hydrochloric acid (12.3 million tonnes in 1991), anhydrous  $\text{HF}$  and hydrofluoric acid (1.5 million tonnes in 1994),  $\text{Br}_2$  (370 000 tonnes in 1993) and  $\text{ClO}_2$  (200 000 tonnes/year).

## OCCURRENCE AND ABUNDANCE

The halogens are all very reactive, and do not occur in the free state. However, all except astatine are found in combined form in the earth's crust. (Astatine is radioactive and has a short half life.) Fluorine is the thirteenth most abundant element by weight in the earth's crust, and

*continued overleaf*

Table 16.2 Abundance of the elements in the earth's crust by weight

	ppm	Relative abundance
F	544	13
Cl	126	20
Br	2.5	47
I	0.46	67

chlorine the twentieth. These two elements are reasonably abundant but bromine and iodine are comparatively rare.

The main source of fluorine is the mineral  $\text{CaF}_2$ , called fluor spar or fluorite. (The name fluor spar was given because the mineral fluoresces that is it emits light when it is heated.) World production was 3.6 million tonnes in 1992. The largest producers are China 42%, Mexico, Mongolia and the Soviet Union 8% each and South Africa 7%. Another well known fluorine containing mineral is fluoroapatite  $[\text{3}(\text{Ca}_3(\text{PO}_4)_2 \cdot \text{CaF}_2)]$ . This is used primarily as a source of phosphorus. It is not used to produce  $\text{HF}$  and  $\text{F}_2$  because the mineral contains appreciable amounts of  $\text{SiO}_2$ . The  $\text{HF}$  produced reacts with the  $\text{SiO}_2$  in the mineral to form fluorosilicic acid  $\text{H}_2[\text{SiF}_6]$ . Some  $\text{H}_2[\text{SiF}_6]$  is made in this way and is used as an alternative to  $\text{NaF}$  for fluoridizing drinking water. The mineral cryolite  $\text{Na}_3[\text{AlF}_6]$  is rather rare. It is found only in Greenland and is used in the electrolytic extraction of aluminium.

The most abundant compound of chlorine is  $\text{NaCl}$  and it is used to produce virtually all the  $\text{Cl}_2$  and  $\text{HCl}$  made. World consumption of  $\text{NaCl}$  was 183.5 million tonnes in 1992. Some salt is mined and some is obtained by solar evaporation of sea water. Chlorides and bromides are leached from the land by rain and are washed into the sea. Sea water usually contains about 15000 ppm (1.5%) of  $\text{NaCl}$ . Certain inland seas contain much more (the Dead Sea contains 8% and the Great Salt Lake, Utah contains 23%). The dried up beds of inland lakes and seas contain large deposits of  $\text{NaCl}$  mixed with smaller amounts of  $\text{CaCl}_2$ ,  $\text{KCl}$  and  $\text{MgCl}_2$ . In contrast, the fluoride content of sea water is very low (1.2 ppm). This is because the water contains a large concentration of  $\text{Ca}^{2+}$  and  $\text{CaF}_2$  is insoluble.




Bromides occur in sea water. Iodides only occur in low concentration in sea water but they are absorbed and concentrated by seaweed. At one time iodine was extracted from seaweed. There are now better sources. Natural brines have higher concentrations of  $\text{I}^-$ . Sodium iodate  $\text{NaIO}_3$  and sodium periodate  $\text{NaIO}_4$  occur as impurities in  $\text{NaNO}_3$  deposits in Chile.

## EXTRACTION AND USES OF THE ELEMENTS

### Fluorine

Fluorine is extremely reactive and this causes great difficulties in the preparation and handling of the element. The first preparation of fluorine

was by Moissan in 1886. He was subsequently awarded the Nobel Prize for Chemistry in 1906 for this work. Fluorine is obtained by treating  $\text{CaF}_2$  with concentrated  $\text{H}_2\text{SO}_4$  to give an aqueous mixture of HF. This is distilled, yielding anhydrous liquid HF. Then a cooled solution of  $\text{KHF}_2$  in anhydrous HF is electrolysed, giving  $\text{F}_2$  and  $\text{H}_2$  (Figure 16.1).



There are many difficulties in obtaining fluorine.

1. HF is corrosive, and etches glass and also causes very painful skin wounds. These arise partly by dehydrating the tissue, and partly from the acidic nature of HF. The wounds are slow to heal because  $\text{F}^-$  ions remove  $\text{Ca}^{2+}$  ions from the tissues.
2. Gaseous HF is also very toxic (3 ppm) compared with HCN (10 ppm).
3. Anhydrous HF is only slightly ionized and is therefore a poor conductor of electricity. Thus a mixture of KF and HF is electrolysed to increase the conductivity. Moissan used a solution of KF in HF with a mole ratio of 1 : 13. This has the disadvantage that the vapour pressure of HF is high, and this gives problems with toxicity and corrosion, even when the reaction mixture is cooled to  $-24^\circ\text{C}$ . Modern methods use medium temperature fluorine generators. These use a mole ratio of 1 : 2 of KF : HF so that the vapour pressure of HF is much lower. This mixture melts at about  $72^\circ\text{C}$  which is a much easier temperature to maintain. Note that KF and HF react to form the acid salt  $\text{K}^+[\text{F}-\text{H}-\text{F}]^-$ .
4. Water must be rigorously excluded or the fluorine produced will oxidize it to dioxygen.
5. The hydrogen liberated at the cathode must be separated from the fluorine liberated at the anode by a diaphragm, otherwise they will react explosively.
6. Fluorine is extremely reactive. It catches fire, for example with traces of grease or with crystalline silicon. Glass and most metals are attacked. It is difficult to find suitable materials from which to make the reaction vessels. Moissan used a platinum U-tube, since platinum is very unreactive (but it is very expensive). Copper or Monel metal (Cu/Ni alloy) are now used instead, because they cost less. A protective fluoride film forms on the surface of the metal and slows down further attack.
7. The cathodes are made of steel, the anodes are carbon, and teflon is used for electrical insulation. Graphite anodes must not be used, since graphite reacts with fluorine, forming graphite compounds  $\text{CF}_x$ . In these, fluorine atoms progressively invade the space between the sheets of graphite, forcing them apart, and buckling them. This gradually stops the graphite from conducting, the current needed increases, more heat is produced, and eventually an explosion may occur. Ungraphitized carbon is used to avoid this. It is made from powdered coke compacted and impregnated with copper.





Figure 16.1 Fluorine cell.


*continued overleaf*

Cylinders of  $F_2$  are now commercially available. However, for many purposes  $F_2$  is converted to  $ClF_3$  (b.p.  $12^\circ C$ ), which though very reactive is less unpleasant and easier to transport




Production of fluorine first became important for the manufacture of inorganic fluorides such as  $AlF_3$  and synthetic  $Na_3[AlF_6]$ . Both are used in the extraction of aluminium. The natural mineral cryolite is only found in Greenland, and this source is largely exhausted.

It was discovered in the 1940s that the isotopes of uranium could be separated by gaseous diffusion of  $UF_6$ . This was important in preparing enriched uranium to make the first atomic bomb. Gaseous diffusion is still used to make enriched uranium fuel for nuclear reactors. The nuclear industry uses about 75% of the fluorine produced.  $UF_6$  is made as follows



The fluorocarbons are a very interesting and useful group of compounds, derived from hydrocarbons by substituting F for H. Tetrafluoromethane  $CF_4$  is the fluorocarbon corresponding to methane. Completely fluorinated compounds  $C_nF_{2n+2}$  are called perfluoro compounds. Thus  $CF_4$  is perfluoromethane. Perfluoro compounds have very low boiling points for their molecular weight; this is associated with very weak intermolecular forces. Fluorocarbons are extremely inert. Unlike methane,  $CF_4$  can be heated in air without burning. Fluorocarbons are inert to concentrated  $HNO_3$  and  $H_2SO_4$ , to strong oxidizing agents such as  $KMnO_4$  or  $O_3$ , and to strong reducing agents such as  $Li[AlH_4]$  or C at  $1000^\circ C$ . They are attacked by molten Na. When pyrolysed at very high temperatures the C—C bonds break rather than the C—F bonds. Tetrafluoroethene  $F_2C=CF_2$  (b.p.  $-76.6^\circ C$ ) can be made



Fluoroalkenes of this type can be polymerized either thermally, or using a free radical initiator. Depending on the degree of polymerization, that is on the molecular weight produced, the products may be oils, greases or a solid of high molecular weight called polytetrafluoroethylene. This is similar to ethene (formerly called ethylene) polymerizing to give polyethylene (polythene). Polytetrafluoroethylene is known commercially as PTFE or Teflon. It is a very inert solid plastic material, and is useful because it is completely resistant to chemical attack and is an electrical insulator. Though expensive, it is used in laboratories. It is also used as a coating for non-stick pans.

Freons are mixed chlorofluorocarbons. Compounds such as  $CClF_3$ ,  $CCl_2F_2$  and  $CCl_3F$  are important as non-toxic refrigerating fluids and


aerosol propellants. They too are very inert, and are discussed later.  $\text{CF}_3\text{CHBrCl}$  is used as an anaesthetic called Fluothane.

Another use of  $\text{F}_2$  is to make  $\text{SF}_6$ , which is a very inert gas used as a dielectric (insulating) medium for high voltage equipment.  $\text{F}_2$  is also used to make other fluorinating agents  $\text{ClF}_3$ ,  $\text{BrF}_3$  and  $\text{IF}_5$  and  $\text{SbF}_5$ . The earlier use of liquid  $\text{F}_2$  as an oxidizing agent in rocket motors has now been discontinued. Anhydrous  $\text{HF}$  has many uses.

Traces of fluoride ions  $\text{F}^-$  in drinking water (about 1 ppm) greatly reduce the incidence of dental caries (tooth decay). The  $\text{F}^-$  ions make the enamel on teeth much harder, by converting hydroxyapatite [ $3(\text{Ca}_3(\text{PO}_4)_2 \cdot \text{Ca}(\text{OH})_2$ ] (the enamel on the surface of teeth) into the much harder fluoroapatite [ $3(\text{Ca}_3(\text{PO}_4)_2 \cdot \text{CaF}_2)$ ]. However,  $\text{F}^-$  concentrations above 2 ppm cause discoloration, the brown mottling of teeth, and higher concentrations are harmful. In some places  $\text{NaF}$  and  $\text{H}_2[\text{SiF}_6]$  are added to drinking water, where the natural water is very soft and contains insufficient naturally occurring  $\text{F}^-$  ions.  $\text{NaF}$  is now used in fluoride toothpaste. (The original fluoride toothpaste contained  $\text{SnF}_2$  and  $\text{Sn}_2\text{P}_2\text{O}_7$ .)

## Chlorine

Chlorine was first prepared by Scheele by oxidizing  $\text{HCl}$  with  $\text{MnO}_2$ . This method was used as a laboratory preparation, but chlorine is now readily available in cylinders.




Gas prepared from  $\text{MnO}_2$  in this way must be purified. First it is passed through water to remove  $\text{HCl}$ , and then through concentrated  $\text{H}_2\text{SO}_4$  to remove water. It may be further dried by passing it over  $\text{CaO}$  and  $\text{P}_4\text{O}_{10}$ .

Chlorine is produced commercially on a vast scale by two main methods. (About 35.3 million tonnes were produced in 1994.)

1. By the electrolysis of aqueous  $\text{NaCl}$  solutions in the manufacture of  $\text{NaOH}$ .
2. By electrolysis of fused  $\text{NaCl}$  in the manufacture of sodium. (See Chapter 10.)


Before 1960 chlorine was a by-product from these processes. Since then there has been a great increase in the use of chlorine, mainly in the manufacture of plastics such as polyvinyl chloride (14.9 million tonnes of PVC were made in 1991). Thus chlorine is now the major product.



At one time chlorine was produced by oxidizing  $\text{HCl}$  with air, using the Deacon process. This process became obsolete. (See Chapter 10.) How-

*continued overleaf*

ever a modified Deacon process is now used to a small extent. It utilizes HCl obtained as a by product from the pyrolysis of 1,2-dichloroethane to vinyl chloride, and uses an improved catalyst ( $\text{CuCl}_2$  with didymium oxide as promoter, didymium is an old name meaning 'twin' and it consists of two lanthanide elements praseodymium and neodymium). This works at a slightly lower temperature than the original process.



Chlorine gas is toxic. It was used as a poison gas in World War I. The gas is detectable by smell at a concentration of 3 ppm, and 15 ppm causes a sore throat and running eyes. Higher concentrations cause coughing, lung damage, and death.

World production of chlorine is about 35.3 million tonnes per year (the Soviet Union 43%, the USA 24%, Germany 7%, Canada and France 3% each, and Japan and the UK 2% each). About two thirds of this is used to make organic chloro compounds, one fifth for bleaching, and the rest for the manufacture of a variety of inorganic chemicals. The main two organic compounds produced are

- 1,2-dichloroethane
- vinyl chloride monomer

Both are used in the plastics industry. Other uses include the production of

- chlorinated solvents including methyl and ethyl chlorides
- perchloro- and dichloroethene
- mono-, di- and trichlorobenzene
- benzene hexachloride
- the insecticide DDT
- chlorinated phenols
- plant growth hormones (2,4-dichlorophenoxyacetic acid and 2,4,6-trichlorophenoxyacetic acid are used as selective weedkillers)


Large amounts of chlorine are used for bleaching textiles, wood, pulp and paper. Chlorine is widely used throughout the developed world to purify drinking water, because it kills bacteria. It is also used to make a wide variety of inorganic chemicals including

- bleaching powder
- sodium hypochlorite  $\text{NaOCl}$
- chlorine dioxide  $\text{ClO}_2$
- sodium chlorate  $\text{NaClO}_3$
- many metal and non metal chlorides




### Bromine

Bromine is obtained from sea water and brine lakes. Sea water contains about 65 ppm  $\text{Br}^-$ . Thus 15 tonnes of sea water contain about 1 kg of bromine. Bromine is extracted from sea water, but it is more economic

to use more concentrated brine sources such as the Dead Sea, or brine from wells in Arkansas and Michigan (USA) and Japan, which contain 2000–5000 ppm of  $\text{Br}^-$ . First  $\text{H}_2\text{SO}_4$  is added to adjust the pH to about 3.5. Then  $\text{Cl}_2$  gas is passed through the solution to oxidize the  $\text{Br}^-$  to  $\text{Br}_2$ . This is an example of displacement of one element by another higher in the electrochemical series.



The  $\text{Br}_2$  is removed by a stream of air, because  $\text{Br}_2$  is quite volatile. The gas is passed through a solution of  $\text{Na}_2\text{CO}_3$ , when the  $\text{Br}_2$  is absorbed, forming a mixture of  $\text{NaBr}$  and  $\text{NaBrO}_3$ . Finally the solution is acidified and distilled to give pure bromine.



World production of bromine was 370 000 million tonnes in 1993 (the USA 45%, Israel 36%, the UK 8% and Japan 4%). In 1955 about 90% was used to make 1,2-dibromoethane,  $\text{CH}_2\text{Br} \cdot \text{CH}_2\text{Br}$ , but the figure is now under 50%. 1,2-dibromoethane is added to petrol to act as a lead scavenger. Tetraethyl lead is added to petrol to improve its octane rating, but when it burns it forms lead deposits. 1,2-dibromoethane is added to prevent the build-up of lead deposits on the sparking plug and in the engine. The lead passes out with the exhaust gases, mainly as  $\text{PbClBr}$ . The use of  $\text{PbEt}_4$  as an anti-knock additive to petrol has already declined, and will decline further because of legislation against its use, and environmental concern over the toxic effects of lead. Therefore the use of 1,2-dibromoethane has also declined.

Almost 20% of the bromine produced is used to make organic derivatives such as methyl bromide, ethyl bromide and dibromochloropropane. These are used in agriculture:  $\text{MeBr}$  acts as a nematocide (kills earthworms) and as a pesticide against insects and fungi. The other compounds are used as pesticides.

Nearly 10% is used to make flame retardants. Bromo compounds may be included in the polymerization when making acrylic and polyester fibres. It is more common to 'fireproof' fabrics and carpets by treating them with tris(dibromopropyl)phosphate,  $(\text{Br}_2\text{C}_3\text{H}_5\text{O})_3\text{PO}$ . This may be done either when spinning the thread, or after manufacture.

Other uses include the manufacture of photographic emulsions and pharmaceuticals.  $\text{AgBr}$  is light sensitive and is used for photographic films, and also for water sanitation and dyestuffs.  $\text{KBr}$  is used as a sedative, and as an anticonvulsant in treating epilepsy.



## Iodine

There are two different commercial methods of obtaining iodine. The method used depends on whether the source is Chile saltpetre or natural

*continued overleaf*

brines (for example from wells in Oklahoma or Michigan USA, and Japan)

Chile saltpetre is mainly  $\text{NaNO}_3$ , but it contains traces of sodium iodate  $\text{NaIO}_3$  and sodium periodate  $\text{NaIO}_4$ . Pure  $\text{NaNO}_3$  is obtained by dissolving saltpetre in water and crystallizing  $\text{NaNO}_3$ . The iodate residues thus accumulate and concentrate in the mother liquor. Eventually, this concentrate is divided into two parts. One part is reduced with  $\text{NaHSO}_3$  to give  $\text{I}^-$ . This is mixed with the untreated part, giving  $\text{I}_2$ , which is filtered off as a solid and then purified by sublimation.




Sea water contains only about 0.05 ppm of  $\text{I}^-$ , which is too low for commercial recovery. Natural brine, which may contain 50–100 ppm, is treated with  $\text{Cl}_2$ , to oxidize  $\text{I}^-$  ions to  $\text{I}_2$ . This is blown out with air in the same way as bromine. Alternatively, after oxidation with  $\text{Cl}_2$ , the solution may be passed through an ion-exchange resin. The  $\text{I}_2$  is adsorbed on the column as the triiodide ion  $\text{I}_3^-$ , and finally is removed from the resin by treatment with alkali.

World production of  $\text{I}_2$  was 17 500 tonnes in 1992 (Japan 42%, Chile 35%, the USA 11%, and the Soviet Union 9%). There is no one dominant use. Half is used to make a variety of organic compounds including iodoform  $\text{CHI}_3$  (used as an antiseptic), and methyl iodide  $\text{CH}_3\text{I}$ .  $\text{AgI}$  is used for photographic films, and for seeding clouds to produce rain. Small amounts of iodine are required in the human diet, so traces (10 ppm) of  $\text{NaI}$  are added to table salt.  $\text{KI}$  is added to animal and poultry feeds. The thyroid gland produces a growth regulating hormone called thyroxine which contains iodine. Deficiency of iodine causes the disease goitre. Iodine has limited use as an antiseptic, tincture of iodine is an aqueous solution of  $\text{I}_2$  in  $\text{KI}$ , and French iodine is a solution in alcohol. In the laboratory iodides and iodates are used in volumetric analysis, and Nessler's reagent  $\text{K}_2[\text{HgI}_4]$  is used to detect ammonia.

### Astatine

Astatine does not occur in nature, but over twenty artificial isotopes have been made. All of these are radioactive. The most stable isotopes are  $^{210}\text{At}$  (half life 8.3 hours), and  $^{211}\text{At}$  (half life 7.5 hours). The latter was first made in 1940 by a nuclear reaction in which bismuth was bombarded with high energy  $\alpha$  particles.



Tracer methods were used to study the chemistry of  $^{211}\text{At}$ , using minute quantities of about  $10^{-14}$  mole. This isotope decays by orbital electron capture and by  $\alpha$ -emission (see Chapter 31 under 'Modes of decay'). Astatine appears to resemble iodine quite closely.



## SIZE OF ATOMS AND IONS

Table 16.3 Ionic and covalent radii

	Covalent radius (Å)	Ionic radius $X^-$ (Å)
F	0.72	1.33
Cl	0.99	1.84
Br	1.14	1.96
I	1.33	2.20

## IONIZATION ENERGY

The ionization energies of the halogens show the usual trend to smaller values as the atoms increase in size. The values are very high, and there is little tendency for the atoms to lose electrons and form positive ions.

Table 16.4 Ionization and hydration energies, electron affinity

	First ionization energy (kJ mol <sup>-1</sup> )	Electron affinity (kJ mol <sup>-1</sup> )	Hydration energy $X^-$ (kJ mol <sup>-1</sup> )
F	1681	-333	-513
Cl	1256	-349	-370
Br	1143	-325	-339
I	1009	-296	-274
At	-	-270	-

The ionization energy for F is appreciably higher than for the others, because of its small size. F always has an oxidation state of (-I) except in  $F_2$ . It forms compounds either by gaining an electron to form  $F^-$ , or by sharing an electron to form a covalent bond.

Hydrogen has an ionization energy of 1311 kJ mol<sup>-1</sup>, and it forms  $H^+$  ions. It is at first surprising that the halogens Cl, Br and I have lower ionization energies than H, yet they do not form simple  $X^+$  ions. The ionization energy is the energy required to produce an ion from a single isolated gaseous atom. Usually we have a crystalline solid, or a solution, so the lattice energy or hydration energy must also be considered. Because  $H^+$  is very small, crystals containing  $H^+$  have a high lattice energy, and in solution the hydration energy is also very high (1091 kJ mol<sup>-1</sup>). The negative ions also have a hydration energy. Thus  $H^+$  ions are formed because the lattice energy, or the hydration energy, exceeds the ionization energy. In contrast the halide ions  $X^+$  would be large and thus have low hydration and lattice energies. Since the ionization energy would be larger than the lattice energy or hydration energy, these ions are not normally

Table 16.5 Electronegativity and electrode potential

	Pauling's electronegativity	Standard electrode potential $E^\circ$ (volts)
F	4.0	+2.87
Cl	3.0	+1.40
Br	2.8	+1.09
I	2.5	+0.62
At	2.2	+0.3

formed. However, a few compounds are known where  $I^+$  is stabilized by forming a complex with a Lewis base, for example  $[I(\text{pyridine})_2]^+ \text{NO}_3^-$ . These are discussed later under 'Basic properties of the halogens'.

The electron affinities for the halogens are all negative. This shows that energy is evolved when a halogen atom gains an electron, and  $X \rightarrow X^-$ . Thus, the halogens all form halide ions.

### TYPE OF BONDS FORMED AND OXIDATION STATES

Most compounds formed by the halogens and metals are ionic. However, covalent halides are formed in a few cases where the metal ions are very small and have a high charge. (The structures of  $\text{BeCl}_2$  and  $\text{AlCl}_3$  are unusual – see Chapters 11 and 12.)

The halogens all have very high electronegativity values (see Table 16.5). When they react with metals there will be a large electronegativity difference, hence they form ionic bonds. Halide ions are produced quite easily. This is shown by the large electron affinity values (Table 16.4). Note that energy is evolved when a gaseous halogen atom gains an electron, and also because of their large positive standard electrode potentials for  $X_2|2X^-$  (Table 16.5). (The standard electrode potentials may be converted to an energy term using the relationship  $\Delta G^\circ = -nFE^\circ$ , where  $n$  is the number of electrons (2 in this case), and  $F$  is the Faraday constant  $96486 \text{ kJ mol}^{-1}$ .) The  $E^\circ$  values decrease down the group and thus the energy evolved on forming halide ions also decreases down the group. Many iodides are partly covalent. For example,  $\text{CdI}_2$  forms a layer structure, and all the iodides have much lower melting points than the fluorides.

When two halogen atoms form a molecule, they form a covalent bond. Most compounds between the halogens and non-metals are also covalent. Fluorine is always univalent, and since it is the most electronegative element it always has the oxidation number  $(-1)$ . With Cl, Br and I, a covalence of one is the most common. The oxidation state may be either  $(-1)$  or  $(+1)$  depending on which atom in the molecule has the greater electronegativity.

Cl, Br and I also exhibit higher valencies, with oxidation numbers of




Figure 16.2 Structure of (a)  $\text{BeCl}_2$  and (b)  $\text{AlCl}_3$

(+III), (+V) and (+VII): These higher valency states are covalent, and arise quite logically by promoting electrons from filled  $p$  and  $s$  levels to empty  $d$  levels. The unpaired electrons then form three, five or seven covalent bonds. There are numerous examples of higher valency states in the interhalogens and halogen oxides.

Electronic structure of halogen atom – ground state

full inner shell	$ns$	$np$	$nd$
	$\uparrow\downarrow$	$\uparrow\downarrow \uparrow\downarrow \uparrow$	$\square \square \square \square \square$

(Only one unpaired electron, so can only form one covalent bond)

Electronic structure of halogen atom – excited state

full inner shell	$ns$	$np$	$nd$
	$\uparrow\downarrow$	$\uparrow\downarrow \uparrow \uparrow$	$\uparrow \square \square \square \square$

(Three unpaired electrons, so can form three covalent bonds)

Electronic structure of halogen atom – further excited state

full inner shell	$ns$	$np$	$nd$
	$\uparrow\downarrow$	$\uparrow \uparrow \uparrow$	$\uparrow \uparrow \square \square \square$

(Five unpaired electrons, so can form five covalent bonds)

Electronic structure of halogen atom – still further excited

full inner shell	$ns$	$np$	$nd$
	$\uparrow$	$\uparrow \uparrow \uparrow$	$\uparrow \uparrow \uparrow \square \square$

(Seven unpaired electrons, so can form seven covalent bonds)

The oxidation states (+IV) and (+VI) occur in the oxides  $\text{ClO}_2$ ,  $\text{BrO}_2$ ,  $\text{Cl}_2\text{O}_6$  and  $\text{BrO}_3$ .

## MELTING AND BOILING POINTS

The melting and boiling points of the elements increase with increased atomic number. At room temperature, fluorine and chlorine are gases, bromine is liquid, and iodine is a solid. In temperate climates, only two elements are liquid at room temperature, bromine and mercury. (In very hot climates caesium and thallium are also liquid.) At atmospheric pressure  $\text{I}_2$  solid sublimes without melting.

Table 16.6 Melting and boiling points

	Melting point (°C)	Boiling point (°C)
$\text{F}_2$	-219	-188
$\text{Cl}_2$	-101	-34
$\text{Br}_2$	-7	60
$\text{I}_2$	114	185

Table 16.7 Bond energy and bond lengths of  $X_2$ 

	Bond energy (free energy of dissociation) (kJ mol <sup>-1</sup> )	Bond length $\lambda$ , (Å)
F	126	1.43
Cl	210	1.99
Br	158	2.28
I	118	2.66

### BOND ENERGY IN $X_2$ MOLECULE

The elements all form diatomic molecules. It would be expected that the bond energy in the  $X_2$  molecules would decrease as the atoms become larger, since increased size results in less effective overlap of orbitals.  $Cl_2$ ,  $Br_2$  and  $I_2$  show the expected trend (Table 16.7), but the bond energy for  $F_2$  does not fit the expected trend.

The bond energy in  $F_2$  is abnormally low (126 kJ mol<sup>-1</sup>) and this is largely responsible for its very high reactivity. (Other elements in the first row of the periodic table also have weaker bonds than the elements which follow in their respective groups. For example in Group 15 the N—N bond in hydrazine is weaker than P—P, and in Group 16 the O—O bond in peroxides is weaker than S—S.) Two different explanations have been suggested for the low bond energy.

1. Mulliken postulated that in  $Cl_2$ ,  $Br_2$  and  $I_2$  some *pd* hybridization occurred allowing some multiple bonding. This would make the bonds stronger than in  $F_2$  in which there are no *d* orbitals available.
2. Coulson suggested that since fluorine atoms are small the F—F distance is also small (1.48 Å) and hence internuclear repulsion is appreciable. The large electron—electron repulsions between the lone pairs of electrons on the two fluorine atoms weaken the bond.

It seems unnecessary to invoke multiple bonding to explain these facts, and the simpler Coulson explanation is widely accepted.

### OXIDIZING POWER

Electron affinity is the tendency of the atoms to gain electrons. This reaches a maximum at chlorine (See Table 16.4.) Oxidation may be regarded as the removal of electrons, so that an oxidizing agent gains electrons. Thus the halogens act as oxidizing agents. The strength of an oxidizing agent (that is, its oxidation potential) depends on several energy terms and is best represented by a Born–Haber type of energy cycle (Figure 16.3).

The oxidation potential is the energy change between the element in its standard state, and in its hydrated ions. Thus for iodine the change is from




Figure 16.3 Energy cycle showing the oxidation potentials of the halogens. (Oxidation potential is used here in preference to reduction potential to stress that the halogens are strong oxidising agents. Note  $\Delta G^\circ = -nFE^\circ$ )

$\frac{1}{2}I_{2(solid)}$  to  $I_{(hydrated)}^-$ . Thus the oxidation potential is equal to the sum of the energy put in as the enthalpies of fusion, vaporization and dissociation, less the energy evolved as the electron affinity and enthalpy of hydration.

In a similar cycle the oxidation potential for bromine can be calculated for the change from  $\frac{1}{2}Br_{2(liquid)}$  to  $Br_{(hydrated)}^-$ . (Note that since in its standard state bromine is liquid, the enthalpy of fusion must be omitted. Similarly in calculating the oxidation potential for chlorine and fluorine,

Table 16.8 Enthalpy ( $\Delta H^\circ$ ) values for  $\frac{1}{2}X_2 \rightarrow X_{(hydrated)}$  (all values in  $\text{kJ mol}^{-1}$ )

	$\frac{1}{2}$ Enthalpy of fusion	$\frac{1}{2}$ Enthalpy of vaporization	$\frac{1}{2}$ Enthalpy of dissociation	Electron affinity	Enthalpy of hydration	Sum of $\Delta H^\circ$
$F_2$	—	—	+159/2	—333	—513	—836
$Cl_2$	—	—	+243/2	—349	—370	—597.5
$Br_2$	—	+30/2	+193/2	—325	—339	—552.5
$I_2$	+15/2	+42/2	+151/2	—296	—274	—466

since they are gases both the enthalpies of fusion and vaporization must be omitted )


Chlorine has the highest electron affinity, so gaseous Cl atoms accept electrons most readily. However, Cl is *not* the strongest oxidizing agent. Table 16.8 shows that, summing all the energy terms in the cycle, fluorine has the most negative  $\Delta H^\circ$  value. Since the difference between  $\Delta G^\circ$  and  $\Delta H^\circ$  is not significant, it follows that fluorine accepts electrons more readily than chlorine, so fluorine is the strongest oxidizing agent. There are two main reasons for this change of order:

1.  $F_2$  has a low enthalpy of dissociation (arising from the weakness of the F—F bond)
2.  $F_2$  has a high free energy of hydration (arising from the smaller size of the  $F^-$  ion)


Fluorine is a very strong oxidizing agent, and it will replace  $Cl^-$  both in solution and also when dry. Similarly, chlorine gas will displace  $Br^-$  from solution. (This is the basis of the commercial extraction of bromine from sea water.) In general any halogen of low atomic number will oxidize halide ions of higher atomic number.

### REACTION WITH WATER

The halogens are all soluble in water, but the extent to which they react with the water, and the reaction mechanism that is followed, vary. Fluorine is so strong an oxidizing agent that it oxidizes water to dioxygen. The reaction is spontaneous and strongly exothermic. (The free energy change is large and negative.) Oxidation may be regarded as the removal of electrons, so that an oxidizing agent gains electrons. Thus the fluorine atoms are reduced to fluoride ions:



A similar reaction between chlorine and water is thermodynamically possible, but the reaction is very slow because the energy of activation is high:



With chlorine an alternative disproportionation reaction occurs rapidly:





Table 16.9 Concentrations in saturated aqueous solutions at 25°C

	Solubility (mol l <sup>-1</sup> )	Concentration X <sub>2</sub> (hydrated) (mol l <sup>-1</sup> )	Concentration HOX (mol l <sup>-1</sup> )
Cl <sub>2</sub>	0.091	0.061	0.030
Br <sub>2</sub>	0.21	0.21	1.1 × 10 <sup>-3</sup>
I <sub>2</sub>	0.0013	0.0013	6.4 × 10 <sup>-6</sup>

A similar disproportionation reaction occurs to a very limited extent with  $\text{Br}_2$  and  $\text{I}_2$ . Thus a saturated aqueous solution of  $\text{Cl}_2$  at  $25^\circ\text{C}$  contains about two thirds hydrated  $\text{X}_2$  and one third  $\text{OCl}^-$ . Solutions of  $\text{Br}_2$  and  $\text{I}_2$  contain only a very small amount of  $\text{OBr}^-$ , and a negligible amount of  $\text{OI}^-$ , respectively.


Iodine is an even weaker oxidizing agent. The free energy change is positive, which shows that energy must be supplied to make it oxidize water.



It follows that for the reverse reaction  $\Delta G^\circ$  would be  $-105 \text{ kJ mol}^{-1}$ , so the reverse reaction should occur spontaneously. This is the case. Atmospheric dioxygen oxidizes iodide ions to iodine. At the end point of an iodine titration with sodium thiosulphate, the iodine originally present is all converted to iodide ions. Thus the bluish colour produced by the starch indicator with iodine disappears, and the solution becomes colourless.



If the titration flask is allowed to stand for two or three minutes, the indicator turns blue again. This is because some atmospheric oxidation has taken place, forming  $\text{I}_2$ , which reacts with the starch to give the blue colour again.



The end point of the titration is usually taken as being when the colour disappears *and the solution remains colourless for half a minute*.

## REACTIVITY OF THE ELEMENTS

Fluorine is the most reactive of all the elements in the periodic table. It reacts with all the other elements except the lighter noble gases He, Ne and Ar. It reacts with xenon under mild conditions to form xenon fluorides. (See Chapter 17.) Reactions with many elements are vigorous, and often explosive. In the massive form a few metals such as Cu, Ni, Fe and Al acquire a protective fluoride coating. However, if these metals are in powdered form (with a large surface area), or if the reaction mixture is heated, then the reaction is vigorous. The reactivity of the other halogens decreases in the order  $\text{Cl} > \text{Br} > \text{I}$ . Chlorine and bromine react with most of the elements, though less vigorously than does fluorine. Iodine is less reactive and does not combine with some elements such as S and Se. Fluorine and chlorine often oxidize elements further than do bromine and iodine, by this means bringing out higher valencies, for example in  $\text{PBr}_3$  and  $\text{PCl}_5$ , and in  $\text{S}_2\text{Br}_2$ ,  $\text{SCl}_2$  and  $\text{SF}_6$ .

The great reactivity of fluorine is attributable to two factors:

1. The low dissociation energy of the  $\text{F}-\text{F}$  bond (which results in a low activation energy for the reaction).
2. The very strong bonds which are formed.

Table 16.10 Some bond energies of halogen compounds (all values in  $\text{kJ mol}^{-1}$ )

	HX	BX <sub>3</sub>	AlX <sub>3</sub>	CX <sub>4</sub>	NX <sub>3</sub>	X <sub>2</sub>
F	566	645	582	439	272	159
Cl	431	444	427	347	201	243
Br	366	368	360	276	243	193
I	299	272	285	238	*	151

\* Unstable and explosive

Both of these properties arise from the small size of fluorine. The weak F—F bond arises because of repulsion between the lone pairs of electrons on the two atoms. Strong bonds arise because of the high coordination number and high lattice energy.

Some bond energies are shown in Table 16.10. These explain why the halogens form very strong bonds. Many are stronger than the C—C bond, which is itself regarded as a very strong bond (The C—C bond energy is  $347 \text{ kJ mol}^{-1}$ ).

Table 16.11 Some reactions of the halogens

Reaction	Comment
$2\text{F}_2 + 2\text{H}_2\text{O} \rightarrow 4\text{H}^+ + 4\text{F}^- + \text{O}_2$	Vigorous reaction with F
$2\text{I}_2 + 2\text{H}_2\text{O} \leftarrow 4\text{H}^+ + 4\text{X}^- + \text{O}_2$	I reaction in reverse direction
$\text{X}_2 + \text{H}_2\text{O} \rightarrow \text{H}^+ + \text{X}^- + \text{HOX}$	Cl > Br > I (F not at all)
$\text{X}_2 + \text{H}_2 \rightarrow 2\text{HX}$	All the halogens
$n\text{X}_2 + 2\text{M} \rightarrow 2\text{MX}_n$	Most metals form halides F the most vigorous
$\text{X}_2 + \text{CO} \rightarrow \text{COX}_2$	Cl and Br form carbonyl halides
$3\text{X}_2 + 2\text{P} \rightarrow \text{PX}_3$	All the halogens form trihalides
$5\text{X}_2 + 2\text{P} \rightarrow \text{PX}_5$	As, Sb and Bi also form trihalides F, Cl and Br form pentahalides AsF <sub>5</sub> , SbF <sub>5</sub> , BiF <sub>5</sub> , SbCl <sub>5</sub>
$\text{X}_2 + 2\text{S} \rightarrow \text{S}_2\text{X}_2$	Cl and Br
$2\text{Cl}_2 + \text{S} \rightarrow \text{SCl}_4$	Cl only
$3\text{F}_2 + \text{S} \rightarrow \text{SF}_6$	F only
$\text{X}_2 + \text{H}_2\text{S} \rightarrow 2\text{HX} + \text{S}$	All the halogens oxidize S <sup>2-</sup> to S
$\text{X}_2 + \text{SO}_2 \rightarrow \text{SO}_2\text{X}_2$	F and Cl
$3\text{X}_2 + 8\text{NH}_3 \rightarrow \text{N}_2 + 6\text{NH}_4\text{X}$	F, Cl and Br
$\text{X}_2 + \text{X}'_2 \rightarrow 2\text{XX}'$	Interhalogen compounds formed higher interhalogen compounds
$\text{X}_2 + \text{X}'\text{X} \rightarrow \text{X}'\text{X}_3$	






## HYDROGEN HALIDES HX

It is usual to refer to pure anhydrous HX compounds as hydrogen halides, and their aqueous solutions as hydrohalic acids or simply halogen acids.

The halogens all react with hydrogen and form hydrides HX, though except for HCl this is not the usual way of preparing them. Reactivity towards hydrogen decreases down the group. Hydrogen and fluorine react violently. The reaction with chlorine is slow in the dark, faster in daylight, and explosive in sunlight. The reaction with iodine is slow at room temperature.


### HF

Industrially HF is made by heating  $\text{CaF}_2$  with strong  $\text{H}_2\text{SO}_4$ . The reaction is endothermic: hence the need for heating. It is important that  $\text{SiO}_2$  impurities are removed from the  $\text{CaF}_2$ , as otherwise they consume much of the HF produced.




The HF is purified by successive washing, cooling and fractional distillation, giving a product that is 99.95% pure. World production of HF was 1.5 million tonnes in 1994, with over 80 000 tonnes a year being produced in the UK.

Gaseous HF is very toxic, and should be handled only in a good fume cupboard. Solutions of HF are called hydrofluoric acid, and this is very corrosive. Hydrofluoric acid is normally handled in metal apparatus made of copper or Monel, because hydrofluoric acid attacks glass with the formation of fluorosilicate ions  $[\text{SiF}_6]^{2-}$ .




Surprisingly little corrosion occurs at concentrations above 80%. The main uses of HF are as follows:

1. Two thirds are used to make chlorofluorocarbons (Freons). These are sometimes called CFCs. They are used as refrigerating fluids and as the propellant in aerosols. The use of CFCs is being phased out because they damage the ozone layer in the upper atmosphere. (See Chapter 13, under 'Tetrahalides'.)




- About 14% is used to make  $\text{AlF}_3$  and synthetic cryolite used in the electrolytic extraction of aluminium (See Chapter 3)
- About 2% is used for uranium processing (through intermediates  $\text{UF}_4$  and  $\text{UF}_6$ )
- About 4% is used in the anhydrous form as an alkylation catalyst in the petrochemical industry, for making long chain alkylbenzene compounds. These are then converted into alkylbenzene sulphonates and used as detergents
- Aqueous  $\text{HF}$  is used for pickling steel (about 4%) and for etching glass, making herbicides and many metal fluorides and also  $\text{BF}_3$



### HCl


HCl is produced on a very large scale. World production was 12.3 million tonnes in 1991 (USA 24%, China 21%, Germany and Japan 7% each, France and Italy 5% each, and Belgium 3%). There are several different preparative methods.

- At one time HCl was made exclusively by the 'salt cake' method. In this method, concentrated  $\text{H}_2\text{SO}_4$  was added to rock salt ( $\text{NaCl}$ ). The reaction was endothermic, and was performed in two stages at different temperatures. The first of the reactions was carried out at about  $150^\circ\text{C}$ . The solid  $\text{NaCl}$  reacted with  $\text{H}_2\text{SO}_4$  and became coated with insoluble  $\text{NaHSO}_4$ . This prevented further reaction, and accounts for the name 'salt cake'. In the second stage, the mixture was heated to about  $550^\circ\text{C}$ , when further reaction with  $\text{H}_2\text{SO}_4$  occurred and  $\text{Na}_2\text{SO}_4$  was formed. This by-product was sold, mostly for paper making (Kraft process).



- Large amounts of impure HCl have become available in recent years as a by-product from the heavy organic chemical industry. For example, HCl is produced in the conversion of 1,2 dichloroethane  $\text{CH}_2\text{Cl}-\text{CH}_2\text{Cl}$  to vinyl chloride  $\text{CH}_2=\text{CHCl}$ , and in the manufacture of chlorinated ethanes and chlorinated fluorocarbons. This is now the largest source of HCl.
- High purity HCl is made by direct combination of the elements. A gaseous mixture of  $\text{H}_2$  and  $\text{Cl}_2$  is explosive. However, the reaction proceeds quietly if the gases are burnt in a hydrogen-chlorine flame in a special combustion chamber. The process is strongly exothermic.
- HCl is conveniently made in the laboratory by treating  $\text{NH}_4\text{Cl}$  with concentrated  $\text{H}_2\text{SO}_4$ .  $\text{NH}_4\text{Cl}$  costs more than  $\text{NaCl}$  (which was used in the 'salt cake' process). However,  $\text{NH}_4\text{Cl}$  is preferred because

$\text{NH}_4\text{HSO}_4$  is soluble, and the reaction does not stop at the halfway stage.




Hydrogen chloride gas is very soluble in water. Aqueous solutions of HCl are sold as *hydrochloric acid*. A saturated solution at 20°C contains 42% HCl by weight, and 'concentrated' acid normally contains about 38% HCl by weight (approx. 12M). Pure hydrochloric acid is colourless, but technical grades are sometimes yellow because of contamination by Fe(III). The largest use is for 'pickling' metals, that is removing oxide layers from the surface. It is also used to make metal chlorides, in the manufacture of dyestuffs, and in the sugar industry.




Gaseous HCl is conveniently prepared in the laboratory from concentrated HCl and concentrated  $\text{H}_2\text{SO}_4$ .

### HBr and HI

HBr and HI are made by the reaction of concentrated phosphoric acid  $\text{H}_3\text{PO}_4$  on metal bromides or iodides, in a similar reaction to the 'salt cake' process for HCl. Note that a non-oxidizing acid such as phosphoric acid must be used. Concentrated  $\text{H}_2\text{SO}_4$  is a strong oxidizing agent and would oxidize HBr to  $\text{Br}_2$  and HI to  $\text{I}_2$ .



The usual laboratory preparation involves reducing bromine or iodine with red phosphorus in water. Thus HBr is made by adding bromine to a mixture of red phosphorus and water. For HI, water is added to a mixture of phosphorus and iodine.



HF is only just liquid at room temperature (b.p. 19.9°C), and HCl to HBr and HI are gases. The boiling points increase regularly from HCl,

Table 16.12 Some properties of HX compounds

	Melting point (°C)	Boiling point (°C)	Density (g cm <sup>-3</sup> )	pK <sub>a</sub> values	Composition of azeotrope (weight %)
HF	-83.1	19.9	0.99	3.2	35.37
HCl	-114.2	-85.0	1.19	-7	20.24
HBr	-86.9	-66.7	2.16	-9	47.0
HI	-50.8	-35.4	2.80	-10	57.0





Figure 16.4 Hydrogen bonded chain in solid HF

HBr to HI, but the value for HF is completely out of line with the others

The unexpectedly high boiling point of HF arises because of the hydrogen bonds formed between the F atom of one molecule and the H atom of another molecule. This links the molecules together as  $(\text{HF})_n$ , and they form zigzag chains in both the liquid and the solid. Some hydrogen bonding also occurs in the gas, which consists of a mixture of cyclic  $(\text{HF})_6$  polymers, dimeric  $(\text{HF})_2$ , and monomeric HF. HCl, HBr and HI are not hydrogen bonded in the gas and liquid, though HCl and HBr are weakly hydrogen bonded in the solid.

Hydrogen bonds are generally weak ( $5\text{--}35\text{ kJ mol}^{-1}$ ) compared with normal covalent bonds ( $\text{C—C } 347\text{ kJ mol}^{-1}$ ), but their effect is highly significant. The most electronegative elements fluorine and oxygen (and to a lesser extent chlorine) form the strongest hydrogen bonds. (The bond energy of the hydrogen bond in  $\text{F—H} \cdots \text{F}$  is  $29\text{ kJ mol}^{-1}$  in  $\text{HF}_{(g)}$ .)


In the gaseous state the hydrides are essentially covalent. However, in aqueous solutions they ionize.  $\text{H}^+$  are not produced since the proton is transferred from HCl to  $\text{H}_2\text{O}$ , thus giving  $[\text{H}_3\text{O}]^+$ . HCl, HBr and HI ionize almost completely and are therefore strong acids. HF only ionizes slightly and is therefore a weak acid.



The aqueous solutions form azeotropic mixtures with maximum boiling points, because of a negative deviation from Raoult's law. Azeotropic mixtures are sometimes used as standards for volumetric analysis, because the azeotrope always has the same composition.

Though HCl, HBr and HI completely ionize in water, the degree of ionization is much less in poorer ionizing solvents such as anhydrous acetic acid. HCl ionizes less than HI in glacial acetic acid as solvent. Thus in acetic acid, HI is the strongest acid, followed by HBr and HCl, and HF is the weakest.

It is at first paradoxical that HF is the weakest acid in water, since HF has a greater electronegativity difference than the other hydrides and therefore has more ionic character. However, acidic strength is the tendency of hydrated molecules to form hydrogen ions.



This may be represented in stages: dissociation, ionization and hydration in an energy cycle.




Figure 16.5 Energy cycle showing the acid strengths of the halogens.

The acid strength is equal to the sum of all the energy terms round the energy cycle in Figure 16.5.

$$\begin{aligned} \text{acid strength} = & \text{enthalpy of dehydration} \\ & + \text{enthalpy of dissociation} \\ & + \text{ionization energy of } H^+ \\ & + \text{electron affinity } X^- \\ & + \text{enthalpy of hydration of } H^+ \text{ and } X^- \end{aligned}$$

The factors which make HF the weakest halogen acid in water become apparent if the various thermodynamic terms are examined in more detail. The dissociation constant  $k$  for the change




Table 16.13 Energy cycle (All values in  $\text{kJ mol}^{-1}$ )

	Enthalpy dehydration	Enthalpy dissociation	Ionization energy $\text{H} \rightarrow \text{H}^+$	Electron affinity of X	Enthalpy hydration		Total $\Delta H$	$T\Delta S$	$\Delta G =$ $(\Delta H - T\Delta S)$
					$\text{H}^+$	X			
HF	48	574	1311	-338	-1091	-513	-18	51	-69
HCl	18	428	1311	-355	-1091	-370	-68	56	-124
HBr	21	363	1311	-331	-1091	-339	-75	59	-134
HI	23	295	1311	-302	-1091	-394	-167	62	-229

is given by the equation

$$\Delta G^\circ = -RT \ln k$$

(where  $\Delta G^\circ$  is the Gibbs standard free energy  $R$  the gas constant and  $T$  the absolute temperature) However  $\Delta G$  depends on the change in enthalpy  $\Delta H$  and the change in entropy  $\Delta S$

$$\Delta G = \Delta H - T\Delta S$$

Table 16.13 shows the enthalpy changes ( $\Delta H$ ) for the various stages in the above energy cycle

Consider first the total enthalpy change  $\Delta H$  for the dissociation of  $\text{HX}_{(\text{hydrated})}$  into  $\text{H}^+_{(\text{hydrated})}$  and  $\text{X}^-_{(\text{hydrated})}$ . The  $\Delta H$  values for the various halogen acids are all negative which means that energy is evolved in the process so the change is thermodynamically possible. However the value for HF is small compared with the values for HCl, HBr and HI. Thus HF is only slightly exothermic in aqueous solution whereas the others evolve a considerable amount of heat.

The low total  $\Delta H$  value for HF is the result of several factors

- 1 The enthalpies of dissociation show that the H—F bond is much stronger than the H—Cl, H—Br or H—I bonds. Thus the dissociation energy of HF is nearly twice that required to dissociate HI. (The strength of the HF bond is also shown by the short bond length of  $1.0 \text{ \AA}$  compared with  $1.7 \text{ \AA}$  in HI.)
- 2 The enthalpy of dehydration for the step  $\text{HX}_{(\text{hydrated})} \rightarrow \text{HX}_{(\text{gas})}$  is much higher for HF than for the others. This is because of the strong hydrogen bonding which occurs in aqueous HF solutions.
- 3 The unexpectedly low value for the electron affinity of  $\text{F}^-$  also contributes and though the enthalpy of hydration of  $\text{F}^-$  is very high it is not enough to offset these other terms.

If allowance is made for the  $T\Delta S$  term the  $\Delta H$  values can be converted into corresponding  $\Delta G$  values. From these the dissociation constants are obtained: HF  $k = 10^{-3}$ , HCl  $k = 10^8$ , HBr  $k = 10^{10}$  and HI  $k = 10^{11}$ .

The dissociation constants show quite clearly that HF is only very slightly

ionized in water, and is therefore a weak acid. In a similar way, the others are almost totally dissociated, and are therefore strong acids.

Liquid HF has been used as a non-aqueous solvent. It undergoes self-ionization:



Acid-base reactions occur in this solvent system. However, the solvent itself has a very strong tendency to donate protons. Thus when the familiar mineral acids  $\text{HNO}_3$ ,  $\text{H}_2\text{SO}_4$  and  $\text{HCl}$  are dissolved in HF, the mineral acids are forced to accept protons from the HF. Thus the so-called mineral acids are actually behaving as bases *in this solvent*. The very strong proton donating powers of HF mean that very few substances act as acids in HF. Perchloric acid is an exception, and it does behave as an acid. The only other known acids in liquid HF are fluoride acceptors such as  $\text{SbF}_5$ ,  $\text{NbF}_5$ ,  $\text{AsF}_5$  and  $\text{BF}_3$ . Many compounds react with HF, thus limiting its usefulness as a solvent. It is a useful medium for preparing fluoro complexes such as  $[\text{SbF}_6]^-$ , and fluorides.


## HALIDES

### Ionic halides

Most halides where the metal has an oxidation state of (+I), (+II), or (+III) are ionic. This includes Group 1, Group 2 (except Be), the lanthanides, and *some* of the transition metals. Most ionic halides are soluble in water, giving hydrated metal ions and halide ions. A few are insoluble:  $\text{LiF}$ ,  $\text{CaF}_2$ ,  $\text{SrF}_2$ ,  $\text{BaF}_2$ , and the chlorides, bromides and iodides of  $\text{Ag}(+I)$ ,  $\text{Cu}(+I)$ ,  $\text{Hg}(+I)$  and  $\text{Pb}(+II)$ . The solubilities usually increase from  $\text{F}^-$  to  $\text{Br}^-$  to  $\text{Cl}^-$  to  $\text{I}^-$  (provided that they are all ionic), because the lattice energy decreases as the ionic radii increase.

### Molecular (covalent) halides

Among the metals which show variable valency, the highest oxidation state is usually found with the fluorides. Thus osmium forms  $\text{OsF}_6$ , but only  $\text{OsCl}_4$ ,  $\text{OsBr}_4$  and  $\text{OsI}_4$ . High oxidation states are covalent. For a metal with variable oxidation states, the higher oxidation states will be covalent and the lower ones ionic. For example,  $\text{UF}_6$  is covalent and gaseous, whereas  $\text{UF}_4$  is an ionic solid. Similarly  $\text{PbCl}_4$  is covalent and  $\text{PbCl}_2$  is ionic. Most of the more electronegative elements also form covalent halides, sometimes called molecular halides. A large number of these are hydrolysed quite readily by water:



Sometimes when the maximum covalency is obtained the halides are inert to water. Thus  $\text{CCl}_4$  and  $\text{SF}_6$  are stable. This is because of kinetic rather than thermodynamic factors and  $\text{CCl}_4$  does hydrolyse with superheated steam to form phosgene  $\text{COCl}_2$ . Molecular halides are usually gases or volatile liquids. This is because there are strong bonds within the molecule but only weak van der Waals forces holding the molecules together. A number of fluorides show multiple bonding when the central atom has suitable vacant orbitals. This contributes to the high strength and shortness of many bonds of fluorine ( $\text{B}-\text{F}$   $\text{C}-\text{F}$   $\text{N}-\text{F}$  and  $\text{P}-\text{F}$ ).

### Bridging halides




Halide bridges are sometimes formed between two atoms (Less commonly they are formed between three atoms). Thus  $\text{AlCl}_3$  forms a dimeric structure whereas  $\text{BeF}_2$  and  $\text{BeCl}_2$  form infinite chains. The bridges are depicted as the halogen forming one normal covalent bond and donating a lone pair of electrons to form a second (coordinate) bond. Both bonds are identical. The bridge may be described in molecular orbital terms as a three centre four electron bond. Halogen bridges involving chlorine and bromine are typically bent but those involving fluorine may be either bent or linear. Several pentafluorides such as  $\text{NbF}_5$  and  $\text{TaF}_5$  form cyclic tetramers with linear bridges.

### Preparation of anhydrous halides

There are several general methods for making anhydrous halides.

#### *Direct reaction of the elements*


Most metals react vigorously with  $\text{F}_2$  and give fluorides in the highest oxidation states. Some non metals such as P and S explode. Elevated temperatures are usually required to prepare chlorides, bromides and iodides.



Reactions are easier in a solvent such as tetrahydrofuran though the products are often solvated.

#### *Reacting the oxide with carbon and the halogen*




It is assumed that the carbon first reduces the oxide to the metal followed by reaction of the metal with the halogen.








### Reaction of metal with anhydrous HX

Many metals will react with HF, HCl, HBr or HI gases.





### Reaction of oxides with halogen compounds

Heating halogen compounds such as  $\text{NH}_4\text{Cl}$ ,  $\text{CCl}_4$ ,  $\text{ClF}_3$ ,  $\text{BrF}_3$ ,  $\text{S}_2\text{Cl}_2$  or  $\text{SOCl}_2$  with oxides often gives halides.




### Halogen exchange

Many halides will react either with the halogens, or with excess of another halide and replace one halogen atom by another. Thus several metal fluorides such as  $\text{AgF}_2$ ,  $\text{ZnF}_2$ ,  $\text{CoF}_3$ ,  $\text{AsF}_3$ ,  $\text{SbF}_3$  and  $\text{SbF}_5$  can be used to make fluorides, and also HF.





Chlorides may be converted to iodides by treatment with KI in acetone. Similarly KBr can be used for bromides.



### Dehydrating hydrated halides

Hydrated halides may be prepared in a variety of ways, such as dissolving carbonates, oxides or metals in the appropriate halogen acid. Evaporation gives hydrated halides. Some of these may be dehydrated simply by heating, or by heating in a vacuum, but oxohalides are often produced. Chlorides may be dehydrated by distilling with thionyl chloride. Other halides may be dehydrated by treatment with 2,2-dimethoxypropane.



## HALOGEN OXIDES

The compounds with oxygen probably show greater differences between the different halogens than any other class of compound. Differences

Table 16 14 Compounds of the halogens with oxygen (and their oxidation states)


Oxidation state	(-I) (+I)	(+IV)	(+V)	(+VI)	(+VIII)	Others
Fluorides	OF <sub>2</sub> (-I) O <sub>2</sub> F <sub>2</sub> (-I)					O <sub>4</sub> F <sub>2</sub>
Oxides	Cl <sub>2</sub> O(+I) Br <sub>2</sub> O(+I)	ClO <sub>2</sub> BrO <sub>2</sub>		Cl O <sub>6</sub> ClO <sub>3</sub>	Cl <sub>2</sub> O <sub>7</sub>	ClClO <sub>4</sub> I <sub>4</sub> O <sub>9</sub> I <sub>2</sub> O <sub>4</sub>
			I <sub>2</sub> O <sub>5</sub>			

between F and the others arise for the usual reasons (small size, lack of *d* orbitals and high electronegativity). In addition oxygen is less electronegative than F, but more electronegative than Cl, Br and I. Thus binary compounds of F and O are fluorides of oxygen rather than oxides of fluorine. The other halogens are less electronegative than oxygen and thus form oxides. There is only a small difference in electronegativity between the halogens and oxygen, so the bonds are largely covalent. Rather surprisingly I<sub>2</sub>O<sub>4</sub> and I<sub>4</sub>O<sub>9</sub> are stable and ionic.

Most of the halogen oxides are unstable, and tend to explode when subjected to shock, or sometimes even when exposed to light. The iodine oxides are the most stable, then the chlorine oxides, but the bromine oxides all decompose below room temperature. The higher oxidation states are more stable than the lower states. Of the compounds shown in Table 16 14, ClO<sub>2</sub>, Cl<sub>2</sub>O, I<sub>2</sub>O<sub>5</sub> and OF<sub>2</sub> are the most important.

### OF<sub>2</sub> Oxygen difluoride

OF<sub>2</sub> is a pale yellow gas, formed by passing F<sub>2</sub> into dilute (2%) NaOH




OF<sub>2</sub> is a strong oxidizing agent, and has been used as a rocket fuel. It reacts vigorously with metals, S, P and the halogens, giving fluorides and oxides. It dissolves in water and gives a neutral solution, so it is not an acid anhydride. With NaOH it gives fluoride ions and dioxygen.

### O<sub>2</sub>F<sub>2</sub> Dioxygen difluoride

O<sub>2</sub>F<sub>2</sub> is an unstable orange-yellow solid and is a violent oxidizing and fluorinating agent. It is formed by passing an electric discharge through a mixture of F<sub>2</sub> and O<sub>2</sub> at very low pressure and at liquid air temperature. It decomposes at -95°C. Its structure is similar to that of H<sub>2</sub>O<sub>2</sub>, except that the O—O bond length of 1.22 Å is much shorter than the O—O distance of 1.48 Å in H<sub>2</sub>O<sub>2</sub>. The O—F bond lengths are 1.58 Å, which is much longer than in OF<sub>2</sub>. O<sub>4</sub>F<sub>2</sub> is made in a similar way, and apparently contains a chain of four oxygen atoms. O<sub>5</sub>F<sub>2</sub> and O<sub>6</sub>F<sub>2</sub> have been reported.

### Cl<sub>2</sub>O Dichlorine monoxide


Cl<sub>2</sub>O is a yellow-brown gas. It is commercially important. Both laboratory and commercial preparations are by heating freshly precipitated (yellow) mercuric oxide with the halogen gas diluted with dry air.




Cl<sub>2</sub>O explodes in the presence of reducing agents, or NH<sub>3</sub>, or on heating.



Cl<sub>2</sub>O gas is very soluble in water (144 g Cl<sub>2</sub>O dissolves in 100 g H<sub>2</sub>O at -9°C), forming hypochlorous acid, and the two are in equilibrium.




Cl<sub>2</sub>O dissolves in NaOH solution, forming sodium hypochlorite.




Most of the Cl<sub>2</sub>O produced is used to make hypochlorites. NaOCl is sold in aqueous solution. Ca(OCl)<sub>2</sub> is a solid. An impure form mixed with Ca(OH)<sub>2</sub> and CaCl<sub>2</sub> is sold as 'bleaching powder'. The latter is also made by passing Cl<sub>2</sub> into Ca(OH)<sub>2</sub>. These are used to bleach wood pulp and fabrics, and as disinfectants. Some Cl<sub>2</sub>O is used to make chlorinated solvents.

The structures of OF<sub>2</sub>, Cl<sub>2</sub>O and Br<sub>2</sub>O are all related to a tetrahedron with two positions occupied by lone pairs of electrons.

Electronic structure of oxygen atom in its ground state



Electronic structure of oxygen atom having gained two electrons by forming bonds to two halogen atoms



four electron pairs – tetrahedral  
with two positions occupied by lone pairs

Repulsion between the lone pairs reduces the bond angle in F<sub>2</sub>O from the tetrahedral angle of 109°28' to 103° (Figure 16.6). In Cl<sub>2</sub>O (and presumably Br<sub>2</sub>O) the bond angle is increased because of steric crowding of the larger halogen atoms.





Figure 16.6 Bond angles in F<sub>2</sub>O, Cl<sub>2</sub>O and Br<sub>2</sub>O.


**ClO<sub>2</sub> Chlorine dioxide**

ClO<sub>2</sub> is a yellow gas which condenses to a deep red liquid, b.p. 11°C. In spite of its high reactivity (or perhaps because of this) ClO<sub>2</sub> is of commercial importance, and is the most important of the oxides. ClO<sub>2</sub> is a powerful oxidizing and chlorinating agent. Large quantities are used for bleaching wood pulp and cellulose, and for purifying drinking water. It is 30 times as effective as chlorine in bleaching flour (to make white bread).


ClO<sub>2</sub> liquid explodes above -40°C. The gas detonates readily when concentrated above 50 mm Hg partial pressure. It explodes when mixed with reducing agents. Because of this, it is made in situ, and is used diluted with air or CO<sub>2</sub>. The safest laboratory preparation is from sodium chlorate and oxalic acid, as this automatically dilutes the gas with CO<sub>2</sub>.




The gas is made commercially from NaClO<sub>3</sub>. It is difficult to obtain total production figures, since for safety reasons ClO<sub>2</sub> is produced where it is used, and is always diluted (for safety). An estimate is 200 000 tonnes per year, half in the USA. A pure product is formed using SO<sub>2</sub>. Using HCl causes contamination with Cl<sub>2</sub>, but this may be unimportant or even useful for bleaching and sterilization.




ClO<sub>2</sub> dissolves in water, evolving heat, and giving a dark green solution. This decomposes very slowly in the dark, but rapidly if illuminated.



It is also used to manufacture sodium chlorite NaClO<sub>2</sub>, which is also used for bleaching textiles and paper.




Some other reactions are



The ClO<sub>2</sub> molecule is paramagnetic and contains an odd number of electrons. Odd electron molecules are generally highly reactive and ClO<sub>2</sub> is typical. Odd electron molecules often dimerize in order to pair the electrons, but ClO<sub>2</sub> does not. This is thought to be because the odd electron is delocalized. The molecule is angular with an O—Cl—O angle of 118°. The bond lengths are both 1.47 Å and are shorter than for single bonds.

### Chlorine perchlorate $\text{Cl} \cdot \text{ClO}_4$

This can be made by the following reaction at  $-45^\circ\text{C}$ .



It is less stable than  $\text{ClO}_2$ , and decomposes to  $\text{O}_2$ ,  $\text{Cl}_2$  and  $\text{Cl}_2\text{O}_6$  at room temperature.

### $\text{Cl}_2\text{O}_6$ Dichlorine hexoxide

$\text{Cl}_2\text{O}_6$  is a dark red liquid, which freezes to give a yellow solid at  $-180^\circ\text{C}$ .  $\text{Cl}_2\text{O}_6$  is in equilibrium with the monomer  $\text{ClO}_3$ , and is made from  $\text{ClO}_2$  and  $\text{O}_3$ . The structure of neither the liquid nor the solid is known. Both are diamagnetic, and so have no unpaired electrons. Possible structures are shown in Figure 16.7.





Figure 16.7 Possible structures of  $\text{Cl}_2\text{O}_6$ .

$\text{Cl}_2\text{O}_6$  is a strong oxidizing agent and explodes on contact with grease. Hydrolysis of  $\text{Cl}_2\text{O}_6$  with water or alkali gives chlorate and perchlorate. Reaction with anhydrous  $\text{HF}$  is reversible.



### Dichlorine heptoxide $\text{Cl}_2\text{O}_7$


$\text{Cl}_2\text{O}_7$  is a colourless oily liquid. It is moderately stable and is the only exothermic oxide of chlorine, but it is shock sensitive. It is made by carefully dehydrating perchloric acid with phosphorus pentoxide, or  $\text{H}_3\text{PO}_4$  at  $-10^\circ\text{C}$ , followed by distillation at  $-35^\circ\text{C}$  and a pressure of 1 mm Hg. Its structure is  $\text{O}_3\text{Cl}-\text{O}-\text{ClO}_3$ , with a bond angle of  $118^\circ 36'$  at the central oxygen. It is less reactive than the lower oxides, and does not ignite organic materials. It reacts with water, forming perchloric acid.



### Oxides of bromine

Less is known about the oxides of bromine, and they are much less important than those of chlorine.  $\text{Br}_2\text{O}$  is a dark brown liquid, prepared either by reacting  $\text{Br}_2$  gas with  $\text{HgO}$  (in the same way as  $\text{Cl}_2\text{O}$  is made), or by carefully decomposing  $\text{BrO}_2$ . It does not form  $\text{HOBr}$  to any appreciable extent by reaction with water, but with  $\text{NaOH}$  it gives  $\text{OBr}^-$ . It is a strong oxidizing agent, and oxidizes  $\text{I}_2$  to  $\text{I}_2\text{O}_5$ .

Bromine dioxide  $\text{BrO}_2$  is a pale yellow solid. It may be prepared by the action of an electric discharge on  $\text{Br}_2$  and  $\text{O}_2$  gas at low temperature and pressure, or by reacting bromine and ozone at  $-78^\circ\text{C}$ .




It is only stable below  $-40^\circ\text{C}$ . It has a similar structure to  $\text{ClO}_2$ , but it is much less important than  $\text{ClO}_2$ .  $\text{BrO}_2$  hydrolyses in alkaline solutions giving bromide and bromate.




With  $\text{I}_2$  it gives  $\text{I BrO}_2$ .

### Oxides of iodine


The oxides of iodine are much more stable than those of the other elements. Iodine pentoxide  $\text{I}_2\text{O}_5$  forms stable white hygroscopic crystals. It is formed by heating iodic acid  $\text{HIO}_3$  to  $170^\circ\text{C}$ .



It is very soluble in water, and is the anhydride of iodic acid. Because it is hygroscopic, commercial  $\text{I}_2\text{O}_5$  has usually picked up some water, and has the formula  $\text{I}_2\text{O}_5 \cdot \text{H}_2\text{O}$ .  $\text{I}_2\text{O}_5$  decomposes to  $\text{I}_2$  and  $\text{O}_2$  on heating to  $300^\circ\text{C}$ . It is also an oxidizing agent, which leads to its use analytically for the detection and estimation of carbon monoxide. It oxidizes  $\text{CO}$  to  $\text{CO}_2$  quantitatively at room temperature, liberating iodine, which can be titrated with sodium thiosulphate.



This is useful in analysing gases, such as the exhaust gas from car engines or gases from blast furnaces, for  $\text{CO}$ .  $\text{I}_2\text{O}_5$  also oxidizes  $\text{H}_2\text{S}$  to  $\text{SO}_2$  and  $\text{NO}$  to  $\text{NO}_2$ . With fluorinating agents such as  $\text{F}_2$ ,  $\text{BrF}_3$  or  $\text{SF}_6$  it forms  $\text{IF}_5$ .



The structure of  $\text{I}_2\text{O}_5$  is shown in Figure 16.8. The solid is a three-dimensional network, with strong intermolecular  $\text{I} \cdots \text{O}$  interactions linking molecules together.

The oxides  $\text{I}_2\text{O}_4$  and  $\text{I}_4\text{O}_7$  are moderately stable, though less stable than  $\text{I}_2\text{O}_5$ .  $\text{I}_2\text{O}_4$  is a yellow hygroscopic solid, which can be made as follows.








Figure 16.8 Structure of  $\text{I}_2\text{O}_5$



When heated above  $75^\circ\text{C}$  it decomposes to  $\text{I}_2\text{O}_5$ .



Dehydrating  $\text{HIO}_3$  with concentrated  $\text{H}_2\text{SO}_4$  gives  $\text{I}_2\text{O}_4$ . When heated above  $135^\circ\text{C}$  it decomposes to  $\text{I}_2\text{O}_5$ .



The structures of these oxides are not known, but  $\text{I}_2\text{O}_4$  is probably  $\text{IO}^+ \cdot \text{IO}_3^-$  and  $\text{I}_4\text{O}_9$  is probably  $\text{I}^{3+} \cdot (\text{IO}_3^-)_3$ .

## STANDARD REDUCTION POTENTIALS (VOLTS)

Acid solution (activity of $\text{H}^+ = 1$ )					
Oxidation state					
+VII	+V	+III	+I	0	-I
$\begin{array}{c} \begin{array}{ccccccc} & & & & & \frac{1}{2}\text{F}_2 & \xrightarrow{+2.87} & \text{F}^- \\ \hline \text{ClO}_4^- & \xrightarrow{+1.19} & \text{ClO}_3^- & \xrightarrow{+1.21} & \text{HClO}_2 & \xrightarrow{+1.65} & \text{HOCl} & \xrightarrow{+1.61} & \frac{1}{2}\text{Cl}_2 & \xrightarrow{+1.36} & \text{Cl}^- \\ & & & & & & & & & & \uparrow \\ & & & & & & & & & & +1.48 \\ & & & & & & & & & & \uparrow \\ & & & & & & & & & & +1.45 \\ & & & & & & & & & & \uparrow \\ & & & & & & & & & & +1.39 \\ & & & & & & & & & & \uparrow \\ & & & & & & & & & & +1.47 \\ & & & & & & & & & & \uparrow \\ & & & & & & & & & & +1.64 \\ & & & & & & & & & & \uparrow \\ & & & & & & & & & & +1.60 \end{array} \end{array}$					
$\begin{array}{c} \begin{array}{ccccccc} & & & & & \frac{1}{2}\text{Br}_{2(l)} & \xrightarrow{+1.07} & \text{Br}^- \\ \hline \text{BrO}_4^- & \xrightarrow{+1.74} & \text{BrO}_3^- & \xrightarrow{+1.47} & \text{HOBr} & \xrightarrow{+1.60} & \frac{1}{2}\text{Br}_{2(l)} & \xrightarrow{+1.07} & \text{Br}^- \\ & & & & & & & & \uparrow \\ & & & & & & & & +1.33 \\ & & & & & & & & \uparrow \\ & & & & & & & & +1.42 \\ & & & & & & & & \uparrow \\ & & & & & & & & +1.50 \\ & & & & & & & & \uparrow \\ & & & & & & & & +1.47 \end{array} \end{array}$					
$\begin{array}{c} \begin{array}{ccccccc} & & & & & \frac{1}{2}\text{I}_{2(s)} & \xrightarrow{+0.54} & \text{I}^- \\ \hline \text{IO}_4^- & \xrightarrow{+1.65} & \text{IO}_3^- & \xrightarrow{+1.34} & \text{HOI} & \xrightarrow{+1.44} & \frac{1}{2}\text{I}_{2(s)} & \xrightarrow{+0.54} & \text{I}^- \\ & & & & & & & & \uparrow \\ & & & & & & & & +0.99 \\ & & & & & & & & \uparrow \\ & & & & & & & & +1.19 \\ & & & & & & & & \uparrow \\ & & & & & & & & +1.60 \end{array} \end{array}$					

Basic solution (activity of $\text{OH}^- = 1$ )					
Oxidation state					
+VII	+V	+III	+I	0	-I
$\text{ClO}_4^-$	$\xrightarrow{+0.36}$ $\text{ClO}_3^-$	$\xrightarrow{+0.33}$ $\text{ClO}_2^*$	$\xrightarrow{+0.66}$ $\text{OCl}^-$	$\xrightarrow{+0.40}$ $\frac{1}{2}\text{Cl}_2^*$	$\xrightarrow{+1.36}$ $\text{Cl}^-$
		$\xrightarrow{+0.50}$		$\xrightarrow{+0.88}$	
$\text{BrO}_4^*$	$\xrightarrow{+0.92}$ $\text{BrO}_3^-$	$\xrightarrow{+0.54}$ $\text{OBr}^-$	$\xrightarrow{+0.46}$ $\frac{1}{2}\text{Br}_{2(l)}^*$	$\xrightarrow{+1.07}$ $\text{Br}$	
		$\xrightarrow{+0.61}$		$\xrightarrow{+0.76}$	
$\text{H}_5\text{IO}_6^{2-}$	$\xrightarrow{+0.7}$ $\text{IO}_3^-$	$\xrightarrow{+0.14}$ $\text{OI}^*$	$\xrightarrow{+0.45}$ $\frac{1}{2}\text{I}_{2(s)}$	$\xrightarrow{+0.535}$ $\text{I}^-$	
		$\xrightarrow{+0.26}$		$\xrightarrow{+0.49}$	

\* Disproportionates

## OXOACIDS

Table 16 15 The oxoacids

	HOX	HXO	HXO <sub>3</sub>	HXO <sub>4</sub>
Oxidation states of the halogens	(+I)	(+III)	(+V)	(+VII)
	HOF HOCl HOBr HOI	HClO	HClO <sub>3</sub> HBrO <sub>3</sub> HIO <sub>3</sub>	HClO <sub>4</sub> HBrO <sub>4</sub> HIO <sub>4</sub>

Four series of oxoacids are known (Table 16 15). The structures of the ions formed are shown in Figure 16 9. All these structures are based on a tetrahedron. The  $sp^3$  hybrid orbitals used for bonding form only weak  $\sigma$  bonds, because the  $s$  and  $p$  levels differ appreciably in energy. The ions are stabilized by strong  $p\pi-d\pi$  bonding between full  $2p$  orbitals on oxygen with empty  $d$  orbitals on the halogen atoms. Even so, many of the oxoacids are known only in solution or as their salts.

Fluorine has no  $d$  orbitals, and thus cannot form  $p\pi-d\pi$  bonds. For a long time it was thought that F could not form any oxoacids. It is now known that HOF can be made under special conditions, but it is very unstable. No other oxoacids of F are known.







Figure 16.9 Structures of the oxoacids.

### Hypohalous acids HOX


The hypohalous acids HOF, HOCl, HOBr and HOI are all known, and the halogen has the oxidation state (+I).

HOF is a colourless unstable gas. It was first made in 1968, using the matrix isolation technique.  $\text{F}_2$  and  $\text{H}_2\text{O}$  were trapped in an unreactive matrix of solid nitrogen. (This requires a very low temperature.) The gases were photolysed, and the HOF formed. Since this too was trapped in the solid nitrogen, it was unable to collide and react with any other molecules such as  $\text{H}_2\text{O}$ ,  $\text{F}_2$  or  $\text{O}_2$ . Thus a product was obtained. More recently HOF has been made by passing  $\text{F}_2$  over ice at  $0^\circ\text{C}$ , and removing the product into a cold trap.




HOF is unstable, and decomposes on its own to HF and  $\text{O}_2$ . It is a strong oxidizing agent and oxidizes  $\text{H}_2\text{O}$  to  $\text{H}_2\text{O}_2$  quite readily. The  $-\text{OF}$  group occurs in  $\text{F}_3\text{C}-\text{OF}$ ,  $\text{O}_2\text{N}-\text{OF}$ ,  $\text{F}_5\text{S}-\text{OF}$  and  $\text{O}_3\text{Cl}-\text{OF}$  and these are all strong oxidizing agents. HOF should be a stronger acid than HOCl.


HOCl, HOBr and HOI are not very stable, and are known only in aqueous solutions. They are very weak acids, but they are good oxidizing agents especially in acidic solutions. They can be prepared by shaking the halogen with freshly precipitated  $\text{HgO}$  in water, for example:



Hypochlorous acid is the most stable. Sodium hypochlorite  $\text{NaOCl}$  is well known, and is used extensively for bleaching cotton fabric, and as a domestic bleach (sold under various trade names: Parazone, Lanry, Domestos, Chlorox etc.). It is also used as a disinfectant and sterilizing agent.  $\text{NaOCl}$  is produced commercially by electrolysis of cold brine whilst stirring vigorously. During electrolysis hydrogen is liberated at the cathode. This increases the concentration of  $\text{OH}^-$  in the solution. The stirring mixes the  $\text{Cl}_2$  formed at the anode with the  $\text{OH}^-$  so they can react together.




The halogens  $\text{Cl}_2$ ,  $\text{Br}_2$  and  $\text{I}_2$  all dissolve to some extent in water, forming hydrated  $\text{X}_2$  molecules and  $\text{X}^-$  and  $\text{OX}^-$  ions.




In a saturated solution of chlorine, about two thirds exists as hydrated molecules, and the rest as hydrochloric and hypochlorous acids. A much smaller amount of HOBr and a negligible amount of HOI are formed by similar means.


Dissolving the halogens in NaOH can in principle be used to make all the hypohalite ions



However, the hypohalite ions tend to disproportionate, particularly in basic solutions. The rate of the disproportionation reaction increases with temperature. Thus when  $\text{Cl}_2$  dissolves in NaOH at or below room temperature, a reasonably pure solution of NaOCl and NaCl is obtained. However, in hot solutions ( $80^\circ\text{C}$ ) the sodium hypochlorite disproportionates rapidly, and a good yield of sodium chlorate is obtained




Hypobromites can only be made at about  $0^\circ\text{C}$  at temperatures above  $50^\circ\text{C}$  quantitative yields of  $\text{BrO}_3^-$  are obtained




Hypoiodites disproportionate rapidly at all temperatures, and  $\text{IO}_3^-$  is produced quantitatively

Thus the hypohalites all tend to disproportionate. The reduction potentials show that  $\text{OBr}^-$  and  $\text{OI}^-$  are unstable to disproportionation, since their reduction potentials do not decrease progressively from oxidation state (+V) to (+I) to (0). However, the standard reduction potentials suggest that  $\text{OCl}^-$  should just be stable under standard conditions




However, the values +1.65 volts and +1.61 volts are almost the same. These are standard potentials, measured under standard conditions. Differences from standard conditions of temperature and concentration change the potentials sufficiently for disproportionation to occur




### Halous acids $\text{HXO}_2$

The only halous acid known for certain is chlorous acid  $\text{HClO}_2$ . This only exists in solution. It is a weak acid, but is stronger than HOCl. The


chlorine atom exists in the oxidation state (+III).  $\text{HClO}_2$  is made by treating barium chlorite with  $\text{H}_2\text{SO}_4$ , and filtering off the  $\text{BaSO}_4$ .



Salts of  $\text{HClO}_2$  are called chlorites, and are made either from  $\text{ClO}_2$  and sodium hydroxide, or  $\text{ClO}_2$  and sodium peroxide.




Chlorites are used as bleaches. They are stable in alkaline solution even when boiled, but in acid solution they disproportionate, particularly when heated.




### Halic acids $\text{HXO}_3$

Three halic acids are known:  $\text{HClO}_3$ ,  $\text{HBrO}_3$  and  $\text{HIO}_3$ . The halogen has the oxidation state (+V).  $\text{HClO}_3$  and  $\text{HBrO}_3$  are not very stable, but are known in solution, and as salts.  $\text{HClO}_3$  and  $\text{HBrO}_3$  detonate if attempts are made to evaporate them to dryness. The main reaction is:



In contrast, iodic acid  $\text{HIO}_3$  is reasonably stable, and exists as a white solid. The halic acids all behave as strong oxidizing agents and strong acids.




$\text{HIO}_3$  can be made by oxidizing  $\text{I}_2$  with concentrated  $\text{HNO}_3$  or  $\text{O}_3$ .  $\text{HClO}_3$  and  $\text{HBrO}_3$  are made by treating the barium halates with  $\text{H}_2\text{SO}_4$ , and filtering off the  $\text{BaSO}_4$ .



Chlorates may be made in two ways:


1. Passing  $\text{Cl}_2$  into a hot solution of  $\text{NaOH}$ .
2. Electrolysing hot chloride solutions that are vigorously stirred.

Only one sixth of the chlorine is converted to  $\text{ClO}_3^-$ , which appears very inefficient. However, the  $\text{NaCl}$  produced is electrolysed again, and is thus not wasted.




Chlorates and bromates decompose on heating, but the way they decompose is complex and is not fully understood.  $\text{KClO}_3$  may decompose in two different ways, depending on the temperature.

- 1 Heating  $\text{KClO}_3$  to  $400-500^\circ\text{C}$  is the well known laboratory experiment to produce dioxygen. It also gives a trace of  $\text{Cl}_2$  or  $\text{ClO}_2$  (though this is seldom mentioned). Decomposition occurs at  $150^\circ\text{C}$  if a catalyst such as  $\text{MnO}_2$  or powdered glass is present to provide a surface from which  $\text{O}_2$  can escape.



When  $\text{Zn}(\text{ClO}_3)_2$  is heated it decomposes to  $\text{O}_2$  and  $\text{Cl}_2$



- 2 In the absence of a catalyst especially at a lower temperature,  $\text{KClO}_3$  tends to disproportionate to perchlorate and chloride




Chlorates are much more soluble than bromates and iodates. The iodates of  $\text{Ce}^{4+}$ ,  $\text{Zr}^{4+}$ ,  $\text{Hf}^{4+}$  and  $\text{Th}^{4+}$  are precipitated from 6 M  $\text{HNO}_3$  and this is a useful means of separation for these metals.

Chlorates are used to make fireworks and matches. Sodium chlorate is widely used as a powerful weedkiller. Its effects remain for some time, and it prevents growth for one growing season. Solid chlorates, bromates and iodates should be handled with care. Chlorates can explode on grinding, on heating, or if they come into contact with easily oxidized substances such as organic matter or sulphur. They are particularly dangerous in the solid form but are much safer in solution. Solid sodium chlorate has been used by terrorists in making bombs. The solid must be finely powdered (a dangerous process), and mixed intimately with something it can reduce such as sugar. Mixing is highly dangerous. Such bombs are notoriously unreliable and dangerous.

#### Perhalic acids $\text{HXO}_4$

Perchloric and periodic acids and their salts are well known. Perbromates were unknown until 1968 and are not common.

World consumption of perchlorates is about 30 000 tonnes per year.  $\text{NaClO}_4$  is made by electrolysis of aqueous  $\text{NaClO}_3$  using smooth platinum anodes in a steel container which also acts as the cathode. The platinum electrode gives a high oxygen overpotential, and thus prevents the electrolysis of water.




All other perchlorates and perchloric acid  $\text{HClO}_4$  are made from  $\text{NaClO}_4$ .


- 1  $\text{NH}_4\text{ClO}_4$  is a white solid and was formerly used as a blasting compound in mining. It is now used in the booster rockets in the Challenger Space Shuttle.  $\text{NH}_4\text{ClO}_4$  oxidizes the fuel (Al powder). A Shuttle launch uses nearly 700 tonnes of  $\text{NH}_4\text{ClO}_4$ , and this accounts for half the per

chlorates used.  $\text{NH}_4\text{ClO}_4$  will absorb sufficient ammonia to liquefy itself.


- Nearly 500 tonnes of  $\text{HClO}_4$  are used annually, mostly to make other perchlorates.  $\text{HClO}_4$  is a colourless liquid and can be made from  $\text{NH}_4\text{ClO}_4$  and dilute nitric acid, or from  $\text{NaClO}_4$  and concentrated hydrochloric acid.



In principle perchlorates could be made from the disproportionation of chlorates, but the reaction is slow and of little use.



$\text{HClO}_4$  is commercially available as 70%  $\text{HClO}_4$ , which has almost the composition of the dihydrate  $\text{HClO}_4 \cdot 2\text{H}_2\text{O}$ . It is the only oxoacid of chlorine that can be isolated in the anhydrous state. It is made by dehydrating  $\text{HClO}_4 \cdot 2\text{H}_2\text{O}$  with fuming sulphuric acid, then removing  $\text{HClO}_4$  by vacuum distillation.





$\text{HClO}_4$  is one of the strongest acids known. The anhydrous compound is a powerful oxidizing agent which explodes on contact with organic material (wood, paper, cloth, grease, rubber or chemicals), and sometimes on its own. The cold concentrated (70% aqueous) solution is a much weaker oxidizing agent. Hot concentrated solutions have been used for 'wet ashing', where all organic materials in the sample are oxidized to  $\text{CO}_2$ , leaving only the inorganic constituents for analysis. Alcohols must not be present since perchlorate esters are explosive. Often a mixture of  $\text{HClO}_4$  and  $\text{HNO}_3$  is used for wet ashing, since the  $\text{HNO}_3$  oxidizes alcohols and removes this risk.

- Magnesium perchlorate  $\text{MgClO}_4$  is used as the electrolyte in so-called 'dry batteries'. It is very hygroscopic, and is a very effective desiccant called 'anhydrone'.
- $\text{KClO}_4$  is used in fireworks and flares. Those with a bang and flash usually use  $\text{KClO}_4$ , Al and S, and those that are flares have  $\text{KClO}_4$  and Mg. A red colour is obtained by adding some  $\text{SrCO}_3$  or  $\text{Li}_2\text{CO}_3$ , and  $\text{CuCO}_3$  gives blue. Making fireworks is dangerous – do not attempt it!

Virtually all metal perchlorates, except those with the larger Group 1 ions  $\text{K}^+$ ,  $\text{Rb}^+$  and  $\text{Cs}^+$ , are soluble in water. The sparing solubility of  $\text{KClO}_4$  is used to detect potassium in qualitative analysis. (A solution of  $\text{NaClO}_4$  is added to the solution containing  $\text{K}^+$ , and  $\text{KClO}_4$  is precipitated.) The  $\text{ClO}_4^-$  ion has only a very slight tendency to form complexes with metal ions. Thus perchlorates are often used as an inert ion in the study of metal ions in aqueous solution. However, in the absence of other ligands,  $\text{ClO}_4^-$  ions may act as unidentate or bidentate ligands. The perchlorate ion is tetrahedral.



For a long time efforts to make perbromates were unsuccessful, and it

was thought that they could not exist, until traces were obtained from  $\beta$  decay of  $^{83}\text{SeO}_3^{2-}$ . They can be made from bromates by the action of powerful oxidizing agents such as  $\text{F}_2$  or  $\text{XeF}_2$ , or by electrolysis of an aqueous solution




Solid perbromates are stable.  $\text{KBrO}_4$  is stable up to  $275^\circ\text{C}$ , and is isomorphous with  $\text{KClO}_4$ .  $\text{HBrO}_4$  is stable in solution up to a concentration of 6M, but the concentrated acid is a vigorous oxidizing agent. In dilute solutions perbromates only oxidize slowly, and  $\text{Cl}^-$  is not oxidized.

Periodates can be made by oxidizing  $\text{I}_2$  or  $\text{I}^-$  in aqueous solution. Commercially they are made by oxidizing iodates in alkaline solution either with  $\text{Cl}_2$  or electrolytically




The common form of periodic acid is  $\text{HIO}_4 \cdot 2\text{H}_2\text{O}$  or  $\text{H}_5\text{IO}_6$ . This is called paraperiodic acid, and exists as white crystals which melt with decomposition at  $128.5^\circ\text{C}$ . Water is lost on heating to  $100^\circ\text{C}$  under reduced pressure, yielding periodic acid  $\text{HIO}_4$ . On strong heating this eventually decomposes losing  $\text{O}_2$  and forming  $\text{I}_2\text{O}_5$ .



Periodates are of two structural types: tetrahedral  $\text{IO}_4^-$  and octahedral  $(\text{OH})_5\text{IO}$ . In aqueous solutions at room temperature, the main ion is  $\text{IO}_4^-$ . The structures of periodates are much more complicated than this implies. A wide range of isopolyacids exist with octahedral units (based on one I and six O atoms), linked together by sharing the O atoms at two corners (that is sharing an edge of the octahedron), or sharing three corners (that is a face of the octahedron).

Chemically, periodates are important as oxidants, and they will oxidize  $\text{Mn}^{2+}$  to  $\text{MnO}_4^-$ . They are also used to oxidize organic compounds. Solutions of periodic acid are used to determine the structure of organic compounds by degradative methods.  $\text{HIO}_4$  is called a glycol splitting agent since it splits (oxidizes) 1,2 glycols into aldehydes



### Strength of the oxoacids

$\text{HClO}_4$  is an extremely strong acid, whilst  $\text{HOCl}$  is a very weak acid. The dissociation of an oxoacid involves two energy terms:

1. Breaking an  $\text{O—H}$  bond to produce a hydrogen ion and an anion.
2. Hydrating both ions.

Plainly the  $\text{ClO}_4^-$  ion is larger than the  $\text{OCl}^-$  ion, so the hydration energy of  $\text{ClO}_4^-$  is less than that for  $\text{OCl}^-$ . This would suggest that  $\text{HOCl}$  should ionize more readily than  $\text{HClO}_4$ . Since we know the reverse to be true, the reason must be the energy required to break the  $\text{O—H}$  bond.

Oxygen is more electronegative than chlorine. In the series of oxoacids  $\text{HOCl}$ ,  $\text{HClO}_2$ ,  $\text{HClO}_3$ ,  $\text{HClO}_4$ , an increasing number of oxygen atoms are bonded to the chlorine atom. The more oxygen atoms that are bonded, the more the electrons will be pulled away from the  $\text{O—H}$  bond, and the more this bond will be weakened. Thus  $\text{HClO}_4$  requires the least energy to break the  $\text{O—H}$  bond and form  $\text{H}^+$ . Hence  $\text{HClO}_4$  is the strongest acid.

In general, for any series of oxoacids, the acid with the most oxygen (that is the one with the highest oxidation number) is the most dissociated. Thus the acid strengths decrease  $\text{HClO}_4 > \text{HClO}_3 > \text{HClO}_2 > \text{HOCl}$ . In exactly the same way,  $\text{H}_2\text{SO}_4$  is a stronger acid than  $\text{H}_2\text{SO}_3$ , and  $\text{HNO}_3$  is a stronger acid than  $\text{HNO}_2$ .

### INTERHALOGEN COMPOUNDS


The halogens react with each other to form interhalogen compounds. These are divided into four types  $\text{AX}$ ,  $\text{AX}_3$ ,  $\text{AX}_5$  and  $\text{AX}_7$ .

They can all be prepared by direct reaction between the halogens, or by the action of a halogen on a lower interhalogen. The product formed depends on the conditions.

Table 16.16 Interhalogen compounds, and their physical state at  $25^\circ\text{C}$

$\text{AX}$	$\text{AX}_3$	$\text{AX}_5$	$\text{AX}_7$
$\text{ClF}(\text{g})$ colourless			
$\text{BrF}(\text{g})$ pale brown	$\text{ClF}_3(\text{g})$ colourless		
$\text{BrCl}(\text{g})$ red-brown	$\text{BrF}_3(\text{l})$ pale yellow	$\text{ClF}_5(\text{g})$ colourless	
$\text{ICl}(\text{s})$ ruby red	$(\text{ICl}_3)_2(\text{s})$ bright yellow	$\text{BrF}_5(\text{l})$ colourless	$\text{IF}_7(\text{g})$ colourless
$\text{IBr}(\text{s})$ black	$(\text{IF}_3)(\text{s})$ (unstable) yellow	$\text{IF}_5(\text{l})$ colourless	
$(\text{IF})^*$ (unstable)			



\* Disproportionates rapidly into  $\text{IF}_5$  and  $\text{I}_2$ .




There are never more than two different halogens in a molecule. The bonds are essentially covalent because of the small electronegativity difference, and the melting and boiling points increase as the difference in electronegativity increases.

The compounds formed in the AX and AX<sub>3</sub> groups are those where the electronegativity difference is not too great. The higher valencies AX<sub>5</sub> and AX<sub>7</sub> are shown by large atoms such as Br and I associated with small atoms such as F. This is because it is possible to pack more small atoms round a large one.

The interhalogens are generally more reactive than the halogens (except F<sub>2</sub>). This is because the A—X bond in interhalogens is weaker than the X—X bond in the halogens. The reactions of interhalogens are similar to those of the halogens. Hydrolysis gives halide and oxohalide ions. Note that the oxohalide ion is always formed from the larger halogen present.




Interhalogen compounds will fluorinate many metal oxides, metal halides and metals.



### AX compounds




All six compounds can be made by controlled reaction of the elements. ClF is very reactive. ICl and IBr are the most stable and can be obtained pure at room temperature. The compounds have properties intermediate between those of the constituent halogens.

ClF fluorinates many metals and non-metals.







It can simultaneously chlorinate and fluorinate a compound either by oxidizing the element or adding to a double bond.




Iodine monochloride ICl is well known. It is used as Wij's reagent in the estimation of the iodine number of fats and oils. The iodine number is a measure of the number of double bonds, i.e. the degree of unsaturation of the fat. The ICl adds to double bonds in the fat. The ICl solution is brown coloured, and when it is added to an unsaturated fat the colour disappears until all the double bonds have reacted. The iodine number is simply the volume (ml) of a standard solution of ICl which reacts with a fixed weight of fat.



When ICl reacts with organic compounds it often iodinate them, though chlorination may occur depending on the conditions.





It is thought that the attacking species is  $\text{I}^+$ , since the I atoms substitute in positions where there is an excess of electrons. Both ICl and IBr are partially ionized in the fused state. Conductivity measurements show that ICl ionizes to the extent of about 1%. Rather than form the simple ions  $\text{I}^+$  and  $\text{Cl}^-$ , the ions are solvated.




Both ICl and IBr can be used as non-aqueous ionizing solvents.

The interhalogens also form addition compounds with alkali halides. These compounds are ionic, and are called polyhalides.




### AX<sub>3</sub> compounds


The compounds  $\text{ClF}_3$ ,  $\text{BrF}_3$ ,  $\text{IF}_3$  and  $(\text{ICl}_3)_2$  can all be made by direct combination of the elements if the conditions are chosen with care.  $\text{ClF}_3$  is a liquid (b.p.  $11.8^\circ\text{C}$ ), and is commercially available. It is produced by direct action:



or



$\text{ClF}_3$  reacts with excess  $\text{Cl}_2$  forming  $\text{ClF}$   $\text{BrF}_3$  behaves similarly




$\text{IF}_3$  is only stable below  $-30^\circ\text{C}$ , and tends to form the more stable  $\text{IF}_5$ . It can also be made using  $\text{XeF}_2$  to fluorinate  $\text{I}_2$










$\text{I}_2\text{Cl}_6$  is easily made by adding  $\text{I}_2$  solid to liquid  $\text{Cl}_2$ , but on warming to room temperature it dissociates




Both  $\text{ClF}_3$  and  $\text{BrF}_3$  are well known as covalent liquids.  $\text{ClF}_3$  is one of the most reactive compounds known, and its properties are aggressive. It catches fire spontaneously with wood and most building materials – even asbestos. It was used in incendiary bombs in World War II. Despite the dangers, peace time production of  $\text{ClF}_3$  runs into hundreds of tonnes per year. It is available in steel cylinders. It is mainly used by the nuclear industry for fuel processing. It is used to make gaseous  $\text{UF}_6$ , which is useful in making enriched  $^{235}\text{U}$  fuel. It is also important in separating the fission products from spent fuel rods. Pu and most of the fission products form involatile tetrafluorides like  $\text{PuF}_4$ , whilst U forms volatile  $\text{UF}_6$ .




$\text{ClF}_3$  reacts explosively with water, stopcock grease and many organic compounds, including cotton and paper. It is a powerful fluorinating agent for inorganic compounds





$\text{ClF}_3$  can be used to fluorinate organic compounds provided it is diluted with dinitrogen to moderate the reaction.  $\text{ClF}_3$  has been used as fuel in short range rockets reacting with hydrazine. This is technically easier than using liquid  $\text{O}_2$  or  $\text{F}_2$ , since the reactants can be stored without refrigeration and they ignite spontaneously on mixing



Bromine trifluoride  $\text{BrF}_3$  is a red liquid, and can be made from the elements at or near room temperature. It is manufactured in multi-tonne quantities. It is less violent in its reactions than  $\text{ClF}_3$ , but it reacts in an analogous manner. The order of reactivity of the interhalogens is:




Like  $\text{ClF}_3$ ,  $\text{BrF}_3$  is used in nuclear processing and reprocessing to make  $\text{UF}_6$ , and it is used to make many other fluorides. It liberates dioxygen quantitatively from many oxides ( $\text{B}_2\text{O}_3$ ,  $\text{SiO}_2$ ,  $\text{As}_2\text{O}_5$ ,  $\text{I}_2\text{O}_5$ ,  $\text{CuO}$ ,  $\text{TiO}_2$ ), and also from oxosalts such as carbonates and phosphates. Measuring the  $\text{O}_2$  evolved is used as a method of analysis.



The interhalogens are all potential non-aqueous ionizing solvents.  $\text{BrF}_3$  has been more widely used as a solvent than the others. This is for three main reasons:


1. It has a convenient liquid range (m.p.  $8.8^\circ\text{C}$ , b.p.  $126^\circ\text{C}$ ).
2. It is a good, but not too violent, fluorinating agent.
3. It self-ionizes considerably, and much more than  $\text{ClF}_3$ .



Thus substances producing  $[\text{BrF}_2]^+$  ions are acids and  $[\text{BrF}_4]^-$  ions are bases in this solvent.

The structure of the  $\text{AX}_3$  type of interhalogen molecule is of interest. In  $\text{ClF}_3$ , Cl is the central atom (Figure 16.10).

Electronic structure of chlorine atom – excited state



Three unpaired electrons form bonds with three fluorine atoms, plus two lone pairs, giving a total of five electron pairs. Shape trigonal bipyramid with two positions occupied by lone pairs

The way to predict which of the three possible arrangements will be formed is described in Chapter 4.

A structural study of  $\text{ClF}_3$  by microwave spectroscopy shows that the molecule is T-shaped, with bond angles of  $87^\circ 40'$ . This is close to  $90^\circ$ , and suggests structure 3. The distortion from  $90^\circ$  is because of repulsion between the lone pairs. Note that two of the bond lengths are the same and are different from the third. This is to be expected because a trigonal bipyramid is not a regular shape. Equatorial bonds (those in the triangle) are different from apical bonds (those pointing up and down). The X-ray structure of crystalline  $\text{ClF}_3$  shows that the molecule is T-shaped, with a




Figure 16 10 Possible structures for chlorine trifluoride  $\text{ClF}_3$

bond angle of  $87^\circ 0'$  and bond lengths  $1.716 \text{ \AA}$  and  $1.621 \text{ \AA}$ . The structure of  $\text{BrF}_3$  (by microwave) is also T-shaped, with a bond angle of  $86^\circ 12'$  and bond lengths of  $1.810 \text{ \AA}$  and  $1.721 \text{ \AA}$ .

$\text{ICl}_3$  does not exist, but the dimer  $\text{I}_2\text{Cl}_6$  is a bright yellow solid. Its structure (Figure 16 11) is planar. The terminal  $\text{I}-\text{Cl}$  bonds are normal single bonds of length  $2.38 \text{ \AA}$  and  $2.39 \text{ \AA}$ . The bridging  $\text{I}-\text{Cl}$  bonds are appreciably longer ( $2.68 \text{ \AA}$  and  $2.72 \text{ \AA}$ ), suggesting delocalized bonding rather than simple halogen bridges formed by coordinate bonds from Cl to I. The liquid has an appreciable electrical conductivity, due to self ionization.










Figure 16 11 Structure of  $\text{I}_2\text{Cl}_6$




It has been less studied as an ionizing solvent than the others because the gas decomposes into  $\text{ICl}$  and  $\text{Cl}_2$ .

### $\text{AX}_5$ compounds

Three compounds are known:  $\text{ClF}_5$ ,  $\text{BrF}_5$ , and  $\text{IF}_5$ .  $\text{ClF}_5$  and  $\text{BrF}_5$  react extremely vigorously, but they are exceeded in violence by  $\text{ClF}_3$ . (See the order of reactivity given earlier.)  $\text{IF}_5$  is a little less reactive, and unlike the others it can be used in glass apparatus. Production is several hundred tonnes per year. They fluorinate many compounds, react explosively with water, attack silicates, and form polyhalides.




Liquid  $\text{IF}_5$  self-ionizes, and therefore conducts electricity



The  $\text{AX}_5$  compounds all have structures based on a square based pyramid that is octahedral with one position unoccupied. The central atom is displaced slightly below the plane. The structure may be understood by considering  $\text{IF}_5$ . I is the central atom in the molecule (Figure 16 12).

Electronic structure of iodine atom – excited state



five unpaired electrons form bonds with five fluorine atoms, plus one lone pair giving a total of six electron pairs  
structure is octahedral with one position occupied by a lone pair (alternatively described as square based pyramid)





Figure 16.12 Structure of  $\text{IF}_5$ .




Rather surprisingly,  $\text{IF}_5$  reacts with the xenon halides, forming adducts  $\text{XeF}_2 \cdot 2\text{IF}_5$  and  $\text{XeF}_4 \cdot \text{IF}_5$ .

### $\text{AX}_7$ compounds

$\text{IF}_7$  is formed by direct combination of the elements at  $250\text{--}300^\circ\text{C}$ , by heating  $\text{IF}_5$  with  $\text{F}_2$ , or by treating iodides with  $\text{F}_2$ .



$\text{IF}_7$  is a violent fluorinating agent, and reacts with most elements. It also reacts with water,  $\text{SiO}_2$  and  $\text{CsF}$ .



The structure of  $\text{IF}_7$  is unusual – a pentagonal bipyramid (Figure 16.13). It is probably the only known example of a non-transition element using three  $d$  orbitals for bonding.





Figure 16.13 Structure of  $\text{IF}_7$ .


Electronic structure of iodine atom – excited state



seven unpaired electrons form bonds with seven fluorine atoms  
seven pairs of electrons form a pentagonal bipyramid

### POLYHALIDES

Halide ions often react with molecules of halogens or interhalogens and form polyhalide ions. Iodine is only slightly soluble in water ( $0.34\text{ g l}^{-1}$ ). Its solubility is greatly increased if some iodide ions are present in the solution. The increase in solubility is due to the formation of a polyhalide ion, in this case the triiodide ion  $\text{I}_3^-$ . This is stable both in aqueous solution and in ionic crystals.






The I-I distances in  $[\text{Me}_4\text{N}]^+[\text{I}_3]^-$  are 2.92 Å. If the bond length of 2.66 Å in  $\text{I}_2$  is taken as a normal single bond, the bonds in  $\text{I}_3^-$  are very weak, and the VSEPR theory provides no explanation why. The molecular orbital approach is more helpful. Assuming that bonding in  $\text{I}_3^-$  arises from singly occupied  $5p_z$  orbitals on two I atoms and a full  $5p_z$  orbital on  $\text{I}^-$ , then there are three atomic orbitals involved. Thus three molecular orbitals are formed, one bonding, one non-bonding and one antibonding. There are 4 electrons, and 2 occupy the bonding MO and 2 occupy the non-bonding MO. This gives one bond, spread over two positions, i.e. a bond order of 0.5, and explains the very long bonds.



More complex ions such as pentaiodide  $\text{I}_5^-$ , heptaoidide  $\text{I}_7^-$  and enneaoide  $\text{I}_9^-$  have also been prepared. Crystalline compounds containing the larger polyiodide ions generally contain large metal ions such as  $\text{Cs}^+$  or large complex cations such as  $\text{R}_4\text{N}^+$ . This is because a large anion together with a large cation give a high coordination number and hence a high lattice energy. Polyhalides such as  $\text{KI}_3$ ,  $\text{H}_2\text{O}$ ,  $\text{RbI}_3$ ,  $\text{NH}_4\text{I}_5$ ,  $[(\text{C}_2\text{H}_5)_4\text{N}]\text{I}_7$  and  $\text{RbI}_9 \cdot 2\text{C}_6\text{H}_6$  may be formed by the direct addition of  $\text{I}_2$  to  $\text{I}^-$ , either with or without a solvent.

The  $\text{Br}_3^-$  ion is much less stable and less common than  $\text{I}_3^-$ . A few unstable  $\text{Cl}_3^-$  compounds are known, and the ion is formed in concentrated solution. No  $\text{F}_3^-$  compounds are known.

Many polyhalides are known which contain two or three different halogens, for example  $\text{K}[\text{ICl}_2]$ ,  $\text{K}[\text{ICl}_4]$ ,  $\text{Cs}[\text{IBrF}]$  and  $\text{K}[\text{IBrCl}]$ . These are formed from interhalogens and metal halides.



Polyhalides are typical ionic compounds (crystalline, stable and soluble in water, conduct electricity when in solution), though they tend to decompose on heating. The products of the decomposition (that is which halogen remains attached to the metal) are governed by the lattice energy of the products. The lattice energy of the alkali metal halides is highest for the smaller halide ions, so the smaller halogen remains bonded to the metal.



The structures of the polyhalides are known. The trihalides  $\text{K}[\text{I}_3]$ ,  $\text{K}[\text{ICl}_2]$  and  $\text{Cs}[\text{IBrF}]$  all contain a linear trihalide ion. This may be explained by considering the orbitals used. For example, see  $[\text{ICl}_2]^-$  in Figure 16.14.





Figure 16.14 Structure of  $[\text{ICl}_2]^-$  ion



Similarly the structures of the pentahalide ions  $[\text{ICl}_4]^-$  and  $[\text{BrF}_4]^-$  are square planar (see Figure 16.15).







Figure 16.15 Structure of  $[\text{I}]$  ion. (The structure of the  $[\text{I}_5]$  ion is different.)

## BASIC PROPERTIES OF THE HALOGENS

Elements typically become more metallic or basic on descending a main group. Thus in Groups 14, 15 and 16 the first elements C, N and O are non-metals, but the heavier members Sn, Pb, Bi and Po are metals. Metallic properties decrease on crossing a period. Little is known about astatine, though it would be expected to show more tendency to form cations than the other members of the group. Thus the trend to metallic properties is less obvious in Group 17. The increasing stability of positive ions indicates an increasing tendency to basic or metallic character. It must be emphasized that iodine is not a metal.




Fluorine is the most electronegative element and has no basic properties (that is, it has no tendency to form positive ions).

Iodine dissolves in oleum and other strongly oxidizing solvents, forming bright blue solutions which are paramagnetic. For a long time these solutions were thought to contain  $\text{I}^+$ , but they are now known to contain the  $[\text{I}_2]^+$  cation. (The Group 16 elements S, Se and Te behave in a similar way. Thus S dissolves, forming blue coloured paramagnetic solutions containing various  $[\text{S}_n]^{2+}$  cations such as  $[\text{S}_4]^{2+}$ ,  $[\text{S}_8]^{2+}$  and  $[\text{S}_{10}]^{2+}$ .)  $[\text{Br}_2]^+$  is also formed in oleum and is bright red coloured and paramagnetic.  $[\text{Cl}_2]^+$  has been observed spectroscopically in discharge tubes. Several crystalline compounds containing  $[\text{I}_2]^+$  or  $[\text{Br}_2]^+$  have been prepared.





The bond length in the  $[\text{Br}_2]^+$  cation is 2.15 Å compared with 2.27 Å in  $\text{Br}_2$ . The bond in the cation is shorter and stronger than in the element, and shows that the electron removed came from an antibonding orbital. In a similar way the bond in  $[\text{I}_2]^+$  is stronger than in  $\text{I}_2$ .

Many other compounds containing cations such as  $[\text{Cl}_3]^+$ ,  $[\text{Br}_3]^+$ ,  $[\text{I}_3]^+$ ,  $[\text{Br}_5]^+$  and  $[\text{I}_5]^+$  have been prepared



The structures of several compounds containing the cationic halogen ions  $[\text{Br}_3]^+$  and  $[\text{I}_3]^+$  have been established by X-ray crystallography or Raman spectroscopy. These ions are always bent, in contrast to the triiodide ion  $[\text{I}_3]^-$  which is linear. The structures of the other ions are not known with certainty. A compound  $\text{I}_7\text{SO}_3\text{F}$  has been reported (as a maximum on a phase diagram). It is a black solid but it is not known whether it contains  $[\text{I}_7]^+$ .


Positive bromine also exists in other complexes such as  $\text{Br}(\text{pyridine})_2\text{NO}_3$  and  $\text{BrF}_3$ . These ionize and give




Complexes containing positive iodine are more numerous.  $\text{ICl}$  and  $\text{IBr}$  both conduct electricity when molten. Electrolysis of  $\text{ICl}$  liberates  $\text{I}_2$  and  $\text{Cl}_2$  at both electrodes. This is consistent with the following ionization




Molten  $\text{ICN}$  behaves in a similar way to  $\text{ICl}$



However, electrolysis of  $\text{ICl}$  dissolved in pyridine gives  $\text{I}_2$  only at the cathode. This suggests the more simple type of ionization




The addition of  $\text{AlCl}_3$  to a melt of  $\text{ICl}$  greatly increases its conductivity, and is explained by the formation of complex ions







ICl behaves as an electrophilic iodinating agent. It converts acetanilide to 4-iodoacetanilide, and salicylic acid to 3,5-diiodosalicylic acid. Because the attacked sites have an electron excess, the iodine must be positive.


If a solution of iodine in an inert solvent is passed down a cationic ion-exchange column, some iodine is retained in the resin.



The positive ion retained may be eluted with KI, to estimate the amount of  $\text{I}^+$ , or it may be allowed to react with various reagents.




$\text{I}^+$  reacts with  $\text{OH}^-$  in aqueous solutions.




For this reason  $\text{I}^+$  will only exist in water if it is stabilized by coordination to some other molecule. A large number of compounds are known which contain  $\text{I}^+$  stabilized in a complex ion. Many pyridine complexes are known such as  $[\text{I}(\text{pyridine})_2]\text{NO}_3$ ,  $[\text{I}(\text{pyridine})_2]\text{ClO}_4$ ,  $[\text{I}(\text{pyridine})]\text{acetate}$  and  $[\text{I}(\text{pyridine})]\text{benzoate}$ .

Molten  $\text{ICl}_3$  has a high conductivity ( $8.4 \times 10^{-3} \text{ ohm}^{-1} \text{ cm}^{-1}$ ). When  $\text{ICl}_3$  is electrolysed both  $\text{I}_2$  and  $\text{Cl}_2$  are liberated at both electrodes. This suggests ionization:



Treatment of  $\text{I}_2$  with fuming  $\text{HNO}_3$  and acetic anhydride gives the ionic compound  $\text{I}(\text{acetate})_3$ . If a saturated solution of  $\text{I}(\text{acetate})_3$  in acetic anhydride is electrolysed using silver electrodes, one equivalent of  $\text{AgI}$  is formed at the cathode for every three Faradays of electricity passed. This would seem to indicate ionization giving  $\text{I}^{3+}$ :



There is no structural evidence for the presence of  $\text{I}^{3+}$ . Other ionic compounds which may contain  $\text{I}^{3+}$  are iodine phosphate  $\text{IPO}_4$  and iodine fluosulphonate  $\text{I}(\text{SO}_3\text{F})_3$ .

## PSEUDOHALOGENS AND PSEUDOHALIDES

A few ions are known, consisting of two or more atoms of which at least one is N, that have properties similar to those of the halide ions. They are therefore called pseudohalide ions. Pseudohalide ions are univalent, and these form salts resembling the halide salts. For example, the sodium salts are soluble in water, but the silver salts are insoluble. The hydrogen compounds are acids like the halogen acids  $\text{HX}$ . Some of the pseudohalide

Table 16.17 The important pseudohalogens

Anion		Acid	Dimer
CN <sup>-</sup>	cyanide ion	HCN	hydrogen cyanide (CN) <sub>2</sub> , cyanogen
SCN <sup>-</sup>	thiocyanate ion	HSCN	thiocyanic acid (SCN) <sub>2</sub> , thiocyanogen
SeCN <sup>-</sup>	selenocyanate ion		(SeCN) <sub>2</sub> selenocyanogen
OCN <sup>-</sup>	cyanate ion	HO-CN	cyanic acid
NCN <sup>2-</sup>	cyanamide ion	H <sub>2</sub> NCN	cyanamide
ONC <sup>-</sup>	fulminate ion	HONC	fulminic acid
N <sub>3</sub> <sup>-</sup>	azide ion	HN <sub>3</sub>	hydrogen azide

ions combine to form dimers comparable with the halogen molecules X<sub>2</sub>. These include cyanogen (CN)<sub>2</sub>, thiocyanogen (SCN)<sub>2</sub> and selenocyanogen (SeCN)<sub>2</sub>.

The best known pseudohalide is CN<sup>-</sup>. This resembles Cl<sup>-</sup>, Br<sup>-</sup> and I<sup>-</sup> in the following respects:

- 1 It forms an acid HCN
- 2 It can be oxidized to form a molecule cyanogen (CN)<sub>2</sub>
- 3 It forms insoluble salts with Ag<sup>+</sup>, Pb<sup>2+</sup> and Hg<sup>2+</sup>
- 4 Interpseudohalogen compounds ClCN, BrCN and ICN can be formed
- 5 AgCN is insoluble in water but soluble in ammonia, as is AgCl
- 6 It forms a large number of complexes similar to halide complexes, e.g. [Cu(CN)<sub>4</sub>]<sup>2-</sup> and [CuCl<sub>4</sub>]<sup>2-</sup> and [Co(CN)<sub>6</sub>]<sup>3-</sup> and [CoCl<sub>6</sub>]<sup>3-</sup>

### FURTHER READING

- Banks, R. E. (ed.) (1982) *Preparation, Properties and Industrial Applications of Organofluorine Compounds*. Ellis Horwood, Chichester.
- Banks, R. E., Sharp, D. W. A. and Tatlow, J. C. (1987) *Fluorine the First 100 Years (1886-1986)*. Elsevier.
- Brown, D. (1968) *Halides of the Transition Elements*. Vol. I (Halides of the lanthanides and actinides). Wiley, London and New York.
- Brown, I. (1987) Astatine: organonuclear chemistry and biomedical applications. *Adv. Inorg. Chem.* 31, 43-88.
- Canterford, J. H. and Cotton, R. (1968) *Halides of the Second and Third Row Transition Elements*. Wiley, London.
- Canterford, J. H. and Cotton, R. (1969) *Halides of the First Row Transition Elements*. Wiley, London.
- Cotton, R. and Canterford, J. H. (1968) *Halides of the Second and Third Row Transition Elements*. Wiley, London.
- Cotton, R. and Canterford, J. H. (1969) *Halides of the First Row Transition Elements*. Wiley, London.
- Donovan, R. J. (1978) Chemistry and pollution of the stratosphere. *Education in Chemistry* 15, 110-113.
- Downs, A. J. and Adams, C. J. (1973) *Comprehensive Inorganic Chemistry*. Vol. II (Chapter on Chlorine, bromine, iodine and astatine). Pergamon Press, Oxford.
- Downs, A. J. and Adams, C. J. (1975) *The Chemistry of Chlorine, Bromine, Iodine and Astatine*. Pergamon, New York.
- Fogg, P. G. T. and Gerrard, W. (eds.) (1989) *Hydrogen Halides in Non-aqueous Solvents*. Pergamon.

- Gillespie, R.J. and Morton, M.J. (1971) Halogen and interhalogen cations, *Q. Rev. Chem. Soc.*, **25**, 553.
- Golub, A.M., Kohler, H. and Skopenko, V.V. (eds) (1986) *Chemistry of Pseudo-halides* (Topics in Inorganic and General Chemistry Series No. 21), Elsevier, Oxford.
- Gutman, V. (ed.) (1967) *Halogen Chemistry*, 3 Volumes, Academic Press, London. (Vol. I: Halogens, interhalogens, polyhalides, noble gas halides, Vol II: Halides of non-metals, Vol. 3: Complexes), (Old but comprehensive.)
- Lagowski, J. (ed.) (1978) *The Chemistry of Non-aqueous Solvents*, Vol. II (Chapter 1 by Klanberg, F., Liquid HCl, HBr and HI; Chapter 2 by Kilpatrick, M. and Jones, J.G., Anhydrous hydrogen fluoride as a solvent medium; Chapter 3 by Martin, D.M., Rousson, R. and Weulersse, J.M., The Interhalogens), Academic Press, New York.
- Langley, R.H. and Welch, L. (1983) Fluorine (Chemical of the month), *J. Chem. Ed.*, **60**, 759–761.
- O'Donnell, T.A. (1973) *Comprehensive Inorganic Chemistry*, Vol. II (Chapter 25: Fluorine), Pergamon Press, Oxford.
- Price, D., Iddon, B. and Wakefield, B.J. (eds) (1988) *Bromine Compounds*, Elsevier.
- Sconce, J.S. (1962) *Chlorine: Its Manufacture, Properties and Uses*, Reinhold, New York.
- Shamir, J. (1979) Polyhalogen cations, *Structure and Bonding*, **37**, 141–210.
- Tatlow, J.C. *et al.* (eds), *Advances in Fluorine Chemistry*, Butterworths, London. (A continuing series.)
- Thompson, R. (ed.) (1986) *The Modern Inorganic Chemicals Industry* (Chapter by Fielding, H.C. and Lee, B.E., Hydrogen fluoride, Inorganic fluorides and fluorine; Chapter by Purcell, R.W., The chlor-alkali industry, Chapter by Campbell, A., Chlorine and chlorination; Chapter by McDonald, R.B. and Merriman, W.R., Bromine and the bromine-chemicals industry), Special Publication No. 31, The Chemical Society, London, (reprinted 1986).
- Thrush, B.A. (1977) The chemistry of the stratosphere and its pollution, *Endeavour*, **1**, 3–6.
- Waddington, T.C. (ed.) (1969) *Nonaqueous Solvent Systems* (Chapter 2 by Hyman, H.H. and Katz, J.J., Liquid hydrogen fluoride; Chapter 3 by Peach, M.E. and Waddington, T.C. The higher hydrogen halides as ionizing solvents), Nelson.

## PROBLEMS

1. Describe how fluorine is produced, the apparatus used and any precautions you consider necessary. Is elemental fluorine widely used in reactions?
2. Why is it not possible to obtain  $F_2$  by electrolysis of aqueous NaF, aqueous HF or anhydrous HF?
3. What fluorinating agents are often used instead of  $F_2$ ? Give equations to show their use.
4. What are the main uses of fluorine?
5. Write balanced equations to show the reactions between HF and (a)  $SiO_2$ , (b) CaO, (c) KF, (d)  $CCl_4$ , (e) U, (f) graphite.

- 6 What are the common sources of chlorine bromine and iodine in salts? Where do they occur and how are the elements extracted from the appropriate salts?
- 7 What are the main uses of  $\text{Cl}_2$ ?
- 8 Give equations to show how the halogen acids HF, HCl, HBr and HI may be prepared in aqueous solution. Why is HF a weak acid compared with HI in water?
- 9  $\text{HCl}_{(\text{g})}$  can be prepared from NaCl and  $\text{H}_2\text{SO}_4$ .  $\text{HBr}_{(\text{g})}$  and  $\text{HI}_{(\text{g})}$  cannot be made in a similar way from NaBr and NaI. Explain why this is so.
- 10 Write equations for the reactions between  $\text{Cl}_2$  and (a)  $\text{H}_2$ , (b) CO, (c) P, (d) S, (e)  $\text{SO}_2$ , (f)  $\text{Br}^-_{(\text{aq})}$ , (g) NaOH.
- 11 Explain what happens when an aqueous solution of  $\text{AgNO}_3$  is added to solutions of NaF, NaCl, NaBr and NaI. What change (if any) occurs when ammonia is added to each of these mixtures?
- 12 (a) Draw the structures of  $\text{OF}_2$ ,  $\text{Cl}_2\text{O}$ ,  $\text{O}_2\text{F}_2$  and  $\text{I}_2\text{O}_4$ .  
 (b) Explain the bond angle in  $\text{OF}_2$  and give a reason why it is different in  $\text{Cl}_2\text{O}$ .  
 (c) Why are the O—F bonds in  $\text{O}_2\text{F}_2$  longer than in  $\text{OF}_2$ , whereas the O—O bond in  $\text{O}_2\text{F}_2$  is short compared with that in  $\text{H}_2\text{O}_2$ ?
- 13 Describe the preparation and an analytical use of  $\text{I}_2\text{O}_5$ .
- 14 (a) Give the names of four different types of oxoacid of the halogens and give the formula of either an acid or a salt derived from the acid for each type.  
 (b) Describe the preparation of the following compounds and give one use of each:  $\text{NaOCl}$ ,  $\text{NaClO}_2$ ,  $\text{NaClO}_3$ ,  $\text{HIO}_4$ .
- 15 Iodine is almost insoluble in water, but it dissolves readily in an aqueous solution of KI. Explain why this is so.
- 16 (a) Explain the shape of the  $\text{I}_3^-$  ion.  
 (b) Explain why solid  $\text{CsI}$  is stable but solid  $\text{NaI}_3$  is not.
- 17 (a) Give the formulae of 11 interhalogen compounds.  
 (b) Draw the shapes of the following molecules and ions, showing the positions of the lone pairs of electrons:  
 $\text{ClF}$ ,  $\text{BrF}_3$ ,  $\text{IF}_4$ ,  $\text{IF}_7$ ,  $\text{I}_3^-$ ,  $\text{ICl}_4^-$  and  $\text{I}_5^-$ .
- 18 List differences between the chemistry of fluorine and the other halogens and give reasons for these differences.

# Group 18 – the noble gases

17

Table 17.1 Electronic structures

Element	Symbol		Electronic structure
Helium	He		$1s^2$
Neon	Ne	[He]	$2s^2 2p^6$
Argon	Ar	[Ne]	$3s^2 3p^6$
Krypton	Kr	[Ar]	$3d^{10} 4s^2 4p^6$
Xenon	Xe	[Kr]	$4d^{10} 5s^2 5p^6$
Radon	Rn	[Xe]	$4f^{14} 5d^{10} 6s^2 6p^6$

## NAME OF GROUP AND THEIR ELECTRONIC STRUCTURES

The elements of Group 18 have been called 'the inert gases' and 'the rare gases'. Both are misnomers, since the discovery of the xenon fluorides in 1962 shows that xenon is not inert, and argon makes up 0.9% by volume of the atmosphere. The name 'noble gases' implies that they tend to be unreactive, in the same way that the noble metals are often reluctant to react and are the least reactive metals.

Helium has two electrons which form a complete shell  $1s^2$ . The other noble gases have a closed octet of electrons in their outer shell  $ns^2 np^6$ . This electronic configuration is very stable and is related to their chemical inactivity. These atoms have an electron affinity of zero (or slightly negative), and have very high ionization energies – higher than any other elements. Under normal conditions the noble gas atoms have little tendency to gain or lose electrons. Thus they have little tendency to form bonds, and so they exist as single atoms.


## OCCURRENCE AND RECOVERY OF THE ELEMENTS

The gases He, Ne, Ar, Kr and Xe all occur in the atmosphere. A mixture of the noble gases was first obtained by Cavendish in 1784. Cavendish removed  $N_2$  from air by adding excess  $O_2$  and sparking. The  $NO_2$  formed was absorbed in NaOH solution. The excess  $O_2$  was removed by burning

*continued overleaf*

with S, and absorbing the  $\text{SO}_2$  in NaOH solution. This gave a small volume of unreactive gas.

Ar is quite abundant and can be recovered by fractional distillation of liquid air (see under 'Nitrogen', Chapter 14). Ar constitutes 0.93% by volume of air (i.e. 9300 ppm). It originates in the air mostly from electron capture ( $\beta^+$  decay) of potassium.




World production of Ar is over 700 000 tonnes/year.

The other noble gases are much less abundant. The abundance of He in the atmosphere is only about 5 ppm by volume and recovery from air would be very expensive. A cheaper source is from natural gas deposits, where the hydrocarbons are liquified, leaving He gas. The He has been produced by radioactive decay and trapped underground. The richest source is in southwest USA, where the natural gas contains 0.5–0.8% He. This provides most of the world's supply of He. Other natural gas deposits containing appreciable amounts of He have been found in Algeria, Poland, the USSR and Canada. World production was 18 800 tonnes in 1993.

The non-radioactive noble gases are all produced industrially by fractional distillation of liquid air. This gives large amounts of dinitrogen and dioxygen, and only a small amount of the noble gases. (The dioxygen is mainly used for steel making.) Of the noble gases, Ar is obtained in the largest amounts, and it is the cheapest.

Rn is radioactive and is produced by the decay of radium and thorium minerals. A convenient source is  ${}^{226}\text{Ra}$ , and 100 g of radium yields about 2 ml of radon per day.



The most stable isotope  ${}^{222}\text{Rn}$  is itself  $\alpha$  active and has a half life of only 3.8 days, so only tracer studies have been made.

## USES OF THE ELEMENTS

The largest use of Ar is to provide an inert atmosphere for metallurgical processes. This includes welding stainless steel, titanium, magnesium and aluminium, and in the production of titanium (Kroll and IMI processes). Smaller amounts are used in growing silicon and germanium crystals for transistors, and in electric light bulbs, fluorescent lamps, radio valves and Geiger–Müller radiation counters.

Helium has the lowest boiling point of any liquid, and it is used in cryoscopy to obtain the very low temperatures required for superconductivity, and lasers. It is used as the cooling gas in one type of gas-cooled nuclear reactor, and as the flow gas in gas–liquid chromatography. It is also used in weather balloons and airships. Though  $\text{H}_2$  has a lower density and is cheaper and more readily available than He,  $\text{H}_2$  is highly flammable. Thus on safety grounds He is used in preference to  $\text{H}_2$  in airships. He is much less dense than air. One cubic metre of He gas at atmospheric

*continued overleaf*

pressure can lift 1 kg. Helium is used in preference to dinitrogen to dilute dioxygen in the gas cylinders used by divers. This is because dinitrogen is quite soluble in blood, so a sudden change in pressure causes degassing and gives bubbles of  $N_2$  in the blood. This causes the painful (or fatal) condition called 'bends'. Helium is only slightly soluble so the risk of 'bends' is reduced.

Small amounts of Ne are used in neon discharge tubes which give the familiar reddish orange glow of 'neon' signs. The other gases are also used in discharge tubes to give different colours.

## PHYSICAL PROPERTIES

The elements are all colourless, odourless monatomic gases. The enthalpy of vaporization is a measure of the forces holding the atoms together. The values are very low because the only forces between the atoms are very weak van der Waals forces. The enthalpy of vaporization increases down the group as the polarizability of the atoms increases.

Table 17.2 Physical properties of the noble gases

	First ionization energy ( $\text{kJ mol}^{-1}$ )	Enthalpy of vaporization ( $\text{kJ mol}^{-1}$ )	Melting point ( $^{\circ}\text{C}$ )	Boiling point ( $^{\circ}\text{C}$ )	Atomic radii ( $\text{\AA}$ )	Abundance in atmosphere (% volume)
He	2372	0.08		-269.0	1.20	$5.2 \times 10^{-4}$
Ne	2080	1.7	-248.6	-246.0	1.60	$1.5 \times 10^{-3}$
Ar	1521	6.5	-189.4	-186.0	1.91	0.93
Kr	1351	9.1	-157.2	-153.6	2.00	$1.1 \times 10^{-4}$
Xe	1170	12.7	-111.8	-108.1	2.20	$8.7 \times 10^{-6}$
Rn	1037	18.1	-71	-62		

Because the interatomic forces are very weak, the melting points and boiling points are also very low. The boiling point of He is the lowest of any element, only four degrees above absolute zero.

The atomic radii of the elements are all very large, and increase on descending the group. It must be noted that these are non-bonded radii, and should be compared with the van der Waals radii of other elements rather than with covalent (bonded) radii.

The noble gases are all able to diffuse through glass, rubber and plastic materials, and some metals. This makes them difficult to handle in the laboratory, particularly since glass Dewar flasks cannot be used for low temperature work.

## SPECIAL PROPERTIES OF HELIUM

Helium is unique. It has the lowest boiling point of any substance known. All other elements become solids on cooling, but cooling only produces helium liquid. It only forms a solid under high pressure (about 25 atmos-

pheres) There are two different liquid phases. Helium I is a normal liquid, but helium II is a superfluid. A superfluid is a most unusual state of matter. Normally atoms are free to move in a gas, can move in a more restricted way in a liquid, and can only vibrate about fixed positions in a solid. As the temperature decreases, the amount of thermal motion of atoms decreases, and gases become liquids, and eventually solids. When the temperature of helium gas is lowered to 4.2 K it liquifies as helium I. Rather surprisingly the liquid continues to boil vigorously. At 2.2 K, the liquid suddenly stops boiling (which with normal materials is when a solid is formed). In this case helium II is formed. This is still a liquid because the interatomic forces are not strong enough to form a solid, but thermal motion of the atoms has actually stopped. Helium I is a normal liquid and when it changes to helium II at the  $\lambda$ -point temperature, many physical properties change abruptly. The specific heat changes by a factor of 10. The thermal conductivity increases by  $10^6$  and becomes 800 times greater than for copper. It becomes a superconductor (i.e. shows zero electrical resistance). The viscosity becomes effectively zero and 1/100th of that of gaseous hydrogen. It spreads to cover all surfaces at temperatures below the  $\lambda$ -point. Thus *the liquid can actually flow up the sides of the vessel and over the edge until the levels on both sides are the same*. The surface tension and compressibility are also anomalous.

### CHEMICAL PROPERTIES OF THE NOBLE GASES

The noble gases were isolated and discovered because of their lack of reactivity. For a long time it was thought that they really were chemically inert. Before 1962, the only evidence for compound formation by the noble gases was some molecular ions formed in discharge tubes, and clathrate compounds.

#### Molecular ions formed under excited conditions

Several molecular ions such as  $\text{He}_2^+$ ,  $\text{HeH}^+$ ,  $\text{HeH}^{2+}$  and  $\text{Ar}_2^+$  are formed under high energy conditions in discharge tubes. They only survive momentarily and are detected spectroscopically. Neutral molecules such as  $\text{He}_2$  are unstable.

#### Clathrate compounds

Clathrate compounds of the noble gases are well known. Normal chemical compounds have ionic or covalent bonds. However, in the clathrates atoms or molecules of the appropriate size are trapped in cavities in the crystal lattice of other compounds. *Though the gases are trapped, they do not form bonds*.

If an aqueous solution of quinol (1,4 dihydroxybenzene) is crystallized under a pressure of 10–40 atmospheres of Ar, Kr or Xe, the gas becomes trapped in cavities of about 4 Å diameter in the  $\beta$ -quinol structure. When




the clathrate is dissolved, the hydrogen bonded arrangement of  $\beta$ -quinol breaks down and the noble gas escapes. Other small molecules such as  $O_2$ ,  $SO_2$ ,  $H_2S$ ,  $MeCN$  and  $CH_3OH$  form clathrates as well as Ar, Kr and Xe. The smaller noble gases He and Ne do not form clathrate compounds because the gas atoms are small enough to escape from the cavities. The composition of these clathrate compounds corresponds to 3 quinol:1 trapped molecule, though normally all the cavities are not filled.


The gases Ar, Kr and Xe may be trapped in cavities in a similar way when water is frozen under a high pressure of the gas. These are clathrate compounds, but are more commonly called 'the noble gas hydrates'. They have formulae approximating to  $6H_2O:1$  gas atom. He and Ne are not trapped because they are too small. The heavier noble gases can also be trapped in cavities in synthetic zeolites, and samples have been obtained containing up to 20% of Ar by weight. Clathrates provide a convenient means of storing radioactive isotopes of Kr and Xe produced in nuclear reactors.

## CHEMISTRY OF XENON

The first real compound of the noble gases was made in 1962. Bartlett and Lohman had previously used the highly oxidizing compound platinum hexafluoride to oxidize dioxygen.



The first ionization energy for  $O_2 \rightarrow O_2^+$  is  $1165 \text{ kJ mol}^{-1}$ , which is almost the same as the value of  $1170 \text{ kJ mol}^{-1}$  for  $Xe \rightarrow Xe^+$ . It was predicted that xenon should react with  $PtF_6$ . Experiments showed that when deep red  $PtF_6$  vapour was mixed with an equal volume of Xe, the gases combined immediately at room temperature to produce a yellow solid. They (incorrectly) thought the product obtained was xenon hexafluoroplatinate(V),  $Xe^+[PtF_6]^-$ . The reaction has since been shown to be more complicated, and the product is really  $[XeF]^+[Pt_2F_{11}]^-$ .



Soon after this it was found that Xe and  $F_2$  reacted at  $400^\circ C$  to give a colourless volatile solid  $XeF_4$ . This has the same number of valency electrons as, and is isostructural with, the polyhalide ion  $[ICl_4]^-$ . Following these discoveries there was a rapid extension of the chemistry of the noble gases, and in particular of xenon.


The ionization energies of He, Ne and Ar are much higher than for Xe, and are too high to allow the formation of similar compounds. The ionization energy for Kr is a little lower than for Xe, and Kr does form  $KrF_2$ . The ionization energy of Rn is less than for Xe, and Rn might be expected to form compounds similar to those of Xe. Rn is radioactive, has no stable isotopes, and all the isotopes have short half lives. This has limited work on radon compounds, and only  $RnF_2$  and a few complexes are known.

Table 17.3 Structures of some xenon compounds


Formula	Name	Oxidation state	m p (°C)	Structure
XeF <sub>2</sub>	xenon difluoride	(+II)	129	linear (RnF <sub>2</sub> and XeCl <sub>2</sub> are similar)
XeF <sub>4</sub>	xenon tetrafluoride	(+IV)	117	square planar (XeCl <sub>4</sub> is similar)
XeF <sub>6</sub>	xenon hexafluoride	(+VI)	49.6	distorted octahedron
XeO <sub>3</sub>	xenon trioxide	(+VI)	explodes	pyramidal (tetrahedral with one corner unoccupied)
XeO <sub>3</sub> F <sub>2</sub>		(+VI)	30.8	trigonal bipyramid (with one position unoccupied)
XeOF <sub>4</sub>		(+VI)	-46	square pyramidal (octahedral with one position unoccupied)
XeO <sub>4</sub>	xenon tetroxide	(+VIII)	-35.9	tetrahedral
XeO <sub>3</sub> F <sub>2</sub>		(+VIII)	-54.1	trigonal bipyramid
Ba·[XeO <sub>6</sub> ] <sup>4-</sup>	barium perxenate	(+VIII)	dec >300	octahedral



Xe reacts directly only with F<sub>2</sub>. However, oxygen compounds can be obtained from the fluorides. There is some evidence for the existence of XeCl<sub>2</sub> and XeCl<sub>4</sub> and one compound is known with a Xe—N bond. Thus there is quite an extensive chemistry of Xe. The principal compounds are listed in Table 17.3.

Xenon reacts directly with fluorine when the gases are heated at 400°C in a sealed nickel vessel and the products depend on the F<sub>2</sub>/Xe ratio






The compounds XeF<sub>2</sub>, XeF<sub>4</sub> and XeF<sub>6</sub> are all white solids. They can be sublimed at room temperature, and can be stored indefinitely in nickel or Monel containers. The lower fluorides form higher fluorides when heated with F<sub>2</sub> under pressure. The fluorides are all extremely strong oxidizing and fluorinating agents. They react quantitatively with hydrogen as follows










They oxidize  $\text{Cl}^-$  to  $\text{Cl}_2$ ,  $\text{I}^-$  to  $\text{I}_2$  and cerium(III) to cerium(IV):







They fluorinate compounds:




$\text{XeF}_2$  is now commercially available and is quite widely used in synthetic organic chemistry. It can oxidize and fluorinate the 'hetero element' in an organometallic compound, but does not attack the alkyl or aryl groups.




If  $\text{XeF}_2$  is mixed with anhydrous HF its reactivity is greatly increased, possibly due to the formation of  $\text{XeF}^+$ .




The fluorides differ in their reactivity with water.  $\text{XeF}_2$  is soluble in water, but undergoes slow hydrolysis. Hydrolysis is more rapid with alkali.





$\text{XeF}_4$  reacts violently with water, giving xenon trioxide  $\text{XeO}_3$ .




$\text{XeF}_6$  also reacts violently with water, but slow hydrolysis by atmospheric moisture gives the highly explosive solid  $\text{XeO}_3$ .




With small quantities of water, partial hydrolysis occurs, giving a colourless liquid xenon oxofluoride  $\text{XeOF}_4$ . The same product is formed when  $\text{XeF}_6$  reacts with silica or glass:



$\text{XeO}_3$  is an explosive white hygroscopic solid. It reacts with  $\text{XeF}_6$  and  $\text{XeOF}_4$



$\text{XeO}_3$  is soluble in water, but does not ionize. However, in alkaline solution above pH 10.5 it forms the xenate ion  $[\text{HXeO}_4]^-$




Xenates contain  $\text{Xe}(+VI)$  and they slowly disproportionate in solution to perxenates (which contain  $\text{Xe}(+VIII)$ ) and  $\text{Xe}$



Several perxenates of Group 1 and 2 metals have been isolated, and the crystal structures of  $\text{Na}_4\text{XeO}_6 \cdot 6\text{H}_2\text{O}$  and  $\text{Na}_4\text{XeO}_6 \cdot 8\text{H}_2\text{O}$  have been determined by X-ray crystallography. The solubility of sodium perxenate in 0.5M NaOH is only 0.2 grams per litre, so precipitation of sodium perxenate could be used as a gravimetric method of analysis for sodium. Perxenates are extremely powerful oxidizing agents, which will oxidize  $\text{HCl}$  to  $\text{Cl}_2$ ,  $\text{H}_2\text{O}$  to  $\text{O}_2$ , and  $\text{Mn}^{2+}$  to  $\text{MnO}_4^-$ . With concentrated  $\text{H}_2\text{SO}_4$  they give xenon tetroxide  $\text{XeO}_4$ , which is volatile and explosive.

### Xenon fluoride complexes

$\text{XeF}_2$  acts as a fluoride donor and forms complexes with covalent pentafluorides including  $\text{PF}_5$ ,  $\text{AsF}_5$ ,  $\text{SbF}_5$  and the transition metal fluorides  $\text{NbF}_5$ ,  $\text{TaF}_5$ ,  $\text{RuF}_5$ ,  $\text{OsF}_5$ ,  $\text{RhF}_5$ ,  $\text{IrF}_5$  and  $\text{PtF}_5$ . These are thought to have the structure



and






Figure 17.1 Structure of  $\text{XeF}_2 \cdot 2\text{SbF}_5$  (From Mackay and Mackay *Introduction to Modern Inorganic Chemistry*, 4th ed., Blackie, 1989)




The structures of some of the  $\text{XeF}_2$  complexes in the solid state are known. In the complex  $\text{XeF}_2 \cdot 2\text{SbF}_5$  (Figure 17.1) the two Xe–F distances differ greatly (1.84 Å and 2.35 Å). This suggests the formulation  $[\text{XeF}]^+ [\text{Sb}_2\text{F}_{11}]^-$ . However, the Xe–F distance of 2.35 Å is much less than the van der Waals (non-bonded) distance of 3.50 Å. This suggests that one fluorine atom forms a fluorine bridge between Xe and Sb. In fact the structure is intermediate between that expected for the ionic structure, and that for the fully covalent bridge structure.


$\text{XeF}_4$  forms only a few complexes, for example those with  $\text{PF}_5$ ,  $\text{AsF}_5$  and  $\text{SbF}_5$ .  $\text{XeF}_6$  can act as a fluoride donor, forming complexes such as:



$\text{XeF}_6$  may also act as a fluoride acceptor. With  $\text{RbF}$  and  $\text{CsF}$  it reacts as follows:



On heating, the  $[\text{XeF}_7]^-$  ion decomposes:



## STRUCTURE AND BONDING IN XENON COMPOUNDS

The structures of the more common xenon halides, oxides and oxoions are given in Table 17.4 (on page 647). The nature of the bonds and the orbitals used for bonding in these compounds are of great interest and have been the subject of considerable controversy.

### $\text{XeF}_2$

$\text{XeF}_2$  is a linear molecule with both Xe–F distances 2.00 Å. The bonding may be explained quite simply by promoting an electron from the  $5p$  level of Xe to the  $5d$  level. The two unpaired electrons form bonds with fluorine atoms. The five electron pairs point to the corners of a trigonal bipyramid. Of these, three are lone pairs and occupy the equatorial positions, and two are bond pairs and occupy the apical positions. The atoms thus form a linear molecule (Figure 17.2).





Figure 17.2  $\text{XeF}_2$  molecule.



This explains the observed structure, but an objection is that the  $5d$  orbitals of Xe appear to be too large for effective overlap of orbitals. The maximum in the radial electron distribution function for a  $5d$  orbital in a Xe atom occurs at a distance of  $4.9 \text{ \AA}$  from the nucleus. It has been noted in Chapter 4 in the section 'The extent of  $d$  orbital participation in molecular bonding' that highly electronegative atoms like fluorine cause a large contraction in the size of  $d$  orbitals. If this contraction is big enough, the valence bond explanation will suffice.

A second objection is over the mixing of orbitals ( $sp^3d$  hybridization). Mixing is only effective between orbitals of similar energy, and the Xe  $5d$  orbitals would seem too high in energy to contribute to such a scheme of hybridization. (The difference in energy between a  $5p$  and a  $5d$  level is about  $960 \text{ kJ mol}^{-1}$ .)



The molecular orbital explanation involving three centre bonds is more acceptable. The outer electronic configurations of the atoms are



Assume that bonding involves the  $5p_z$  orbital of Xe and the  $2p_z$  orbitals of the two F atoms. For bonding to occur, orbitals with the same symmetry must overlap. These three atomic orbitals combine to give three molecular orbitals, one bonding, one non-bonding and one antibonding. This is represented in a simple way in Figure 17.3. The original three atomic orbitals contained four electrons (two in the Xe  $5p_z$  and one in each of the F  $2p_z$ ). These electrons will occupy the molecular orbitals of lowest energy. The order of energy is


$$\text{bonding MO} < \text{non-bonding MO} < \text{antibonding MO}$$


Thus two electrons occupy the bonding MO, and this pair of electrons is responsible for binding all three atoms. The remaining two electrons occupy the non bonding MO. These electrons are situated mainly on the F atoms, and confer some ionic character. The bonding may be described as three centre, four electron  $\sigma$  bonding. A linear arrangement of the atoms gives the best overlap of orbitals, in agreement with the observed structure. These bonds should be compared with the three-centre two-electron bonds described for  $\text{B}_2\text{H}_6$  (see Chapter 12).

Figure 17.3 Possible combinations of atomic orbitals in  $\text{XeF}_2$ .Figure 17.4 Molecular orbitals in  $\text{XeF}_2$ .

### $\text{XeF}_4$

The structure of  $\text{XeF}_4$  is square planar, with Xe-F distances of  $1.95 \text{ \AA}$ . The valence bond theory explains this by promoting two electrons as shown:



Figure 17.5 XeF<sub>4</sub> molecule

The problem of whether the size of the xenon 5d orbitals will allow effective overlap or their energy will allow mixing and hybridization, is the same as in XeF<sub>2</sub>. The molecular orbital explanation of XeF<sub>4</sub> is similar to that for XeF<sub>2</sub>. The Xe atom bonds to four F atoms. The xenon 5p<sub>x</sub> orbital forms a three centre MO with 2p orbitals from two F atoms just as in XeF<sub>2</sub>. The 5p<sub>y</sub> orbital forms another three centre MO involving two more F atoms. The two three centre orbitals are at right angles to each other, thus giving a square planar molecule.


Table 17.4 Possible explanation of structures

Formula	Structure	Number of electron pairs	Number of lone pairs	VSEPR explanation of structure
XeF <sub>2</sub>	linear	5	3	five electron pairs form trigonal bipyramid with three lone pairs in equatorial positions
XeF <sub>4</sub>	square planar	6	2	six electron pairs form an octahedron with two positions occupied by lone pairs
XeF <sub>6</sub>	distorted octahedron	7	1	pentagonal bipyramid or capped octahedron with one lone pair
XeO <sub>3</sub>	pyramidal	7	1	three $\pi$ bonds so the remaining four electron pairs form a tetrahedron with one corner occupied by a lone pair
XeO <sub>2</sub> F <sub>2</sub>	trigonal bipyramid	7	1	two $\pi$ bonds so remaining five electron pairs form trigonal bipyramid with one equatorial position occupied by a lone pair
XeOF <sub>4</sub>	square pyramidal	7	1	one $\pi$ bond so remaining six electron pairs form an octahedron with one position occupied by a lone pair
XeO <sub>4</sub>	tetrahedral	8	0	four $\pi$ bonds so remaining four electron pairs form a tetrahedron
XeO <sub>3</sub> F <sub>2</sub>	trigonal bipyramid	8	0	three $\pi$ bonds so remaining five electron pairs form a trigonal bipyramid
Ba <sub>2</sub> [XeO <sub>6</sub> ] <sup>4-</sup>	octahedral	8	0	two $\pi$ bonds so remaining six electron pairs form an octahedron



$\text{XeF}_6$ 

The structure of  $\text{XeF}_6$  is a distorted octahedron. The bonding in  $\text{XeF}_6$  has caused considerable controversy which is not completely resolved. The structure may be explained in valence bond terms by promoting three electrons in Xe:



The six unpaired electrons form bonds with fluorine atoms. The distribution of seven orbitals gives either a capped octahedron or a pentagonal bipyramid (as in  $\text{IF}_7$ ). (A capped octahedron has a lone pair pointing through one of the faces of the octahedron.) Since there are six bonds and one lone pair, a capped octahedron would give a distorted octahedral molecule. The molecular orbital approach fails with  $\text{XeF}_6$ , since three three-centre molecular orbital systems mutually at right angles would give a regular octahedral shape.

The vibrational spectrum of gaseous  $\text{XeF}_6$  indicates  $C_{3v}$  symmetry, i.e. an octahedron distorted by the lone pair at the centre of one triangular face. The structure of the molecule rapidly fluctuates between structures where the lone pair occupies each of the eight triangular faces. In various non-aqueous solvents, xenon hexafluoride forms a tetramer  $\text{Xe}_4\text{F}_{24}$ . Solid xenon hexafluoride is polymorphic. Except at very low temperatures it contains tetramers, where four square pyramidal  $\text{XeF}_5^+$  ions are joined to two similar ions by means of two bridging  $\text{F}^-$  ions. The  $\text{XeF}$  distances are 1.84 Å on the square pyramidal units and 2.23 Å and 2.60 Å in the bridging groups.

The shapes of oxygen containing compounds of Xe are correctly predicted by the valence bond method. (Electrons in  $\pi$  bonds (double bonds) must be subtracted before counting the number of electron pairs which determine the primary shape of the molecule.)

## VALEDICTION

For many years the noble gases were thought to be completely unreactive. This was associated with the concept that an octet of electrons is the only stable arrangement. The octet rule has done much to help the understanding of why atoms react, how many bonds they will form, and the shape of the periodic table. The discovery of the noble gas compounds has shown that though the 'octet' arrangement is very stable, it can be broken, and that there are other stable arrangements of electrons.

Two important points emerge:

1. Only the heavier noble gases (Kr, Xe and Rn) form these compounds.  
This is related to their lower ionization energies.
2. Compounds are only formed with electronegative ligands.




Figure 17.6 Capped octahedron.




Figure 17.7 Structures of some xenon compounds

The discovery of the noble gas compounds led to a flurry of practical work attempting the synthesis of new compounds. There was also much theoretical work attempting to explain the structure and bonding in these compounds. This involved calculations on large computers on the extent of  $d$  orbital participation in bonding by elements in the  $s$ - and  $p$  blocks. These conclusions may be summarized as follows:

- 1 In compounds of high coordination number with elements of high electronegativity, such as  $\text{PF}_5$ ,  $\text{SF}_6$ ,  $\text{IF}_5$  and  $\text{XeF}_6$ , the  $d$  orbitals appear to be significantly involved in  $\sigma$  bonding. (These compounds may all be described without using  $d$  orbitals if three-centre bonds are formed.)
- 2 In compounds with elements of low electronegativity such as  $\text{H}_2\text{S}$  and  $\text{PH}_3$ , the  $d$  orbital population is very low (1–2%). However, this small contribution considerably improves the agreement between the observed and calculated values for the dipole moments and the energy levels.
- 3 The use of  $d$  orbitals makes a very significant contribution to  $\pi$  bonds for example  $p\pi-d\pi$  bonding in the phosphates and oxoacids of sulphur, and in  $\text{PF}_3$ .

## FURTHER READING

- Bartlett, N. (1962) Xenon hexafluoroplatinate(V),  $\text{Xe}^+[\text{PtF}]^-$ , *Proc. Chem. Soc.*, 218. (The original paper on the first true noble gas compound.)
- Bartlett, N. (1971) *The Chemistry of the Noble Gases*, Elsevier, Amsterdam.
- Bartlett, N. and Sladky, F.E. (1973) *Comprehensive Inorganic Chemistry*, Vol. I (Chapter 6: The chemistry of the krypton, xenon and radon), Pergamon Press, Oxford.
- Berecz, E. and Balla-Ach, S.M. (1984) *Gas Hydrates* (Studies in Inorganic Chemistry, Vol. 4), Elsevier, Oxford.
- Cockett, A.H. and Smith, K.C. (1973) *Comprehensive Inorganic Chemistry*, Vol. I (Chapter 5: The monatomic gases: physical properties and production), Pergamon Press, Oxford.
- Hawkins, D.T., Falconer, W.E. and Bartlett, N. (1978) *Noble Gas Compounds*, Plenum Press, London. (Contains references from 1962 to 1976.)
- Holloway, J.H. (1987) Twenty-five years of noble gas chemistry, *Chemistry in Britain*, 23, 658–672.
- Holloway, J.H. and Laycock, D. (1983) Preparations and reactions of inorganic main-group oxide fluorides, *Adv. Inorg. Chem. Radiochem.*, 27, 157–195.
- Huston, J.L. (1982) Chemical and physical properties of some xenon compounds, *Inorg. Chem.*, 21, 685–688.
- Moody, G.J. (1974) A decade of xenon chemistry, *J. Chem. Ed.*, 51, 628.
- Selig, H. and Holloway, J.H. (1984) *Topics in Current Chemistry*, Cationic and anionic complexes of the noble gases, (ed. by Bosche, F.L.), Springer Verlag, 124, 33.
- Seppelt, K. and Lentz, D. (1982) Novel developments in noble gas chemistry, *Progr. Inorg. Chem.*, 29, 167–202.
- Thompson, R. (ed.) (1986) *The Modern Inorganic Chemicals Industry*, (Chapter by Grant W.J. and Redfearn, S.L., Industrial Gases), Special Publication No. 31, The Chemical Society, London. (reprinted 1986).
- Wilks, J. and Betts, D.S. (1987) *An Introduction to Liquid Helium*, 2nd ed., Clarendon, Oxford.

## PROBLEMS

1. Where did the helium present in the earth and its atmosphere come from? How is He obtained commercially, and what is it used for? What is the boiling point of He in °C and K?
2. How much argon is present in the earth's atmosphere? How is Ar obtained commercially, and what is it used for?
3. Explain why Ar is used in the Kroll process to extract Ti, for welding, and in electric light bulbs.
  - (a) Draw the structures of  $\text{XeF}_2$ ,  $\text{XeF}_4$  and  $\text{XeF}_6$ .
  - (b) How may these compounds be prepared from Xe?
  - (c) Give balanced equations to show how these three compounds react with water.
4. How did Bartlett interpret the reaction between Xe and  $\text{PtF}_6$ , and how is this reaction now interpreted?
5.
  - (a) Draw the structures of  $\text{XeF}_2$ ,  $\text{XeF}_4$  and  $\text{XeF}_6$ .
  - (b) How may these compounds be prepared from Xe?

- (c) Give balanced equations to show how these three compounds react with water
- 6 How may the compounds  $\text{XeO}_3$ ,  $\text{XeOF}_4$  and  $\text{Ba}_2\text{XeO}_6$  be prepared, and what are their structures?
  - 7 'In some ways the discovery of the noble gas compounds has created more problems than it has solved' Discuss this statement with particular reference to the stability of a closed electron shell and the participation of *d* orbitals in bonding by elements of the *s*- and *p*-blocks
  - 8 Suggest reasons why the only binary compounds of the noble gases are fluorides and oxides of Kr, Xe and Rn

# The *d*-Block Elements

## Part Four

# An introduction to the transition elements

18

Table 18.1 The elements

Group									
3	4	5	6	7	8	9	10	11	12
Sc Scandium	Ti Titanium	V Vanadium	Cr Chromium	Mn Manganese	Fe Iron	Co Cobalt	Ni Nickel	Cu Copper	Zn Zinc
Y Yttrium	Zr Zirconium	Nb Niobium	Mo Molybdenum	Tc Technetium	Ru Ruthenium	Rh Rhodium	Pd Palladium	Ag Silver	Cd Cadmium
La Lanthanum	Hf Hafnium	Ta Tantalum	W Tungsten	Re Rhenium	Os Osmium	Ir Iridium	Pt Platinum	Au Gold	Hg Mercury
Ac Actinium									

## INTRODUCTION

Three series of elements are formed by filling the  $3d$ ,  $4d$  and  $5d$  shells of electrons. Together these comprise the  $d$ -block elements. They are often called 'transition elements' because their position in the periodic table is between the  $s$ -block and  $p$ -block elements. Their properties are transitional between the highly reactive metallic elements of the  $s$ -block, which typically form ionic compounds, and the elements of the  $p$ -block, which are largely covalent. In the  $s$ - and  $p$ -blocks, electrons are added to the outer shell of the atom. In the  $d$ -block, electrons are added to the penultimate shell, expanding it from 8 to 18 electrons. Typically the transition elements have an incompletely filled  $d$  level. Group 12 (the zinc group) has a  $d^{10}$  configuration and since the  $d$  shell is complete, compounds of these elements are not typical and show some differences from the others. The elements make up three complete rows of ten elements and an incomplete fourth row. The position of the incomplete fourth series is discussed with the  $f$ -block elements.


## METALLIC CHARACTER

In the  $d$  block elements the penultimate shell of electrons is expanding. Thus they have many physical and chemical properties in common. Thus all the transition elements are metals. They are therefore good conductors of electricity and heat, have a metallic lustre and are hard, strong and ductile. They also form alloys with other metals.

## VARIABLE OXIDATION STATE

One of the most striking features of the transition elements is that the elements usually exist in several different oxidation states. Furthermore, the oxidation states change in units of one, e.g.  $\text{Fe}^{3+}$  and  $\text{Fe}^{2+}$ ,  $\text{Cu}^{2+}$  and  $\text{Cu}^{+}$ .

The oxidation states shown by the transition elements may be related to their electronic structures. Calcium, the  $s$ -block element preceding the first row of transition elements, has the electronic structure



It might be expected that the next ten transition elements would have this electronic arrangement with from one to ten  $d$  electrons added in a regular way  $3d^1, 3d^2, 3d^3 \dots 3d^{10}$ . This is true except in the cases of Cr and Cu. In these two cases one of the  $s$  electrons moves into the  $d$  shell, because of the additional stability when the  $d$  orbitals are exactly half filled or completely filled (Table 18.2).

Table 18.2 Oxidation states

	Sc	Ti	V	Cr	Mn	Fe	Co	Ni	Cu	Zn
Electronic structure	$d^1 s^2$	$d^2 s^2$	$d^3 s^2$	<del><math>d^4 s^2</math></del> $d^5 s^1$	$d^5 s^2$	$d^6 s^2$	$d^7 s^2$	$d^8 s^2$	<del><math>d^9 s^2</math></del> $d^{10} s^1$	$d^{10} s^2$
Oxidation states	II III	II III IV	II III IV IV	I II III IV V VI	II III IV V VI VII	II III IV V VI	II III IV V	II III IV	I II III	II

Thus Sc could have an oxidation number of (+II) if both  $s$  electrons are used for bonding and (+III) when two  $s$  and one  $d$  electrons are involved. Ti has an oxidation state (+II) when both  $s$  electrons are used for bonding, (+III) when two  $s$  and one  $d$  electrons are used and (+IV) when two  $s$  and two  $d$  electrons are used. Similarly, V shows oxidation numbers (+II), (+III), (+IV) and (+V). In the case of Cr, by using the single  $s$  electron for bonding, we get an oxidation number of (+I) hence by using varying


numbers of  $d$  electrons oxidation states of (+II), (+III), (+IV), (+V) and (+VI) are possible. Mn has oxidation states (+II), (+III), (+IV), (+V), (+VI) and (+VII). Among these first five elements, the correlation between electronic structure and minimum and maximum oxidation states in simple compounds is complete. In the highest oxidation states of these first five elements, all of the  $s$  and  $d$  electrons are being used for bonding. Thus the properties depend only on the size and valency, and consequently show some similarities with elements of the main groups in similar oxidation states. For example,  $\text{SO}_4^{2-}$  (Group 16) and  $\text{CrO}_4^{2-}$  (Group 6) are isostructural, as are  $\text{SiCl}_4$  (Group 14) and  $\text{TiCl}_4$  (Group 4).

Once the  $d^5$ -configuration is exceeded, i.e. in the last five elements, the tendency for all the  $d$  electrons to participate in bonding decreases. Thus Fe has a maximum oxidation state of (+VI). However, the second and third elements in this group attain a maximum oxidation state of (+VIII), in  $\text{RuO}_4$  and  $\text{OsO}_4$ . This difference between Fe and the other two elements Ru and Os is attributed to the increased size.

These facts may be conveniently memorized, because the oxidation states form a regular 'pyramid' as shown in Table 18.2. Only Sc(+II) and Co(+V) are in doubt. The oxidation number of all elements in the elemental state is zero. In addition, several of the elements have zero-valent and other low-valent states in complexes. Low oxidation states occur particularly with  $\pi$  bonding ligands such as carbon monoxide and dipyriddy.


Similar but not identical pyramids of oxidation states are found in the second and third rows of transition elements. The main differences are as follows:

1. In Group 8 (the iron group) the second and third row elements show a maximum oxidation state of (+VIII) compared with (+VI) for Fe.
2. The electronic structures of the atoms in the second and third rows do not always follow the pattern of the first row. The structures of Group 10 elements (the nickel group) are:



Since a full shell of electrons is a stable arrangement, the place where this occurs is of importance.

The  $d$  levels are complete at copper, palladium and gold in their respective series.



Even though the ground state of the atom has a  $d^{10}$  configuration, Pd and the coinage metals Cu, Ag and Au behave as typical transition elements. This is because in their most common oxidation states Cu(II) has a  $d^9$



configuration and Pd(II) and Au(III) have  $d^8$  configurations, that is they have an incompletely filled  $d$  level. However, in zinc, cadmium and mercury the ions  $Zn^{2+}$ ,  $Cd^{2+}$  and  $Hg^{2+}$  have a  $d^{10}$  configuration. Because of this, these elements do not show the properties characteristic of transition elements.

### Stability of the various oxidation states

Compounds are regarded as stable if they exist at room temperature, are not oxidized by the air, are not hydrolysed by water vapour and do not disproportionate or decompose at normal temperatures. Within each of the transition Groups 3–12, there is a difference in stability of the various oxidation states that exist. In general the second and third row elements exhibit higher coordination numbers, and their higher oxidation states are more stable than the corresponding first row elements. This can be seen from Table 18.3. This gives the known oxides and halides of the first, second and third row transition elements. Stable oxidation states form

Table 18.3 (a) Oxides and halides of the first row

	Sc	T	V	Cr	Mn	Fe	Co	Ni	Cu	Zn
+II	O F Cl Br I	TO TiO TiCl TiBr TiI	VO <sup>m</sup> VF VCl VBr VI	CrO CrF <sub>2</sub> CrCl CrBr CrI	MnO MnF <sub>2</sub> MnCl <sub>2</sub> MnBr <sub>2</sub> MnI <sub>2</sub>	FeO FeF FeCl <sub>2</sub> FeBr <sub>2</sub> FeI <sub>2</sub>	CoO CoF <sub>2</sub> CoCl CoBr <sub>2</sub> CoI <sub>2</sub>	NiO NiF <sub>2</sub> NiCl <sub>2</sub> NiBr <sub>2</sub> NiI <sub>2</sub>	CuO CuF <sub>2</sub> CuCl CuBr CuI <sub>2</sub>	ZnO ZnF <sub>2</sub> ZnCl <sub>2</sub> ZnBr <sub>2</sub> ZnI <sub>2</sub>
+III	O F Cl Br I	Sc <sub>2</sub> O <sub>3</sub> ScF <sub>3</sub> ScCl <sub>3</sub> ScBr <sub>3</sub> ScI <sub>3</sub>	TiO TiF <sub>3</sub> TiCl TiBr TiI	VO VF <sub>3</sub> VCl <sub>3</sub> VBr <sub>3</sub> VI <sub>3</sub>	Cr <sub>2</sub> O <sub>3</sub> CrF CrCl <sub>3</sub> CrBr <sub>3</sub> CrI <sub>3</sub>	MnO MnF <sub>3</sub>	FeO <sub>3</sub> FeF FeCl FeBr	(CoO) <sup>h</sup> C F	(NiO) <sup>h</sup>	
+IV	O F Cl Br I		TiO <sub>2</sub> TiF <sub>4</sub> TiCl <sub>4</sub> TiBr <sub>4</sub> TiI <sub>4</sub>	VO VF <sub>2</sub> VCl <sub>2</sub> VBr VI <sub>2</sub>	CrO CrF CrCl <sub>2</sub> CrBr CrI <sub>2</sub>	MnO MnF <sub>2</sub>	(CoO) <sup>h</sup>	NiO <sup>h</sup>		
+V	O F Cl Br I			VO VF CrF <sub>3</sub>						
+VI	O F Cl Br I			CrO (CrF <sub>6</sub> )						
+VII	O F Cl Br I				MnO					
Other compounds					MnO	FeO <sub>2</sub>	CoO <sub>2</sub>		CuO CuCl CuBr CuI	

## (b) Oxides and halides of the second row

	Y	Zr	Nb	Mo	Tc	Ru	Rh	Pd	Ag	Cd
+II	O		NbO				RhO	PdO	AgO <sup>s</sup>	CdO
	F							PdF <sub>2</sub>	AgF <sub>2</sub>	CdF <sub>2</sub>
	Cl	ZrCl <sub>2</sub>		[Mo <sub>6</sub> Cl <sub>8</sub> ]Cl <sub>4</sub> <sup>c</sup>				PdCl <sub>2</sub>		CdCl <sub>2</sub>
	Br	ZrBr <sub>2</sub> ?		[Mo <sub>6</sub> Br <sub>8</sub> ]Br <sub>4</sub> <sup>c</sup>				PdBr <sub>2</sub>		CdBr <sub>2</sub>
	I	ZrI <sub>2</sub> ?		[Mo <sub>6</sub> I <sub>8</sub> ]I <sub>4</sub> <sup>c</sup>				PdI <sub>2</sub>		CdI <sub>2</sub>
+III	O	Y <sub>2</sub> O <sub>3</sub>				Ru <sub>2</sub> O <sub>3</sub> <sup>h</sup>	Rh <sub>2</sub> O <sub>3</sub>	(Pd <sub>2</sub> O <sub>3</sub> ) <sup>h</sup> ?	(Ag <sub>2</sub> O <sub>3</sub> )	
	F	YF <sub>3</sub>	(NbF <sub>3</sub> ) <sup>c</sup>	MoF <sub>3</sub>		RuF <sub>3</sub>	RhF <sub>3</sub>	Pd[PdF <sub>6</sub> ]		
	Cl	YCl <sub>3</sub>	ZrCl <sub>3</sub>	NbCl <sub>3</sub> <sup>c</sup>		RuCl <sub>3</sub>	RhCl <sub>3</sub>			
	Br	YBr <sub>3</sub>	ZrBr <sub>3</sub>	NbBr <sub>3</sub> <sup>c</sup>		RuBr <sub>3</sub>	RhBr <sub>3</sub>			
	I	YI <sub>3</sub>	ZrI <sub>3</sub>	NbI <sub>3</sub> <sup>c</sup>		RuI <sub>3</sub>	RhI <sub>3</sub>			
+IV	O		ZrO <sub>2</sub>	NbO <sub>2</sub>	MoO <sub>2</sub> <sup>m</sup>	TcO <sub>2</sub> <sup>m</sup>	RuO <sub>2</sub>	RhO <sub>2</sub>	(PdO <sub>2</sub> ) <sup>h</sup>	
	F		ZrF <sub>4</sub>	NbF <sub>4</sub>	MoF <sub>4</sub>		RuF <sub>4</sub>	RhF <sub>4</sub>	PdF <sub>4</sub>	
	Cl		ZrCl <sub>4</sub>	NbCl <sub>4</sub> <sup>m</sup>	MoCl <sub>4</sub> <sup>m</sup>	TcCl <sub>4</sub>	RuCl <sub>4</sub>			
	Br		ZrBr <sub>4</sub>	NbBr <sub>4</sub> <sup>m</sup>	MoBr <sub>4</sub>					
	I		ZrI <sub>4</sub>	NbI <sub>4</sub> <sup>m</sup>	MoI <sub>4</sub> ?					
+V	O			Nb <sub>2</sub> O <sub>5</sub>	Mo <sub>2</sub> O <sub>5</sub>					
	F			NbF <sub>5</sub>	MoF <sub>5</sub>	TcF <sub>5</sub>	RuF <sub>5</sub>	(RhF <sub>5</sub> )		
	Cl			NbCl <sub>5</sub>	MoCl <sub>5</sub>					
	Br			NbBr <sub>5</sub>						
	I			NbI <sub>5</sub>						
+VI	O				MoO <sub>3</sub>	TcO <sub>3</sub>	(RuO <sub>3</sub> ) <sup>h</sup>			
	F				MoF <sub>6</sub>	TcF <sub>6</sub>	RuF <sub>6</sub>	RhF <sub>6</sub>		
	Cl				(MoCl <sub>6</sub> )	(TcCl <sub>6</sub> )?				
	Br									
	I									
+VII	O				Tc <sub>2</sub> O <sub>7</sub>					
	F									
	Cl									
	Br									
	I									
Other compounds			Nb <sub>6</sub> F <sub>14</sub> <sup>c</sup>			RuO <sub>4</sub>			Ag <sub>2</sub> O	
			Nb <sub>6</sub> I <sub>14</sub> <sup>c</sup>						AgF	
									AgCl	
									AgBr	
									AgI	

oxides, fluorides, chlorides, bromides and iodides. Strongly reducing states probably do not form fluorides and/or oxides, but may well form the heavier halides. Conversely, strongly oxidizing states form oxides and fluorides, but not iodides.

## COMPLEXES

A The transition elements have an unparalleled tendency to form coordination compounds with Lewis bases, that is with groups which are able to donate an electron pair. These groups are called ligands. A ligand may be a neutral molecule such as NH<sub>3</sub>, or an ion such as Cl<sup>-</sup> or CN<sup>-</sup>. Cobalt forms more complexes than any other element, and forms more compounds than any other element except carbon.





Table 18.3 (continued) (c) Oxides and halides of the third row

	La	Hf	Ta	W	Re	Os	Ir	Pt	Au	Hg
+II	O		(TaO)					(PtO) <sup>h</sup>		HgO
	F									HgF
	Cl	HfCl <sup>g</sup>		W <sub>6</sub> Cl <sup>c</sup>	(ReCl) <sup>g</sup>		(IrCl) <sup>g</sup>	PtCl <sub>2</sub>		HgCl
	Br	HfBr <sup>g</sup>		W <sub>6</sub> Br <sup>c</sup>	(ReBr) <sup>g</sup>			PtBr <sub>2</sub>		HgBr
	I			W <sub>6</sub> I <sup>c</sup>	(ReI) <sup>g</sup>			PtI <sub>2</sub>		HgI
+III	O	La <sub>2</sub> O <sub>3</sub>			Re <sub>2</sub> O <sub>7</sub> <sup>h</sup>		Ir <sub>2</sub> O <sub>3</sub> <sup>h</sup>	(Pt <sub>2</sub> O) <sup>h,g</sup>	Au <sub>2</sub> O	
	F	LaF <sub>3</sub>	(TaF <sub>5</sub> )				IrF <sub>3</sub>		AuF <sub>3</sub>	
	Cl	LaCl <sub>3</sub>	TaCl <sub>5</sub>	W <sub>6</sub> Cl <sub>14</sub> <sup>x</sup>	ReCl <sub>5</sub> <sup>g</sup>		IrCl <sub>3</sub>	PtCl <sub>4</sub> <sup>g</sup>	AuCl <sub>3</sub>	
	Br	LaBr <sub>3</sub>	TaBr <sub>5</sub>	W <sub>6</sub> Br <sub>14</sub> <sup>x</sup>	ReBr <sub>5</sub> <sup>g</sup>		IrBr <sub>3</sub>	PtBr <sub>4</sub> <sup>g</sup>	AuBr <sub>3</sub>	
	I	LaI <sub>3</sub>	HI	W <sub>6</sub> I <sub>14</sub> <sup>x</sup>	ReI <sub>5</sub> <sup>g</sup>		IrI <sub>3</sub>	PtI <sub>4</sub>		
+IV	O		HfO <sub>2</sub>	Ta <sub>2</sub> O <sub>5</sub>	WO <sub>3</sub> <sup>m</sup>	ReO <sub>3</sub> <sup>m</sup>	OsO <sub>2</sub>	IrO <sub>2</sub>	PtO <sub>2</sub>	
	F		HfF <sub>2</sub>		WF <sub>6</sub>	ReF <sub>4</sub>	OsF <sub>4</sub>	IrF <sub>4</sub>	PtF <sub>4</sub>	
	Cl		HfCl <sub>3</sub>	TaCl <sub>4</sub> <sup>m</sup>	WCl <sub>4</sub>	ReCl <sub>4</sub> <sup>m</sup>	OsCl <sub>4</sub>	(IrCl <sub>4</sub> )	PtCl <sub>4</sub>	
	Br		HfBr <sub>3</sub>	TaBr <sub>4</sub> <sup>m</sup>	WBr <sub>4</sub>	ReBr <sub>4</sub>	OsBr <sub>4</sub>		PtBr <sub>4</sub>	
	I		HfI <sub>3</sub>	TaI <sub>4</sub> <sup>m</sup>	WI <sub>4</sub> <sup>g</sup>	ReI <sub>4</sub>	OsI <sub>4</sub>		PtI <sub>4</sub>	
+V	O		Ta <sub>2</sub> O <sub>5</sub>	(W <sub>6</sub> O) <sup>g</sup>	(Re <sub>2</sub> O) <sup>g</sup>					
	F		TaF <sub>5</sub>	WF <sub>6</sub> <sup>d</sup>	ReF <sub>5</sub>	OsF <sub>5</sub>	(IrF <sub>5</sub> )	(PtF <sub>5</sub> ) <sub>2</sub>		
	Cl		TaCl <sub>5</sub>	WCl <sub>5</sub>	ReCl <sub>5</sub>	OsCl <sub>5</sub>				
	Br		TaBr <sub>5</sub>	WBr <sub>5</sub>	ReBr <sub>5</sub>					
	I		TaI <sub>5</sub>							
+VI	O			WO <sub>3</sub>	ReO <sub>3</sub>	(OsO <sub>3</sub> ) <sup>h</sup>	(IrO <sub>3</sub> )	(PtO <sub>3</sub> ) <sup>h</sup>		
	F			WF <sub>6</sub>	ReF <sub>6</sub>	OsF <sub>6</sub>	IrF <sub>6</sub>	PtF <sub>6</sub>		
	Cl			WCl <sub>6</sub>	(ReCl <sub>6</sub> )					
	Br			WBr <sub>6</sub>						
	I									
+VII	O				Re <sub>2</sub> O <sub>7</sub>					
	F				ReF <sub>7</sub>	(O <sub>2</sub> F <sub>2</sub> )				
	Cl									
	Br									
	I									
Other compounds						OsO <sub>4</sub> OsCl <sub>4</sub>		PtO	AuO AuCl AuI	HgF <sup>m</sup> HgCl <sup>m</sup> HgBr <sup>m</sup> HgI <sup>m</sup>

In Table 18.3 the most stable compounds are bold unstable compounds are in parentheses h indicates hydrated oxides g indicates that it occurs only as a gas m indicates metal-metal bonding c indicates cluster compounds, x indicates mixed oxide and d indicates that it disproportionates

This ability to form complexes is in marked contrast to the *s*- and *p*-block elements which form only a few complexes. The reason transition elements are so good at forming complexes is that they have small, highly charged ions and have vacant low energy orbitals to accept lone pairs of electrons donated by other groups or ligands. Complexes where the metal is in the (+III) oxidation state are generally more stable than those where the metal is in the (+II) state.

Some metal ions form their most stable complexes with ligands in which the donor atoms are N, O or F. Such metal ions include Group 1 and 2 elements, the first half of the transition elements, the lanthanides and actinides, and the *p*-block elements except for their heaviest member. These metals are called class-a acceptors, and correspond to 'hard acids' (see 'Acids and bases', Chapter 8). In contrast the metals Rh, Ir, Pd, Pt, Ag, Au and Hg form their most stable complexes with the heavier

elements of Groups 15, 16 and 17. These metals are called class-b acceptors, and correspond to 'soft' acids. The rest of the transition metals, and the heaviest elements in the *p*-block, form complexes with both types of donors, and are thus 'intermediate' in nature. These are shown (a/b) in Table 18.4.

Table 18.4 Class-a and class-b acceptors

Li (a)	Be (a)												B (a)	C (a)	N (a)	O
Na (a)	Mg (a)												Al (a)	Si (a)	P (a)	S (a)
K (a)	Ca (a)	Sc (a)	Ti (a)	V (a)	Cr (a)	Mn (a)	Fe (a/b)	Co (a/b)	Ni (a/b)	Cu (a/b)	Zn (a)	Ga (a)	Ge (a)	As (a)	Se (a)	
Rb (a)	Sr (a)	Y (a)	Zr (a)	Nb (a)	Mo (a)	Tc (a/b)	Ru (a/b)	Rh (b)	Pd (b)	Ag (b)	Cd (a/b)	In (a)	Sn (a)	Sb (a)	Te (a)	
Cs (a)	Ba (a)	La (a)	Hf (a)	Ta (a)	W (a)	Re (a/b)	Os (a/b)	Ir (b)	Pt (b)	Au (b)	Hg (b)	Tl (a/b)	Pb (a/b)	Bi (a/b)	Po (a/b)	
Fr (a)	Ra (a)	Ac (a)														
			Ce (a)	Pr (a)	Nd (a)	Pm (a)	Sm (a)	Eu (a)	Gd (a)	Tb (a)	Dy (a)	Ho (a)	Er (a)	Tm (a)	Yb (a)	
			Th (a)	Pa (a)	U (a)	Np (a)	Pu (a)	Am (a)	Cm (a)	Bk (a)	Cf (a)	Es (a)	Fm (a)	Md (a)	Mo (a)	

The nature of coordination complexes and the important crystal field theory of bonding are discussed in Chapter 7.


## SIZE OF ATOMS AND IONS

The covalent radii of the elements (Table 18.5) decrease from left to right across a row in the transition series, until near the end when the size increases slightly. On passing from left to right, extra protons are placed in the nucleus and extra orbital electrons are added. The orbital electrons shield the nuclear charge incompletely (*d* electrons shield less efficiently than *p* electrons, which in turn shield less effectively than *s* electrons). Because of this poor screening by *d* electrons, the nuclear charge attracts all of the electrons more strongly; hence a contraction in size occurs.

Atoms of the transition elements are smaller than those of the Group 1 or 2 elements in the same horizontal period. This is partly because of the usual contraction in size across a horizontal period discussed above, and

Table 18.5 Covalent radii of the transition elements (Å)

K 1.57	Ca 1.74	Sc 1.44	Ti 1.32	V 1.22	Cr 1.17	Mn 1.17	Fe 1.17	Co 1.16	Ni 1.15	Cu 1.17	Zn 1.25
Rb 2.16	Sr 1.91	Y 1.62	Zr 1.45	Nb 1.34	Mo 1.29	Tc -	Ru 1.24	Rh 1.25	Pd 1.28	Ag 1.34	Cd 1.41
Cs 2.35	Ba 1.98	La 1.69	Hf 1.44	Ta 1.34	W 1.30	Re 1.28	Os 1.26	Ir 1.26	Pt 1.29	Au 1.34	Hg 1.44



 14 Lanthanide elements

partly because the orbital electrons are added to the penultimate  $d$  shell rather than to the outer shell of the atom.

The transition elements are divided into vertical groups of three (triads) or sometimes four elements, which have similar electronic structures. On descending one of the main groups of elements in the  $s$ - and  $p$ -blocks, the size of the atoms increases because extra shells of electrons are present. The elements in the first group in the  $d$  block (Group 3) show the expected increase in size  $\text{Sc} \rightarrow \text{Y} \rightarrow \text{La}$ . However, in the subsequent Groups (3–12) there is an increase in radius of  $0.1 \rightarrow 0.2 \text{ Å}$  between the first and second member but hardly any increase between the second and third elements. This trend is shown both in the covalent radii (Table 18.5) and in the ionic radii (Table 18.6). Interposed between lanthanum and hafnium are the 14 lanthanide elements in which the antepenultimate  $4f$  shell of electrons is filled.

Table 18.6 The effect of the lanthanide contraction on ionic radii

$\text{Ca}^{2+}$ 1.00	$\text{Sc}^{3+}$ 0.745	$\text{Ti}^{4+}$ 0.605	$\text{V}^{5+}$ 0.64
$\text{Sr}^{2+}$ 1.18	$\text{Y}^{3+}$ 0.90	$\text{Zr}^{4+}$ 0.72	$\text{Nb}^{5+}$ 0.72
$\text{Ba}^{2+}$ 1.35	$\text{La}^{3+}$ 1.032	$\text{Hf}^{4+}$ 0.71	$\text{Ta}^{5+}$ 0.72


 14 Lanthanides

There is a gradual decrease in size of the 14 lanthanide elements from cerium to lutetium. This is called the lanthanide contraction, and is discussed in Chapter 29. The lanthanide contraction cancels almost exactly the normal size increase on descending a group of transition elements. The covalent radius of Hf and the ionic radius of  $\text{Hf}^{4+}$  are actually smaller than the corresponding values for Zr. The covalent and ionic radii of Nb are the same as the values for Ta. Therefore the second and third row transition elements have similar radii. As a result they also have similar lattice energies, solvation energies and ionization energies. Thus the differences in properties between the first row and second row elements are much greater than the differences between the second and third row elements. The effects of the lanthanide contraction are less pronounced towards the right of the  $d$  block. However, the effect still shows to a lesser degree in the  $p$  block elements which follow.

## DENSITY

The atomic volumes of the transition elements are low compared with elements in neighbouring Groups 1 and 2. This is because the increased nuclear charge is poorly screened and so attracts all the electrons more strongly. In addition, the extra electrons added occupy inner orbitals. Consequently the densities of the transition metals are high. Practically all have a density greater than  $5 \text{ g cm}^{-3}$ . (The only exceptions are Sc  $3.0 \text{ g cm}^{-3}$  and Y and Ti  $4.5 \text{ g cm}^{-3}$ .) The densities of the second row are high and third row values are even higher. (See Appendix D.) The two elements with the highest densities are osmium  $22.57 \text{ g cm}^{-3}$  and iridium  $22.61 \text{ g cm}^{-3}$ . To get some feel for how high this figure really is, a football made of osmium or iridium measuring 30 cm in diameter would weigh 320 kg or almost one third of a tonne!

## MELTING AND BOILING POINTS

The melting and boiling points of the transition elements are generally very high (see Appendices B and C). Transition elements typically melt above  $1000^\circ\text{C}$ . Ten elements melt above  $2000^\circ\text{C}$  and three melt above  $3000^\circ\text{C}$  (Ta  $3000^\circ\text{C}$ , W  $3410^\circ\text{C}$  and Re  $3180^\circ\text{C}$ ). There are a few exceptions. The melting points of La and Ag are just under  $1000^\circ\text{C}$  ( $920^\circ\text{C}$  and  $961^\circ\text{C}$  respectively). Other notable exceptions are Zn ( $420^\circ\text{C}$ ), Cd ( $321^\circ\text{C}$ ) and Hg which is liquid at room temperature and melts at  $-38^\circ\text{C}$ . The last three behave atypically because the  $d$  shell is complete, and  $d$  electrons do not participate in metallic bonding. The high melting points are in marked contrast to the low melting points for the  $s$ -block metals Li ( $181^\circ\text{C}$ ) and Cs ( $29^\circ\text{C}$ ).

## REACTIVITY OF METALS

Many of the metals are sufficiently electropositive to react with mineral acids, liberating  $\text{H}_2$ . A few have low standard electrode potentials and remain unreactive or noble. Noble character is favoured by high enthalpies of sublimation, high ionization energies and low enthalpies of solvation. (See 'Born-Haber cycle', Chapter 6.) The high melting points indicate high heats of sublimation. The smaller atoms have higher ionization energies, but this is offset by small ions having high solvation energies. This tendency to noble character is most pronounced for the platinum metals (Ru, Rh, Pd, Os, Ir, Pt) and gold.

## IONIZATION ENERGIES

The ease with which an electron may be removed from a transition metal atom (that is, its ionization energy) is intermediate between those of the  $s$ - and  $p$ -blocks. Values for the first ionization energies vary over a wide range from  $541 \text{ kJ mol}^{-1}$  for lanthanum to  $1007 \text{ kJ mol}^{-1}$  for mercury.

These are comparable with the values for lithium and carbon respectively. This would suggest that the transition elements are less electropositive than Groups 1 and 2 and may form either ionic or covalent bonds depending on the conditions. Generally, the lower valent states are ionic and the higher valent states covalent. The first row elements have many more ionic compounds than elements in the second and third rows.

## COLOUR

Many ionic and covalent compounds of transition elements are coloured. In contrast compounds of the *s*- and *p*-block elements are almost always white. When light passes through a material it is deprived of those wavelengths that are absorbed. If absorption occurs in the visible region of the spectrum, the transmitted light is coloured with the complementary colour to the colour of the light absorbed. Absorption in the visible and UV regions of the spectrum is caused by changes in electronic energy. Thus the spectra are sometimes called electronic spectra. (These changes are often accompanied by much smaller changes in vibrational and rotational energy.) It is always possible to promote an electron from one energy level to another. However, the energy jumps are usually so large that the absorption lies in the UV region. Special circumstances can make it possible to obtain small jumps in electronic energy which appear as absorption in the visible region.

### Polarization

NaCl, NaBr and NaI are all ionic, and are all colourless. AgCl is also colourless. Thus the halide ions  $\text{Cl}^-$ ,  $\text{Br}^-$  and  $\text{I}^-$ , and the metal ions  $\text{Na}^+$  and  $\text{Ag}^+$  are typically colourless. However, AgBr is pale yellow and AgI is yellow. The colour arises because the  $\text{Ag}^+$  ion polarizes the halide ions. This means that it distorts the electron cloud and implies a greater covalent contribution. The polarizability of ions increases with size, thus  $\text{I}^-$  is the most polarized and is the most coloured. For the same reason,  $\text{Ag}_2\text{CO}_3$  and  $\text{Ag}_3\text{PO}_4$  are yellow and  $\text{Ag}_2\text{O}$  and  $\text{Ag}_2\text{S}$  are black.

### Incompletely filled *d* or *f* shell

Colour may arise from an entirely different cause in ions with incomplete *d* or *f* shells. This source of colour is very important in most of the transition metal ions.

In a free isolated gaseous ion the five *d* orbitals are degenerate, that is they are identical in energy. In real life situations the ion will be surrounded by solvent molecules if it is in solution, by other ligands if it is in a complex, or by other ions if it is in a crystal lattice. The surrounding groups affect the energy of some *d* orbitals more than others. Thus the *d* orbitals are no longer degenerate, and at their simplest they form two groups of

orbitals of different energy. Thus in transition element ions with a partly filled  $d$  shell it is possible to promote electrons from one  $d$  level to another  $d$  level of higher energy. This corresponds to a fairly small energy difference, and so light is absorbed in the visible region. The colour of a transition metal complex is dependent on how big the energy difference is between the two  $d$  levels. This in turn depends on the nature of the ligand, and on the type of complex formed. Thus the octahedral complex  $[\text{Ni}(\text{NH}_3)_6]^{2+}$  is blue,  $[\text{Ni}(\text{H}_2\text{O})_6]^{2+}$  is green and  $[\text{Ni}(\text{NO}_2)_6]^{4-}$  is brown-red. The colour changes with the ligand used. The colour also depends on the number of ligands and the shape of the complex formed.

The source of colour in the lanthanides and the actinides is very similar, arising from  $f \rightarrow f$  transitions. With the lanthanides the  $4f$  orbitals are deeply embedded inside the atom, and are well shielded by the  $5s$  and  $5p$  electrons. The  $f$  electrons are practically unaffected by complex formation: hence the colour remains almost constant for a particular ion regardless of the ligand. The absorption bands are also very narrow.

Some compounds of the transition metals are white, for example  $\text{ZnSO}_4$  and  $\text{TiO}_2$ . In these compounds it is not possible to promote electrons within the  $d$  level.  $\text{Zn}^{2+}$  has a  $d^{10}$  configuration and the  $d$  level is full.  $\text{Ti}^{4+}$  has a  $d^0$  configuration and the  $d$  level is empty. In the series  $\text{Sc}(+\text{III})$ ,  $\text{Ti}(+\text{IV})$ ,  $\text{V}(+\text{V})$ ,  $\text{Cr}(+\text{VI})$  and  $\text{Mn}(+\text{VII})$ , these ions may all be considered to have an empty  $d$  shell: hence  $d-d$  spectra are impossible and they should be colourless. However, as the oxidation number increases these states become increasingly covalent. Rather than form highly charged simple ions, oxoions are formed  $\text{TiO}^{2+}$ ,  $\text{VO}_2^+$ ,  $\text{VO}_4^{3-}$ ,  $\text{CrO}_4^{2-}$  and  $\text{MnO}_4^-$ .  $\text{VO}_2^+$  is pale yellow, but  $\text{CrO}_4^{2-}$  is strongly yellow coloured, and  $\text{MnO}_4^-$  has an intense purple colour in solution though the solid is almost black. The colour arises by charge transfer. In  $\text{MnO}_4^-$  an electron is momentarily transferred from O to the metal, thus momentarily changing  $\text{O}^{2-}$  to  $\text{O}^-$  and reducing the oxidation state of the metal from  $\text{Mn}(\text{VII})$  to  $\text{Mn}(\text{VI})$ . Charge transfer requires that the energy levels on the two different atoms are fairly close. Charge transfer always produces intense colours since the restrictions of the Laporte and spin selection rules do not apply to transitions between atoms. (See Chapter 32.)

The  $s$ - and  $p$ -block elements do not have a partially filled  $d$  shell so there cannot be any  $d-d$  transitions. The energy to promote an  $s$  or  $p$  electron to a higher energy level is much greater and corresponds to ultraviolet light being absorbed. Thus compounds of  $s$ - and  $p$ -block elements typically are not coloured.

## MAGNETIC PROPERTIES

When a substance is placed in a magnetic field of strength  $H$ , the intensity of the magnetic field in the substance may be greater than or less than  $H$ .

If the field in the substance is greater than  $H$ , the substance is paramagnetic. It is easier for magnetic lines of force to travel through a paramagnetic material than through a vacuum. Thus paramagnetic materials attract lines of force, and, if it is free to move, a paramagnetic



material will move from a weaker to a stronger part of the field. Paramagnetism arises as a result of unpaired electron spins in the atom.

If the field in the substance is less than  $H$ , the substance is diamagnetic. Diamagnetic materials tend to repel lines of force. It is harder for magnetic lines of force to travel through diamagnetic materials than through a vacuum, and such materials tend to move from a stronger to a weaker part of a magnetic field. In diamagnetic compounds all the electron spins are paired. The paramagnetic effect is much larger than the diamagnetic effect.

It should be noted that Fe, Co and Ni are ferromagnetic. Ferromagnetic materials may be regarded as a special case of paramagnetism in which the moments on individual atoms become aligned and all point in the same direction. When this happens the magnetic susceptibility is greatly enhanced compared with what it would be if all the moments behaved independently. Alignment occurs when materials are magnetized, and Fe, Co and Ni can form permanent magnets. Ferromagnetism is found in several of the transition metals and their compounds. It is also possible to get antiferromagnetism by pairing the moments on adjacent atoms which point in opposite directions. This gives a magnetic moment less than would be expected for an array of independent ions. It occurs in several simple salts of  $\text{Fe}^{3+}$ ,  $\text{Mn}^{2+}$  and  $\text{Gd}^{3+}$ . Since ferromagnetism and antiferromagnetism depend on orientation, they disappear in solution.

Many compounds of the transition elements are paramagnetic, because they contain partially filled electron shells. If the magnetic moment is measured, the number of unpaired electrons can be calculated. The magnetochemistry of the transition elements shows whether the  $d$  electrons are paired. This is of great importance in distinguishing between *high spin* and *low spin* octahedral complexes.

There are two common methods of measuring magnetic susceptibilities: the Faraday and the Gouy methods. The Faraday method is useful for measurements on a very small single crystal, but there are practical difficulties because the forces are very small. The Gouy method is more often used. Here the sample may be presented as a long rod of material, a solution, or a glass tube packed with powder. One end of the sample is placed in a uniform magnetic field and the other end in a very low or zero field. The forces observed here are much larger, and can be measured using a modified laboratory balance.

The volume susceptibility  $\kappa_v$  of a compound is measured using a magnetic balance (Gouy balance).  $\kappa_v$  is dimensionless and is readily converted into the molar susceptibility  $\chi_M$ , which has units  $\text{m}^3 \text{mol}^{-1}$ . From this the magnetic moment of the compound  $\mu$  can be calculated if the small diamagnetic contribution is ignored:

$$\mu^2 = \frac{3kT\chi_M}{N^0\mu_0}$$

where  $k$  is the Boltzmann constant ( $1.3805 \times 10^{-23} \text{J K}^{-1}$ )

$\mu_0$  is the permeability of free space ( $4\pi \times 10^{-7} \text{H m}^{-1}$ )

$T$  is the absolute temperature and  $N^0$  is the Avogadro constant

Thus  $\mu$  has SI units  $\text{JT}^{-1}$ , and

$$\mu = \sqrt{(3k)/(N^\circ \mu_o)} \cdot \sqrt{\chi_M T}$$

It is convenient to express the magnetic moment  $\mu$  in units of Bohr magnetons  $\mu_B$ , where

$$\mu_B = \frac{eh}{4\pi m_e} = 9.273 \times 10^{-24} \text{JT}^{-1}$$

where  $e$  is the electronic charge,  $h$  is Planck's constant and  $m_e$  is the mass of an electron.

Thus the magnetic moment in Bohr magnetons becomes.

$$\frac{\mu}{\mu_B} = \text{constant} \cdot \sqrt{\chi_M \cdot T} \quad (18.1)$$

where  $\text{constant} = \sqrt{(3k)/(N^\circ \mu_o)}/\mu_B = 797.5 \text{ m}^{3/2} \text{ mol}^{-1/2} \text{ K}^{1/2}$

The magnetic moment  $\mu$  of a transition metal can give important information about the number of unpaired electrons present in the atom and the orbitals that are occupied, and sometimes indicates the structure of the molecule or complex. If the magnetic moment is due entirely to the spin of unpaired electrons  $\mu_S$ , then

$$\mu_S = \sqrt{4S(S+1)} \cdot \mu_B$$




Figure 18.1 Diagram of a Gouy magnetic balance

where  $S$  is the total spin quantum number. This gives the magnetic moment in SI units of  $\text{JT}^{-1}$ , and the magnetic moment in Bohr magnetons is given by  $\sqrt{4S(S+1)}$ . This equation is related to the number of unpaired electrons  $n$  by the equation

$$\mu_s \approx \sqrt{n(n+2)} \mu_B$$

The object of the experiment is to determine the volume susceptibility  $\kappa$  by weighing a sample in and out of a magnetic field and calculate in turn the molar susceptibility  $\chi_M$ , the magnetic moment  $\mu$ , the total spin quantum number  $S$  and eventually  $n$  the number of electrons responsible for the paramagnetism.

### Measurement of magnetic moments

Let us examine how  $\mu$  is obtained. First  $\chi_M$  can be determined experimentally. A sample tube which has a narrow diameter and a flat bottom is filled with sample up to the calibration mark. The sample may be a finely divided solid, or a solution. The cross-sectional area of the tube is  $a$ . The sample and tube are weighed in the usual way. Then the apparent mass is measured again by weighing in the presence of a strong magnetic field of force  $H$ . A difference in weight occurs. If  $g$  is the acceleration due to gravity then the force  $F$  acting on the sample is given by

$$F = \Delta m \cdot g \quad (18.2)$$

If  $\kappa_1$  is the volume susceptibility of the sample and  $\kappa_2$  the volume susceptibility of air then

$$F = \frac{1}{2}(\kappa_1 - \kappa_2) a \mu_0 H^2 \quad (18.3)$$

Combining equations (18.2) and (18.3)

$$\Delta m \cdot g = \frac{1}{2}(\kappa_1 - \kappa_2) a \mu_0 H^2$$

hence

$$\kappa_1 = \kappa_2 + \frac{2\Delta m \cdot g}{a \mu_0 H^2}$$

We wish to calculate the volume susceptibility of the sample  $\kappa_1$ . The volume susceptibility of air  $\kappa_2$  is known ( $0.364 \times 10^{-12}$ ) but the field strength  $H$  and cross sectional area  $a$  are not known. Thus we carry out the experiment using a standard whose magnetic susceptibility is known accurately. This allows us to calibrate the apparatus and thus deduce the value of the constant  $a/H^2$ . The complex mercury(II) tetrathiocyanato cobalt(II)  $\text{Hg}[\text{Co}(\text{NCS})_4]$  is often used as a solid standard ( $\chi_M = 206.6 \times 10^{-12} \text{ m}^3 \text{ mol}^{-1}$  at 293 K). Now that the apparatus has been calibrated we use the same sample tube filled up to the same mark and the same magnetic field and measure the weight loss for an unknown compound. The volume susceptibility  $\kappa_1$  of the unknown compound can thus be

obtained. This is readily converted into the molar susceptibility of the compound  $\chi_M$  as follows:

$$\chi_M = \frac{\kappa_1 \cdot M}{D} = \frac{M}{D} \left[ \frac{2\Delta m \cdot g}{a \cdot \mu_0 \cdot H^2} \right]$$

where  $M$  is the molar mass of the compound, and  $D$  is its density.

Diamagnetic materials have no unpaired electrons, and have a magnetic moment  $\mu = 0$ . The external magnetic field induces a small magnetic moment which is in opposition to the external field. Thus diamagnetic materials repel lines of force, and show a slight decrease in weight. In contrast paramagnetism arises where there is one or more unpaired electron in a compound. Paramagnetic materials attract lines of force and increase in weight, because the sample is pulled down into the gap between the pole-pieces of the magnetic balance (see Figure 18.1). For a transition metal complex the weight change measured with the Gouy balance is the sum of the effects from the paramagnetic metal ion and the diamagnetic ligands and ions present. Thus the value of  $\chi_M$  derived from this weight change is the net magnetism, which is the sum of  $\chi_{\text{paramagnetic}} + \chi_{\text{diamagnetic}}$ . Since we wish to measure the paramagnetism of the metal ion, we must make a diamagnetic correction. The easiest way to make the correction for  $\chi_{\text{diamagnetic}}$  is to add up the diamagnetic corrections (sometimes called Pascal's constants) for the atoms and ions in the molecule and contributions from multiple bonds. These data are known (Table 18.7).

$$\chi_{\text{diamagnetic}} = \Sigma \chi_{(\text{atom corrections})} + \Sigma \chi_{(\text{multiple bonds})}$$

Thus  $\chi_{\text{paramagnetic}}$  can be obtained:

$$\chi_{\text{paramagnetic}} = \chi_{\text{measured}} - \chi_{\text{diamagnetic}}$$

Finally  $\chi_{\text{paramagnetic}}$  is converted into magnetic moment of the metal ion in Bohr magnetons using equation 18.1:

$$\frac{\mu}{\mu_B} = 797.5 \cdot \sqrt{\chi_M \cdot T}$$

The unpaired electron gives rise to a magnetic field because of its spin, and also because of the orbital angular momentum. The general equation for the magnetic moments of the first row of transition metal ions is:

$$\mu(S + L) = \sqrt{4S(S + 1) + L(L + 1)} \cdot \mu_B$$

where  $S$  is the total of the spin quantum numbers, and  $L$  is the resultant of the orbital angular momentum quantum numbers of all the electrons in the molecule. (See coupling of orbital angular momenta and coupling of spins in Chapter 32.) For an electron the spin quantum number  $m_s$  has a value of  $\pm \frac{1}{2}$ ; hence  $S = m_s \cdot n$  where  $n$  is the number of unpaired electrons.

In many compounds of the first row transition elements, the orbital contribution is quenched by the electric fields of the surrounding atoms. As a slight approximation the orbital contributions can be ignored and the

Table 18.7 Some diamagnetic corrections (Pascal's constants) (All table values must be multiplied by  $10^{-12}$  Units are  $\text{m}^3 \text{mol}^{-1}$ )

$\text{NH}_4^+$ -167	$\text{OH}^-$ -151	H -36	$\text{C}=\text{C}$ +30
$\text{Li}^+$ -12	$\text{O}^{2-}$ -151	C -75	$\text{C}\equiv\text{N}$ +105
$\text{Na}^+$ -85	$\text{F}^-$ -114	C (aromatic) -79	$\text{C}=\text{O}$ +81
$\text{K}^+$ -187	$\text{Cl}^-$ -294	N -70	$\text{N}=\text{N}$ +23
$\text{Rb}^+$ -269	$\text{Br}^-$ -435	N (aromatic) -59	$\text{N}=\text{O}$ +22
$\text{Cs}^+$ -422	$\text{I}^-$ -636	P(+V) -331	$\text{C}\equiv\text{C}$ +10
$\text{Mg}^{2+}$ -63	$\text{CO}_3^{2-}$ -370	O ether/ROH -58	$\text{C}\equiv\text{N}$ +10
$\text{Ca}^{2+}$ -131	$\text{NO}_3^-$ -126	$\text{O}_2$ (in COOH) -42	
$\text{Cr}^{2+}$ -188	$\text{NO}_2^-$ -326	S -189	
$\text{Cr}^{3+}$ -138	$\text{SO}_3^{2-}$ -478	F -79	
$\text{Mn}^{2+}$ -176	$\text{SO}_4^{2-}$ -503	Cl -253	
$\text{Mn}^{3+}$ -126	$\text{BF}_4^-$ -490	Br -395	
$\text{Fe}^{2+}$ -161	$\text{CN}^-$ -163	I -561	
$\text{Fe}^{3+}$ -126	$\text{CNO}^-$ -264	acetate -402	
$\text{Co}^{2+}$ -161	CNS -390	oxalate -427	
$\text{Co}^{3+}$ -126	$\text{ClO}_2$ -380	ethylenediamine -578	
$\text{Ni}^{2+}$ -161	$\text{ClO}_4^-$ -402	$\text{NH}_3$ -226	
$\text{Cu}^{2+}$ -161	$\text{H}_2\text{O}$ -163	dipyridyl -1319	
$\text{Zn}^{2+}$ -189		$\text{PPh}_3$ -2098	

observed magnetic moment may be considered to arise only from unpaired spins. The *spin-only* magnetic moment  $\mu_s$  may be written

$$\mu_s = \sqrt{4S(S+1)} \mu_B$$

The magnetic moment  $\mu$  (measured in Bohr magnetons BM) is related to the number of unpaired spins  $n$  by the equation

$$\mu_s = \sqrt{n(n+2)} \mu_B$$

The spin only results are shown in Table 18.8. The simple spin-only formula gives good agreement with many *high-spin* complexes of first row transition metals shown in Table 18.9

Table 18.8 Spin only magnetic moments for numbers of unpaired electrons

Number of unpaired electrons $n$	Magnetic moment $\mu_s$ (BM)	Total spin quantum number $S$
1	1.73	1/2
2	2.83	2/2 = 1
3	3.87	3/2
4	4.90	4/2 = 2
5	5.92	5/2

Table 18.9 Magnetic moments of some first row complexes

Ion	Number of unpaired electrons	Experimental magnetic moment (BM)	Calculated magnetic moment spin only formula $\mu_s$ (BM)
Ti <sup>3+</sup>	1	1.7–1.8	1.73
V <sup>3+</sup>	2	2.8–3.1	2.83
Cr <sup>3+</sup>	3	3.7–3.9	3.87
Cr <sup>2+</sup> , Mn <sup>3+</sup>	4	4.8–4.9	4.90
Mn <sup>2+</sup> , Fe <sup>3+</sup>	5	5.7–6.0	5.92
Fe <sup>2+</sup>	4	5.0–5.6	4.90
Co <sup>2+</sup>	3	4.3–5.2	3.87
Ni <sup>2+</sup>	2	2.9–3.9	2.83
Cu <sup>2+</sup>	1	1.9–2.1	1.73

## An example

This is best explained by an example. Magnetic measurements on  $\text{CuSO}_4 \cdot 5\text{H}_2\text{O}$  at 293 K using a Gouy balance gave a value  $\chi_1 = 1.70 \times 10^{-4}$ . The molecular weight is 250.18, so the molar mass  $M$  is  $0.250 \text{ kg mol}^{-1}$ . The density  $D$  is  $2.29 \text{ g cm}^{-3} = 2.29 \times 10^3 \text{ kg m}^{-3}$ . The value for  $\chi_M$  (not corrected for diamagnetic effects) is:

$$\chi_M = \frac{1.70 \times 10^{-4} \times 0.250 \text{ kg mol}^{-1}}{2.29 \times 10^3 \text{ kg m}^{-3}} = 1.858 \times 10^{-8} \text{ mol}^{-1} \text{ m}^3$$

The diamagnetic correction is obtained by adding together the contributions from each of the constituent ions and molecules given in Table 18.7:

$$\begin{array}{rcl}
 \text{Cu}^{2+} & & -161 \times 10^{-12} \\
 \text{SO}_4^{2-} & & -503 \times 10^{-12} \\
 5\text{H}_2\text{O} & 5 \times (-163 \times 10^{-12}) = & -815 \times 10^{-12} \\
 \hline
 \chi_{\text{diamagnetic}} & & -1479 \times 10^{-12} \\
 & \text{or} & -0.148 \times 10^{-8}
 \end{array}$$

The corrected value for  $\chi_M$  is thus:

$$(1.856 + 0.148) \times 10^{-8} \text{ mol}^{-1} \text{ m}^3 = 2.004 \times 10^{-8} \text{ mol}^{-1} \text{ m}^3$$

Using equation (18.1) the true magnetic moment in Bohr magnetons is:

$$\begin{aligned}
 \frac{\mu}{\mu_B} &= 797.5 \sqrt{2.004 \times 10^{-8}} \times 293 \\
 &= 1.93 \text{ Bohr magnetons}
 \end{aligned}$$

Assuming the spin-only formula

$$\mu = \sqrt{n(n+2)} \cdot \mu_B$$

$$\text{If } n = 1 \quad \mu = \sqrt{1(1+2)} \cdot \mu_B = 1.73 \text{ BM}$$

Thus  $\text{Cu}^{2+}$  in  $\text{CuSO}_4 \cdot 5\text{H}_2\text{O}$  has one unpaired electron

Though the agreement for first row transition metal complexes given in Table 18.9 is generally very good, in some cases, for example  $\text{Co}^{2+}$ , the observed value for  $\mu$  is higher than calculated by the spin-only formula. This suggests that there is also an orbital contribution. To have an orbital angular momentum it must be possible to transform an orbital into an equivalent (degenerate) orbital by rotation. It is possible to transform the  $t_{2g}$  orbitals ( $d_{xy}$ ,  $d_{xz}$  and  $d_{yz}$ ) into each other by rotating  $90^\circ$ . It is not possible to transform the  $e_g$  orbitals in this way (e.g. the  $d_{x^2-y^2}$  into the  $d_{z^2}$ ), since they have different shapes. If the  $t_{2g}$  orbitals are all singly occupied, then it is not possible to transform the  $d_{xy}$  into  $d_{xz}$  or  $d_{yz}$  since they already contain an electron with the same spin. Similarly it is not possible to transform the  $t_{2g}$  orbitals if they are all doubly occupied. Thus configurations with  $(t_{2g})^1$  or  $(t_{2g})^6$  have no orbital contribution, but the others all have an orbital contribution. Thus in octahedral complexes the following arrangements have an orbital contribution

$$(t_{2g})^1(e_g)^0 \quad (t_{2g})^2(e_g)^0 \quad (t_{2g})^4(e_g)^2 \quad (t_{2g})^5(e_g)^2$$

$\text{Co}^{2+}$  has the  $(t_{2g})^5(e_g)^2$  configuration hence the high value of  $\mu$  is due to the orbital contribution. In a similar way an orbital contribution arises in tetrahedral cases with the following configurations

$$(e)^2(t_2)^1 \quad (e)^2(t_2)^2 \quad (e)^4(t_2)^1 \quad (e)^4(t_2)^5$$

In the second and third row transition elements, and particularly in the lanthanide elements (where unpaired electrons occupy  $4f$  orbitals) the orbital motion is not prevented or quenched. Thus the orbital contribution  $L$  must be included in the calculations. In some cases there is coupling between the spin contribution  $S$  and the orbital contribution  $L$  (spin orbit coupling, or Russell-Saunders coupling) to give a new quantum number  $J$ . In this case a more complicated formula is used. This is described in Chapter 29. The equations are

$$\mu = g\sqrt{J(J+1)} \mu_B$$

where

$$g = 1 + \frac{S(S+1) - L(L+1) + J(J+1)}{2J(J+1)}$$

Rearranging this becomes

$$g = 1\frac{1}{2} + \frac{S(S+1) - L(L+1)}{2J(J+1)}$$

Using this equation the agreement between the observed and the calculated magnetic moments of the trivalent lanthanide elements is very close. For further details see Chapter 29. Spin orbit coupling gives rise to fine structure in absorption spectra. It splits the degenerate lower levels into a set of different levels. These levels may be populated by using thermal energy, giving rise to a temperature dependent magnetic moment.

Pierre Curie found that the measured magnetic susceptibility  $\chi_M$  for

paramagnetic materials varied with temperature. He put forward the Curie law that the paramagnetic susceptibility  $\chi_M$  varies inversely with the absolute temperature, and

$$\chi_M = \frac{C}{T}$$

where  $C$  is a constant characteristic for the particular substance, called the Curie constant. Thus the magnetic field tends to align the moments of the paramagnetic atoms or ions, and thermal agitation tends to randomize them. Applying a statistical treatment:

$$\chi_M = \frac{\mu_o(N^\circ \mu^2)/(3k)}{T}$$

Thus the magnetic moment in Bohr magnetons is given by:

$$\frac{\mu}{\mu_B} = \sqrt{(3k/N^\circ)/\mu_B} \cdot \sqrt{\chi_M \cdot T}$$

hence

$$\frac{\mu}{\mu_B} = 797.5 \sqrt{\chi_M \cdot T}$$

The Curie law is obeyed with great accuracy by some systems such as  $[\text{FeF}_6]^{3-}$ . However, many paramagnetic materials deviate slightly from this ideal behaviour, and obey the Curie-Weiss law:

$$\chi_M = \frac{C}{T + \theta} \quad \text{and} \quad \mu = 797.5 \sqrt{\chi_M \cdot (T + \theta)} \cdot \mu_B$$

( $\theta$  is called the Weiss constant and is an empirical quantity.)

## CATALYTIC PROPERTIES

Many transition metals and their compounds have catalytic properties. Some of the more important ones are listed here:

$\text{TiCl}_3$	Used as the Ziegler-Natta catalyst in the production of polythene.
$\text{V}_2\text{O}_5$	Converts $\text{SO}_2$ to $\text{SO}_3$ in the Contact process for making $\text{H}_2\text{SO}_4$ .
$\text{MnO}_2$	Used as a catalyst to decompose $\text{KClO}_3$ to give $\text{O}_2$ .
$\text{Fe}$	Promoted iron is used in the Haber-Bosch process for making $\text{NH}_3$ .
$\text{FeCl}_3$	Used in the production of $\text{CCl}_4$ from $\text{CS}_2$ and $\text{Cl}_2$ .
$\text{FeSO}_4$ and $\text{H}_2\text{O}_2$	Used as Fenton's reagent for oxidizing alcohols to aldehydes.
$\text{PdCl}_2$	Wacker process for converting $\text{C}_2\text{H}_4 + \text{H}_2\text{O} + \text{PdCl}_2$ to $\text{CH}_3\text{CHO} + 2\text{HCl} + \text{Pd}$ .
$\text{Pd}$	Used for hydrogenation (e.g. phenol to cyclohexanone).
$\text{Pt/PtO}$	Adams catalyst, used for reductions.




Pt	Formerly used for $\text{SO}_2 \rightarrow \text{SO}_3$ in the Contact process for making $\text{H}_2\text{SO}_4$
Pt	Is increasingly being used in three stage convertors for cleaning car exhaust fumes
Pt/Rh	Formerly used in the Ostwald process for making $\text{HNO}_3$ to oxidize $\text{NH}_3$ to $\text{NO}$
Cu	Is used in the direct process for manufacture of $(\text{CH}_3)_2\text{SiCl}_2$ used to make silicones
Cu/V	Oxidation of cyclohexanol/cyclohexanone mixtures to adipic acid which is used to make nylon 66
$\text{CuCl}_2$	Deacon process of making $\text{Cl}_2$ from $\text{HCl}$
Ni	Raney nickel numerous reduction processes (e.g. manufacture of hexamethylenediamine production of $\text{H}_2$ from $\text{NH}_3$ reducing anthraquinone to anthraquinol in the production of $\text{H}_2\text{O}_2$ )
Ni	Reppe synthesis (polymerization of alkynes e.g. to give complexes benzene or cyclooctatetraene)

In some cases the transition metals with their variable valency may form unstable intermediate compounds. In other cases the transition metal provides a suitable reaction surface.

Enzymes are catalysts that enhance the rates of specific reactions. They are proteins and are produced by living cells from amino acids. They work under mild conditions, often give 100% yields and may speed a reaction by  $10^6$  or  $10^{12}$  times. Some enzymes require the presence of metal ions as *cofactors* and these are called *metalloenzymes*. Many (but not all) metalloenzymes contain a transition metal. Some metalloenzymes are listed in Table 18.10.

## NONSTOICHIOMETRY

A further feature of the transition elements is that they sometimes form nonstoichiometric compounds. These are compounds of indefinite structure and proportions. For example, iron(II) oxide  $\text{FeO}$  should be written with a bar over the formula  $\overline{\text{FeO}}$  to indicate that the ratio of Fe and O atoms is not exactly 1 : 1. Analysis shows that the formula varies between  $\text{Fe}_{0.94}\text{O}$  and  $\text{Fe}_{0.96}\text{O}$ . Vanadium and selenium form a series of compounds ranging from  $\text{VSe}_{0.98}$  to  $\text{VSe}_1$ . These are given the formulae



Nonstoichiometry is shown particularly among transition metal compounds of the Group 16 elements (O, S, Se, Te). It is mostly due to the variable valency of transition elements. For example, copper is precipitated from a solution containing  $\text{Cu}^{2+}$  by passing in  $\text{H}_2\text{S}$ . The sulphide is completely insoluble, but this is not used as a gravimetric method for

**Table 18.10** Metalloenzymes and metalloproteins (metalloproteins in brackets)

Metal	Enzyme/metalloprotein	Biological function
Mo	Xanthine oxidase	Metabolism of purines
	Nitrate reductase	Utilization of nitrates
Mn <sup>II</sup>	Arginase	Urea formation
	Phosphotransferases	Adding or removing PO <sub>4</sub> <sup>3-</sup>
Fe <sup>II</sup> or Fe <sup>III</sup>	Aldehyde oxidase	Oxidation of aldehydes
	Catalase	Decomposes H <sub>2</sub> O <sub>2</sub>
	Peroxidase	Decomposes H <sub>2</sub> O <sub>2</sub>
	Cytochromes	Electron transfer
	Ferredoxin	Photosynthesis
	(Haemoglobin)	O <sub>2</sub> transport in higher animals
	Succinic dehydrogenase	Aerobic oxidation of carbohydrates
Fe and Mo	Nitrogenase	Fixation of dinitrogen
Co	Glutamic mutase	Metabolism of amino acids
	Ribonucleotide reductase	Biosynthesis of DNA
Cu <sup>I</sup> or Cu <sup>II</sup>	Amine oxidases	Oxidation of amines
	Ascorbate oxidase	Oxidation of ascorbic acid
	Cytochrome oxidase	Principal terminal oxidase
	Galactose oxidase	Oxidation of galactose
	Lysine oxidase	Elasticity of aortic walls
	Dopamine hydroxylase	Producing noradrenaline to generate nerve impulses in the brain
	Tyrosinase	Skin pigmentation
	Ceruloplasmin	Utilization of Fe
	(Haemocyanin)	O <sub>2</sub> transport in invertebrates
	Plastocyanin	Photosynthesis
Zn <sup>II</sup>	Alcohol dehydrogenase	Metabolism of alcohol
	Alkaline phosphatase	Releasing PO <sub>4</sub> <sup>3-</sup>
	Carbonic anhydrase	Regulation of pH and CO <sub>2</sub> formation
	Carboxypeptidase	Digestion of proteins

analysing for Cu because the precipitate is a mixture of CuS and Cu<sub>2</sub>S. Sometimes nonstoichiometry is caused by defects in the solid structures.

## ABUNDANCE

Three of the transition metals are very abundant in the earth's crust. Fe is the fourth most abundant element by weight, Ti the ninth and Mn the twelfth. The first row of transition elements largely follow Harkins' rule that elements with an even atomic number are in general more abundant than their neighbours with odd atomic numbers. Manganese is an exception. The second and third row elements are much less abundant than the first row. Tc does not occur in nature. Of the last six elements in the second and third rows (Tc, Ru, Rh, Pd, Ag, Cd; Re, Os, Ir, Pt, Au, Hg) none occurs to an extent of more than 0.16 parts per million (ppm) in the earth's crust.

**Table 18.11** Abundance of the transition elements in the earth's crust in ppm by weight

Sc 25	Ti 6320	V 136	Cr 122	Mn 1060	Fe 60000	Co 29	Ni 99	Cu 68	Zn 76
Y 31	Zr 162	Nb 20	Mo 12	Tc -	Ru 0.0001	Rh 0.0001	Pd 0.015	Ag 0.08	Cd 0.16
La 35	Hf 2.8	Ta 1.7	W 1.2	Re 0.0007	Os 0.005	Ir 0.001	Pt 0.01	Au 0.004	Hg 0.08


## DIFFERENCES BETWEEN THE FIRST ROW AND THE OTHER TWO ROWS

### Metal-metal bonding and cluster compounds

Metal-metal (M-M) bonding occurs not only in the metals themselves but also in some compounds. M-M bonding is quite rare in the first row transition elements. It occurs only in a few carbonyl compounds such as  $\text{Mn}_2(\text{CO})_{10}$ ,  $\text{Fe}_2(\text{CO})_9$ ,  $\text{Co}_2(\text{CO})_8$ ,  $\text{Fe}_3(\text{CO})_{12}$  and  $\text{Co}_4(\text{CO})_{12}$  and in carboxylate complexes such as chromium(II) acetate  $\text{Cr}_2(\text{CH}_3\text{COO})_4(\text{H}_2\text{O})_2$  and in solid nickel dimethylglyoxime.

In the second and third row elements M-M bonds are much more common.

- 1 They form carbonyls with M-M bonds similar to those from the first row such as  $\text{Ru}_3(\text{CO})_{12}$ ,  $\text{Os}_3(\text{CO})_{12}$ ,  $\text{Rh}_4(\text{CO})_{12}$  and  $\text{Ir}_4(\text{CO})_{12}$  and a type not formed by the first row  $\text{Rh}_6(\text{CO})_{16}$ .
- 2 The metals Mo, Ru and Rh form binuclear carboxylate complexes such as  $\text{Mo}_2(\text{CH}_3\text{COO})_4(\text{H}_2\text{O})_2$  which are similar to chromium(II) acetate.
- 3 The halide ions  $[\text{Re}_2\text{Cl}_8]^{2-}$  and  $[\text{Mo}_2\text{Cl}_9]^-$  also have M-M bonds.
- 4 The lower halides of several elements have a group of three or six metal atoms bonded together and are called cluster compounds. The elements are



$[\text{Nb}_6\text{Cl}_{12}]^{2+}$  and  $[\text{Ta}_6\text{Cl}_{12}]^{2+}$  have unusual structures. Both contain six metal atoms arranged in a cluster at the corners of an octahedron, with 12 bridging halogen atoms across the corners. There is extensive M-M bonding within the octahedron. The so-called 'dihalides' of Mo and W are really  $\text{Mo}_6\text{Cl}_{12}$  and  $\text{W}_6\text{Br}_{12}$ , and these contain the  $[\text{M}_6\text{X}_8]^{4+}$  ion. This too has a remarkable structure. Six metal atoms are arranged in a cluster at the corners of an octahedron, with eight halogen atoms located above each of the eight faces of the octahedron and 'bonded' to three metal atoms.  $\text{ReCl}_4$  is really trimeric  $\text{Re}_3\text{Cl}_9$ , and comprises a triangle of three Re atoms with three bridging halogen atoms across the three corners, and six halogen atoms that bridge to other  $\text{Re}_3\text{Cl}_9$  units.

### Stability of oxidation states

The (+II) and (+III) states are important for all the first row transition elements. Simple ions  $M^{2+}$  and  $M^{3+}$  are common with the first row but are less important for second and third row elements, which have few ionic compounds. Similarly the first row form a large number of extremely stable complexes such as  $[Cr^{III}Cl_6]^{3-}$  and  $[Co^{III}(NH_3)_6]^{3+}$ . No equivalent complexes of Mo or W, or Rh or Ir, are known.

The higher oxidation states of the second and third row elements are more important and much more stable than those of the first row elements. Thus the chromate ion  $[CrO_4]^{2-}$  is a strong oxidizing agent but molybdate  $[MoO_4]^{2-}$  and tungstate  $[WO_4]^{2-}$  are stable. Similarly the permanganate ion  $[MnO_4]^-$  is a strong oxidizing agent but pertechnetate  $[TcO_4]^-$  and perrhenate  $[ReO_4]^-$  ions are stable.

Some compounds exist in high oxidation states which have no counterparts in the first row, for example  $WCl_6$ ,  $ReF_7$ ,  $RuO_4$ ,  $OsO_4$  and  $PtF_6$ .

### Complexes

The coordination number 6 is widespread in the transition elements, giving an octahedral structure. The coordination number 4 is much less common, giving tetrahedral and square planar complexes. Coordination numbers of 7 and 8 are uncommon for the first row but are much more common in the early members of the second and third rows. Thus in  $Na_3[ZrF_7]$  the  $[ZrF_7]^{2-}$  is a pentagonal bipyramid, and in  $(NH_4)_3[ZrF_7]$  it is a capped trigonal prism. In  $Cu_2[ZrF_8]$  the Zr is at the centre of a square antiprism.

### Size

The second row elements are all larger than the first row elements. Because of the lanthanide contraction the radii of the third row are almost the same as those for the second row.

### Magnetism

When transition elements form octahedral complexes, the  $d$  levels are split into  $t_{2g}$  and  $e_g$  sub-levels. Consider a first row element. If the ligands possess a strong field they cause a large difference in energy between these two sub-levels. Thus the electrons occupying the  $d$  level fill the lower  $t_{2g}$  level even if this means they must be paired. If pairing of electrons occurs, the complex is called *low spin* or *spin paired*. Alternatively if the ligands have only a weak field the splitting is small, and only when each of the  $t_{2g}$  and  $e_g$  levels contains one electron does pairing of spins occur. Such complexes are called *high spin* or *spin free*. Thus with a first row element the strength of the ligand field determines whether a low-spin or a high-spin complex is formed.

The second and third row transition elements tend to give low-spin complexes, that is it is more favourable in terms of energy to pair electrons

in the lower energy  $d$  levels rather than use the higher levels regardless of the ligand

The spin only formula gives reasonable agreement relating the observed magnetic moment of first row transition metal complexes to the number of unpaired electrons. For the second and third row transition elements the orbital contribution is significant and in addition spin orbit coupling may occur. Thus the spin only approximation is no longer valid and more complicated equations must be used. Thus the simple interpretation of magnetic moments in terms of the number of unpaired electrons cannot be extended from the first row of transition elements to the second and third rows. The second and third rows also show extensive temperature dependent paramagnetism. This is explained by the spin orbit coupling removing the degeneracy from the lowest energy level in the ground state.

### Abundance

The ten first row transition elements are reasonably common and make up 6.79% of the earth's crust. The remaining transition elements are mostly very scarce. Even though the abundance of Zr is 162 ppm, La 31 ppm, Y 31 ppm and Nb 20 ppm, the 20 elements in the second and third rows elements together make up only 0.025% of the earth's crust. Tc does not occur in nature.

### FURTHER READING

- Bevan, D. J. M. (1973) *Comprehensive Inorganic Chemistry*, Vol. 3 (Chapter 49 Nonstoichiometric compounds), Pergamon Press, Oxford. (A good introduction to nonstoichiometric compounds.)
- Brown, D. (1968) *Halides of the Transition Elements*, Vol. 1 (Halides of the lanthanides and actinides), Wiley, London and New York.
- Canterford, J. H. and Cotton, R. (1968) *Halides of the Second and Third Row Transition Elements*, Wiley, London.
- Canterford, J. H. and Cotton, R. (1969) *Halides of the First Row Transition Elements*, Wiley, London.
- Corbett, J. D. (1981) Extended metal-metal bonding in halides of the early transition metals. *Acc. Chem. Res.* **14**, 239.
- Cotton, F. A. (1983) Multiple metal-metal bonds. *J. Chem. Ed.* **60**, 713-720.
- Crangle, J. (1977) *The Magnetic Properties of Solids*, Arnold, London.
- Diatom metals and metallic clusters* (1980) (Conference papers of the Faraday Symposia of the Royal Society of Chemistry, No. 14), Royal Society of Chemistry, London.
- Earnshaw, A. (1968) *Introduction to Magnetochemistry*, Academic Press, London.
- Emeleus, H. J. and Sharpe, A. G. (1973) *Modern Aspects of Inorganic Chemistry*, 4th ed. (Chapters 14 and 15: Complexes of Transition Metals; Chapter 16: Magnetic properties), Routledge and Kegan Paul, London.
- Figgis, B. N. and Lewis, J. (1960) The magnetochemistry of complex compounds. Chapter 6 in *Modern Inorganic Chemistry* (ed. Lewis, J. and Wilkins, R. G.), Interscience, New York and Wiley, London, 1960. (A good account of measuring magnetic moments.)
- Greenwood, N. N. (1968) *Ionic Crystals, Lattice Defects and Non-Stoichiometry*, Butterworths, London.

- Griffith, W.P. (1973) *Comprehensive Inorganic Chemistry*, Vol. 4 (Chapter 46: Carbonyls, cyanides, isocyanides and nitrosyls), Pergamon Press, Oxford.
- Johnson, B.F.G. (1976) The structures of simple binary carbonyls, *JCS Chem. Comm.*, 211–213.
- Johnson, B.F.G. (ed.) (1980) *Transition Metal Clusters*, John Wiley, Chichester.
- Lewis, J. (1988) Metal clusters revisited, *Chemistry in Britain*, **24**, 795–800.
- Lewis, J. and Green, M.L. (eds) (1983) *Metal Clusters in Chemistry* (Proceedings of the Royal Society Discussion Meeting May 1982), The Society, London.
- Lever, A.B.P. (1984) *Inorganic Electronic Spectroscopy*, Elsevier, Amsterdam. (Up-to-date and comprehensive, and a good source of spectral data.)
- Moore, P. (1982) Colour in transition metal chemistry, *Education in Chemistry*, **19**, 10–11, 14.
- Muetterties, E.L. (1971) *Transition Metal Hydrides*, Marcel Dekker, New York.
- Muetterties, E.L. and Wright, C.M. (1967) High coordination numbers, *Q. Rev. Chem. Soc.*, **21**, 109.
- Nyholm, R.S. (1953) Magnetism and inorganic chemistry, *Q. Rev. Chem. Soc.*, **7**, 377.
- Nyholm, R.S. and Tobe, M.L. (1963) The stabilization of oxidation states of the transition metals, *Adv. Inorg. Radiochem.*, **5**, 1.
- Shriver, D.H., Kaesz, H.D. and Adams, R.D. (eds) (1990) *Chemistry of Metal Cluster Complexes*, VCH, New York.
- Sharpe, A.G. (1976) *Chemistry of Cyano Complexes of the Transition Metals*, Academic Press, London, 1976.

## PROBLEMS

1. How would you define a transition element? List the properties associated with transition elements.
2. How do the following properties vary in the transition elements:
  - (a) ionic character
  - (b) basic properties
  - (c) stability of the various oxidation states
  - (d) ability to form complexes?
3. Give examples of, and suggest reasons for, the following features of transition metal chemistry:
  - (a) The lowest oxide of a transition metal is basic whereas the highest oxide is usually acidic.
  - (b) A transition metal usually exhibits higher oxidation states in its fluorides than in its iodides.
  - (c) The halides become more covalent with increasing oxidation state of the metal and are more susceptible to hydrolysis.
4. Write notes on the following:
  - (a) The effective atomic number rule
  - (b) Ligands which stabilize low oxidation states
  - (c) Back bonding in metal carbonyls
5. Describe the methods by which extremely pure samples of the metals may be prepared.
6. Which of the  $M^{2+}$  and  $M^{3+}$  ions of the first row transition elements are

stable in aqueous solution, which are oxidizing and which are reducing?

- 7 Explain why certain ligands such as  $F^-$  tend to bring out the maximum oxidation state of an element, whilst others such as CO and dipyrldyl bring out the lowest oxidation states
- 8 Give reasons why carbonyl and cyanide complexes of the later transition elements Cr, Mn, Fe, Co, Ni are more stable, more common, and more likely to exist than similar compounds of the *s* block or early transition elements
- 9 Why do the second and third rows of transition elements resemble each other much more closely than they resemble the first row?
- 10 What do you understand by the terms paramagnetism and diamagnetism? Predict the magnetic moment for octahedral complexes of  $Fe^{2+}$  with strong field ligands and with weak field ligands

# Group 3 – the scandium group

19

Table 19.1 Electronic structures and oxidation states

Element		Electronic structure	Oxidation states
Scandium	Sc	[Ar] $3d^1 4s^2$	III
Yttrium	Y	[Kr] $4d^1 5s^2$	III
Lanthanum	La	[Xe] $5d^1 6s^2$	III
Actinium	Ac	[Rn] $6d^1 7s^2$	III

## INTRODUCTION

These four elements are sometimes grouped with the 14 lanthanides and called collectively the 'rare earths'. This is a misnomer because the scandium group are *d*-block elements and the lanthanides are *f*-block elements. In addition the scandium group is by no means rare, except for actinium which is radioactive. The trends in properties in the family Sc, Y, La and Ac are quite regular, and similar to the trends in Groups 1 and 2. There are few important industrial uses of the elements or their compounds apart from Mischmetal, which is used in the metallurgical industries.

## OCCURRENCE, SEPARATION, EXTRACTION AND USES

Sc is the thirty-first most abundant element by weight in the earth's crust. It is thinly distributed. It occurs as the rather rare mineral thortveitite  $\text{Sc}_2[\text{Si}_2\text{O}_7]$ . It is available as a by-product from the extraction of U. There is very little use for Sc or its compounds.

Y and La are the twenty-ninth and twenty-eighth most abundant elements. They are found together with the lanthanide elements in bastnaesite  $\text{M}^{\text{III}}\text{CO}_3\text{F}$ , monazite  $\text{M}^{\text{III}}\text{PO}_4$  and other minerals. It is extremely difficult to separate the individual elements. This is covered in some detail in Chapter 29. It is also difficult to extract the metals from their compounds. The metals are electropositive and react with water. Their oxides are very stable so that a thermite reaction cannot be used ( $\text{Al}_2\text{O}_3$

*continued overleaf*



Table 19.2 Abundance of the elements in the earth's crust by weight

	ppm	Relative abundance
Sc	25	31
Y	31	29
La	35	28
Ac	trace	


enthalpy of formation  $1675 \text{ kJ mol}^{-2}$ ,  $\text{La}_2\text{O}_3$  enthalpy of formation  $1884 \text{ kJ mol}^{-2}$ ). The metals can be obtained by reduction of the chlorides or fluorides with calcium at  $1000^\circ\text{C}$ , under an atmosphere of argon.

Small amounts of Y are used to make the red phosphor for TV tubes. Some is used to make synthetic garnets used in radar and as gemstones. In contrast about 5000 tonnes of La is produced annually, mostly as Mischmetal. This is an unseparated mixture of La and the lanthanide metals (50% Ce, 40% La, 7% Fe, 3% other metals). It is used extensively to improve the strength and workability of steel, and also in Mg alloys. Small amounts are used as 'lighter flints'.  $\text{La}_2\text{O}_3$  is used in optical glass such as Crooke's lenses, which give protection against UV light.

Traces of Ac are always found associated with U and Th as it is formed as a decay product in both the thorium and actinium natural radioactive decay series (Chapter 31).



Ac can be made by irradiating Ra with neutrons in a nuclear reactor



At best this produces milligram quantities. Separation from other elements is performed by ion exchange.  ${}_{89}^{228}\text{Ac}$  and  ${}_{89}^{227}\text{Ac}$  are the only naturally occurring isotopes, and both are intensely radioactive. The half-lives of  ${}_{89}^{228}\text{Ac}$  and  ${}_{89}^{227}\text{Ac}$  are 6 hours and 21.8 years respectively. Thus any Ac present when the earth was formed will have long since decayed. Any found now must have been produced fairly recently by radioactive decay of another element. This explains the scarcity of naturally occurring Ac. The high activity has limited the study of the chemistry of the element.

### OXIDATION STATE

The elements always exist in the oxidation state (+III) and occur as  $\text{M}^{3+}$  ions. The formation of  $\text{M}^{3+}$  requires the removal of the two s and one d electron. Thus the ions have a  $d^0$  configuration and d-d spectra are impossible. As a result the ions and their compounds are colourless and

diamagnetic. The sum of the first three ionization energies for scandium is a little less than the sum for aluminium. The properties of scandium are similar in some ways to those of aluminium.

## SIZE


The covalent and ionic radii of the elements increase regularly on descending the group as in the s-block. In the groups of transition elements shown in Table 19.3 the second and third row elements are almost identical in size because of the lanthanide contraction. However, this happens after La.

Table 19.3 Some physical properties



Element	Covalent radius (Å)	Ionic radius M <sup>3+</sup> (Å)	Ionization energies (kJ mol <sup>-1</sup> )			Standard electrode potential E° (V)	Melting point (°C)	Pauling's electro- negativity
			1st	2nd	3rd			
Sc	1.44	0.745	631	1235	2393	-2.08	1539	1.3
Y	1.62	0.900	616	1187	1968	-2.37	1530	1.2
La	1.69	1.032	541	1100	1852	-2.52	920	1.1
Ac		1.12				-2.6	817	1.1

## CHEMICAL PROPERTIES


The metals have moderately high standard electrode potentials. They are quite reactive, and reactivity increases with increased size. They tarnish in air and burn in dioxygen, giving oxides M<sub>2</sub>O<sub>3</sub>. Y forms a protective oxide coating in air, which makes it unreactive.




The metals react slowly with cold water, but more rapidly with hot water, liberating hydrogen and forming either the basic oxide or the hydroxide.







Sc(OH)<sub>3</sub> appears not to exist as a definite compound, but the basic oxide ScO·OH is well established, and is amphoteric like Al(OH)<sub>3</sub>. Since scandium is amphoteric, it dissolves in NaOH, liberating H<sub>2</sub>:




Basic properties of the oxides and hydroxides increase on descending the group, and Y(OH)<sub>3</sub> and La(OH)<sub>3</sub> are basic. Thus the oxides and hydroxides form salts with acids, and Y(OH)<sub>3</sub> and La(OH)<sub>3</sub> react with carbon dioxide:




$La(OH)_3$  is a strong enough base to liberate  $NH_3$  from ammonium salts. Because the oxides (and hydroxides) are either amphoteric or weak bases, their oxosalts can be decomposed to oxides by heating. This is similar to the behaviour of Group 2 elements, but the decomposition occurs more easily, i.e. at a lower temperature.



The metals react with the halogens, forming trihalides  $MX_3$ . These resemble the halides of Ca. The fluorides are insoluble (like  $CaF_2$ ) and the other halides are deliquescent and very soluble (like  $CaCl_2$ ). If the chlorides are prepared in solution, they crystallize as hydrated salts. Heating these hydrated salts does not yield anhydrous halides. On heating  $ScCl_3 \cdot (H_2O)_7$  decomposes to the oxide, whilst the others give oxohalides.



Anhydrous chlorides can be made from the oxides with  $NH_4Cl$ .




Anhydrous  $ScCl_3$  differs from  $AlCl_3$  as  $ScCl_3$  is monomeric whilst  $(AlCl_3)_2$  is dimeric. In addition  $ScCl_3$  shows no Friedel-Crafts catalytic properties.

The salts generally resemble those of calcium, and the fluorides, carbonates, phosphates and oxalates are insoluble.

The elements all react with hydrogen on heating to  $300^\circ C$ , forming highly conducting compounds of formula  $MH_2$ . These do not contain  $M^{2+}$ , but probably contain  $M^{3+}$  and  $2H^-$ , and have the extra electron in a conduction band. Except for Sc they can absorb more  $H_2$  and lose their conducting power, forming compounds which are not quite stoichiometric but approach the composition  $MH_3$ . The exact composition depends on the temperature and the pressure of the hydrogen. The hydrides react with water, liberating hydrogen, and are salt-like (ionic) hydrides containing the hydride ion  $H^-$ .

Scandium forms a carbide  $ScC_2$  when the oxide is heated with carbon in an electric furnace. The carbide reacts with water, liberating ethyne.




At one time the carbide was thought to contain  $Sc(+II)$  and to contain  $Sc^{2+}$  and  $(C \equiv C)^{2-}$ . Magnetic measurements suggest that it contains  $Sc^{3+}$ .

ions and  $\text{C}_2^{2-}$  ions and the free electrons are delocalized into a conduction band, thus giving some metallic conduction.

## COMPLEXES

Despite the charge of +3, the metal ions in this group do not have a strong tendency to form complexes. This is because of their fairly large size.  $\text{Sc}^{3+}$  is the smallest ion in the group and forms complexes more readily than the other elements. These include  $[\text{Sc}(\text{OH})_6]^{3-}$  and  $[\text{ScF}_6]^{3-}$ , both of which have a coordination number of 6 and are octahedral in shape.



By far the most common donor atom in complexes is O, and complexes occur particularly with chelating ligands. Thus complexes are formed with strong complexing agents such as oxalic acid, citric acid, acetylacetone and EDTA. The complexes of the larger metals Y and La often have higher coordination numbers than 6, and coordination number 8 is the most common. Thus  $[\text{Sc}(\text{acetylacetone})_3]$  has a coordination number of 6 and is octahedral.  $\text{Y}(\text{acetylacetone})_3(\text{H}_2\text{O})$  has a coordination number of 7 and the structure is a capped trigonal prism. In  $[\text{La}(\text{acetylacetone})_3 \cdot (\text{H}_2\text{O})_2]$  the coordination number is 8 and the structure is a distorted square antiprism. In  $[\text{La} \cdot \text{EDTA} \cdot (\text{H}_2\text{O})_4] \cdot 3\text{H}_2\text{O}$  the EDTA forms four bonds from O atoms and two from N atoms, and the O atoms in the four water molecules all form bonds to La, giving a coordination number of 10. The ions  $\text{NO}_3^-$  and  $\text{SO}_4^{2-}$  also act as bidentate ligands and form complexes with high coordination numbers. In  $[\text{Sc}(\text{NO}_3)_5]^{2-}$  four  $\text{NO}_3^-$  groups are bidentate and one is unidentate giving a coordination number of 9. In  $[\text{Y}(\text{NO}_3)_5]^{2-}$  all five  $\text{NO}_3^-$  groups are bidentate and the coordination number is 10. In  $\text{La}_2(\text{SO}_4)_3 \cdot 9\text{H}_2\text{O}$  half of the La atoms are 12-coordinate.

Lanthanum salts have been used as a biological tracer.  $\text{La}^{3+}$  appears to replace  $\text{Ca}^{2+}$  in the conduction of nerve impulses along the axons of nerve cells, and also in structure promoting in cell membranes.  $\text{La}^{3+}$  is readily detected by electron spin resonance. The similarity in biological role may arise because the ions are similar in size ( $\text{La}^{3+} = 1.032 \text{ \AA}$ ,  $\text{Ca}^{2+} = 1.00 \text{ \AA}$ ).

## FURTHER READING

- Callow, R.J. (1967) *The Industrial Chemistry of the Lanthanons, Yttrium, Thorium and Uranium*, Pergamon Press, New York.
- Horowitz, C.T. (ed.) (1975) *Scandium: Its Occurrence, Chemistry, Physics, Metallurgy, Biology and Technology*, Academic Press, London.
- Melson, G.A. and Stotz, R.W. (1971) The coordination chemistry of scandium, *Coordination Chem. Rev.*, 7, 133.
- Vickery, R.C. (1973) *Comprehensive Inorganic Chemistry*, Vol. 3 (Chapter 31: Scandium, yttrium, lanthanum), Pergamon Press, Oxford.

## Group 4 – the titanium group

Table 20.1 Electronic structures and oxidation states

Element		Electronic structure	Oxidation states*
Titanium	Ti	[Ar] 3d <sup>2</sup> 4s <sup>2</sup>	(-I) (0) (II) <b>III</b> <b>IV</b>
Zirconium	Zr	[Kr] 4d <sup>2</sup> 5s <sup>2</sup>	(II) (III) <b>IV</b>
Hafnium	Hf	[Xe] 4f <sup>14</sup> 5d <sup>2</sup> 6s <sup>2</sup>	(II) (III) <b>IV</b>

\* The most important oxidation states (generally the most abundant and stable) are shown in bold. Other well characterized but less important states are shown in normal type. Oxidation states that are unstable or in doubt are given in parentheses.

### INTRODUCTION

Titanium is a commercially important element. Vast quantities of  $\text{TiO}_2$  are used as a pigment and filler, and Ti metal is important for its strength, low density, and corrosion resistance.  $\text{TiCl}_4$  is important as a Ziegler-Natta catalyst for making polythene and other polymers. Zirconium is used to make the cladding for fuel rods in water cooled nuclear reactors. Hafnium is used to make control rods for certain reactors.

### OCCURRENCE AND ABUNDANCE

Ti is the ninth most abundant element by weight in the earth's crust. The main ores are ilmenite  $\text{FeTiO}_3$  and rutile  $\text{TiO}_2$ . In 1992 world production was 7.8 million tonnes of ilmenite and 471 000 tonnes of rutile. These had a  $\text{TiO}_2$  content of 4.1 million tonnes. The main producers are Canada 27%, Australia 24% and Norway 9%. Zr is the eighteenth most abundant element and is found mainly as zircon  $\text{ZrSiO}_4$  and small amounts of baddeleyite  $\text{ZrO}_2$ . World production of zirconium minerals was 808 000 tonnes in 1992. Hf is very similar in size and properties to Zr because of the lanthanide contraction. Thus Hf occurs to the extent of 1–2% in Zr ores. It is particularly difficult to separate Zr and Hf – even more difficult than separating the lanthanides.

**Table 20.2** Abundance of the elements in the earth's crust, by weight

	ppm	Relative abundance
Ti	6320	9
Zr	162	18
Hf	2.8	45

## EXTRACTION AND USES



Ti has been called 'the wonder metal' because of its unique and useful properties. It is very hard, high melting ( $1667^{\circ}\text{C}$ ) and is stronger and much lighter than steel (densities  $\text{Ti} = 4.4 \text{ g cm}^{-3}$ ,  $\text{Fe} = 7.87 \text{ g cm}^{-3}$ ). However, even traces of non-metal impurities, for example H, C, N or O, make Ti, and also the other two metals Zr and Hf, brittle. Ti has better corrosion resistance than stainless steel. It is a better conductor of heat and electricity than Group 3 (Sc group) metals. Ti metal and alloys of Ti with Al are used extensively in the aircraft industry in jet and gas turbine engines, and in airframes. Supersonic aircraft like Concorde can use Al as the structural

**Table 20.3** Some physical properties

Element	Covalent radius (Å)	Ionic radius $\text{M}^{4+}$ (Å)	Melting point ( $^{\circ}\text{C}$ )	Boiling point ( $^{\circ}\text{C}$ )	Density ( $\text{g cm}^{-3}$ )	Pauling's electro-negativity
Ti	1.32	0.605	1667	3285	4.50	1.5
Zr	1.45	0.72	1857	4200	6.51	1.4
Hf	1.44	0.71	2222	4450	13.28	1.3

skin (m.p.  $660^{\circ}\text{C}$ ) by limiting the speed to Mach 2.2 (2.2 times the speed of sound). If and when SST (supersonic transport) planes are made which fly at three times the speed of sound, it is probable that they will be made of Ti (m.p.  $1667^{\circ}\text{C}$ ). Ti is also used in marine equipment and in chemical plant. Small amounts of Ti alloyed with steel harden and toughen the steel. World production of Ti metal is almost 50 000 tonnes per year.

The metal is difficult to extract because of its high melting point and because it reacts readily with air, dioxygen, dinitrogen, and hydrogen at elevated temperatures. The oxide cannot be reduced by C or CO because it forms carbides. Since  $\text{TiO}_2$  is very stable, the first stage is to form  $\text{TiCl}_4$  by heating it with C and  $\text{Cl}_2$  at  $900^{\circ}\text{C}$ .




$\text{TiCl}_4$  is a liquid (b.p.  $137^{\circ}\text{C}$ ) and is removed from  $\text{FeCl}_3$  and other impurities by distillation. One of the following methods is then used.

*continued overleaf*

### Kroll process


Originally Wilhelm Kroll produced Ti by reducing  $\text{TiCl}_4$  with Ca in an electric furnace. Later Mg was used and Imperial Metal Industries (IMI) use Na instead. At this temperature Ti is highly reactive and reacts readily with air or  $\text{N}_2$ . It is therefore necessary to perform the reaction under an atmosphere of argon.



The  $\text{MgCl}_2$  formed can be removed by leaching with water, or better with dilute HCl as this dissolves any excess Mg. Alternatively the  $\text{MgCl}_2$  is removed by vacuum distillation. This leaves a sponge of Ti rather than a solid block. The Ti is converted to the massive form by melting in an electric arc under a high vacuum or an atmosphere of argon. The IMI process is almost the same.  $\text{TiCl}_4$  is reduced by Na under an atmosphere of argon, and NaCl is leached out with water. The Ti is in the form of small granules. These can be fabricated into metal parts using 'powder forming' techniques and sintering in an inert atmosphere. The high fuel costs, the necessity to use argon, the cost of Mg or Na, and the need to reheat a second time all make Ti expensive. The high cost prevents its being more widely used. Zirconium is also produced by the Kroll process.

### The van Arkel-de Boer method

Small amounts of very pure metal can be produced by this process. Impure Ti or Zr are heated in an evacuated vessel with  $\text{I}_2$ .  $\text{TiI}_4$  or  $\text{ZrI}_4$  is formed and volatilizes (thus separating it from any impurities). At atmospheric pressure  $\text{TiI}_4$  melts at  $150^\circ\text{C}$  and boils at  $377^\circ\text{C}$ ,  $\text{ZrI}_4$  melts at  $499^\circ\text{C}$  and boils at  $600^\circ\text{C}$ . Under reduced pressure however the boiling points are lower. The gaseous  $\text{MI}_4$  is decomposed on a white hot tungsten filament. As more metal is deposited on the filament it conducts electricity better. Thus more electric current must be passed to keep it white hot.



Zr is produced on a much smaller scale than Ti. Zr is even more corrosion resistant than is Ti, and is used in chemical plants. Its most important use is to make the cladding (that is the casing) for  $\text{UO}_2$  fuel in water cooled nuclear reactors. Its corrosion resistance, high melting point ( $1857^\circ\text{C}$ ) and low absorption of neutrons make it very suitable. (Of the metallic elements only Be and Mg have lower neutron absorption cross sections than Zr. They are unsuitable for use as cladding as Be is brittle and Mg corrodes too easily.) Hf always occurs with Zr. Their chemical properties are almost identical, and for most purposes there is no need to separate them. However, Hf absorbs neutrons very strongly, and Zr used for cladding must be free from Hf.

The similarity in size of the ions makes separation exceedingly difficult.

The same problem is encountered in separating the lanthanide elements (see Chapter 29). Zr and Hf are separated by solvent extraction of their nitrates into tri-*n*-butyl phosphate or thiocyanates into methylisobutyl ketone. Alternatively the elements can be separated by ion exchange of an alcoholic solution of the tetrachlorides on silica gel columns. On eluting the column with an alcohol/HCl mixture, the Zr comes off first.

Zr is also used to make alloys with steel, and a Zr/Nb alloy is an important superconductor. The very high absorption of thermal neutrons by Hf is turned to good use. Hf is used to make control rods for regulating the free neutron levels in the nuclear reactors used in submarines.

## OXIDATION STATES


The most common and most stable oxidation state for all the elements is (+IV). Anhydrous compounds such as  $\text{TiCl}_4$  are covalent and the molecules are tetrahedral in the gaseous state. Most of the halides retain their tetrahedral structure in the solid.  $\text{TiF}_4$  has the largest electronegativity difference and is the most likely compound to be ionic. It is a volatile white powder, which sublimates at  $284^\circ\text{C}$  – not behaviour typical of an ionic salt. Its crystal structure is a polymeric F bridged structure in which each Ti is octahedrally surrounded by six F atoms.

In the oxidation state (+IV) the elements have a  $d^0$  configuration with no unpaired electrons: hence their compounds are typically white or colourless and diamagnetic.

$\text{Ti}^{4+}$  ions do not exist in solution, but oxoions are formed instead. The titanyl ion  $\text{TiO}^{2+}$  is found in solution but it usually polymerizes in crystalline salts.

The oxidation state (+III) is reducing, and  $\text{Ti}^{3+}$  ions are more strongly reducing than  $\text{Sn}^{2+}$ . They are reasonably stable, and exist as solids and in solution. Since the  $\text{M}^{3+}$  ions have a  $d^1$  configuration they have one unpaired electron and are paramagnetic. The magnetic moments of their compounds are close to the spin only value of 1.73 Bohr magnetons. With only one  $d$  electron, there is only one possible  $d-d$  electronic transition: hence there is only one band in the visible spectrum, and nearly all the compounds are a pale purple-red colour.

The (+II) state is very unstable and is so strongly reducing that it reduces water. Thus few compounds are known and these exist only in the solid state. The (0), (−I) and (−II) states are found in the dipyriddy complexes  $[\text{Ti}^0(\text{dipy})_3]$ ,  $\text{Li}[\text{Ti}^{-I}(\text{dipy})_3] \cdot 3.5$  tetrahydrofuran and  $\text{Li}_2[\text{Ti}^{-II}(\text{dipy})_3] \cdot 5$  tetrahydrofuran. The lower oxidation states tend to disproportionate.



## SIZE


The covalent and ionic radii increase normally from Ti to Zr, but Zr and Hf are almost identical in size. The reason why Hf does not show the expected



increase in size is that between La and Hf the 4f level is filled with the 14 lanthanide elements. There is a small decrease in size from one lanthanide element to the next. The overall decrease in size across the 14 elements is called the *lanthanide contraction* (see Chapter 29). The decrease in size caused by the lanthanide contraction cancels out the expected size increase from Zr to Hf. Since the sizes of Hf and La are almost identical and they have a similar outer electronic structure, their chemical properties are almost identical. Separation of these two elements is difficult as noted above under 'Extraction and uses'.

### REACTIVITY AND PASSIVE BEHAVIOUR

The compact (massive) forms of the metals are unreactive or passive at low and moderate temperatures. This results from a thin impermeable oxide film which forms on the surface and prevents further attack. This is particularly effective with Ti (Note however, that the finely divided metals are pyrophoric). At room temperature the metals are unaffected by either acids or alkali. However, Ti dissolves slowly in hot concentrated HCl, giving  $\text{Ti}^{3+}$  and  $\text{H}_2$ . Ti is oxidized by hot  $\text{HNO}_3$  giving the hydrated oxide  $\text{TiO}_2 \cdot (\text{H}_2\text{O})_n$ . Zr dissolves in hot concentrated  $\text{H}_2\text{SO}_4$  and aqua regia. The best solvent for all the metals is HF, because they form hexafluoro complexes.



At about  $450^\circ\text{C}$  all three metals begin to react with many substances. At temperatures over  $600^\circ\text{C}$  they are highly reactive. They form oxides  $\text{MO}_2$ , halides  $\text{MX}_4$ , interstitial nitrides  $\text{MN}$  and interstitial carbides  $\text{MC}$  by direct combination. Like the scandium group, the powdered metals absorb  $\text{H}_2$ . The amount absorbed depends on the temperature and pressure, and interstitial compounds are formed of limiting composition  $\text{MH}_2$ . These interstitial hydrides are stable in air, and are unaffected by water. This is in contrast to the behaviour of the ionic hydrides of the scandium group and s-block elements.

### STANDARD REDUCTION POTENTIALS (VOLTS)



Acid solution				
Oxidation state				
+IV	+III	+II	+I	0
$\text{TiO}^{2+}$	$\xrightarrow{+0.10} \text{Ti}^{3+}$	$\xrightarrow{-0.37} \text{Ti}^{2+}$	$\xrightarrow{-1.63}$	$\text{Ti}$

## (+IV) STATE

## Oxides

World production of  $\text{TiO}_2$  was 4.1 million tonnes in 1992. More than half is used as a white pigment in paint, and as an opacifier to make coloured paint opaque. It has replaced the earlier pigments white lead ( $2\text{PbCO}_3 \cdot \text{Pb}(\text{OH})_2$ ),  $\text{BaSO}_4$  and  $\text{CaSO}_4$  for this purpose. It has three advantages over Pb: it covers better, it is non-toxic, and it does not blacken if exposed to  $\text{H}_2\text{S}$ . The other major uses of  $\text{TiO}_2$  are for whitening paper, and as a filler in plastics and rubber. Some is used for delustering and whitening nylon.


Naturally occurring  $\text{TiO}_2$  is invariably coloured by impurities. There are two commercial processes for obtaining pure  $\text{TiO}_2$ , the older sulphate process and the more recent chloride process. In the chloride process rutile ( $\text{TiO}_2$ ) is heated with chlorine and coke at  $900^\circ\text{C}$ , forming  $\text{TiCl}_4$ . This is volatile and can thus be separated from any impurities. The  $\text{TiCl}_4$  is heated with  $\text{O}_2$  at about  $1200^\circ\text{C}$ , forming pure  $\text{TiO}_2$  and  $\text{Cl}_2$ . The chlorine is reused.



In the sulphate process, ilmenite  $\text{FeTiO}_3$  is digested with concentrated  $\text{H}_2\text{SO}_4$ :  $\text{Fe}^{\text{II}}\text{SO}_4$ ,  $\text{Fe}_2^{\text{III}}(\text{SO}_4)_3$  and titanyl sulphate  $\text{TiO} \cdot \text{SO}_4$  are formed as a sulphate cake. This latter is leached with water and any insoluble material is removed.  $\text{Fe}^{\text{III}}$  in the solution is reduced to  $\text{Fe}^{\text{II}}$  using scrap iron, and then  $\text{FeSO}_4$  is crystallized out by vacuum evaporation and cooling. The  $\text{TiOSO}_4$  solution is hydrolysed by boiling, and then the solution is seeded with rutile or anatase crystals as required.

The crystal structures of the oxides suggest that they are ionic. However, the sum of the first four ionization energies is so high ( $8800 \text{ kJ mol}^{-1}$  for  $\text{Ti}^{4+}$ ) that this seems improbable.  $\text{TiO}_2$  occurs in three different crystalline forms: rutile, anatase and brookite. Rutile is the most common: here each Ti is surrounded octahedrally by six O atoms (see Chapter 3, under 'Ionic compounds of the type  $\text{AX}_2$ '). The structures of the other two forms are distorted octahedral arrangements. The oxides are insoluble in water.  $\text{M}^{4+}$  ions do not exist in solution, but  $\text{MO}^{2+}$  ions are formed, giving basic salts such as titanyl sulphate  $\text{TiO} \cdot \text{SO}_4$ . Either  $\text{TiO}^{2+}$  ions or  $[\text{Ti}(\text{OH})_2]^{2+}$  are present in solution, but in the solid they polymerize into oxygen bridged  $(\text{MO})_n^{2+}$  chains. The X-ray structure of  $\text{TiO} \cdot \text{SO}_4$  shows that each Ti is surrounded octahedrally by six O atoms: two chain O atoms, O atoms from three  $\text{SO}_4^-$  groups and O from one  $\text{H}_2\text{O}$ .


In a similar way zirconyl ions  $\text{ZrO}^{2+}$  exist in solution, and they form polymeric species in crystals. Zirconyl nitrate  $\text{ZrO}(\text{NO}_3)_2$  forms an oxygen bridged chain structure similar to  $\text{TiO} \cdot \text{SO}_4$ .  $\text{ZrO}(\text{NO}_3)_2$  is soluble in water and dilute  $\text{HNO}_3$ , and is used to remove phosphate in qualitative analysis. Otherwise it would interfere with the systematic analysis for metals. The phosphates of Ti, Zr and Hf are all insoluble.



**Figure 20.1** Polymeric  $(\text{TiO})_n^{3+}$  chain

$\text{TiO}_2$ ,  $\text{ZrO}_2$  and  $\text{HfO}_2$  are all very stable white solids, are non volatile and are rendered refractory by strong ignition. On strong heating  $\text{ZrO}_2$  becomes very hard and its high melting point of  $2700^\circ\text{C}$  and its resistance to chemical attack make it useful for making high temperature crucibles and furnace linings. Fibres of  $\text{ZrO}_2$  are made commercially and are similar to those of  $\text{Al}_2\text{O}_3$  described in Chapter 12. If the solids have been prepared dry, or have been heated, they do not react with acids. If they are prepared in solution, for example by hydrolysing  $\text{TiCl}_4$ , the oxide dissolves in  $\text{HCl}$ ,  $\text{HF}$  and  $\text{H}_2\text{SO}_4$ , forming complexes  $[\text{TiCl}_6]^{2-}$ ,  $[\text{TiF}_6]^{2-}$  or  $[\text{Ti}(\text{SO}_4)_3]^{2-}$ .

The basic properties of the oxides increase with atomic number.  $\text{TiO}_2$  is amphoteric and  $\text{ZrO}_2$  and  $\text{HfO}_2$  are increasingly basic.  $\text{TiO}_2$  dissolves in both bases and acids, forming titanates and titanyl compounds.



$\text{Ti}(\text{OH})_3$  is not known because it dehydrates to give the hydrated oxide

### Mixed oxides

If the oxides  $\text{TiO}_2$ ,  $\text{ZrO}_2$  or  $\text{HfO}_2$  are fused (at temperatures of 1000–2500°C) with the appropriate quantities of other metal oxides titanates, zirconates and hafnates are formed. These are mixed oxides, and typically do not contain discrete ions. Thus anhydrous sodium titanate  $\text{Na}_2\text{TiO}_3$  can be made by fusing  $\text{TiO}_2$  with  $\text{Na}_2\text{O}$ ,  $\text{Na}_2\text{CO}_3$  or  $\text{NaOH}$ . Reduction of  $\text{Na}_2\text{TiO}_3$  with  $\text{H}_2$  at high temperatures gives titanium bronzes which are nonstoichiometric materials of formula  $\text{Na}_{0.2-0.25}\text{TiO}_2$ . These have a high electrical conductivity, and have a blue–black metal like appearance, and are similar to the tungsten bronzes. Calcium titanate  $\text{CaTiO}_3$  occurs naturally as perovskite and ilmenite (iron titanate)  $\text{Fe}^{II}\text{TiO}_3$  provides the largest source of Ti.

The ilmenite structure consists of a lattice of hexagonal close packed O atoms, with Ti atoms occupying one third of the octahedral sites, and Fe (or the other metal) occupying another one third of the octahedral sites. This structure is formed when the other metal is about the same size as Ti. The structure is the same as corundum  $\text{Al}_2\text{O}_3$ , except that corundum has two  $\text{Al}^{3+}$  ions rather than one  $\text{Ti}^{4+}$  and one  $\text{Fe}^{2+}$ .

When the two metals differ appreciably in size the *perovskite structure* (Figure 20 2) is formed. This is a cubic close-packed array of O and Ca (so that the Ca has a coordination number of 12) with Ti occupying one




Figure 20.2 Perovskite structure.

quarter of the octahedral holes. The holes occupied are those bounded completely by O atoms, thus keeping Ca and Ti as far apart as possible.

$\text{BaTiO}_3$  has a perovskite structure. The  $\text{Ba}^{2+}$  ion is too large to fit into the close-packed oxide lattice without expanding it. This increases the size of the octahedral holes, so that Ti can 'rattle' in its octahedral hole. In an electric field the Ti atoms are drawn to one side of the hole, thus causing some polarization and making the crystal strongly ferroelectric. It is also piezoelectric (pressure produces an electric current, and vice versa). This makes it useful as a transducer for crystals in gramophone pickups and microphones, and for ceramic capacitors and other electronic uses.


Other titanates have the formula  $\text{M}_2^{II}\text{TiO}_4$ , where M may be Mg, Mn, Fe, Co or Zn.  $\text{Mg}_2\text{TiO}_4$  has a *spinel structure* (like  $\text{MgAl}_2\text{O}_4$ ). The oxide ions form a cubic close-packed array and the Mg ions occupy one half of the octahedral holes and Ti occupies one eighth of the tetrahedral holes. Thus these compounds contain discrete  $[\text{TiO}_4]^{4-}$  ions.

### Peroxides

A characteristic property of Ti(IV) solutions is that they form an intense yellow-orange colour on addition of  $\text{H}_2\text{O}_2$ . This reaction can be used for the colorimetric determination of either Ti(IV) or  $\text{H}_2\text{O}_2$ . The colour is thought to be due to the formation of a peroxo complex. Below pH 1 the main species is  $[\text{Ti}(\text{O}_2) \cdot \text{OH} \cdot (\text{H}_2\text{O})_n]^+$ , in which the peroxo group is bidentate.

### Halides



$\text{TiCl}_4$  is the best known halide and is made commercially by passing  $\text{Cl}_2$  over heated  $\text{TiO}_2$  and C. The other halides  $\text{MX}_4$  can be made in a similar way. To avoid handling  $\text{F}_2$ , the fluorides can be prepared from  $\text{TiCl}_4$  by reaction with anhydrous HF.



The iodides can also be made by heating the halogens and metal. They are important in the van Arkel-de Boer process for purifying the metals.


$\text{TiCl}_4$  is a colourless, diamagnetic, covalent fuming liquid.  $\text{ZrCl}_4$  is a

white solid. In the gaseous state, all the halides are tetrahedral, but in the solid zig-zag chains of  $MX_n$  octahedra exist. The halides are all hydrolysed vigorously by water, and fume in moist air, giving  $TiO_2$ , though hydrolysis with aqueous  $HCl$  gives the oxochloride  $TiOCl_2$ .



The fluorides are more stable than the other halides.

The tetrahalides act as Lewis acids (electron pair acceptors) with a wide variety of donors, forming a large number of octahedral complexes.




Other ligands include phosphines  $R_3P$ , arsines  $R_3As$ , oxygen donors  $R_2O$ , and nitrogen donors such as pyridine, ammonia and trimethylamine. The complexes formed have the formula  $[TiX_4 \cdot L_2]$  and are octahedral. In most cases the added ligands are *cis* to each other.

Other coordination numbers are found in complexes. A few unusual five coordinate complexes exist such as  $Et_4N[Ti^{IV}Cl_5]^-$  and  $[TiCl_4 \cdot AsH_3]$ . A few seven coordinate complexes are known,  $Na_3[ZrF_7]$  and  $Na_3[HfF_7]$ . These have a pentagonal bipyramidal shape like  $IF_7$ . However, the structure of  $(NH_4)_3[ZrF_7]$  is a capped trigonal prism: the Zr is at the centre of a trigonal prism of six F atoms, with an extra F in the middle of one face. Another unusual compound is  $Ti(NO_3)_4$ . The  $NO_3^-$  groups are bidentate, that is two O atoms from each  $NO_3^-$  are bonded to Ti. Thus the coordination number of Ti is 8, and the shape is a nearly regular triangulated dodecahedron called a bisdisphenoid.  $Na_4[ZrF_8]$  and  $Na_4[HfF_8]$  also have a bisdisphenoid configuration. However, in  $[Cu(H_2O)_6]_2^{2+}[ZrF_8]^{4-}$  the Zr is eight-coordinate but has a square antiprism structure. (This may be visualized as a cube in which the top face has been rotated  $45^\circ$ .) The structures of the seven- and eight coordinate complexes are given in Figure 20.3.


### (+III) STATE

All the (+III) compounds have a  $d^1$  configuration and are coloured and paramagnetic.  $Ti(III)$  is much more basic than  $Ti(IV)$ , and the addition of alkali to  $Ti^{3+}$  solutions precipitates  $Ti_2O_3 \cdot (H_2O)_n$ , which is purple in colour, and insoluble in excess alkali.


The halides  $TiX_3$  are readily formed by reducing  $TiX_4$  compounds. Thus anhydrous  $TiCl_3$  can be obtained as a violet powder by reducing  $TiCl_4$  with  $H_2$  at  $600^\circ C$ .  $TiCl_3$  is important as the Ziegler-Natta catalyst (see later). Reduction of aqueous solutions containing  $Ti(+IV)$  with Zn gives the purple aqua ion  $[Ti(H_2O)_6]^{3+}$ . This is a powerful reducing agent, and is more powerful than  $Sn^{2+}$ . It is oxidized directly by air, and must be kept




(a)  $[\text{ZrF}_7]^{3-}$  ion in  $\text{Na}_3[\text{ZrF}_7]$   
pentagonal bipyramid



(b)  $[\text{ZrF}_7]^{3-}$  ion in  
 $(\text{NH}_4)_3[\text{ZrF}_7]$  trigonal prism  
with an extra atom in the middle  
of a rectangular face



(c)  $[\text{ZrF}_8]^{4-}$  ion in  
 $[\text{Cu}(\text{H}_2\text{O})_6]^{2+} [\text{ZrF}_8]^{4-}$  square  
antiprism (like a cube with the  
top face rotated  $45^\circ$ )





(d)  $[\text{ZrF}_8]^{4-}$  ion in  $\text{Na}_4[\text{ZrF}_8]$   
bisdisphenoid

Figure 20.3 Structures of some fluoride complexes.

out of direct sunlight. There are two different hydrated forms of  $\text{Ti}^{\text{III}}\text{Cl}_3$ . These have different colours. In one complex the  $\text{Ti}^{\text{III}}$  is surrounded by six  $\text{H}_2\text{O}$  molecules,  $[\text{Ti}(\text{H}_2\text{O})_6]^{3+} 3\text{Cl}^-$ , and in the other it is surrounded by five  $\text{H}_2\text{O}$  molecules and one  $\text{Cl}^-$ , giving  $[\text{TiCl}(\text{H}_2\text{O})_5]^{2+} 2\text{Cl}^-$ . These two environments give rise to a different degree of crystal field splitting of the  $d$  levels: hence the energy jump for the single  $d$  electron is different in the two cases, and their colours are different.

$\text{Ti}^{3+}$  is used in volumetric analysis for the determination of  $\text{Fe}^{3+}$  and also organic nitro compounds. In the iron titration the end point may be detected with ammonium thiocyanate which remains red whilst any  $\text{Fe}^{3+}$  is present, or by methylene blue which is reduced and decolorized as soon as  $\text{Ti}^{3+}$  is in excess.





A wide variety of complexes are formed for example  $[\text{Ti}^{\text{III}}\text{F}_6]^{-1}$ ,  $[\text{Ti}^{\text{III}}\text{Cl}_6]^{-1}$ ,  $[\text{Ti}^{\text{III}}\text{Cl}_5\text{H}_2\text{O}]^{2-}$ ,  $[\text{TiBr}_3(\text{dipyridyl})]$  and  $[\text{TiBr}_2(\text{dipyridyl})_2]^+$ ,  $[\text{TiBr}_4(\text{dipyridyl})]$

Zr(III) and Hf(III) are unstable in water and exist only as solid compounds

## ORGANOMETALLIC COMPOUNDS

### Ziegler-Natta catalysts

Solutions of  $\text{AlEt}_3$  and  $\text{TiCl}_4$  in a hydrocarbon solvent react exothermically to form a brown solid. This is the important Ziegler-Natta catalyst for polymerizing ethene (ethylene) to form polythene. Ziegler and Natta were awarded the Nobel Prize for Chemistry in 1963 for this work. (See also Chapter 12.) (Similar catalytic activity has been found from mixtures of Li, Be or Al alkyls with halides from Groups 4, 5 and 6, the Ti, V and Cr groups.)

The  $\text{AlEt}_3/\text{TiCl}_4$  catalyst is of great commercial importance. It produces stereoregular polymers (that is polymers where the molecules have the same orientation). These are stronger and have higher melting points than atactic or random polymers. Practically any alkene can be polymerized.

A large amount of work has been directed to how the catalyst works. The active species is  $\text{Ti}^{\text{III}}$  and the  $\text{AlEt}_3$  can reduce  $\text{TiCl}_4$  to  $\text{TiCl}_3$  in situ or  $\text{TiCl}_3$  may be added instead. Then one of the Cl atoms is replaced by an ethyl group. A possible mechanism is that the double bond in ethene attaches itself to a vacant site on a Ti atom on the surface of the catalyst. A carbon shift reaction occurs and the ethene migrates and is inserted between Ti and C in the Ti—Et bond. This extends the C chain from two to four atoms, leaving a vacant site on Ti. The process is repeated and the C chain grows in length. A similar reaction occurs with other alkenes such as propylene  $\text{CH}_3\text{—CH=CH}_2$ . When the double bond attaches to Ti the  $\text{CH}_3$  group must always point away from the surface simply because the reaction occurs on a surface. Thus when the molecule migrates and is inserted into the Ti—C bond it always has the same orientation. This is called *cis insertion* of the alkene and explains why the polymers produced are stereoregular.

Polymerization of ethene was originally carried out using a high temperature and pressure. By using a Ziegler-Natta catalyst polymerization can be carried out under relatively mild conditions from room temperature to  $93^\circ\text{C}$  and from atmospheric pressure to 100 atmospheres. Eventually the product is hydrolysed with water or alcohol and the catalyst is removed. The polymer produced is called high density polythene and has a density  $0.95\text{--}0.97\text{ g cm}^{-3}$  and a melting point of  $135^\circ\text{C}$ . It has a molecular weight of 20 000–30 000 and consists of straight chains with very little branching. This form of polythene is relatively hard and stiff. Another




Figure 20.4 Suggested polymerization with a Ziegler-Natta catalyst.

form of polythene called low-density polythene is much softer and has a lower density,  $0.91\text{--}0.94\text{ g cm}^{-3}$ , and a lower melting point of about  $115^\circ\text{C}$ . This consists of much branched chains, and is produced by a free radical polymerization of ethene and a promoter under much more severe conditions ( $190\text{--}210^\circ\text{C}$  and 1500 atmospheres pressure). Production of all forms of polythene was 24.6 million tonnes, and of polypropylene 12 million tonnes, both in 1991.

### Other compounds

No stable carbonyl compounds are known.  $\text{Ti}(\text{CO})_6$  has been formed using the matrix isolation technique by condensing Ti vapour and CO in a solid matrix of inert gas at very low temperatures. It has been studied spectroscopically. The absence of carbonyls is probably due to the shortage of  $d$  electrons for back bonding.

Cyclopentadienyl compounds are much more stable and better known. In describing organometallic compounds it is convenient to describe the hapticity  $\eta$  of a group as the number of C atoms associated with the metal. Several stable bis(cyclopentadienyls) are known such as  $[\text{Ti}(\eta^5\text{-C}_5\text{H}_5)_2(\text{CO})_2]$ ,  $[\text{Ti}(\eta^5\text{-C}_5\text{H}_5)_2(\text{NR}_2)_2]$  and  $[\text{Ti}(\eta^5\text{-C}_5\text{H}_5)_2(\text{SCN})_2]$ . The structures are roughly tetrahedral, but the cyclopentadienyl molecules are pentahaptic, that is five C atoms in each ring are attached to Ti. Reduction of these compounds gives  $[\text{Ti}(\text{C}_5\text{H}_5)_2\cdot\text{X}]$  or  $[\text{Ti}(\text{C}_5\text{H}_5)_2]$ . The latter formula resembles ferrocene  $[\text{Fe}(\text{C}_5\text{H}_5)_2]$ , but the structure of the Ti compound is dimeric, and hence is different.



Tetra(cyclopentadienyl) compounds such as  $\text{Ti}(\text{C}_5\text{H}_5)_4$  can be made from  $\text{TiCl}_4$  and  $\text{NaC}_5\text{H}_5$ . The formula may be written  $[\text{Ti}(\eta^5\text{-C}_5\text{H}_5)_2(\eta^1\text{-C}_5\text{H}_5)_2]$ , where two cyclopentadienyl rings are attached by five C atoms ( $\pi$  bonded) and two rings are attached by one C atom ( $\sigma$  bonded). Nuclear magnetic resonance studies on these tetra(cyclopentadienyl) compounds suggest that in the  $\eta^1$  rings the C bonded to Ti continually changes, and also the  $\eta^5$  and  $\eta^1$  rings interchange their roles. Hf forms an identical compound, but rather surprisingly the Zr compound has three  $\eta^5$  rings and only one  $\eta^1$  ring.

Only a few alkyls and aryls are known and they are generally unstable in air and water.  $\text{C}_6\text{H}_5\text{Ti}(\text{C}_3\text{H}_7\text{O})_3$ ,  $\text{CH}_3\text{TiCl}_3$  and  $\text{Ti}(\text{CH}_2\text{Ph})_4$  are stable at  $10^\circ\text{C}$ , and  $\text{Ti}(\text{CH}_3)_4$  is stable below  $-20^\circ\text{C}$ . Most compounds with an alkyl group attached to Ti will polymerize alkenes.

Some organometallic  $\text{Ti}^{\text{II}}$  compounds are able to fix  $\text{N}_2$  gas and produce  $\text{NH}_3$ . One example is  $(\text{C}_{10}\text{H}_{10}\text{Ti})_2$ . This cycle could be similar to the dinitrogen fixation process in nature. (Dinitrogen complexes are discussed under ruthenium(II) complexes in Chapter 24.)




Figure 20.5 Cycle for fixation of dinitrogen

## FURTHER READING

- Allen, A. D. (1973) Complexes of dinitrogen. *Chem. Rev.*, **73**, 11.  
 Boor, J. (1979) *Ziegler-Natta Catalysts and Polymerizations*, Academic Press, New York.  
 Canterford, J. H. and Cotton, R. (1968) *Halides of the Second and Third Row Transition Elements*, Wiley, London.  
 Canterford, J. H. and Cotton, R. (1969) *Halides of the First Row Transition Elements*, Wiley, London.  
 Corbett, J. D. (1981) Extended metal-metal bonding in halides of the early transition metals, *Acc. Chem. Res.*, **14**, 239.  
 Davis, K. A. (1982) Titanium dioxide (Chemical of the month), *J. Chem. Ed.*, **59**, 158-159.  
 Jones, D. J. (1988) The story of titanium, *Chemistry in Britain*, **24**, 1135-1138.  
 Kepert, D. L. (1972) *The Early Transition Metals* (Chapter 2), Academic Press, London.  
 Kettle, S. F. A. (1969) *Coordination Compounds*, Nelson, London. (Spectra  $\text{Ti}^{3+}$ ).  
 Shriver, D. H., Kaesz, H. D. and Adams, R. D. (eds) (1990) *Chemistry of Metal Cluster Complexes*, VCH, New York.  
 Sinn, H. and Kaminsky, W. (1980) Ziegler-Natta Catalysts. *Adv. Organometallic Chem.*, **18**, 99-143. (A good account).  
 Thompson, R. (ed.) (1986) *The Modern Inorganic Chemicals Industry*, (Chapter by Darby, R. S. and Leighton, J. Titanium dioxide pigments), Special Publication No. 31, The Chemical Society, London.

# Group 5 – the vanadium group

21

**Table 21.1** Electronic structures and oxidation states

Element		Electronic structure	Oxidation states*
Vanadium	V	[Ar] 3d <sup>3</sup> 4s <sup>2</sup>	(-I) (0) (I) (II) III IV V
Niobium	Nb	[Kr] 4d <sup>3</sup> 5s <sup>2</sup>	(-I) (0) (I) (II) III (IV) V
Tantalum	Ta	[Xe] 4f <sup>14</sup> 5d <sup>3</sup> 6s <sup>2</sup>	(-I) (0) (I) (II) III (IV) V

\* The most important oxidation states (generally the most abundant and stable) are shown in bold. Other well-characterized but less important states are shown in normal type. Oxidation states that are unstable, or in doubt, are given in parentheses.

## INTRODUCTION

Vanadium is commercially important as the alloy ferrovanadium which is used to make alloy steels. V<sub>2</sub>O<sub>5</sub> is well known and is an important catalyst, and V metal is also used as a catalyst. The vanadates have an extensive solution chemistry. Niobium and tantalum are only used in small quantities. However, there is great theoretical interest in the cluster compounds they form in their low oxidation states.

## ABUNDANCE, EXTRACTION AND USES

V, Nb and Ta have odd atomic numbers and are less abundant than their neighbours. However, V is the nineteenth most abundant element by weight in the earth's crust, and is the fifth most abundant transition element. It is widely spread, and there are few concentrated deposits. Much is obtained as a by-product from other processes. It occurs in lead ores as vanadinite PbCl<sub>2</sub>·3Pb<sub>3</sub>(VO<sub>4</sub>)<sub>2</sub>, in uranium ores as carnotite K<sub>2</sub>(UO<sub>2</sub>)<sub>2</sub>(VO<sub>4</sub>)<sub>2</sub>·3H<sub>2</sub>O and in some crude oil from Venezuela and Canada. Vanadate residues are heated with Na<sub>2</sub>CO<sub>3</sub> or NaCl at 800°C. The sodium vanadate NaVO<sub>3</sub> formed is then leached out with water, acidified with H<sub>2</sub>SO<sub>4</sub> to precipitate red coloured sodium polyvanadate, and heated to 700°C to give V<sub>2</sub>O<sub>5</sub>. (This is black, possibly because of

*continued overleaf*

impurities usually  $V_2O_5$  is red or orange ) Over 75% of the  $V_2O_5$  is converted to an iron/vanadium alloy called ferrovanadium. This contains about 50% Fe. It is made by heating  $V_2O_5$  with iron or iron oxide and a reducing agent such as C, Al or ferrosilicon. Ferrovanadium is used commercially to make steel alloys for springs and high speed cutting tools. Vanadium metal is seldom used on its own. It is difficult to prepare because at the elevated temperatures used in metallurgy it reacts with  $O_2$ ,  $N_2$  and C. Pure vanadium can be obtained by reducing  $VCl_5$  with H or Mg, by reducing  $V_2O_5$  with Ca, or by electrolysis of a fused halide complex. World production of V in alloys and pure metal was 28 400 tonnes in 1992.

$V_2O_5$  is extremely important as the catalyst in the conversion of  $SO_2$  into  $SO_3$  in the Contact process for making  $H_2SO_4$ . It has replaced Pt as catalyst

Table 21.2 Abundance of the elements in the earth's crust by weight

	ppm	Relative abundance
V	136	19
Nb	20	32
Ta	1.7	53

because it is much cheaper and is less susceptible to poisoning by impurities such as arsenic. Vanadium is an important catalyst in oxidation reactions such as naphthalene  $\rightarrow$  phthalic acid and toluene  $\rightarrow$  benzaldehyde. A Cu/V alloy is used as a catalyst in the oxidation of cyclohexanol/cyclohexanone mixtures to adipic acid. (Adipic acid is used to make nylon 66.) Vanadium is also used as a catalyst for the reduction (hydrogenation) of alkenes and aromatic hydrocarbons.

Niobium and tantalum occur together. The most important mineral is pyrochlorite  $CaNaNb_2O_6F$ . Much smaller amounts of columbite  $(Fe, Mn)Nb_2O_6$  and tantalite  $(Fe, Mn)Ta_2O_6$  are also mined. However, 60% of Ta is recovered from the slag from extracting Sn. The ores are dissolved either by fusion with alkali or in acid. Formerly separation of Nb and Ta was achieved by treatment with a solution of HF when Nb formed soluble  $K_2[NbOF_6]$  and Ta formed insoluble  $K_2[TaF_7]$ . Separation is now performed by solvent extraction from dilute HF to methyl isobutyl ketone. The metals are obtained either by reducing the pentoxides with Na, or by electrolysis of molten fluoro complexes such as  $K_2[NbF_7]$ . In 1992 world production was 15 200 tonnes of Nb and 600 tonnes of Ta.

Nb is used in various stainless steels and Nb/steel is used to encapsulate the fuel elements for some nuclear reactors. A Nb/Zr alloy is a superconductor at low temperatures and is used to make wire for very powerful electromagnets. Ta is used to make capacitors for the electronics industry. Because it is not rejected by the human body it is valuable for making metal plates, screws and wire for repairing badly fractured bones. Tantalum carbide TaC is one of the highest melting solids known (about 3800°C).

## OXIDATION STATES

The maximum oxidation state for this group is (+V). All three elements show the full range of oxidation states from (−I) to (+V). For vanadium the (+II) and (+III) states are reducing, (+IV) is stable, and (+V) slightly oxidizing. For Nb and Ta the (+V) state is by far the most stable and the best known, although lower oxidation states are known.

V(+V) is reduced by zinc and acid to  $V^{2+}$ , Nb(+V) is reduced to  $Nb^{3+}$  but Ta(+V) is not reduced. This illustrates the increasing stability of the (+V) state on descending the group. At the same time the lower oxidation states become less stable. *This is the opposite trend to that in the main groups.*

## SIZE

The atoms are smaller than those of Group 4 due to the poor shielding of the nucleus by *d* electrons. The covalent and ionic radii of Nb and Ta are identical because of the lanthanide contraction (Table 21.3). Consequently these two elements have very similar properties, occur together, and are very difficult to separate.

## GENERAL PROPERTIES

V, Nb and Ta are silvery coloured metals with high melting points. V has the highest melting point in the first row transition elements. This is associated with the maximum participation of *d* electrons in metallic bonding. The melting points of Nb and Ta are high, but the maximum melting point in the second and third row transition elements occurs in the next group (Group 6) with Mo and W.

The pure metals V, Nb and Ta are moderately soft and ductile, but traces of impurities make them harder and brittle. They are extremely resistant to corrosion due to the formation of a surface film of oxide. At room temperature they are not affected by air, water or acids, other than HF with which they form complexes. V also dissolves in oxidizing acids such as hot concentrated  $H_2SO_4$ ,  $HNO_3$  and aqua regia. V is unaffected by alkali, showing that it is completely basic, but Nb and Ta dissolve in fused alkali.

Table 21.3 Some physical properties

	Covalent radius (Å)	Ionic radius (Å)		Melting point (°C)	Boiling point (°C)	Density (g cm <sup>−3</sup> )	Pauling's electro- negativity
		M <sup>2+</sup>	M <sup>3+</sup>				
V	1.22	0.79	0.640	1915	3350	6.11	1.6
Nb	1.34	–	0.72	2468	4758	8.57	1.6
Ta	1.34	–	0.72	2980	5534	16.65	1.5

At high temperatures all three metals react with many non-metals. The products are often interstitial compounds which are non stoichiometric.

V forms many different positive ions but Nb and Ta form virtually none. Thus though Nb and Ta are metals, their compounds in the (+V) state are mostly covalent, volatile, and readily hydrolysed – properties associated with non-metals.

The tendency to form simple ionic compounds decreases as the oxidation state increases. Even though  $V^{2+}$  and  $V^{3+}$  are reducing, they exist both in the solid and in solution (as hexahydrate ions). They have an extensive aqueous chemistry. The oxidation state (+IV) is dominated by the  $VO^{2+}$  ion. This is very stable and exists in a wide range of compounds both as solids and in solution (as the hydrated ion). Some covalent (+IV) compounds such as  $VCl_4$  also exist. The (+V) state may be covalent as in  $VF_5$ , or form  $VO_2^+$  or  $VO_3^-$  hydrated ions. The chemistry of Nb and Ta is largely confined to the (+V) state.

The basic properties of the oxides  $M_2O_5$  increase down the group.  $V_2O_5$  is amphoteric but mainly acidic. It dissolves slightly in water, giving a pale yellow acidic solution. It dissolves readily in NaOH, forming colourless solutions which contain a wide range of vanadate ions. The ions formed depend on the pH: various isopolyvanadates at intermediate pH and orthovanadate  $VO_4^{3-}$  at high pH. The aqueous chemistry of the polymerized vanadates is quite complex.  $V_2O_5$  also dissolves slightly in concentrated  $H_2SO_4$  forming the pale yellow  $VO_2^+$  ion.  $Nb_2O_5$  and  $Ta_2O_5$  are rather unreactive but are amphoteric. They have only very weak acidic properties. Niobates and tantalates are only formed by fusing with NaOH. They are decomposed by weak acids or  $CO_2$ , and only partially imitate the behaviour of the isopolyvanadates.

Whilst  $V^{2+}$  and  $V^{3+}$  are well known, Nb(II), Ta(II), Nb(III) and Ta(III) are not ionic but exist as cluster compounds  $M_6X_{12}$ , in which groups of metal atoms are bonded together.

## COLOUR

Colour in transition metal compounds very commonly arises from  $d-d$  electronic transitions. It can also arise from defects in the solid state (see Chapter 3) and from charge transfer spectra. (Charge transfer spectra are discussed under  $SnI_4$  in Chapter 13.) The oxidation states below (+V) are coloured because they have an incomplete  $d$  shell of electrons and give  $d-d$  spectra. However, the (+V) state has a  $d^0$  configuration and so colourless compounds would be expected.  $NbF_5$ ,  $TaF_5$  and  $TaCl_5$  are white, but  $V_2O_5$  is red or orange,  $NbCl_5$  is yellow,  $NbBr_5$  is orange and  $NbI_5$  is brass coloured. The colours arise because of charge transfer.

## COMPOUNDS WITH NITROGEN, CARBON AND HYDROGEN

At high temperatures the metals react with  $N_2$  forming interstitial nitrides  $MN$ , and with C, forming two series of carbides  $MC$  and  $MC_2$ . Carbides

such as NbC and TaC are interstitial, refractory and very hard, like TiC and HfC in the previous group. TaC has the highest melting point of any compound, about 3800 °C. In contrast, carbides such as VC<sub>2</sub> are ionic and react with water, liberating ethyne.

All three elements react with H<sub>2</sub> on heating, forming nonstoichiometric hydrides. The amount of hydrogen absorbed depends on the temperature and pressure. Here, as in the titanium group, the metal lattice expands as hydrogen enters interstitial positions. Thus the density of the hydride is less than that of the metal. It is difficult to decide if these are true compounds or solid solutions, as the maximum hydrogen contents are VH<sub>0.71</sub>, NbH<sub>0.86</sub> and TaH<sub>0.76</sub>.

## HALIDES

When V is heated with the halogens, halides of different oxidation states are formed: VF<sub>5</sub>, VCl<sub>4</sub>, VBr<sub>3</sub> and VI<sub>3</sub>. Nb and Ta react with all of the halogens on heating to give pentahalides MX<sub>5</sub>. The range of halides which have been formed is summarized in Table 21.4. All the halides are volatile, covalent and hydrolysed by water.

Table 21.4 Halides


Oxidation states				
(+II)	(+III)	(+IV)	(+V)	
VF <sub>2</sub> blue	VF <sub>3</sub> yellow-green	VF <sub>4</sub> green	VF <sub>5</sub> colourless	
VCl <sub>2</sub> pale green	VCl <sub>3</sub> red-violet	VCl <sub>4</sub> reddish brown	— (liquid)	
VBr <sub>2</sub> orange-brown	VBr <sub>3</sub> brown	VBr <sub>4</sub> magenta	—	
VI <sub>2</sub> red-violet	VI <sub>3</sub> black-brown	—	—	
—	(NbF <sub>3</sub> ) *blue	NbF <sub>4</sub> black	NbF <sub>5</sub> white	
—	NbCl <sub>3</sub> black	NbCl <sub>4</sub> violet	NbCl <sub>5</sub> yellow	
—	NbBr <sub>3</sub> brown	NbBr <sub>4</sub> brown	NbBr <sub>5</sub> orange	
—	NbI <sub>3</sub>	NbI <sub>4</sub> grey	NbI <sub>5</sub> brass	
—	(TaF <sub>3</sub> ) *blue	—	TaF <sub>5</sub> white	
—	TaCl <sub>3</sub> black	TaCl <sub>4</sub> black	TaCl <sub>5</sub> white	
—	TaBr <sub>3</sub>	TaBr <sub>4</sub> blue	TaBr <sub>5</sub> yellow	
—	—	TaI <sub>4</sub>	TaI <sub>5</sub> black	

The most stable oxidation states are shown in bold.

\* may be oxide fluorides.

### (+V) halides

V forms only a pentafluoride, but Nb and Ta form the full range of halides. These may be formed by direct reaction of the elements or by the reactions






Figure 21.1 Tetrameric structure of  $\text{NbF}_5$  and  $\text{TaF}_5$

$\text{VF}_5$  is a colourless liquid but the other pentahalides are solids. They adopt several different structures. The fluorides are built of octahedral  $\text{MF}_6$  units with two *cis* fluorine atoms in each octahedron acting as bridging groups  $\text{V}-\text{F}-\text{V}$  with other octahedra.  $\text{VF}_5$  forms long chains of octahedra in this way, but  $\text{NbF}_5$  and  $\text{TaF}_5$  form cyclic tetramers with four octahedra joined in this way (Figure 21.1).

This structure is also found in other pentahalides, e.g.  $\text{MoF}_5$ ,  $\text{RuF}_5$  and  $\text{OsF}_5$ . Solid  $\text{NbCl}_5$  and  $\text{TaCl}_5$  are dimeric with two octahedra joined by sharing two corners, i.e. one edge (Figure 21.2).

All of the pentahalides can be sublimed under an atmosphere of the appropriate halogen. In the vapour phase they probably exist as monomeric trigonal bipyramids.

The pentafluorides all react with  $\text{F}^-$  ions, forming octahedral  $[\text{MF}_6]^-$  complexes. As in Group 4, the heavier elements can form complexes with higher coordination numbers. With high concentrations of  $\text{F}^-$  the complexes  $[\text{NbOF}_5]^{2-}$ ,  $[\text{NbF}_7]^{2-}$  and  $[\text{TaF}_7]^{2-}$  are formed. The structures of the seven coordinate species are capped trigonal prisms, i.e. a trigonal prism with one extra atom in a rectangular face (see Figure 20.3b). With an even higher concentration of  $\text{F}^-$ , Ta forms  $[\text{TaF}_8]^{3-}$  with a square antiprism structure (Figure 20.3c) while Nb forms  $[\text{NbOF}_6]^{3-}$  which is an octahedron with an extra atom in one of the faces. This inability of Ta to form oxohalides has been used to separate Nb and Ta.

On warming the halides  $\text{MF}_5$  and  $\text{MCl}_5$  with donors such as dimethyl ether  $(\text{CH}_3)_2\text{O}$  or dimethyl sulfoxide  $(\text{CH}_3)_2\text{SO}$ , the halides extract O and form oxochlorides  $\text{MOCl}_3$ . Oxohalides are also formed when the pentahalides are heated in air.  $\text{VOCl}_3$  can also be made by heating  $\text{V}_2\text{O}_5$  with  $\text{Cl}_2$  (or sometimes C and  $\text{Cl}_2$ ). The oxohalides are all readily hydrolysed by water to the hydrated pentoxide. The oxohalides are tetrahedral in shape.

The pentahalides react with  $\text{N}_2\text{O}_4$  in giving solvated nitrates such as  $\text{NbO}_2 \cdot \text{NO}_3 \cdot 0.67\text{MeCN}$ , and anhydrous nitrates such as  $\text{NbO}(\text{NO}_3)_3$ .

The (+V) halides have a  $d^0$  configuration, and cannot give  $d-d$  spectra. The fluorides are white but the other halides are coloured due to charge transfer spectra.






Figure 21.2 Dimeric structure of  $\text{NbCl}_5$ .

### (+IV) halides

All the tetrahalides are known except  $\text{TaF}_4$ . These may be prepared as follows:



$\text{VCl}_4$  is tetrahedral in the gas. The  $d^1$  configuration of  $\text{V}(+IV)$  would be expected to make this unstable and to cause distortion. In the liquid it is dimeric.  $\text{NbF}_4$  is a black, paramagnetic involatile solid made up of regular octahedra joined in a chain by their edges. The tetrachlorides, tetrabromides and tetraiodides of Nb and Ta are also brown-black solids and are diamagnetic. This suggests extensive metal-metal interaction. In  $\text{NbI}_4$ , the structure is a chain of octahedra joined by their edges. The Nb atoms are displaced from the centre of the  $\text{NbI}_6$  octahedron and occur in pairs, thus permitting weak Nb—Nb bonds of length  $3.20 \text{ \AA}$ , and pairing the previously unpaired electron spins (Figure 21.3).  $\text{NbCl}_4$  is similar and has M—M bonds of length  $3.06 \text{ \AA}$ .

The tetrahalides tend to disproportionate:









Figure 21.3 Polymeric structure of  $\text{NbI}_4$ , with metal-metal bonds.





They also hydrolyse with water




### (+III) halides

All the trihalides are known except for  $\text{TaI}_3$ . They are reducing, have a  $d^2$  configuration, and are brown or black in colour. The  $\text{VX}_3$  compounds are all polymeric compounds in which V is octahedrally surrounded.  $\text{VCl}_3$  and  $\text{VBr}_3$  can be made from the elements, and  $\text{VF}_3$  is made from  $\text{VCl}_3$  and  $\text{HF}$ .  $\text{VF}_3$  can be crystallized from water, giving  $[\text{VF}_3(\text{H}_2\text{O})_3]$ , and for the other halides  $[\text{V}(\text{H}_2\text{O})_6]^{3+}$  and three  $\text{X}^-$  ions.  $\text{VCl}_3$  forms complexes such as  $\text{VCl}_3(\text{NMe}_3)_2$  which has a trigonal bipyramid shape.  $\text{VI}_3$  disproportionates as follows




### Spectra

The  $\text{V}^{3+}$  ion has a  $d^2$  configuration. The two  $d$  electrons occupy two of the  $t_{2g}$  orbitals, i.e. any two from  $d_{xy}$ ,  $d_{xz}$  and  $d_{yz}$ . The ground state is triply degenerate and has the symbol  ${}^3T_{1g}(F)$ . At first sight it might be expected that by promoting these electrons to the  $e_g$  level two  $d-d$  absorption bands would occur in the electronic spectrum. Under suitable conditions three bands are observed. If one electron is promoted from the  $t_{2g}$  level to the  $e_g$  level then the most stable arrangement (i.e. that with the lowest energy) will be when the two electrons occupy orbitals as far apart as possible, i.e. at right angles to each other. Thus if one electron occupies the  $d_{xy}$  orbital, the structure would be more stable if the other electron occupied the  $d_{xz}$  orbital rather than the  $d_{yz}$  orbital. There are three degenerate ways of arranging these two electrons in orbitals perpendicular to each other



This state is the  ${}^3T_{2g}$ . Somewhat higher in energy is another triply degenerate state written as  ${}^1T_{2g}$  in which the orbitals occupied are at  $45^\circ$  to each other



If both electrons are promoted to the  $e_g$  level then assuming they remain unpaired the only arrangement possible is

$$(d_{x^2-y^2})^1 (d_{z^2})^1$$

This state has the symbol  ${}^3A_{2g}$ . Thus there are three possible transitions from the ground state to excited states with the same multiplicity:

$${}^3T_{1g}(F) \rightarrow {}^3T_{2g}$$

$${}^3T_{1g}(F) \rightarrow {}^3T_{1g}(P)$$

and

$${}^3T_{1g}(F) \rightarrow {}^3A_{2g}$$

Thus three bands are possible. (See Chapter 32, particularly Figure 32.16). In the spectrum of  $[V(H_2O)_6]^{3+}$  only two bands are actually observed, at about  $17000\text{ cm}^{-1}$  and  $24000\text{ cm}^{-1}$ . The third band arising from the transition to  ${}^3A_{2g}$  is not observed experimentally. Since this transition is a two electron transition it is less probable than the others and so will have a low intensity. Furthermore this band overlaps, and is hidden by, the very intense charge transfer band in the UV region. All three bands are observed when  $V^{3+}$  is incorporated into an  $Al_2O_3$  lattice.


The discussion above indicates that in addition to the crystal field splitting  $\Delta_o$  the interelectronic repulsion must also be taken into account when explaining the spectra. The repulsion terms are described by the Racah parameters B and C (see Chapter 32).

### *Nb and Ta halides*

The trihalides of Nb and Ta are typically nonstoichiometric. In  $NbCl_3$  the Nb ions occupy octahedral holes in a distorted hexagonal close-packed array of  $Cl^-$  ions in such a way that niobium atoms in three adjacent octahedra are close enough to be bonded together into a metal cluster. Compounds where three or more metal atoms are held together by multi-centre bonding are called cluster compounds.

### *(+II) halides*

All the vanadium dihalides are known. The  $VX_2$  compounds are prepared by reducing the trihalides with Zn/acid in aqueous solution.  $VF_2$  has a rutile  $TiO_2$  structure, and the others have a  $CdI_2$ -type layer structure. They are soluble in water, giving violet solutions containing  $[V(H_2O)_6]^{2+}$ . Addition of NaOH precipitates  $V(OH)_2$ , and addition of  $H_2SO_4$  and ethanol precipitates violet crystals of  $VSO_4 \cdot 6H_2O$ . The compounds are strongly reducing, and are hygroscopic. Their solutions are readily oxidized by air to  $[V(H_2O)_6]^{3+}$ , and they are often used to remove traces of  $O_2$  from the noble gases. They also reduce  $H_2O$  with the liberation of  $H_2$ . Nb and Ta behave very differently. High temperature reduction of the pentahalides  $NbX_5$  and  $TaX_5$  with sodium or aluminium yields a series of lower halides such as  $M_6Cl_{14}$ ,  $M_6I_{14}$ ,  $Nb_6F_{15}$ ,  $Ta_6Cl_{15}$ ,  $Ta_6Br_{15}$  and  $Ta_6Br_{17}$ . These are all based on the  $[M_6X_{12}]^{n+}$  unit. For example, if  $Nb_6Cl_{14}$  is dissolved in water and alcohol, and treated with  $AgNO_3$




solution, only two chlorine atoms are precipitated as AgCl. This indicates the presence of  $[\text{Nb}_6\text{Cl}_{12}]^{2+}$  ions and two  $\text{Cl}^-$  ions, and this structure has been confirmed by X ray crystallography (Figure 21.4). The Nb atoms are bonded together, forming an octahedral cluster of six metal atoms. The halogen atoms are situated above each edge of the octahedron and are bonded to two Nb atoms. Thus the halogens form bridges along the 12 edges of the octahedron. The structure is held together by both multi-centre bonding over the six metal atoms and by the halogen bridges.

### STANDARD REDUCTION POTENTIALS (VOLTS)

Acid solution								
Oxidation state								
+V	IV	III	+II	+1	0			
$\text{V}(\text{OH})_4^+$	$\xrightarrow{+1.0}$	$\text{VO}^{2+}$	$\xrightarrow{+0.34}$	$\text{V}^{3+}$	$\xrightarrow{-0.26}$	$\text{V}^{2+}$	$\xrightarrow{-1.18}$	V
				$\xrightarrow{-0.26}$				
$\text{Nb}_2\text{O}_5$	$\xrightarrow{0.05}$		$\text{Nb}^{3+}$	$\xrightarrow{-1.10}$		Nb		
				$\xrightarrow{-0.64}$				
$\text{Ta}_2\text{O}_5$			$\xrightarrow{-0.75}$		Ta			



paramagnetic and the magnetic moment corresponds to one unpaired electron. Cluster compounds of this type are characteristic of the lower oxidation states of Nb and Ta. Many of these cluster compounds are soluble in water, and the cluster remains intact during reactions. The clusters can be oxidized:



A very unusual structure is found in  $Nb_6I_{11}$ , where the six Nb atoms form an octahedral cluster as before, but eight iodine atoms are situated above the eight faces of the octahedron. Each of these I atoms act as bridging group to three metal atoms within the octahedron. The rest of the I atoms are bonded to the six corners of the metal octahedron. These act as halogen bridges to other octahedra. The formula is thus  $[Nb_6I_8] + \frac{1}{2}I_6$  which is  $Nb_6I_{11}$ .

## OXIDES

The metals all react with dioxygen at elevated temperatures and give pentoxides  $M_2O_5$ .  $V_2O_5$  is orange or red depending on the state of division, but the others are white. When made this way,  $VO_2$  can also be formed. Pure  $V_2O_5$  is obtained either by acidifying ammonium metavanadate, or simply by heating it:



The main oxides formed are shown in Table 21.5. The lower oxides often exist over a wide range of composition.

### (+V) oxides




The oxides  $M_2O_5$  can all be made by heating the metal in dioxygen. However,  $V_2O_5$  is best made by heating ammonium metavanadate  $NH_4VO_3$ .  $Nb_2O_5$  and  $Ta_2O_5$  are commonly made by ignition of other Nb or Ta compounds in air. In the pentoxides the metal atoms all have a  $d^0$  configuration, and might be expected to be colourless.  $Nb_2O_5$  and  $Ta_2O_5$  are white, but  $V_2O_5$  is orange or red coloured due to charge transfer.

Table 21.5 Oxides

Oxidation state			
(+II)	(+III)	(+IV)	(+V)
VO	$V_2O_3$	$VO_2$	<b><math>V_2O_5</math></b>
NbO	—	$NbO_2$	<b><math>Nb_2O_5</math></b>
(TaO)	—	$TaO_2$	<b><math>Ta_2O_5</math></b>

The most stable oxidation states are shown in bold.

$V_2O_5$  is amphoteric, but is mainly acidic. With very strong NaOH it forms colourless orthovanadate ions  $VO_4^{3-}$ . At slightly higher pH these polymerize to form a wide range of isopolyacids called polyvanadates. These are described later.  $V_2O_5$  dissolves in very strong acid, forming eventually the pale yellow dioxovanadium(V) ion  $VO_2^+$ . This ion has an angular shape. Some reactions of  $V_2O_5$  are as follows:



Though  $Nb_2O_5$  and  $Ta_2O_5$  react with HF and form niobates and tantalates when fused with NaOH, they are better described as unreactive rather than amphoteric.

The structure of  $V_2O_5$  is unusual and consists of distorted trigonal bipyramids of  $VO_5$  units sharing edges with other units to form zig zag double chains. Its use as a catalyst in the Contact process has been mentioned previously. The catalytic activity may be because it can reversibly lose or gain oxygen when heated.

#### (+IV) oxides

$VO_2$  can be made from  $V_2O_5$  with mild reducing agents such as  $Fe^{2+}$ ,  $SO_2$  or oxalic acid. V(+IV) has a  $d^1$  configuration and  $VO_2$  is dark blue in colour. The oxide is amphoteric, but is more basic than acidic. In acids it forms blue solutions containing the oxovanadium(IV) ion  $VO^{2+}$ . This is commonly called the vanadyl ion. A large number of vanadyl compounds are known: vanadyl sulphate  $VOSO_4$  and vanadyl halides  $VOX_2$ . Several vanadyl complexes are also known,  $[VOX_4]^{2-}$  where X is a halogen,  $[VO(\text{oxalate})_3]^{2-}$ ,  $[VO(\text{bipyridyl})_2Cl]^+$ ,  $[VO(NCS)_3]^{2-}$  and  $[VO(\text{acetylacetonate})_2]$ .




Figure 21.5 Structure of vanadyl acetylacetonate  $[VO(\text{acetylacetonate})_2]$

The structure of these is related to an octahedron with one position unoccupied (Figure 21.5). The sixth position may be filled quite readily by a sixth ligand, for example pyridine  $C_5H_5N$  in  $[VO(\text{acetylacetonate})_2]$ .

(pyridine)]. In these compounds the V—O bonds are 1.56–1.59 Å. This is shorter than a single bond, and the bond is better represented as V=O. The  $\pi$  bond arises from back bonding from a filled  $p$  orbital on O with an empty  $d$  orbital on V, similar to the oxides and oxoacids of phosphorus.

### (+III) oxides

$\overline{\text{V}_2\text{O}_3}$  is nonstoichiometric ( $\text{VO}_{1.35-1.5}$ ) and contains simple ions arranged in the corundum  $\text{Al}_2\text{O}_3$  type of structure. It can be produced by high temperature reduction of  $\text{V}_2\text{O}_5$  with carbon or hydrogen, or by electrolytic reduction of a vanadate. The oxide is completely basic. It dissolves in acids, forming blue or green hydrated ions  $[\text{V}(\text{H}_2\text{O})_6]^{3+}$ , and these solutions are quite strongly reducing. Addition of NaOH precipitates hydrated  $\text{V}(\text{OH})_3$ , but this has no tendency to dissolve in excess NaOH. The oxidation state (+III) has a  $d^2$  configuration, and the oxide is black and the hydrated ion is blue. A considerable number of octahedral complexes are known such as  $[\text{V}(\text{H}_2\text{O})_6]^{3+}$ ,  $[\text{VF}_6]^{3-}$ ,  $[\text{V}(\text{CN})_6]^{3-}$  and  $[\text{V}(\text{oxalate})_3]^{3-}$ . Vanadium also forms a triacetate complex, which is dimeric  $[\text{V}^{\text{III}}_2(\text{acetate})_6]$ . This has an unusual structure. Four of the acetate groups act as bridging groups through O atoms to the two V atoms. The remaining two acetate groups act as unidentate ligands and one is attached to each V. The structure is related to the structures of chromium(II) acetate  $[\text{Cr}_2(\text{acetate})_4 \cdot (\text{H}_2\text{O})_2]$  and copper acetate  $[\text{Cu}_2(\text{acetate})_4 \cdot (\text{H}_2\text{O})_2]$ . (See Figure 22.2.) Both are dimeric, and both have four bridging acetate groups, but the terminal acetate groups in the V compound are replaced by two molecules of water. In water,  $[\text{V}(\text{H}_2\text{O})_6]^{3+}$  partially hydrolyses to  $\text{V}(\text{OH})^{2+}$  and  $\text{VO}^+$ .


### (+II) oxides

$\overline{\text{VO}}$  is nonstoichiometric, of composition  $\text{VO}_{0.94-1.12}$ . The solid is ionic and has a defect NaCl type of structure. The (+II) state has a  $d^3$  configuration, and the oxide is grey-black and has a metallic lustre. It is made by reducing  $\text{V}_2\text{O}_5$  with hydrogen at 1700°C. It has a fairly high electrical conductivity, which is probably due to metal-metal bonding in the structure. The oxide is completely basic, and is soluble in water. Addition of NaOH to this solution precipitates  $\text{V}(\text{OH})_2$ . VO dissolves in acids, forming violet coloured  $[\text{V}(\text{H}_2\text{O})_6]^{2+}$  ions. These solutions are strongly reducing, and are very readily oxidized both by air and water. Thus the violet solution soon turns green through oxidation to  $[\text{V}(\text{H}_2\text{O})_6]^{3+}$ . A few octahedral complexes are known such as  $\text{K}_4[\text{V}(\text{CN})_6] \cdot 7\text{H}_2\text{O}$  and  $[\text{V}(\text{ethylenediamine})_3]\text{Cl}_2$ .  $\text{K}_4[\text{V}(\text{CN})_7] \cdot 2\text{H}_2\text{O}$  is also known, and the structure of the anion is a pentagonal bipyramid.

## VANADATES

Though  $\text{V}_2\text{O}_5$  is amphoteric, it is mainly acidic. It dissolves in very strong NaOH, forming a colourless solution containing orthovanadate ions

$\text{VO}_4^{3-}$  These are tetrahedral in shape. If acid is added gradually to lower the pH, the ions add protons and polymerize. Thus a very large number of different isopolyacids are formed in solution. The oxoions polymerize to form dimers, trimers and pentamers. When the solution becomes acidic the hydrated oxide  $\text{V}_2\text{O}_5 \cdot (\text{H}_2\text{O})_n$  is precipitated. This dissolves in very strong acid, forming various complex ions until finally the dioxovanadium ion  $\text{VO}_2^+$  is formed. Various solids have been crystallized out at different pH values, but these do not necessarily have the same structure and are unlikely to be hydrated to the same extent as the species in solution. The following scheme could explain the observations though the extent to which the various species are hydrated is unknown.



\* Included because solids of this formula have been precipitated

$\text{Nb}_2\text{O}_5$  and  $\text{Ta}_2\text{O}_5$  are white and chemically inert. They are hardly attacked by acids, except HF which forms fluoro complexes. If the pentoxides are fused with NaOH, niobates and tantalates are formed. These precipitate the hydrated oxides at pH 7 and 10 respectively, and the only isopolyion found in solution is  $[\text{M}_6\text{O}_{19}]^{8-}$ .

In the main groups, the phosphates, silicates and borates all show a strong tendency for the oxoions to polymerize, forming a very large number of isopolyacids. In a similar way in the *d* block molybdates and tungstates also polymerize to form a large number of isopolyacids. This tendency is shown to a lesser extent by  $(\text{TiO}_2^{2+})_n$  and  $\text{CrO}_4^{2-} \rightarrow \text{Cr}_2\text{O}_7^{2-}$ .

Vanadate ions also form complexes with the ions of other acids. Because there is more than one type of acid unit which condenses these are called heteropolyacids. They always contain vanadate, molybdate or tungstate ions together with one or more acidic ions (such as phosphate, arsenate or silicate) from about 40 elements. The ratio between the numbers of the different types of units is commonly 12 : 1 or 6 : 1, giving the 12 polyacids and the 6 polyacids. However, other ratios are also found. A study of heteropolyacids is very difficult because

- 1 The molecular weight is high, often 3000 or more
- 2 The water content is variable
- 3 The ions present change with the pH
- 4 The species present in solution are probably different from those which crystallize out

## LOW OXIDATION STATES

Only a few compounds are known. The (-I) state occurs with  $[\text{M}(\text{CO})_6]^-$  for all three elements, and for the dipyrindyl complex  $\text{Li}[\text{V}(\text{dipyndyl})_3]$ .

ether. The zero-valent state occurs with  $[\text{V}(\text{CO})_6]$ . This is not very stable. Since V has an odd atomic number, it follows that in  $\text{V}(\text{CO})_6$  it has an unpaired electron and hence an incomplete shell of electrons. Other first row metal carbonyls with an unpaired electron dimerize and form a M—M bond, thus pairing the electrons.  $\text{V}(\text{CO})_6$  is unusual in that it remains monomeric.  $[\text{V}(\text{dipyridyl})_3]$  is another example of V(0). The (+I) state is found in  $[\text{V}(\text{dipyridyl})_3]^+$ .

## ORGANOMETALLIC COMPOUNDS

This group does not form many compounds with M—C  $\sigma$  bonds. The main examples are  $\text{V}(\text{CO})_6$ , which, though pyrophoric and not very stable, can be prepared in much larger quantities than  $\text{Ti}(\text{CO})_6$ . An unusual compound hexakis(dinitrogen)  $[\text{V}(\text{N}_2)_6]$  is also known, and is thought to be isoelectronic and isostructural with the carbonyl.

V forms bis(cyclopentadienyl) compounds such as  $[\text{V}(\eta^5 - \text{C}_5\text{H}_5)_2\text{Cl}_2]$ ,  $[\text{V}(\eta^5 - \text{C}_5\text{H}_5)_2\text{Cl}]$  and  $[\text{V}(\eta^5 - \text{C}_5\text{H}_5)_2]$ . The last is a simple sandwich compound and is called vanadocene. This is like ferrocene in the next chapter, and unlike the titanium compounds. The hapticity  $\eta^5$  indicates that in each ring five carbon atoms are 'bonded' to V. Vanadocene is extremely air sensitive, and is a dark violet paramagnetic solid. Nb and Ta also form cyclopentadienyl compounds such as  $[\text{Nb}(\eta^5 - \text{C}_5\text{H}_5)_2(\eta^1 - \text{C}_5\text{H}_5)_2]$ , in which two rings are  $\eta^5$ , and two rings are  $\eta^1$  bonded. Other complexes are  $[\text{Nb}(\eta^5 - \text{C}_5\text{H}_5)_2\text{Cl}_2]$  and  $[\text{Nb}(\eta^5 - \text{C}_5\text{H}_5)_2\text{Cl}_3]$ .

## FURTHER READING

- Brown, D. (1973) *Comprehensive Inorganic Chemistry*, Vol. 3 (Chapter 35: Niobium and tantalum), Pergamon Press, Oxford.
- Clark, R.J.H. (1973) *Comprehensive Inorganic Chemistry*, Vol. 3 (Chapter 34: Vanadium), Pergamon Press, Oxford.
- Canterford, J.H. and Cotton, R. (1968) *Halides of the Second and Third Row Transition Elements*, Wiley, London.
- Canterford, J.H. and Cotton, R. (1969) *Halides of the First Row Transition Elements*, Wiley, London.
- Corbett, J.D. (1981) Extended metal-metal bonding in halides of the early transition metals, *Acc. Chem. Res.*, **14**, 239.
- Cotton, F.A. (1975) Compounds with multiple metal to metal bonds, *Chem. Soc. Rev.*, **27**, 27–53.
- Diatom metals and metallic clusters* (1980) (Conference papers of the Faraday Symposia of the Royal Society of Chemistry, No. 14), Royal Society of Chemistry, London.
- Emeléus, H.J. and Sharpe, A.G. (1973) *Modern Aspects of Inorganic Chemistry*, 4th ed. (Chapters 14 and 15: Complexes of Transition Metals: Chapter 20: Carbonyls) Routledge and Kegan Paul, London.
- Fairbrother, F. (1967) *The Chemistry of Niobium and Tantalum*, Elsevier, Amsterdam.
- Hagenmuller, P. (1973) *Comprehensive Inorganic Chemistry*, Vol. 4 (Chapter 50: Tungsten bronzes, vanadium bronzes), Pergamon Press, Oxford.
- Hunt, C.B. (1977) Metallocenes – the first 25 years, *Education in Chemistry*, **14**, 110–113.
- Johnson, B.F.G. (ed.) (1980) *Transition Metal Clusters*, John Wiley, Chichester.



- Kepert, D L (1972) *The Early Transition Metals* (Chapter 3 V, Nb, Ta), Academic Press, London
- Kepert, D L (1973) *Comprehensive Inorganic Chemistry*, Vol 4 (Chapter 51 Isopolyanions and heteropolyanions), Pergamon Press, Oxford
- Lewis, J and Green, M L (eds) (1983) *Metal Clusters in Chemistry* (Proceedings of the Royal Society Discussion Meeting May 1982), The Society, London
- Muetterties, E L (1971) *Transition Metal Hydrides*, Marcel Dekker, New York
- Ophard, C E and Stuppia, S (1984) Synthesis and spectra of vanadium complexes, *J Chem Ed*, 61, 1102-1103
- Pope, M T (1983) *Heteropoly and Isopoly Oxo Metalates*, Springer-Verlag (A good account of polyacids)
- Shriver, D H, Kaesz, H D and Adams, R D (eds) (1990) *Chemistry of Metal Cluster Complexes*, VCH, New York, 1990

# Group 6 – the chromium group

22

Table 22.1 Electronic structures and oxidation states

Element		Electronic structure	Oxidation states*
Chromium	Cr	[Ar] 3d <sup>5</sup> 4s <sup>1</sup>	(-II) (-I) 0 (I) <b>II</b> <b>III</b> (IV) (V) <b>VI</b>
Molybdenum	Mo	[Kr] 4d <sup>5</sup> 5s <sup>1</sup>	(-II) (-I) 0 <b>I</b> (II) <b>III</b> <b>IV</b> <b>V</b> <b>VI</b>
Tungsten	W	[Xe] 4f <sup>14</sup> 5d <sup>4</sup> 6s <sup>2</sup>	(-II) (-I) 0 <b>I</b> (II) (III) <b>IV</b> <b>V</b> <b>VI</b>

\* The most important oxidation states (generally the most abundant and stable) are shown in bold. Other well-characterized but less important states are shown in normal type. Oxidation states that are unstable, or in doubt, are given in parentheses.

## INTRODUCTION

Chromium metal is produced on a large scale, and is used extensively in ferrous and non-ferrous alloys, and for electroplating. The metals molybdenum and tungsten are produced in appreciable amounts. Sodium dichromate is also used in large amounts. CrO<sub>3</sub> and Cr<sub>2</sub>O<sub>3</sub> are both used commercially.

Tungstate and molybdate ions both form extensive series of iso- and heteropolyacids. Chromium(II) acetate has an unusual structure with a quadruple bond. The lower halides MoX<sub>2</sub> and WX<sub>2</sub> form interesting cluster compounds based on the octahedral [M<sub>6</sub>X<sub>8</sub>]<sup>4+</sup> metal cluster. Mo is important in the fixation of dinitrogen.

## ABUNDANCE, EXTRACTION AND USES


Chromium is the twenty-first most abundant element by weight in the earth's crust. This is about as common as chlorine. Molybdenum and tungsten are quite rare (Table 22.2).

The only commercially important ore of Cr is chromite FeCr<sub>2</sub>O<sub>4</sub>. This is the chromium analogue of magnetite Fe<sub>3</sub>O<sub>4</sub>, which is better written as Fe<sup>II</sup>Fe<sup>III</sup><sub>2</sub>O<sub>4</sub>. Chromite has a spinel structure. In this structure the O atoms are arranged in a cubic close-packed lattice with Fe<sup>II</sup> in one eighth of the available tetrahedral holes and Cr<sup>III</sup> in one quarter of the octahedral holes.


*continued overleaf*

Chromite has a slight lustre and looks like pitch, with a brownish cast to the colour. It may be slightly magnetic. World production of chromite was 11.4 million tonnes in 1992, with a Cr content of 3.3 million tonnes. The largest sources of chromite ore are the Soviet Union 32%, South Africa 30%, Turkey and India 9% each, and Albania and Zimbabwe 5% each. Small amounts of crocoite  $\text{PbCrO}_4$  and chrome ochre  $\text{Cr}_2\text{O}_3$  are also mined.


Chromium is produced in two forms: ferrochrome and pure Cr metal, depending on what it is to be used for. Ferrochrome is an alloy containing Fe, Cr and C. It is produced by reducing chromite with C. In 1991, 3.1 million tonnes of ferrochrome were produced. It is used to make many ferrous alloys, including stainless steel and hard chromium steel.



Several steps are required to obtain pure chromium. First chromite is fused with NaOH in air, when the Cr is oxidized to sodium chromate.



$\text{Fe}_2\text{O}_3$  is insoluble but sodium chromate is soluble. Thus the  $\text{Na}_2[\text{CrO}_4]$  is removed by dissolving it in water, and is then acidified to give sodium dichromate. This is less soluble, and can be precipitated. The sodium dichromate is reduced to  $\text{Cr}_2\text{O}_3$  by heating with C.



Finally  $\text{Cr}_2\text{O}_3$  is reduced to the metal by Al or Si.



Since the metal is brittle, it is seldom used on its own. It is used to make non ferrous alloys. Alternatively  $\text{Cr}_2\text{O}_3$  is dissolved in  $\text{H}_2\text{SO}_4$ , and deposited electrolytically on the surface of a metal. This both protects the metal from corrosion and gives it a shiny appearance.

Molybdenum occurs as the mineral molybdenite  $\text{MoS}_2$ . World production of ores in 1992 had a molybdenum content of 129 000 tonnes. The largest sources are the USA 38% and China 29%. Some  $\text{MoS}_2$  is also

Table 22.2 Abundance of the elements in the earth's crust by weight

	ppm	Relative abundance
Cr	122	21
Mo	1.2	56 =
W	1.2	56 =

obtained as a by-product from CuS ores.  $\text{MoS}_2$  is roasted in air, converting it to  $\text{MoO}_3$ . This may be added to steel directly, or  $\text{MoO}_3$  may be heated with Fe and Al to give ferromolybdenum, which is then added to steel. Almost 90% of Mo is used to make cutting steel or stainless steel. Pure Mo is obtained by dissolving  $\text{MoO}_3$  in dilute  $\text{NH}_4\text{OH}$  and precipitating ammonium molybdate, dimolybdate or paramolybdate. This is reduced with hydrogen to give the metal. Mo metal is used as a catalyst in the petrochemical industry.

Tungsten occurs as tungstates, the most common being wolframite  $\text{FeWO}_4 \cdot \text{MnWO}_4$  and scheelite  $\text{CaWO}_4$ . World production in 1992 had 39 000 tonnes metal content. The largest sources are China 65% and the Soviet Union 17%. Different processes are used to extract W from wolframite and scheelite. Wolframite is fused with  $\text{Na}_2\text{CO}_3$ , forming sodium tungstate, which is leached out and acidified to give 'tungstic acid' (the hydrated oxide). Scheelite is acidified with HCl when 'tungstic acid' is precipitated and other materials dissolve. 'Tungstic acid' is then heated to give the anhydrous oxide, which is reduced to give the metal by heating with hydrogen at  $850^\circ\text{C}$ .

Mo and W are obtained by this method in the form of powders. Their melting points are high, so melting to give the massive metal would be expensive. Instead metal objects are obtained by fabricating the powder into the required shape and sintering (heating but not melting) under an atmosphere of  $\text{H}_2$ . Both Mo and W are alloyed with steel, giving very hard alloys, which are used to make 'cutting steel'. This is used to make machine tools. Cutting steel retains its cutting edge even when the metal becomes red hot. About half the W produced is used to make tungsten carbide WC, which is extremely hard (10 on Moh's scale) and will cut glass. WC is used to make the tips for drills. W metal is used to make the filaments in electric light bulbs. Molybdenum disulphide  $\text{MoS}_2$  has a layer lattice and is an excellent lubricant, either on its own or when added to hydrocarbon oil.

## OXIDATION STATES

The ground state electronic configuration of Cr and Mo is  $d^5s^1$ , with a stable half-filled  $d^5$  configuration, whilst W has a  $d^4s^2$  arrangement.

From the electronic structures, Cr and Mo might be expected to form compounds with oxidation states from (+I) to (+VI), and W from (+II) to (+VI) inclusive. They form these states, and in addition some lower states occur as dipyridyl complexes, carbonyl complexes and carbonyl ions.

For Cr the (+II), (+III) and (+VI) states are well known. Cr(+II) is reducing, Cr(+III) is the most stable and important and Cr(+VI) is strongly oxidizing. The most stable states for Mo and W are (+VI), though Mo(+V) and W(+V) are well represented and are stable in water. Whilst Cr(+VI) is strongly oxidizing, Mo(+VI) and W(+VI) are stable. Similarly Cr(+III) is stable but Mo(+III) and W(+III) are strongly reducing. This fits the usual trend that on descending a group the higher

Table 22 3 Oxides and halides

Oxidation states				
(+II)	(+III)	(+IV)	(+V)	(+VI)
-	<b>Cr<sub>2</sub>O<sub>3</sub></b>	<b>CrO<sub>2</sub></b>	-	<b>CrO<sub>3</sub></b>
-	-	<b>MoO<sub>2</sub></b>	<b>Mo<sub>2</sub>O<sub>5</sub></b>	<b>MoO<sub>3</sub></b>
-	-	<b>WO<sub>3</sub></b>	(W <sub>2</sub> O <sub>5</sub> )	<b>WO<sub>3</sub></b>
<b>CrF<sub>2</sub></b>	<b>CrF<sub>3</sub></b>	<b>CrF<sub>4</sub></b>	<b>CrF<sub>5</sub></b>	( <b>CrF<sub>6</sub></b> )
<b>CrCl<sub>3</sub></b>	<b>CrCl<sub>3</sub></b>	<b>CrCl<sub>3</sub></b>	-	-
<b>CrBr<sub>2</sub></b>	<b>CrBr<sub>3</sub></b>	<b>CrBr<sub>3</sub></b>	-	-
<b>CrI<sub>3</sub></b>	<b>CrI<sub>3</sub></b>	<b>CrI<sub>4</sub></b>	-	-
-	<b>MoF<sub>3</sub></b>	<b>MoF<sub>4</sub></b>	<b>MoF<sub>5</sub></b>	<b>MoF<sub>6</sub></b>
<b>MoCl<sub>2</sub></b>	<b>MoCl<sub>3</sub></b>	<b>MoCl<sub>3</sub></b>	<b>MoCl<sub>5</sub></b>	( <b>MoCl<sub>6</sub></b> )
<b>MoBr<sub>2</sub></b>	<b>MoBr<sub>3</sub></b>	<b>MoBr<sub>4</sub></b>	-	-
<b>MoI<sub>2</sub></b>	<b>MoI<sub>3</sub></b>	<b>MoI<sub>4</sub>?</b>	-	-
-	-	<b>WF<sub>4</sub></b>	<b>WF<sub>5</sub></b>	<b>WF<sub>6</sub></b>
<b>WCl<sub>3</sub></b>	<b>WCl<sub>3</sub></b>	<b>WCl<sub>3</sub></b>	<b>WCl<sub>5</sub></b>	<b>WCl<sub>6</sub></b>
<b>WBr<sub>2</sub></b>	<b>WBr<sub>3</sub></b>	<b>WBr<sub>4</sub></b>	<b>WBr<sub>5</sub></b>	<b>WBr<sub>6</sub></b>
<b>WI<sub>2</sub></b>	<b>WI<sub>3</sub></b>	<b>WI<sub>4</sub>?</b>	-	-

The most stable oxidation states are bold unstable are bracketed

oxidation states become more stable and the lower states become less stable. A list of known oxides and halides is given in Table 22 3

### GENERAL PROPERTIES

The metals are hard and have very high melting points and low volatility (Table 22 4). The melting point of W is the next highest to carbon.

Cr is unreactive or passive at low temperatures because it is protected by a surface coating of oxide, thus resembling Ti and V in previous groups. It is because of this passive behaviour that Cr is extensively used for electroplating onto iron and other metals to prevent corrosion. Cr dissolves





Table 22 4 Some physical properties

	Covalent radius (Å)	Ionic radius (Å)		Melting point (°C)	Boiling point (°C)	Density (g cm <sup>-3</sup> )	Pauling's electro negativity
		M <sup>3+</sup>	M <sup>4+</sup>				
Cr	1.17	0.80 <sup>b</sup> 0.73 <sup>l</sup>	0.615	1900	2690	7.14	1.6
Mo	1.29	-	0.69	2620	4650	10.28	1.8
W	1.30	-	-	3380	5500	19.3	1.7

b = high spin value l = low spin radius

in HCl and  $\text{H}_2\text{SO}_4$ , but is passivated by  $\text{HNO}_3$  or aqua regia. Mo and W are relatively inert, and are only slightly attacked by aqueous acids and alkalis. Mo reacts initially with  $\text{HNO}_3$ , but then becomes passive. Both Mo and W dissolve in  $\text{HNO}_3/\text{HF}$  mixtures, and also in fused  $\text{Na}_2\text{O}_2$  and fused  $\text{KNO}_3/\text{NaOH}$ . Cr reacts with HCl gas, forming anhydrous  $\text{CrCl}_2$  and  $\text{H}_2$ .

The metals do not react with  $\text{O}_2$  at normal temperatures (apart from the surface coating). However, on strong heating Cr forms  $\alpha\text{-Cr}_2\text{O}_3$ , which is green coloured and has a corundum structure. In contrast, Mo and W form  $\text{MO}_3$ . Similarly, on heating Cr with the halogens, trivalent halides  $\text{CrX}_3$  are formed. In contrast Mo and W form  $\text{MCl}_6$  on heating with  $\text{Cl}_2$ , and  $\text{MF}_6$  is formed at room temperature.



As a result of the lanthanide contraction, there is a close similarity in the size and the properties of Mo and W. The difference between these two elements is greater than in Group 4 between Zr and Hf and in Group 5 between Nb and Ta. Thus Mo and W can be easily separated in the conventional scheme for qualitative analysis of metals:  $\text{WO}_3(\text{H}_2\text{O})_n$  is precipitated with the insoluble chlorides in Group 1, and molybdates are reduced by  $\text{H}_2\text{S}$  in Group 2 and  $\text{MoS}_2$  and S are precipitated.

#### STANDARD REDUCTION POTENTIALS (VOLTS)

Acid solution						
Oxidation state						
+VI	+V	+VI	+III	+II	+I	0
$\text{Cr}_2\text{O}_7^{2-}$	+1.33	$\text{Cr}^{3+}$	-0.41	$\text{Cr}^{2+}$	-0.91	Cr
				-0.74		
			+0.295			
$\text{MoO}_4^{2-}$	+0.48	$\text{MoO}_2^+$	+0.31	$\text{Mo}^{3+}$	-0.20	Mo
			+0.08			
$\text{WO}_4^{2-}$	-0.03	$\text{W}_2\text{O}_5$	-0.04	$\text{WO}_2$	-0.15 *	$\text{W}^{3+}$
				-0.11		W
				-0.12		

Basic solution						
Oxidation state						
+VI	+V	+VI	+III	+II	+I	0
$\text{CrO}_4^{2-}$	$-0.13$		$\text{Cr(OH)}^3$	$-1.1$	$\text{Cr(OH)}^2$	$-1.4$
				$-1.3$		
$\text{MoO}_4^{2-}$	$-0.96$	$\text{MoO}_2^*$		$-0.91$		$\text{Mo}$
			$-0.927$			
$\text{WO}_4^{2-}$			$-1.007$			$\text{W}$
* = Disproportionates						


Many of these potentials have been calculated from thermodynamic data and the existence of species such as  $\text{Mo}^{3+}$ ,  $\text{W}^{3+}$  and  $\text{W}_2\text{O}_4$  is questionable

### (+VI) STATE

A limited number of Cr(+VI) compounds are known. These are very strong oxidizing agents and include chromates  $[\text{CrO}_4]^{2-}$ , dichromates  $[\text{Cr}_2\text{O}_7]^{2-}$ , chromium trioxide  $\text{CrO}_3$ , oxohalides  $\text{CrO}_3\text{X}^-$  and  $\text{CrO}_2\text{X}_2$  ( $\text{X} = \text{F}, \text{Cl}, \text{Br}$  or  $\text{I}$ ), and  $\text{CrOX}_4$  ( $\text{X} = \text{F}$  or  $\text{Cl}$ ) and  $\text{CrF}_6$ .

### Chromate and dichromate

Sodium chromate  $\text{Na}_2\text{CrO}_4$  is a yellow solid, and should strictly be called sodium chromate(VI). Its preparation from chromite by fusing with  $\text{NaOH}$  and oxidizing with air has already been described under 'Abundance, extraction and uses', and it can also be prepared by fusion with  $\text{Na}_2\text{CO}_3$ .




It is quite soluble in water and is a strong oxidizing agent. Sodium dichromate  $\text{Na}_2\text{Cr}_2\text{O}_7$  is an orange coloured solid, and is made by acidifying a chromate solution. The dichromate is less soluble in water, and is widely used as an oxidizing agent.  $\text{K}_2\text{Cr}_2\text{O}_7$  is preferred to  $\text{Na}_2\text{Cr}_2\text{O}_7$  for use in volumetric analysis (titrations) because the Na compound is hygroscopic whilst the K compound is not. Thus  $\text{K}_2\text{Cr}_2\text{O}_7$  can be used as a primary standard.



### Peroxo compounds

When hydrogen peroxide is added to an acidified solution of a dichromate (or any other Cr(+VI) species), a complicated reaction occurs. The products depend on the pH and the concentration of Cr.



A deep blue-violet coloured peroxo compound  $\text{CrO}(\text{O}_2)_2$  is formed. This decomposes rapidly in aqueous solution into  $\text{Cr}^{3+}$  and dioxygen. The peroxo compound can be extracted into ether, where it reacts with pyridine, forming the adduct  $\text{py} \cdot \text{CrO}(\text{O}_2)_2$  (Figure 22.1a). The structure of this is approximately a pentagonal pyramid. Cr is at the centre of a pentagon of four O atoms (from the two peroxo groups) and the N from pyridine, and one O above the pentagon in an apical position.

In less acidic solutions  $\text{K}_2\text{Cr}_2\text{O}_7$  and  $\text{H}_2\text{O}_2$  give salts which are violet coloured and diamagnetic. These are thought to contain  $[\text{CrO}(\text{O}_2)(\text{OH})]^-$ , but the structures are not known as the compounds are explosive. In alkaline solution with 30%  $\text{H}_2\text{O}_2$ , a red-brown compound  $\text{K}_3\text{CrO}_8$  is formed which is a tetraperoxo species  $[\text{Cr}(\text{O}_2)_4]^{3-}$ , and contains Cr(+V). In ammonia solution the dark red-brown compound  $(\text{NH}_3)_3\text{CrO}_4$  is formed which contains Cr(+IV) (Figure 22.1b).





Figure 22.1 Structures of (a)  $\text{py} \cdot \text{CrO}(\text{O}_2)_2$ , (b)  $(\text{NH}_3)_3\text{CrO}_4$  (pentagonal bipyramid).

### Chromium trioxide (chromic acid)


$\text{CrO}_3$  is a bright orange solid, and is commonly called 'chromic acid'. It is usually prepared by adding concentrated  $\text{H}_2\text{SO}_4$  to a saturated solution of sodium dichromate.






The colour arises from charge transfer (not  $d-d$  spectra as Cr(+VI) has a  $d^0$  configuration).  $\text{CrO}_3$  is toxic, and corrosive. The crystal structure



consists of chains of fused tetrahedra.  $\text{CrO}_3$  dissolves readily in water, and is both a very strong acid and an oxidizing agent. It is an acidic oxide, and dissolves in  $\text{NaOH}$  solutions, forming the chromate ion  $\text{CrO}_4^{2-}$ . On heating above  $250^\circ\text{C}$  it loses oxygen in stages, eventually forming green coloured  $\text{Cr}_2\text{O}_3$ .



$\text{CrO}_3$  reacts with  $\text{F}_2$  at normal pressures, forming the oxofluorides  $\text{CrO}_2\text{F}_2$  and  $\text{CrOF}_4$ , but at  $170^\circ\text{C}$  and 25 atmospheres  $\text{CrF}_6$  is formed



$\text{CrO}_3$  is widely used to make chromium plating solutions. It can be dissolved in acetic acid and used in this form as an oxidant in organic chemistry, though reactions may be explosive. Chromic acid solutions are used to clean laboratory glassware.

### $\text{MoO}_3$ and $\text{WO}_3$

$\text{MoO}_3$  and  $\text{WO}_3$  are formed by heating the metal in air. They are acidic. They are not attacked by acids except  $\text{HF}$ , but they dissolve in  $\text{NaOH}$  forming  $\text{MoO}_4^{2-}$  and  $\text{WO}_4^{2-}$  ions.  $\text{MoO}_3$  and  $\text{WO}_3$  differ from  $\text{CrO}_3$  in several ways



- 1 They have almost no oxidizing properties
- 2 They are insoluble in water
- 3 Their melting points are much higher ( $\text{CrO}_3$  m.p.  $197^\circ\text{C}$ ,  $\text{MoO}_3$  m.p.  $795^\circ\text{C}$  and  $\text{WO}_3$  m.p.  $1473^\circ\text{C}$ )
- 4 Their colour and structures are different.  $\text{MoO}_3$  is white as expected for  $d^0$  but on heating it turns yellow due to the formation of defects in the solid. The structure is a layer lattice.  $\text{WO}_3$  is lemon yellow in colour, and has a slightly distorted rhenium trioxide  $\text{ReO}_3$  structure of  $\text{WO}_6$  octahedra sharing corners in three dimensions (See Figure 23.4a)

### Mixed oxides

Several mixed oxides can be made by fusing  $\text{MoO}_3$  or  $\text{WO}_3$  with Group 1 or 2 oxides. These comprise chains or rings of  $\text{MoO}_6$  or  $\text{WO}_6$  octahedra. Moist  $\text{WO}_3$  turns slightly blue on exposure to UV light. Mild reduction of aqueous suspensions of  $\text{MoO}_3$  and  $\text{WO}_3$  or acidic solutions of molybdates or tungstates also gives a blue colour. The 'blue oxides' so produced are thought to have Mo or W in oxidation states of (+IV) and (+V) and contain some  $\text{OH}^-$  instead of  $\text{O}^{2-}$  to balance the charges.

### Oxohalides

Oxohalides of the type  $\text{MO}_2\text{Cl}_2$  may be formed by dissolving the trioxide in strong acid, or in some cases by the action of strong acids on salts such as dichromates, or by direct addition of the halogens to the dioxide.



Chromyl chloride  $\text{CrO}_2\text{Cl}_2$  is a deep red coloured liquid. It is formed in qualitative analysis to confirm the presence of chloride ions. The suspected chloride is mixed with solid  $\text{K}_2\text{Cr}_2\text{O}_7$  and gently warmed with concentrated  $\text{H}_2\text{SO}_4$ . Deep red vapours of  $\text{CrO}_2\text{Cl}_2$  are formed, and if these are passed into aqueous  $\text{NaOH}$  the solution turns yellow due to the formation of  $\text{Na}_2\text{CrO}_4$ .

Chromyl and molybdenyl chlorides are covalent acid chlorides and are readily decomposed by water. Tungstenyl chloride hydrolyses less readily.

### Halides

$\text{CrF}_6$  is a yellow solid made by heating the elements under pressure in a bomb, and cooling rapidly. The product is unstable and decomposes into  $\text{CrF}_5$  and  $\text{F}_2$ . In contrast  $\text{MoF}_6$  and  $\text{WF}_6$  are very stable. They are both low melting ( $\text{MoF}_6$   $17.4^\circ\text{C}$ ,  $\text{WF}_6$   $1.9^\circ\text{C}$ ), volatile, and easily hydrolysed. They are diamagnetic and colourless as expected for a  $d^0$  configuration. However,  $\text{MoCl}_6$  and  $\text{WCl}_6$  are black and  $\text{WBr}_6$  is dark blue.  $\text{WCl}_6$  is made by heating the metal in  $\text{Cl}_2$ . It reacts with water, forming tungstic acid.  $\text{WCl}_6$  is soluble in  $\text{EtOH}$ , ether and  $\text{CCl}_4$ , and is used as the starting point for making other compounds.

### (+V) STATE

There are few  $\text{Cr}(+V)$  compounds, and they are unstable and decompose to  $\text{Cr}(+III)$  and  $\text{Cr}(+VI)$ . One example is  $\text{K}_3\text{CrO}_8$ , a red-brown compound formed from  $\text{NaCrO}_4$  and  $\text{H}_2\text{O}_2$  in alkaline solution (see above).  $\text{K}_3\text{CrO}_8$  contains the tetraperoxo species  $[\text{Cr}(\text{O}_2)_4]^{3-}$ . Another example is  $\text{CrF}_5$  which is made by heating the elements at  $500^\circ\text{C}$  or heating  $\text{CrO}_3$  with  $\text{F}_2$ . It is a red solid, based on  $\text{CrF}_6$  octahedra linked to give a *cis*-bridged polymer.

$\text{MoF}_5$  has a tetrameric structure of four octahedra joined into a ring, like  $\text{NbF}_5$  and  $\text{TaF}_5$  (see Figure 21.1). Heating  $\text{Mo}$  and  $\text{Cl}_2$  gives  $\text{Mo}_2\text{Cl}_{10}$ . This is soluble in benzene and other organic solvents. It exists as monomeric  $\text{MoCl}_5$  in solution, but dimerizes to  $\text{Mo}_2\text{Cl}_{10}$  in the solid.  $\text{Mo}_2\text{Cl}_{10}$  is used as the starting point for making other  $\text{Mo}$  compounds. It is rapidly hydrolysed by water, and removes  $\text{O}$  from oxygenated solvents, forming oxochlorides.  $\text{Mo}_2\text{Cl}_{10}$  is paramagnetic ( $\mu = 1.6 \text{ BM}$ ), indicating that there is one unpaired electron and thus no metal-metal bonding.

## (+IV) STATE

Cr(+IV) compounds are also rare.  $\text{CrF}_4$  is formed by heating the elements at  $350^\circ\text{C}$ .  $\text{MoCl}_4$  exists in two polymeric forms, one like  $\text{NbCl}_4$  (see Figure 21.3) comprising chains of octahedra with the metal atoms displaced in pairs, forming metal-metal bonds, and the other form without metal-metal bonds.



$\text{CrO}_2$  is made from  $\text{CrO}_3$  by hydrothermal reduction, and has a rutile ( $\text{TiO}_2$ ) structure. The oxide is black in colour and has some metallic conductivity. It is also ferromagnetic, and is widely used to make high quality magnetic recording tapes.  $\text{MoO}_2$  and  $\text{WO}_2$  are both made by reducing the trioxide with hydrogen. They are brown-violet in colour and are insoluble in non oxidizing acids, but dissolve in concentrated  $\text{HNO}_3$ , forming  $\text{MoO}_3$  or  $\text{WO}_3$ . The dioxides have a copper-like lustre and have distorted rutile structures with strong metal-metal bonds. The oxohalide  $\text{CrOF}_2$  is also known.

## (+III) STATE


## Chromium

Cr(+III) compounds (often called chromic compounds) are ionic and contain  $\text{Cr}^{3+}$  are the most important and most stable compounds of chromium. Although this oxidation state is very stable in acidic solution it is easily oxidized to Cr(+VI) in alkaline solution.

$\text{Cr}_2\text{O}_3$  is a green solid which is used as a pigment. The most convenient preparation is by heating ammonium dichromate  $(\text{NH}_4)_2\text{Cr}_2\text{O}_7$  in the well known volcano experiment used in some fireworks. (Once the reaction is started, it produces enough heat to continue on its own. The green coloured  $\text{Cr}_2\text{O}_3$  powder is blown in the air by the large volume of  $\text{N}_2$  and water vapour produced, and settles like dust from a volcano.)  $\text{Cr}_2\text{O}_3$  is also formed by burning the metal in air or by heating  $\text{CrO}_3$ . It has a corundum  $\text{Al}_2\text{O}_3$  structure.




The addition of  $\text{NaOH}$  to  $\text{Cr}^{3+}$  solutions does *not* precipitate the hydroxide, but the hydrous (hydrated) oxide is precipitated instead.




The oxide becomes inert to acids and bases if heated strongly but otherwise it is amphoteric, giving  $[\text{Cr}(\text{H}_2\text{O})_6]^{3+}$  with acids, and 'chromites' with concentrated alkali. The species present in 'chromite' solutions is probably  $[\text{Cr}^{\text{III}}(\text{OH})_6]^{1-}$  or  $[\text{Cr}^{\text{III}}(\text{OH})_4\text{H}_2\text{O}]^{2-}$ .  $\text{Cr}_2\text{O}_3$  is commercially important. It is formed as one step in the extraction of chromium. It is used as a pigment in paint, rubber and cement and as a catalyst for a wide variety of reactions including the manufacture of polythene and butadiene.

All the anhydrous  $\text{CrX}_3$  halides are known.  $\text{CrCl}_3$  is a solid which forms red-violet flakes. The flakiness is related to the layer lattice structure of the solid. The chloride ions are cubic close-packed, and to maintain stoichiometry one third of the octahedral holes must be occupied by  $\text{Cr}^{3+}$  ions. Two thirds of the holes are occupied in one layer, and none in the next layer, and consequently only weak van der Waals forces hold some chloride layers together. In aqueous solution the halides form the violet coloured hexaaqua ion  $[\text{Cr}(\text{H}_2\text{O})_6]^{3+}$ , and halogen complexes such as  $[\text{Cr}(\text{H}_2\text{O})_5\text{Cl}]^{2+}$ ,  $[\text{Cr}(\text{H}_2\text{O})_4\text{Cl}_2]^+$  and  $[\text{Cr}(\text{H}_2\text{O})_3\text{Cl}_3]$ . The hexaaqua ion also occurs in many crystalline compounds such as  $[\text{Cr}(\text{H}_2\text{O})_6]\text{Cl}_3$  and the alums. The alums are double salts, for example chrome alum  $\text{K}_2\text{SO}_4 \cdot \text{Cr}_2(\text{SO}_4)_3 \cdot 24\text{H}_2\text{O}$ , which crystallizes from mixed solutions of  $\text{Cr}_2(\text{SO}_4)_3$  and  $\text{K}_2\text{SO}_4$ . The structure is better shown if the formula is written  $[\text{K}(\text{H}_2\text{O})_6][\text{Cr}^{III}(\text{H}_2\text{O})_6][\text{SO}_4]_2$ . In solution the alums dissociate completely into simple ions.


The hexaaqua ion is acidic, and it may form a dimer by means of two hydroxo bridges.



$\text{Cr}^{3+}$  ions form an enormous number and variety of complexes. These are typically six-coordinate with octahedral structures, and are very stable both as solids and in aqueous solution. The stability is related to the high crystal field stabilization energy from its  $d^3$  electronic configuration. The magnetic moments of these complexes are close to the spin only value of 3.87 BM expected for three unpaired electrons. Complexes include the hexaaqua  $[\text{Cr}(\text{H}_2\text{O})_6]^{3+}$  and halogen complexes  $[\text{Cr}(\text{H}_2\text{O})_5\text{Cl}]^{2+}$ , mentioned above. The ammine and oxalate complexes show many different forms of isomerism, for example the ammine complexes:



and in the oxalate complexes:



Isomerism is discussed more fully in Chapter 7 (see Figure 7.3). There are also many cyanide and thiocyanate complexes. Reinecke's salt  $\text{NH}_4[\text{Cr}(\text{NH}_3)_2(\text{NCS})_4] \cdot \text{H}_2\text{O}$  is often used to precipitate large positive ions. This is because when the anion and cation are similar in size, the




Figure 22.2 Structure of  $[\text{Cr}_3\text{O}(\text{CH}_3\text{COO})_6(\text{H}_2\text{O})_3]^+$

crystal has a high coordination number and thus a higher lattice energy


$\text{Cr}(\text{+III})$  forms an unusual basic acetate  $[\text{Cr}_3\text{O}(\text{CH}_3\text{COO})_6\text{L}_3]^+$  (where L is water or some other ligand). The structure consists of a triangle of three Cr atoms with an O atom at the centre. The six acetate groups act as bridges between the Cr atoms – two acetate groups across each edge of the triangle. Each Cr atom is octahedrally surrounded by six atoms: O atoms from four acetate groups, the central O, and L in the sixth position. L may be water or another ligand.  $\text{Cr}^{3+}$  has a  $d^3$  arrangement and should have a magnetic moment of 3.87 BM. The magnetic moment of the complex at room temperature is only 2 BM. It is thought that the smaller value is due to partial pairing of  $d$  electrons on the three metal atoms by means of  $d\pi-p\pi$  bonding through O. This type of carboxylate complex is formed by the trivalent ions of Cr, Mn, Fe, Ru, Rh and Ir. (Partial spin pairing and a reduced magnetic moment are also found in other complexes such as  $[(\text{NH}_3)_5\text{Cr}-\text{OH}-\text{Cr}(\text{NH}_3)_5]^{4+}$  and  $[(\text{NH}_3)_5\text{Cr}-\text{O}-\text{Cr}(\text{NH}_3)_5]^{4+}$  where the magnetic moment is temperature dependent, and is about 1.3 BM at room temperature but almost zero at  $-200^\circ\text{C}$ .)

### Spectra

$\text{Cr}(\text{+III})$  has a  $d^3$  electronic configuration. In the ground state these electrons occupy the  $t_{2g}$  orbitals, i.e.  $(t_{2g})^3$ . The two  $e_g$  orbitals are empty, providing two 'holes' into which electrons can be promoted. The situation is analogous to that for  $d^2$  described for  $\text{V}^{3+}$  in Chapter 21. The electronic spectra of  $\text{Cr}(\text{+III})$  complexes exhibit three absorption bands. In the ground state, the  $d_{xy}$ ,  $d_{xz}$ , and  $d_{yz}$  orbitals each contain one electron, giving the singly degenerate state  ${}^4A_{2g}(F)$ . The first excited state corresponds to promoting one electron, i.e.  $(t_{2g})^2(e_g)^1$ , and gives two terms  ${}^4T_{2g}(F)$  and  ${}^4T_{1g}(F)$ . The second excited state corresponds to promoting two electrons, i.e.  $(t_{2g})^1(e_g)^2$ . This gives only one quartet that is triply degenerate, so the term symbol is  ${}^4T_{1g}(P)$ . The transitions are  ${}^4T_{2g}(F) \rightarrow {}^4T_{2g}(F)$ ,  ${}^4T_{2g}(F) \rightarrow {}^4T_{1g}(F)$  and  ${}^4A_{2g}(F) \rightarrow {}^4T_{1g}(P)$ . In the hexaaqua ion  $[\text{Cr}(\text{H}_2\text{O})_6]^{3+}$  bands are found at  $17400\text{ cm}^{-1}$  and  $24700\text{ cm}^{-1}$ , and there is a shoulder on the charge transfer band at  $37800\text{ cm}^{-1}$ . (See also Chapter 32.)

### Molybdenum and tungsten

$\text{Mo}(\text{+III})$  and  $\text{W}(\text{+III})$  do not exist as oxides, but all the halides are known except  $\text{WF}_3$  (Table 22.3). These compounds do not contain simple ions.  $\text{Mo}(\text{+III})$  compounds are fairly stable, but slowly oxidize in air and slowly hydrolyse in water. They form octahedral complexes with halide ions in solution.




Two solid forms of  $\text{MoCl}_3$  are known, one with cubic close packing of chlorine atoms, the other based on hexagonal close packing. In both forms the Mo atoms are displaced from the centres of adjacent octahedra, and


form metal-metal bonds of length 2.76 Å. In contrast W(+III) compounds are unstable.  $\text{WCl}_3$  is really  $\text{W}_6\text{Cl}_{18}$  and forms a cluster compound  $[\text{W}_6\text{Cl}_{12}]^{6+}$  structurally like  $[\text{Nb}_6\text{Cl}_{12}]^{2+}$  (Figure 22.3).  $\text{W}_6\text{Br}_{18}$  also forms a cluster compound, but its structure contains  $[\text{W}_6\text{Br}_8]^{6+}$  and has the same structure as  $[\text{Mo}_6\text{Br}_8]^{4+}$  (Figure 22.4).

### (+II) STATE

Cr(+II) compounds (often called chromous compounds) are well known, are ionic and contain  $\text{Cr}^{2+}$ . Solutions containing  $[\text{Cr}(\text{H}_2\text{O})_6]^{2+}$  can be produced either by electrolytically reducing solutions containing  $\text{Cr}^{3+}$ , or by reducing them with zinc amalgam. They can also be produced from Cr metal and acids. The  $[\text{Cr}(\text{H}_2\text{O})_6]^{2+}$  ion is sky blue coloured. It is one of the strongest reducing agents known in aqueous solution.



If the solution is acidic  $\text{Cr}^{2+}$  slowly reduces water to  $\text{H}_2$ . Cr(+II) compounds are oxidized by air to  $\text{Cr}^{3+}$ .  $\text{Cr}^{2+}$  is used to remove the last trace of dioxygen from dinitrogen, and has other uses as a reducing agent. Cr(+II) may be stabilized by forming coordination compounds, such as  $[\text{Cr}(\text{NH}_3)_6]^{2+}$  or  $[\text{Cr}(\text{dipyridyl})_3]^{2+}$ . Though  $\text{Cr}^{2+}$  is stable to disproportionation, the dipyridyl complex disproportionates.



Hydrated salts such as  $\text{CrSO}_4 \cdot 7\text{H}_2\text{O}$ ,  $\text{Cr}(\text{ClO}_4)_2 \cdot 6\text{H}_2\text{O}$  and  $\text{CrCl}_2 \cdot 4\text{H}_2\text{O}$  can be isolated, but they cannot be dehydrated as they decompose on heating.

Anhydrous Cr(+II) halides can be made either by reducing the trihalides with hydrogen at 500°C, or from the metal and HF, HCl, HBr or  $\text{I}_2$  at 600°C. The dihalides are all readily oxidized in air to the (+III) state unless protected by an inert atmosphere such as  $\text{N}_2$ .  $\text{CrCl}_2$  is the most important, and it dissolves in water, giving the sky blue coloured  $[\text{Cr}(\text{H}_2\text{O})_6]^{2+}$  ion.

Chromium forms many complexes, especially with N ligands and chelating groups. These are easily oxidized, particularly if moist. Almost all the complexes are octahedral, and both high-spin and low-spin complexes are known. The high-spin complexes have the electronic configuration  $(t_{2g})^3 (e_g)^1$ . The asymmetrical filling of the  $e_g$  orbitals causes Jahn-Teller distortion similar to that found in complexes of  $\text{Cu}^{2+}$ .

Chromium(II) acetate dihydrate  $\text{Cr}_2(\text{CH}_3\text{COO})_4 \cdot 2\text{H}_2\text{O}$  is one of the most stable chromous compounds. It is easily prepared by adding sodium acetate to a solution containing  $\text{Cr}^{2+}$  under an atmosphere of  $\text{N}_2$ . Hydrated chromium(II) acetate is precipitated as a red solid. It is a good starting material for the preparation of other Cr(+II) salts. It has an unusual dimeric bridge structure (Figure 22.5). Each  $\text{Cr}^{2+}$  is surrounded by a distorted octahedron made up of four O atoms from four bidentate acetate groups, one O from a  $\text{H}_2\text{O}$  molecule, and the other  $\text{Cr}^{2+}$  ion. The four




Figure 22.3  $[\text{W}_6\text{Cl}_{12}]^{6+}$  cluster.






Figure 22.4  $[\text{W}_6\text{Br}_8]^{6+}$  cluster.

Figure 22.5 Structure of  $\text{Cr}_2(\text{CH}_3\text{COO})_4 \cdot 2\text{H}_2\text{O}$ 

acetate groups bridge between the two Cr atoms. The very short distance of 2.36 Å between the two Cr atoms is evidence of a strong metal-metal bond.  $\text{Cr}^{2+}$  has a  $d^4$  configuration and has four unpaired electrons, but chromium(II) acetate is diamagnetic. This suggests that all four unpaired electrons take part in M-M bonding. Assuming that the ligands are bonded using one  $s$ , three  $p$  and the  $d_{x^2-y^2}$  orbitals, the  $d_{z^2}$  orbital can form a  $\sigma$  bond to the other  $\text{Cr}^{2+}$ . In addition the  $d_{xz}$  and  $d_{yz}$  orbitals can form  $\pi$  bonds between the Cr atoms, and the  $d_{xy}$  orbital forms a  $\delta$  bond. Quadruple bonds of this type are found with other heavy transition metals Mo, W, Ta and Re, e.g.  $[\text{Mo}_2(\text{CH}_3\text{COO})_4]$  (note there are no axial  $\text{H}_2\text{O}$  ligands),  $[\text{Mo}_2\text{Cl}_8]^{4-}$ ,  $[\text{W}_2\text{Cl}_4(\text{PR}_3)_4]$ ,  $[\text{W}_2(\text{CH}_3)_8]^{4-}$ ,  $[\text{W}_2(\text{C}_8\text{H}_8)_3]$ ,  $[\text{Re}_2\text{Cl}_8]^{2-}$  and  $[\text{Re}_2\text{Br}_8]^{2-}$ . At one time quadruple bonds were regarded as anomalies, but they may be more common than originally thought. It is suggested that once a M-M multiple bond has been formed, the metal can easily be reduced to give a bond of higher order.

Figure 22.6 Structure of  $[\text{Mo}_2\text{Cl}_8]^{4-}$  and  $[\text{Re}_2\text{Cl}_8]^{2-}$ 

Mo and W do not form difluorides, but the other six (+II) halides are known. They are usually made by reduction or thermal decomposition of higher halides. They do not exist as simple ions, but form 'cluster compounds' instead.  $\text{MoBr}_2$  is really  $[\text{Mo}_6\text{Br}_8]\text{Br}_4 \cdot 2\text{H}_2\text{O}$ , and all six of these so called 'dihalides' have the same structure based on a cluster  $[\text{M}_6\text{X}_8]^{4+}$  with four halide ions and two  $\text{H}_2\text{O}$  acting as electron donors. The structure of the  $[\text{M}_6\text{X}_8]^{4+}$  unit is an octahedral cluster of six metal atoms. There is extensive M-M bonding, and eight face bridging halogen atoms occupy the eight triangular faces of the octahedron (Figure 22.7). Thus each halogen is bonded to three metal atoms. Each metal atom has an unoccupied coordination position. The  $\text{M}_6\text{X}_8^{4+}$  units can thus accept six coordinate bonds to the metal atoms at the corners of the octahedron from the remaining four  $\text{X}^-$  ions and two  $\text{H}_2\text{O}$  molecules, or from any other suitable electron pair donor. Addition of six  $\text{Cl}^-$  gives the  $[\text{Mo}_6\text{Cl}_{14}]^{2-}$  cluster. The six ligands on the corners are labile, and undergo replacement reactions quite readily. In contrast the bridging halogens in the cluster




Figure 22.7 Structure of  $[\text{Mo}_6\text{Br}_8]^{4+}$  ion showing the octahedral  $\text{M}_6$  cluster.

undergo replacement very slowly. The low oxidation state suggests that these clusters should oxidize fairly readily.  $[\text{Mo}_6\text{Cl}_8]^{4+}$  is only oxidized to  $[\text{Mo}_6\text{Cl}_{12}]^{3+}$  (a formal oxidation state of  $2\frac{1}{2}$ ), though  $[\text{W}_6\text{Cl}_8]^{4+}$  is oxidized to the  $[\text{W}_6\text{Cl}_{12}]^{6+}$  cluster (Figure 21.4).

The bonding in these compounds is not settled. The compounds are diamagnetic; therefore Mo must use all six outer electrons  $d^5s^1$  or W  $d^4s^2$  for bonding. Since there are six M atoms there are 36 valence electrons. It seems probable that eight electrons are used to bond the eight Cl atoms on the faces, and four electrons are transferred to form four  $\text{X}^-$  ions. This leaves 24 electrons to form M–M bonds along the 12 edges of the  $\text{M}_6$  octahedron.

### (+I) STATE


The oxidation state (+I) expected for the atoms with a  $d^5s^1$  configuration is very uncommon. It is doubtful if  $\text{Cr}^+$  exists except when stabilized in a complex. Trisdipyridyl chromium(I) perchlorate  $[\text{Cr}(\text{dipyridyl})_3]^+ \text{ClO}_4^-$  is known. Mo and W form sandwich-type structures such as  $(\text{C}_6\text{H}_6)_2\text{Mo}^+$  and  $\text{C}_5\text{H}_5\text{MoC}_6\text{H}_6$  where the metal is in the (+I) state.

### ZERO STATE, (-I) AND (-II)


The zero oxidation state arises in metal carbonyls such as  $\text{M}(\text{CO})_6$ , where the  $\sigma$  bonding electrons are donated by the CO group to the metal, and strong  $d\pi-p\pi$  back bonding occurs from the filled metal orbitals. All three metals form octahedral carbonyl compounds of this type. They are stable and may be sublimed under reduced pressure. They are soluble in organic solvents. The bipyridyl complex  $[\text{Cr}(\text{bipyridyl})_3]$  is also octahedral.

An unusual complex dibenzene chromium  $[\text{Cr}(\eta^6\text{-C}_6\text{H}_6)_2]$  was made by E.O. Fischer in 1955. It forms dark brown crystals and has a sandwich structure similar to ferrocene, though it is much more air sensitive than ferrocene. Cr has a coordination number of 12. It was made as follows:





It may also be made by a Grignard reaction




For work on this and similar organometallic compounds, Fischer was awarded the Nobel Prize for Chemistry in 1973, jointly with G. Wilkinson who did parallel work on cyclopentadienyl compounds.

The  $\eta^5\text{-C}_5\text{H}_5$  compounds include complexes containing only one cyclopentadienyl ring, and in a similar way complexes are formed with one benzene ring. For example, benzene tricarbonyl complexes for Cr, Mo and W, e.g.  $[\text{Cr}(\eta^6\text{-C}_6\text{H}_6)(\text{CO})_3]$ , are yellow solids, the metal has a coordination number of 9. The benzene complexes are more reactive and less thermally stable than their  $\eta^5\text{-C}_5\text{H}_5$  counterparts.

The lower oxidation states occur in carbonyl ions ( $-I$ ) in  $[\text{M}_2(\text{CO})_{10}]^{2-}$ , and ( $-II$ ) in  $[\text{M}(\text{CO})_5]^{2-}$ .

### CHROMATES, MOLYBDATES AND TUNGSTATES


The oxides  $\text{CrO}_3$ ,  $\text{MoO}_3$  and  $\text{WO}_3$  are strongly acidic, and dissolve in aqueous  $\text{NaOH}$  forming discrete tetrahedral chromate  $\text{CrO}_4^{2-}$ , molybdate  $\text{MoO}_4^{2-}$  and tungstate  $\text{WO}_4^{2-}$  ions.



Chromates, molybdates and tungstates exist both in solution and as solids. Chromates are strong oxidizing agents, but molybdates and tungstates have only weak oxidizing powers. Molybdates and tungstates can be reduced to form the blue oxides.

On acidifying, chromates  $\text{CrO}_4^{2-}$  form  $\text{HCrO}_4^-$  and orange-red dichromates  $\text{Cr}_2\text{O}_7^{2-}$ , in which two tetrahedral units join together by sharing the oxygen atom at one corner (Figure 22.8).  $\text{HCrO}_4^-$  and  $\text{Cr}_2\text{O}_7^{2-}$  exist in equilibrium over a wide range of pH from 2–6.

$\text{CrO}_3$  is precipitated from very concentrated acid (below pH 1)



$\text{Na}_2\text{Cr}_2\text{O}_7$  is the most important chromium compound, and is produced as one step in the extraction of chromium. Apart from that used in the extraction of the metal, 369 300 tonnes were used in 1991 for chrome tanning of leather, making various lead chromes, for 'anodizing' aluminium, and as an oxidizing agent. There is some evidence for further polymerization giving a limited polychromate series. Trichromates  $\text{Cr}_3\text{O}_{10}^{2-}$  and tetrachromates  $\text{Cr}_4\text{O}_{13}^{2-}$  have been found.

When molybdate and tungstate solutions are acidified they condense and give an extensive range of polymolybdates and polytungstates. Below a pH of 1 the hydrated oxides are precipitated.  $\text{MoO}_3 \cdot 2\text{H}_2\text{O}$  is yellow and  $\text{WO}_3 \cdot 2\text{H}_2\text{O}$  is white. The formation of polyacids is a prominent feature of the chemistry of Mo and W. Other transition elements V, Nb, Ta and U





Figure 22.8 Chromate and dichromate ions.

also form polyacids, but to a lesser extent. The polyanions contain  $\text{MoO}_6$  or  $\text{WO}_6$  octahedra, which are joined together in a variety of ways by sharing corners or edges, but not faces. The polyacids of Mo and W are divided into two main types:

1. Isopolyacids, where the anions which condense together are all of the same type – for example all  $\text{MoO}_6$  groups or all  $\text{WO}_6$  groups.
2. Heteropolyacids, where two or more different types of anion condense together – for example molybdate or tungstate groups with phosphate, silicate or borate groups.

The isopolyacids of Mo and W are not completely understood. They are very difficult to study because the extent of hydration and protonation of the various species in solution is not known. The fact that a solid can be crystallized from solution does not prove that the ion has that structure or even exists in solution. The first step in polyacid formation as the pH is lowered must be to increase the coordination number of Mo or W from 4 to 6 by adding water molecules. The relationship between the stable species so far known is:



The structures of the paramolybdate and octamolybdate ions have been confirmed by X-ray crystallographic studies of their crystalline salts (Figure 22.9).




Figure 22.9 Some molybdate ions. (From H.J. Eméleus and A.G. Sharpe, *Modern Aspects of Inorganic Chemistry*, 4th ed., Routledge and Kegan Paul, 1973.)



The 6-heteropolyacids accommodate larger central atoms, which have a coordination number of 6. The arrangement of six  $\text{MoO}_6$  octahedra as shown in Figure 22.11 leaves a central cavity large enough to accept the octahedron from the hetero atom, and has been found in  $\text{K}_6[\text{TeMo}_6\text{O}_{24}]$ .




Figure 22.11 6-polyacid, e.g.  $\text{K}_6[\text{TeMo}_6\text{O}_{24}]$ . (From H.J. Emeléus and A.G. Sharpe, *Modern Aspects of Inorganic Chemistry*, 4th ed., RKP, 1973.)

## TUNGSTEN BRONZES

Tungsten bronzes were originally made by strongly heating sodium tungstate  $\text{Na}_2\text{WO}_4$  with  $\text{WO}_3$  and  $\text{H}_2$ . They are now made by heating  $\text{Na}_2\text{WO}_4$  with W metal, when blue, purple, red or yellow tungsten bronzes are formed. These are semi-metallic solids which have a lustre and conduct electricity. They are very inert to both strong acids and strong alkali. They are used in the production of 'bronze' and 'metallic' paints.

Tungsten bronzes are nonstoichiometric compounds of formula  $\text{M}_x\text{WO}_3$ , where M is Na, K, a Group 2 metal or a lanthanide, and  $x$  is always less than one. The  $\text{Na}^+$  or other metal ions occupy interstitial positions. The colour depends on the proportion of M present, and for the sodium compounds:  $x \sim 0.9$  yellow or gold,  $x \sim 0.7$  orange,  $x \sim 0.5$  red,  $x \sim 0.3$  blue-black. The variable amount of  $\text{Na}^+$  produces a defective lattice and some of the sites which should be occupied by alkali metals are vacant. It might be thought that for each  $\text{Na}^+$  removed from  $\text{NaWO}_3$ , one tungsten would change from W(+V) to W(+VI). The properties of the tungsten bronzes are better explained by assuming that all the tungsten atoms are in the (+VI) state. The valency electrons from the alkali metals are free to move throughout the lattice, giving metallic conduction. The conductivity decreases with increased temperature, as in a metal. The structure is  $\text{WO}_6$  octahedra joined together by sharing all their corners with other

octahedra Further details of tungsten bronzes are given in Further Reading

Molybdenum also forms bronzes similar to those of W, but a high pressure is needed to form them, and the Mo compounds are less stable This may be because Mo(+V) is less stable than W(+V), or because the solid structure is different and contains  $\text{MoO}_6$  octahedra joined by a mixture of corner and edge sharing with other octahedra Lithium also forms bronzes, but these do not conduct electricity

### BIOLOGICAL IMPORTANCE

Trace amounts of Cr and Mo are necessary in the diet of mammals Cr(+III) and insulin are both involved in maintaining the correct level of glucose in the blood In cases of Cr deficiency, glucose is only removed from the blood half as fast as normally Some cases of diabetes may reflect faulty metabolism of Cr The most important medical aspect of Cr salts is that larger amounts either ingested or on the skin are carcinogenic Compounds containing Cr(VI), e.g. dichromate and chromate, are particularly so Thus care should be taken when performing titrations using  $\text{K}_2\text{Cr}_2\text{O}_7$  or  $\text{KCrO}_4$

Mo is present in the catalysts of dinitrogen fixing bacteria (The amount of dinitrogen fixed biologically is estimated at 175 million tonnes per year, compared with a total of 110 million tonnes of  $\text{NH}_3$  produced by the Haber-Bosch process and the distillation of coal) The best known dinitrogen fixing bacterium is *Rhizobium* This contains the metallo enzyme nitrogenase

Nitrogenase contains two proteins, molybdoferredoxin and azoferredoxin Molybdoferredoxin is brown, air sensitive contains two Mo atoms 24-36 Fe atoms and 24-36 S atoms together with a protein, and has a molecular weight of about 225 000 Azoferredoxin is yellow, air sensitive, is a derivative of ferredoxin  $\text{Fe}_4\text{S}_4(\text{SR})_4$  and has a molecular weight in the range 50 000-70 000 It is not certain exactly how dinitrogen fixation occurs It is thought that  $\text{N}_2$  bonds to the Mo in molybdoferredoxin (whether end on or sideways on is not known) If the Mo is sufficiently reduced it can probably bond to the antibonding orbitals on  $\text{N}_2$  Then the Fe in azoferredoxin is reduced by free ferredoxin  $\text{Fe}_4\text{S}_4(\text{SR})_4$  An electron is transferred from reduced azoferredoxin to molybdoferredoxin, possibly via the Fe, then from the Mo to the  $\text{N}_2$  Protons are then added to  $\text{N}_2$  eventually giving  $\text{NH}_3$  Adenosine triphosphate ATP is required to provide the necessary energy for the process Nitrogenase is not specific for the reaction  $\text{N}_2 \rightarrow \text{NH}_3$ , but also reduces alkynes to alkenes, and cyanides

### FURTHER READING

Abel E W and Stone F G (1969-1970) The chemistry of transition metal carbonyls *Q Rev Chem Soc* Part I - Structural considerations 23 325 Part II - Synthesis and reactivity 24 498

- Bevan, D.J.M. (1973) *Comprehensive Inorganic Chemistry*, Vol. 4 (Chapter 49: Non-stoichiometric compounds), Pergamon Press, Oxford.
- Burgmayer, S.J.N. and Stiefel, E.I. (1985) Molybdenum enzymes, *J. Chem. Ed.*, **62**, 943–953.
- Canterford, J.H. and Cotton, R. (1968) *Halides of the Second and Third Row Transition Elements*, Wiley, London.
- Canterford, J.H. and Cotton, R. (1969) *Halides of the First Row Transition Elements*, Wiley, London.
- Corbett, J.D. (1981) Extended metal–metal bonding in halides of the early transition metals, *Acc. Chem. Res.*, **14**, 239.
- Cotton, F.A. (1975) Compounds with multiple metal to metal bonds, *Chem. Soc. Rev.*, **4**, 27–53.
- Cotton, F.A. (1978) Discovering and understanding multiple metal to metal bonds, *Acc. Chem. Res.*, **11**, 225–232.
- Cotton, F. A. and Chisholm, M.H. (1978) Chemistry of compounds containing metal–metal bonds, *Acc. Chem. Res.*, **11**, 356–362.
- Coughlin, M. (ed.) (1980) *Molybdenum and Molybdenum-containing Enzymes*, Pergamon Press, Oxford.
- Diatom metals and metallic clusters* (Conference papers of the Faraday Symposia of the Royal Society of Chemistry, No. 14), Royal Society of Chemistry, London.
- Dilworth, J.R. and Lappert, M.F. (eds) (1983) *Some Recent Developments in the Chemistry of Chromium, Molybdenum and Tungsten*, Royal Society of Chemistry, Dalton Division. (Proceedings of a conference at the University of Sussex.)
- Emeléus, H.J. and Sharpe, A.G. (1973) *Modern Aspects of Inorganic Chemistry*, 4th ed. (Chapters 14 and 15: Complexes of Transition Metals: Chapter 20: Carbonyls) Routledge and Kegan Paul, London.
- Greenwood, N.N. (1968) *Ionic Crystals, Lattice Defects and Non-Stoichiometry*, Butterworths, London. (Defect structures.)
- Hagenmuller, P. (1973) *Comprehensive Inorganic Chemistry*, Vol. 4 (Chapter 50: Tungsten bronzes, vanadium bronzes), Pergamon Press, Oxford.
- Hudson, M. (1982) Tungsten: its sources, extraction and uses, *Chemistry in Britain*, **18**, 438–442.
- Hunt, C.B. (1977) Metallocenes – the first 25 years, *Education in Chemistry*, **14**, 110–113.
- Johnson, B.F.G. (ed.) (1980) *Transition Metal Clusters*, John Wiley, Chichester.
- Keper, D.L. (1972) *The Early Transition Metals* (Chapter 4: Cr, Mo, W), Academic Press, London.
- Keper, D.L. (1973) *Comprehensive Inorganic Chemistry*, Vol. 4 (Chapter 51: Isopolyanions and heteropolyanions), Pergamon Press, Oxford.
- Lewis, J. and Green, M.L. (eds) (1983) *Metal Clusters in Chemistry* (Proceedings of the Royal Society Discussion Meeting May 1982), The Society, London.
- Mitchell, P.C.H. (ed.) (1974) Chemistry and uses of molybdenum, *J. Less Common Metals*, **36**, 3–11.
- Pope, M.T. (1983) *Heteropoly and Isopoly Oxo Metalates*, Springer-Verlag. (A good account of poly acids.)
- Richards, R.L. (1979) Nitrogen fixation, *Education in Chemistry*, **16**, 66–69.
- Rollinson, C.L. (1973) *Comprehensive Inorganic Chemistry*, Vol. 3 (Chapter 36: Chromium, molybdenum and tungsten), Pergamon Press, Oxford.
- Shriver, D.H., Kaesz, H.D. and Adams, R.D. (eds) (1990) *Chemistry of Metal Cluster Complexes*, VCH, New York.
- Templeton, J.L. (1979) Metal–metal bonds of order four, *Progr. Inorg. Chem.*, **26**, 211–300.
- Toth, L.E. (1971) *Transition Metal Carbides and Nitrides*, Academic Press, London.

## Group 7 – the manganese group

**Table 23 1** Electronic structures and oxidation states

Element		Electronic structure	Oxidation states*
Manganese	Mn	[Ar] 3d <sup>5</sup> 4s <sup>2</sup>	(-I) 0 <b>(I)</b> <b>II</b> (III) <b>IV</b> (V) (VI) VII
Technetium	Tc	[Kr] 4d <sup>5</sup> 5s <sup>2</sup>	0 <b>(II)</b> (III) <b>IV</b> (V) VI VII
Rhenium	Re	[Xe] 4f <sup>14</sup> 5d <sup>5</sup> 6s <sup>2</sup>	0 (I) (II) <b>III</b> <b>IV</b> (V) VI VII

\*The most important oxidation states (generally the most abundant and stable) are shown in bold. Other well-characterized but less important states are shown in normal type. Oxidation states that are unstable or in doubt are given in parentheses.

### INTRODUCTION

Manganese is produced in very large amounts, most of which is used in the steel industry. Large quantities of MnO<sub>2</sub> are also produced, and are used mainly for making 'dry' batteries and in the brick industry. KMnO<sub>4</sub> is an important oxidizing agent. Mn(+III) forms a basic acetate with an unusual structure. Mn is biologically important and is necessary for photosynthesis. The elements technetium and rhenium are rarely encountered. They differ from manganese in that they have little cationic chemistry, their high oxidation states are much more stable, and the oxidation states (+II), (+III) and (+IV) form cluster compounds and compounds with metal-metal bonds.

### ABUNDANCE, EXTRACTION AND USES

Manganese is the twelfth most abundant element by weight in the earth's crust, and is mined as the ore pyrolusite MnO<sub>2</sub>. This is a secondary material, which has been formed by alkaline waters leaching Mn from igneous rocks and depositing it as MnO<sub>2</sub>. World production of Mn ores was 22.7 million tonnes in 1992, containing about 9 million tonnes of Mn. The largest producers are the Soviet Union 31%, China 25%, South Africa and Brazil 11% each, Gabon 7%, India 6% and Australia 5%.

Pure Mn is now obtained by electrolysis of aqueous  $\text{MnSO}_4$  solutions. (Formerly it was made by reducing  $\text{MnO}_2$  or  $\text{Mn}_3\text{O}_4$  with Al in a thermite reaction, but the reaction with  $\text{MnO}_2$  was particularly violent.) There is little use for the pure metal. Ninety-five per cent of the Mn ores mined are used in the steel industry to produce alloys. Ferromanganese is the most important, and contains 80% Mn. World production of ferromanganese was 3.4 million tonnes in 1991. It is made by reducing the appropriate mixture of  $\text{Fe}_2\text{O}_3$  and  $\text{MnO}_2$  with carbon in a blast furnace, or an electric-arc furnace, with some limestone added to remove silicate impurities as calcium silicate slag. Alloys with a lower Mn content include silicomanganese (approximately 65% Mn, 20% Si, 15% Fe) and spiegeleisen which is similar to cast iron and contains 5–25% Mn. Mn is an important additive in making steel. It acts as a scavenger (removing both oxygen and sulphur and thus preventing bubbles and brittleness) and in addition it forms a very hard steel alloy. (Hadfield steel contains about 13% Mn and 1.25% C. It is very hard wearing and resistant to shock, and is used for rock crushing machinery and excavators.) Smaller amounts of Mn are also used in non-ferrous alloys. For example, manganin is an alloy containing 84% Cu, 12% Mn and 4% Ni. It is widely used in electrical instruments because its electrical resistance is almost unaffected by temperature.

Table 23.2 Abundance of the elements in the earth's crust, by weight

	ppm	Relative abundance
Mn	1060	12
Tc	0	
Re	0.0007	76

Technetium does not occur in nature, and was the first man-made element. All its isotopes are radioactive, and its chemistry has only recently been studied.  $^{99}\text{Tc}$  is one of the fission products of uranium. It is a  $\beta$  emitter with a half life of  $2.1 \times 10^5$  years. It is obtained in kilogram quantities from spent fuel rods from reactors at nuclear power stations. The rods may contain 6% Tc. These rods must be stored for several years to allow the short-lived radioactive species to decay. Tc can be extracted by oxidation to  $\text{Tc}_2\text{O}_7$  which is volatile. Alternatively solutions can be separated by ion exchange and solvent extraction. The  $\text{Tc}_2\text{O}_7$  can be dissolved in water, forming the pertechnetate ion  $\text{TcO}_4^-$ , and crystallized as ammonium or potassium pertechnetate. Ammonium pertechnetate  $\text{NH}_4\text{TcO}_4$  can be reduced with  $\text{H}_2$  to give the metal. Tc metal has no commercial uses.  $^{97}\text{Tc}$  and  $^{98}\text{Tc}$  can be made by neutron bombardment of Mo. Small amounts of Tc compounds are sometimes injected into patients to allow radiographic scanning of the liver and other organs.

Rhenium is a very rare element, and occurs in small amounts in molybdenum sulphide ores. Re is recovered as  $\text{Re}_2\text{O}_7$  from the flue dust from roasting these ores. This is dissolved in NaOH, giving a solution containing perrhenate ions  $\text{ReO}_4^-$ . The solution is concentrated and then KCl added

*continued overleaf*



to precipitate potassium perrhenate  $\text{KReO}_4$ . The metal is obtained by reducing  $\text{KReO}_4$  or  $\text{NH}_4\text{ReO}_4$  with hydrogen. World production was only 32 tonnes in 1992. Most of it is used to make Pt-Re alloys which are used as catalysts for making low-lead or lead free petrol for cars. Small amounts are used as a catalyst for hydrogenation and dehydrogenation reactions. Because of its very high melting point (Table 23.4) it is used in thermocouples, electric furnace windings and mass spectrometer filaments.

### OXIDATION STATES

The electronic structure for this group of elements is  $d^5s^2$ . The highest oxidation state of (+VII) is obtained when all these electrons are used for bonding. Mn shows the widest range of oxidation states of all the elements ranging from (-III) to (+VII). The (+II) state is the most stable and most common and  $\text{Mn}^{2+}$  ions exist in the solid, in solution and as complexes. However, in alkaline solution  $\text{Mn}^{2+}$  is readily oxidized to  $\text{MnO}_2$ . The (+IV) state is found in the main ore pyrolusite  $\text{MnO}_2$ .  $\text{Mn}(+VII)$  is well known as  $\text{KMnO}_4$ . This is one of the strongest oxidizing agents known in solution, and is stronger than  $\text{Cr}(+VI)$  in the previous group.  $\text{Mn}(+III)$  and  $\text{Mn}(+VI)$  tend to disproportionate. The lower oxidation states exist as carbonyl compounds or as substituted carbonyl complexes.

In contrast to the highly oxidizing properties of  $\text{Mn}(+VII)$ , the (+VII) state is the most common and most stable for Tc and Re.  $\text{Tc}(+VII)$  and  $\text{Re}(+VII)$  show only slight oxidizing properties. The (+VI) state tends to disproportionate and is not well known. The (+V) and (+IV) states for Tc

Table 23.3 Oxides and halides

Oxidation states						
(+II)	(+III)	(+IV)	(+V)	(+VI)	(+VII)	Others
<b>MnO</b>	<b>Mn<sub>2</sub>O<sub>3</sub></b>	<b>MnO<sub>2</sub></b>	-	-	<b>Mn<sub>2</sub>O<sub>7</sub></b>	<b>Mn<sub>2</sub>O<sub>4</sub></b>
-	-	<b>TcO<sub>2</sub></b>	-	<b>TcO<sub>3</sub></b>	<b>Tc<sub>2</sub>O<sub>7</sub></b>	-
-	<b>Re<sub>2</sub>O<sub>3</sub><sup>h</sup></b>	<b>ReO<sub>2</sub></b>	( <b>Re<sub>2</sub>O<sub>5</sub></b> )	<b>ReO<sub>3</sub></b>	<b>Re<sub>2</sub>O<sub>7</sub></b>	-
<b>MnF<sub>2</sub></b>	<b>MnF<sub>3</sub></b>	<b>MnF<sub>4</sub></b>	-	-	-	-
<b>MnCl<sub>2</sub></b>	-	-	-	-	-	-
<b>MnBr<sub>2</sub></b>	-	-	-	-	-	-
<b>MnI<sub>2</sub></b>	-	-	-	-	-	-
-	-	-	<b>TcF<sub>5</sub></b>	<b>TcF<sub>6</sub></b>	-	-
-	-	<b>TcCl<sub>4</sub></b>	-	( <b>TcCl<sub>6</sub></b> ?)	-	-
-	-	-	-	-	-	-
-	-	-	-	-	-	-
-	-	<b>ReF<sub>4</sub></b>	<b>ReF<sub>5</sub></b>	<b>ReF<sub>6</sub></b>	<b>ReF<sub>7</sub></b>	-
( <b>ReCl<sub>2</sub></b> )	<b>ReCl<sub>3</sub></b>	<b>ReCl<sub>4</sub></b>	<b>ReCl<sub>5</sub></b>	( <b>ReCl<sub>6</sub></b> ?)	-	-
( <b>ReBr<sub>2</sub></b> )	<b>ReBr<sub>3</sub></b>	<b>ReBr<sub>4</sub></b>	<b>ReBr<sub>5</sub></b>	-	-	-
( <b>ReI<sub>2</sub></b> )	<b>ReI<sub>3</sub></b>	<b>ReI<sub>4</sub></b>	-	-	-	-

The most stable oxidation states are shown in bold, unstable ones in brackets.  
h = hydrous oxide

and Re have an extensive chemistry. Re(+III) is also stable and the halides form cluster compounds with metal-metal bonds. The (+II) and lower oxidation states are uncommon and are strongly reducing.

Thus on descending the group there is an increase in stability of the highest oxidation state and also a decrease in stability of the lower states. The stability of the various states is shown in Table 23.3. The tendency to disproportionate is shown in the reduction potentials.

### STANDARD REDUCTION POTENTIALS (VOLTS)

Acid solution						
Oxidation state						
+VII	+VI	+IV	+III	+II	0	
MnO <sub>4</sub> <sup>-</sup>	$\xrightarrow{+0.56}^*$ MnO <sub>4</sub> <sup>2-</sup>	$\xrightarrow{+2.26}$ MnO <sub>2</sub>	$\xrightarrow{+0.95}^*$ Mn <sup>3+</sup>	$\xrightarrow{+1.51}$ Mn <sup>2+</sup>	$\xrightarrow{-1.19}$	Mn
		$\xrightarrow{+1.69}$			$\xrightarrow{+1.23}$	
		$\xrightarrow{+1.51}$				
TcO <sub>4</sub> <sup>-</sup>	$\xrightarrow{+0.698}^*$ (TcO <sub>3</sub> )	$\xrightarrow{+0.757}$ TcO <sub>2</sub>	$\xrightarrow{0.144}$		$\xrightarrow{+0.272}$	
		$\xrightarrow{-0.737}$			$\xrightarrow{+0.400}$	Tc
		$\xrightarrow{+0.50}$				
ReO <sub>4</sub> <sup>-</sup>	$\xrightarrow{+0.734}$ ReO <sub>3</sub>	$\xrightarrow{+0.425}^*$ ReO <sub>2</sub>	$\xrightarrow{+1.04}$ Re <sup>3+</sup>	$\xrightarrow{+0.251}$		
		$\xrightarrow{+0.318}$		$\xrightarrow{+0.300}$		Re
		$\xrightarrow{+0.422}$				

\* Disproportionates  
Potentials involving TcO<sub>3</sub> are calculated values

### GENERAL PROPERTIES

Mn is more reactive than its neighbours in the periodic table. It reacts slowly with  $\text{H}_2\text{O}$ , liberating  $\text{H}_2$ , and it dissolves readily in dilute acids. The finely divided metal is pyrophoric in air, but the massive metal does not react unless heated. When strongly heated the massive metal reacts with many non-metals such as  $\text{O}_2$ ,  $\text{N}_2$ ,  $\text{Cl}_2$  and  $\text{F}_2$ , forming  $\text{Mn}_3\text{O}_4$ ,  $\text{Mn}_3\text{N}_2$ ,  $\text{MnCl}_2$  and a mixture of  $\text{MnF}_2$  and  $\text{MnF}_3$ . The melting point of the metal is appreciably lower than for the earlier first row elements Ti, V and Cr. It is

unusual in that it has four different solid structures ( $\alpha$  or body-centred cubic, cubic close packed,  $\beta$ , and  $\chi$ ) The  $\alpha$  form is stable at room temperature and has a body-centred cubic structure (See Chapter 5)

Tc and Re metals are less reactive than Mn. They do not react with  $\text{H}_2\text{O}$ , or non-oxidizing acids. They do not dissolve in HCl and HF, but they react with oxidizing acids such as concentrated  $\text{HNO}_3$  and  $\text{H}_2\text{SO}_4$ , forming pertechnic acid  $\text{HTcO}_4$  and perrhenic acid  $\text{HReO}_4$  (This is not the usual reaction of acid + metal to give a salt +  $\text{H}_2$ . For example, with concentrated  $\text{HNO}_3$ , the  $\text{NO}_3^-$  ion is a stronger oxidizing agent than  $\text{H}_3\text{O}^+$ , and  $\text{NO}_2$  is evolved.) Tc and Re undergo similar reactions with  $\text{H}_2\text{O}_2$  and bromine water. The massive metals tarnish (oxidize) slowly in moist air, but the powdered metals are more reactive. Heating with  $\text{O}_2$  gives  $\text{Tc}_2\text{O}_7$  and  $\text{Re}_2\text{O}_7$  which are both low melting ( $119.5^\circ\text{C}$  and  $300^\circ\text{C}$  respectively) and volatile. Heating with  $\text{F}_2$  gives  $\text{TcF}_5$  and  $\text{TcF}_6$ , and  $\text{ReF}_6$  and  $\text{ReF}_7$ .

Table 23.4 Some physical properties

	Covalent radius (Å)	Ionic radius (Å)		Melting point ( $^\circ\text{C}$ )	Boiling point ( $^\circ\text{C}$ )	Density ( $\text{g cm}^{-3}$ )	Pauling's electronegativity
		$\text{M}^{2+}$	$\text{M}^{3+}$				
Mn	1.22	0.67	0.645 <sup>h</sup> 0.58 <sup>l</sup>	1244	2060	7.43	1.5
Tc	1.34	—	—	2200	4567	11.5	1.9
Re	1.34	—	—	3180	5650	21.0	1.9

h = high spin value l = low spin radius

Many ionic compounds of Mn are known including  $\text{Mn}^{2+}$ ,  $\text{Mn}^{3+}$ ,  $\text{MnO}_4^{2-}$  and  $\text{MnO}_4^-$ . In contrast Tc and Re have virtually no aqueous ionic chemistry apart from the oxoions  $\text{TcO}_4^-$  and  $\text{ReO}_4^-$ . The elements Tc and Re have a marked tendency to form metal-metal bonds in the lower oxidation states (+II), (+III) and (+IV).

Trace amounts of manganese are essential for plant and animal growth. For this reason small amounts of  $\text{MnSO}_4$  are often added to fertilizers.

The basic character of any element changes with the oxidation state. Low oxidation states are more basic and high oxidation states are more acidic.  $\text{MnO}$  and  $\text{Mn}_2\text{O}_3$  are basic oxides and are ionic.  $\text{MnO}_2$  is amphoteric and does not exist as  $\text{Mn}^{4+}$  ions.  $\text{Mn}(+V)$  is rather uncommon.  $\text{Mn}(+VI)$  is represented by manganates such as  $\text{Na}_2[\text{MnO}_4]$ . This may be regarded as a salt of the unstable acidic oxide  $\text{MnO}_3$ , which does not exist in the free state.  $\text{Mn}(+VII)$  occurs as  $\text{Mn}_2\text{O}_7$  which is strongly acidic. The corresponding acid, permanganic acid  $\text{HMnO}_4$ , is a very strong acid.

Almost all manganese compounds are coloured.  $\text{Mn}^{2+}$  is pale pink and  $\text{MnO}_2$  is black, both because of  $d-d$  transitions. The (+VII) oxidation state has a  $d^0$  configuration and would be expected to be colourless. Whilst perrhenates  $\text{ReO}_4^-$  containing  $\text{Re}(+VII)$  are colourless, permanganates  $\text{MnO}_4^-$  containing  $\text{Mn}(+VII)$  are intensely coloured. The purple-black colour arises from charge transfer spectra.

Mn resembles iron in its physical and chemical properties. Mn is harder and more brittle than iron, but melts at a lower temperature (Mn = 1244°C, Fe = 1535°C). All three metals Mn, Tc and Re are usually obtained as grey powders, but in the massive form they look like platinum. Re has the second highest melting point of all the metals (W = 3380°C; Re = 3180°C).

Manganese is quite electropositive and dissolves in cold dilute non-oxidizing acids. It is not very reactive towards non-metals at room temperature, but reacts readily on heating.

Mn is much more reactive than Re. Similar behaviour is observed in adjacent groups: Cr is more reactive than W, and Fe more reactive than Os. This decrease in electropositive character is opposite to the trend shown in the main groups of the periodic table. In addition, Re tends to attain a higher oxidation state than Mn when they both react with the same element. A comparison of some of the reactions of Mn and Re is given in Table 23.5.

Table 23.5 Some reactions of manganese and rhenium


Reagent	Mn	Re
N <sub>2</sub>	Mn <sub>3</sub> N <sub>2</sub> formed at 1200°C	No reaction
C	Mn <sub>3</sub> C	No reaction
H <sub>2</sub> O	Mn <sup>2+</sup> + H <sub>2</sub>	No reaction
Dilute acid	Mn <sup>2+</sup> + H <sub>2</sub>	No reaction
Strong acid	Mn <sup>2+</sup> + H <sub>2</sub>	Dissolves slowly
Halogens	MnX <sub>2</sub> and MnF <sub>3</sub>	ReF <sub>6</sub> , ReCl <sub>5</sub> , ReBr <sub>3</sub>
S	MnS	ReS <sub>2</sub>
O <sub>2</sub>	Mn <sub>3</sub> O <sub>4</sub>	Re <sub>2</sub> O <sub>7</sub>

Group 7 (manganese group) elements have seven outer electrons, but the similarity to Group 17 elements, the halogens, is very slight except in the highest oxidation state. Mn<sub>2</sub>O<sub>7</sub> and Cl<sub>2</sub>O<sub>7</sub> may be compared; MnO<sub>4</sub><sup>-</sup> and ClO<sub>4</sub><sup>-</sup> are isomorphous and have similar solubilities, and IO<sub>4</sub><sup>-</sup> and ReO<sub>4</sub><sup>-</sup> are quite similar. There are much closer similarities between Mn and its horizontal neighbours Cr and Fe. The chromates CrO<sub>4</sub><sup>2-</sup>, manganates MnO<sub>4</sub><sup>2-</sup> and ferrates FeO<sub>4</sub><sup>2-</sup> are similar. The solubilities of the lower oxides are also similar, which accounts for the occurrence of iron and manganese together.

## LOWER OXIDATION STATES

The (-I) oxidation state is found in the carbonylate anion [Mn(CO)<sub>5</sub>]<sup>-</sup>. The zero-valent state exists as the carbonyls [Mn<sub>2</sub>(CO)<sub>10</sub>] and [Re<sub>2</sub>(CO)<sub>10</sub>] and as a coordination complex K<sub>6</sub>[Mn(CN)<sub>6</sub>] · 2NH<sub>3</sub> which is unstable and highly reducing.


Mn(+I) and Re(+I) are only obtained with difficulty and are strongly reducing.



The cyano complex  $\text{Na}_5[\text{Mn}^{\text{I}}(\text{CN})_6]$  is formed by dissolving powdered Mn in aqueous NaCN in the complete absence of air

### (+II) STATE

Mn(+II) salts (often called manganous salts) can easily be made from  $\text{MnO}_2$



Most Mn(+II) salts are soluble in water and form hydrated  $\text{Mn}^{2+}$  ions, but  $\text{Mn}_3(\text{PO}_4)_2$  and  $\text{MnCO}_3$  are sparingly soluble.  $[\text{Mn}(\text{H}_2\text{O})_6]^{2+}$  ions are pink. They are also formed by dissolving the metal in acid, or by reducing higher oxidation states. Small amounts of  $\text{MnSO}_4$  are added to fertilizers, as Mn is an essential trace element for plants. Adding NaOH or  $\text{NH}_4\text{OH}$  to a solution of  $\text{Mn}^{2+}$  ions gives a very pale pink gelatinous precipitate of  $\text{Mn}(\text{OH})_2$ , which turns brown-black due to oxidation to  $\text{MnO}_2$ . The standard electrode potentials show that this cannot occur in acid solution but occurs easily in basic solutions

Oxidation state						
+VII	+VI	+V	+IV	+III	+II	0
Acid solution						
$\text{MnO}_4^-$	$\xrightarrow{+0.56^*}$	$\text{MnO}_4^{2-}$	$\xrightarrow{+2.26}$	$\text{MnO}_2$	$\xrightarrow{+0.95^*}$	$\text{Mn}^{3+} \xrightarrow{+1.51} \text{Mn}^{2+} \xrightarrow{-1.19} \text{Mn}$
Basic solution						
$\text{MnO}_4^-$	$\xrightarrow{+0.56}$	$\text{MnO}_4^{2-}$	$\xrightarrow{+0.27^*}$	$\text{MnO}_4^{3-}$	$\xrightarrow{+0.93}$	$\text{MnO}_2 \xrightarrow{+0.1} \text{Mn}^{3+} \xrightarrow{-0.2} \text{Mn}(\text{OH})_2 \xrightarrow{-1.55} \text{Mn}$
* = Disproportionates						

$\text{Mn}^{2+}$  has the electronic configuration  $3d^5$  which corresponds to a half filled  $d$  shell. Thus  $\text{Mn}^{2+}$  is more stable than other divalent ions of transition metals and is more difficult to oxidize than  $\text{Cr}^{2+}$  or  $\text{Fe}^{2+}$ . Most Mn(+II) complexes are octahedral and have a high-spin arrangement with five unpaired electrons (Figure 23.1). This arrangement gives zero crystal field stabilization energy (see Chapter 7). Thus complexes such as  $[\text{Mn}(\text{NH}_3)_6]^{2+}$  and  $[\text{MnCl}_6]^{4-}$  are not stable except in solution. Complexes with chelating ligands are more stable and  $[\text{Mn}(\text{ethylenediamine})_3]^{2+}$ ,  $[\text{Mn}(\text{oxalate})_3]^{4-}$  and  $[\text{Mn}(\text{EDTA})]^{4-}$  can be isolated as solids.

These complexes all have very pale colours. This is because a  $d-d$  transition in a high-spin  $d^5$  complex requires not only the promotion of an





Figure 23.1 High- and low-spin arrangements in octahedral crystal field.

electron from the  $t_{2g}$  level to the  $e_g$  level, but also the reversing of its spin. The spin selection rule states that when promoting an electron its spin may not be changed. The rule is only partially obeyed, but the probability of a transition where the spin is changed is low. Such transitions are termed *spin forbidden*. Because the probability of a spin forbidden transition is small, the colour is only about one hundredth the intensity of those observed in most normal *spin allowed* transitions. (It must also be remembered that all  $d-d$  transitions are forbidden by the Laporte selection rule. This states that when promoting an electron the change in the subsidiary quantum number  $l$  must be  $\pm 1$ , so  $s \rightarrow p$  or  $p \rightarrow d$  transitions are allowed but not  $d \rightarrow d$ . This selection rule is less restrictive as it is possible to get round it if the complex is not symmetrical, or by the mixing of orbitals, or by thermal motion of the ligands. These are discussed in Chapter 32.) Details of crystal field splitting of the  $d$  levels are given in Chapter 7.

Strong field ligands may force the electrons to pair up, giving a *spin paired* complex. The only common spin paired complex of Mn is  $[\text{Mn}(\text{CN})_6]^{4-}$  which has only one unpaired electron (Figure 23.1).  $\text{K}_4[\text{Mn}(\text{CN})_6] \cdot 3\text{H}_2\text{O}$  is blue in colour, and has the same structure as  $\text{K}_4[\text{Fe}(\text{CN})_6]$ . Similarly,  $[\text{Mn}(\text{CNR})_6]^{2+}$  and  $[\text{Mn}(\text{CN})_5 \cdot \text{NO}]^{3-}$  have a spin paired or low-spin arrangement with only one unpaired electron. The low-spin arrangement is a slightly more stable arrangement than the high-spin case. In the low-spin case the crystal field stabilization energy is five times  $\Delta_o$  from filling five electrons into the low energy  $t_{2g}$  orbitals. This is partly cancelled out by the energy needed to pair two electron spins. The low-spin complexes are more reactive. They can be oxidized very readily because removing an electron removes one unit of pairing energy and thus increases the crystal field stabilization energy. These complexes can also be reduced fairly readily, since adding an electron fills the orbitals symmetrically.



In low-spin  $d^5$  complexes,  $d-d$  electronic transitions are *spin permitted* and the compounds are quite strongly coloured.

A few examples of square planar complexes are also known, including Mn phthalocyanine, and  $\text{MnSO}_4 \cdot 5\text{H}_2\text{O}$  which contains square planar  $[\text{Mn}(\text{H}_2\text{O})_4]^{2+}$  units


The halide complexes  $[\text{MnCl}_4]^{2-}$ ,  $[\text{MnBr}_4]^{2-}$  and  $[\text{MnI}_4]^{2-}$  are tetrahedral and are green-yellow in colour. In solution they add two molecules of water or two halide ions to form pink coloured octahedral complexes. These octahedra can polymerize by means of halide bridges.

$\text{Re}(+II)$  is not ionic, and is found only in a few complexes such as  $[\text{Re}(\text{pyridine})_2\text{Cl}_2]$ . This has been resolved into *cis* and *trans* isomers, showing that it is square planar rather than tetrahedral.

### (+III) STATE

$\text{Mn}_3\text{O}_4$  is black in colour and is the most stable oxide at high temperatures. It is formed by heating any oxide or hydroxide of Mn to  $1000^\circ\text{C}$ . It contains both Mn(+II) and Mn(+III), i.e.  $(\text{Mn}^{II}\text{Mn}_2^{III}\text{O}_4)$ , and has a spinel structure. The O atoms are close packed with Mn(+III) in octahedral holes and Mn(+II) in tetrahedral holes.

The hydrated manganic ion  $[\text{Mn}(\text{H}_2\text{O})_6]^{3+}$  can be obtained in solution by electrolysis by oxidizing  $\text{Mn}^{2+}$  with potassium peroxodisulphate  $\text{K}_2\text{S}_2\text{O}_8$ , or by reducing  $\text{MnO}_4^-$ . It cannot be obtained in strong concentrations partly because water reduces  $\text{Mn}^{3+}$  to the very stable  $\text{Mn}^{2+}$  (which has enhanced stability due to the  $d^5$  configuration).  $\text{Mn}^{3+}$  disproportionates in acid solution (see the standard reduction potentials). A small number of  $\text{Mn}^{3+}$  salts are known, e.g.  $\text{MnF}_3$ ,  $\text{Mn}_2(\text{SO}_4)_3$  and the oxide  $\text{Mn}_2\text{O}_3$ . These disproportionate in acid and hydrolyse in water.



Mn(+III) complexes are stable in aqueous solution. Most complexes are octahedral and high spin, with magnetic moments close to the spin only value of  $4.90\text{ BM}$  for four unpaired electrons. These include  $[\text{Mn}(\text{H}_2\text{O})_6]^{3+}$  which is found in alums such as  $\text{Cs}^+\text{Mn}^{III}(\text{SO}_4)_3 \cdot 12\text{H}_2\text{O}$ , and in the acetylacetonate complex  $[\text{Mn}(\text{acac})_3]$  whose crystal structure is a slightly distorted octahedron. The Jahn-Teller theorem predicts a slight distortion of the shape, as the electronic structure is  $(t_{2g})^3(e_g)^2$  and the  $e_g$  level is not symmetrically filled. This distortion is similar to that found in  $\text{Cr}^{2+}$  and  $\text{Cu}^{2+}$  complexes. The oxalate complex  $[\text{Mn}^{III}(\text{oxalate})_3]^{3-}$  may be formed during permanganate-oxalate titrations. This would upset analytical calculations which are based on the reduction of  $\text{MnO}_4^-$  to  $\text{Mn}^{2+}$ . However, the oxalate complex is thermally unstable so the titration is performed at about  $60^\circ\text{C}$  to decompose the complex.

The complex  $\text{K}_4[\text{Mn}^{III}(\text{CN})_6]$  is formed when air is bubbled through a solution containing  $\text{Mn}^{2+}$  and KCN. Since  $\text{CN}^-$  acts as a strong field ligand, it causes spin pairing and the complex is low spin. The electronic

structure is  $(t_{2g})^4 (e_g)^0$ , the  $e_g$  level is symmetrically filled, and the complex ion is a regular octahedron as expected.

Manganese forms an unusual basic acetate when  $Mn^{2+}$  is oxidized with  $KMnO_4$  in glacial acetic acid. The compound has the formula  $[Mn_3O(CH_3COO)_6]^+ [CH_3 \cdot COO]^-$  and is a deep red-brown coloured solid. It is used industrially for the oxidation of toluene  $C_6H_5 \cdot CH_3$  to phenol  $C_6H_5OH$ . It will also oxidize alkenes to lactones, and it is used as the starting material for making many  $Mn(+III)$  compounds. The structure is unusual and consists of a triangle of three Mn atoms with an O atom at the centre. The six acetate groups act as bridges between the Mn atoms – two groups across each edge of the triangle. Thus each Mn atom is linked to four acetate groups and the central O, and the sixth position of the octahedron is occupied by water or another ligand giving  $[Mn_3O(CH_3COO)_6L_3]^+$ . This type of carboxylate complex is formed by the trivalent ions of Cr, Mn, Fe, Ru, Rh and Ir. A similar preparation in sulphuric acid gives an intensely red coloured solution. This is thought to contain a very similar sulphate complex with  $SO_4^{2-}$  groups acting as bridging groups. The solution is as strongly oxidizing as  $KMnO_4$  and at one time it was used as an alternative oxidizing agent for use in sulphate solutions.

$Mn(+III)$  and  $Mn(+IV)$  complexes are involved in the release of  $O_2$  during photosynthesis.

Tc(+III) is unstable but  $Re_2O_3 \cdot (H_2O)_n$  and the heavier halides are known. The halides are trimeric and  $(ReCl_3)_3$  and  $(ReBr_3)_3$  are dark red solids and  $(ReI_3)_3$  is black. Their structure consists of a metal atom cluster in which three Re atoms form an equilateral triangle (with formal double bonds between the metal atoms). Three halogen atoms act as bridging groups along the edges of the triangle, and the remaining six halogen atoms are coordinated two to each Re. An isolated  $Re_3X_9$  unit is shown in Figure 23.3a. There is one unfilled coordination position on each Re atom, marked L. In the solid this is filled by further halogen bridging with other  $Re_3X_9$  units, giving a polymer (Figure 23.3b). The trimeric structure is very stable, with Re-Re distances of 2.48 Å, and this structure remains even in the gas phase at 600 °C. This structure also forms the basis of the structure of many Re(+III) complexes, where three additional groups L are added to the isolated  $Re_3X_9$  unit (Figure 23.3c).

The simplest explanation of the double bonds between Re atoms is that each Re has nine atomic orbitals available for bonding (five  $d$ , one  $s$ , and three  $p$ ). The metal is surrounded by five ligands, leaving four unused orbitals. Assuming the unused orbitals are pure  $d$  or mainly  $d$  in character, there are 12 atomic orbitals for Re-Re bonding. If these are delocalized over the three atoms there will be six bonding MOs and six antibonding MOs. Each Re(+III) has a  $d^4$  configuration: hence the 12 electrons can enter the six bonding MOs, corresponding to double bonds between each of the three Re atoms. Since all the electrons are paired, the clusters should be diamagnetic, and this has been found experimentally.

If  $Re_3Cl_9$  or  $Re_3Br_9$  is dissolved in concentrated HCl or HBr, one, two




Figure 23.2 Structure of  $[Mn_3O(CH_3COO)_6(H_2O)_3]^+$ .






Figure 23 3 Various  $\text{Re}_3\text{X}_9$  structures

or three halide ions may be added to the isolated  $\text{Re}_3\text{X}_9$  unit. Halide complexes such as  $\text{K}^+[\text{Re}_3\text{Br}_{10}]^-$ ,  $\text{K}_2^+[\text{Re}_3\text{Br}_{11}]^{2-}$  and  $\text{K}_3^+[\text{Re}_3\text{Br}_{12}]^{3-}$  can be obtained from solution. It is also possible to obtain  $[\text{Re}_3\text{X}_9 \cdot 3\text{H}_2\text{O}]$ . The extra ligands L are more labile, i.e. more reactive, than the bridging groups.

A quite different type of halide complex is formed when perrhenates are reduced by  $\text{H}_2$  or sodium hypophosphite  $\text{NaH}_2\text{PO}_2$  in acid solution. These contain a dimeric unit  $[\text{Re}_2\text{Cl}_8]^{2-}$  or  $[\text{Re}_2\text{Br}_8]^{2-}$  which is isostructural with  $[\text{Mo}_2\text{Cl}_8]^{4-}$ . It is made up of two approximately square planar  $\text{ReX}_4$  units linked by a  $\text{Re}-\text{Re}$  bond of length  $2.24 \text{ \AA}$  (Figure 23.4).





Figure 23.4 Structure of  $[\text{Re}_2\text{Cl}_8]^{2-}$  ion.

The metal-metal bond length is very short, and is interpreted as a quadruple bond. If the  $\text{Re}-\text{Re}$  bond points along the  $z$  axis, the square planar  $\text{ReX}_4$  unit uses the  $s$ ,  $p_x$ ,  $p_y$  and  $d_{x^2-y^2}$  orbitals for  $\sigma$  bonding to the X atoms. A  $\sigma$  bond between the two Re atoms will have contributions from the  $p_z$  and  $d_{z^2}$  orbitals which lie along the axis. With the eclipsed conformation the  $d_{xz}$  and  $d_{yz}$  orbitals on the two Re atoms overlap sideways, forming two  $\pi$  bonds. Finally the  $d_{xy}$  orbitals which lie in the two  $\text{ReX}_4$  planes overlap with each other, giving a  $\delta$  bond.

#### (+IV) STATE

Very few  $\text{Mn}(+IV)$  compounds are known. However,  $\text{MnO}_2$  is the most important oxide in the group, and is commercially important. It is not the most stable oxide, as it is an oxidizing agent, and decomposes to  $\text{Mn}_3\text{O}_4$  on heating to  $530^\circ\text{C}$ .  $\text{MnO}_2$  occurs naturally as the black coloured mineral pyrolusite. It has the rutile structure which is also found for many other oxides of formula  $\text{MO}_2$ . It can be made as follows:

1. By heating Mn in  $\text{O}_2$ .
2. By oxidizing  $\text{Mn}^{2+}$ , for example by heating  $\text{Mn}(\text{NO}_3)_2 \cdot 6\text{H}_2\text{O}$  in air.
3. Very pure  $\text{MnO}_2$  is made by electrolytic oxidation of  $\text{Mn}^{II}\text{SO}_4$ .
4. In the laboratory hydrated  $\text{MnO}_2$  is precipitated from solution when performing permanganate titrations in alkaline solution.




Hydrated  $\text{MnO}_2$  has some cation exchange properties, and if it is dehydrated it loses some  $\text{O}_2$ , forming a nonstoichiometric product

$\text{MnO}_2$  does not react with most acids unless heated. It dissolves in concentrated  $\text{HCl}$ , but does not form  $\text{Mn}(+IV)$  in solution. Instead it oxidizes  $\text{Cl}^-$  to  $\text{Cl}_2$ , and is itself reduced to  $\text{Mn}^{2+}$ . Scheele discovered  $\text{Cl}_2$  using this reaction





This was the commercial method of producing  $\text{Cl}_2$  until electricity became commercially available and electrolysis became the preferred method. This reaction is still used to produce  $\text{Cl}_2$  in the laboratory if cylinders are not available.  $\text{MnO}_2$  oxidizes hot concentrated  $\text{H}_2\text{SO}_4$  in a similar way, liberating  $\text{O}_2$





Fusing  $\text{MnO}_2$  with  $\text{NaOH}$  gives sodium manganate(VI)  $\text{Na}_2[\text{MnO}_4]$ . This is a dark green colour and is oxidizing.

$\text{MnF}_4$  is formed by direct reaction between  $\text{Mn}$  and  $\text{F}_2$ . It is blue coloured and unstable. It is the highest halide formed by  $\text{Mn}$ . A few (+IV) complexes are also known including  $\text{K}_2[\text{MnF}_6]$ ,  $\text{K}_2[\text{MnCl}_6]$ ,  $\text{K}_2[\text{Mn}(\text{CN})_6]$  and  $\text{K}_2[\text{Mn}(\text{IO}_3)_6]$ . This is the highest oxidation state in which  $\text{Mn}$  forms complexes.


Over half a million tonnes per year of  $\text{MnO}_2$  is used in 'dry batteries' (Leclanche cells). This must be very pure, and is produced electrolytically (see above). Large amounts of  $\text{MnO}_2$  are also used in the brick industry to colour bricks red or brown. It is used to make red or purple glass.  $\text{MnO}_2$  is used in the production of potassium permanganate



$\text{MnO}_2$  is also used as an oxidizing agent in organic chemistry, for oxidizing alcohols and other compounds



$\text{MnO}_2$  is used as a catalyst in the preparation of dioxygen from  $\text{KClO}_3$ . If  $\text{KClO}_3$  is heated to a temperature of  $400\text{--}500^\circ\text{C}$  it decomposes and evolves  $\text{O}_2$ . With  $\text{MnO}_2$  present decomposition occurs at  $150^\circ\text{C}$ . The product is contaminated with  $\text{Cl}_2$  or  $\text{ClO}_2$ .




The (+IV) state is the second most stable state for both Tc and Re. The oxides  $\text{TcO}_2$  and  $\text{ReO}_2$  are black and brown respectively, and can be made in a variety of ways:

1. By burning the metals in a limited amount of dioxygen.
2. By heating the heptoxides  $\text{M}_2\text{O}_7$  with M.
3. By thermal decomposition of the ammonium salts  $\text{NH}_4\text{MO}_4$ .
4. The hydrated oxides are conveniently made by reducing solutions of  $\text{TcO}_4^-$  or  $\text{ReO}_4^-$  with  $\text{Zn/HCl}$ . These may be dehydrated by heating.

$\text{TcO}_2$  is insoluble in alkali, but  $\text{ReO}_2$  reacts with fused alkali, forming rhenites  $\text{ReO}_3^{2-}$ . Both oxides have a distorted rutile structure. The metal atoms in adjacent octahedra are displaced from the centre, giving a substantial metal-metal interaction like that in  $\text{MoO}_2$  and  $\text{WO}_2$ .


The sulphides  $\text{TcS}_2$  and  $\text{ReS}_2$  are both known. Rhenium sulphides are effective catalysts for organic hydrogenation reactions, and have the advantage over Pt that they are not 'poisoned' by sulphur compounds.

$\text{TcCl}_4$  has a solid structure of  $\text{TcCl}_6$  octahedra linked into a zig-zag chain, similar to  $\text{ZrCl}_4$ . It is paramagnetic, and there are no metal-metal bonds. All four  $\text{ReX}_4$  halides are known.  $\text{ReCl}_4$  can be prepared as follows:




It is metastable and reactive, and has a structure based on cubic close-packed chlorine atoms. The Re atoms occupy one quarter of the octahedral holes but occur in pairs of adjacent octahedra, forming metal-metal bonds with a Re-Re distance of  $2.73 \text{ \AA}$ .

Many complexes are known.  $[\text{ReCl}_6]^{2-}$  is octahedral, and is obtained by reduction of  $\text{KReO}_4$ :



$[\text{ReCl}_6]^{2-}$  is hydrolysed in water:



The other halide complexes  $[\text{MF}_6]^{2-}$ ,  $[\text{MBr}_6]^{2-}$  and  $[\text{MI}_6]^{2-}$  are made from the hexachloride and the appropriate halogen acid.  $[\text{ReF}_6]^{2-}$  is stable in water. Cyanide complexes are formed by treating  $[\text{MI}_6]^{2-}$  with KCN. Tc forms  $[\text{Tc}^{\text{IV}}(\text{CN})_6]^{2-}$ . Re is oxidized by  $\text{CN}^-$  and forms  $[\text{Re}^{\text{V}}(\text{CN})_8]^{3-}$ . In this complex Re has an oxidation state of (+V) and a coordination number of 8, and the structure is probably dodecahedral.

**(+V) STATE**


Mn(+V) is little known except as the manganate(V) ion  $\text{MnO}_4^{3-}$  (formerly called hypomanganate). This can be obtained as a bright blue salt  $\text{K}_3\text{MnO}_4$  by reducing an aqueous solution of  $\text{KMnO}_4$  with an excess of sodium sulphite. It is not stable, and tends to disproportionate. Tc is reluctant to form the (+V) state, and Re(+V) compounds are readily hydrolysed by water and at the same time they disproportionate




$\text{ReCl}_5$  is dimeric, and has a structure like  $(\text{NbCl}_5)_2$  (Figure 21.2) in which two octahedra are joined by an edge. The Re-Re distance is 3.74 Å, and therefore there is no metal-metal bonding. The oxide  $\text{Re}_2\text{O}_7$  is also known.

**(+VI) STATE**

The only example of Mn(+VI) is the manganate(VI) ion  $\text{MnO}_4^{2-}$ . These compounds are sometimes called manganates, and they are dark green. Manganates are formed by oxidizing  $\text{MnO}_2$  in fused KOH with air,  $\text{KNO}_3$ ,  $\text{PbO}_2$ ,  $\text{NaBiO}_3$  or other oxidizing agents. They can also be obtained by treating  $\text{KMnO}_4$  with alkali




$\text{MnO}_4^{2-}$  is quite strongly oxidizing and is only stable in very strong alkali. In dilute alkali, water or acidic solutions it disproportionates



Re(+VI) is known as the red coloured oxide  $\text{ReO}_3$ , but the existence of  $\text{TcO}_3$  is uncertain. The structure of  $\text{ReO}_3$  is shown in Figure 23.5a and the same structure is adopted by other oxides such as  $\text{WO}_3$ . Each metal is octahedrally surrounded by oxygen atoms. The structure is closely related to the perovskite structure for compounds  $\text{ABO}_3$  by the insertion of a large cation at the centre of the cube as shown in Figure 23.5b.

The halides  $\text{TcF}_6$ ,  $\text{ReF}_6$  and  $\text{ReCl}_6$  are known. The fluorides are made by direct reaction of the elements, and the chloride by treating the fluoride with  $\text{BCl}_3$ . They have a  $d^1$  configuration, and the fluorides are yellow and the chloride is green-black. The magnetic moment is lower than the spin only value for  $d^1$  because of strong spin orbital coupling. The compounds have low melting points ranging from 18°C to 33°C, and they are sensitive to water.


**(+VII) STATE**

Mn(+VII) is not common, but is very well known as the manganate(VII) ion  $\text{MnO}_4^-$ , which is still commonly called the permanganate ion. The



**Figure 23.5** Structures of (a) rhenium trioxide  $\text{ReO}_3$  and (b) perovskite  $\text{ABO}_3$ , e.g.  $\text{CaTiO}_3$ . (From A.F. Wells, *Structural Inorganic Chemistry*, Oxford, Clarendon Press, 1950.)

potassium salt  $\text{KMnO}_4$  is widely used as an oxidizing agent in both preparative and analytical chemistry. Titrations are normally carried out in acidic solutions, and  $\text{MnO}_4^-$  is reduced to  $\text{Mn}^{2+}$ , a change of five electrons.



In alkaline solution  $\text{Mn}^{\text{IV}}\text{O}_2$  is formed, involving a three-electron change.




Thus the reaction which occurs, and hence the stoichiometry, depend on the pH. The purple colour of  $\text{MnO}_4^-$  acts as its own indicator in titrations.

Permanganate solutions are intrinsically unstable in acidic solution, and decompose slowly. Decomposition is catalysed by sunlight, so  $\text{KMnO}_4$  solutions should be stored in dark bottles and they must be standardized frequently.




If a small quantity of  $\text{KMnO}_4$  is added to concentrated  $\text{H}_2\text{SO}_4$ , a green solution containing  $\text{MnO}_3^+$  ions is formed.



With larger amounts of  $\text{KMnO}_4$ , an explosive oil  $\text{Mn}_2\text{O}_7$  is formed. (Do not try this.)

$\text{KMnO}_4$  is manufactured on a large scale:



Permanganates can also be prepared by treating a solution of  $\text{Mn}^{2+}$  ions with very strong oxidizing agents such as  $\text{PbO}_2$  or sodium bismuthate

$\text{NaBiO}_3$ . In qualitative analysis the presence of manganese is confirmed by treating the solution with sodium bismuthate, when the purple colour of  $\text{MnO}_4^-$  is obtained. Permanganites can also be made by acidifying manganates, when they disproportionate into  $\text{MnO}_4^-$  and  $\text{MnO}_2$ , but the yields are not good.

The permanganate ion has an intense purple colour.  $\text{Mn}(+VII)$  has a  $d^0$  configuration, so the colour arises from charge transfer and not from  $d-d$  spectra.

$\text{KMnO}_4$  is used as an oxidizing agent in many organic preparations including the manufacture of saccharin, ascorbic acid (vitamin C), and nicotinic acid (niacin). It is also used for treating drinking water (it oxidizes and thus kills bacteria, but does not leave an unpleasant taste as does  $\text{Cl}_2$ ).

In contrast to the scarcity of  $\text{Mn}(+VII)$  compounds  $\text{Tc}(+VII)$  and  $\text{Re}(+VII)$  occur in several compounds. These include the heptoxides  $\text{M}_2\text{O}_7$ , heptasulphides  $\text{M}_2\text{S}_7$ ,  $\text{MO}_4^-$  ions, oxohalides, a hydride complex  $\text{MH}_3^-$  and  $\text{ReF}_7$ . These are only slightly oxidizing and are relatively stable compounds.

The oxides  $\text{Tc}_2\text{O}_7$  and  $\text{Re}_2\text{O}_7$  are formed when the metals are heated in air or dioxygen. They are both stable yellow solids.  $\text{Tc}_2\text{O}_7$  melts at  $120^\circ\text{C}$  and  $\text{Re}_2\text{O}_7$  at  $220^\circ\text{C}$ , in contrast to  $\text{Mn}_2\text{O}_7$  which is an explosive oil.  $\text{Tc}_2\text{O}_7$  is more oxidizing than  $\text{Re}_2\text{O}_7$ .

Both oxides dissolve in water and form colourless solutions of pertechnic acid  $\text{HTcO}_4$  or perrhenic acid  $\text{HReO}_4$ . A second form of perrhenic acid exists as  $\text{H}_3\text{ReO}_4$  (compare with periodic acid  $\text{HIO}_4$  and  $\text{H}_3\text{IO}_4$ ). The peracids are strong acids, i.e. completely ionized in aqueous solution. The solubilities of perrhenates are similar to those of perchlorates. The ions  $\text{MnO}_4^-$ ,  $\text{TcO}_4^-$  and  $\text{ReO}_4^-$  are all tetrahedral. The  $\text{MnO}_4^-$  ion is a powerful oxidizing agent.  $\text{TcO}_4^-$  and  $\text{ReO}_4^-$  show mild oxidizing properties. The difference is illustrated by their reaction with  $\text{H}_2\text{S}$ .  $\text{KMnO}_4$  oxidizes  $\text{H}_2\text{S}$  to  $\text{S}$ , and is itself reduced to  $\text{Mn}^{2+}$ , whereas  $\text{KTcO}_4$  and  $\text{KReO}_4$  precipitate sulphides  $\text{Tc}_2\text{S}_7$  and  $\text{Re}_2\text{S}_7$ .

Whilst  $\text{MnO}_4^-$  is unstable in alkaline solution,  $\text{TcO}_4^-$  and  $\text{ReO}_4^-$  are stable from bases.

$\text{KMnO}_4$  is a very dark purple-black solid. The  $\text{MnO}_4^-$  ion is deep purple coloured due to charge transfer spectra. In contrast solutions of  $\text{TcO}_4^-$  and  $\text{ReO}_4^-$  are colourless, as the charge transfer band occurs at higher energy in the UV region. However solutions of  $\text{HReO}_4$  become yellow-green when they are concentrated, and  $\text{HTcO}_4$  has been isolated as a red solid. These colours arise because the tetrahedral  $\text{ReO}_4^-$  ion becomes less symmetrical when undissociated  $\text{HO}-\text{ReO}_3$  is formed, and the Raman spectrum of the concentrated solution shows lines due to the acid.

The elements in this group do not form binary hydrides. However, when potassium pertechnetate  $\text{KTcO}_4$  or potassium perrhenate  $\text{KReO}_4$  is treated with potassium in ethylenediamine or ethanolic solution, hydrido complexes  $\text{K}_2[\text{TcH}_9]$  and  $\text{K}_2[\text{ReH}_9]$  are formed. The structure is a tri-capped trigonal prism, that is a trigonal prism with an extra group pointing out of




Figure 23.6 Structure of the enneaahydridorhenium(VII) ion  $[\text{ReH}_9]^{2-}$

each of the three rectangular faces (Figure 23.6). The proton magnetic resonance spectrum of this ion rather surprisingly shows a single sharp line. This suggests that the H atoms are equivalent. This suggests that the H atoms undergo a very rapid intramolecular site exchange.

When Re is heated with fluorine  $\text{ReF}_7$  is formed, but Tc only forms  $\text{TcF}_6$ .  $\text{ReF}_7$  and  $\text{IF}_7$  are the only heptahalides known throughout the periodic table, and both have a pentagonal bipyramid structure. Several oxahalides can be made by treating the oxides with the appropriate halogen, or  $\text{ReF}_7$  with dioxygen or water. These include  $\text{ReOF}_5$ ,  $\text{ReO}_2\text{F}_3$ ,  $\text{ReO}_3\text{F}$ ,  $\text{ReO}_3\text{Cl}$ ,  $\text{TcO}_3\text{F}$  and  $\text{TcO}_3\text{Cl}$ . The oxahalides are all pale yellow or colourless compounds which are either low-melting solids or liquids.

## BIOLOGICAL IMPORTANCE

$\text{Mn}^{II}$  is important in both animal and plant enzymes. In mammals the enzyme arginase is produced in the liver. This is important because it converts nitrogenous waste products into urea in the ornithine–arginine–citrulline cycle (discovered by Hans Krebs who also discovered the tricarboxylic acid cycle). The urea is carried by the blood to the kidneys, where it is excreted in urine.

Mn is an essential trace element for plant growth. It is added to fertilizers in parts of the world where there is a deficiency in the soil. It is essential in a group of enzymes called phosphotransferases.

## FURTHER READING

- Abel, E.W. and Stone, F.G. (1969, 1970) The chemistry of transition metal carbonyls, *Q. Rev. Chem. Soc.*, Part I – Structural considerations, **23**, 325; Part II – Synthesis and reactivity, **24**, 498.
- Canterford, J.H. and Cotton, R. (1968) *Halides of the Second and Third Row Transition Elements*, Wiley, London.
- Canterford, J.H. and Cotton, R. (1969) *Halides of the First Row Transition Elements*, Wiley, London.



- Clarke, M J and Fackler, P H (1982) The chemistry of technetium toward improved diagnostic agents, *Structure and Bonding*, 50, 57-78
- Corbett, J D (1981) Extended metal-metal bonding in halides of the early transition metals, *Acc Chem Res*, 14, 239
- Cotton, F A (1983) Multiple metal-metal bonds, *J Chem Ed*, 60, 713-720
- Cotton, F A (1975) Compounds with multiple metal to metal bonds, *Chem Soc Rev*, 4, 27-53
- Cotton, F A (1978) Discovering and understanding multiple metal to metal bonds *Acc Chem Res*, 11, 225-232
- Cotton, F A and Chisholm, M H (1978) Chemistry of compounds containing metal-metal bonds, *Acc Chem Res*, 11, 356-362
- Diatomic metals and metallic clusters* (Conference papers of the Faraday Symposia of the Royal Society of Chemistry, No 14), Royal Society of Chemistry London
- Emeléus, H J and Sharpe, A G (1973) *Modern Aspects of Inorganic Chemistry*, 4th ed (Chapters 14 and 15 Complexes of Transition Metals, Chapter 20 Carbonyls), Routledge and Kegan Paul, London
- Griffith, W P (1973) *Comprehensive Inorganic Chemistry*, Vol 4 (Chapter 46 Carbonyls, cyanides, isocyanides and nitrosyls), Pergamon Press, Oxford
- Johnson, B F G (ed) (1980) *Transition Metal Clusters*, John Wiley, Chichester
- Kemmitt, R D W (1973) *Comprehensive Inorganic Chemistry*, Vol 3 (Chapter 37 Manganese), Pergamon Press, Oxford
- Levason, W and McAuliffe, C A (1972) Higher oxidation state chemistry of manganese, *Coordination Chem Rev*, 7, 353-384
- Lewis, J and Green, M L (eds) (1983) *Metal Clusters in Chemistry* (Proceedings of the Royal Society Discussion Meeting May 1982), The Society, London
- Peacock, R D (1973) *Comprehensive Inorganic Chemistry*, Vol 3 (Chapter 38 Technetium, Chapter 39 Rhenium), Pergamon Press, Oxford
- Pinkerton, T C *et al* (1985) Bioinorganic activity of technetium radiopharmaceuticals, *J Chem Ed*, 62, 965-973
- Rard, J A (1985) Inorganic aspects of ruthenium chemistry, *Chem Rev*, 81, 1
- Rouschias, G (1974) Recent advances in the chemistry of rhenium, *Chem Rev*, 74, 531-566
- Shriver, D H, Kaesz, H D and Adams, R D (eds) (1990) *Chemistry of Metal Cluster Complexes*, VCH, New York
- Templeton, J L (1979) Metal-metal bonds of order four, *Progr Inorg Chem*, 26, 211-300

# Group 8 – the iron group

24

## IRON, COBALT AND NICKEL GROUPS

Iron	Fe	Cobalt	Co	Nickel	Ni
Ruthenium	Ru	Rhodium	Rh	Palladium	Pd
Osmium	Os	Iridium	Ir	Platinum	Pt

These nine elements made up Group VIII in the old Mendeleev periodic table. They are now treated as Groups 8, 9 and 10 (in vertical groups or *triads*) in the same way as the other transition elements:

Group 8	Group 9	Group 10
Fe	Co	Ni
Ru	Rh	Pd
Os	Ir	Pt

However, the horizontal similarities between these elements are greater than anywhere else in the periodic table except among the lanthanides. As a consequence of the lanthanide contraction, the second and third rows of transition elements are much alike. Because of this, the horizontal similarities are sometimes emphasized by considering these nine elements as two horizontal groups: the three ferrous metals Fe, Co and Ni, and the six platinum metals Ru, Rh, Pd, Os, Ir and Pt.

Fe	Co	Ni
Ru	Rh	Pd
Os	Ir	Pt

## INTRODUCTION TO THE IRON GROUP

Iron is used in larger quantities than any other metal, and steel making is of immense importance throughout the world. Iron is also the most important

Table 24.1 Electronic structures and oxidation states

Element	Electronic structure	Oxidation states*
Fe	[Ar] 3d <sup>6</sup> 4s <sup>2</sup>	0 <b>II</b> <b>III</b> (IV) (V) (VI)
Ru	[Kr] 4d <sup>7</sup> 5s <sup>1</sup>	0 <b>II</b> <b>III</b> <b>IV</b> (V) <b>VI</b> (VII) VIII
Os	[Xe] 4f <sup>14</sup> 5d <sup>6</sup> 6s <sup>2</sup>	0 (I) (II) (III) <b>IV</b> (V) <b>VI</b> (VII) VIII

\* The most important oxidation states (generally the most abundant and stable) are shown in bold. Other well characterized but less important states are shown in normal type. Oxidation states that are unstable or in doubt are given in parentheses.

transition element in plants and animals. Its biological importance is as an electron carrier in plants and animals (cytochromes and ferredoxins), as haemoglobin, the oxygen carrier in the blood of mammals, as myoglobin for oxygen storage, for iron scavenging and storage (ferritin and transferrin) and in nitrogenase (the enzyme in nitrogen fixing bacteria). Iron forms several unusual complexes including ferrocene.

### ABUNDANCE, EXTRACTION AND USES

Iron is the fourth most abundant element in the earth's crust, after O, Si and Al. It makes up 62 000 ppm or 6.2% by weight of the earth's crust where it is the second most abundant metal (Appendix A). In addition iron and nickel make up most of the earth's core.

The chief ores are haematite  $\text{Fe}_2\text{O}_3$ , magnetite  $\text{Fe}_3\text{O}_4$ , limonite  $\text{FeO}(\text{OH})$  and siderite  $\text{FeCO}_3$ . (Smaller amounts of pyrites  $\text{FeS}_2$  are also found. This has a yellow metallic appearance and is called 'fool's gold' because it has been mistaken for gold.) World production of iron ores was 959 million tonnes in 1992. The largest sources are China 22%, the Soviet Union 18%, Brazil 16%, Australia 12%, and the USA and India 6% each. This yielded 497 million tonnes of pig iron in 1992.

Ruthenium and osmium are very rare. They are found in the metallic state together with the platinum metals and the coinage metals (Cu, Ag and Au). The main sources are traces found in the  $\text{NiS}/\text{CuS}$  ores mined in South Africa, Canada (Sudbury, Ontario), and the Soviet Union (the river sand from the Ural mountains). World production of all six platinum group metals was only 281 tonnes in 1992. The largest sources were South Africa 45%, the Soviet Union 44%, Canada 4%, the USA 2% and Japan 0.8%.

Table 24.2 Abundance of the elements in the earth's crust by weight

	ppm	Relative abundance
Fe	62 000	4
Ru	0.0001	77 =
Os	0.005	72

## EXTRACTION OF IRON

The extraction of iron has played a considerable part in the development of modern civilization. The iron age began when man found how to use the charcoal formed by burning wood to extract iron from iron ores, and how to use it to make implements. The industrial revolution began when Abraham Darby developed a process which used coke instead of charcoal at Coalbrookdale in Shropshire, England, in 1773. It is much cheaper and easier to produce coke from coal rather than make charcoal by partly burning wood. Furthermore the greater mechanical strength of coke made it possible to blow air through a mixture of coke and iron ore in a blast furnace and thus extract iron on a much larger scale. These two factors increased the availability of iron and greatly reduced its price. It became possible for the first time to make bridges, ships, steam engines and railway lines using iron. The scale on which iron and steel are produced and their widespread use justify detailed examination of the processes involved.

### Blast furnace

Iron is extracted from its oxides in a blast furnace. This is an almost cylindrical furnace, lined with fire bricks. It runs continuously and works on the counter-current principle. It is charged from the top with iron ore, a reducing agent (coke) and slag forming substances (calcium carbonate). The amount of  $\text{CaCO}_3$  is varied, depending on the amount of silicate materials in the ore. Air is blown in at the bottom. The coke burns producing heat and CO. The temperature of the furnace is nearly  $2000^\circ\text{C}$  at the point where the air enters, but is about  $1500^\circ\text{C}$  at the bottom and  $200^\circ\text{C}$  at the top. The iron oxide is reduced to iron mainly by CO (though perhaps some reduction by C takes place). The molten iron dissolves 3–4% of C from the coke, resulting in the formation of pig iron. The melting point of pure iron is  $1535^\circ\text{C}$ . The impurities in pig iron lower the melting point, possibly to as low as  $1015^\circ\text{C}$  (the eutectic temperature) by the presence of 4.3% C. Molten iron collects in the hearth at the bottom of the blast furnace.

The temperature of the furnace decomposes  $\text{CaCO}_3$  to  $\text{CaO}$ , which then reacts with any silicate impurities present (such as sand or clay), forming calcium silicate or slag. This is also molten and also drips to the bottom. The slag floats on the molten iron, thus protecting it from oxidation. Molten slag and molten iron are drawn off through separate openings at intervals. The molten iron is run into moulds made of sand and is allowed to solidify into ingots called 'pigs'. Pig iron or cast iron is hard but is very brittle.

A small amount of pig iron is remelted and cast into metal parts, but the brittleness makes it almost impossible to machine the metal on a lathe, though it can be shaped by grinding. Pig iron contains up to 4.3% carbon and possibly other impurities such as Si, P, S and Mn. The non-metallic elements must be removed to reduce the brittleness. All Fe/C alloys

*continued overleaf*




Figure 24.1 Diagram of a blast furnace.

containing less than 2% C are called steel. Steel is ductile and can be rolled or machined into shape. The hardness and strength increase with increasing C content. The most common forms are mild steel (otherwise called soft steel or low carbon steel) and hard steel (otherwise called high carbon steel).

The source of the impurities in pig iron are as follows. C arises from the coke used in the blast furnace. Si, P and S arise from the reduction by C of silicates, phosphates or sulphates present in the ore, or from S in the coke. Small amounts of Mn are often found in iron ore, but for most purposes this is beneficial rather than harmful, as small amounts of Mn actually enhance the physical properties of the metal. Typical analyses of pig iron and mild steel are shown in Table 24.3.


The slag is used as a building material, for example to make breeze blocks, or cement.

Table 24.3 Typical impurities that may be present in pig iron and mild steel


	Pig iron (%)	Mild steel (%)
C	3-4.3	0.15
Si	1-2	0.03
P	0.05-2	0.05
S	0.05-1	0.05
Mn	0.5-2	0.5

#### Reactions involved


The overall process for the extraction of Fe is





The reaction proceeds in several stages at different temperatures. Since the air passes through in a few seconds, the individual reactions do not reach equilibrium.



The C is deposited as soot and reduces FeO to Fe, but it also reacts with the refractory lining of the furnace, and is harmful.





A modern blast furnace may be 120 feet (40 metres) high, and 50 feet (15 metres) in diameter at the bottom, and can produce 10000 tonnes of pig iron per day.

## STEEL MAKING

Steel is made by removing most of the C and other impurities from pig iron. The process involves melting, and oxidizing the C, Si, Mn and P in the pig iron so that the impurities are given off as gases or converted into slag.

### Puddling

Originally steel was made by 'puddling', which involved mixing molten pig iron with haematite  $\text{Fe}_3\text{O}_4$ , and burning off all the C and other impurities to give wrought iron. Wrought iron has had all the C removed and is fairly soft, and is extremely malleable. It can be converted into steel by adding the required amount of C or other metals to give the type of steel required, but this process is now entirely obsolete.


### Bessemer and Thomas processes

In 1855 H. Bessemer (a Frenchman living in England) patented the process named after him which uses a Bessemer converter. This is a large pear-shaped furnace lined with silica. The furnace can be tilted and whilst it is in the horizontal position molten pig iron is poured in. It is then tilted to the vertical position and a blast of compressed air is blown through holes in the bottom of the furnace and through the molten metal. This burns the Si and Mn in the pig iron to give first  $\text{SiO}_2$  (then iron silicate) and manganese oxide slag. These reactions produce a lot of heat which leads to stronger oxidation of C to CO or  $\text{CO}_2$ . The course of the reaction can be followed by burning the waste gases and observing the colour or the spectrum of the flame produced. When the C content is sufficiently low, the converter is tipped and the molten steel is poured into cast iron moulds. This gives an ingot of steel, which can be rolled or forged. The process typically takes 20 minutes for a 6 tonne ingot of metal.

Iron ores typically contain either Si or P as impurities, which are oxidized to  $\text{SiO}_2$  or  $\text{P}_4\text{O}_{10}$ . A phosphorus content of over 0.05% in steel

*continued overleaf*

leads to a low tensile strength and cold brittleness. The Bessemer process does not remove phosphorus so satisfactory steel or wrought iron can only be obtained from pig iron containing little or no P. Furthermore the phosphorus damages the lining of the converter, and this can only be replaced by taking the converter out of use



In some countries steel making is based on phosphorus rich ores. In this case the basic Bessemer process (often called the Thomas and Gilchrist process patented by S G Thomas in 1879) is used instead. There are two differences from the normal Bessemer process

- 1 The Thomas converter is lined with a basic material such as calcined (strongly heated) dolomite or limestone. This reduces reaction between the iron phosphate slag and the lining of the converter. This prolongs the life of the converter lining.
- 2 Limestone  $\text{CaCO}_3$  or lime  $\text{CaO}$  are added as slag formers. These are basic and react with  $\text{P}_4\text{O}_{10}$  forming basic slag  $\text{Ca}_3(\text{PO}_4)_2$  thus removing P from the steel. Basic slag is a valuable by product and is finely ground and sold as a phosphate fertilizer.

Thus a Bessemer converter with its silicate lining was used for iron ore containing silicate impurities and Thomas converter lined with limestone or dolomite was used with ores which had a high P content. A small amount of Mn is added to the molten metal to remove S and O. The Bessemer process reduced the price of steel by a factor of 5 in the UK. It was adopted by Andrew Carnegie in the USA and reduced the price by a factor of 10. The process dominated world steel production until World War I and was still used in England until the 1960s.

#### Siemens open hearth process

The open hearth process was invented by Sir William Siemens soon after the Bessemer process was invented. The furnace required external heating by burning gas or oil in air. Molten pig iron was put in a shallow hearth and the impurities were oxidized by air. The lining of the furnace was acidic or basic depending on the impurities in the pig iron. This process replaced the Bessemer process in many places. The open hearth process is slow and it took about 10 hours to convert 350 tonnes. For this reason it has largely been replaced by the basic oxygen process.

#### Siemens electric arc furnace

Siemens also patented an electric arc furnace in 1878. Heat is provided either by having an electric arc just above the metal or by passing an

electric current through the metal. This process is still used to produce steel alloys and other high quality steel. Stainless steel typically contains 12–15% of Ni, but that used for cutlery may contain 20% Cr and 10% Ni. High speed cutting steel used as the cutting edges on lathes may contain 18% W and 5% Cr. Alloys with 0.4–1.6% Mn give steel with a high tensile strength. Hadfield steel, which is very tough and is used for rock breaking machinery and excavators, contains about 13% Mn and 1.25% C. Spring steel contains 2.5% Si.

### Basic oxygen process

The main process nowadays is the more modern *basic oxygen process* (BOP). It originated in 1952 as the Kaldo and LD processes in Austria. One problem with the older Bessemer and Thomas processes was that the molten metal took up small amounts of nitrogen. In concentrations above 0.01% nitrogen makes steel brittle, and nitriding of the surface makes the metal more difficult to weld. The remedy is to use pure  $O_2$  instead of air to oxidize the pig iron. If  $O_2$  was blown through the bottom of the furnace in the same way as air was blown through in the Bessemer process, the bottom of the furnace would melt. The Kaldo and LD processes both use pure  $O_2$ . In the LD process strong convection currents were set up in the melt to obtain an effective reaction, whilst in the Kaldo process the convertor was rotated to ensure mixing and hence an effective reaction. The BOP process is now very widely used. The furnace is initially charged with molten pig iron and lime, and pure  $O_2$  is blown onto the surface of the liquid metal at great speed through retractable water cooled lances. The  $O_2$  penetrates into the melt and oxidizes the impurities rapidly. The heat evolved in oxidizing the impurities keeps the contents of the furnace molten despite the rise in melting point as impurities are removed. No external heat is required. Eventually the furnace is tipped and the molten steel is poured either into moulds to give steel castings, or into ingots, which in turn may be passed to rolling mills. The advantages of using  $O_2$  rather than air are:

1. There is a faster conversion, so a given plant can produce more in a day.
2. Larger quantities can be handled. (A 300 tonnes charge can be converted in 40 minutes compared with 6 tonnes in 20 minutes by the Bessemer process.)
3. It gives a purer product, and the surface is free from nitrides.

Table 24.4 Composition of various steels

%C	name
0.15–0.3	Mild steel
0.3–0.6	Medium steel
0.6–0.8	High-carbon steel
0.8–1.4	Tool steel

continued overleaf



**Phase diagram**

The iron-carbon phase diagram is very complicated and is described under 'Interstitial alloys and related compounds' in Chapter 5. The production of alloys containing small amounts of V, Cr, Mo, W or Mn gives steels with special properties for particular purposes.

**Production figures and uses**

World production of steel ingots and castings was 717 million tonnes in 1992. The largest steel producing countries were the Soviet Union 16%, Japan 14%, the USA 12% and China 11%. The largest use is as mild steel for ship building, girders and motor car bodies. Mild steel is malleable and can be bent or machined. It can also be hardened (tempered) by heating to red heat and quenching (cooling rapidly) by plunging into water or oil. In a year, 14 million tonnes of tin plate, i.e. thin sheets of mild steel electroplated with a very thin protective layer of tin, are used for packaging food and other materials as 'tin cans'. Several ferrous alloys are produced in large amounts: ferrosilicon 3.5 million tonnes/year, ferrochrome 3.1 million tonnes/year, ferromanganese 3.4 million tonnes/year and ferronickel 569 000 tonnes/year.

Promoted iron is used as the catalyst in the Haber-Bosch process for making  $\text{NH}_3$ .

**EXTRACTION OF RUTHENIUM AND OSMIUM**

Ru and Os are obtained from the anode slime which accumulates in the electrolytic refining of Ni. This contains a mixture of the platinum metals together with Ag and Au. The elements Pd, Pt, Ag and Au are dissolved in aqua regia and the residue contains Ru, Os, Rh and Ir. After a complex separation Ru and Os are obtained as powders, and powder forming techniques are used to give the massive metal. These elements are both scarce and expensive. Ru is used to alloy with Pd and Pt, and Os is also used to make hard alloys. All of the platinum metals have specific catalytic properties.

**OXIDATION STATES**

In the previous groups of transition elements (Groups 3-7), the maximum oxidation number was attained when all of the valency electrons in the  $d$  and  $s$  levels were used for valency purposes. If this trend continued then the maximum oxidation number for Group 8 would be (+VIII). However, this trend is not continued in the second half of the  $d$  block and the highest oxidation state for Fe is (+VI). This state is rare and is of little importance.

The main oxidation states for Fe are (+II) and (+III).  $\text{Fe}(+II)$  is the

most stable, and exists in aqueous solution. Fe(+III) is slightly oxidizing, but the Fe(+II) and Fe(+III) states are much closer in stability than has been found in previous groups. In marked contrast the elements Ru and Os form  $\text{RuO}_4$  and  $\text{OsO}_4$  which are in the (+VIII) state. Ru(+III) and Os(+IV) are the most stable states, though Ru(+V), Os(+VI) and Os(+VIII) are also reasonably stable. Thus the usual trend is observed that on descending a group, the higher oxidation states become more stable. The stability of the various oxidation states is shown by the range of oxides and halides which are known (see Table 24.5).

Table 24.5 Oxides and halides

Oxidation states							
(+II)	(+III)	(+IV)	(+V)	(+VI)	(+VII)	(+VIII)	Others
FeO	$\text{Fe}_2\text{O}_3$	—	—	—	—	—	$\text{Fe}_3\text{O}_4$
—	$\text{Ru}_2\text{O}_3^{\text{h}}$	<b><math>\text{RuO}_2</math></b>	—	$(\text{RuO}_3)^{\text{h}}$	—	$\text{RuO}_4$	
—	—	<b><math>\text{OsO}_2</math></b>	—	$(\text{OsO}_3)^{\text{h}}$	—	<b><math>\text{OsO}_4</math></b>	
$\text{FeF}_2$	<b><math>\text{FeF}_3</math></b>	—	—	—	—	—	
$\text{FeCl}_2$	$\text{FeCl}_3$	—	—	—	—	—	
$\text{FeBr}_2$	$\text{FeBr}_3$	—	—	—	—	—	
$\text{FeI}_2$	—	—	—	—	—	—	
—	<b><math>\text{RuF}_3</math></b>	$\text{RuF}_4$	<b><math>\text{RuF}_5</math></b>	$(\text{RuF}_6)$	—	—	
—	<b><math>\text{RuCl}_3</math></b>	$\text{RuCl}_4$	—	—	—	—	
—	<b><math>\text{RuBr}_3</math></b>	—	—	—	—	—	
—	<b><math>\text{RuI}_3</math></b>	—	—	—	—	—	
—	—	<b><math>\text{OsF}_4</math></b>	$\text{OsF}_5$	<b><math>\text{OsF}_6</math></b>	$(\text{OsF}_7)$	—	
—	—	<b><math>\text{OsCl}_4</math></b>	$\text{OsCl}_5$	—	—	—	$\text{OsCl}_3$
—	—	$\text{OsBr}_4$	—	—	—	—	
—	—	$\text{OsI}_4$	—	—	—	—	

The most stable oxidation states are shown in bold, unstable ones in brackets.  
h = hydrous oxide.

## GENERAL PROPERTIES



Pure iron is silvery in colour, is not very hard, and is quite reactive (see Table 24.6). The finely divided metal is pyrophoric. Dry air has little effect on massive Fe, but moist air quite quickly oxidizes the metal to hydrous iron(III) oxide (rust). This forms a non-coherent layer which flakes off, and exposes more metal to attack. Iron dissolves in cold dilute non-oxidizing acids, forming  $\text{Fe}^{2+}$  and liberating hydrogen. If the acid is warm and if air is present some  $\text{Fe}^{3+}$  ions are formed as well as  $\text{Fe}^{2+}$ , whilst oxidizing acids give only  $\text{Fe}^{3+}$ . Strong oxidizing agents such as concentrated  $\text{HNO}_3$  or  $\text{K}_2\text{Cr}_2\text{O}_7$  passivate the metal because of the formation of a protective coat of oxide. If this layer is scratched, the exposed metal is once again vulnerable to chemical attack. Fe is slightly amphoteric. It is not affected by dilute NaOH, but it is attacked by concentrated NaOH.

Table 24 6 Some reactions of Fe, Ru and Os

Reagent	Fe	Ru	Os
O <sub>2</sub>	Fe <sub>3</sub> O <sub>4</sub> at 500°C Fe <sub>2</sub> O <sub>3</sub> at higher temp	RuO <sub>2</sub> at 500°C	OsO <sub>4</sub> at 200°C
S	FeS FeS <sub>2</sub> with excess	RuS <sub>2</sub>	OsS <sub>2</sub>
F <sub>2</sub>	FeF <sub>3</sub>	RuF <sub>5</sub>	OsF <sub>6</sub>
Cl <sub>2</sub>	FeCl <sub>3</sub>	RuCl <sub>3</sub>	OsCl <sub>4</sub>
H <sub>2</sub> O	Rusts slowly Fe <sub>3</sub> O <sub>4</sub> formed at red heat	No reaction	No reaction
Dilute HCl	Fe <sup>2+</sup> + H <sub>2</sub>	No reaction	No reaction
Dilute HNO <sub>3</sub>	Fe <sup>3+</sup> + H <sub>2</sub>	No reaction	No reaction
Aqua regia	Passive	No reaction	OsO <sub>4</sub>

In contrast Ru and Os are noble, and are very resistant to attack by acids. However, Os is oxidized to OsO<sub>4</sub> by aqua regia.

The rusting of iron is a special case of corrosion, and is of great practical importance. The process is very complex, but a simplified explanation is that Fe atoms are converted to Fe<sup>2+</sup> ions and electrons. The electrons move to a more noble metal which may be present as an impurity in the iron, or in contact with it. The electrons discharge H<sup>+</sup> ions present in the water, forming hydrogen, which reacts with atmospheric dioxygen to give water.



The iron becomes positive and forms the anode, and the noble metal serves as the cathode, i.e. small local electrochemical cells are formed in the surface. The Fe<sup>2+</sup> ions are subsequently oxidized to Fe(+III), either FeO·OH, Fe<sub>2</sub>O<sub>3</sub> or Fe<sub>3</sub>O<sub>4</sub>. Since the oxide does not form a coherent protective film, corrosion continues.

To prevent corrosion, O<sub>2</sub>, H<sub>2</sub>O and the impurities must be excluded. In practice Fe is often given a protective coating to exclude the water. Electroplating Fe with a thin layer of Sn is widely used and 14 million tonnes of 'tin plate' were produced in 1991. Other methods include 'hot dipping' the Fe in molten zinc, galvanizing (electroplating with Zn), Sherardizing, and painting with red lead. Another effective treatment is to convert the outer layer of iron into iron phosphate. This may be done by treating with phosphoric acid or acid solutions of Mn(H<sub>2</sub>PO<sub>4</sub>)<sub>2</sub> or Zn(H<sub>2</sub>PO<sub>4</sub>)<sub>2</sub> in the Parkerizing and Bonderizing processes. Alternatively a sacrificial anode may be used which makes the iron the cathode in the electrolytic cell. Ru and Os are noble, and do not react with water.

The effect of the lanthanide contraction is less pronounced in this part of

Table 24.7. Some physical properties

	Covalent radius (Å)	Ionic radius (Å)		Melting point (°C)	Boiling point (°C)	Density (g cm <sup>-3</sup> )	Pauling's electronegativity
		M <sup>2+</sup>	M <sup>3+</sup>				
Fe	1.17	0.78 <sup>h</sup> 0.61 <sup>l</sup>	0.645 <sup>h</sup> 0.55 <sup>l</sup>	1535	2750	7.87	1.8
Ru	1.24	—	0.68	2282	(4050)	12.41	2.2
Os	1.26	—	—	3045	(5025)	22.57	2.2

h = high spin value, l = low spin radius.

the periodic table: hence the similarities between the second and third row elements are not so close as are found in the earlier transition groups (see Table 24.7). The close horizontal similarities in the ferrous metals and in the platinum metals are largely due to the similarity of their atoms and ions in size (e.g. Fe<sup>2+</sup> 0.61 Å (low spin), Co<sup>2+</sup> 0.65 Å (low spin) and Ni<sup>2+</sup> 0.69 Å). Because osmium is only a little larger than ruthenium, it would be expected to have a much higher density and indeed Os is the second most dense element known (density 22.57 g cm<sup>-3</sup>) exceeded only by a small margin by Ir (density 22.61 g cm<sup>-3</sup>) (see Appendix D).

## LOW OXIDATION STATES


The (-II) state is rare, but occurs in the carbonyl ions [Fe(CO)<sub>4</sub>]<sup>2-</sup> and [Ru(CO)<sub>4</sub>]<sup>2-</sup>. The zero-valent state occurs in the carbonyls, which may be mononuclear, e.g. Fe(CO)<sub>5</sub>, Ru(CO)<sub>5</sub> and Os(CO)<sub>5</sub>, dinuclear, e.g. Fe<sub>2</sub>(CO)<sub>9</sub> and Os<sub>2</sub>(CO)<sub>9</sub>, or trinuclear, e.g. Fe<sub>3</sub>(CO)<sub>12</sub>, Ru<sub>3</sub>(CO)<sub>12</sub>, Os<sub>3</sub>(CO)<sub>12</sub> (Figure 24.2).


Fe(CO)<sub>5</sub>, Ru(CO)<sub>5</sub> and Os(CO)<sub>5</sub> are liquids at room temperature. The other carbonyls are volatile solids. Fe(CO)<sub>5</sub> is available commercially. The di- and trinuclear carbonyls contain M—M bonds. Fe<sub>2</sub>(CO)<sub>9</sub> has three bridging CO groups joining the two metal atoms, but in Os<sub>2</sub>(CO)<sub>9</sub> there is probably only one bridging group. Fe<sub>3</sub>(CO)<sub>12</sub> has two CO bridges between one pair of Fe atoms, whilst Os<sub>3</sub>(CO)<sub>12</sub> has no bridging groups. Fe<sub>2</sub>Ru(CO)<sub>12</sub> has the same structure as Fe<sub>3</sub>(CO)<sub>12</sub>, but FeRu<sub>2</sub>(CO)<sub>12</sub> has the same structure as Os<sub>3</sub>(CO)<sub>12</sub>.

Fe(CO)<sub>5</sub> is oxidized quite easily, and the gas forms an explosive mixture with air. These carbonyls react with aqueous alkali or water, forming carbonylate anions:





They undergo substitution reactions with other ligands such as PF<sub>3</sub>, PCl<sub>3</sub>, PPh<sub>3</sub>, AsPh<sub>3</sub> and unsaturated organic molecules such as benzene. In the polynuclear carbonyls the metal-metal bond and the metal cluster are often retained.






**Figure 24 2** Structures of (a)  $\text{Fe}(\text{CO})_5$ , (b)  $\text{Fe}_2(\text{CO})_9$ , (c)  $\text{Fe}_3(\text{CO})_{12}$ , (d) suggested structure of  $\text{Os}_2(\text{CO})_9$  and (e) structure of  $\text{Os}_3(\text{CO})_{12}$  and  $\text{Ru}_3(\text{CO})_{12}$

These carbonyl compounds are used as catalysts in various reactions



Nitrosyl compounds are formed by the action of NO on the dinuclear carbonyls



An unusual derivative  $\text{Ru}_6\text{C}(\text{CO})_{17}$  contains a distorted octahedral cluster of six Ru atoms with a carbon atom at the centre (similar to the arrangement in interstitial metal carbides), but four of the Ru atoms have three terminal CO groups and the remaining two Ru atoms have two terminal CO groups and one bridging CO.


The complex  $[\text{Fe}(\text{H}_2\text{O})_5\text{NO}]^{2+}$  is formed in the 'brown ring' test for nitrates. The colour is due to charge transfer. This complex formally contains Fe(+I) and  $\text{NO}^+$ . Its magnetic moment is approximately 3.9 BM, confirming the presence of three unpaired electrons.

## (+II) STATE

Iron(+II) is one of the most important oxidation states, and salts are often called *ferrous salts*. They are well known as crystalline compounds. Most are pale green and contain the  $[\text{Fe}(\text{H}_2\text{O})_6]^{2+}$  ion, for example  $\text{FeSO}_4 \cdot 7\text{H}_2\text{O}$ ,  $\text{FeCl}_2 \cdot 6\text{H}_2\text{O}$  and  $\text{Fe}(\text{ClO}_4)_2 \cdot 6\text{H}_2\text{O}$ . The  $[\text{Fe}(\text{H}_2\text{O})_6]^{2+}$  ion exists in aqueous solutions. Iron(II) compounds are easily oxidized, and so are difficult to obtain pure. However, the double salt  $\text{FeSO}_4 \cdot (\text{NH}_4)_2\text{SO}_4 \cdot 6\text{H}_2\text{O}$  is used as a standard compound in volumetric analysis for titrations with oxidizing agents such as dichromate, permanganate and ceric solutions.  $\text{FeSO}_4$  and  $\text{H}_2\text{O}_2$  are used as Fenton's reagent for producing hydroxyl radicals and, for example, oxidizing alcohols to aldehydes.

## Oxides

$\overline{\text{FeO}}$  is nonstoichiometric and is metal deficient. It commonly has the formula  $\text{Fe}_{0.95}\text{O}$ . It may be formed as a black powder by strongly heating iron(+II) oxalate  $\text{Fe}^{\text{II}}(\text{COO})_2$  in a vacuum and then quenching to prevent its disproportionation:



$\overline{\text{FeO}}$  dissolves in acids and is completely basic. It has a sodium chloride type of lattice, comprising a cubic close-packed arrangement of  $\text{O}^{2-}$  ions with  $\text{Fe}^{2+}$  ions occupying all (or almost all) of the octahedral holes.  $\text{Fe}(\text{OH})_2$  is precipitated from solutions containing Fe(+II) as a white solid, but it rapidly absorbs  $\text{O}_2$  from the air and turns dark green and then brown. This is because it oxidizes first to a mixture of  $\text{Fe}(\text{OH})_2$  and  $\text{Fe}(\text{OH})_3$ , and then to hydrous  $\text{Fe}_2\text{O}_3 \cdot (\text{H}_2\text{O})_n$ .  $\text{Fe}(\text{OH})_2$  dissolves in acids. It also dissolves in strong solutions of NaOH, giving a blue-green complex  $\text{Na}_4[\text{Fe}(\text{OH})_6]$  which can be crystallized.

## Halides

Iron dissolves in the halogen acids in the absence of air, and from these solutions the hydrated dihalides  $\text{FeF}_2 \cdot 8\text{H}_2\text{O}$  (white),  $\text{FeCl}_2 \cdot 4\text{H}_2\text{O}$  (pale



green) and  $\text{FeBr}_2 \cdot 4\text{H}_2\text{O}$  (pale green) are obtained. Hydrated iron(II) chloride contains the  $[\text{FeCl}_2 \cdot 4\text{H}_2\text{O}]$  octahedral unit in which the two chlorine atoms occupy *trans* positions.

Anhydrous  $\text{FeF}_2$  and  $\text{FeCl}_2$  are made by heating the metal with gaseous  $\text{HF}$  or  $\text{HCl}$ , as heating the elements gives  $\text{FeF}_3$  and  $\text{FeCl}_3$ .  $\text{FeBr}_2$  and  $\text{FeI}_2$  are made by heating the elements. The anhydrous  $\text{Fe}(+II)$  halides react with gaseous  $\text{NH}_3$ , forming salts containing the octahedral complex ion  $[\text{Fe}(\text{NH}_3)_6]^{2+}$ . This complex decomposes in water to give  $\text{Fe}(\text{OH})_2$ .

### Complexes

$\text{Fe}^{2+}$  ions form many complexes. The most important one is haemoglobin (the red pigment in blood) which is discussed later in the section 'Bioinorganic chemistry of iron'. Most of the complexes are octahedral though a few tetrahedral halide complexes  $[\text{FeX}_4]^{2-}$  are formed.

The best known complex is the hexacyanoferrate(II) or ferrocyanide ion  $[\text{Fe}^{II}(\text{CN})_6]^{4-}$ . Potassium hexacyanoferrate(II)  $\text{K}_4[\text{Fe}(\text{CN})_6]^{4-}$  is a yellow coloured solid and can be made by the action of  $\text{CN}^-$  on an iron(II) salt in solution. Potassium ferrocyanide is used to test for iron in solution.  $\text{Fe}^{2+}$  ions give a white precipitate of  $\text{K}_2\text{Fe}^{III}[\text{Fe}^{II}(\text{CN})_6]$ , but  $\text{Fe}^{3+}$  ions give deep blue  $\text{KFe}^{III}[\text{Fe}^{II}(\text{CN})_6]$  known as Prussian blue. A deep blue colour is also produced by  $\text{Fe}^{2+}$  with hexacyanoferrate(III) ions (ferricyanides)  $[\text{Fe}^{III}(\text{CN})_6]^{3-}$ , and this is known as Turnbull's blue  $\text{KFe}^{II}[\text{Fe}^{III}(\text{CN})_6]$ . Both have been used as pigments in ink and paint. Recent X ray work, infrared and Mossbauer spectroscopy have shown that Turnbull's blue is identical to Prussian blue. The intense colour arises from electron transfer between  $\text{Fe}(+II)$  and  $\text{Fe}(+III)$ . The standard reduction potentials show that it is easier to oxidize the  $[\text{Fe}^{II}(\text{CN})_6]^{4-}$  ion in aqueous solution to  $[\text{Fe}^{III}(\text{CN})_6]^{3-}$ , than it is to oxidize  $[\text{Fe}^{II}(\text{H}_2\text{O})_6]^{2+}$  to  $[\text{Fe}^{III}(\text{H}_2\text{O})_6]^{3+}$ .





This means that  $\text{Fe}(+III)$  forms a more stable complex with  $\text{CN}^-$  than does  $\text{Fe}(+II)$ . This is surprising since  $\text{CN}^-$  forms  $\pi$  bonds by accepting electrons from metal ions.  $\text{Fe}(+II)$  has more electrons than  $\text{Fe}(+III)$ , so it follows that  $\text{Fe}(+II)$  should have stronger  $\pi$  bonding and hence shorter bonds than  $\text{Fe}(+III)$ . The  $\text{Fe}-\text{C}$  bond lengths of  $1.95 \text{ \AA}$  in  $[\text{Fe}^{III}(\text{CN})_6]^{3-}$  and  $1.92 \text{ \AA}$  in  $[\text{Fe}^{II}(\text{CN})_6]^{4-}$  confirm this. Thermodynamic data show that  $\Delta H^\circ$  for the oxidation of  $[\text{Fe}^{II}(\text{CN})_6]^{4-}$  is more positive than for the oxidation of  $[\text{Fe}^{II}(\text{H}_2\text{O})_6]^{2+}$ , and the reason why the observed  $E^\circ$  values (and the  $\Delta G$  values) are different is largely due to the large negative entropy of hydration resulting from the high charge on  $[\text{Fe}^{II}(\text{CN})_6]^{4-}$ . This shows that the solvent plays an important role, and behaviour in the solid and solution are not always the same.


$\text{Cu}^{2+}$  ions may be precipitated from solution as the red-brown complex  $\text{Cu}_2^{II}[\text{Fe}(\text{CN})_6]$  in gravimetric analysis.

The cyanide groups in  $\text{K}_4[\text{Fe}(\text{CN})_6]$  are kinetically inert, and are not

easily removed or substituted. Though the salt is said not to be poisonous, care must be taken as it evolves HCN with dilute acids. It is possible to obtain mono-substitution products by replacing one  $\text{CN}^-$  by  $\text{H}_2\text{O}$ ,  $\text{CO}$ ,  $\text{NO}_2^-$  or  $\text{NO}^+$ . The best known is sodium nitrosopentacyanoferrate(II)  $\text{Na}_2[\text{Fe}(\text{CN})_5(\text{NO})] \cdot 2\text{H}_2\text{O}$ , which is usually called sodium nitroprusside. This complex has  $\text{NO}^+$  as a ligand, and is formed as brown-red crystals by reacting a hexacyanoferrate(II) with either 30%  $\text{HNO}_3$  or with a nitrite:



Sodium nitroprusside reacts with sulphide ions to give a purple complex  $[\text{Fe}(\text{CN})_5(\text{NOS})]^{4-}$ . This is used as a sensitive qualitative test for sulphides.



Other stable complexes are formed with bidentate ligands such as ethylenediamine, 2,2'-dipyridyl and 1,10-phenanthroline (formerly called *ortho*-phenanthroline (Figure 24.3). The latter complex  $[\text{Fe}^{\text{II}}(\text{phen})_3]^{2+}$  is bright red, and is used for the colorimetric determination of iron, and also as the redox indicator 'ferroin' in titrations. It is easier to oxidize  $[\text{Fe}(\text{H}_2\text{O})_6]^{2+}$  to  $[\text{Fe}(\text{H}_2\text{O})_6]^{3+}$  than it is to oxidize  $[\text{Fe}(\text{phen})_3]^{2+}$  (red colour) to  $[\text{Fe}(\text{phen})_3]^{3+}$  (blue colour). Thus the red colour persists until there is excess oxidizing agent present. The greater stability of the iron(II) phenanthroline complex is due to  $\pi$  bonding between the metal and low energy  $\pi^*$  antibonding orbitals on the ligand. Similar stabilization also occurs in the dipyridyl complex.




Figure 24.3 1,10-phenanthroline.

$\text{Fe}^{2+}$  has a  $d^6$  electronic configuration, and octahedral complexes with weak field ligands have a high-spin arrangement with four unpaired electrons (Figure 24.4a). Strong field ligands such as  $\text{CN}^-$  and 1,10-phenanthroline cause spin pairing. This makes them more stable because they have a larger crystal field stabilization energy (Figure 24.4b). Spin pairing also results in the complexes being diamagnetic.

The brown ring test for nitrates and nitrites depends on forming a brown complex  $[\text{Fe}(\text{H}_2\text{O})_5 \cdot \text{NO}]^{2+}$ . In this test a freshly prepared solution of  $\text{FeSO}_4$  is mixed with the solution containing  $\text{NO}_2^-$  or  $\text{NO}_3^-$  ions in a test tube. Concentrated  $\text{H}_2\text{SO}_4$  is run down the side of the tube so that the acid forms a layer at the bottom. The  $\text{H}_2\text{SO}_4$  reacts with  $\text{NO}_3^-$ , forming  $\text{NO}$ , which combines with  $\text{Fe}^{2+}$ , slowly forming the brown complex  $[\text{Fe}(\text{H}_2\text{O})_5 \cdot \text{NO}]^{2+}$  at the interface between the two liquids. If the mixture gets hot or is shaken the brown colour disappears,  $\text{NO}$  is evolved and a yellow solution






Figure 24.4 Electronic arrangements of the  $d^6$  ion  $\text{Fe}^{2+}$

of  $\text{Fe}^{III}_2(\text{SO}_4)_3$  remains. Nitrites give the brown colour before  $\text{H}_2\text{SO}_4$  is added.

In addition to these octahedral complexes, the heavier halides form crystalline complexes  $[\text{Fe}^{II}\text{X}_4]^{2-}$ . These are tetrahedral complexes and are formed only with large cations. The presence of a large anion and a large cation gives a high lattice energy.

There are few simple compounds of  $\text{Ru}(+II)$  and  $\text{Os}(+II)$ , though  $[\text{Ru}^{II}(\text{H}_2\text{O})_6]^{2+}$  is known. Except in the presence of non-complexing anions such as  $\text{BF}_4^-$  and  $\text{ClO}_4^-$ , the  $(+II)$  state exists as complexes. A large number of complexes are formed with ligands capable of back bonding, such as  $\text{CO}$  and phosphine ligands  $\text{PR}_3$ . Other complexes are formed with  $\text{CN}^-$ ,  $\text{Cl}^-$ ,  $\text{NH}_3$  and amines. These are all tetrahedral. These complexes are formed by reducing solutions containing  $\text{M}(+III)$  or  $\text{M}(+IV)$  in the presence of the ligand. The metal has a  $d^6$  configuration, and the complexes are all diamagnetic, indicating a spin paired arrangement, with a large crystal field stabilization energy.

Ruthenium forms a binuclear carboxylate  $\text{Ru}_2(\text{CH}_3\text{COO})_4(\text{H}_2\text{O})_2$  similar to chromium(II) acetate and containing a  $\text{M}-\text{M}$  bond. Similar complexes are also formed by  $\text{Mo}$  and  $\text{Rh}$ .


Ruthenium also forms an interesting series of complexes  $\text{Ru}^{II}\text{NO L}_5$ , where the ligand  $\text{L}$  may be  $\text{Cl}^-$ ,  $\text{NH}_3$ ,  $\text{H}_2\text{O}$ ,  $\text{NO}^-$ ,  $\text{OH}^-$ ,  $\text{CN}^-$  and many others. The  $\text{NO}$  is strongly bonded to the metal by  $\sigma$  and  $\pi$  bonds, and the  $\text{Ru}-\text{NO}$  bond persists through a wide variety of substitution and oxidation-reduction reactions. X-ray studies show that in some of the complexes the  $\text{Ru}-\text{N}-\text{O}$  atoms are linear, whilst in others they are bent.




Similar osmium complexes are known, though they have been studied less.

Carbonyl complexes of  $\text{Fe}$ ,  $\text{Ru}$  and  $\text{Os}$  have been known for a long time.  $\text{CO}$  and  $\text{N}_2$  are isoelectronic, and for a long time it was speculated that  $\text{M}-\text{NN}$  bonds might be formed analogous to  $\text{M}-\text{CO}$ . The first example of a dinitrogen complex  $[\text{Ru}(\text{NH}_3)_5\text{N}_2]\text{Cl}_2$  was reported in 1965. The


complex can be made by reducing an aqueous solution of  $\text{RuCl}_3$  with hydrazine sulphate or by treating  $[\text{Ru}^{\text{III}}(\text{NH}_3)_5 \cdot \text{H}_2\text{O}]^{3+}$  with  $\text{NaN}_3$ . The reaction where  $\text{H}_2\text{O}$  is replaced directly by  $\text{N}_2$  is of greatest interest, since this might be closer to how bacteria fix atmospheric dinitrogen.



Terminal  $\text{N}_2$  ligands have a strong IR band in the range  $1930\text{--}2230\text{ cm}^{-1}$ . This compares with a band at  $2331\text{ cm}^{-1}$  in  $\text{N}_2$  gas. The IR band may be used to show that a dinitrogen complex has been formed, and the lowering of the wavenumber shows  $\pi$  bonding has occurred from Ru to N, thus reducing the N—N bond order. Thus  $\text{N}_2$  is acting as a  $\pi$  acceptor ligand.  $\text{N}_2$  is a weaker  $\sigma$  donor and a weaker  $\pi$  acceptor than CO, and hence dinitrogen complexes are not very stable. Complexes of other metals including Mo, Fe and Co can also take up  $\text{N}_2$  at atmospheric pressure, particularly with tertiary phosphine ligands:



The  $\text{N}_2$  ligand may also act as a bridging group:



In the dinuclear complex the N—N bond is  $1.24\text{ \AA}$ , only slightly longer than the distance of  $1.098\text{ \AA}$  in  $\text{N}_2$ . The interest in complexes which can coordinate dinitrogen arises from the possibility of dinitrogen fixation (see also Chapter 20). Dinitrogen complexes have also been made for all of the metals in Groups 7, 8 and 9 (Mn, Fe and Co groups), together with Mo and Ni. The complexes typically contain the metal in a low oxidation state, often with phosphine or hydride ligands such as  $(\text{R}_3\text{P})_2\text{Ni} \cdot \text{N}_2 \cdot \text{Ni}(\text{PR}_3)_2$  and  $(\text{R}_3\text{P})_3 \cdot \text{Fe} \cdot \text{N}_2 \cdot \text{H}_2$ . Since the  $\text{N}_2$  molecule is symmetrical and has zero dipole moment,  $\sigma$  bonding from N to the metal will be very slight (hence the very small change in N—N bond length), and back bonding from the metal to  $\pi$  orbitals on the nitrogen is the main interaction.

### (+III) STATE

$\text{Fe}(+\text{III})$  is a very important oxidation state. Salts are often called ferric salts, and are obtained by oxidizing the corresponding  $\text{Fe}(+\text{II})$  salts.  $\text{Fe}(+\text{III})$  solutions are frequently yellow–brown, but the colour is due to the presence of colloidal iron oxide, or  $\text{FeO} \cdot \text{OH}$ .  $\text{Fe}(+\text{III})$  forms crystalline salts with all the common anions except  $\text{I}^-$ , and many of the salts exist in both anhydrous and hydrated forms. These have a variety of colours:  $\text{FeCl}_3 \cdot 6\text{H}_2\text{O}$ ,  $\text{FeF}_3 \cdot 4\frac{1}{2}\text{H}_2\text{O}$  and  $\text{Fe}_2(\text{SO}_4)_3 \cdot 9\text{H}_2\text{O}$  are yellow;  $\text{FeBr}_3 \cdot 6\text{H}_2\text{O}$  and  $\text{FeF}_3$  are green;  $\text{Fe}(\text{NO}_3)_3 \cdot 6\text{H}_2\text{O}$  is colourless; and  $\text{Fe}(\text{NO}_3)_3 \cdot 9\text{H}_2\text{O}$  is pale purple. Several salts contain the  $[\text{Fe}(\text{H}_2\text{O})_6]^{3+}$  ion. The most common is  $\text{Fe}_2(\text{SO}_4)_3$ . This exists as six different hydrates, and is quite widely used as a coagulant to clarify drinking water and also in the

treatment of industrial effluent and sewage. The alums are double salts, and crystallize easily. They also contain  $[\text{Fe}(\text{H}_2\text{O})_6]^{3+}$ . The best known are ammonium ferric alum  $(\text{NH}_4)[\text{Fe}^{III}(\text{H}_2\text{O})_6][\text{SO}_4]_2 \cdot 6\text{H}_2\text{O}$  and potash alum  $[\text{K}(\text{H}_2\text{O})_6][\text{Fe}^{III}(\text{H}_2\text{O})_6][\text{SO}_4]_2$ . Like the chrome alums, these are used as mordants in the dyeing industry.


### Oxides and hydrated oxides

There is no evidence that  $\text{Fe}(\text{OH})_3$  exists. Hydrolysis of  $\text{FeCl}_3$  does not give the hydroxide but gives a red-brown gelatinous precipitate of the hydrous oxide  $\text{Fe}_2\text{O}_3(\text{H}_2\text{O})_n$ . At least part of this precipitate consists of  $\text{FeO} \cdot \text{OH}$ . Heating the hydrous oxide to  $200^\circ\text{C}$  gives red-brown  $\alpha\text{-Fe}_2\text{O}_3$ . The structure comprises a hexagonally close packed lattice of  $\text{O}^{2-}$  ions with  $\text{Fe}^{3+}$  ions in two thirds of the octahedral holes. However, if  $\text{Fe}_2\text{O}_3$  is oxidized,  $\gamma\text{-Fe}_2\text{O}_3$  is formed, which has a cubic close-packed arrangement of  $\text{O}^{2-}$  ions with  $\text{Fe}^{3+}$  ions randomly distributed in both the octahedral and tetrahedral sites.


$\text{Fe}_3\text{O}_4$  is formed as a black solid by igniting  $\text{Fe}_2\text{O}_3$  at  $1400^\circ\text{C}$ .  $\text{Fe}_3\text{O}_4$  is a mixed oxide  $\text{Fe}^{II}\text{Fe}_2^{III}\text{O}_4$  and has an inverse spinel structure. The  $\text{O}^{2-}$  ions are cubic close-packed, with the larger  $\text{Fe}^{2+}$  in one quarter of the octahedral holes. Half of the  $\text{Fe}^{3+}$  occupy octahedral holes and half occupy tetrahedral holes.

$\text{Fe}_2\text{O}_3$  and  $\text{Fe}_3\text{O}_4$ , like  $\text{FeO}$ , all tend to be nonstoichiometric. The nonstoichiometry is related to their similarity in structure. The cubic close packed forms differ only in the arrangement of  $\text{Fe}^{2+}$  and  $\text{Fe}^{3+}$  in the octahedral and tetrahedral holes.

Basic properties decrease with increased oxidation number.  $\text{Fe}^{III}_2\text{O}_3$  is largely basic. The ignited form is difficult to dissolve in acids. However, the freshly precipitated hydrous form dissolves in acids, giving the very pale violet  $[\text{Fe}(\text{H}_2\text{O})_6]^{3+}$  ion, and in concentrated  $\text{NaOH}$ , forming  $[\text{Fe}(\text{OH})_4]^{3-}$ . This shows that the oxide is slightly amphoteric. Fusion with  $\text{LiOH}$ ,  $\text{NaOH}$  or  $\text{Na}_2\text{CO}_3$  gives  $\text{LiFeO}_2$  or  $\text{NaFeO}_2$ .



At one time these compounds were called ferrites, but they are better represented as mixed oxides, as  $\text{LiFeO}_2$  has a  $\text{NaCl}$  structure, and  $\text{Li}^+$  and  $\text{Fe}^{3+}$  are approximately the same size. The average charge on the metal ions is +2, which matches the charge of -2 on the oxide ions. Ferrites hydrolyse with water, forming  $\text{NaOH}$ . At one time this was used in the obsolete Lowig process for manufacturing caustic soda.






If  $\text{Cl}_2$  is passed into an alkaline solution of hydrated iron(III) oxide, a red-purple solution is formed containing the ferrate ion  $\text{Fe}^{VI}\text{O}_4^{2-}$ . Ferrates are also made by oxidizing  $\text{Fe}^{(III)}$  with  $\text{NaOCl}$  or electrolytically. They contain  $\text{Fe}^{(VI)}$  and are stronger oxidizing agents than is  $\text{KMnO}_4$ .

## Halides

The halides  $\text{FeF}_3$ ,  $\text{FeCl}_3$  and  $\text{FeBr}_3$  can all be made by direct reaction of halogen and metal. The iodide does not exist in a pure state because  $\text{Fe}^{3+}$  oxidizes  $\text{I}^-$ . In solution this oxidation is complete but some  $\text{FeI}_3$  may exist with  $\text{FeI}_2$  in the solid.  $\text{Fe}(+III)$  compounds are less ionized than those of  $\text{Fe}(+II)$ .  $\text{FeF}_3$  is a white solid. It is sparingly soluble in water but the solution does not give a positive test for  $\text{Fe}^{3+}$  or  $\text{F}^-$  ions. It combines with alkali metal fluorides, forming complexes, e.g.  $\text{Na}_3[\text{FeF}_6]$ .  $\text{Fe}^{3+}$  has a  $d^5$  configuration. Since  $\text{F}^-$  is a weak field ligand, each of the  $d$  orbitals will be singly occupied, giving a high-spin octahedral complex (Figure 24.5a). As a result of the small size of  $\text{Fe}^{3+}$ ,  $\text{Fe}(+III)$  complexes are generally more stable than those of  $\text{Fe}(+II)$ .

Any  $d-d$  electronic transition breaks the Laporte selection rule. (This states that  $\Delta l$ , the change in the secondary quantum number for the transition, must be  $\pm 1$ . For a  $d-d$  transition  $\Delta l = 0$ .) In  $[\text{FeF}_6]^{3-}$  the electronic transition is 'spin forbidden' too, as it involves both promoting an electron and reversing its spin. There is only a low probability of doing this: hence the lack of colour. A similar effect is observed with  $\text{Mn}^{2+}$  spectra (see also Chapter 32).




In contrast to the absence of colour in  $\text{FeF}_3$ ,  $\text{FeCl}_3$  solid is almost black. It sublimes at about  $300^\circ\text{C}$ , giving a dimeric gas.  $\text{FeBr}_3$  is red-brown. The colours arise from charge transfer spectra. The solid structures are layer lattices, consisting of close-packed halide ions with  $\text{Fe}^{3+}$  occupying two thirds of the octahedral holes in one layer, and none in the next layer.  $\text{FeCl}_3$  dissolves in both ether and water, giving solvated monomeric species (Figure 24.6). Iron(III) chloride is usually obtained as yellow-brown lumps of the hydrate  $\text{FeCl}_3 \cdot 6\text{H}_2\text{O}$ . This is very soluble in water and is used both as an oxidizing agent, and as a mordant in dyeing.  $\text{FeCl}_3$  is also used in the manufacture of  $\text{CCl}_4$ .



(a) weak ligand high spin

(b) strong ligand spin paired

Figure 24.5  $d^5$  electronic arrangement for  $\text{Fe}^{3+}$


(a)  $(\text{FeCl}_3)_2$  gas dimer(b) solvated  $\text{FeCl}_3$ (c) hydrated  $\text{FeCl}_3$   
( $\text{FeCl}_3 \cdot 6\text{H}_2\text{O}$ )Figure 24.6 Structures of  $\text{FeCl}_3$ 

The structure of  $\text{FeCl}_3 \cdot 6\text{H}_2\text{O}$  is unusual. It normally consists of *trans*  $[\text{Fe}(\text{H}_2\text{O})_4\text{Cl}_2]\text{Cl} \cdot 2\text{H}_2\text{O}$ , though in strong  $\text{HCl}$  it forms tetrahedral  $[\text{FeCl}_4]^-$  ions.


### Complexes

$\text{Fe}^{3+}$  shows a preference for forming complexes with ligands which coordinate through O as opposed to N. Complexes with  $\text{NH}_3$  are unstable in water. Complexes with chelating N ligands such as dipyridyl and 1,10-phenanthroline are formed, but are less stable than their  $\text{Fe}(\text{+II})$  counterparts. These ligands cause spin pairing.

The most common complex is the hydrated ion  $[\text{Fe}(\text{H}_2\text{O})_6]^{3+}$ . This is pale purple in very strongly acid solutions, and tends to hydrolyse to yellow solutions at pH 2–3.



At pH 4–5 the hydroxo species polymerizes to form a dimer which forms a brownish solid. Polymerization of aqua ions is quite common, especially if they have a high charge.



At even higher pH values a reddish brown precipitate of the hydrous oxide is formed.

Other complexes with O donors include those with phosphate ions giving  $[\text{Fe}(\text{PO}_4)_3]^{6-}$  and  $[\text{Fe}(\text{HPO}_4)_3]^{3-}$  (which are colourless), and with oxalate ions giving the dark green complex  $[\text{Fe}(\text{oxalate})_3]^{3-}$ . Rust stains can be removed from fabric by treating with oxalic acid and forming the  $[\text{Fe}(\text{oxalate})_3]^{3-}$  ion which is soluble in water. This treatment may also remove dyes from the fabric.  $[\text{Fe}(\text{acetylacetonate})_3]$  is red.  $[\text{Fe}(\text{CN})_6]^{3-}$  is red and  $[\text{Fe}(\text{phen})_3]^{3+}$  is blue, and both can be obtained by oxidizing the corresponding  $\text{Fe}(\text{+II})$  complex with  $\text{KMnO}_4$ , or by electrolysis.

One of the best tests for  $\text{Fe}(\text{+III})$  is to mix aqueous solutions containing  $\text{Fe}^{3+}$  and  $\text{SCN}^-$  ions. A blood red colour is produced, which is due to a

mixture of  $[\text{Fe}(\text{SCN})(\text{H}_2\text{O})_5]^{2+}$  and also some  $\text{Fe}(\text{SCN})_3$  and  $[\text{Fe}(\text{SCN})_4]^-$ . The colour may also be used for the estimation of iron(III). This colour is destroyed by the addition of  $\text{F}^-$  ions, because  $[\text{FeF}_6]^{3-}$  is formed.

$\text{Fe}^{3+}$  has a  $d^5$  electronic configuration. Thus complexes with weak field ligands will have a high-spin arrangement with five unpaired electrons. Thus  $d-d$  spectra will be 'spin forbidden': hence the absorption will be very weak.  $\text{Mn}^{2+}$  also has a  $d^5$  electronic arrangement and also has very weak  $d-d$  spectra. However,  $\text{Fe}^{(+III)}$  has an extra charge and is more able to polarize the ligands, thus giving intense charge transfer spectra not found in  $\text{Mn}^{2+}$ . The only complex which actually shows the weak  $d-d$  bands is  $[\text{Fe}(\text{H}_2\text{O})_6]^{3+}$ . The hydrolysed species have charge transfer bands which mask the  $d-d$  spectra. Strong field ligands such as  $\text{CN}^-$ ,  $\text{SCN}^-$  and oxalate form complexes with  $\text{Fe}^{3+}$  which have a spin paired arrangement (Figure 24.5b). These would be expected to show reasonably intense colours from  $d-d$  spectra, but these colours too are masked by charge transfer.

$\text{Fe}^{(+III)}$  and  $\text{Ru}^{(+III)}$  form basic acetates of the type  $[\text{Fe}_3\text{O}(\text{CH}_3\text{COO})_6\text{L}_3]^+$ . The structure consists of a triangle of three Fe atoms with an O atom at the centre. The six acetate groups act as bridges between the Fe atoms, two groups across each edge of the triangle. Thus each Fe atom is linked to four acetate groups and the central O, and the sixth position of the octahedron is occupied by water or another ligand. This type of carboxylate complex is formed by the trivalent ions of Cr, Mn, Fe, Ru, Rh and Ir.

### Ruthenium and osmium

In the (+III) state, Ru complexes are more numerous than those of Os. Both elements form  $[\text{M}^{III}(\text{NH}_3)_6]^{3+}$ , and Ru forms a range of mixed halogen-ammonia complexes. If  $\text{RuO}_4$  is added to concentrated  $\text{HCl}$  and evaporated, a dark red material formulated  $\text{RuCl}_3 \cdot 3\text{H}_2\text{O}$  is formed. This is readily soluble in water, and is the starting point of many preparations. It seems to contain not only  $\text{Ru}^{III}$  species but also some polynuclear  $\text{Ru}^{IV}$  species.  $\text{Ru}^{(+III)}$  chloro species catalyse the hydration of alkynes.  $\text{Ru}^{(+III)}$  forms a basic acetate similar to  $[\text{Fe}_3\text{O}(\text{CH}_3\text{COO})_6\text{L}_3]^+$  described above.

### (+IV) AND HIGHER STATES

Burning Ru or Os metals in air gives  $\text{RuO}_2$  as a blue-black solid and  $\text{OsO}_2$  as a coppery coloured solid. Both oxides have rutile ( $\text{TiO}_2$ ) structures. Os forms a stable tetrafluoride and tetrachloride.

### (+V) STATE

The (+V) state is unstable, and is found only as the pentafluorides, which are tetrameric with bridging F groups as in  $\text{NbF}_5$  and  $\text{TaF}_5$  (see Figure 21.1). Fluoride complexes are also known.





Figure 24.7 Structure of  $[\text{Fe}_3\text{O}(\text{CH}_3\text{COO})_6(\text{H}_2\text{O})_3]^+$




### (+VI) STATE

Ferrates  $\text{Fe}^{\text{VI}}\text{O}_4^{2-}$  can be made by passing  $\text{Cl}_2$  into an alkaline solution of hydrated iron(III) oxide, by oxidizing  $\text{Fe}(+\text{III})$  with  $\text{NaOCl}$ , or electrolytically. They contain  $\text{Fe}(+\text{VI})$ , are purple coloured and are stronger oxidizing agents than  $\text{KMnO}_4$ . The stability of the (+VI) state decreases across the periodic table



Ferrates are only stable in strongly alkaline solution, and decompose in water or acid, liberating dioxygen





Sodium and potassium ferrates are very soluble, but  $\text{BaFeO}_4$  is precipitated. The ferrate ion is tetrahedral like the chromate ion  $\text{CrO}_4^{2-}$ .


$\text{RuF}_6$  is the highest halide of Ru. It is made by heating the elements and quenching (i.e. cooling very rapidly).  $\text{RuF}_6$  is unstable, but in contrast  $\text{OsF}_6$  is stable.

### (+VIII) STATE

$\text{RuO}_4$  and  $\text{OsO}_4$  are yellow coloured volatile solids with melting points of  $25^\circ\text{C}$  and  $40^\circ\text{C}$  respectively.  $\text{OsO}_4$  is made either by burning finely divided metal in  $\text{O}_2$ , or by treating it with concentrated  $\text{HNO}_3$ .  $\text{RuO}_4$  is less stable and is formed by oxidation with permanganate or bromate in  $\text{H}_2\text{SO}_4$ . Both oxides are toxic, smell like ozone and are strongly oxidizing. They have tetrahedral structures. Both are slightly soluble in water but very soluble in  $\text{CCl}_4$ . Aqueous solutions of  $\text{OsO}_4$  are used as a biological stain because the organic matter reduces it to black  $\text{OsO}_2$  or  $\text{Os}$ .  $\text{OsO}_4$  vapour is harmful to the eyes for this reason.  $\text{OsO}_4$  is used in organic chemistry to add to double bonds and give *cis* glycols. The tetroxides do not show basic properties and  $\text{HCl}$  reduces  $\text{OsO}_4$  to *trans*  $[\text{Os}^{\text{VI}}\text{O}_2\text{Cl}_4]^{2-}$ ,  $[\text{Os}^{\text{IV}}\text{Cl}_6]^{2-}$  and  $[\text{Os}^{\text{IV}}_2\text{OCl}_{10}]^{2-}$ .  $\text{RuO}_4$  dissolves in  $\text{NaOH}$  solutions and liberates  $\text{O}_2$ .  $\text{Ru}(+\text{VIII})$  is reduced forming first the perruthenate (+VII) ion, then the ruthenate (+VI) ion



The ruthenate ion contains  $\text{Ru}(+\text{VI})$  and is analogous to the ferrate ion  $\text{FeO}_4^{2-}$ .  $\text{OsO}_4$  is more stable and is not reduced by  $\text{NaOH}$ . Instead,  $\text{OH}^-$  ligands are added forming the octahedral *trans*-osmate(VIII) ion



The osmate(VIII) ion reacts with  $\text{NH}_3$  giving an unusual nitrido complex  $[\text{OsO}_3\text{N}]^-$ , and is reduced by  $\text{EtOH}$  to form *trans*- $[\text{Os}^{\text{VI}}\text{O}_2(\text{OH})_4]^{2-}$

## BIOINORGANIC CHEMISTRY OF IRON

Iron is essential in small amounts for both plant and animal life. However, like Cu and Se it is toxic in larger quantities. Biologically iron is the most important transition element. It is involved in several different processes:

1. As an oxygen carrier in the blood of mammals, birds and fish (haemoglobin).
2. For oxygen storage in muscle tissue (myoglobin).
3. As an electron carrier in plants, animals and bacteria (cytochromes) and for electron transfer in plants and bacteria (ferredoxins).
4. For storage and scavenging of Fe in animals (ferretin and transferrin).
5. As nitrogenase (the enzyme in dinitrogen fixing bacteria).
6. As a number of other enzymes: aldehyde oxidase (oxidation of aldehydes), catalase and peroxidase (decomposition of  $\text{H}_2\text{O}_2$ ) and succinic dehydrogenase (the aerobic oxidation of carbohydrates).

### Haemoglobin

The human body contains about 4 g of iron. About 70% of this is found as haemoglobin, the red pigment in the erythrocytes (red blood cells). Most of the rest is stored as ferretin. The function of haemoglobin is to pick up dioxygen at the lungs. The arteries carry blood to parts of the body where oxygen is required such as the muscles. Here the oxygen is transferred to a myoglobin molecule, and stored until the oxygen is required to release energy from glucose sugar. When  $\text{O}_2$  is removed from haemoglobin, it is replaced by a water molecule. Next the protein part of haemoglobin absorbs  $\text{H}^+$ . Indirectly this helps remove  $\text{CO}_2$  from the tissues, since  $\text{CO}_2$  is converted to  $\text{HCO}_3^-$  and  $\text{H}^+$ . The blood removes the more soluble  $\text{HCO}_3^-$  ions and the reduced haemoglobin removes the  $\text{H}^+$ . The blood returns to the heart through the veins. It is then pumped to the lungs, where the  $\text{HCO}_3^-$  ions are converted back to  $\text{CO}_2$ . This is excreted into the air in the lungs and exhaled. The blood picks up dioxygen again, and the process is repeated.

The important factor in haemoglobin acting as an oxygen carrier is the reversibility of the process. If too stable a complex were formed with dioxygen, then too much energy would be released in the lungs leaving less energy when dioxygen is released in the muscles. The oxygenated form is called *oxyhaemoglobin* and the reduced form is called *deoxyhaemoglobin*. This transfer of  $\text{O}_2$  is remarkable because it involves only  $\text{Fe}(+II)$ , and not  $\text{Fe}(+III)$ . Other groups such as  $\text{CO}$ ,  $\text{CN}^-$  and  $\text{PF}_3$  can occupy the  $\text{O}_2$  site. Coordination is still reversible, but is much stronger. In the case of  $\text{CN}^-$ , coordination is irreversible. These ligands reduce or prevent oxygen transfer and may result in death. However,  $\text{CN}^-$  also interferes with the



cytochrome enzyme system, which is the principal reason for its extreme toxicity

Haemoglobin has a molecular weight of nearly 65 000 and is made up of four subunits. Each subunit comprises a porphyrin complex haem (Figure 24.8) which contains  $\text{Fe}^{2+}$  bonded to four N atoms, and a globular protein called globin. The globular protein is coordinated to the  $\text{Fe}^{2+}$  in haem through a fifth N atom from a histidine molecule in the protein. The sixth position round the  $\text{Fe}^{2+}$  is occupied either by a dioxygen molecule or a water molecule.

In oxyhaemoglobin the  $\text{Fe}^{2+}$  is in the low-spin state and is diamagnetic. It is just the right size to fit in the hole at the centre of the porphyrin ring. The porphyrin is both planar and rigid. In deoxyhaemoglobin the  $\text{Fe}^{2+}$  is in the high spin state and is paramagnetic. The size of  $\text{Fe}^{2+}$  increases by 28% when it changes from low spin to high spin, i.e. from 0.61 Å to 0.78 Å (see Table 24.7). Thus in deoxyhaemoglobin the  $\text{Fe}^{2+}$  is too large to fit in the hole at the centre of the porphyrin, and is situated 0.7–0.8 Å above the ring, thus distorting the bonds round the Fe. Thus the presence of  $\text{O}_2$  changes the electronic arrangement of  $\text{Fe}^{2+}$  and also distorts the shape of the complex. The globular protein appears to be essential since if it is removed oxidation of  $\text{Fe}(+II)$  to  $\text{Fe}(+III)$  occurs which is not reversible.

Haemoglobin is made up of four subunits, and when one subunit picks up an  $\text{O}_2$  molecule the  $\text{Fe}^{2+}$  contracts and moves into the plane of the ring. In doing so, it moves the histidine molecule attached to it and causes conformational changes in the globin chain. Since this chain is hydrogen bonded to the other three units it changes their conformations too and enhances their ability to attract  $\text{O}_2$ . This phenomenon is called the *cooperative effect*. The affinity of haemoglobin for  $\text{O}_2$  decreases as the pH decreases, but as blood is well buffered this has only a slight effect. In a similar way when the blood reaches the muscles, once one  $\text{O}_2$  has been released the others are released even more easily due to the cooperative effect in reverse.





Figure 24.8 Structure of haem b

$\text{CO}_2$  is the end product from the breakdown of glucose to release energy. There is an appreciable build-up of  $\text{CO}_2$  in the muscles. This is removed from the tissue and converted into soluble  $\text{HCO}_3^-$  ions.



This process is facilitated by the terminal amine groups of deoxyhaemoglobin which pick up the protons produced and thus act as a buffer. The reverse process occurs at the lungs.

The porphyrin ring is conjugated and planar. The characteristic red colour arises from charge transfer between stable  $\pi$  and low-lying  $\pi^*$  orbitals on the ring and Fe.

### Myoglobin

Haem is also important biologically in myoglobin which is used to store dioxygen in muscles. Myoglobin is similar to one of the units in haemoglobin. It contains only one Fe atom, has a molecular weight of about 17 000, and binds  $\text{O}_2$  more strongly than haemoglobin.

### Cytochromes

There are many cytochromes, which differ in slight detail, but these are broadly grouped together as cytochrome a, cytochrome b and cytochrome c. The prosthetic group in all cytochromes comprises four haem units, and cytochromes have a molecular weight of about 12 400. As in haemoglobin, Fe is bonded to four N atoms in each porphyrin ring, and the fifth site is occupied by a N atom from the associated protein. The big difference is that the sixth position is usually occupied by a S atom from an amino acid such as methionine, which is part of a protein.

Cytochromes are involved in the release of energy by oxidizing glucose with molecular  $\text{O}_2$  in the mitochondria inside living cells. The cytochromes are reversibly oxidized (and thus act as electron carriers). The Fe is in the low-spin state, and it changes reversibly between the (+II) and (+III) states. Cytochromes a, b and c have slightly different reduction potentials and reactions involve all three one after the other in the order b, c, a. In this way the energy from oxidizing glucose is released gradually. The energy is stored in the form of adenosine triphosphate ATP, which is used when required by the cell.

**Table 24.8** Reduction potentials  $E^\circ$  for cytochrome


Cytochrome b	0.04 V
Cytochrome c	0.26 V
Cytochrome a	0.28 V

### Ferretin


Animals, including man, absorb iron as  $\text{Fe}(+II)$  from food in their digestive systems. Their requirements for Fe are very small (man requires only 1 mg per day) as the existing Fe in the body is recycled. Any iron absorbed immediately reacts to form transferrin. A human body contains about 4 g of Fe, roughly 3 g as haemoglobin, and 1 g as ferretin. Ferretin is found in the spleen, liver and bone marrow. When a red blood cell has become aged after an average of 16 weeks, the haemoglobin is broken down and the iron is recovered by transferrin, a non haem protein. This is a single chain polypeptide of molecular weight 76 000–80 000 which contains two Fe atoms. This transports the Fe to the bone marrow where it is converted to ferretin which is brown and water soluble. Ferretin contains about 23% Fe. It consists of a roughly spherical sheath of protein called apoferretin which is approximately 120 Å in diameter and which encloses a micelle of  $\text{Fe}(+III)$  hydroxide, oxide and phosphate. The micelle is an aggregate of particles whose surface bears a charge. The micelle contains 2000–5000 atoms of Fe.

### Catalases and peroxidases

Catalases are enzymes which promote the disproportionation of  $\text{H}_2\text{O}_2$ . They also catalyse the oxidation of substrates by  $\text{H}_2\text{O}_2$ . The catalase molecule contains four  $\text{Fe}(+III)$  haem b groups and has a molecular weight of about 240 000.



The peroxidases also catalyse the decomposition of  $\text{H}_2\text{O}_2$ , but they are associated with a coenzyme  $\text{AH}_2$  which is oxidized in the reaction



### Ferredoxins

These are a group of non haem iron proteins which are responsible for electron transfer in plants and bacteria. They serve the same function that cytochromes perform in animals, but ferredoxins have much lower molecular weights (6000–12 000) and they may contain one, two, four or eight Fe atoms. Rubedoxin is the simplest and contains only one Fe atom. This is surrounded by four S atoms from the amino acid cysteine which is linked into protein chains and may be represented  $\text{Fe}(\text{S-cysteine})_4$ . The four S atoms are roughly tetrahedral.

Other ferredoxins include inorganic sulphide ions as well as cysteine S atoms, e.g.  $\text{Fe}_2(\text{S}_2)(\text{S-cysteine})_4$ . Since they contain inorganic sulphide ions, treatment with dilute acids liberates  $\text{H}_2\text{S}$ .

Some bacterial ferredoxins form cluster compounds. The simplest is  $\text{Fe}_4\text{S}_4(\text{S-cysteine})_4$ . The cluster may be imagined as a cube with two Fe atoms at diagonally opposite corners on the top face and two Fe atoms


occupying the other two diagonally opposite corners on the bottom face. S atoms fill the four unoccupied positions. In addition, each Fe is bonded to a S atom in a cysteine molecule.

### Haemerythrin

Despite its name, haemerythrin is a non-haem iron protein which serves as the oxygen carrier in some marine worms. It has a molecular weight of about 108 000, and is made up of eight subunits. Other marine worms have myohaemerythrin in their muscles which comprises just one of these subunits. This is analogous to haemoglobin and myoglobin in higher animals. However, deoxyhaemerythrin contains two high-spin  $\text{Fe}^{\text{II}}$  atoms and oxyhaemerythrin contains two  $\text{Fe}^{\text{III}}$  atoms and oxygen bound as  $\text{O}_2^{2-}$ .

## CYCLOPENTADIENYL AND RELATED COMPOUNDS

Interest in organometallic chemistry began in 1951 when G. Wilkinson *et al.* reported making an astonishing iron-hydrocarbon derivative called di- $\pi$ -cyclopentadienyliron. Rather surprisingly two research groups working independently prepared the same compound about the same time.



This compound is now called ferrocene and has the formula  $(\pi\text{-C}_5\text{H}_5)_2\text{Fe}$ . It is stable in air, forms orange crystals, and is diamagnetic. Ferrocene is soluble in organic solvents (alcohol, ether and benzene), and insoluble in water, NaOH solution and concentrated HCl. It is thermally stable up to 500°C. The X-ray structure shows that this has a sandwich structure in which the metal atom is sandwiched between two parallel planar cyclopentadienyl rings. This gave the clue that organic ligands could use their  $\pi$  system to bond to metals, and this opened up the study of compounds with metal-carbon bonds.

For ferrocene the symmetry of the space group requires the two five-membered rings to have the staggered conformation. In contrast, in the corresponding Ru and Os compounds ruthenocene and osmocene the rings adopt the eclipsed conformation (Figure 24.9). The exact arrangement in ferrocene is not simple. The barrier to internal rotation of the rings is only about  $4\text{kJ mol}^{-1}$ , and electron diffraction (on the gas) suggests an eclipsed arrangement. It is possible that crystal packing forces result in the staggered arrangement. More recent X-ray and neutron diffraction studies on the solid suggest the space group symmetry is met by a disordered arrangement of nearly eclipsed molecules with an angle of  $9^\circ$  between the rings rather than  $0^\circ$  for eclipsed and  $36^\circ$  for a staggered conformation.

Since all five C atoms in the cyclopentadienyl ring are equidistant from Fe, the ring has a hapticity  $\eta$  of 5, i.e.  $\eta^5\text{-C}_5\text{H}_5$ . All the first row transition elements form similar compounds, but they are much less stable than ferrocene.

The perpendicular distance between the rings is  $3.25\text{ \AA}$  compared with






Figure 24.9 Ferrocene and ruthenocene


3.35 Å in graphite. The C—C bond lengths are all equal ( $1.39 \text{ Å} \pm 0.00 \text{ Å}$ ). This is exactly the same bond length as in benzene, and the bond orders are also similar to those in benzene. The cyclopentadienyl rings do not undergo reactions of dienes such as the Diels–Alder reaction or catalytic hydrogenation, but they do display aromatic character. Thus ferrocene undergoes Friedel–Crafts acylation. With an equimolar amount of acetyl chloride the following reaction occurs:




With excess acetyl chloride, disubstitution occurs. (Other cyclopentadienyl compounds are decomposed.) This suggests that the ligand is really  $\text{C}_5\text{H}_5^-$ .




The general method for making cyclopentadienyl compounds is from cyclopentadiene in tetrahydrofuran solution:



Another preparative method uses  $\text{C}_5\text{H}_5\text{Ti}$ , which is stable, and insoluble in water:



Another convenient preparative method is to use a strong base to remove a proton from  $\text{C}_5\text{H}_6$ :



A large number of  $\eta^5\text{-C}_5\text{H}_5$  complexes are now known.

Other ring systems are now known to form similar sandwich complexes, including  $\text{C}_6\text{H}_6$ ,  $\text{C}_8\text{H}_8$ ,  $\text{C}_3\text{Ph}_3$ ,  $\text{C}_4\text{H}_4$  and  $\text{C}_7\text{H}_7$ . Examples include  $[\text{Cr}(\eta^6\text{-C}_6\text{H}_6)_2]$  and  $[\text{U}(\eta^8\text{-C}_8\text{H}_8)_2]$ .

Some cyclopentadienyl compounds have two rings at an angle, rather than forming a sandwich. For example,  $[(\eta^5\text{-C}_5\text{H}_5)_2\text{TiCl}_2]$ ,  $[\text{Ti}(\eta^5\text{-C}_5\text{H}_5)_2(\text{CO})_2]$ ,  $[\text{Ti}(\eta^5\text{-C}_5\text{H}_5)_2(\text{NR}_2)_2]$ ,  $[\text{Ti}(\eta^5\text{-C}_5\text{H}_5)_2(\text{SCN})_2]$  and  $[\text{V}(\eta^5\text{-C}_5\text{H}_5)_2\text{Cl}_2]$  have roughly tetrahedral structures, but the cyclopentadienyl mole-

Table 24.9 Some di- $\eta^5$ -cyclopentadienyl sandwich compounds

$[(\eta^5\text{-C}_5\text{H}_5)_2\text{V}^{\text{II}}]$	Vanadocene	Dark violet solid, air sensitive
$[(\eta^5\text{-C}_5\text{H}_5)_2\text{Cr}^{\text{II}}]$	Chromocene	scarlet crystals, m.p. 173 °C; very air sensitive
$[(\eta^5\text{-C}_5\text{H}_5)_2\text{Fe}^{\text{II}}]$	Ferrocene	Orange crystals, m.p. 174 °C; stable to >500 °C
$[(\eta^5\text{-C}_5\text{H}_5)_2\text{Co}^{\text{III}}]^+$	Cobalticinium	Yellow salts, stable in water, stable to about 400 °C
$[(\eta^5\text{-C}_5\text{H}_5)_2\text{Ni}^{\text{II}}]$	Nickelocene	Bright green solid, m.p. 173 °C (dec); oxidizes in air to $[(\eta^5\text{-C}_5\text{H}_5)_2\text{Ni}]^+$

cules are pentahaptic, with five C atoms in each ring attached to Ti. Reduction of these compounds gives  $[\text{Ti}(\text{C}_5\text{H}_5)_2 \cdot \text{X}]$  or  $[\text{Ti}(\text{C}_5\text{H}_5)_2]_2$ . Note that the latter compound is dimeric, and thus has a different structure to ferrocene.

$\text{Ti}(\text{C}_5\text{H}_5)_4$  is unusual because two cyclopentadienyl rings are pentahaptic ( $\pi$  bonding) and two are monohaptic ( $\sigma$  bonding), i.e.  $[\text{Ti}(\eta^5\text{-C}_5\text{H}_5)_2(\eta^1\text{-C}_5\text{H}_5)_2]$ . A similar arrangement is found in  $[\text{Nb}(\eta^5\text{-C}_5\text{H}_5)_2(\eta^1\text{-C}_5\text{H}_5)_2]$ ,  $[\text{Nb}(\eta^5\text{-C}_5\text{H}_5)_2(\eta^1\text{-C}_5\text{H}_5)_2\text{Cl}_2]$  and  $[\text{Nb}(\eta^5\text{-C}_5\text{H}_5)_2(\eta^1\text{-C}_5\text{H}_5)_2\text{Cl}_3]$ .

Other compounds have only one ring, e.g.  $[\text{Cr}(\eta^5\text{-C}_5\text{H}_5)(\text{CO})_3]^-$ ,  $[\text{Mn}(\eta^5\text{-C}_5\text{H}_5)(\text{CO})_3]$ ,  $[\text{Cr}(\eta^6\text{-C}_6\text{H}_6)(\text{CO})_3]$ ,  $[\text{Mo}(\eta^7\text{-C}_7\text{H}_7)(\text{CO})_3]^+$  and  $[\text{Fe}(\eta^4\text{-C}_4\text{H}_4)(\text{CO})_3]$ .

Ferrocene is sometimes regarded as a compound of  $\text{Fe}^{2+}$  and two  $\text{C}_5\text{H}_5^-$  ions. The bonding in these aromatic sandwich-type structures is better considered as  $\pi$  bonding involving the lateral overlap of the  $d_{xz}$  and  $d_{yz}$  orbitals on Fe with the delocalized  $p\pi$  aromatic orbital from each cyclopentadienyl ring. The bonding is too complicated to be described in detail here.

The sandwich compounds were discovered and studied independently by E.O. Fischer in Munich and G. Wilkinson at Imperial College, London. For this work they were jointly awarded the Nobel Prize for Chemistry in 1973.

## FURTHER READING

- Abel, E.W. and Stone, F.G. (1969, 1970) The chemistry of transition metal carbonyls, *Q. Rev. Chem. Soc.*, Part I – Structural considerations, **23**, 325; Part II – Synthesis and reactivity, **24**, 498.
- Allen, A.D. (1973) Complexes of dinitrogen, *Chem. Rev.*, **73**, 11.
- Canterford, J.H. and Cotton, R. (1968) *Halides of the Second and Third Row Transition Elements*, Wiley, London.
- Canterford, J.H. and Cotton, R. (1969) *Halides of the First Row Transition Elements*, Wiley, London.
- Corbett, J.D. (1981) Extended metal–metal bonding in halides of the early transition metals, *Acc. Chem. Res.*, **14**, 239.

- Diatomic metals and metallic clusters* (1980) (Conference papers of the Fajaday Symposia of the Royal Society of Chemistry No 14) Royal Society of Chemistry London
- Emeleus H J and Sharpe A G (1973) *Modern Aspects of Inorganic Chemistry* 4th ed (Chapters 14 and 15 Complexes of Transition Metals Chapter 20 Carbonyls) Routledge and Kegan Paul London
- Griffith W P (1968) Organometallic nitrosyls *Adv Organometallic Chem* 7 211
- Griffith W P (1973) *Comprehensive Inorganic Chemistry* Vol 4 (Chapter 46 Carbonyls cyanides isocyanides and nitrosyls) Pergamon Press Oxford
- Hunt C B (1977) Metallocenes – the first 25 years *Education in Chemistry* 14 110–113
- Johnson B F G and McCleverty J A (1966) Nitric oxide compounds of transition metals *Progr Inorg Chem* 7 277
- Johnson B F G (1976) The structures of simple binary carbonyls *JCS Chem Commun* 211–213
- Johnson B F G (ed) (1980) *Transition Metal Clusters* John Wiley Chichester
- Kauffman G B (1983) The discovery of ferrocene the first sandwich compound *J Chem Ed* 60 185–186
- Levason W and McAuliffe C A (1974) Higher oxidation state chemistry of iron cobalt and nickel *Coordination Chem Rev* 12 151–184
- Lever P and Gray H B (eds) (1989) *Iron Porphyrins* (Physical Bioinorganic Chemistry Series) VCH Publishers
- Lewis J and Green M L (eds) (1983) *Metal Clusters in Chemistry* (Proceedings of the Royal Society Discussion Meeting May 1982) The Society London
- Nicholls D (1973) *Comprehensive Inorganic Chemistry* Vol 3 (Chapter 40 Iron) Pergamon Press Oxford
- Perutz M (1970) Stereochemistry of cooperative effects in haemoglobin *Nature* 228 726–739
- Seddon E A and Seddon K R (1984) *Chemistry of Ruthenium* (Topics in Inorganic Chemistry Series Vol 19) Elsevier
- Suslick K S and Reinert T J (1985) The synthetic analogs of O<sub>2</sub> binding heme proteins *J Chem Ed* 62 974–982
- Toth L E (1971) *Transition Metal Carbides and Nitrides* Academic Press
- Williams R V (1969) Carbon determination in modern steel making *Chemistry in Britain* 5 213–216
- Wilkinson G Rosenblum M Whiting M C and Woodward R B (1952) The structure of iron bis cyclopentadienyl *J Am Chem Soc* 74 2125–2126 (The first report of a sandwich type of organometallic compound)

# Group 9 – the cobalt group

25

**Table 25.1** Electronic structure and oxidation states

Element		Electronic structure	Oxidation states*
Cobalt	Co	[Ar] 3d <sup>7</sup> 4s <sup>2</sup>	(-I) 0 (I) <b>II</b> <b>III</b> (IV)
Rhodium	Rh	[Kr] 4d <sup>8</sup> 5s <sup>1</sup>	(-I) 0 (I) <b>II</b> <b>III</b> IV (VI)
Iridium	Ir	[Xe] 4f <sup>14</sup> 5d <sup>9</sup>	(-I) 0 (I) (II) <b>III</b> <b>IV</b> (V) (VI)

\* The most important oxidation states (generally the most abundant and stable) are shown in bold. Other well-characterized but less important states are shown in normal type. Oxidation states that are unstable, or in doubt, are given in parentheses.

## OCCURRENCE, EXTRACTION AND USES

The elements have odd atomic numbers and have low abundance in the earth's crust. Co occurs to the extent of 23 ppm by weight, whilst rhodium and iridium are extremely rare.

**Table 25.2** Abundance of the elements in the earth's crust, by weight

	ppm	Relative abundance
Co	30	29
Rh	0.0001	77 =
Ir	0.001	74

There are many ores which contain Co. The commercially important ones are cobaltite CoAsS, smaltite CoAs<sub>2</sub> and linnaeite Co<sub>3</sub>S<sub>4</sub>. These are always found together with Ni ores, often with Cu ores and sometimes with Pb ores. Co is obtained as a by-product from the extraction of the other metals. In 1992, world production of Co ores was 30 100 tonnes of contained metal. The main producers were Zaire 22%, Canada 17%, Zambia and the Soviet Union 15% each, and Australia 9%.

The ore is roasted to convert it to a mixture of oxides called 'speisses'. As<sub>4</sub>O<sub>10</sub> and/or SO<sub>2</sub> come off as gases and are valuable by-products. The

*continued overleaf*



oxides are treated with  $\text{H}_2\text{SO}_4$  when Fe (which is often present as an impurity), Co and Ni dissolve and can be separated from Cu or Pb. Lime is added to the solution to precipitate Fe as the hydrous oxide  $\text{Fe}_2\text{O}_3 \cdot (\text{H}_2\text{O})$ . Then  $\text{NaOCl}$  is added to precipitate  $\text{Co}(\text{OH})_2$ . The hydroxide is ignited to give  $\text{Co}_3\text{O}_4$  which is reduced by heating with  $\text{H}_2$  or charcoal to give Co metal.

Co forms important high temperature alloys with steel and about one third of the metal produced is used for this purpose. These alloys find important uses in gas turbine engines and in high speed steel which is used to make cutting tools for lathes. High working speeds can be used as these tools retain their hardness and cutting edge even at red heat. Exceptionally hard alloys can be made which can be used instead of diamonds in rock drills, e.g. stellite (50% Co, 27% Cr, 12% W, 5% Fe and 2.5% C) and widia metal (tungsten carbide WC with 10% Co).


A third of the Co produced is used to make pigments for the ceramic glass and paint industries. Historically the oxide was used as a blue pigment in the ceramic industry. It is used to make blue glass. Nowadays it is mainly used to counteract the yellow colour of Fe and give a white colour.

Co is ferromagnetic (i.e. it can be magnetized permanently) like Fe and Ni. One fifth of the Co produced is used to make magnetic alloys such as Alnico (containing Al, Ni and Co). These alloys make powerful permanent magnets which are 20–30 times more powerful than magnets of Fe.

Small amounts of the Co salts of fatty acids from linseed oil and naphthenic acid are used as 'driers' to speed the drying of oil paints.

Co is an essential constituent of fertile soil and is present in some enzymes and in vitamin  $\text{B}_{12}$ .

The artificial isotope  $^{60}\text{Co}$  is radioactive, and undergoes  $\beta$  decay (half life 5.2 years). At the same time it gives out intense high energy  $\gamma$  radiation, which is used in hospitals for radiotherapy of cancerous tumours.  $^{60}\text{Co}$  is prepared by neutron irradiation of the only naturally occurring isotope  $^{59}\text{Co}$  in a nuclear reactor.



Trace amounts of rhodium and iridium are found in the metallic state together with the platinum metals and the coinage metals in the  $\text{NiS}/\text{CuS}$  ores mined in South Africa, Canada (Sudbury, Ontario), and the Soviet Union (the river sand from the Ural mountains). World production of all six platinum group metals was only 281 tonnes in 1992. The largest sources were South Africa 54%, the Soviet Union 37%, and Canada 4%. Rh and Ir are obtained from the anode slime which accumulates in the electrolytic refining of Ni. This contains a mixture of the platinum metals together with Ag and Au. The elements Pd, Pt, Ag and Au are dissolved in aqua regia and the residue contains Ru, Os, Rh and Ir. After a complex separation Rh and Ir are obtained as powders. Their melting points are very high and powder forming techniques are used to fabricate metal components. (The powder is formed into the required shape, then sintered, i.e. heated in hydrogen until it congeals. It does not

melt.) These elements are both scarce and expensive, and have a limited number of specialist uses.

All the platinum metals have specific catalytic properties. A Pt/Rh alloy was formerly used in the Ostwald process (for making  $\text{HNO}_3$ ) to oxidize  $\text{NH}_3$  to NO. Rh is an important catalyst in the control of car exhaust emissions. Rh-phosphine complexes are used as catalysts for hydrogenation reactions. Ir (like Os in the previous group) is used to make very hard alloys which are used to make pivots for instruments. A Pt/Ir alloy is used to make the electrodes for long life sparking plugs. These are expensive but have important military uses, for example in helicopters. The USA used a lot of this alloy during the Vietnam war.

## OXIDATION STATES

The trend for the elements in the second half of the  $d$ -block not to use all their outer electrons for bonding in the maximum oxidation state is continued. A possible report of  $\text{Co}(+\text{V})$  has been disproved, and even  $\text{Co}(+\text{IV})$  is unstable. The maximum oxidation state for Rh and Ir is  $(+\text{VI})$ . For Co, the  $(+\text{II})$  and  $(+\text{III})$  states are by far the most important. The trend in the later elements of the first row for the  $(+\text{II})$  state to be more stable than  $(+\text{III})$  is also observed.  $\text{Co}^{2+}$  ions and the hydrated ion  $[\text{Co}(\text{H}_2\text{O})_6]^{2+}$  exist in many simple compounds and the hydrated ion is stable in water. In contrast simple compounds containing  $\text{Co}(+\text{III})$  are oxidizing and are relatively unstable. However,  $\text{Co}(+\text{III})$  is stable and is very important in complexes.

The most stable states for the other elements are  $\text{Rh}(+\text{III})$ ,  $\text{Ir}(+\text{III})$  and  $\text{Ir}(+\text{IV})$ . Simple ionic compounds of these elements are uncommon. The oxides and halides formed are shown in Table 25.3.

## GENERAL PROPERTIES

Co resembles iron and is very tough. It is harder and has a higher tensile strength than steel. Co is bluish white and lustrous in appearance. Like iron it is ferromagnetic, but on heating above  $1000^\circ\text{C}$  it changes to a non-magnetic form.

Co is relatively unreactive, and does not react with  $\text{H}_2\text{O}$ ,  $\text{H}_2$ , or  $\text{N}_2$ , though it reacts with steam, forming  $\text{CoO}$ . It is oxidized when heated in air and burns at white heat to  $\text{Co}_3\text{O}_4$ . Co dissolves slowly in dilute acids, but like Fe it is rendered passive by concentrated  $\text{HNO}_3$ . Co combines readily with the halogens, and at elevated temperatures with S, C, P, As, Sb and Sn.

Rh and Ir are also hard metals. In common with the other platinum metals they are much more noble and unreactive. Ir has the highest density of any element,  $22.61\text{ g cm}^{-3}$ . Rh and Ir are resistant to acids, but react with  $\text{O}_2$  and the halogens at high temperatures (Table 25.5). All three elements form a large number of coordination compounds.

Table 25.3 Oxides and halides

Oxidation states					
(+II)	(+III)	(+IV)	(+V)	(+VI)	Others
CoO	(Co <sub>2</sub> O <sub>3</sub> ) <sup>h</sup>	(CoO <sub>2</sub> ) <sup>h</sup>	—	—	Co <sub>3</sub> O <sub>4</sub>
RhO	Rh <sub>2</sub> O <sub>3</sub>	RhO <sub>2</sub>	—	—	
—	Ir <sub>2</sub> O <sub>3</sub>	IrO <sub>2</sub>	—	(IrO <sub>3</sub> )	
CoF <sub>2</sub>	CoF <sub>3</sub>	—	—	—	
CoCl <sub>2</sub>	—	—	—	—	
CoBr <sub>2</sub>	—	—	—	—	
CoI <sub>2</sub>	—	—	—	—	
—	RhF <sub>3</sub>	RhF <sub>4</sub>	(RhF <sub>5</sub> )	RhF <sub>6</sub>	
—	RhCl <sub>3</sub>	—	—	—	
—	RhBr <sub>3</sub>	—	—	—	
—	RhI <sub>3</sub>	—	—	—	
—	IrF <sub>3</sub>	IrF <sub>4</sub>	(IrF <sub>5</sub> )	IrF <sub>6</sub>	
(IrCl <sub>2</sub> ?)	IrCl <sub>3</sub>	(IrCl <sub>4</sub> )	—	—	
—	IrBr <sub>3</sub>	—	—	—	
—	IrI <sub>3</sub>	—	—	—	

The most stable oxidation states are shown in bold, unstable ones in brackets  
h = hydrous oxide

Table 25.4 Some physical properties

	Covalent radius (Å)	Ionic radius (Å)		Melting point (°C)	Boiling point (°C)	Density (g cm <sup>-3</sup> )	Pauling's electronegativity
		M <sup>2+</sup>	M <sup>3+</sup>				
Co	1.16	0.745 <sup>h</sup> 0.65 <sup>l</sup>	0.61 <sup>h</sup> 0.545 <sup>l</sup>	1495	3100	8.90	1.8
Rh	1.25	—	0.665	1960	3760	12.39	2.2
Ir	1.26	—	0.68	2443	(4550)	22.61	2.2

h = high spin value, l = low spin radius

Table 25.5 Some reactions of Co, Rh and Ir

Reagent	Co	Rh	Ir
O <sub>2</sub>	Co <sub>3</sub> O <sub>4</sub>	Rh <sub>2</sub> O <sub>3</sub> at 600°C	IrO <sub>2</sub> at 1000°C
F <sub>2</sub>	CoF <sub>2</sub> and CoF <sub>3</sub>	RhF <sub>3</sub> at 600°C	IrF <sub>6</sub>
Cl <sub>2</sub>	CoCl <sub>2</sub>	RhCl <sub>3</sub> at 400°C	IrCl <sub>3</sub> at 600°C
H <sub>2</sub> O	No reaction	No reaction	No reaction
Dilute HCl or HNO <sub>3</sub>	[Co(H <sub>2</sub> O) <sub>6</sub> ] <sup>2+</sup> + H <sub>2</sub>	No reaction	No reaction
Conc. HNO <sub>3</sub>	Passive	No reaction	No reaction

## LOWER OXIDATION STATES

The oxidation states (-I) and (0) occur in a few compounds with  $\pi$  bonding ligands such as CO,  $\text{PF}_3$ , NO and  $\text{CN}^-$ . The (-I) state is found in the tetrahedral complexes  $[\text{Co}(\text{CO})_4]^-$ ,  $[\text{Rh}(\text{CO})_4]^-$ ,  $[\text{Co}(\text{CO})_3\text{NO}]$  and  $\text{K}[\text{Ir}(\text{PF}_3)_4]$ . The zero oxidation state occurs in  $\text{Co}_2(\text{CO})_8$ , though there is some doubt about the corresponding Ru compounds (Figure 25.1). Other zero-valent compounds are  $\text{K}_4[\text{Co}(\text{CN})_4]$  and  $[\text{Co}(\text{PMe}_3)_4]$ .




Figure 25.1 Two isomeric forms of  $\text{Co}_2(\text{CO})_8$ , both with metal-metal bonding.

The carbonyls  $\text{Co}_4(\text{CO})_{12}$ ,  $\text{Rh}_4(\text{CO})_{12}$  and  $\text{Ir}_4(\text{CO})_{12}$  all have M—M bonds and contain a cluster of four metal atoms. The CO groups may be either apical (terminal) or bridging. There are slight differences between compounds of the metals. The Co and Rh compounds have three bridging CO groups but the Ir compound has none (Figure 25.2).





Figure 25.2 The structures of (a)  $\text{Co}_4(\text{CO})_{12}$  and  $\text{Rh}_4(\text{CO})_{12}$  and (b)  $\text{Ir}_4(\text{CO})_{12}$ .

The carbonyl ion from  $\text{Na}_3[\text{Co}_6(\text{CO})_{14}]$  and the carbonyls  $\text{Co}_6(\text{CO})_{16}$  and  $\text{Rh}_6(\text{CO})_{16}$  have unusual structures, comprising an octahedral cluster of six metal atoms with a CO group bridging three metal atoms on each triangular face of the octahedron. The remaining CO groups are normal terminal groups.

**(+I) STATE**

Co(+I) exists in many complexes with  $\pi$  bonded ligands. The (+I) state is better known for Co than for any other first row transition metal except Cu. Compounds are usually made by reducing  $\text{CoCl}_2$  with Zn or  $\text{N}_2\text{H}_4$  in the presence of the ligand. Their structures are typically a trigonal bipyramid or tetrahedral.

The ion  $[\text{Co}^{-\text{I}}(\text{CO})_4]^-$  reacts with organic isonitriles  $\text{R}-\text{NC}$ , giving  $[\text{Co}^{\text{I}}(\text{CNR})_5]^+$  which has a trigonal bipyramid structure. A dinitrogen complex can be formed by direct uptake of  $\text{N}_2$  gas at atmospheric pressure.



The ligand (acac) is acetylacetonate. The complex  $[\text{Co}^{\text{I}}(\text{H})(\text{N}_2)(\text{PPh}_3)_3]$  also has a trigonal bipyramidal structure (Figure 25.3) which has a  $\text{N}\equiv\text{N}$  bond length of 1.11 Å compared with 1.098 Å in  $\text{N}_2$ . Since the  $\text{N}\equiv\text{N}$  bond length is almost unchanged, this indicates that  $\sigma$  bonding from N to Co is extremely weak. Thus the N—Co bond is mainly due to  $\pi$  bonding (back bonding) from Co to N similar to that in  $[\text{Ru}(\text{NH}_3)_5\text{N}_2]^{2+}$  (Dinitrogen complexes are discussed in Chapter 24 under '+II state - complexes').





Figure 25.3 The structure of  $[\text{Co}^{\text{I}}\text{H}(\text{N}_2)(\text{PPh}_3)_3]$

The reduced form of vitamin  $\text{B}_{12}$  also appears to contain Co(+I).

There is a fairly extensive chemistry of Rh(+I) and Ir(+I) complexes with  $\pi$  bonding ligands such as CO, phosphines  $\text{PR}_3$  and alkenes. These normally have either a square planar structure, for example *trans*- $[\text{Ir}(\text{Cl})(\text{CO})(\text{PPh}_3)_2]$  (called Vaska's compound) and  $[\text{Rh}(\text{Cl})(\text{PPh}_3)_3]$  (called Wilkinson's catalyst), or a trigonal bipyramid structure as in  $[\text{Rh}(\text{H})(\text{CO})(\text{PPh}_3)_3]$ . The square planar (+I) compounds undergo an unusual type of reaction called *oxidative addition*. In this a neutral molecule is added to the (+I) complex to give a (+III) octahedral complex.



A similar reaction occurs with  $\text{H}_2$ ,  $\text{H}_2\text{S}$ ,  $\text{CH}_3\text{I}$ , and  $\text{Cl}-\text{HgCl}$ . A different reaction occurs when other molecules such as  $\text{O}_2$ ,  $\text{SO}_2$ ,  $\text{CS}_2$ ,  $\text{RNCS}$





Figure 25.4  $[\text{Ir}^{\text{III}}\text{Cl}(\text{CO})(\text{O}_2)(\text{PPh}_3)_2]$  complex.

$\text{RNCO}$  and  $\text{RC}\equiv\text{CR}$  are added to the (+I) square planar compounds. (The added molecules all contain multiple bonds.) Here the added molecule acts as a bidentate ligand, thus forming a cyclic structure (Figure 25.4).


Vaska's compound is yellow, and it readily absorbs  $\text{O}_2$  and becomes orange coloured. The  $\text{O}_2$  may be removed by flushing with  $\text{N}_2$ . This reversible oxygenation has been studied as a model for the oxygen carrying ability of haemoglobin (see Chapter 24). Oxidative addition reactions have been observed for complexes where the central metal has a  $d^8$  or  $d^{10}$  configuration involving  $\text{Rh}^{\text{I}}$ ,  $\text{Ir}^{\text{I}}$ ,  $\text{Ni}^0$ ,  $\text{Pd}^0$ ,  $\text{Pt}^0$ ,  $\text{Pd}^{\text{II}}$  and  $\text{Pt}^{\text{II}}$ . There must be non-bonding d electrons available on the metal, and also two vacant coordination sites.

Wilkinson's catalyst  $[\text{Rh}(\text{Cl})(\text{PPh}_3)_3]$  is red-violet in colour, and is made by refluxing  $\text{RhCl}_3 \cdot 3\text{H}_2\text{O}$  with triphenyl phosphine. It has a square planar structure. It is very effective for selective hydrogenation of organic molecules at room temperature and pressure. Alkene groups at the end of a chain (alk-1-enes) are hydrogenated but double bonds elsewhere in the chain are not affected. It is of importance in the pharmaceutical industry.

Wilkinson's catalyst and various Co compounds such as the carbonyl hydride  $\text{HCo}^{\text{I}}(\text{CO})_4$  have been used as catalysts in the OXO process. In this process, CO and  $\text{H}_2$  are added to an alkene, thus forming an aldehyde. A temperature of  $150^\circ\text{C}$  and 200 atmospheres pressure are required. The OXO process is of considerable industrial importance, as the aldehydes produced can be converted into alcohols. About 3 million tonnes of  $\text{C}_6$ – $\text{C}_9$  alcohols are produced annually in this way. These are a mixture of straight chain and branched chain molecules depending on the position of the double bond in the hydrocarbon. The straight chain alcohols are used to make polyvinyl chloride and detergents. Efforts to improve the yield of the straight chain products involve the use of triphenylphosphine substituted carbonyls of Co. The complex *trans*- $[\text{Rh}(\text{CO})(\text{H})(\text{PPh}_3)_3]$  has also been used in the OXO process, and is an important catalyst in the hydrogenation of alkenes. It is active at  $25^\circ\text{C}$  and 1 atmosphere pressure, and for steric reasons it is specific to terminal alkenes rather than double bonds elsewhere in the chain.



Acetic acid is also produced synthetically from methyl alcohol and this reaction is catalysed by complexes such as  $[\text{Rh}(\text{Cl})(\text{CO})(\text{PPh}_3)_2]$  or  $[\text{Rh}(\text{Cl})(\text{CO})_2]_2$  in the presence of  $\text{CH}_3\text{I}$ ,  $\text{I}_2$  or  $\text{HI}$  as activator



### (+II) STATE


The (+II) state is the most important for simple compounds of Co (though the (+III) state is the most important in complexes) Rh(+II) and Ir(+II) are only of minor importance

A wide range of simple Co(+II) compounds are known including  $\text{CoO}$ ,  $\text{Co(OH)}_2$ ,  $\text{CoS}$ , and salts of the common acids such as  $\text{CoCl}_2$ ,  $\text{CoBr}_2$ ,  $\text{CoSO}_4$ ,  $\text{Co(NO}_3)_2$  and  $\text{CoCO}_3$ . The hydrated salts are all pink or red and contain the hexahydrate ion  $[\text{Co}(\text{H}_2\text{O})_6]^{2+}$ . Most Co(+II) compounds except the carbonate are soluble in water.


If  $\text{NaOH}$  is added to a solution containing  $\text{Co}^{2+}$  then  $\text{Co(OH)}_2$  is first obtained as a blue precipitate which turns pale pink on standing. This is mainly basic, but it is weakly amphoteric as it dissolves in very strong  $\text{NaOH}$ , giving a blue coloured solution which contains  $[\text{Co(OH)}_4]^{-}$ .  $\text{Co(OH)}_2$  slowly oxidizes in air to brown  $\text{Co}^{III}\text{O} \cdot \text{OH}$ .

$\text{CoO}$  is olive green and is formed by heating  $\text{Co(OH)}_2$  or by heating many Co(+II) salts such as  $\text{CoCO}_3$  in the absence of air. If  $\text{CoO}$  is melted with  $\text{SiO}_2$  and  $\text{K}_2\text{CO}_3$  a deep blue glass potassium cobalt(II) silicate is formed. Commercially this blue glass is ground up and the powder which is called *smalt*, is used as a pigment to give a blue colour to glass, enamels and glazes. Smalt was known to the ancient Egyptians and the Romans. In the laboratory 'cobalt glass' is used to observe the flame test for potassium in the presence of sodium. The blue glass absorbs the intense yellow coloration from sodium thus allowing the colour from potassium to be seen.

$\text{CoCl}_2$  is used as a test for water, both as 'cobalt chloride paper' and as an indicator added to the drying agent silica gel. Hydrated  $\text{CoCl}_2 \cdot 6\text{H}_2\text{O}$  is pink coloured and contains octahedral  $[\text{Co}(\text{H}_2\text{O})_6]^{2+}$  ions. If this is partially dehydrated by heating then blue coloured tetrahedral ions  $[\text{Co}(\text{H}_2\text{O})_4]^{2+}$  are formed. Addition of water produces the reverse change. Thus when the indicator in silica gel is blue the drying agent is effective but when it is pink the drying agent needs changing.



In a similar way the octahedral aqua ion reacts with excess  $\text{Cl}^-$  to give the blue coloured tetrahedral ion  $[\text{CoCl}_4]^{2-}$ .



Co(+II) has a  $d^7$  configuration.  $[\text{Co}(\text{H}_2\text{O})_6]^{2+}$  and most Co(+II) complexes are low-spin octahedral. Tetrahedral complexes are also common and have more intense colours than octahedral complexes. This is because a tetrahedron lacks a centre of symmetry and thus easily overcomes the Laporte selection rule (that  $\Delta l = 1$ ), whereas the octahedral complexes have to rely on asymmetric vibrations of ligands to destroy the centre of symmetry. The magnetic moments of both octahedral and tetrahedral complexes are higher than predicted using the spin only formula which would give  $\mu = 3.87 \text{ BM}$ . In the octahedral case this is because there is an orbital contribution since with a  $(t_{2g})^5 (e_g)^2$  arrangement it is possible to transform one  $t_{2g}$  orbital into another. In tetrahedral complexes the electronic arrangement is  $(e_g)^4 (t_{2g})^3$  so transformation of the  $t_{2g}$  orbitals is not possible and the orbital contribution is zero. However, in this case spin orbit coupling occurs. This accounts for the higher than expected value of  $\mu$  (see 'Measurement of magnetic moments', Chapter 18).

Cobalt(II) acetate  $\text{Co}(\text{CH}_3\text{COO})_2 \cdot 4\text{H}_2\text{O}$  is formed by dissolving  $\text{CoCO}_3$  in acetic acid. It forms red crystals which are very soluble, and is used as a drying agent for varnish and lacquers.


Anhydrous Co salts cannot be made by heating the hydrated salts, because they decompose to the oxide. Thus dry preparative methods are used. Anhydrous  $\text{CoF}_2$  is pink and is obtained from the reaction of HF with  $\text{CoCl}_2$ . Anhydrous  $\text{CoCl}_2$  (blue) and  $\text{CoBr}_2$  (green) are made by heating the elements. Anhydrous  $\text{CoI}_2$  is blue-black and is made by heating the metal with HI. They all have solid structures in which  $\text{Co}^{2+}$  is octahedrally coordinated.

Co(+II) forms a number of complexes, but these are less stable than those of Co(+III). Co(+II) complexes may be tetrahedral or octahedral. Since there is only a small difference in stability between them the two forms sometimes exist in equilibrium. The large monodentate ligands  $\text{Cl}^-$ ,  $\text{Br}^-$ ,  $\text{I}^-$ ,  $\text{OH}^-$  and  $\text{SCN}^-$  commonly form tetrahedral complexes. Co(+II) forms more tetrahedral complexes than any other transition metal ion. This is associated with the fairly small loss of crystal field stabilization energy of  $0.27\Delta_o$  with a  $d^7$  ion in a weak ligand field (see Table 7.15).


The blue coloured complex  $\text{Hg}[\text{Co}(\text{NCS})_4]$  is unusual. The  $\text{Co}^{2+}$  is tetrahedrally coordinated by N atoms, and  $\text{Hg}^{2+}$  is tetrahedrally coordinated by S atoms, giving a polymeric solid. This compound is often used to calibrate a magnetic balance when measuring magnetic moments.

Most Co(+II) complexes are high spin, but the  $\text{CN}^-$  ligand produces low-spin complexes. If a solution of a  $\text{Co}^{2+}$  salt is treated with excess  $\text{CN}^-$  a green coloured complex  $[\text{Co}(\text{CN})_5]^{3-}$  is formed. This can be isolated as the barium salt. It is a good catalyst for the hydrogenation of alkenes. The complex is paramagnetic with one unpaired electron, and its shape is a square pyramid. It may dimerize to give purple  $[\text{Co}_2(\text{CN})_{10}]^{6-}$ , which is diamagnetic and has the structure  $(\text{CN})_5\text{Co}-\text{Co}(\text{CN})_5$  similar to the carbonyl  $\text{Mn}_2(\text{CO})_{10}$ . It is interesting that  $[\text{Co}^{\text{II}}(\text{CN})_5]^{3-}$  is formed instead





Acetic acid is also produced synthetically from methyl alcohol, and this reaction is catalysed by complexes such as  $[\text{Rh}(\text{Cl})(\text{CO})(\text{PPh}_3)_2]$  or  $[\text{Rh}(\text{Cl})(\text{CO})_2]_2$  in the presence of  $\text{CH}_3\text{I}$ ,  $\text{I}_2$  or  $\text{HI}$  as activator



### (+II) STATE


The (+II) state is the most important for simple compounds of Co (though the (+III) state is the most important in complexes).  $\text{Rh}(+II)$  and  $\text{Ir}(+II)$  are only of minor importance.

A wide range of simple  $\text{Co}(+II)$  compounds are known including  $\text{CoO}$ ,  $\text{Co}(\text{OH})_2$ ,  $\text{CoS}$ , and salts of the common acids such as  $\text{CoCl}_2$ ,  $\text{CoBr}_2$ ,  $\text{CoSO}_4$ ,  $\text{Co}(\text{NO}_3)_2$ , and  $\text{CoCO}_3$ . The hydrated salts are all pink or red and contain the hexahydrate ion  $[\text{Co}(\text{H}_2\text{O})_6]^{2+}$ . Most  $\text{Co}(+II)$  compounds except the carbonate are soluble in water.


If  $\text{NaOH}$  is added to a solution containing  $\text{Co}^{2+}$  then  $\text{Co}(\text{OH})_2$  is first obtained as a blue precipitate which turns pale pink on standing. This is mainly basic, but it is weakly amphoteric as it dissolves in very strong  $\text{NaOH}$ , giving a blue coloured solution which contains  $[\text{Co}(\text{OH})_4]^{2-}$ .  $\text{Co}(\text{OH})_2$  slowly oxidizes in air to brown  $\text{Co}^{III}\text{O} \cdot \text{OH}$ .

$\text{CoO}$  is olive green and is formed by heating  $\text{Co}(\text{OH})_2$  or by heating many  $\text{Co}(+II)$  salts such as  $\text{CoCO}_3$  in the absence of air. If  $\text{CoO}$  is melted with  $\text{SiO}_2$  and  $\text{K}_2\text{CO}_3$  a deep blue glass potassium cobalt(II) silicate is formed. Commercially this blue glass is ground up and the powder which is called *smalt* is used as a pigment to give a blue colour to glass, enamels and glazes. Smalt was known to the ancient Egyptians and the Romans. In the laboratory 'cobalt glass' is used to observe the flame test for potassium in the presence of sodium. The blue glass absorbs the intense yellow coloration from sodium, thus allowing the colour from potassium to be seen.

$\text{CoCl}_2$  is used as a test for water, both as 'cobalt chloride paper' and as an indicator added to the drying agent silica gel. Hydrated  $\text{CoCl}_2 \cdot 6\text{H}_2\text{O}$  is pink coloured and contains octahedral  $[\text{Co}(\text{H}_2\text{O})_6]^{2+}$  ions. If this is partially dehydrated by heating then blue coloured tetrahedral ions  $[\text{Co}(\text{H}_2\text{O})_4]^{2+}$  are formed. Addition of water produces the reverse change. Thus when the indicator in silica gel is blue the drying agent is effective, but when it is pink the drying agent needs changing.



In a similar way the octahedral aqua ion reacts with excess  $\text{Cl}^-$  to give the blue coloured tetrahedral ion  $[\text{CoCl}_4]^{2-}$ .



Co(+II) has a  $d^7$  configuration.  $[\text{Co}(\text{H}_2\text{O})_6]^{2+}$  and most Co(+II) complexes are low-spin octahedral. Tetrahedral complexes are also common and have more intense colours than octahedral complexes. This is because a tetrahedron lacks a centre of symmetry and thus easily overcomes the Laporte selection rule (that  $\Delta l = 1$ ), whereas the octahedral complexes have to rely on asymmetric vibrations of ligands to destroy the centre of symmetry. The magnetic moments of both octahedral and tetrahedral complexes are higher than predicted using the spin only formula which would give  $\mu = 3.87 \text{ BM}$ . In the octahedral case this is because there is an orbital contribution since with a  $(t_{2g})^5 (e_g)^2$  arrangement it is possible to transform one  $t_{2g}$  orbital into another. In tetrahedral complexes the electronic arrangement is  $(e_g)^4 (t_{2g})^3$  so transformation of the  $t_{2g}$  orbitals is not possible and the orbital contribution is zero. However, in this case spin orbit coupling occurs. This accounts for the higher than expected value of  $\mu$  (see 'Measurement of magnetic moments', Chapter 18).

Cobalt(II) acetate  $\text{Co}(\text{CH}_3\text{COO})_2 \cdot 4\text{H}_2\text{O}$  is formed by dissolving  $\text{CoCO}_3$  in acetic acid. It forms red crystals which are very soluble, and is used as a drying agent for varnish and lacquers.

Anhydrous Co salts cannot be made by heating the hydrated salts, because they decompose to the oxide. Thus dry preparative methods are used. Anhydrous  $\text{CoF}_2$  is pink and is obtained from the reaction of HF with  $\text{CoCl}_2$ . Anhydrous  $\text{CoCl}_2$  (blue) and  $\text{CoBr}_2$  (green) are made by heating the elements. Anhydrous  $\text{CoI}_2$  is blue-black and is made by heating the metal with HI. They all have solid structures in which  $\text{Co}^{2+}$  is octahedrally coordinated.

Co(+II) forms a number of complexes, but these are less stable than those of Co(+III). Co(+II) complexes may be tetrahedral or octahedral. Since there is only a small difference in stability between them the two forms sometimes exist in equilibrium. The large monodentate ligands  $\text{Cl}^-$ ,  $\text{Br}^-$ ,  $\text{I}^-$ ,  $\text{OH}^-$  and  $\text{SCN}^-$  commonly form tetrahedral complexes. Co(+II) forms more tetrahedral complexes than any other transition metal ion. This is associated with the fairly small loss of crystal field stabilization energy of  $0.27\Delta_o$  with a  $d^7$  ion in a weak ligand field (see Table 7.15).

The blue coloured complex  $\text{Hg}[\text{Co}(\text{NCS})_4]$  is unusual. The  $\text{Co}^{2+}$  is tetrahedrally coordinated by N atoms, and  $\text{Hg}^{2+}$  is tetrahedrally coordinated by S atoms, giving a polymeric solid. This compound is often used to calibrate a magnetic balance when measuring magnetic moments.


Most Co(+II) complexes are high spin, but the  $\text{CN}^-$  ligand produces low-spin complexes. If a solution of a  $\text{Co}^{2+}$  salt is treated with excess  $\text{CN}^-$  a green coloured complex  $[\text{Co}(\text{CN})_5]^{3-}$  is formed. This can be isolated as the barium salt. It is a good catalyst for the hydrogenation of alkenes. The complex is paramagnetic with one unpaired electron, and its shape is a square pyramid. It may dimerize to give purple  $[\text{Co}_2(\text{CN})_{10}]^{6-}$ , which is diamagnetic and has the structure  $(\text{CN})_5\text{Co}-\text{Co}(\text{CN})_5$  similar to the carbonyl  $\text{Mn}_2(\text{CO})_{10}$ . It is interesting that  $[\text{Co}^{\text{II}}(\text{CN})_5]^{3-}$  is formed instead

of an octahedral complex  $[\text{Co}^{\text{II}}(\text{CN})_6]^{4-}$ . A low spin octahedral complex would have the configuration  $(t_{2g})^6 (e_g)^1$  and as the  $e_g$  level is not symmetrically filled it would suffer from Jahn-Teller distortion. The CN ligand is a strong  $\pi$  acceptor i.e. it accepts electrons from the metal in back bonding. Back bonding increases the crystal field splitting  $\Delta$  which makes the  $e_g$  orbitals very high in energy and thus strongly antibonding. If an octahedral complex was formed these high energy  $e_g$  orbitals must contain one electron. This makes the octahedral complex too unstable to exist. (In marked contrast  $\text{Co}(+\text{III})$  has the configuration  $(t_{2g})^6 (e_g)^0$  and the octahedral complex  $[\text{Co}^{\text{III}}(\text{CN})_6]^{3-}$  is extremely stable).

The  $[\text{Co}^{\text{II}}(\text{CN})_5]^{4-}$  complex is oxidized by air to give a brown coloured peroxo complex  $\text{K}_6[(\text{CN})_5\text{Co}^{\text{III}}-\text{O}-\text{O}-\text{Co}^{\text{III}}(\text{CN})_5]$  which is discussed under (+III) complexes.

Less commonly  $\text{Co}(+\text{II})$  forms square planar complexes with bidentate ligands such as dimethylglyoxime and with tetradentate ligands such as porphyrins. Magnetic measurements can be used to distinguish between tetrahedral and square planar arrangements. Tetrahedral complexes have three unpaired electrons and square planar only one.

$\text{Co}^{2+}$  ions are very stable and are difficult to oxidize.  $\text{Co}^{3+}$  ions are less stable and are reduced by water. In contrast many  $\text{Co}(+\text{II})$  complexes are readily oxidized to  $\text{Co}(+\text{III})$  complexes and  $\text{Co}(+\text{III})$  complexes are very stable.



This happens because the crystal field stabilization energy of  $\text{Co}(+\text{III})$  with a  $d^6$  configuration is higher than for  $\text{Co}(+\text{II})$  with a  $d^7$  arrangement (Figure 25.5).

Certain porphyrin complexes of  $\text{Co}(+\text{II})$  are structurally similar to haemoglobin (Figure 25.6).




Figure 25.5 Electronic arrangements for  $d^6$  and  $d^7$  ions in a strong octahedral field




Figure 25.6 Vitamin B<sub>12</sub>. The corrin ring is shown in heavy type.

The complex (Figure 25.7) is a Schiff's base and is capable of reversible oxygenation and deoxygenation in pyridine solution at room temperature. Though Co complexes are not involved in oxygen metabolism in the body, they serve as useful models for metal-oxygen binding in biological systems.




Figure 25.7 A complex of Co(+II) with both N and O donors.

Ferrocene-like complexes are formed by Co and Rh. Cobaltocene [Co<sup>II</sup>( $\eta^5$ -C<sub>5</sub>H<sub>5</sub>)<sub>2</sub>] is formed by reacting sodium cyclopentadienide NaC<sub>5</sub>H<sub>5</sub> with anhydrous CoCl<sub>2</sub> in tetrahydrofuran. It is dark purple, and is air sensitive. It is easily oxidized (i.e. loses an electron) to form the very stable yellow coloured ion [Co<sup>III</sup>( $\eta^5$ -C<sub>5</sub>H<sub>5</sub>)<sub>2</sub>]<sup>+</sup>. The latter is not oxidized even by concentrated HNO<sub>3</sub>, but like ferrocene the rings are attacked by nucleophilic

reagents Rhodocene  $[\text{Rh}^{\text{II}}(\eta^5\text{-C}_5\text{H}_5)_2]$  is rather less stable, and tends to dimerize

Rhodium and iridium form few (+II) compounds. The existence of  $\text{RhO}$  is uncertain, and  $\text{IrCl}_2$  exists as a polymer. There appear to be no complexes comparable with those of  $\text{Co}(\text{+II})$ . However, if  $\text{RhCl}_3 \cdot 3\text{H}_2\text{O}$  is warmed with a solution of sodium acetate in methanol, a dimeric diacetate is formed  $\text{HOH}_3\text{C Rh (R COO)}_4 \text{ Rh CH}_3\text{OH}$ . The four carboxylate groups bridge the two Rh atoms, giving a structure like that for chromium(II) acetate (Figure 22.2). This has a M—M bond length of  $2.39 \text{ \AA}$  which is interpreted as a quadruple M—M bond. Some complexes with phosphine ligands are known.

### (+III) STATE

This is the most common oxidation state for all three metals, particularly in complexes.  $\text{Co}(\text{+III})$  occurs in only a few simple compounds such as  $\text{Co}_2(\text{SO}_4)_3 \cdot 18\text{H}_2\text{O}$ ,  $\text{NH}_4\text{Co}(\text{SO}_4)_2 \cdot 12\text{H}_2\text{O}$  and  $\text{KCo}(\text{SO}_4)_2 \cdot 12\text{H}_2\text{O}$ . These are blue coloured and contain the hexaaqua ion  $[\text{Co}(\text{H}_2\text{O})_6]^{3+}$ . They are all strongly oxidizing.  $\text{Co}_2\text{O}_3$  is not known in the pure state, only as a hydrated oxide which oxidizes water.  $\text{CoF}_3$  is a light brown solid, which is made from  $\text{CoF}_2$  and  $\text{F}_2$ .  $\text{CoF}_3$  is rapidly hydrolysed by water. It is commonly used as a strong fluorinating agent as it is easier to handle and is less reactive than  $\text{F}_2$ . Anhydrous  $\text{Co}^{\text{III}}(\text{NO}_3)_3$  may be prepared from  $\text{CoF}_3$  in a non aqueous solvent such as  $\text{N}_2\text{O}_4$  or  $\text{N}_2\text{O}_5$  at low temperatures. It has an unusual structure with Co at the centre of an octahedron of O atoms from three bidentate  $\text{NO}_2^-$  groups. The chemistry of  $\text{Co}(\text{+III})$  is largely that of its coordination compounds.

The oxide  $\text{Co}_3\text{O}_4$  is black and is formed by heating the metal in air at  $500^\circ\text{C}$ . It has a spinel structure like  $\text{Fe}_3\text{O}_4$ . These are better written  $\text{Fe}^{\text{II}}\text{Fe}^{\text{III}}_2\text{O}_4$  and  $\text{Co}^{\text{II}}\text{Co}^{\text{III}}_2\text{O}_4$ . In this structure the O atoms are approximately close packed. The larger low spin  $\text{Co}(\text{+III})$  ions occupy half of the octahedral holes and the smaller high-spin  $\text{Co}(\text{+II})$  are in one eighth of the tetrahedral holes.

$\text{Co}(\text{+III})$  complexes are produced easily, in contrast to the difficulty in preparing compounds with simple  $\text{Co}^{3+}$  ions.  $\text{Co}(\text{+III})$  forms more complexes than any other element.

Some common complexes are listed below with their colours. It can be seen that the cobalt can form cation, anion and neutral complexes.

$[\text{Co}(\text{NH}_3)_6]^{3+}$	yellow
$[\text{Co}(\text{NH}_3)_5 \text{H}_2\text{O}]^{3+}$	pink
$[\text{Co}(\text{NH}_3)_5\text{Cl}]^{2+}$	purple
$[\text{Co}(\text{NH}_3)_4\text{CO}_3]^+$	purple
$[\text{Co}(\text{NH}_3)_3(\text{NO}_2)_3]$	yellow
$[\text{Co}(\text{CN})_6]^{3-}$	violet
$[\text{Co}(\text{NO}_2)_6]^{3-}$	orange


Practically all complexes of Co(+III) have six ligands in an octahedral arrangement. The metal has a  $d^6$  configuration, and most of the ligands are strong enough to cause spin pairing, giving the electronic arrangement  $(t_{2g})^6 (e_g)^0$ . This arrangement has a very large crystal field stabilization energy. Such complexes are diamagnetic. The one exception is  $[\text{CoF}_6]^{3-}$  which is a high-spin complex, and is paramagnetic. Complexes with nitrogen donor ligands (ammonia and amines) are the most common.

These complexes may be prepared by oxidation of a solution containing  $\text{Co}^{2+}$  with air or  $\text{H}_2\text{O}_2$  in the presence of appropriate ligands and a catalyst such as activated charcoal. It is also possible to substitute ligands in an existing complex. The complexes are very stable, and ligand exchange (substitution) reactions occur only slowly. This is the reason why complexes of Co(+III) have been so extensively studied since the 1890s by Werner and others. Much of our knowledge on the stereochemistry, isomerism and general properties of octahedral complexes has come from these studies.

$\text{Co}^{3+}$  has an affinity for N donors such as  $\text{NH}_3$ , ethylenediamine, amines, EDTA and the nitrite ion  $\text{NO}_2^-$ . The salt sodium cobaltinitrite  $\text{Na}_3[\text{Co}(\text{NO}_2)_6]$  is an orange coloured solid. It is used in both qualitative and quantitative analysis to precipitate  $\text{K}^+$  as  $\text{K}_3[\text{Co}(\text{NO}_2)_6]$ . The complex  $[\text{Co}(\text{CN})_6]^{3-}$  is extremely stable and is not decomposed even by alkalis. The  $\text{CN}^-$  ligands are very firmly bonded by  $\pi$  back bonding, and the crystal field stabilization energy is very high. The complex is claimed to be non-toxic.

An aqueous solution containing  $[\text{Co}^{\text{II}}(\text{CN})_5]^{3-}$  and KCN can be oxidized by air to give a brown coloured complex  $\text{K}_6[(\text{CN})_5\text{Co}^{\text{III}}-\text{O}-\text{O}-\text{Co}^{\text{III}}(\text{CN})_5]$ . The peroxo bond length  $\text{O}-\text{O}$  is  $1.45 \text{ \AA}$  compared with  $1.48 \text{ \AA}$  in  $\text{H}_2\text{O}_2$ . This complex can be oxidized by air, or better by  $\text{Br}_2$ , to give a red complex  $\text{K}_5[(\text{CN})_5\text{Co}-\text{O}-\text{O}-\text{Co}(\text{CN})_5]$ . Whilst this might contain  $\text{Co}^{\text{III}}$  and  $\text{Co}^{\text{IV}}$ , the X-ray structure shows that the  $\text{O}-\text{O}$  bond length is very much shorter than before at  $1.26 \text{ \AA}$ . The reason for this shortening is that an antibonding electron has been removed from the  $\text{O}-\text{O}^{2-}$  ion and this has now become a superoxide linkage with a bond order of 1.5 (see Chapter 4). If solutions of the peroxo or superoxo complexes are boiled, yellow coloured  $\text{K}_3[\text{Co}(\text{CN})_6]$  is formed.

Several different isomers are found in complexes with the bidentate ligands such as ethylenediamine (en), acetylacetonate or oxalate ions:



The complex potassium tris(ethylenediamine)cobalt(III) contains the  $[\text{Co}^{\text{III}}(\text{en})_3]^{3+}$  ion which is optically active and exists in *d* and *l* forms (see Chapter 7 under 'Isomerism'). A similar preparation in the presence of HCl gives the dark green salt *trans*- $[\text{Co}^{\text{III}}(\text{en})_2(\text{Cl})_2]^{2+}$  which on careful evaporation of a neutral solution gives the purple *cis* isomer. Both isomers undergo substitution reactions on heating with water, giving first  $[\text{Co}(\text{en})_2(\text{Cl})(\text{H}_2\text{O})]^{2+}$  then  $[\text{Co}(\text{en})_2(\text{H}_2\text{O}_2)]^{3+}$ . Similar substitution reactions occur with other ligands such as  $\text{NCS}^-$ , giving  $[\text{Co}(\text{en})_2(\text{NCS})_2]^+$ .

Complexes with O donors are generally less stable but those with chelating ligands such as  $[\text{Co}(\text{acetylacetonate})_3]$  and  $[\text{Co}(\text{oxalate})_3]^{3-}$  are stable and are optically active

Halogen complexes are rare and  $[\text{CoF}_6]^{3-}$  is the only hexahalide complex known This is blue as is  $[\text{CoF}_3(\text{H}_2\text{O})_3]$  and both are unusual because they are high spin and hence are paramagnetic with a magnetic moment of about 5.8 Bohr magnetons

Vitamin  $\text{B}_{12}$  is an important Co complex The vitamin was isolated from liver after it was found that eating large quantities of raw liver was an effective treatment for pernicious anaemia Injections of vitamin  $\text{B}_{12}$  are now used for treatment (more pleasant than eating raw liver!) Vitamin  $\text{B}_{12}$  is a coenzyme and serves as a prosthetic group which is tightly bound to several enzymes in the body but the precise role of vitamin  $\text{B}_{12}$  is not fully understood Dorothy Crowfoot Hodgkin was awarded the Nobel Prize for Chemistry in 1964 for X ray crystallographic work including solving the structure of this enzyme The complex contains a  $\text{Co}(+\text{III})$  ion at the centre of a corrin ring system (Figure 25.6) This is similar to the arrangement of  $\text{Fe}(+\text{II})$  in a porphyrin ring in haemoglobin except that the corrin ring is less conjugated and rings A and D are joined directly The Co atom is bonded to four ring N atoms The fifth position is occupied by another N from a side chain ( $\alpha$ -5,6-dimethylbenzimidazole) and this is also attached to the corrin ring The sixth group which makes up the octahedron is the active site and is occupied by a CN group in cyanocobalamin The CN is introduced in isolating the coenzyme and is not present in the active form in living tissue This position is occupied by OH in hydroxocobalamin by water or by an organic group such as  $\text{CH}_3$  (methylcobalamin) or adenosine This shows that a metal to carbon  $\sigma$  bond can be formed The cobalamins can be reduced from  $\text{Co}^{\text{III}}$  to  $\text{Co}^{\text{II}}$  and  $\text{Co}^{\text{I}}$  in neutral or alkaline solutions both in the laboratory and in vivo (in the living body) The  $\text{Co}^{\text{I}}$  complex is strongly reducing Its structure is five coordinate i.e. the site usually occupied by CN or OH is vacant


Methylcobalamin is important in the metabolism of certain bacteria which produce methane These bacteria can also transfer a methyl group  $\text{CH}_3$  to a few metals such as  $\text{Pt}^{\text{II}}$ ,  $\text{Au}$  and  $\text{Hg}^{\text{II}}$  The latter poses a considerable ecological problem as the bacteria can transform elemental Hg or inorganic Hg salts into highly toxic methyl mercury  $\text{CH}_3\text{Hg}^+$  or dimethyl mercury  $(\text{CH}_3)_2\text{Hg}$  at the bottom of lakes

Cobalt is also biologically important in some enzymes Glutamic mutase is involved in the metabolism of amino acids and ribonucleotide reductase in the biosynthesis of DNA Traces of cobalt are essential in the diet of animals Some sheep raised in Australia New Zealand Florida and Britain suffered from a deficiency disease which was traced to them grazing on cobalt deficient soil This can be remedied either by treating the soil periodically or by forcing the animals to swallow a pellet of cobalt This pellet remains in the rumen and slowly releases cobalt into the gut (Sometimes the animals are made to swallow a metal screw as well This too remains in the rumen and its purpose is to scrape any coating off the

cobalt pellet. The pellet is recovered and reused when the animals are slaughtered.) Larger amounts of cobalt appear to be harmful. Traces of cobalt (1–1.5 ppm) are added to beer to make it froth better. This has been linked with an increased rate of heart failure among heavy beer drinkers who have a dietary deficiency of protein or thiamine.


All the (+III) halides  $RhX_3$  and  $IrX_3$  are known.  $RhF_3$  is prepared by fluorinating  $RhCl_3$ ,  $IrF_3$  by reducing  $IrF_6$  with Ir, and the others by direct reaction. They are all insoluble in water, unreactive and probably have layer lattices. The oxide  $Rh_2O_3$  is obtained by burning the metal in air.  $Ir_2O_3$  is only obtained with difficulty as the hydrated oxide, by adding alkali to  $Ir^{III}$  solutions under an inert atmosphere, as it oxidizes easily to  $Ir^{IV}O_2$ . In contrast to the oxidizing properties of  $[Co^{III}(H_2O)_6]^{3+}$ ,  $[Rh^{III}(H_2O)_6]^{3+}$  exists as a stable yellow coloured ion.

A considerable number of  $Rh(+III)$  and  $Ir(+III)$  complexes are known. Like the complexes of  $Co(+III)$  they are typically octahedral, stable, low spin and diamagnetic, e.g.  $[RhCl_6]^{3-}$ ,  $[Rh(H_2O)_6]^{3+}$ , and  $[Rh(NH_3)_6]^{3+}$ . The chloride complexes are made by heating finely divided Rh or Ir with a Group 1 metal chloride and chlorine.



The complex  $Na_3[RhCl_6] \cdot 12H_2O$  is red coloured and is the best known compound of rhodium. On boiling with water it gives  $[Rh(H_2O)_6]^{3+}$ , and with NaOH it gives  $Rh_2O_3 \cdot H_2O$ . The yellow coloured hydrated ion is converted back to the chloro complex with HCl. If  $Rh_2O_3 \cdot H_2O$  is treated with a limited amount of HCl then  $[RhCl_3 \cdot 3H_2O]$  is formed, but with excess acid  $[RhCl_6]^{3-}$  is formed instead.  $[RhCl_3 \cdot 3H_2O]$  is octahedral, and should exist as two different isomeric forms *fac* and *mer* (see Figure 7.3).

A small number of complexes are known which are not octahedral, e.g.  $[RhBr_5]^{2-}$  and  $[RhBr_7]^{4-}$ . Metal–metal bonds are found in a few complexes:



$Rh(+III)$  and  $Ir(+III)$  form basic acetates  $[Rh_3O(CH_3COO)_6L_3]^+$  which have unusual structures. The Rh atoms form a triangle with an O atom at the centre. The six acetate groups act as bridges between the Rh atoms – two acetate groups across each edge of the triangle. Thus each Rh atom is linked to four acetate groups and the central O, and the sixth position of the octahedron is occupied by water or another ligand. The magnetic moment is reduced due to partial pairing of *d* electrons on the three metal atoms by means of *dπ*–*pπ* bonding through O. This type of carboxylate complex is also formed by the trivalent ions of Cr, Mn, Fe, Ru, Rh and Ir.

Several hydride complexes are also known:  $[Rh(R_3P)_3 \cdot H \cdot Cl_2]^{2+}$  and  $[Ir(R_3P)_3 \cdot H \cdot Cl_2]^{2+}$ ,  $[Ir(R_3P)_3 \cdot H_2Cl]^{4+}$  and  $[Ir(R_3P)_3H_3]^{6+}$ . Reduction of  $Rh(+III)$  and  $Ir(+III)$  complexes gives the metal, whereas reduction of  $Co(+III)$  gives  $Co(+II)$ .





Figure 25.8 Structure of  $[Rh_3O(CH_3COO)_6(H_2O)_3]^+$



### {+IV} STATE




This is the highest oxidation state normally obtained for cobalt. Oxidation of alkaline  $\text{Co}^{2+}$  solutions gives an ill defined product thought to be hydrated  $\text{CoO}_2$ , and a complex  $\text{Ba}_2\text{Co}^{\text{IV}}\text{O}_4$  has been reported.

If the activated charcoal catalyst is omitted from the preparation of  $[\text{Co}(\text{NH}_3)_6]^{3+}$  by the air oxidation of  $\text{Co}^{2+}$ , then a brown compound containing  $[(\text{NH}_3)_5\text{Co}^{\text{III}}-\text{O}-\text{O}-\text{Co}^{\text{III}}(\text{NH}_3)_5]^{4+}$  can be isolated. This is stable in concentrated  $\text{NH}_4\text{OH}$  solution, or as the solid but can be oxidized by strong oxidizing agents such as persulphate  $(\text{S}_2\text{O}_8)^{2-}$  to give a green peroxo complex which formally contains  $\text{Co}(+\text{IV})$ .



The magnetic moment of the green complex is about 1.7 Bohr magnetons. This is in agreement with the presence of  $\text{Co}(+\text{III})$  ( $d^6$  low spin, diamagnetic) and  $\text{Co}(+\text{IV})$  ( $d^5$  low spin, one unpaired electron). However, electron spin resonance indicates that both Co atoms are identical. Thus an electron must be able to move across the peroxo bridge and spend an equal amount of time on both metal atoms.

Several other binuclear complexes are known which use  $-\text{O}-\text{O}-$ ,  $\text{OH}^-$ ,  $\text{NH}_2^-$  or  $\text{NH}^{2-}$  as bridging groups.



$\text{Ir}(+\text{IV})$  is one of the most stable states but  $\text{Rh}(+\text{IV})$  is unstable and forms few compounds. Both metals form tetrafluorides.  $\text{RhF}_4$  can be made from  $\text{RhCl}_3$  and  $\text{BrF}_3$ .  $\text{IrCl}_4$  is not very stable.  $\text{IrO}_2$  is formed by burning the metal in air, but  $\text{RhO}_2$  is only formed by strongly oxidizing  $\text{Rh}(+\text{III})$  in alkaline solution, for example with sodium bismuthate. Rhodium forms only a few complexes, e.g.  $\text{K}_2[\text{RhF}_6]$  and  $\text{K}_2[\text{RhCl}_6]$  but these react with water, liberating  $\text{O}_2$  and eventually forming  $\text{RhO}_2$ . Iridium forms a variety of halide and aqua complexes  $[\text{IrCl}_6]^{2-}$ ,  $[\text{IrCl}_3(\text{H}_2\text{O})_3]^+$ ,  $[\text{IrCl}_4(\text{H}_2\text{O})_2]$  and  $[\text{IrCl}_5(\text{H}_2\text{O})]^-$ . The oxalate complex  $[\text{Ir}(\text{oxalate})_3]^{3-}$  can be resolved into *d* and *l* optical isomers.

## ND (+VI) STATES

' compounds do not exist under normal conditions. Rh(+V) and exist as pentafluorides (RhF<sub>5</sub>)<sub>4</sub> and (IrF<sub>5</sub>)<sub>4</sub>. These are very reactive readily hydrolysed. They have a tetrameric structure with M—F—M similar to Nb, Ta, Mo, Ru and Os (Figure 21.1). The only compounds known are Cs[RhF<sub>6</sub>] and Cs[IrF<sub>6</sub>].

VI) and Ir(+VI) occur only in RhF<sub>6</sub> and IrF<sub>6</sub>, which are made by reaction. Neither is stable, though the heavier IrF<sub>6</sub> is more stable F<sub>6</sub>.

## FURTHER READING

W. and Stone, F.G. (1969, 1970) The chemistry of transition metal compounds, *Q. Rev. Chem. Soc.*, Part I – Structural considerations, **23**, 325; Part II – Synthesis and reactivity, **24**, 498.

D. (1973) Complexes of dinitrogen, *Chem. Rev.*, **73**, 11.

ord, J.H. and Cotton, R. (1968) *Halides of the Second and Third Row Transition Elements*, Wiley, London.

ord, J.H. and Cotton, R. (1969) *Halides of the First Row Transition Elements*, Wiley, London.

*metals and metallic clusters* (1980) (Conference papers of the Faraday Division of the Royal Society of Chemistry, No. 14), Royal Society of Chemistry, London.

, H.J. and Sharpe, A.G. (1973) *Modern Aspects of Inorganic Chemistry*, 2nd ed. (Chapters 14 and 15: Complexes of Transition Metals: Chapter 20: Carbonyls), Routledge and Kegan Paul, London.

, B.T. (1983) Cobalt and vitamin B<sub>12</sub>, *Education in Chemistry*, **20**, 207.

W. P. (1973) *Comprehensive Inorganic Chemistry*, Vol. 4 (Chapter 46: Carbonyls, cyanides, isocyanides and nitrosyls), Pergamon Press, Oxford.

, B.F.G. (1976) The structures of simple binary carbonyls, *JCS Chem. Commun.*, 211–213.

, B.F.G. (ed.) (1980) *Transition Metal Clusters*, John Wiley, Chichester.

, W. and McAuliffe, C.A. (1974) Higher oxidation state chemistry of iron, cobalt and nickel, *Coordination Chem. Rev.*, **12**, 151–184.

, and Green, M.L. (eds) (1983) *Metal Clusters in Chemistry* (Proceedings of Royal Society Discussion Meeting May 1982), The Society, London.

, D. (1973) *Comprehensive Inorganic Chemistry*, Vol. 3 (Chapter 41: Carbonyls), Pergamon Press, Oxford.

D.A. (1976) *Metals and Metabolism*, Oxford University Press, Oxford.

# 26

## Group 10 – the nickel group

**Table 26 1** Electronic structures and oxidation states

Element		Electronic structure	Oxidation states*
Nickel	Ni	[Ar] $3d^8 4s^2$	-1 0 (I) <b>II</b> (III) (IV)
Palladium	Pd	[Kr] $4d^{10}$	0 (I)? <b>II</b> IV
Platinum	Pt	[Xe] $4f^{14} 5d^9 6s^1$	0 (I) <b>II</b> (III)? IV (V) (VI)

\* The most important oxidation states (generally the most abundant and stable) are shown in bold. Other well characterized but less important states are shown in normal type. Oxidation states that are unstable or in doubt are given in parentheses.

### INTRODUCTION

Nickel is moderately abundant and is produced in large quantities. It is used in large quantities in a wide variety of alloys, both ferrous and non ferrous. It is predominantly divalent and ionic in simple compounds, and exists as Ni(+II) in the most of its complexes. These are commonly square planar or octahedral. Palladium and platinum are both rare and expensive. They are noble and not very reactive but are slightly more reactive than the other platinum group metals. They are both used as catalysts. The most common oxidation states are Pd(+II) and Pt(+II) and Pt(+IV). These are not ionic.

### OCCURRENCE, EXTRACTION AND USES

#### Nickel

Nickel is the twenty second most abundant element by weight in the earth's crust. Commercially important Ni ores include sulphides, which are usually mixed with Fe or Cu sulphides, and alluvial deposits of silicates and oxides/hydroxides. Pentlandite  $(Fe,Ni)_9S_8$  is the most important ore. It always has a Fe : Ni ratio of 1 : 1. It usually occurs with a form of FeS called pyrrhotite – both are bronze coloured, and are found in the USSR, Canada, and South Africa. Several other sulphide and arsenide ores such as millerite NiS, niccolite NiAs and nickel glance NiAsS were

once important, but are now little used. Important alluvial deposits include garnierite, a magnesium–nickel silicate of variable composition  $(\text{Mg,Ni})_6\text{Si}_4\text{O}_{10}(\text{OH})_8$ , and nickeliferous limonite  $(\text{Fe,Ni})\text{O}(\text{OH})(\text{H}_2\text{O})_n$ . Mine production of ore contained 850 000 tonnes of Ni in 1992. The main sources of ore were Canada 23%, the Soviet Union 21%, and New Caledonia 12%.


The extraction of Ni is complicated by the presence of other metals. Sulphide ores now provide most of the nickel produced. The ore is concentrated by flotation and magnetically, then heated with  $\text{SiO}_2$ .  $\text{FeS}$  decomposes to  $\text{FeO}$ , which reacts with  $\text{SiO}_2$  to form slag  $\text{FeSiO}_3$ , which

**Table 26.2** Abundance of the elements in the earth's crust, by weight

	ppm	Relative abundance
Ni	99	22
Pd	0.015	69
Pt	0.01	70

is easily removed. The remaining sulphide matte is cooled slowly giving an upper silvery layer of  $\text{Cu}_2\text{S}$  and a lower black layer of  $\text{Ni}_2\text{S}_3$  which can be separated mechanically. (A small amount of metallic Cu/Ni alloy is also formed. This dissolves any of the platinum group metals present, and is used as a source of these rare and expensive elements.) The  $\text{Ni}_2\text{S}_3$  is then roasted with air and converted to  $\text{NiO}$ . This may be used directly in steel making. Alternatively  $\text{NiO}$  may be reduced to the metal by carbon in a smelter. The metal is cast into electrodes which are purified by electrolysis in an aqueous solution of  $\text{NiSO}_4$ .

The Mond process provides an alternative method for producing high purity Ni. This process was patented by L. Mond and was used in South Wales from 1899 until about 1970.  $\text{NiO}$  and water gas ( $\text{H}_2$  and  $\text{CO}$ ) were warmed under atmospheric pressure to  $50^\circ\text{C}$ . The  $\text{H}_2$  reduced  $\text{NiO}$  to Ni, which in turn reacted with  $\text{CO}$ , forming volatile nickel carbonyl  $\text{Ni}(\text{CO})_4$ . (This is highly toxic and flammable.) Any impurities remained solid. The gas was heated to  $230^\circ\text{C}$ , when it decomposed to give pure metal and the  $\text{CO}$  was recycled. A new plant in Canada now uses  $\text{CO}$  and impure metal, but runs at  $150^\circ\text{C}$  and 20 atmospheres pressure to form  $\text{Ni}(\text{CO})_4$ .



Nickel silicate ores such as garnierite are mixed with gypsum ( $\text{CaSO}_4$ ) and smelted with coke. The silicates form  $\text{CaSiO}_3$  slag, and the Ni forms a sulphide matte which is treated as above.

Most of the Ni produced is used to make ferrous and non-ferrous alloys. Ni improves both the strength of steel and its resistance to chemical attack. In 1991, 569 000 tonnes of ferronickel were produced. Stainless steel may

*continued overleaf*

contain 12–15% Ni and steel for cutlery contains 20% Cr and 10% Ni. Very strong permanent magnets are made from Alnico steel. Monel metal is very resistant to corrosion and is used in apparatus to handle  $F_2$  and other corrosive fluorides. It contains 68% Ni, 32% Cu and traces of Fe and Mn. Several non ferrous alloys are important. The Nimonic series of alloys (75% Ni with Cr, Co, Al and Ti) are used in gas turbine and jet engines where they are subjected to high stresses and high temperatures. Others such as Hastelloy C are used for their corrosion resistance. Nichrome contains 60% Ni and 40% Cr and is used to make the wire which gets red hot in electric radiators. Cupro nickel (80% Cu and 20% Ni) is used to make silver coins. The so called nickel–silver contains roughly 60% Cu, 20% Ni and 20% Zn. This is used to make imitation silver articles and can be electroplated on other metals to give EPNS (electroplated nickel–silver). The name nickel–silver is confusing as it contains no silver. Often steel is electroplated with Ni before electroplating with Cr. Some Ni is used in Ni/Fe storage batteries which have the advantage that they can be charged at very fast rates without damaging the battery plates. Small amounts of very finely divided Ni (Raney Ni) are used for many reduction processes. Examples include the manufacture of hexamethylenediamine, the production of  $H_2$  from  $NH_3$  and the reduction of anthraquinone to anthraquinol in the production of  $H_2O_2$ .

#### Palladium and platinum

Pd and Pt are rare elements but they are appreciably more abundant than the other platinum group metals (Ru, Os, Rh and Ir). World production of all six platinum group metals was only 281 tonnes in 1992. Nearly 100 tonnes of this was Pt. Even though Pd is slightly more abundant than Pt, production of Pt is greater than that of Pd. The largest sources were South Africa 54%, the Soviet Union 37% and Canada 4%. South African sources yield more Pt than Pd but Soviet sources yield more Pd than Pt.

The platinum group metals occur as traces in the sulphide ores of Cu and Ni. They are obtained as concentrates as anode sludge from electrolytic processes for the major metals. The platinum group metals are also obtained from the Cu/Ni alloy produced in the separation of the sulphide matte of  $Cu_2S$  and  $Ni_3S_2$  in the process outlined for Ni above. Separation of the platinum metals is complex but in the last stages  $(NH_4)_2[PtCl_6]$  and  $[Pd(NH_3)_2Cl]$  are ignited to give the respective metals. The metals are obtained as powders or sponges and are fabricated into solid objects by sintering.

Roughly one third of the Pt produced is used in jewellery, one third in cars and one third for investment and for industrial uses. Pt has been used in jewellery since several centuries BC. The earliest users were the ancient Egyptians and the Indians of Peru and Ecuador. Nowadays it is often used to make the mountings for diamonds in rings and other jewellery. It resembles silver and has been called white gold. Rather confusingly this name is now used for a Pd/Au alloy.

A new and increasing use of Pt is in 'three-way catalytic convertors'. These convertors are fitted to many new cars to reduce pollution from the exhaust gases. It is essential that lead-free petrol is used in the car. The main component of the convertor is a ceramic honeycomb which is coated with Pt, Pd and Rh. The exhaust gases from the engine exhaust pass through the honeycomb at about 300°C. The precious metals convert unburnt fuel, CO and oxides of nitrogen into harmless CO<sub>2</sub> and N<sub>2</sub>. (Leaded petrol must not be used as Pb poisons the catalyst.)

Both Pd and Pt find extensive chemical uses as catalysts. PdCl<sub>2</sub> is used in the Wacker process for converting C<sub>2</sub>H<sub>4</sub> to CH<sub>3</sub>CHO. Pd is used for hydrogenations such as phenol to cyclohexanone, and also for dehydrogenations. Pt is very important as a catalyst in the oil industry in the reforming of hydrocarbons. Pt/PtO is used as Adam's catalyst for reductions. At one time Pt was used in the Contact process in the manufacture of H<sub>2</sub>SO<sub>4</sub> (to convert SO<sub>2</sub> to SO<sub>3</sub>); V<sub>2</sub>O<sub>5</sub> is now used as catalyst instead of Pt as it is cheaper and less susceptible to poisoning. A Pt/Rh alloy was formerly used to oxidize NH<sub>3</sub> to NO in the Ostwald process for making HNO<sub>3</sub>.

In the laboratory Pt crucibles are sometimes used and Pt is also used to make apparatus to handle HF. Pt is also used to seal into soda glass to allow electrical connections to pass through the glass. This is important in making electrodes, thermionic valves etc. Soda glass and Pt have almost the same coefficient of expansion, so the glass does not crack on cooling.

## OXIDATION STATES

Ni shows a range of oxidation states from (–I) to (+IV), but its chemistry is predominantly that of the (+II) state. [Ni(H<sub>2</sub>O)<sub>6</sub>]<sup>2+</sup> ions are green coloured and are stable both in solution and in many simple compounds. Ni(+II) also forms many complexes, which are mainly square planar or octahedral. The higher oxidation states of all three metals are unstable.

Pd(+II) is the most important state, and occurs as the hydrated ion [Pd(H<sub>2</sub>O)<sub>4</sub>]<sup>2+</sup> and in complexes. Pt does not form an aqua ion. Both Pt(+II) and Pt(+IV) are important, but these are not ionic. The (+II) complexes are square planar and (+VI) complexes are octahedral.

Zero-valent states occur for all three elements with  $\pi$  bonding ligands such as CO. The maximum oxidation state of (+VI) is only attained in PtF<sub>6</sub>, and Pt(+V) occurs in [PtF<sub>6</sub>]<sup>–</sup>. The highest oxidation state attained by Ni and Pd is (+IV) in NiF<sub>4</sub> and PdF<sub>4</sub>. The so-called PdF<sub>3</sub> does not contain Pd<sup>III</sup> but is really Pd<sup>2+</sup>[Pd<sup>IV</sup>F<sub>6</sub>]<sup>2–</sup>. The oxides and halides formed are shown in Table 26.3.

## GENERAL PROPERTIES

Ni is a silvery white metal, and Pd and Pt are both grey–white. All three elements are unreactive in the massive state. They do not tarnish or react with air or water at normal temperatures.

Ni is often electroplated on to other metals to provide a protective

Table 26 3 Oxides and halides

Oxidation states					
(+II)	(+III)	(+IV)	(+V)	(+VI)	Other
NiO	(Ni <sub>2</sub> O <sub>3</sub> ) <sup>h</sup>	NiO <sub>2</sub> <sup>h</sup>	—	—	
PdO	—	(PdO <sub>2</sub> ) <sup>h</sup>	—	—	
(PtO) <sup>h</sup>	(Pt <sub>2</sub> O <sub>3</sub> ) <sup>h</sup>	PtO <sub>2</sub>	—	(PtO <sub>3</sub> ) <sup>h</sup>	Pt <sub>3</sub> O <sub>4</sub>
NiF <sub>2</sub>	—	—	—	—	
NiCl <sub>2</sub>	—	—	—	—	
NiBr <sub>2</sub>	—	—	—	—	
NiI <sub>2</sub>	—	—	—	—	
PdF <sub>2</sub>	Pd[PdF <sub>6</sub> ]	PdF <sub>4</sub>	—	—	
PdCl <sub>2</sub>	—	—	—	—	
PdBr <sub>2</sub>	—	—	—	—	
PdI <sub>2</sub>	—	—	—	—	
—	—	PtF <sub>4</sub>	(PtF <sub>5</sub> ) <sub>4</sub>	PtF <sub>6</sub>	
PtCl <sub>2</sub>	PtCl <sub>3</sub> <sup>?</sup>	PtCl <sub>4</sub>	—	—	
PtBr <sub>2</sub>	PtBr <sub>3</sub> <sup>?</sup>	PtBr <sub>4</sub>	—	—	
PtI <sub>2</sub>	PtI <sub>3</sub> <sup>?</sup>	PtI <sub>4</sub>	—	—	

The most stable oxidation states are shown in bold unstable ones in brackets  
h = hydrous oxide

Table 26 4 Some physical properties

	Covalent radius (Å)	Ionic radius (Å)		Melting point (°C)	Boiling point (°C)	Density (g cm <sup>-3</sup> )	Pauling's electro- negativity <sup>§</sup>
		M <sup>2+</sup>	M <sup>3+</sup>				
Ni	1.15	0.69	0.60 <sup>h</sup> 0.56 <sup>l</sup>	1455	2920	8.91	1.8
Pd	1.28	0.86	0.76	1552	2940	11.99	2.2
Pt	1.29	0.80	—	1769	4170	21.41	2.2

h = high spin value, l = low spin radius

coating. However, Ni does tarnish when heated in air. Raney Ni is a very finely divided form of Ni used as a catalyst. It is readily oxidized by air and is pyrophoric. Red hot Ni reacts with steam.

Ni dissolves readily in dilute acids, giving hydrated [Ni(H<sub>2</sub>O)<sub>6</sub>]<sup>2+</sup> ions and H<sub>2</sub>. Like Fe and Co it is rendered passive by concentrated HNO<sub>3</sub> and aqua regia. Pd and Pt are more noble (less reactive) than Ni but are more reactive than the other elements in the platinum group. Pd dissolves slowly in concentrated HCl in the presence of O<sub>2</sub> or Cl<sub>2</sub>, and fairly readily in concentrated HNO<sub>3</sub>, giving [Pd<sup>IV</sup>(NO<sub>3</sub>)<sub>2</sub>(OH)<sub>2</sub>]. Pt is the most resistant to acids but dissolves in aqua regia, giving chloroplatinic acid H<sub>2</sub>[PtCl<sub>6</sub>] (see Table 26 5).

Ni is unaffected by aqueous alkalis and is therefore used to make the

Table 26.5 Some reactions of Ni, Pd and Pt

Reagent	Ni	Pd	Pt
O <sub>2</sub>	NiO	PdO at red heat	PtO at high temp. and pressure
F <sub>2</sub>	NiF <sub>2</sub>	Pd <sup>II</sup> [Pd <sup>IV</sup> F <sub>6</sub> ] at 500°C	PtF <sub>4</sub> at red heat
Cl <sub>2</sub>	NiCl <sub>2</sub>	PdCl <sub>2</sub>	PtCl <sub>2</sub>
H <sub>2</sub> O	No action	No action	No action
Dilute HCl or dilute HNO <sub>3</sub>	Ni <sup>2+</sup> + H <sub>2</sub>	Dissolves very slowly	No action
Concentrated HNO <sub>3</sub>	Passive	Dissolves	No action
Aqua regia	Passive	Dissolves	H <sub>2</sub> [PtCl <sub>6</sub> ]

apparatus for manufacturing NaOH. Pd and Pt are both rapidly attacked by fused alkali metal oxides and peroxides, e.g. Na<sub>2</sub>O and Na<sub>2</sub>O<sub>2</sub>.

Ni reacts with the halogens on heating. It reacts only slowly with fluorine, so Ni and alloys such as Monel are often used to handle F<sub>2</sub> and corrosive fluorides. Ni also reacts with S, P, Si and B on heating. Red hot Pd reacts with F<sub>2</sub>, Cl<sub>2</sub> and O<sub>2</sub>. Pt is less reactive but at red heat it reacts with F<sub>2</sub>, and at a high temperature and pressure it reacts with O<sub>2</sub>.

All three metals absorb gaseous H<sub>2</sub>. The amount absorbed depends on the physical state of the metal. However, Pd absorbs very large volumes of H<sub>2</sub>, more than any other metal. If red hot Pd is cooled in H<sub>2</sub> it can absorb 935 times its own volume of H<sub>2</sub>. The hydrogen is mobile and diffuses through the metal lattice. The conductivity of the metal falls as H<sub>2</sub> is absorbed. The H<sub>2</sub> is evolved on heating. Other gases, including He, are not absorbed, so this process is used to purify H<sub>2</sub>.

Pt(+II) and Pt(+IV) form an extremely large number of complexes. (The two most prolific complex forming elements are Co and Pt.)


### LOW VALENCY STATES (-I), (0), (+I)

Ni(-I) is found in the carbonyl anion [Ni<sub>2</sub>(CO)<sub>6</sub>]<sup>2-</sup>.

The zero-valent state is formed by all three metals. [Ni<sup>0</sup>(CO)<sub>4</sub>] is formed by warming Ni and CO. Its formation and subsequent pyrolysis was important in the Mond process for the purification of the metal. Though the original process became obsolete in about 1970, a modified process is used in Canada. [Ni(CO)<sub>4</sub>] is perhaps the best known carbonyl, but its stability is much lower than that of carbonyls in earlier transition metal groups. The [Ni(CO)<sub>4</sub>] molecule is tetrahedral, volatile, very poisonous, easily oxidized and flammable. A phosphine derivative [Ni<sup>0</sup>(PF<sub>3</sub>)<sub>4</sub>], and mixed compounds such as [Ni(CO)<sub>2</sub>(PF<sub>3</sub>)<sub>2</sub>], are also known. Reduction of [Ni<sup>II</sup>(CN)<sub>4</sub>]<sup>2-</sup> by potassium in liquid ammonia gives K<sub>4</sub>[Ni<sup>0</sup>(CN)<sub>4</sub>], whilst reduction with hydrazine sulphate in aqueous



media gives  $K_4[Ni_2(CN)_6]$  Pd and Pt do not form simple carbonyls like  $[Ni(CO)_4]$ , but they do form phosphine complexes such as  $[Pt^0(PPh_3)_4]$  and  $[Pt^0(PPh_3)_3]$



$Pd^0(CO)(PPh_3)_3$  and  $[Pt^0(CO)_2(PPh_3)_2]$  are also known. The ligand CO is a weak  $\sigma$  donor and a strong  $\pi$  acceptor, whilst  $PPh_3$  is a stronger  $\sigma$  donor but a weaker  $\pi$  acceptor. The absence of simple carbonyls for Pd and Pt is probably because they form  $\pi$  bonds less readily than Ni. Introducing a  $\sigma$  bonded ligand such as a halogen reverses the position, and  $[Pt^{II}(CO)_2Cl_2]$  is stable,  $[Pd^{II}(CO)_2Cl_2]$  is not very stable, and Ni does not form any carbonyl halides.  $[Ni(CO)_4]$  is reduced by sodium in liquid ammonia to give a carbonyl hydride  $[Ni(CO)_3H]_2(NH_3)_4$ . This is red coloured and is dimeric. Reduction may also yield cluster compounds such as  $[Ni_5(CO)_{12}]^{2-}$  and  $[Ni_6(CO)_{12}]^{2-}$ . A series of cluster compounds such as  $[Pt_3(CO)_6]^{2-}$  are formed by reducing  $[PtCl_6]^{2-}$  in alkaline solution under an atmosphere of CO. No similar Pd compounds have so far been observed.

### (+II) STATE

The (+II) state is very important for all three elements. A wide variety of simple  $Ni^{2+}$  compounds exist. These include all the halides, the oxide, sulphide, selenide and telluride, salts of all the common acids and also some less stable ones such as  $NiCO_3$  and salts of oxidizing ions like  $Ni(ClO_4)_2$ . The hydrated ion  $[Ni(H_2O)_6]^{2+}$  gives rise to the green colour characteristic of many hydrated Ni salts. Many anhydrous Ni salts are yellow. Double salts are formed with alkali metals and  $NH_4^+$ , for example  $NiSO_4(NH_4)_2SO_4 \cdot 6H_2O$ . These are isomorphous with the corresponding double salts of  $Fe^{2+}$ ,  $Co^{2+}$  and  $Mg^{2+}$ .

Though the chemistry of Ni is simplified by the dominance of the (+II) state, the Ni(+II) complexes are quite complicated. Octahedral and square planar complexes are commonly formed, and a few tetrahedral, trigonal bipyramidal and square-based pyramidal structures are also formed. Pd(+II) and Pt(+II) complexes are all square planar.




Figure 26.1  $d^8$  arrangement in (a) weak and (b) strong octahedral fields

The complexes formed with ammonia  $[\text{Ni}(\text{NH}_3)_6]^{2+}$ ,  $[\text{Ni}(\text{H}_2\text{O})_4(\text{NH}_3)_2]^{2+}$ , and the complex ethylenediamine  $[\text{Ni}(\text{ethylenediamine})_3]^{2+}$  are all octahedral. These octahedral complexes are usually blue in colour, and they are paramagnetic as the  $d^8$  ion has two unpaired electrons (Figure 26.1a). In complexes with strong field ligands such as  $\text{CN}^-$ , the electrons are forced to pair up and diamagnetic square planar complexes such as  $[\text{Ni}(\text{CN})_4]^{2-}$  are formed (Figure 26.1b).

The red coloured complex precipitated by  $\text{Ni}^{2+}$  and dimethylglyoxime from slightly ammoniacal solution is also square planar. However, in the solid the square planar molecules are stacked on top of each other and a Ni–Ni interaction occurs. The Ni–Ni distance is 3.25 Å. This was one of the earliest examples of metal to metal bonding, and in the solid Ni should be regarded as octahedrally coordinated rather than square planar. The formation of this complex is used both for the detection and quantitative estimation of Ni. The dimethylglyoxime loses a proton, and forms a stable complex molecule. The complex is stabilized because two five-membered chelate rings are formed, and also by internal hydrogen bonding, shown by dotted lines in Figure 26.2.




Figure 26.2 Nickel dimethylglyoxime complex.

The square planar complexes are generally red, brown or yellow in colour. The reason for the formation of square planar complexes is discussed further in Chapter 7.

Several tetrahedral  $\text{Ni}(+II)$  complexes are known. These generally contain halide ligands, and often phosphine, phosphine oxide or arsine ligands as well, as in  $[\text{Ph}_4\text{As}]_2^+[\text{NiCl}_4]^{2-}$ ,  $[(\text{Ph}_3\text{P})_2 \cdot \text{NiCl}_2]$  and  $[\text{Ph}_3\text{AsO})_2\text{NiBr}_2]$ . These complexes are typically intensely blue coloured, and can be easily distinguished from square planar complexes both by the colour, and because they are paramagnetic (Figure 26.3).

When nickel cyanide is crystallized from a mixture containing ammonia and benzene, benzene ammino nickel cyanide is formed. The benzene molecules are not bonded, but are trapped in the cagework of the crystal. Such compounds are called clathrates and other molecules of a similar size may be trapped in a similar way.

$\text{Pd}(+II)$  and  $\text{Pt}(+II)$  exist as oxides, halides, nitrates and sulphates. The anhydrous solids are generally not ionic.  $\text{PdO}$  exists in the anhydrous state, but  $\text{PtO}$  is only known as an unstable hydrated oxide. All the dihalides  $\text{MX}_2$  are known except for  $\text{PtF}_2$ . Unlike the other halides,  $\text{PdF}_2$  is ionic.





Figure 26.3  $d^n$  arrangement in tetrahedral field

The  $\text{Pd}^{2+}$  ion has a  $d^8$  configuration and is paramagnetic. The  $[\text{Pd}(\text{H}_2\text{O})_4]^{2+}$  ion exists in water, and is diamagnetic. Because this complex is spin paired it is presumed to have a square planar structure. All  $\text{Pd}(+II)$  and  $\text{Pt}(+II)$  complexes are diamagnetic. In hydrochloric acid the diamagnetic  $[\text{PdCl}_4]^{2-}$  ion is formed. All the other dihalides are molecular or polymeric, and are diamagnetic.  $\text{PdCl}_2$  and  $\text{PtCl}_2$  are made from the elements and both exist in  $\alpha$  and  $\beta$  forms. Which is formed depends on the exact conditions used. The  $\alpha$  forms are the more common.



$\alpha\text{-PdCl}_2$  is a dark red solid, whilst  $\alpha\text{-PtCl}_2$  is olive green.  $\alpha\text{-PdCl}_2$  has a flat chain polymeric structure (Figure 26.4a), in which the Pd atoms are in a square planar arrangement. It is hygroscopic and is soluble in water. The structure of  $\alpha\text{-PtCl}_2$  is not known, but it is insoluble in water, and dissolves in  $\text{HCl}$ , giving  $[\text{PtCl}_4]^{2-}$  ions.

The  $\beta$  forms of  $\text{PdCl}_2$  and  $\text{PtCl}_2$  have an unusual molecular structure. This is based on a  $\text{Pd}_6\text{Cl}_{12}$  or  $\text{Pt}_6\text{Cl}_{12}$  unit. The structure is best described as the metal surrounded by four Cl atoms in a square planar environment.





Figure 26.4 Structures of  $\alpha$  and  $\beta\text{-PdCl}_2$

with six such units linked by halogen bridges (Figure 26.4b). This is remarkably similar in shape to the  $[\text{Nb}_6\text{Cl}_{12}]^{2+}$  cluster compound shown in Figure 21.3d. In this the six Nb atoms were linked in an octahedral cluster with halogen atoms bridging all 12 edges.  $\beta\text{-PdCl}_2$  is soluble in benzene and retains its structure. Despite the similarity in shape, the  $\beta\text{-PdCl}_2$  structure appears to be covalent and stabilized largely by halogen bridges rather than by metal-metal bonding as in  $[\text{Nb}_6\text{Cl}_{12}]^{2+}$ .

An important reaction occurs between  $\text{PdCl}_2$  and alkenes. With ethene, complexes such as  $[\text{Pd}(\text{C}_2\text{H}_4)\text{Cl}_3]^-$ ,  $[\text{Pd}(\text{C}_2\text{H}_4)\text{Cl}_2]_2$  and  $[\text{Pd}(\text{C}_2\text{H}_4)_2\text{Cl}_2]$  are formed.



Similar compounds are known for Pt: for example, Zeise's salt  $\text{K}[\text{Pt}(\text{C}_2\text{H}_4)(\text{Cl})_3] \cdot \text{H}_2\text{O}$  forms yellow crystals and has been known since 1825. The structure of these alkene complexes is unusual. In Zeise's salt the  $[\text{Pt}(\text{C}_2\text{H}_4)(\text{Cl})_3]^-$  ion is essentially square planar with Cl at three corners and  $\text{H}_2\text{C}=\text{CH}_2$  at the other corner. However, the  $\text{H}_2\text{C}=\text{CH}_2$  molecule is perpendicular to the  $\text{PtCl}_3$  plane, and the two C atoms are almost equidistant from the Pt. (The Pt—C distances are 2.128 Å and 2.135 Å.) The C=C distance in the complex is 1.375 Å compared with 1.337 Å in ethene and a C—C distance of 1.54 Å in ethane. Thus the double bond is only lengthened slightly in forming the complex. The double bond occupies the coordination position rather than a single C atom, and  $\text{C}_2\text{H}_4$  acts as a dihapto ligand. Thus the complex should be written  $\text{K}[\text{Pt}(\eta^2\text{-C}_2\text{H}_4)(\text{Cl})_3] \cdot \text{H}_2\text{O}$ .

The bonding in these alkene complexes was not understood until 1951 when Dewar suggested that the  $\pi$  bond donated electrons to a vacant  $\sigma$  orbital on the metal, rather than involving bonding an individual C atom. This idea was extended by Chatt in 1953, and current thinking is that bonding is in two parts:

1. A dative bond in which the electron pair in the filled  $\pi$  orbital on ethene overlaps with an empty hybrid orbital on the metal, giving a  $\sigma$  bond.
2.  $\pi$  overlap also occurs between a filled metal  $d$  orbital and an empty antibonding orbital on ethene. This is  $\pi$  back donation or back bonding. Most of the transition elements form complexes with alkenes. The exceptions are the first few elements where the  $d$  orbitals on the metal are not sufficiently populated to allow back bonding. The extent of back bonding varies from one complex to another, and is related to the C=C bond length.






Figure 26.5 Zeise's salt  $[\text{Pt}(\eta^2\text{-C}_2\text{H}_4)(\text{Cl})_3]^-$


Besides theoretical interest in the bonding in these complexes, some are of importance in commercial processes. Complexes between  $\text{PdCl}_2$  and alkenes are decomposed by water, giving ethanal (acetaldehyde)




This reaction forms the basis of the Wacker process for the production of acetaldehyde. The Pd is converted back into  $\text{PdCl}_2$  in situ by  $\text{CuCl}_2$



The solution contains HCl and the  $\text{CuCl}_2$  is regenerated by passing in  $\text{O}_2$




Thus the overall reaction is



This process is practicable because the reaction between Pd and  $\text{CuCl}_2$  is quantitative, so the catalyst is recycled and only small amounts of Pd are required for replenishment.

With propene  $\text{CH}_3\text{CH}=\text{CH}_2$ , the product is acetone. This reaction is also of commercial importance. If the reaction is carried out in acetic acid, ethene is converted to vinyl acetate. Though this is not a commercial process because of corrosion problems and difficulty in catalyst recovery, it has led to a study of palladium(II) acetate  $[\text{Pd}(\text{CH}_3\text{COO})_2]_3$ . This has an unusual structure, comprising three metal atoms in a triangle, held together by six bridging acetate groups.

$\text{PdCl}_2$  catalyses the reaction between ethene, CO and  $\text{H}_2\text{O}$



Magnus' green salt has the formula  $[\text{Pt}(\text{NH}_3)_4]^{2+} [\text{PtCl}_4]^{2-}$ , and the square planar anions and cations are stacked on top of each other. This structure also occurs in other complexes such as  $[\text{Pd}(\text{NH}_3)_4]^{2+} [\text{Pd}(\text{SCN})_4]^{2-}$  and  $[\text{Cu}(\text{NH}_3)_4]^+ [\text{PtCl}_4]^{2-}$ . The metal atoms in adjacent units may interact with each other giving weak metal-metal bonds. Evidence for this is that if the anion and cation contain  $\text{Pt}(+II)$  they are colourless, pale yellow or pale red individually, but when stacked together they show an unusual iridescent green colour. They also show increased electrical conductivity.  $[\text{Pt}(\text{ethylenediamine})\text{Cl}_2]$  is stacked in a similar way (Figure 26.6).

$\text{K}_2[\text{Pt}(\text{CN})_4] \cdot 3\text{H}_2\text{O}$  is a well known complex and is colourless and stable. In the crystal structure the square planar  $[\text{Pt}(\text{CN})_4]^{2-}$  units are stacked on top of each other, but the solid does not conduct electricity. However, several complexes can be derived from it which show electrical conduction in one dimension, and they are also dichroic (Dichroic materials have a different refractive index in different directions, so when they are viewed from different directions they appear differently coloured). If this compound is oxidized it is possible to obtain bronze coloured compounds which are cation deficient such as  $\text{K}_2[\text{Pt}(\text{CN})_4]\text{Br}_{0.3} \cdot 3\text{H}_2\text{O}$  and




Figure 26.6 Stacks of square planar  $[\text{Pt}(\text{ethylenediamine})\text{Cl}_2]$  molecules.

$\text{K}_2[\text{Pt}(\text{CN})_4]\text{Cl}_{0.3} \cdot 3\text{H}_2\text{O}$ . The filled  $d_z^2$  orbitals on the Pt atoms overlap, giving a delocalized band along the Pt chain. In  $\text{K}_2[\text{Pt}(\text{CN})_4] \cdot 3\text{H}_2\text{O}$  this band is full: hence it cannot conduct. In  $\text{K}_2[\text{Pt}(\text{CN})_4]\text{Br}_{0.3} \cdot 3\text{H}_2\text{O}$  the Br act as electron acceptors, removing on average 0.3 electrons from each  $[\text{Pt}(\text{CN})_4]^{2-}$  unit. Thus the  $d_z^2$  band is only five sixths filled, and hence the solid conducts electricity by a metallic mechanism in one dimension (Figure 26.7). In  $\text{K}_2[\text{Pt}(\text{CN})_4] \cdot 3\text{H}_2\text{O}$  the Pt—Pt distance is 3.48 Å, but the strong overlap of the  $d_z^2$  orbitals in  $\text{K}_2[\text{Pt}(\text{CN})_4]\text{Br}_{0.3} \cdot 3\text{H}_2\text{O}$  reduces the Pt—Pt distance to 2.8–3.0 Å.

A very important medical use of Pt(+II) compounds is the use of the *cis* isomer of  $[\text{Pt}(\text{NH}_3)_2(\text{Cl})_2]$  as an anti-cancer drug for treating several types of malignant tumours. The *trans* isomer is ineffective. The *cis* isomer is called cisplatin, and is highly toxic. It is injected into the bloodstream, and the more reactive Cl groups are lost so the Pt atom bonds to a N atom in guanosine (part of the DNA molecule). The cisplatin molecule can bond to two different guanosine units, and by bridging between them it upsets the normal reproduction of DNA. Those cells which are undergoing cell division are attacked by cisplatin. Tumours are usually growing rapidly, but so also are the bone marrow cells (producing red and white blood cells), and cells in the testes (producing sperms), so these are also affected. Dramatic results are possible, and a large number of patients are completely cured. There is a critical balance between giving enough cisplatin to kill the tumour and leaving sufficient white blood cells to protect the body from attack by bacteria and viruses.

### (+III) STATE

This state is not important for any of the three metals. Few Ni(+III) compounds are known. Oxidation of  $\text{Ni}(\text{OH})_2$  in alkaline solution with  $\text{Br}_2$  gives  $\text{Ni}_2\text{O}_3 \cdot 2\text{H}_2\text{O}$  as a black solid, which decomposes to NiO on dehydration. If Ni is fused in NaOH and dioxygen bubbled through, sodium




Figure 26 7 Structure of  $K_2[Pt(CN)_4]BrO_3 \cdot 3H_2O$




Figure 26 8 Structure of  $[Pt(NH_3)_2Br_3]$

nickelate(III)  $\text{Na}[\text{Ni}^{\text{III}}\text{O}_2]$  is formed. The (+III) state can be stabilized in complexes.  $\text{K}_3[\text{NiF}_6]$  can be prepared by fluorinating  $\text{NiCl}_2$  and  $\text{KCl}$  at a high temperature and pressure. It is a violet solid but is strongly oxidizing and reacts with  $\text{H}_2\text{O}$ , evolving  $\text{O}_2$ . The structure is octahedral, but is slightly elongated as expected from Jahn–Teller distortion due to its asymmetrically filled  $(t_{2g})^6 (e_g)^1$  electronic arrangement.  $[\text{Ni}^{\text{III}}(\text{ethylenediamine})_2\text{Cl}_2]\text{Cl}$  is also octahedral. The structure of  $[\text{Ni}^{\text{III}}(\text{PEt}_3)_2\text{Br}_3]$  is a trigonal bipyramid.


$\text{Pd}(+\text{III})$  compounds are very rare and it is doubtful if  $\text{Pt}(+\text{III})$  exists. Hydrated oxides may be known. The complexes  $\text{Na}^+[\text{PdF}_4]^-$  and  $\text{NaK}_2[\text{PdF}_6]$  have been reported. The  $[\text{PdF}_6]^{3-}$  ion has four short bonds and two long bonds as expected for a low-spin  $d^7$  octahedral complex. Heating  $\text{Pd}$  and  $\text{F}_2$  gives a stable solid which was once thought to be  $\text{PdF}_3$ . This has since been shown to be a mixed valency compound  $\text{Pd}^{2+}[\text{Pd}^{\text{IV}}\text{F}_6]^{2-}$  containing  $\text{Pd}(+\text{II})$  and  $\text{Pd}(+\text{IV})$ . Complexes which are apparently in the (+III) state such as  $[\text{Pt}(\text{ethylenediamine})\text{Br}_3]$  and  $[\text{Pt}(\text{NH}_3)_2\text{Br}_3]$  consist of chains of alternate square planar  $\text{Pt}(+\text{II})$  units and octahedral  $\text{Pt}(+\text{IV})$  units (Figure 26.8).

#### (+IV) STATE

$\text{Ni}(+\text{IV})$  is rare. The hydrated oxide is made by powerful oxidation of  $\text{Ni}^{2+}$  in fused alkali, and the product oxidizes  $\text{Mn}^{2+}$  to  $\text{MnO}_4^-$  and decomposes water. Fluorination of  $\text{NiCl}_2$  and  $\text{KCl}$  gives the red complex  $\text{K}_2[\text{Ni}^{\text{IV}}\text{F}_6]$  which is strongly oxidizing and liberates  $\text{O}_2$  with water.

$\text{PdO}_2$  is only known in the hydrated form. In contrast  $\text{PtO}_2$  is the most stable oxide of  $\text{Pt}$  and exists in both anhydrous and hydrated forms. The anhydrous oxide is insoluble, but the hydrated form dissolves in acids and alkalis.

$\text{PdF}_4$  is the only known halide of  $\text{Pd}$ , but all four  $\text{Pt}$  halides  $\text{PtX}_4$  are known. Direct reaction of  $\text{Pd}$  and  $\text{F}_2$  gives  $\text{PdF}_3$  (really  $\text{Pd}^{\text{II}}[\text{Pd}^{\text{IV}}\text{F}_6]$ ) and  $\text{PdF}_4$ , whilst  $\text{Pt}$  gives  $\text{PtF}_4$ ,  $\text{PtF}_5$  and  $\text{PtF}_6$ .  $\text{PtCl}_4$  is formed either by direct reaction, or by heating  $\text{H}_2[\text{PtCl}_6]$ .



$\text{Pd}(+\text{IV})$  forms a few octahedral complexes  $[\text{PdX}_6]^{2-}$  where  $\text{X} = \text{F}, \text{Cl}$  or  $\text{Br}$ , and  $[\text{PdX}_4(\text{NH}_3)_2]$ . These are generally reactive.  $[\text{PdF}_6]^{2-}$  hydrolyses rapidly in water whilst the other halide complexes are decomposed by hot water, giving  $[\text{Pd}^{\text{II}}\text{X}_4]^{2-}$  and halogen.

In contrast  $\text{Pt}(+\text{IV})$  forms a very large number of very stable octahedral complexes. These range from  $[\text{Pt}(\text{NH}_3)_6]^{4+}$ ,  $[\text{Pt}(\text{NH}_3)_5\text{Cl}]^{3+}$ ,  $[\text{Pt}(\text{NH}_3)_4\text{Cl}_2]^{2+}$  ... to  $[\text{PtCl}_6]^{2-}$ . Similar series of complexes exist with a wide range of ligands including  $\text{F}^-$ ,  $\text{Cl}^-$ ,  $\text{Br}^-$ ,  $\text{I}^-$ ,  $\text{OH}^-$ , acetyl acetone,  $\text{NO}_2^-$ ,  $\text{SCN}^-$ ,  $\text{SeCN}^-$ , and  $\text{CN}^-$ . Some of these were studied by Werner in the early studies on coordination complexes (see Chapter 7).


Chloroplatinic acid is commercially the most common  $\text{Pt}$  compound. It



is formed when a Pt metal sponge dissolves in aqua regia or concentrated HCl saturated with  $\text{Cl}_2$ . It forms red crystals of formula  $\text{H}_2[\text{PtCl}_6] \cdot 2\text{H}_2\text{O}$ . The sodium or potassium salts are a common starting material for making other Pt(+IV) compounds. Platinized asbestos is used as a catalyst. It is made by soaking asbestos in a solution of chloroplatinic acid, followed by strong heating to decompose the complex to Pt metal. This leaves a small amount of Pt spread over a very large surface.

Platinized platinum, or platinum black, electrodes are often used for conductivity measurements, and these are made by electrolyzing hexachloroplatinates  $[\text{PtCl}_6]^{2-}$ .

Platinum is unusual in that it forms alkyl derivatives by a Grignard reaction



There were reports of  $[(\text{CH}_3)_4\text{Pt}]_4$ , but these were incorrect and the compound formed is actually  $[(\text{CH}_3)_3\text{Pt}(\text{OH})]_4$ . These complexes exist as tetrameric solids in which Pt is six coordinate. The Pt—C bond is very stable. These organo derivatives are soluble in organic solvents.

#### (+V) AND (+VI) STATES

These are only found for Pt, and are rare. The (+V) state is represented by  $\text{PtF}_5$ , which is tetrameric and has the same structure as many transition metal pentafluorides (Figure 21.1). The  $[\text{PtF}_6]^-$  ion also contains Pt(+V) and was first formed by reacting  $\text{PtF}_6$  and  $\text{O}_2$  to give the compound  $\text{O}_2^+[\text{PtF}_6]^-$ . A similar reaction between Xe and  $\text{PtF}_6$  led to reports by Bartlett in 1962 of the formation of  $\text{Xe}^+[\text{PtF}_6]^-$ , the first reported compound of the noble gases. (This compound was subsequently shown to be  $[\text{XeF}]^+[\text{Pt}_2\text{F}_{11}]^-$ .) The only examples of the (+VI) state which are known for certain are  $\text{PtO}_3$  and  $\text{PtF}_6$ .

#### HORIZONTAL COMPARISONS IN THE IRON, COBALT AND NICKEL GROUPS

The ferrous metals Fe, Co and Ni show horizontal similarities and differ from the platinum metals in that the ferrous metals are much more reactive. Within the ferrous metals the reactivity decreases from Fe to Co to Ni. Although the maximum oxidation states are Fe(+VI), Co(+IV) and Ni(+IV), these elements rarely exceed an oxidation state of (+III). The tendency to trivalency decreases across the period.  $\text{Fe}^{3+}$  is the usual state but  $\text{Co}^{3+}$  is a strong oxidizing agent unless complexed, and nickel is divalent in all its simple compounds. The lower valency states exist as simple ions. The elements are relatively abundant.

The platinum metals Ru, Rh, Pd, Os, Ir and Pt are much more noble than the ferrous metals, and are little affected by acids. The reactivity of the metals increases from Ru to Rh to Pd and from Os to Ir to Pt, which is the opposite of the trend in the ferrous metals. The halogens react with

the metals only at high temperatures, and bring out the higher valencies, e.g.  $\text{OsF}_6$ ,  $\text{IrF}_6$ ,  $\text{PtF}_6$ . The lower valency states are unstable except in complexes. Few simple ions exist. Because of the lanthanide contraction, the radii of the second and third rows of transition elements are very similar. Thus their atomic volumes are almost the same, so the densities of Os, Ir and Pt are almost double those of Ru, Rh and Pd. All six elements are rare.

Both the ferrous metals and the platinum metals are typical transition elements, and are characterized by:

1. coloured compounds
2. variable valency
3. catalytic properties
4. an ability to form coordination compounds

The differences between the two groups are:

1. increased stability of higher oxidation states
2. disappearance of simple ionic forms
3. increased nobility

These are the normal changes expected in a vertical group.

## FURTHER READING

- Abel, E. (1989) The Mond connection, *Chemistry in Britain*, **25**, 1014–1016. (History of nickel carbonyl.)
- Abel, E.W. and Stone, F.G. (1969, 1970) The chemistry of transition metal carbonyls, *Q. Rev. Chem. Soc.*, Part I – Structural considerations, **23**, 325; Part II – Synthesis and reactivity, **24**, 498.
- Canterford, J.H. and Cotton, R. (1968) *Halides of the Second and Third Row Transition Elements*, Wiley, London.
- Canterford, J.H. and Cotton, R. (1969) *Halides of the First Row Transition Elements*, Wiley, London.
- Emeléus H.J. and Sharpe, A.G. (1973) *Modern Aspects of Inorganic Chemistry*, 4th ed. (Chapters 14 and 15: Complexes of Transition Metals; Chapter 20: Carbonyls), Routledge and Kegan Paul, London.
- Hartley, F.R. (1973) *The Chemistry of Platinum and Palladium*, Applied Science Publishers, London.
- Hunt, C. (1984) Platinum drugs in cancer chemotherapy, *Education in Chemistry*, **21**, 111–115, 171.
- Levason, W. and McAuliffe, C.A. (1974) Higher oxidation state chemistry of iron, cobalt and nickel, *Coordination Chem. Rev.*, **12**, 151–184.
- Nicholls, D. (1973) *Comprehensive Inorganic Chemistry*, Vol. 3 (Chapter 42: Nickel), Pergamon Press, Oxford.
- Shaw, B.L. and Tucker, N.I. (1973) *Comprehensive Inorganic Chemistry*, Vol. 4 (Chapter 53: Organo-transition metal compounds and related aspects of homogeneous catalysis), Pergamon Press, Oxford.
- Wiltshaw, E. (1979) Cisplatin in the treatment of cancer, *Platinum Metals Rev.*, **23**, 90–98.

## Group 11 – the copper group: coinage metals

Table 27.1 Electronic structures and oxidation states

Element		Electronic structure	Oxidation states*
Copper	Cu	$[\text{Ar}] 3d^{10} 4s^1$	<b>I</b> <b>II</b> (III)
Silver	Ag	$[\text{Kr}] 4d^{10} 5s^1$	<b>I</b> <b>II</b> (III)
Gold	Au	$[\text{Xe}] 4f^{14} 5d^{10} 6s^1$	<b>I</b> <b>III</b> <b>V</b>

\* The most important oxidation states (generally the most abundant and stable) are shown in bold. Other well characterized but less important states are shown in normal type. Oxidation states that are unstable or in doubt, are given in parentheses.

### INTRODUCTION

The elements all have one *s* electron outside a completed *d* shell. They show only slight similarities in properties and considerable differences. All three metals have the same crystal structure (cubic close packed). They conduct electricity and heat particularly well, and they tend to be noble (unreactive). The only ions which exist in solution (apart from complexes) are  $\text{Cu}^{2+}$  and  $\text{Ag}^+$ . The most stable oxidation state varies, Cu(+II), Ag(+I) and Au(+III). Copper is produced on a large scale and 11 million tonnes were used in 1992, mostly as the metal and in alloys. Copper is biologically important in various oxidase enzymes, as an oxygen carrier in invertebrates and in photosynthesis. There is great interest in various mixed oxides of copper which act as superconductors.

### ABUNDANCE, EXTRACTION AND USES OF THE ELEMENTS

Copper is moderately abundant and is the twenty fifth most abundant element in the earth's crust. It occurs to the extent of 68 ppm by weight. Silver and gold are quite rare (Table 27.2).


**Table 27.2** Abundance of the elements in the earth's crust, by weight

	ppm	Relative abundance
Cu	68	25
Ag	0.08	66 =
Au	0.004	73




## Copper

Copper nuggets (i.e. pieces of metal) have been found in the earth, but this source is largely exhausted. The most common ore is chalcopyrites  $\text{CuFeS}_2$ . This has a metallic lustre and is similar in appearance to pyrites  $\text{FeS}_2$  (fool's gold) but is more copper coloured. Other ores include  $\text{Cu}_2\text{S}$  (called copper glance or chalcocite; dark grey coloured), basic copper carbonate  $\text{CuCO}_3 \cdot \text{Cu}(\text{OH})_2$  (which is called malachite and is green), copper(I) oxide  $\text{Cu}_2\text{O}$  (which is called cuprite and is ruby red coloured) and  $\text{Cu}_5\text{FeS}_4$  (called bornite or 'peacock ore' because it has a mixture of iridescent colours like a peacock's feathers (blue, red, brown and purple)). Turquoise  $\text{CuAl}_6(\text{PO}_4)_4(\text{OH})_8 \cdot 4\text{H}_2\text{O}$  is a popular gemstone because of its blue colour and delicate veining.


The sulphide ores are often lean and may contain only 0.4–1% Cu. These are crushed and concentrated by froth-flotation, giving a concentrate with 15% Cu. This is then roasted with air.



Sand is added to remove the iron as iron silicate slag  $\text{Fe}_2(\text{SiO}_3)_3$  which floats on the surface. Air is blown through the liquid matte of  $\text{Cu}_2\text{S}$  with some FeS and silica, causing partial oxidation:




After some time the air is turned off and self-reduction of the oxide and sulphide occurs, giving impure 'blister copper' which is 98–99% pure.



The 'blister copper' is cast into blocks and refined by electrolysis using Cu electrodes with an electrolyte of dilute  $\text{H}_2\text{SO}_4$  and  $\text{CuSO}_4$ .

It is not economic to treat very lean ores in this way, so these are dug up and left exposed to the air to weather. The CuS oxidizes slowly to  $\text{CuSO}_4$  which is leached (dissolved out) with water or dilute  $\text{H}_2\text{SO}_4$ . Copper is displaced from the resulting copper sulphate solution by adding scrap iron which is sacrificed.



*continued overleaf*

World production of mined Cu was 9.3 million tonnes in 1992. The largest sources of copper ores are in Chile 21%, the USA 19%, the Soviet Union 9%, Canada 8% and Zambia 5%. In addition, about 1.7 million tonnes of scrap metal were recycled, giving a total of 11 million tonnes.

The metal is used in the electrical industry because of its high conductivity. It is also used for water pipes because of its inertness. Over 1000 different alloys of copper exist. These include brass (Cu/Zn with 20–50% Zn), so called 'nickel silver' (55–65% Cu, 10–18% Ni, 17–27% Zn), phosphor bronze (Cu with 1.25–10% Sn and 0.35% P) and various alloys for making coins. Copper sulphate is produced in moderately large amounts, 123 956 tonnes in 1991. Several copper compounds are used in agriculture. For example, Bordeaux mixture is basic copper hydroxide, and is made from  $\text{CuSO}_4$  and  $\text{Ca(OH)}_2$ . It is an important spray for preventing fungus attack on the leaves of potatoes (potato blight) which caused the potato famine in Ireland in 1845–1846. It is also used to spray vines to prevent fungal attack. Basic copper carbonate, copper acetate and copper oxochloride have also been used. Paris Green is an insecticide made from basic copper acetate, arsenious oxide and acetic acid.

There has been enormous interest in a variety of mixed oxides of copper such as  $\text{La}_{1.2-x}\text{Ba}_x\text{CuO}_{4-x}$ , since these behave as superconductors at temperatures below 50 K. G. Bednorz and A. Müller were awarded the Nobel Prize for Physics in 1987 for work on these compounds. Other superconductors which work at higher temperatures (up to 125 K) are based on  $\text{YBa}_2\text{Cu}_3\text{O}_{7-x}$ . These are described in Chapter 5 under 'Superconductivity'.

### Silver

Silver is found as sulphide ores  $\text{Ag}_2\text{S}$  (argentite) as the chloride  $\text{AgCl}$  (horn silver) and as the native metal. There are three extraction processes:

1. Most is now obtained as a by-product from the extraction of Cu, Pb or Zn. It can be obtained from the anode slime formed in the electrolytic refining of Cu or Zn.
2. Zinc is used to extract silver by solvent extraction from molten lead in Parke's process.
3. Silver and gold are extracted by making soluble cyanide complexes.


World production of silver was 13 818 tonnes in 1992. The main producers were Mexico 17%, the USA 13%, Peru 11%. Canada and Australia 9% each, and the Soviet Union and Chile 7% each. The main uses of silver are as  $\text{AgCl}$  and  $\text{AgBr}$  in photographic emulsions, for jewellery and silver ornaments, for batteries and for silvering mirrors.

### Gold

Historically gold has been found as lumps of metal in the ground called nuggets. Finds of this kind have started gold rushes in the USA. How

ever, gold occurs mainly as grains of metal disseminated in quartz veins. Many of these rocks have weathered with time. The gold and powdered rock are washed away in streams and accumulate as sediments in river beds. The grains of gold can be separated from silica by 'panning', i.e. swirling them both with water. Gold is very dense ( $19.3 \text{ g cm}^{-3}$ ) and rapidly settles to the bottom, but the  $\text{SiO}_2$ , with a density of  $2.5 \text{ g cm}^{-3}$ , settles more slowly and is thrown away with the water. This method is little used nowadays since the sources are largely exhausted.

Nowadays rocks containing traces of gold are crushed and extracted either with mercury or with sodium cyanide. Water and powdered rock are passed over mercury, in which the gold dissolves, forming an amalgam. The gold is recovered by distilling the amalgam, when the mercury distils off and is reused. This process is also used with river water and silt in Brazil. Losses of mercury have poisoned considerable stretches of the River Amazon, giving environmental problems. In the cyanide process the crushed rock is treated with a 0.1–0.2% solution of  $\text{NaCN}$  and aerated.



The sodium argentocyanide complex is soluble, thus separating gold from the rest of the rock. The gold is precipitated from this solution by adding Zn powder. World production of gold was 2134 tonnes in 1992, and the main producers were South Africa 29%, the USA 14%, Australia 11%, the Soviet Union 10%, Canada 7% and China 6%. The major uses are as gold bullion (which is used as international currency) and for jewellery. Gold used in jewellery is usually alloyed with a mixture of Cu and Ag. These alloys retain the golden colour, but are harder. The proportion of gold in the alloy is expressed in *carats*. Pure gold is 24 carats. The alloys commonly used are 9 carat, 18 carat and 22 carat, and these contain 9/24, 18/24 and 22/24 pure gold respectively. Small amounts of gold are used to make corrosion-free electrical contacts, for example on computer boards. A thin film  $10^{-11} \text{ m}$  thick is sometimes deposited on glass windows in prestigious skyscraper buildings (e.g. a bank in Toronto). This thin metal film reflects unwanted heat from the sun in the summer, thus keeping the building cool. The film keeps heat in during the winter.

## OXIDATION STATES

The elements Cu, Ag and Au show oxidation states of (+I), (+II) and (+III). However, the only simple hydrated ions found in solution are  $\text{Cu}^{2+}$  and  $\text{Ag}^+$ . The univalent ions  $\text{Cu}^+$  and  $\text{Au}^+$  disproportionate in water, and as a result they only exist as insoluble compounds or complexes.  $\text{Cu}(\text{+III})$ ,  $\text{Ag}(\text{+III})$  and  $\text{Ag}(\text{+II})$  are so strongly oxidizing that they reduce water. Thus they only occur when stabilized in complexes, or as insoluble compounds. The oxides and halides formed are shown in Table 27.3.

Table 27.3 Oxides and halides

Oxidation states					
(+I)	(+II)	(+III)	(+IV)	(+V)	Others
<b>Cu<sub>2</sub>O</b>	<b>CuO</b>	-	-	-	
<b>Ag<sub>2</sub>O</b>	<b>AgO</b>	(Ag <sub>2</sub> O <sub>1</sub> ?)	-	-	
<b>Au<sub>2</sub>O</b>	-	<b>Au<sub>2</sub>O<sub>1</sub></b>	-	-	
-	<b>CuF<sub>2</sub></b>	-	-	-	
<b>CuCl</b>	<b>CuCl<sub>2</sub></b>	-	-	-	
<b>CuBr</b>	<b>CuBr<sub>2</sub></b>	-	-	-	
<b>CuI</b>	-	-	-	-	
<b>AgF</b>	<b>AgF<sub>2</sub></b>	-	-	-	Ag F
<b>AgCl</b>	-	-	-	-	
<b>AgBr</b>	-	-	-	-	
<b>AgI</b>	-	-	-	-	
-	-	<b>AuF<sub>3</sub></b>	-	(AuF <sub>5</sub> )	
<b>AuCl</b>	-	<b>AuCl<sub>3</sub></b>	-	-	
-	-	<b>AuBr<sub>3</sub></b>	-	-	
<b>AuI</b>	-	-	-	-	

The most stable oxidation states are shown in bold unstable ones in brackets

### STANDARD REDUCTION POTENTIALS (VOLTS)

Acid solution					
Oxidation state					
+III		+II		+I	0
CuO <sup>+</sup>	$\xrightarrow{-1.8}$	Cu <sup>2+</sup>	$\xrightarrow{+0.15^*}$	Cu <sup>+</sup>	$\xrightarrow{+0.52}$ Cu
			$\xrightarrow{+0.34}$		
AgO <sup>+</sup>	$\xrightarrow{+2.1}$	Ag <sup>2+</sup>	$\xrightarrow{+1.98}$	Ag <sup>+</sup>	$\xrightarrow{+0.80}$ Ag
Au <sup>3+</sup>	$\xrightarrow{<+1.29}$	Au <sup>2+</sup>	$\xrightarrow{>+1.29^*}$	Au <sup>+</sup>	$\xrightarrow{+1.68}$ Au
			$\xrightarrow{+1.50}$		
* Disproportionates					

### GENERAL PROPERTIES

Group 11 metals (Cu, Ag and Au) have the highest electrical and thermal conductivities known. They are the most malleable and ductile structural metals. This is associated with their cubic close-packed structure. When sufficient force is applied, one plane may be forced to slip over another plane. The structure is very simple, so that when it slips it remains a regular cubic close-packed structure.

Atoms of Cu, Ag and Au (Table 27.1) have one *s* electron in their outer orbital. This is the same outer electronic arrangement as for the Group 1 metals. In spite of this, there are few similarities apart from the formal stoichiometry of compounds in the (+I) state and the high electrical conductivity of both groups of metals.

Group 11 elements differ from Group 1 elements in that the penultimate shell contains ten *d* electrons. The poor screening by the *d* electrons makes the atoms of the copper group much smaller in size. As a result the Cu group have higher densities and are harder. Their ionization energies are higher (Table 27.4), and their compounds are more covalent.

In the Cu group the *d* electrons are involved in metallic bonding. Thus the melting points and enthalpies of sublimation are much higher than for Group 1 metals.

The higher enthalpy of sublimation and higher ionization energy are the reasons why Cu, Ag and Au tend to be unreactive, i.e. show noble character. Group 1 metals have large negative standard reduction potentials ( $E^\circ$  values) and are at the top of the electrochemical series. They are the most reactive metals in the periodic table. In contrast the coinage metals have positive  $E^\circ$  values and are thus below hydrogen in the electrochemical series. Thus they do not react with water or liberate  $H_2$  with acids. The nobility increases from Cu to Ag to Au, whereas on descending Group 1 the reactivity increases. The inertness of Au resembles that of the platinum metals. Cu is inert towards non-oxidizing acids, but reacts with concentrated  $HNO_3$  and  $H_2SO_4$ .





Table 27.4 Some physical properties

	Covalent radius (Å)	Ionic radius (Å)			Melting point (°C)	Boiling point (°C)	Density (g cm <sup>-3</sup> )	Pauling's electro-negativity
		M <sup>+</sup>	M <sup>2+</sup>	M <sup>3+</sup>				
Cu	1.17	0.77	0.73	0.54 <sup>l</sup>	1083	2570	8.95	1.9
Ag	1.34	1.15	0.94	0.75	961	2155	10.49	1.9
Au	1.34	1.37	—	0.85	1064	2808	19.32	2.4


<sup>l</sup> = low spin radius.

However, Cu is very slowly oxidized on the surface in moist air, giving a green coating of verdigris. This is basic copper carbonate  $CuCO_3 \cdot Cu(OH)_2$  and is familiar on the roofs of buildings covered with copper sheet, and also on copper statues such as the Statue of Liberty in New York.


Ag will dissolve in concentrated  $HNO_3$  and in hot concentrated  $H_2SO_4$ . Au is inert to all acids except aqua regia (a 3:1 mixture of concentrated  $HCl$  and  $HNO_3$ ). The  $HNO_3$  acts as an oxidizing agent and the chloride ions as a complexing agent.

Cu reacts with dioxygen, but Ag and Au are inert.





Cu and Ag metals react with  $\text{H}_2\text{S}$  and S, but Au does not. Silver objects tarnish slowly in air (i.e. polished silver articles gradually blacken). This is due to traces of  $\text{H}_2\text{S}$  in the air which react with Ag forming black  $\text{Ag}_2\text{S}$ .



In a similar way passing  $\text{H}_2\text{S}$  into solutions containing  $\text{Cu}^{2+}$  or  $\text{Ag}^+$  gives black precipitates of  $\text{CuS}$  and  $\text{Ag}_2\text{S}$ . All three metals react with the halogens. Simple compounds of Au decompose to the metal quite readily, those of Ag can be reduced fairly easily, and those of Cu less readily.

For metals to react, an atom must first be isolated from the crystal structure and then be ionized. A high enthalpy of sublimation and a high ionization energy will reduce reactivity, though this may be partly offset by the energy gained when the ion is hydrated. Comparing Cu and K, Cu has a much higher melting point (and hence a higher enthalpy of sublimation). Because of the increased nuclear charge of copper, the orbital electrons are more tightly held (and hence the ionization energy is higher). The enthalpy of hydration is not large enough to offset these large amounts of energy, and so potassium is much more reactive than copper.



The oxides and hydroxides of Group 1 are strongly basic, and are soluble in water. In contrast the oxides of copper are insoluble and weakly basic. Group 1 compounds all contain simple colourless univalent ions and only form complexes with very strong complexing agents. In contrast the copper group elements show variable valency. The most common oxidation states are  $\text{Cu}(+II)$ ,  $\text{Ag}(+I)$  and  $\text{Au}(+III)$ , and the three elements differ widely in their chemistries. Their compounds are mainly coloured and they show a strong tendency to form coordination complexes.

Copper is important in several catalysts. Cu is used in the direct process for manufacture of alkylchlorosilanes such as  $(\text{CH}_3)_2\text{SiCl}_2$ , which is used to make silicones. Cu and V catalyse the oxidation of cyclohexanol/cyclohexanone mixtures to adipic acid which is used to make nylon 66.  $\text{CuCl}_2$  was used as the catalyst in the Deacon process for making  $\text{Cl}_2$  from  $\text{HCl}$ .


### (+I) STATE

In the (+I) state most of the simple compounds and complexes are diamagnetic and colourless because the ions have a  $d^{10}$  configuration. There are a few coloured compounds. For example,  $\text{Cu}_2\text{O}$  is yellow or red,  $\text{Cu}_2\text{CO}_3$  is yellow and  $\text{CuI}$  is brown. In these cases the colour arises from charge transfer bands and not from  $d-d$  spectra.

It might be expected that the (+I) state would be the most common and most stable because of the extra stability resulting from a full  $d$  shell. Surprisingly this is not so. Although  $\text{Ag}^+$  is stable in both the solid state and solution,  $\text{Cu}^+$  and  $\text{Au}^+$  disproportionate in water.




The equilibrium constant for the disproportionation of  $\text{Cu}^+$  in solution is high, showing that the equilibrium is largely to the right. Thus the concentration of  $\text{Cu}^+$  is very low in solution and typically a  $\text{Cu}^+$  ion exists in aqueous solution for less than a second. Similarly  $\text{Au}^+$  is virtually non-existent in solution. The only copper(I) and gold(I) compounds that are stable to water are either insoluble or present as complexes. Examples of insoluble  $\text{Cu}(+I)$  compounds include  $\text{CuCl}$ ,  $\text{CuCN}$  and  $\text{CuSCN}$ . Copper(I) thiocyanate  $\text{CuSCN}$  is used to estimate copper gravimetrically.



$\text{Cu}^{2+}$  is reduced to copper(I) oxide  $\text{Cu}_2\text{O}$  by mild reducing agents. This is the basis of Fehling's test for reducing sugars (monosaccharides such as glucose). Equal quantities of two different solutions, Fehling's A and Fehling's B, are mixed immediately before adding the sugar and warming. The solution is deep blue coloured and if a reducing agent is present a yellow or red precipitate of  $\text{Cu}_2\text{O}$  is formed. (Fehling's A solution is a solution of copper(II) tartrate, made from  $\text{CuSO}_4$  and Rochelle salt (sodium potassium tartrate). Fehling's B solution is  $\text{NaOH}$ .)

$\text{Cu}_2\text{O}$  is a basic oxide and reacts with the halogen acids  $\text{HCl}$ ,  $\text{HBr}$  and  $\text{HI}$ , giving insoluble  $\text{CuCl}$ ,  $\text{CuBr}$  and  $\text{CuI}$ .  $\text{CuF}$  is unknown.  $\text{CuCl}$  and  $\text{CuBr}$  are usually made by boiling an acidic solution of  $\text{CuCl}_2$  or  $\text{CuBr}_2$  with excess  $\text{Cu}$ . This gives a solution containing the complex ions  $[\text{CuCl}_2]^-$  and  $[\text{CuBr}_2]^-$  which are linear in shape. Diluting these solutions gives white  $\text{CuCl}$  or yellow  $\text{CuBr}$ .

Addition of  $\text{KI}$  to a solution containing  $\text{Cu}^{2+}$  results in the  $\text{I}^-$  ions reducing  $\text{Cu}^{2+}$  to copper(I) iodide  $\text{CuI}$  and at the same time  $\text{I}^-$  is oxidized to  $\text{I}_2$ . This reaction is used to estimate  $\text{Cu}^{2+}$  in solution by volumetric analysis. Excess of  $\text{KI}$  is added to an acidified solution and the  $\text{I}_2$  produced is estimated by titrating with sodium thiosulphate.



The copper(I) halides are partly covalent and have zinc blende structures with tetrahedrally coordinated  $\text{Cu}^+$  ions. In the vapour  $\text{CuCl}$  and  $\text{CuBr}$  are polymeric and the main species is a six-membered ring.

The copper(I) halides are insoluble in water. However, they dissolve in solutions containing an excess of halide ions by forming soluble halide complexes such as  $[\text{CuCl}_2]^-$ ,  $[\text{CuCl}_3]^{2-}$  and  $[\text{CuCl}_4]^{3-}$ . These and other  $\text{Cu}^+$  complexes are tetrahedral in the solid. (In  $\text{KCuCl}_2$  and  $\text{K}_2\text{CuCl}_3$  there are chains in which  $\text{Cu}$  is tetrahedrally surrounded by  $\text{Cl}$ , with simple units joined into a chain by shared halide ions.)

The copper(I) halides also dissolve in strong HCl, HNO<sub>3</sub> and aqueous solutions of ammonia. Solutions of CuCl in concentrated HCl and CuCl in NH<sub>4</sub>OH are important because they absorb carbon monoxide. Three points arise from this:

1. A solution of CuCl in NH<sub>4</sub>OH is often used to measure the amount of CO in gas samples simply by measuring the change in volume of the gas.
2. Though the metals of this group do not form neutral carbonyl compounds, an unstable carbonyl halide [Cu(CO)Cl] is formed by bubbling CO through a solution of CuCl. Both Cu and Au form carbonyl halides [M(CO)Cl] when CO is passed over the heated halide.
3. Several complexes with alkenes and alkynes can be made in a similar way by bubbling the hydrocarbon through a solution of Cu<sup>I</sup> or Ag<sup>I</sup>. Alkene complexes can also be made by passing the hydrocarbon over the heated halide. These have the formula [MRX] where R is an unsaturated hydrocarbon and X a halogen. These complexes are very reactive and are often polymeric. The M—C bonds are not symmetrical, suggesting  $\sigma$  rather than  $\pi$  bonding. Au<sup>I</sup> forms complexes less readily and only with high molecular weight alkenes.

Cyanide complexes are well known and are used to extract Ag and Au as soluble complexes. The metals are recovered from the complex by reduction with zinc.





Two coordinate complexes such as [Au(CN)<sub>2</sub>]<sup>-</sup> have a linear structure. However, in solid K[Cu<sup>I</sup>(CN)<sub>2</sub>] the Cu is bonded to three CN<sup>-</sup> giving a planar triangular arrangement. The CN<sup>-</sup> are bonded in the usual way through C but the third CN<sup>-</sup> acts as a bridging group to another Cu atom.

Cyanide ions may react with metal ions in two ways:

1. as a reducing agent
2. as complexing agent

Thus adding KCN to a CuSO<sub>4</sub> solution first causes reduction and precipitates copper(I) cyanide. This reacts with excess CN<sup>-</sup> forming a soluble four coordinate complex [Cu(CN)<sub>4</sub>]<sup>3-</sup> which is tetrahedral in shape.



Cu(+I) forms several different polymeric complexes which involve a cluster of four Cu atoms at the corners of tetrahedron but which do not involve metal-metal bonding. The phosphine and arsine complexes Cu<sub>4</sub>I<sub>4</sub>(PR<sub>3</sub>)<sub>4</sub> and Cu<sub>4</sub>I<sub>4</sub>(AsR<sub>3</sub>)<sub>4</sub> are examples of such clusters. In these the four Cu form a tetrahedron. The four phosphine or arsine ligands are attached to the four corners and the I atoms are located above the four faces of the tetrahedron with each I triply bridged to three Cu atoms.

In  $[\text{Cu}_4(\text{SPh})_6]^{2-}$  the Cu atoms form a tetrahedron and the six S atoms bridge the six edges of the tetrahedron.

Ag(+I) is the most important state for silver and many simple ionic compounds are known containing  $\text{Ag}^+$ . Practically all  $\text{Ag}^{\text{I}}$  salts are insoluble in water. Exceptions include  $\text{AgNO}_3$ ,  $\text{AgF}$  and  $\text{AgClO}_4$  which are soluble. The salts are typically anhydrous except for  $\text{AgF} \cdot 4\text{H}_2\text{O}$ . The  $\text{Ag}^+$  ion is hydrated in solution but only as the dihydrate  $[\text{Ag}(\text{H}_2\text{O})_2]^+$ .  $\text{Ag}^{\text{I}}$  commonly forms two-coordinate complexes rather than four-coordinate complexes as in  $\text{Cu}^{\text{I}}$ .

$\text{AgNO}_3$  is one of the most important salts.  $\text{Ag}_2\text{O}$  is mainly basic, dissolving in acids. Moist  $\text{Ag}_2\text{O}$  absorbs carbon dioxide and forms  $\text{Ag}_2\text{CO}_3$ . Since  $\text{Ag}_2\text{O}$  dissolves in  $\text{NaOH}$  it must have slight acidic properties too.

The silver halides are used in photography (see later).  $\text{AgF}$  is soluble in water but the other silver halides are insoluble. In qualitative analysis solutions containing the halide ions  $\text{Cl}^-$ ,  $\text{Br}^-$  and  $\text{I}^-$  are tested by adding  $\text{AgNO}_3$  solution and dilute  $\text{HNO}_3$ . A white precipitate of  $\text{AgCl}$  indicates the presence of a chloride, a pale yellow precipitate of  $\text{AgBr}$  indicates a bromide and a yellow precipitate of  $\text{AgI}$  indicates an iodide. The presence of these halide ions may be confirmed by testing the solubility of the silver halide precipitates in ammonium hydroxide.  $\text{AgCl}$  is soluble in dilute  $\text{NH}_4\text{OH}$ ,  $\text{AgBr}$  dissolves in strong 0.880 ammonia, and  $\text{AgI}$  is insoluble even in 0.880 ammonia. When  $\text{AgCl}$  and  $\text{AgBr}$  dissolve, they form the ammine complex  $[\text{H}_3\text{N} \rightarrow \text{Ag} \leftarrow \text{NH}_3]^+$ , which is linear.

A few silver compounds with colourless anions are coloured. For example,  $\text{AgI}$ ,  $\text{Ag}_2\text{CO}_3$  and  $\text{Ag}_3\text{PO}_4$  are yellow and  $\text{Ag}_2\text{S}$  is black. This is because the  $\text{Ag}^+$  ion is small and highly polarizing and the anion, e.g.  $\text{I}^-$ , is large and highly polarizable. This leads to some covalent character.

$\text{Ag}^+$  forms a variety of complexes. Most simple ligands result in two-coordination and a linear structure, for example  $[\text{Ag}(\text{NH}_3)_2]^+$ ,  $[\text{Ag}(\text{CN})_2]^-$  and  $[\text{Ag}(\text{S}_2\text{O}_3)_2]^{3-}$ . Bidentate ligands form polynuclear complexes. The halide complexes of  $\text{Cu}^+$  and  $\text{Ag}^+$  are unusual because the stability sequence is  $\text{I} > \text{Br} > \text{Cl} > \text{F}$ , whilst for most metals the sequence is the reverse. Ligands capable of  $\pi$  bonding, such as phosphine derivatives, may form both two- and four-coordinate complexes.

$\text{Au}(+\text{I})$  is less stable. It is known as the oxide  $\text{Au}_2\text{O}$ . The halides  $\text{AuCl}$  and  $\text{AuBr}$  can be obtained by gently heating the corresponding  $\text{AuX}_3$  halide.  $\text{AuI}$  is precipitated by adding  $\text{I}^-$  to  $\text{AuI}_3$ . These  $\text{Au}(+\text{I})$  compounds disproportionate in water to Au metal and  $\text{Au}(+\text{III})$ .

$\text{Au}(+\text{I})$  also exists in linear complexes such as  $[\text{NC} \rightarrow \text{Au} \leftarrow \text{CN}]^-$ ,  $[\text{Cl} \rightarrow \text{Au} \leftarrow \text{Cl}]^-$ ,  $[\text{R}_3\text{P} \rightarrow \text{Au} \leftarrow \text{Cl}]$  and  $[\text{R}_3\text{P} \rightarrow \text{Au} \leftarrow \text{CH}_3]$ . The cyanide complex is soluble in water and is formed in the cyanide extraction processes by dissolving Au in an aqueous solution containing  $\text{CN}^-$  in the presence of air or  $\text{H}_2\text{O}_2$ . Phosphine complexes are made by treating  $\text{Au}_2\text{Cl}_6$  with  $\text{R}_3\text{P}$  in ether solution, giving  $\text{R}_3\text{PAuCl}$ . The Cl may be substituted by other groups such as I, SCN or Me. If  $\text{R}_3\text{PAuCl}$  is strongly reduced, e.g. with  $\text{NaBH}_4$ , then a cluster compound  $\text{Au}_{11}\text{Cl}_3(\text{R}_3\text{P})_7$  is formed. The cluster has a structure related to an incomplete icosahedron.

dron There is an Au at the centre and Au at ten of the 12 corners of the icosahedron

An important use of Au(+I) is in drugs to treat rheumatoid arthritis. The drugs are thought to be linear complexes of the type  $[\text{RS} \rightarrow \text{Au} \leftarrow \text{SR}]$  or  $[\text{R}_3\text{P} \rightarrow \text{Au} \leftarrow \text{PR}_3]$ . Changing the organic group R varies the solubility of the drug in lipids and affects how readily the drug is spread round the body.

There is some evidence that gold can exist as the  $\text{Au}^-$  auride ion. This has an electronic configuration  $d^{10}s^2$  which is a stable arrangement. The compound  $\text{CsAu}$  has no metallic lustre and the solid does not conduct electricity like a metal. This compound is ionic  $\text{Cs}^+\text{Au}^-$  and is not an alloy. The  $\text{Au}^-$  ion has been confirmed in liquid ammonia solutions.  $\text{Au}^-$  is large and has been isolated in solids with several large cations.

### Photography


The silver halides are of great importance in photography. A photographic film consists of a light sensitive emulsion of fine particles (grains) of silver salts in gelatine spread on a clear celluloid strip or a glass plate. The grain size is very important to photographers as this affects the quality of the pictures produced.  $\text{AgBr}$  is mainly used as the light sensitive material. Some  $\text{AgI}$  is used in 'fast' emulsions (i.e. ones which can take photographs when the intensity of the light is low or are used for photographing moving objects like racing cars where the exposure must be very short).  $\text{AgCl}$  may also be present in the emulsion.

The film is placed in a camera. When the photograph is exposed, light from the subject enters the camera and is focussed by the lens to give a sharp image on the film. The light starts a photochemical reaction by exciting a halide ion which loses an electron. The electron moves in a conduction band to the surface of the grain, where it reduces a  $\text{Ag}^+$  ion to metallic silver. In the early days of photography, exposures were long, often 10 or 20 minutes, so that sufficient silver was produced to give a negative picture. Parts of the subject which are light become black on the film. In modern photography only a short exposure of perhaps 1/100th of a second is used. In this short time, only a few atoms of silver (perhaps 10–50) are produced in each grain exposed to light. Parts of the film which have been exposed to the bright parts of the subject contain a lot of grains with some silver. Parts exposed to paler parts of the subject contain a few grains with some silver, whilst parts not exposed contain none. Thus the film contains a latent image of the subject. However, the number of silver atoms produced is so small that the image is not visible to the eye.

Next the film is placed in a developer solution. This is a mild reducing agent usually containing quinol. Its purpose is to reduce more silver halide to Ag metal. Ag is deposited mainly where there are already some Ag atoms. Thus the developing process intensifies the latent image on the film so it becomes visible. The correct conditions for processing must be used to obtain an image of the required blackness. The important factors are

the concentration of the developer solution, the pH, the temperature and the length of time that the film is kept in the developer solution.

If the film was brought out into daylight at this stage, the unexposed parts of the emulsion would turn black and thus destroy the picture. To prevent this happening any unchanged silver halides are removed by placing the film in a fixer solution. In the early days, strong ammonia was used to dissolve the unchanged AgBr. Though this was effective, the smell of ammonia in the confined space of a darkroom must have been unpleasant and harmful to the photographer. Nowadays a solution of sodium thiosulphate is used as fixer. It forms a soluble complex with silver halides.



After fixing, the film can safely be brought out into daylight. Parts blackened by silver represent the light parts of the original picture. This is therefore a negative.

To obtain an image with light and dark the right way round, a print must be made. Light is passed through the negative onto a piece of paper coated with AgBr emulsion. This is then developed and fixed in the same way as before.

## (+II) STATE

The (+II) state is the most stable and important for Cu.  $\text{Cu}^{2+}$  has the electronic configuration  $d^9$  and has an unpaired electron. Its compounds are typically coloured due to  $d-d$  spectra and the compounds are paramagnetic.  $\text{CuSO}_4 \cdot 5\text{H}_2\text{O}$  and many hydrated copper(II) salts (formerly called cupric salts) are blue.

On strong heating, oxosalts such as  $\text{Cu}(\text{NO}_3)_2$  decompose into CuO which is black. Very strong heating ( $>800^\circ\text{C}$ ) gives  $\text{Cu}_2\text{O}$ . The addition of NaOH to a solution containing  $\text{Cu}^{2+}$  gives a blue precipitate of the hydroxide. The hydrated ion  $[\text{Cu}(\text{H}_2\text{O})_6]^{2+}$  is formed when the hydroxide or carbonate are dissolved in acid, or when  $\text{CuSO}_4$  or  $\text{Cu}(\text{NO}_3)_2$  are dissolved in water. This ion has the characteristic blue colour associated with copper salts, and has a distorted octahedral shape. There are two long bonds *trans* to each other, and four short bonds (Figure 27.1). This is called tetragonal distortion and is a consequence of the  $d^9$  configuration. The octahedral arrangement causes crystal field splitting of the  $d$  orbitals on Cu into low energy  $t_{2g}$  and higher energy  $e_g$  levels. The nine  $d$  electrons are arranged  $(t_{2g})^6$  and  $(e_g)^3$ . The three  $e_g$  electrons occupy the  $d_{x^2-y^2}$  and  $d_{z^2}$  orbitals, two in one orbital and one in the other. Since the  $e_g$  level is not symmetrically filled, Jahn-Teller distortion occurs. This removes the degeneracy of the  $e_g$  and  $t_{2g}$  orbitals (i.e. they are no longer the same energy). Thus the complex is distorted. The  $d_{x^2-y^2}$  orbital is under the influence of four ligands approaching along the directions  $+x$ ,  $-x$ ,  $+y$  and  $-y$ . The  $d_{z^2}$  orbital is under the influence of only two ligands approaching along  $+z$  and  $-z$ . Thus the energy of the  $d_{x^2-y^2}$  orbital is raised more than that of the  $d_{z^2}$  orbital. Because of this, the three electrons in the  $t_{2g}$  level are





Figure 27.1 Tetragonally distorted octahedron, with four short bonds in a square planar arrangement, and two long *trans* bonds

arranged  $(d_z)^2 (d_{x^2-y^2})^1$ . Because the  $d_z$  orbital contains two electrons the ligands approaching along the  $+z$  and  $-z$  directions are prevented from coming as close to the copper as those approaching along  $+x$ ,  $-x$ ,  $+y$  and  $-y$  (see Chapter 7)

This distorted octahedral arrangement is common in copper compounds. For example, the halides  $\text{CuX}_2$  have a distorted rutile ( $\text{TiO}_2$ ) structure with a coordination number of 6. The bond lengths in the  $\text{Cu}^{II}\text{X}_2$  halides are

$\text{CuF}_2$	4 bonds 1.93 Å and 2 bonds 2.27 Å
$\text{CuCl}_2$	4 bonds 2.30 Å and 2 bonds 2.95 Å
$\text{CuBr}_2$	4 bonds 2.40 Å and 2 bonds 3.18 Å

Similar reasoning to that for the distortion of octahedral  $\text{Cu}^{2+}$  complexes also applies to octahedral complexes of any other metal ion where the  $e_g$  orbitals are not symmetrically filled, i.e. when they contain one or three electrons. Distortions of this kind are found in



Aqueous  $\text{Cu}^{2+}$  solutions form many complexes with ammonia and amines, such as  $[\text{Cu}(\text{H}_2\text{O})_5(\text{NH}_3)]^{2+}$ ,  $[\text{Cu}(\text{H}_2\text{O})_4(\text{NH}_3)_2]^{2+}$ ,  $[\text{Cu}(\text{H}_2\text{O})_3(\text{NH}_3)_3]^{2+}$  and  $[\text{Cu}(\text{H}_2\text{O})_2(\text{NH}_3)_4]^{2+}$ . It is difficult to add a fifth or sixth  $\text{NH}_3$ , though it is possible to make  $[\text{Cu}(\text{NH}_3)_6]^{2+}$  using liquid ammonia as solvent. The reason for this is the Jahn-Teller effect which distorts the octahedral complex and makes the fifth and sixth bonds long and weak. Similarly with the bidentate ligand ethylenediamine (en) the complexes  $[\text{Cu}(\text{en})(\text{H}_2\text{O})_4]^{2+}$  and  $[\text{Cu}(\text{en})_2(\text{H}_2\text{O})_2]^{2+}$  are formed quite easily but  $[\text{Cu}(\text{en})_3]^{2+}$  is formed only with a large excess of ethylenediamine.

The halide complexes show two different stereochemistries. In  $(\text{NH}_4)_2[\text{CuCl}_4]$  the  $[\text{CuCl}_4]^{2-}$  ion is square planar, but in  $\text{Cs}_2[\text{CuCl}_4]$

and  $\text{Cs}_2[\text{CuBr}_4]$  the  $[\text{CuX}_4]^{2-}$  ions have a slightly squashed tetrahedral shape. Tetrahedral  $[\text{CuCl}_4]^{2-}$  ions are orange and square planar  $[\text{CuCl}_4]^{2-}$  ions are yellow.

Most  $\text{Cu}(+II)$  complexes and compounds have a distorted octahedral structure and are blue or green. The metal ion has the  $d^9$  electronic configuration. This leaves only one 'hole' into which an electron may be promoted, so the spectra should be similar to the  $d^1$  case (e.g.  $\text{Ti}^{3+}$ ) and have a single broad absorption band. This is observed, and these complexes absorb in the region  $11\,000\text{--}16\,000\text{ cm}^{-1}$ . However, octahedral complexes of  $\text{Cu}^{II}$  are appreciably distorted (Jahn–Teller effect) so there is more than one peak. These overlap so the band is not symmetrical. It is not possible to assign the peaks unambiguously. The anhydrous salts of  $\text{CuF}_2$  and  $\text{CuSO}_4$  are, perhaps surprisingly, white.

For many years no anhydrous nitrates of the transition metals were known. Heating the hydrated salts simply decomposed them. Water is a stronger ligand than the nitrate group, and so a hydrated nitrate prepared in aqueous solution will lose nitrate groups rather than water on heating. The remedy is to prepare anhydrous nitrates without water rather than attempting to remove water from hydrated salts. Many anhydrous nitrates have now been prepared using a non-aqueous solvent such as liquid  $\text{N}_2\text{O}_4$ .

Anhydrous copper(II) nitrate can be made by dissolving Cu metal in a solution of  $\text{N}_2\text{O}_4$  in ethyl acetate. The reaction is vigorous, and  $\text{Cu}(\text{NO}_3)_2 \cdot \text{N}_2\text{O}_4$  is crystallized from the solution. This has the structure  $\text{NO}^+[\text{Cu}(\text{NO}_3)_3]^-$ . Heating to  $90^\circ\text{C}$  drives off  $\text{N}_2\text{O}_4$  and gives blue anhydrous  $\text{Cu}(\text{NO}_3)_2$ . Anhydrous  $\text{Cu}(\text{NO}_3)_2$  can be sublimed at  $150\text{--}200^\circ\text{C}$ , and has an unusual crystal structure. There are two different crystalline forms. The structure of one of the two solid forms shows infinite chains of Cu and  $\text{NO}_3^-$  groups. Each Cu forms two short Cu—O bonds ( $1.9\text{ \AA}$ ), and the Cu is coordinated to six more oxygen atoms in other chains, forming longer bonds ( $2.5\text{ \AA}$ ), making Cu eight-coordinate (Figure 27.2). In the vapour,  $\text{Cu}(\text{NO}_3)_2$  is monomeric.

Copper(II) acetate is dimeric and hydrated,  $\text{Cu}_2(\text{CH}_3\text{COO})_4 \cdot 2\text{H}_2\text{O}$ . The structure (Figure 27.3) is similar to that of the carboxylate complexes of  $\text{Cr}^{II}$ ,  $\text{Mo}^{II}$ ,  $\text{Rh}^{II}$  and  $\text{Ru}^{II}$ , but there is an important difference. The structure consists of two Cu atoms each with a roughly octahedral structure. The four acetate groups act as bridging ligands between the two Cu atoms. Thus O atoms from the acetate groups occupy four positions (in a square plane) round each Cu. The fifth position round each Cu is occupied by the O atom from a water molecule. The other Cu atom occupies the sixth of the octahedral positions. So far the structure is the same as that of chromous acetate. The difference is that the Cu—Cu distance is  $2.64\text{ \AA}$ , which is significantly longer than the distance of  $2.55\text{ \AA}$  found in metallic copper. Thus Cu does **not** form a M—M bond, whereas Cr and the other metals which form carboxylate complexes do form M—M bonds. The  $\text{Cu}^{II}$  ions in this complex have a  $d^9$  configuration with one unpaired electron. If the two Cu ions form a metal–metal bond these electrons will be paired






Figure 27.2 The crystal structure of one form of anhydrous  $\text{Cu}(\text{NO}_3)_2$  (S C Wall work, *Proc Chem Soc (London)*, 34, 1959)





Figure 27.3 Structure of  $(\text{Cu}(\text{CH}_3\text{COO})_2 \cdot \text{H}_2\text{O})_2$

and the complex will be diamagnetic. If they do not form a bond then the complex will be paramagnetic. However, the magnetic moment measured at  $25^\circ\text{C}$  is 1.4 BM per Cu atom, rather than the spin only value of 1.73 BM. This suggests that there is an 'interaction' or weak coupling of the unpaired spins on the two Cu atoms in this complex. This is thought to involve lateral overlap of the  $3d_{x^2-y^2}$  orbitals on the copper atoms, and is sometimes called  $\delta$  bonding.


$\text{Ag}(+\text{II})$  is known as the fluoride  $\text{AgF}_2$ . This is a brown solid and is made by heating Ag in  $\text{F}_2$ .  $\text{AgF}_2$  is a strong oxidizing agent, and a good fluorinating agent like  $\text{CoF}_3$ . It decomposes on heating



$\text{Ag}^{\text{II}}$  is more stable in complexes such as  $[\text{Ag}(\text{pyridine})_4]^{2+}$ ,  $[\text{Ag}(\text{dipyridyl})_2]^{2+}$  and  $[\text{Ag}(\text{ortho-phenanthroline})_2]^{2+}$  which form stable salts with non-reducing anions such as  $\text{NO}_3^-$  and  $\text{ClO}_4^-$ . They are usually prepared by oxidizing a solution of  $\text{Ag}^+$  and the ligand with potassium persulphate. The complexes are square planar and paramagnetic.

A black oxide of formula  $\text{AgO}$  is formed by strong oxidation of  $\text{Ag}_2\text{O}$  in alkaline solution.  $\text{Ag}^{\text{II}}$  has a  $d^9$  configuration and must be paramagnetic, but  $\text{AgO}$  is diamagnetic.  $\text{AgO}$  does not contain  $\text{Ag}(+\text{II})$ , but is a mixed oxide  $\text{Ag}^{\text{I}}\text{Ag}^{\text{III}}\text{O}_2$ .


$\text{Au}(+\text{II})$  probably occurs in dithiolene compounds and in  $[\text{Au}(\text{B}_9\text{C}_2\text{H}_{11})_2]^{2-}$ , but otherwise it only exists as a transient intermediate.




### (+III) STATE

The (+III) state is uncommon for Cu and Ag. In alkaline solution  $\text{Cu}^{2+}$  can be oxidized to  $\text{KCu}^{\text{III}}\text{O}_2$ , and if a fused mixture of  $\text{KCl}/\text{CuCl}_2$  is fluorinated,  $\text{K}_3[\text{Cu}^{\text{III}}\text{F}_6]$  is formed. Strong oxidation with periodic acid ( $\text{H}_5\text{IO}_6$ ) gives  $\text{K}_7\text{Cu}^{\text{III}}(\text{IO}_6)_2 \cdot 7\text{H}_2\text{O}$ . Fluorination of a fused mixture of alkali metal halide and silver halide gives  $\text{M}^+[\text{Ag}^{\text{III}}\text{F}_4]^-$ , and electrolytic oxidation of  $\text{Ag}^+$  can give impure  $\text{Ag}_2\text{O}_3$ . Oxidation of alkaline  $\text{Ag}_2\text{O}$  with persulphate gives the mixed oxide  $\text{Ag}^{\text{I}}\text{Ag}^{\text{III}}\text{O}_2$ . Persulphate in the presence of periodate or tellurate ions gives compounds such as  $\text{K}_6\text{H}[\text{Ag}^{\text{III}}(\text{IO}_6)_2]$  and  $\text{Na}_6\text{H}_3[\text{Ag}^{\text{III}}(\text{TeO}_6)_2]$ . These compounds are all unstable and are strong oxidizing agents.

In contrast,  $\text{Au}(+\text{III})$  is the most common state for gold. There are few simple compounds, and these do not contain  $\text{Au}^{3+}$  ions.  $\text{Au}^{\text{III}}$  has a  $d^8$  configuration like  $\text{Pt}^{\text{II}}$ , and like Pt it forms square planar complexes. These compounds decompose to the metal quite readily on heating.




All the halides  $\text{AuX}_3$  are known.  $\text{AuCl}_3$  is made from the elements, or by dissolving gold in aqua regia and evaporating.




$\text{AuBr}_3$  is made from the elements and  $\text{AuI}_3$  is made from the bromide.

$\text{AuF}_3$  can only be formed with a strong fluorinating agent:




The fluoride is made up of square planar  $\text{AuF}_4$  units linked into a chain by *cis* fluoride bridges. The chloride and bromide are dimeric.




The 'liquid gold' used to decorate picture frames, glass and ceramic ornaments is a chloro complex of  $\text{Au}^{\text{III}}$  dissolved in an organic solvent. The complex is probably polymeric, and possibly a cluster compound. When 'liquid gold' is heated it decomposes, leaving a film of metallic gold.

Hydrated gold oxide is amphoteric. It dissolves in alkalis to give salts such as sodium aurate  $\text{NaAuO}_2 \cdot \text{H}_2\text{O}$ , and in strong acids to give  $\text{H}[\text{AuCl}_4]$ ,  $\text{H}[\text{Au}(\text{NO}_3)_4]$  and  $\text{H}[\text{Au}(\text{SO}_4)_2]$ . Cationic  $\text{Au}(\text{+III})$  complexes are also known, e.g.  $[\text{Au}(\text{NH}_3)_4](\text{NO}_3)_3$  which is square planar. The complexes are generally square planar, and more stable than the simple compounds. The dialkyls  $\text{R}_2\text{AuX}$  where  $\text{X} = \text{Cl}^-$ ,  $\text{Br}^-$ ,  $\text{CN}^-$ ,  $\text{SO}_3^-$  are stable organometallic compounds with strong  $\text{Au}-\text{C}$  bonds. The halides are dimeric and the cyanides are tetrameric.



### (+V) STATE

$\text{AuF}_5$  is the only (+V) compound known. It is formed as a dark red diamagnetic polymeric solid by warming  $\text{O}_2\text{AuF}_6$  and condensing the product on a 'cold finger'. The compound is unstable, and decomposes to  $\text{AuF}_3$  and  $\text{F}_2$  above  $60^\circ\text{C}$ .



### BIOLOGICAL ROLE OF COPPER

Copper is essential to life and adult humans contain about 100 mg. This is the third largest amount of a transition metal, after Fe (4 g) and Zn (2 g). Though small amounts of Cu are essential, larger amounts are toxic. About 4–5 mg of Cu are required daily in the diet, and deficiency in animals results in the inability to use iron stored in the liver. Thus the

animal suffers from anaemia. The Cu is bound to proteins in the body either as metalloproteins or as enzymes. Examples include various oxidases and blue proteins. These include:

1. Amine oxidases (oxidation of amines).
2. Ascorbate oxidase (oxidation of ascorbic acid).
3. Cytochrome oxidase (acts with haem as the terminal oxidase step).
4. Galactose oxidase (oxidation of an OH group to CHO in the monosaccharide galactose).

Copper is also important in:

1. Lysine oxidase, which affects the elasticity of aortic walls.
2. Dopamine hydroxylase, which affects brain function.
3. Tyrosinase, which affects skin pigmentation.
4. Ceruloplasmin, which plays a role in Fe metabolism.

Wilson's disease is a hereditary shortage of ceruloplasmin, causing Cu accumulation in the liver, kidneys and brain. This disease is treated by feeding the patient with a chelating agent such as EDTA. The Cu forms a complex and is excreted. At the same time many other essential metals involved in other enzyme systems form EDTA complexes and are excreted. The treatment would thus upset many different enzyme systems, so the required metals must be replaced in the diet and treatment must be very carefully monitored.

Haemocyanin is a copper containing protein which is important as an oxygen carrier in some invertebrate animals. Despite its name it is a non-haem protein. The molecular weight is roughly one million, and the molecule contains two  $\text{Cu}^{\text{II}}$  ions. Despite the  $d^9$  configuration of  $\text{Cu}^{2+}$  the molecule is diamagnetic because of strong antiferromagnetic coupling between the copper ions. Haemocyanin is found in the blood of snails, crabs, lobsters, octapuses, and scorpions. The oxygenated haemocyanins are blue coloured (unlike human blood), and have one dioxygen molecule attached to two Cu atoms. Deoxygenated haemocyanin contains  $\text{Cu}^{\text{I}}$  and is also blue.

There are several blue proteins which contain Cu. They act as electron transfer agents by means of a  $\text{Cu}^{2+}/\text{Cu}^+$  couple. Their colour is much more intense than would be expected for  $d-d$  spectra. The colour is thought to be caused by charge transfer between Cu and S. Examples include plastocyanin and azurin. Plastocyanin occurs in the chloroplasts of green plants, has a molecular weight of about 10 500 and contains one Cu atom. It is important in photosynthesis as an electron carrier. Azurin is found in bacteria. It contains one Cu per molecule and is structurally similar to plastocyanin, but it has a molecular weight of about 16 000.

## FURTHER READING

- Ainscough, E.W. and Brodie, A.M. (1985) Gold chemistry and its medical applications. *Education in Chemistry*, 22, 6-8.

- Beinert, H (1977) Structure and function of copper proteins, *Coordination Chem Rev*, **23**, 119-129
- Canterford, J H and Cotton, R (1968) *Halides of the Second and Third Row Transition Elements*, Wiley, London
- Canterford, J H and Cotton, R (1969) *Halides of the First Row Transition Elements*, Wiley, London
- Dirkse, T P (ed) (1986) *Copper, Silver, Gold, Zinc, Cadmium, Mercury Oxides and Hydroxides*, Pergamon, Oxford
- Gerloch, M (1981) The sense of Jahn-Teller distortions in octahedral copper(II) and other transition metal complexes, *Inorg Chem*, **20**, 638-640
- Gernsheim, H (1977) The history of photography, *Endeavour*, **1**, 18-22
- Hathaway, B J and Billing, D E (1970) The electronic properties and stereochemistry of mono-nuclear complexes of the copper(II) ion, *Coordination Chem Rev*, **5**, 143
- Jardine, F H (1975) Copper I complexes, *Adv Inorg Chem Radiochem*, **17**, 115
- Johnson, B G F and Davis, R (1973) *Comprehensive Inorganic Chemistry*, Vol 3 (Chapter 29 Gold), Pergamon Press, Oxford
- Karlin, K D and Gultneh, Y (1985) Bioinorganic chemical modelling of dioxygen-activation copper proteins, *J Chem Ed*, **62**, 983-987
- Karlin, K D and Zubieta, J (eds) (1986) *Biological and Inorganic Copper Chemistry*, Vol 1, Adenine Press
- Knutton, S (1986) Copper - the enduring metal, *Education in Chemistry*, **23**, 135-137
- Massey, A G (1973) *Comprehensive Inorganic Chemistry*, Vol 3 (Chapter 27 Copper), Pergamon Press, Oxford
- Siegl, H (ed) (1981) *Metal Ions in Biological Systems*, Vol 13, Copper proteins Marcel Dekker, New York
- Sorenson, R J (1989) Copper complexes as 'radiation recovery' agents *Chemistry in Britain*, **25**, 169-170, 172
- Thompson, N R (1973) *Comprehensive Inorganic Chemistry*, Vol 3 (Chapter 28 Silver), Pergamon Press, Oxford
- Valentine, J S and de Freitas, D M (1985) Copper-zinc dismutase, *J Chem Ed*, **62**, 990-996
- West, E G (1969) Developments in copper smelting, *Chemistry in Britain*, **5**, 199-202

# Group 12 – the zinc group

28

Table 28.1 Electronic structures and oxidation states

Element		Electronic structure	Oxidation states*
Zinc	Zn	[Ar] $3d^{10} 4s^2$	<b>II</b>
Cadmium	Cd	[Kr] $4d^{10} 5s^2$	<b>II</b>
Mercury	Hg	[Xe] $4f^{14} 5d^{10} 6s^2$	<b>I II</b>

\* The most important oxidation states (generally the most abundant and stable) are shown in bold. Other well-characterized but less important states are shown in normal type.

## INTRODUCTION

These elements all have a  $d^{10} s^2$  electronic arrangement and they typically form  $M^{2+}$  ions. However, many of their compounds are appreciably covalent. Hg(+II) compounds are more covalent and its complexes are more stable than is the case for Zn and Cd. Because these ions have a complete  $d$  shell, they do not behave as typical transition metals. Though the ions are divalent, they show only slight similarity with Group 2 elements. Thus Zn shows some similarities to Mg. However, Zn is more dense and less reactive due to its smaller radius and higher nuclear charge. Also Zn has a much stronger tendency to form covalent compounds. Zn and Cd are broadly similar in most of their properties. The behaviour of Hg differs appreciably from that of Zn and Cd. In many ways Hg is unique. It is a liquid at room temperature, it is noble, and it forms 'apparently univalent' mercury(I) compounds. Mercury is the only element in the group with a well established (+I) oxidation state. The increased stability of the lowest oxidation state in the heaviest element in the group is more typical of the  $p$ -block elements than the transition elements.

Zn is produced on a large scale. In 1992, 7.3 million tonnes of the metal were produced. It is mostly used as a metal for rustproofing, for casting and for making alloys. ZnO is also important commercially.

Zinc has an important role in several enzymes. Biologically it is the second most important transition metal.

## ABUNDANCE AND OCCURRENCE

Zn occurs in the earth's crust to the extent of 132 ppm by weight. It is the twenty fourth most abundant element. World production of Zn was 7.3 million tonnes in 1992. The main regions where it is mined are Canada 18%, Australia 14%, China 10%, and the Soviet Union, Peru and the USA 8% each. Cd production in 1992 was 20 700 tonnes, and Hg production was 3200 tonnes. Cd and Hg are quite rare. In spite of this the elements are familiar because their extraction and purification are simple.

Table 28.2 Abundance of the elements in the earth's crust by weight

	ppm	Relative abundance
Zn	76	24
Cd	0.16	65
Hg	0.08	66 =

When the earth was formed Zn was deposited as sulphides. ZnS is mined and is called sphalerite in the USA and zinc blende in Europe. The structure is like that of diamond with half the positions occupied by S and half by Zn or some other metal. Sphalerite almost always contains iron, and the formula may be written  $(\text{ZnFe})\text{S}$ . This commonly occurs with galena  $\text{PbS}$ . Hydrothermal weathering of the sulphides gave deposits of carbonates and silicates.  $\text{ZnCO}_3$  is another important ore. It is called smithsonite in the USA (after James Smithson the founder of the Smithsonian Institution in Washington DC), but  $\text{ZnCO}_3$  is called calamine in Europe. Hemimorphite  $\text{Zn}_4(\text{OH})_2(\text{Si}_2\text{O}_7) \cdot \text{H}_2\text{O}$  is less important commercially but is an interesting example of a pyrosilicate. In 1988 the main sources of ores were Canada 19%, the USSR 13.5%, Australia 11%, and China and Peru 7% each. Cadmium ores are very rare. Cd is found as traces in Zn ores and it is extracted from these. Hg is mined as the rather scarce ore cinnabar  $\text{HgS}$  mainly in the USSR, Spain, Mexico and Algeria.


## EXTRACTION AND USES

### Extraction of zinc

Zinc ores (mainly ZnS) are concentrated by flotation, then roasted in air to give ZnO and  $\text{SO}_2$ . (The  $\text{SO}_2$  is used to make  $\text{H}_2\text{SO}_4$ .) Zn is extracted from the oxide by two different processes.

1. ZnO may be reduced by carbon monoxide at  $1200^\circ\text{C}$  in a smelter. The reaction is reversible, and the high temperature is required to move the equilibrium to the right. At this temperature the Zn is gaseous. If

the gaseous mixture of Zn and  $\text{CO}_2$  was simply removed from the furnace and cooled, then some reoxidation of Zn would occur. Thus the zinc powder obtained would contain large amounts of ZnO.



Modern smelters minimize the reoxidation in two ways:

- (a) by having excess carbon, so the  $\text{CO}_2$  formed is converted to CO.
  - (b) by shock cooling the gases leaving the smelter so they do not have time to attain equilibrium. This rapid cooling is achieved by spraying the hot gas with droplets of molten lead. This gives 99% pure Zn. Any cadmium present can be separated by distillation.
2. Alternatively ZnS is heated in air at a lower temperature, yielding ZnO and  $\text{ZnSO}_4$ . These are dissolved in  $\text{H}_2\text{SO}_4$ . Zn dust is added to precipitate Cd, and then the  $\text{ZnSO}_4$  solution is electrolysed to give pure Zn. The electrolytic process is expensive and is not used in the UK.

#### Extraction of cadmium


Cd is found as traces (2–3 parts per thousand) in most Zn ores, and is extracted from these. The ore is treated and yields a solution of  $\text{ZnSO}_4$  containing a small amount of  $\text{CdSO}_4$ . Cd is recovered by adding a more electropositive metal (i.e. one higher in the electrochemical series) to displace it from solution. Zn powder is added to the  $\text{ZnSO}_4/\text{CdSO}_4$  solution, when the Zn dissolves and Cd metal is precipitated. Zn is higher in the electrochemical series than Cd, and elements high in the series displace elements lower in the series.





The Cd concentrate so obtained is then dissolved in  $\text{H}_2\text{SO}_4$ , and purified by electrolysis. The Zn is recovered from the  $\text{ZnSO}_4$  solution by electrolysis.

#### Extraction of mercury

Hg is also scarce. It is mined as the bright red coloured ore cinnabar  $\text{HgS}$  mainly in the USSR, Spain, Mexico and Algeria. Sometimes droplets of Hg are found in these ores. The ore is crushed and as  $\text{HgS}$  has a very high density ( $8.1 \text{ g cm}^{-3}$ ) it is separated from other rocks and concentrated by sedimentation. If the ore is lean, it is heated in air. The Hg vapour formed is condensed, and the  $\text{SO}_2$  is used to make  $\text{H}_2\text{SO}_4$ .



Pich ores are heated with scrap iron or quicklime.



*continued overleaf*



Hg obtained in this way may contain traces of other metals dissolved in it, particularly Pb, Zn and Cd. Very pure Hg may be obtained by blowing air through the metal at  $250^{\circ}\text{C}$ , when traces of other metals form oxides. These oxides float on the surface and are easily removed.

- 1 By scraping them off the surface as scum
- 2 By treatment with dilute  $\text{HNO}_3$ , when the oxides dissolve
- 3 Hg can be purified and separated from the other metals and oxides by distillation. The boiling points are Pb,  $1751^{\circ}\text{C}$ , Zn,  $908^{\circ}\text{C}$ , Cd,  $765^{\circ}\text{C}$ , Hg,  $357^{\circ}\text{C}$ .

#### Uses of zinc

Zn is used in large amounts for coating iron to prevent it from rusting. A thin coating of Zn may be applied electrolytically (galvanizing). Thicker layers may be applied by hot dipping (dipping the metal in molten zinc). The latter process is misleadingly called 'hot galvanizing'. Alternatively the object may be coated with powdered Zn and heated (Sherardizing) or sprayed with molten Zn. Large amounts of Zn are used to make alloys. The most common alloy is brass (a Cu/Zn alloy with 20–50% Zn). Zinc is the most widely used metal for casting metal parts. Zinc is also used as the negative electrode in sealed 'dry' batteries (Leclanche cells, mercury cells and alkaline manganese cells).  $\text{ZnO}$  is sometimes used as a white pigment in paint. It is particularly bright as it absorbs UV light and re-emits it as white light.

#### Uses of cadmium

Most of the Cd produced is used for protecting steel from corrosion. It is applied electrolytically by Cd plating. Cd absorbs neutrons very well, and is used to make control rods for nuclear reactors. Cd is also used for alkaline Ni/Cd storage batteries used both in diesel locomotives and also as the 'nicad' rechargeable 'dry batteries' used in radios and electrical appliances. CdS is an important but expensive yellow pigment. This is used in paint.

#### Uses of mercury


The largest use of mercury is in electrolytic cells for the production of NaOH and  $\text{Cl}_2$ . The electrical industry uses Hg in mercury vapour street lights, switches and rectifiers. Historically Hg has been, and still is, used in the extraction of precious metals (particularly silver and gold) as amalgams. Phenyl mercury(II) acetate and other organomercury compounds have fungicidal and germicidal properties. They are sometimes used in agriculture for treating seeds. Mercury(I) chloride [ $\text{Hg}_2\text{Cl}_2$ ] is used for treating club root, a disease in brassicas (the cabbage family of plants).  $\text{HgO}$  has been used in antifouling paints for ships etc.  $\text{HgCl}_2$  is used to make organo

derivatives. All Hg compounds are toxic, but the organo compounds are extremely dangerous and have lasting ecological effects. Small scale uses of mercury include thermometers, barometers and manometers, amalgams, as a detonator (mercury fulminate) and in some medicines.

## OXIDATION STATES

The elements in this group all have two *s* electrons beyond a completed *d* shell. Removal of the *s* electrons results in divalent compounds, and the (+II) oxidation state is characteristic of the group.

Hg(+I) compounds are important. The univalent ion  $\text{Hg}^+$  does not exist, as mercury(I) compounds are dimerized. Mercury(I) chloride is therefore  $\text{Hg}_2\text{Cl}_2$  and contains  $[\text{Hg}-\text{Hg}]^{2+}$  ions. In these, the two  $\text{Hg}^+$  species which have a  $6s^1$  configuration are bonded together using their *s* electrons. Thus mercury(I) compounds are diamagnetic. Unstable species  $\text{Zn}_2^{2+}$  and  $\text{Cd}_2^{2+}$  have been detected in fused mixtures such as  $\text{Cd}/\text{CdCl}_2$ , and  $\text{Cd}/\text{CdCl}_2/\text{AlCl}_3$ . A yellow compound  $[\text{Cd}_2][\text{AlCl}_4]_2$  has been isolated from such melts, but it disproportionates instantly in water.




The normal trend is that on descending a group the bonds become weaker because the orbitals are larger and more diffuse. Thus overlap is less effective. The reverse trend is observed in this group. The Hg—Hg bond is much stronger than the Cd—Cd bond. This is because the first ionization energy of Hg is much higher than for Cd (Table 28.4), and hence Hg shares electrons more readily.

Oxidation states higher than (+II) do not occur. This is because removal of more electrons would destroy the symmetry of a completed *d* shell.

## SIZE

The ionic radii of the  $\text{M}^{2+}$  ions of Group 12 are appreciably smaller than for the corresponding elements in Group 2. This is because Zn, Cd and Hg have 10 *d* electrons which shield the nuclear charge rather poorly. The difference in size accounts for the lack of similarity in properties between the two groups.



The lanthanide contraction results in the size of the second and third row transition elements being nearly the same. With earlier pairs of transition elements, Zr/Hf and Nb/Ta, the sizes were particularly close. With Cd/Hg the effect of the lanthanide contraction is still felt, but to a much smaller degree.  $\text{Hg}^{2+}$  is larger than  $\text{Cd}^{2+}$  but the increase in size is

Table 28.3 Some physical properties

	Covalent radius (Å)	Ionic radius $M^{2+}$ (Å)	Melting point (°C)	Boiling point (°C)	Density (g cm <sup>-3</sup> )	Pauling's electro- negativity
Zn	1.25	0.740	420	907	7.14	1.6
Cd	1.41	0.95	321	765	8.65	1.7
Hg	1.44	1.02	-39	357	13.534	1.9

smaller than that between  $Zn^{2+}$  and  $Cd^{2+}$ . The chemical evidence is that Cd and Hg are dissimilar.

### IONIZATION ENERGIES

The first ionization energy for Group 12 elements (Table 28.4) is considerably higher than for the corresponding Group 2 elements. This is because the atoms are smaller and the filled *d* level is poorly shielding. The filled 4*f* shell in Hg further increases the binding energy of the outer electrons, and the first ionization energy for Hg is greater than for any other metal. The second ionization energies are high, but  $M^{2+}$  ions are known for all three elements as the solvation or lattice energy is sufficient to offset this. Mercury tends to form covalent compounds. The third ionization energies are so high that (+III) compounds do not exist.

Table 28.4 Promotion and ionization energies

	Promotion energy $s^2 \rightarrow s^1p^1$ (kJ mol <sup>-1</sup> )	Ionization energy (kJ mol <sup>-1</sup> )		
		1st	2nd	3rd
Zn	433	906	1733	3831
Cd	408	876	1631	3616
Hg	524	1007	1810	3302

### GENERAL PROPERTIES

Zn, Cd and Hg show few of the properties associated with typical transition elements. This is because they have a complete *d* shell, which is not available for bonding.

1. Zn and Cd do not show variable valency.
2. They have a  $d^{10}$  electronic configuration and so cannot produce *d-d* spectra. Thus many of their compounds are white. However, some compounds of Hg(+II) and a smaller number of Cd(+II) are highly coloured due to charge transfer from the ligands to the metal. (The

metals of this group are smaller and thus have a greater polarizing power than Group 2 metals. This increases the chance of covalency and also the chance of charge transfer.)

3. The metals are relatively soft compared with the other transition metals. This is probably because the *d* electrons do not participate in metallic bonding.
4. The melting and boiling points are very low. This explains why the metals are more reactive than the copper group, even though the ionization energies for the two groups suggest the reverse. (Nobility is favoured by a high heat of sublimation, a high ionization energy and a low heat of hydration.)



Mercury is the only metal which is liquid at room temperature. The reason for this is that the very high ionization energy makes it difficult for electrons to participate in metallic bonding. The liquid has an appreciable vapour pressure at room temperature. Thus exposed mercury surfaces should always be covered (for example with toluene), to prevent vaporization, and hence poisoning. The gas is unusual because it is monatomic like the noble gases.

Similarities between Group 2 elements with an outer electronic structure  $s^2$  and the zinc group an outer electronic structure  $d^{10}s^2$  are slight. Both groups are divalent. The hydrated sulphates are isomorphous, and double salts such as  $K_2SO_4 \cdot HgSO_4 \cdot 6H_2O$  are analogous to  $K_2SO_4 \cdot MgSO_4 \cdot 6H_2O$ . However, the zinc group is more noble, more covalent, has a much greater ability to form complexes and is less basic.


#### STANDARD REDUCTION POTENTIALS (VOLTS)

Acid solution								
Oxidation state								
+II	+I	0	+II	+I	0	+II	+I	0
$Zn^{2+}$	$\xrightarrow{-0.76}$	Zn	$Cd^{2+}$	$\xrightarrow{-0.40}$	Cd	$Hg^{2+}$	$\xrightarrow{+0.91}$	$Hg_2^{2+} \xrightarrow{+0.79} Hg$
						$\xrightarrow{+0.85}$		

The reactivity decreases from Zn to Cd to Hg. This is shown by their standard reduction potentials. Zn and Cd are electropositive metals. Hg has a positive potential and is therefore quite noble. The large difference between Cd and Hg may be partly explained by Hg having the highest first ionization energy of any metal, and by the higher solvation energy of  $Cd^{2+}$




but



Zn and Cd are silvery solids which tarnish rapidly in moist air. Hg is a silvery liquid and does not tarnish readily. Zn and Cd dissolve in dilute non-oxidizing acids, liberating  $H_2$ , but Hg does not. All three metals react with oxidizing acids such as concentrated  $HNO_3$  and concentrated  $H_2SO_4$  forming salts and evolving a mixture of oxides of nitrogen and  $SO_2$ . Under these conditions Hg forms (+II) salts, but with dilute  $HNO_3$  a mercury(I) salt  $Hg_2(NO_3)_2$  is slowly formed.

Zn is the only element in the group which shows any amphoteric properties, and it is soluble in alkalis, forming zincates. These are formulated  $Na_2[Zn(OH)_4]$ ,  $Na[Zn(OH)_3 \cdot H_2O]$  or  $Na[Zn(OH)_3 \cdot (H_2O)_3]$  similar to aluminates.

All three metals form oxides  $MO$ , sulphides  $MS$  and halides  $MX_2$  by heating the elements. On stronger heating  $HgO$  decomposes, and this has been used as a preparation of  $O_2$ .



All three elements form insoluble sulphides. In qualitative analysis  $CdS$  (yellow) and  $HgS$  (black) are precipitated by passing  $H_2S$  into acidified solutions.  $ZnS$  (white) is more soluble and is precipitated by  $H_2S$  only from alkaline solutions.  $ZnCl_2$  and  $CdCl_2$  are ionic, but  $HgCl_2$  is covalent. The energy to promote an  $s$  electron to a  $p$  level prior to forming two covalent bonds decreases from Zn to Cd, but rather surprisingly increases from Cd to Hg. Zn and Cd react with P to give phosphides, but Hg does not.

All three metals form alloys with several other metals. Those formed by Cu and Zn are called brass, and different brasses have from 20% to 50% Zn. These are commercially important. Alloys of other metals with Hg are called amalgams. Sodium amalgam is produced in the mercury cathode cell in the manufacture of  $NaOH$ . Both zinc and sodium amalgams are used as strong reducing agents in the laboratory. Many of the first row transition elements do not form amalgams, and Mn, Cu and Zn are the only ones to do so. The heavier transition elements form amalgams quite readily.


In a vertical group in the  $d$  block the second and third row elements are very similar in both size and chemical properties and differ from the first row element. In this group Zn and Cd are very similar and differ considerably from Hg.

## OXIDES

$ZnO$  is the only oxide of commercial importance. Its main use is in the production of rubber since it shortens the time taken for vulcanization to occur.  $ZnO$  is also used as a white pigment in paint. It is much less used for this purpose than is  $TiO_2$ , which has a higher refractive index and hence a better covering power.  $ZnO$  is the starting point for making other Zn compounds such as zinc stearate and zinc palmitate. These two compounds are 'soaps' and are used to stabilize plastics and to make paint dry. World production of  $ZnO$  was 366 500 tonnes in 1991.

Basic properties increase down the group. ZnO is amphoteric. It dissolves in acids, forming salts, and in alkali, forming zincates such as  $[\text{Zn}(\text{OH})_4]^{2-}$  and  $[\text{Zn}(\text{OH})_3 \cdot \text{H}_2\text{O}]^-$ . Addition of alkali to an aqueous solution of a  $\text{Zn}^{2+}$  salt first gives a white gelatinous precipitate of  $\text{Zn}(\text{OH})_2$ , which redissolves in excess alkali, forming zincates. CdO is largely basic, but with very strong alkali  $\text{Na}_2[\text{Cd}(\text{OH})_4]$  is formed. Both  $\text{Zn}(\text{OH})_2$  and  $\text{Cd}(\text{OH})_2$  dissolve in excess ammonia, giving ammine complexes. HgO is completely basic.

All three oxides are formed by direct combination of the elements or by heating the nitrates. ZnO and CdO both sublime, showing that they are appreciably covalent. HgO does not sublime as it decomposes on heating.



The thermal stability of the oxides thus decreases from Zn to Cd to Hg.

ZnO is white when cold but turns yellow on heating. It returns to white on cooling. CdO may be yellow, green or brown at room temperature, depending on its previous heat treatment. However, it is white at liquid air temperature. These divalent compounds have a complete *d* shell, so the colour is not from *d-d* spectra. Their colour is due to defects in the solid structure. (On heating ZnO it loses O.) The number of defects increases with temperature and is zero at absolute zero (see Chapter 3). HgO exists in red and yellow forms.

Addition of a base to a solution of the salts precipitates  $\text{Zn}(\text{OH})_2$ ,  $\text{Cd}(\text{OH})_2$  and a yellow form of HgO, not  $\text{Hg}(\text{OH})_2$ . The yellow form of HgO has the same crystal structure as the more common red form which is formed by heating the elements or  $\text{Hg}(\text{NO}_3)_2$ . The difference in colour is due to the particle size.

When  $\text{Zn}(\text{OH})_2$  and  $\text{Cd}(\text{OH})_2$  are treated with  $\text{H}_2\text{O}_2$  they form peroxides which have variable compositions.

## DIHALIDES

All 12 dihalides  $\text{MX}_2$  are known. The fluorides have appreciably higher melting points than the other halides, and the fluorides are ionic. The melting points of the chlorides, bromides and iodides are fairly low. This suggests that they are partly covalent.

$\text{ZnF}_2$ ,  $\text{CdF}_2$  and  $\text{HgF}_2$  are white solids and are considerably more ionic

Table 28.5 Dihalides and their melting points

$\text{ZnF}_2$ 872°C	$\text{CdF}_2$ 1049°C	$\text{HgF}_2$ 645°C (decomp.)
$\text{ZnCl}_2$ 283°C	$\text{CdCl}_2$ 568°C	$\text{HgCl}_2$ 276°C
$\text{ZnBr}_2$ 394°C	$\text{CdBr}_2$ 567°C	$\text{HgBr}_2$ 236°C
$\text{ZnI}_2$ 446°C	$\text{CdI}_2$ 387°C	$\text{HgI}_2$ 259°C

and have higher melting points than the other halides. They are not very soluble in water. This is partly because of their higher lattice energies, and partly because they do not form halogen complexes in solution.  $\text{ZnF}_2$  has the rutile ( $\text{TiO}_2$ ) structure in which  $\text{Zn}^{2+}$  is octahedrally surrounded by six  $\text{F}^-$  ions. The larger  $\text{Cd}^{2+}$  and  $\text{Hg}^{2+}$  ions are eight-coordinate with a fluorite ( $\text{CaF}_2$ ) structure.

$\text{ZnCl}_2$ ,  $\text{ZnBr}_2$  and  $\text{ZnI}_2$  may be considered as close-packed arrays of halide ions, with  $\text{Zn}^{2+}$  ions occupying one quarter of the tetrahedral holes. The  $\text{CdX}_2$  compounds are close-packed arrays of halide ions with  $\text{Cd}^{2+}$  occupying half the octahedral holes. There is a considerable amount of polarization, and the crystal lattices are not completely regular as expected for ionic compounds.  $\text{CdCl}_2$  and  $\text{CdI}_2$  form slightly different layer lattices, in which  $\text{Cd}^{2+}$  ions occupy all the octahedral holes in one layer, and none in the next. This illustrates that they are partly covalent (see Chapter 3). In contrast  $\text{HgCl}_2$ ,  $\text{HgBr}_2$  and  $\text{HgI}_2$  are covalent with low melting points.  $\text{HgCl}_2$  solid contains linear  $\text{Cl}-\text{Hg}-\text{Cl}$  molecules with a bond length  $\text{Hg}-\text{Cl}$  of 2.25 Å. There is little interaction between the Hg and Cl atoms other than between the Hg and the two Cl atoms it is closely associated with (interatomic distance 3.34 Å).  $\text{HgBr}_2$  and  $\text{HgI}_2$  form layer lattices.


The halides are all white except for  $\text{CdBr}_2$  which is pale yellow, and  $\text{HgI}_2$  which exists in red and yellow forms. The colour is due to charge transfer.

The chlorides, bromides and iodides of Zn and Cd are hygroscopic, and are very soluble in water. The solubilities are

$\text{ZnCl}_2$      432 g in 100 g water at 25°C

$\text{CdCl}_2$      140 g in 100 g water at 20°C

The high solubility is partly because the crystal lattice is not very strong (hence the low melting points). Another reason for the high solubility is that the metal ions form a variety of complexes in solution such as  $[\text{Zn}(\text{H}_2\text{O})_6]^{2+}$ ,  $\text{ZnCl}^+_{(\text{hydrated})}$ ,  $\text{ZnCl}_2_{(\text{hydrated})}$  and  $[\text{ZnCl}_4(\text{H}_2\text{O})_2]^{2-}$ . Solutions of  $\text{Zn}^{2+}$  and  $\text{Cd}^{2+}$  salts are acidic because of hydrolysis



Concentrated solutions of  $\text{ZnCl}_2$  are corrosive, and dissolve paper.  $\text{ZnCl}_2$  is commercially important and is used for treating textiles.  $\text{ZnCl}_2$  is also used as a flux for soldering. This is sometimes called *killed salts* and it dissolves metal oxides, thus allowing the solder to stick to a clean metal surface.

Zn salts are usually hydrated. Cd salts are less hydrated and when the halides dissolve they do not ionize completely, and may undergo self-complexing. Thus  $\text{CdI}_2$  may give a mixture of hydrated  $\text{Cd}^{2+}$ ,  $\text{CdI}^+$ ,  $[\text{CdI}_3]^-$  and  $[\text{CdI}_4]^{2-}$  in solution, the proportions depending on the concentration. Mercury(II) salts are usually anhydrous and do not ionize appreciably on dissolution in water.  $\text{HgCl}_2$  is called *corrosive sublimate*. It was made by heating  $\text{HgSO}_4$  and  $\text{NaCl}$  and has been used as an antiseptic since the Middle Ages. It is very poisonous. However, calomel  $\text{Hg}_2\text{Cl}_2$  is used in medicine as a powerful laxative.


## COMPLEXES

$\text{Zn}^{2+}$  and  $\text{Cd}^{2+}$  form complexes with O donor ligands and also with N and S donor ligands and with halide ions.  $\text{Hg}(+II)$  forms complexes with N, P and S donor ligands, but is reluctant to bond to O. The stability of Hg complexes is much greater than that of the other two elements. This is unusual because smaller ions usually complex best. No complexes are known with  $\pi$  bonding ligands such as CO, NO or alkenes. However, Zn and Cd do form complexes with  $\text{CN}^-$ , e.g.  $[\text{Zn}(\text{CN})_4]^{2-}$ . Zn complexes are usually colourless, but Hg complexes (and to a lesser extent Cd complexes) are often coloured because of charge transfer. Coordination numbers from 2 to 8 are known. Since the elements have a  $d^{10}$  configuration there is no crystal field stabilization energy.

$\text{Zn}^{II}$  and  $\text{Cd}^{II}$  occur largely in four-coordination as tetrahedral complexes. Many tetrahedral complexes are known (e.g.  $[\text{MCl}_4]^{2-}$ ,  $[\text{M}(\text{H}_2\text{O})_4]^{2+}$ ,  $[\text{M}(\text{NH}_3)_4]^{2+}$ ,  $[\text{M}(\text{NH}_3)_2(\text{Cl})_2]$ ,  $[\text{Zn}(\text{CN})_4]^{2-}$ ,  $[\text{Zn}(\text{pyridine})_2\text{Cl}_2]$  and  $[\text{Cd}(\text{pyridine})_2\text{Cl}_2]$ ). In  $[\text{Zn}(\text{NCS})_4]^{2+}$  the ligand is bonded through N, but in  $[\text{Cd}(\text{SCN})_4]^{2+}$  the ligands bond through S.

Zn and Cd form several six-coordinate octahedral complexes such as  $[\text{M}(\text{H}_2\text{O})_6]^{2+}$ ,  $[\text{M}(\text{NH}_3)_6]^{2+}$ ,  $[\text{M}(\text{ethylenediamine})_3]^{2+}$  and  $[\text{Cd}(\text{ortho-phenanthroline})_3]^{2+}$ . The octahedral complexes of Zn are not very stable, but Cd forms octahedral complexes more readily and they are more stable than those of Zn because Cd is larger.

Most  $\text{Hg}^{II}$  complexes are octahedral. These are appreciably distorted with two short bonds and four long bonds. In the extreme this distortion results in only two bonds. Examples of this are the compounds  $\text{Hg}(\text{CN})_2$  and  $\text{Hg}(\text{SCN})_2$  and the complex  $[\text{Hg}(\text{NH}_3)_2]\text{Cl}_2$ . The latter contains the linear  $[\text{H}_3\text{N}-\text{Hg}-\text{NH}_3]^{2+}$  ion.  $\text{Hg}^{II}$  also forms some tetrahedral complexes (e.g.  $[\text{Hg}(\text{SCN})_4]^{2-}$  and halide complexes such as  $\text{K}_2[\text{HgI}_4]$ ). The latter is used as Nessler's reagent for the detection and quantitative determination of ammonia in solution. Nessler's reagent gives a yellow colour or brown precipitate with concentrations as low as 1 part per million of  $\text{NH}_3$ . This test is used on drinking water. The presence of  $\text{NH}_4^+$  ions in water at this concentration is not in itself harmful, but it may indicate contamination of the water with sewage. Mercury(II) chloride in solution is mainly  $\text{HgCl}_2$ , but  $[\text{HgCl}_4]^{2-}$  can be formed if  $\text{Cl}^-$  are in excess. In the Hg complexes, two ligands are held more strongly than the others, and some ammine complexes lose ammonia from the solid.



Two-coordinate complexes are rare for Zn and Cd.

Three-coordination is rare but an example is  $[\text{HgI}_3]^-$ . Five-coordination is not common, but examples include  $[\text{CdCl}_5]^{3-}$  and  $[\text{Zn}(\text{terpyridyl})\text{Cl}_2]$ , which have a trigonal bipyramid shape. There are a few complexes with coordination numbers of 7 and 8. Examples of coordination number 8 are  $[\text{Zn}(\text{NO}_3)_4]^{2-}$  and  $[\text{Hg}(\text{NO}_3)_4]^{2-}$ . These involve bidentate O donor ligands with a small 'bite' such as  $\text{NO}_3^-$ , in which two O atoms occupy coordination positions.






Figure 28.1 Structure of basic zinc acetate  $(\text{CH}_3\text{COO})_6 \text{Zn}_4\text{O}$



Zinc forms basic zinc acetate  $(\text{CH}_3\text{COO})_6 \text{Zn}_4\text{O}$ , a complex very like basic beryllium acetate both in structure and properties (see Figure 28.1). The zinc complex hydrolyses more readily than the beryllium complex, as zinc can increase its coordination number to 6.

### MERCURY(+I) COMPOUNDS

Only a few Hg(I) compounds (formerly called mercurous compounds) are known. They contain the ion  $(\text{Hg}-\text{Hg})^{2+}$ , not  $\text{Hg}^+$ . The two Hg atoms are bonded together using the 6s orbitals. Mercury is unique in forming stable dinuclear metal ions. The only other metals which form dinuclear ions are  $(\text{Zn}-\text{Zn})^{2+}$  and  $(\text{Cd}-\text{Cd})^{2+}$ . These ions are unstable and have only been detected spectroscopically in melts of  $\text{Zn}/\text{ZnCl}_2$  and  $\text{Cd}/\text{CdCl}_2$ .


Mercury(I) compounds can be made by reducing the mercury(II) salt with the metal. Alternatively mercury(I) nitrate can be made by dissolving Hg in dilute  $\text{HNO}_3$ . Other salts are made from this by adding  $\text{NaHCO}_3$  to precipitate  $\text{Hg}_2\text{CO}_3$ , and treating this with  $\text{HCl}$ ,  $\text{HF}$ ,  $\text{H}_2\text{SO}_4$ , etc. to produce the salt required.

All four mercury(I) halides are known.  $[\text{Hg}_2]\text{F}_2$  is hydrolysed by water, and then disproportionates:




$[\text{Hg}_2]\text{Cl}_2$ ,  $[\text{Hg}_2]\text{Br}_2$  and  $[\text{Hg}_2]\text{I}_2$  are insoluble in water. The nitrate  $[\text{Hg}_2](\text{NO}_3)_2 \cdot 2\text{H}_2\text{O}$  is soluble in water, and contains the linear  $[\text{H}_2\text{O}-\text{Hg}-\text{Hg}-\text{OH}_2]^{2+}$  ion, and  $[\text{Hg}_2](\text{ClO}_4)_2 \cdot 4\text{H}_2\text{O}$  is also soluble. No oxide, hydroxide or sulphide is known.

The standard reduction potentials are so close that oxidizing agents like  $\text{HNO}_3$  will convert Hg to  $\text{Hg}^{2+}$  rather than Hg(I) if the oxidizing agent is present in excess.



The reduction potential diagram shows that  $[\text{Hg}_2]^{2+}$  is stable to disproportionation by a small margin under standard conditions.




The equilibrium constant  $K$  for the reaction can be calculated from the potential  $E^\circ$ :

$$E^\circ = \frac{RT}{nF} \ln K$$

$$K = \frac{\text{concentration } (\text{Hg}_2)^{2+}}{\text{concentration } \text{Hg}^{2+}} = \text{approx. } 170$$

Thus solutions of mercury(I) compounds contain one  $\text{Hg}^{2+}$  ion for every 170  $[\text{Hg}_2]^{2+}$  ions. The equilibrium is finely balanced. If a reagent is added which removes  $\text{Hg}^{2+}$  from this mixture (by forming either an insoluble compound or a complex) then the equilibrium moves to the left. Under these conditions  $(\text{Hg}_2)^{2+}$  ions disproportionate completely into  $\text{Hg}^{2+}$  and  $\text{Hg}$ . For example, the addition of  $\text{OH}^-$  or  $\text{S}^{2-}$  ions gives a precipitate of  $\text{HgO}$  and  $\text{Hg}$ , or  $\text{HgS}$  and  $\text{Hg}$ . The absence of several mercury(I) compounds such as hydroxides, sulphides and cyanides is because they precipitate  $\text{Hg}^{2+}$ , and allow disproportionation to occur. Conversely, mercury(I) compounds can be made by heating mercury(II) compounds with at least a 50% excess of  $\text{Hg}$ .



In qualitative analysis the presence of  $\text{Hg}_2\text{Cl}_2$  in solution is confirmed by the formation of a black precipitate when treated with  $\text{NH}_4\text{OH}$ . The dark residue may be  $\text{Hg}(\text{NH}_3)_2\text{Cl}_2$ ,  $\text{HgNH}_2\text{Cl}$  or  $\text{Hg}_2\text{NCl} \cdot \text{H}_2\text{O}$  or a mixture of all three together with  $\text{Hg}$ .

Mercury(I) ions form few complexes. This is because of the large size of the binuclear ion, and because most ligands cause disproportionation.

Mercury is unique in the  $\text{Hg}(+I)$  state in that it consists of two directly linked metal atoms. The mercury(I) ion thus has the structure  $[\text{Hg}-\text{Hg}]^{2+}$ . Evidence for this comes from several sources:


### X-ray diffraction

The crystal structures of several mercury(I) compounds have been determined by X-ray diffraction. For example, consider  $\text{Hg}^I\text{Cl}$ . If the compounds comprised  $\text{Hg}^+$  and  $\text{Cl}^-$  the structure should contain alternate  $\text{Hg}^+$  and  $\text{Cl}^-$  ions. It does not have this structure, but contains a linear arrangement  $\text{Cl}-\text{Hg}-\text{Hg}-\text{Cl}$ . The other  $\text{Hg}^I$  compounds also have  $\text{Hg}-\text{Hg}$  pairs rather than discrete  $\text{Hg}^+$  ions. The  $\text{Hg}-\text{Hg}$  bond length varies in different compounds:  $[\text{Hg}_2]\text{F}_2$ , 2.51 Å;  $[\text{Hg}_2]\text{Cl}_2$ , 2.53 Å;  $[\text{Hg}_2]\text{Br}_2$ ,

2.49 Å,  $[\text{Hg}_2]\text{I}_2$  2.69 Å,  $[\text{Hg}_2](\text{NO}_3)_2 \cdot 2\text{H}_2\text{O}$ , 2.54 Å,  $[\text{Hg}_2]\text{SO}_4$ , 2.50 Å. These are all much shorter than the Hg—Hg distance of 3.00 Å in solid mercury.

### Equilibrium constant


Equilibrium constants can be measured and provide evidence about the species present. Mercury(I) compounds can often be made from the corresponding mercury(II) compound by treatment with mercury. If the reaction is



then by the law of mass action

$$\frac{[\text{Hg}^+]^2}{[\text{Hg}^{2+}]} = \text{constant}$$


Experiments have shown this to be untrue. If, however



This has been verified experimentally, thus proving that mercury(I) ions are  $(\text{Hg}_2)^{2+}$ , that is  $(\text{Hg—Hg})^{2+}$ .

### Concentration cell

Measurement of the e.m.f. of a concentration cell of mercury(I) nitrate shows that the mercury(I) ion carries two positive charges. For the cell below, the potential  $E^\circ$  was measured and found to be 0.029 V at 25°C.



$$E = \frac{2.303RT}{nF} \log \frac{c_2}{c_1}$$

Substituting values in this equation

$$0.029 = \frac{0.059}{n} \log \frac{0.05}{0.005}$$

hence

$$n = 2.0$$

The number of charges on the ion  $n$  can be calculated since  $R$  the gas constant,  $T$  the absolute temperature,  $F$  the Faraday, and  $c_1$  and  $c_2$  the concentrations of the solutions, are all known. The value of  $n$  was 2 confirming  $(\text{Hg}_2)^{2+}$ .

### Raman spectra

The Raman spectrum for mercury(I) nitrate contains the lines characteristic of the  $\text{NO}_3^-$  group. Similar lines appear in the spectra of many other nitrates. Mercury(I) nitrate has an extra line in the spectrum at  $171.7 \text{ cm}^{-1}$  which is attributed to the  $\text{Hg—Hg}$  bond. Homonuclear stretching of a diatomic species is Raman active but not infra-red active. This was the first example of Raman spectra identifying a new species.

### Magnetic properties


All mercury(I) compounds are diamagnetic both in the solid state and in solution.  $\text{Hg}^+$  would have an unpaired electron and would be paramagnetic, but in  $[\text{Hg—Hg}]^{2+}$  the electrons are all paired and it should therefore be diamagnetic.

### Cryoscopic measurements


The depression of freezing point produced depends on the number of particles dissolved in the liquid. The observed depression fits for mercury(I) nitrate ionizing into  $\text{Hg}_2^{2+}$  and two  $\text{NO}_3^-$  ions, not into  $\text{Hg}^+$  and  $\text{NO}_3^-$ .

## POLYCATIONS


The compounds  $\text{Hg}_3(\text{AlCl}_4)_2$  and  $\text{Hg}_4(\text{AsF}_6)_2$  contain cations with three and four mercury atoms joined together in an almost linear chain. They can be made by reactions such as:



Their crystal structures give the following bond lengths in the cations:



The bond lengths, though not identical, are within the range shown in most mercury(I) compounds. The nature of the bonding in these ions is of interest. In the mercury(I)  $\text{Hg}_2^{2+}$  ion the two Hg atoms are bonded together using the 6s orbital. This idea cannot be extended to three or four Hg atoms. If the mercury(I) ion was made from a  $\text{Hg}^{2+}$  ion with a Hg atom coordinated to it  $\text{Hg}^{2+} \leftarrow \text{Hg}$ , then this might be extended to the trimer  $\text{Hg} \rightarrow \text{Hg}^{2+} \leftarrow \text{Hg}$ . However, it is hard to see how a linear tetramer could be formed. The answer may lie in multi-centre bonding. An unusual solid  $[\text{Hg}_{2.85}(\text{AsF}_6)]_n$  can be made in liquid  $\text{SO}_2$ :




The crystal structure contains chains of Hg atoms in the  $x$  and  $z$  directions. The compound conducts electricity almost as well as mercury and it becomes a superconductor at low temperatures.

### ORGANOMETALLIC COMPOUNDS


The first organometallic compound was Zeise's salt  $K[Pt(\eta^5-C_5H_5)Cl_3] \cdot H_2O$ . This was isolated in 1825 but remained a chemical curiosity. The first useful organometallic compounds were prepared by Sir Edward Frankland in 1849 and they found use in organic synthesis. These were of two types:

- 1 zinc alkyls  $ZnR_2$  and
- 2 alkyl zinc halides  $RZnX$

They were originally prepared as follows:





The reaction works best with alkyl or aryl iodides, but it is cheaper to use  $RBr$  with a  $Zn/Cu$  alloy.  $CO_2$  may also be used as the inert atmosphere. The products  $ZnR_2$  are either covalent liquids or low melting solids. The alkyl zinc halides  $RZnX$  apparently have the structure:



These were used in organic syntheses before Grignard reagents  $RMgX$  were discovered. Grignard compounds are usually more convenient to make and use.

Organo compounds of  $Zn$  and  $Cd$  (and also  $Li$  and  $Mg$ ) all decompose rapidly on contact with water and air. The  $Zn$  and  $Cd$  alkyls are conveniently prepared from Grignard or alkyl lithium reagents or alkyl mercury compounds:




If required the Grignard type compounds can be made as follows:




$R_2Zn$  and  $R_2Cd$  react in a similar way to Grignard reagents and lithium alkyls, but are less reactive and are unaffected by  $CO_2$ . Their lesser reactivity allows selective alkylation:




The most important use of organocadmium compounds is to produce ketones. This also exploits the lower reactivity of the Cd alkyls, as Grignard reagents would react further with the ketone produced.




A large number of organomercury compounds are known of types  $\text{R}_2\text{Hg}$  and monomeric  $\text{RHgX}$ . They are much more stable to air and water than the zinc compounds. They are easily made by Grignard reactions with  $\text{HgCl}_2$  in tetrahydrofuran, or by reacting  $\text{HgX}_2$  with a hydrocarbon:



Arylmercury compounds may be prepared from mercury(II) acetate:




Organomercury compounds are important for the preparation of organometallic compounds of Groups 1 and 2, Al, Ga, Sn, Pb, Sb, Bi, Se, Te, Zn and Cd.



$\text{HgR}_2$  compounds are covalent liquids or low melting solids. They are extremely poisonous.  $\text{RHgX}$  compounds are solids, and they are extremely toxic. Many  $\text{RHgX}$  compounds, particularly  $\text{EtHgCl}$ ,  $\text{PhHgCl}$  and  $\text{PhHgOOC} > \text{CH}_3$ , and  $\text{Hg}(\text{Me})_2$  have been widely used for treating seeds, and as pesticides and fungicides.

Mercury(II) salts will add to double bonds in alkenes.




Mercury(II) salts also act as catalysts in the hydration of alkynes (acetylenes). The production of ethanal (acetaldehyde) from ethyne (acetylene) is commercially important.




## BIOLOGICAL ROLE OF ZINC

Zn has an important biological role in the enzyme systems of animals and plants. Humans contain about 2 g of Zn. This is the second largest amount of a transition metal after Fe, 4 g. There are about 20 enzymes containing Zn, and some of the best known are as follows:

- 1 Carbonic anhydrase which is present in red blood cells is involved in respiration. It speeds up the absorption of  $\text{CO}_2$  by red blood cells in muscles and other tissues and the reverse reaction involving the release of  $\text{CO}_2$  in the lungs. At the same time it regulates the pH



- 2 Carboxypeptidase which is present in the pancreatic juice is involved in the digestion of proteins by animals and protein metabolism in plants and animals. The enzyme catalyses the hydrolysis of the terminal peptide (amide) link at the carboxyl end of the peptide chain. The enzyme is selective. It works only when the group R in the terminal amino acid is aromatic or a branched aliphatic chain and has the L configuration



- 3 Alkaline phosphatase (energy release)
- 4 Dehydrogenases and aldolases (sugar metabolism)
- 5 Alcohol dehydrogenase (metabolism of alcohol)

### TOXICITY OF CADMIUM AND MERCURY

It is strange that Zn is an essential element for life but that the other two elements in the group Cd and Hg are both extremely toxic. The main threat from Cd is in places near Zn smelters as Cd may escape as dust with flue gases. The manufacture of Ni/Cd batteries has caused problems in Sweden and Japan. There is also concern at the amount of Cd in cigarette smoke. If Cd is ingested it accumulates in the kidneys. It causes mal-function of the kidneys and also replaces Zn in some enzymes thus preventing them from working.

Mercury vapour is toxic and if inhaled can cause giddiness, tremors, lung damage and brain damage. In the laboratory mercury should be covered with oil or toluene and spillages should be treated with flowers of sulphur forming  $\text{HgS}$ .

Inorganic compounds such as  $\text{HgCl}_2$ ,  $\text{Hg}_2\text{Cl}_2$  and  $\text{HgO}$  are also poisonous if eaten. Mercury is a cumulative poison (like Cd, Sn, Pb and Sb). Because they have no biological function there is no mechanism for excreting them from the body.  $\text{Hg}^{II}$  inhibits enzymes particularly those containing thiol groups.

These inorganic mercury compounds have been used for controlling the growth of slime moulds in wood pulp and paper making factories. They are also used in antifouling paints for boats as a fungicide for treating seeds.

and plants, and for treating a plant disease called clubroot in brassicas. More recently organomercury compounds such as dimethyl mercury  $\text{Hg}(\text{Me})_2$  and  $\text{MeHgX}$  have been used for treating seeds against attack by fungi. Alkyl mercury compounds such as dimethyl mercury are much more toxic than inorganic mercury compounds. Aryl mercury compounds are even more dangerous. They cause brain damage giving numbness, loss of vision, deafness, madness and death.

There have been several alarming incidents involving mercury poisoning.

1. In the early 1900s mercury salts were used in the production of felt hats. The dust affected the central nervous system of workers, causing tremor of muscles called 'hatter's shakes'. This led to the expression 'mad as a hatter'!
2. More recently 52 people died at Minamata (Japan) in 1952 through eating fish contaminated by mercury. The Hg came from losses from a factory using  $\text{Hg}^{\text{II}}$  salts to catalyse the production of ethanal (acetaldehyde) from ethyne (acetylene). The  $\text{HgCl}_2$  was converted to an organomercurial compound  $\text{MeHgSMe}$  by anaerobic bacteria in the mud on the sea bed. This is concentrated in the food chain. First it is taken up by plankton, which is eaten by the fish, and other seafood, which in turn is eaten by man. There were outbreaks of mercury poisoning in Japan in 1960 and again in 1965 arising through eating contaminated shellfish.
3. Corn seeds which had been treated with an organomercurial compound to prevent fungal attack were eaten as food rather than being planted to grow a crop in Iraq in 1956 and again in 1960. This resulted in many deaths. There have also been problems through loss of mercury salts used as antifungicides in paper mills in Sweden.

The problems of mercury poisoning are now better understood. Though inorganic mercury salts are poisonous, they are nothing like as toxic as alkyl and aryl mercury compounds. However, the loss of inorganic mercury compounds must be prevented as  $\text{Hg}^{2+}$  and  $(\text{Hg}_2)^{2+}$  can be methylated by bacteria present in rivers, lakes and the sea. Algae, molluscs and fish may concentrate the small amounts present by a factor of 2–10 times, and they may be eaten by something else and concentrated again.  $\text{HgMe}_2$  and  $\text{Hg—Me}^+$  are both very stable and persist for a long time because they have a strong  $\text{Hg—C}$  bond. Considerable efforts are now being made to prevent the discharge of mercury compounds with industrial effluent. The main problems come from acetaldehyde and vinyl chloride monomer plants where mercury compounds are used as a catalyst, and from the electrolytic production of  $\text{NaOH}$  and  $\text{Cl}_2$  where it is used as the cathode.

4. The most recent problem is from the widespread use of mercury to extract gold in Brazil. River water and silt are passed over mercury, when the gold dissolves in the mercury, forming an amalgam. Losses of mercury have poisoned considerable stretches of the Amazon river.



## FURTHER READING

- Bertini, I, Luchinat, C and Monnanni R (1985) Zinc enzymes, *J Chem Ed*, **62**, 924-927
- Bryce Smith, D (1989) Zinc deficiency - the neglected factor, *Chemistry in Britain*, **25**, 783-786
- Coates, G E and Wade, K (1967) *Organometallic Compounds*, 3rd ed, Vol 1, Zinc, Cadmium and Mercury, Methuen, London
- Dirkse, T P (ed) (1986) *Copper, Silver Gold Zinc, Cadmium, Mercury Oxides and Hydroxides*, Pergamon, Oxford
- Friberg, L T and Vostal, J J (1972) *Mercury in the Environment*, CRC Press, Cleveland
- Glocking, F and Craig, P J (1988) *The Biological Alkylation of Heavy Elements*, Special Publication No 66, Royal Society of Chemistry London (Mercury alkyls and aryls in the environment)
- McAuliffe, C A (ed) (1977) *The Chemistry of Mercury*, Macmillan, New York
- Ochai, E I (1988) Uniqueness of zinc as a bioelement, *J Chem. Ed*, **65**, 943-946
- Prince, R H (1979) Some aspects of the biochemistry of zinc, *Adv Inorg Chem Radiochem*, **22**, 349-440
- Richards, A W (1969) Zinc extraction metallurgy in the UK, *Chemistry in Britain*, **5**, 203-206
- Roberts, H L (1968) The chemistry of mercury, *Adv Inorg Chem Radiochem*, **11**, 309
- Valentine, J S and de Freitas, D M (1985) Copper-zinc dismutase, *J Chem Ed*, **62**, 990-996

## PROBLEMS (CHAPTERS 19-28)

- 1 Explain why  $\text{La}_2\text{O}_3$  is not reduced by Al
- 2 Explain why  $\text{TiO}_2$  is white but  $\text{TiCl}_3$  is violet
- 3 Draw the structure of rutile. What is the coordination number of the ions and what is the radius ratio?
- 4 Describe how Ti metal is obtained, and explain why it has been called the wonder metal
- 5 Describe the uses of titanium compounds in paint, in the polymerization of ethene and in the fixation of dinitrogen
- 6 Explain why the physical and chemical properties of Zr and Hf compounds are much more similar than the properties of Ti and Zr
- 7 Describe what happens when the pH of a solution containing  $[\text{VO}_4]^{3-}$  ions is gradually reduced
- 8 When ammonium vanadate is heated with oxalic acid solution, a compound (Z) is formed. A sample of (Z) was titrated with  $\text{KMnO}_4$  solution in hot acidic solution. The resulting liquid was reduced with  $\text{SO}_2$ , the excess  $\text{SO}_2$  boiled off, and the liquid again titrated with  $\text{KMnO}_4$ .

The ratio of the volumes of  $\text{KMnO}_4$  used in the two titrations was 5 : 1. What conclusions can you make regarding the nature of compound (Z) ( $\text{KMnO}_4$  oxidizes all oxidation states of vanadium to vanadium (+V).  $\text{SO}_2$  reduces vanadium (+V) to vanadium (+IV).)

9. Give equations to show the reactions between  $\text{CrO}$ ,  $\text{Cr}_2\text{O}_3$  and  $\text{CrO}_3$  with aqueous acids and alkalis.
10. Describe the structures of chromium(II) acetate and copper(II) acetate, and comment on any unusual features they have.
11. How may the last traces of dioxygen be removed from dinitrogen?
12. Manganese has been described as 'the most versatile element'. Explain this, and show the similarities and differences between the chemistry of manganese and rhenium.
13. Explain why  $[\text{Mn}(\text{OH})_6]^{2+}$  is pale pink,  $\text{MnO}_2$  is black and  $\text{MnO}_4^-$  is intensely coloured purple.
14. Explain why a green solution of potassium manganate(VI)  $\text{K}_2\text{MnO}_4$  turns purple and a brown solid is precipitated when carbon dioxide is bubbled into the solution.
15. Draw the crystal structure of  $\text{ReO}_3$ , and compare it with the perovskite structure.
16. Why do metals such as iron corrode, and how may this be prevented?
17. Describe how iron is extracted from its ores, and how it is converted into steel.
18. What are pig iron, wrought iron, mild steel, high carbon steel and stainless steel?
19. Predict the electronic arrangement on the metal from crystal field splitting and the nature of the ligands in the following complexes: (a)  $[\text{Fe}(\text{H}_2\text{O})_6]^{2+}$ , (b)  $[\text{Fe}(\text{CN})_6]^{4-}$  and (c)  $[\text{Fe}(\text{CN})_6]^{3-}$ . How many unpaired electrons are there in each complex, and what would you expect their magnetic moments to be?
20. Iron pentacarbonyl has a trigonal bipyramidal structure, yet the  $^{13}\text{C}$  nmr spectrum of  $\text{Fe}(^{13}\text{CO})_5$  shows only a single peak even when the sample is held at low temperatures. Two peaks would be expected for a trigonal bipyramidal molecule. (The  $^{13}\text{C}$  nucleus has a spin of  $\frac{1}{2}$  and behaves in much the same way as a proton in nmr.) Explain the unusual spectrum.
21. Compare and contrast the structures of haem, vitamin  $\text{B}_{12}$  and chlorophyll.
22. Outline the essential features involved in the binding of  $\text{O}_2$  to the myoglobin molecule.
23. Write a critical account of the various ways in which the nine elements in the iron, cobalt and nickel groups have been grouped together for comparison purposes.
24. Draw and name the possible isomers of the following complexes: (a)  $[\text{Co}(\text{en})_3]^{3+}$ , (b)  $[\text{Co}(\text{en})_2(\text{SCN})_2]^+$

- 25 A monomeric complex of cobalt gave the following results on analysis

	Co	NH <sub>3</sub>	Cl <sup>-</sup>	SO <sub>4</sub> <sup>2-</sup>
%	21.24	24.77	12.81	34.65

The compound is diamagnetic and contains no other groups or elements except water might be present

Calculate the empirical formula of the compound, give the structural formulae of all possible isomers and suggest methods to distinguish between the isomers

- 26 Give examples of metal clusters in transition metal ions
- 27 Draw the structures of six different carbonyl complexes
- 28 Discuss the origin of square planar complexes formed by Ni(II) and explain what other shapes may be formed
- 29 Suggest reasons why the noble metals are relatively unreactive
- 30 Give examples of compounds containing metal-metal bonds
- 31 Compare and contrast the chemistry of the elements copper, silver and gold
- 32 What are the electronic structures of Zn, Cd and Hg and of their 2+ ions? Discuss their position in the periodic table. Would you expect them to behave as typical transition elements?
- 33 Draw the structure of zinc blende. What is the coordination number of the ions and what is the radius ratio?
- 34 Explain how Zn is sacrificed in the extraction of Cd
- 35 Explain why a solution of zinc sulphate gives a white precipitate when added to an aqueous solution of ammonia but not when added to an aqueous solution of ammonia containing ammonium chloride
- 36 What is cadmium used for? how is it produced and why are there problems of cadmium poisoning in the vicinity of zinc smelters?
- 37 List the main ways in which mercury compounds are discharged into the environment. Comment on the toxicity of inorganic and organo mercury compounds
- 38 Give an account of disproportionation. Why is the mercury(I) ion written Hg<sub>2</sub><sup>2+</sup> whilst the copper(I) ion is written Cu<sup>+</sup>?
- 39 What evidence is there that the mercury(I) ion is Hg<sub>2</sub><sup>2+</sup> rather than Hg<sup>+</sup>?
- 40 When mercury is oxidized with a limited amount of oxidizing agent (i.e. an excess of Hg) then Hg<sup>I</sup> compounds are formed. If there is an excess of oxidizing agent then Hg<sup>II</sup> compounds are formed. Explain this

# The *f*-Block Elements

## Part Five

# The lanthanide series

29

## INTRODUCTION

These 14 elements are called the lanthanons, or lanthanides. They are characterized by the filling up of the antepenultimate  $4f$  energy levels. They are extremely similar to each other in properties, and until 1907 they were thought to be a single element. In the past they were called the rare earths. This name is not appropriate because many of the elements are not particularly rare. Furthermore, the name is not precise since in addition to the 14 lanthanides it has been used to include La, or Sc, Y and La which are  $d$ -block elements, and sometimes Th (an actinide) and Zr (another  $d$ -block element).

## ELECTRONIC STRUCTURE

The electronic structures of the lanthanide metals are shown in Table 29.1. Lanthanum (the  $d$ -block element preceding this series) has the electronic structure: xenon core  $5d^1 6s^2$ . It might be expected that the 14 elements from cerium to lutetium would be formed by adding 1, 2, 3, . . . 14 electrons into the  $4f$  level. However, it is energetically favourable to move the single  $5d$  electron into the  $4f$  level in most of the elements, but not in the cases of Ce, Gd and Lu. The reason why Gd has a  $5d^1$  arrangement is that this leaves a half filled  $4f$  level, which gives increased stability. Lu has a  $5d^1$  arrangement because the  $f$  shell is already full. The lanthanides are characterized by the uniform (+III) oxidation state shown by all the metals. They typically form compounds which are ionic and trivalent. The electronic structures of the ions are  $\text{Ce}^{3+} f^1$ ,  $\text{Pr}^{3+} f^2$ ,  $\text{Nd}^{3+} f^3$ , . . .  $\text{Lu}^{3+} f^{14}$ .

The  $4f$  electrons in the antepenultimate shell are very effectively shielded from their chemical environment outside the atom by the  $5s$  and  $5p$  electrons. Consequently the  $4f$  electrons do not take part in bonding. They are neither removed to produce ions nor do they take any significant part in crystal field stabilization of complexes. Crystal field stabilization is very important with the  $d$ -block elements. The octahedral splitting of  $f$  orbitals  $\Delta_o$  is only about  $1 \text{ kJ mol}^{-1}$ . Whether the  $f$  orbitals are filled or empty has little effect on the normal chemical properties. However, it does affect their spectra and their magnetic properties.

Table 29 1 Electronic structures and oxidation states

Element		Electronic structure of atoms	Electronic structure of $M^{3+}$	Oxidation states*
Lanthanum	La	[Xe] 5d <sup>1</sup> 6s	[Xe]	+III
Cerium	Ce	[Xe] 4f 5d <sup>1</sup> 6s	[Xe] 4f <sup>1</sup>	+III +IV
Praseodymium	Pr	[Xe] 4f <sup>3</sup> 6s	[Xe] 4f <sup>3</sup>	+III (+IV)
Neodymium	Nd	[Xe] 4f <sup>4</sup> 6s <sup>2</sup>	[Xe] 4f <sup>3</sup>	(+II) +III
Promethium	Pm	[Xe] 4f <sup>5</sup> 6s	[Xe] 4f <sup>4</sup>	(+II) +III
Samarium	Sm	[Xe] 4f <sup>6</sup> 6s	[Xe] 4f <sup>5</sup>	(+II) +III
Europium	Eu	[Xe] 4f <sup>7</sup> 6s	[Xe] 4f <sup>6</sup>	+II +III
Gadolinium	Gd	[Xe] 4f <sup>7</sup> 5d <sup>1</sup> 6s	[Xe] 4f <sup>7</sup>	+III
Terbium	Tb	[Xe] 4f <sup>9</sup> 6s	[Xe] 4f <sup>8</sup>	+III (+IV)
Dysprosium	Dy	[Xe] 4f 6s	[Xe] 4f	+III (+IV)
Holmium	Ho	[Xe] 4f <sup>1</sup> 6s <sup>2</sup>	[Xe] 4f	+III
Erbium	Er	[Xe] 4f <sup>1</sup> 6s	[Xe] 4f <sup>11</sup>	+III
Thulium	Tm	[Xe] 4f <sup>11</sup> 6s	[Xe] 4f <sup>1</sup>	(+II) +III
Ytterbium	Yb	[Xe] 4f <sup>14</sup> 6s	[Xe] 4f <sup>11</sup>	+II +III
Lutetium	Lu	[Xe] 4f <sup>14</sup> 5d <sup>1</sup> 6s	[Xe] 4f <sup>14</sup>	+III

\* The most important oxidation states (generally the most abundant and stable) are shown in bold. Other well characterized but less important states are shown in normal type. Oxidation states that are unstable or in doubt are given in parentheses.

## OXIDATION STATES

The sum of the first three ionization energies for each element are given in Table 29 2. The values are low. Thus the oxidation state (+III) is ionic and  $Ln^{3+}$  dominates the chemistry of these elements. The  $Ln^{2+}$  and  $Ln^{4+}$  ions that do occur are always less stable than  $Ln^{3+}$ . (In this chapter the symbol Ln is used to denote any of the lanthanides.) In just the same way as for other elements, the higher oxidation states occur in the fluorides and oxides, and the lower oxidation states occur in the other halides, particularly bromides and iodides. Oxidation numbers (+II) and (+IV) do occur, particularly when they lead to

- 1 a noble gas configuration e.g.  $Ce^{4+}$  ( $f^0$ )
- 2 a half filled  $f$  shell e.g.  $Eu^{2+}$  and  $Tb^{4+}$  ( $f^7$ )
- 3 a completely filled  $f$  level e.g.  $Yb^{2+}$  ( $f^{14}$ )

In addition (+II) and (+IV) states exist for elements that are close to these states. Thus  $Sm^{2+}$  and  $Tm^{2+}$  occur with  $f^6$  and  $f^{11}$  arrangements and  $Pr^{4+}$  and  $Nd^{4+}$  have  $f^1$  and  $f^2$  arrangements. The (+III) state is always the most common and the most stable. The only (+IV) and (+II) states which have any aqueous chemistry are  $Ce^{4+}$ ,  $Sm^{2+}$ ,  $Eu^{2+}$  and  $Yb^{2+}$ .

The lanthanide elements resemble each other much more closely than do a horizontal row of the transition elements. This is because the lanthanides effectively have only one stable oxidation state (+III). Thus in this series

Table 29.2 Ionization energies and standard electrode potentials

		Sum of first three ionization energies (kJ mol <sup>-1</sup> )	$E^\circ$ Ln <sup>3+</sup>   Ln (volts)	Radius Ln <sup>3+</sup> (Å)
Lanthanum	La	3493	-2.52	1.032
Cerium	Ce	3512	-2.48	1.020
Praseodymium	Pr	3623	-2.46	0.99
Neodymium	Nd	3705	-2.43	0.983
Promethium	Pm	—	-2.42	0.97
Samarium	Sm	3898	-2.41	0.958
Europium	Eu	4033	-2.41	0.947
Gadolinium	Gd	3744	-2.40	0.938
Terbium	Tb	3792	-2.39	0.923
Dysprosium	Dy	3898	-2.35	0.912
Holmium	Ho	3937	-2.32	0.901
Erbium	Er	3908	-2.30	0.890
Thulium	Tm	4038	-2.28	0.880
Ytterbium	Yb	4197	-2.27	0.868
Lutetium	Lu	3898	-2.26	0.861

Radii are for six-coordination.

it is possible to compare the effects of small changes in size and nuclear charge on the chemistry of these elements.

### ABUNDANCE AND NUMBER OF ISOTOPES

The lanthanide elements are not particularly rare. Cerium is about as abundant as copper. Apart from promethium, which does not occur in nature, all the elements are more abundant than iodine.

The abundance of the elements and the number of naturally occurring isotopes vary regularly (Table 29.3). Elements with an even atomic number (i.e. an even number of protons in the nucleus) are more abundant than their neighbours with odd atomic numbers (*Harkins' rule*). Elements with even atomic numbers also have more stable isotopes. Elements with odd atomic numbers never have more than two stable isotopes. Throughout the periodic table the stability of a nucleus is related to both the number of neutrons and the number of protons in the nucleus (Table 29.4).

Element 61, promethium, does not occur naturally. It was first made and studied at Oak Ridge in Tennessee, USA, in 1946. Its absence may be explained by Mattauch's rule. This states that if two elements with consecutive atomic numbers each have an isotope of the same weight, one of the isotopes will be unstable. Since elements 60 and 62 have seven isotopes each, there are not many stable mass numbers available for promethium, element 61 (Table 29.5).

According to Mattauch's rule, if promethium is to have a stable isotope, it must have a mass number outside the range 142–150. The only isotopes of Pm which have been made so far are radioactive.

*continued overleaf*

**Table 29.3** Abundance of the elements in the earth's crust by weight and number of natural isotopes

Atomic number	Element	Abundance (ppm) in earth's crust	Relative abundance	Naturally occurring isotopes
58	Ce	66	26	4
59	Pr	9.1	37	1
60	Nd	40	27	7
61	Pm	0		0
62	Sm	7	40	7
63	Eu	2.1	49 =	2
64	Gd	6.1	41	7
65	Tb	1.2	56 =	1
66	Dy	4.5	42	7
67	Ho	1.3	55	1
68	Er	3.5	43	6
69	Tm	0.5	61	1
70	Yb	3.1	44	7
71	Lu	0.8	59	2

**Table 29.4** Numbers of stable nuclei with odd and even numbers of neutrons and odd and even atomic number

Atomic number	Number of neutrons	Stable nuclei
Even	Even	164
Even	Odd	55
Odd	Even	50
Odd	Odd	4

**Table 29.5**

Element 60	142	143	144	145	146	148	150		
Element 62			144			147	148	149	150
								152	154

## EXTRACTION AND USES

World production of rare earth minerals was 80 000 tonnes in 1992 containing 47 900 tonnes of lanthanide oxides  $\text{Ln}_2\text{O}_3$ . The main sources of minerals are the USA 27%, China 20%, Australia 8% and India 6%.

1. Monazite sand is the most important and most widespread mineral. It accounts for 78% of the rare earths mined. Before 1960 monazite was the only source of lanthanides. It is a mixture containing mostly La phosphate and trivalent phosphates of the lighter lanthanide elements (Ce, Pr and Nd). In addition it contains smaller amounts of Y and the heavier lanthanides and thorium phosphate. Th is weakly radioactive.



and traces of its daughter product Ra are also present, and are more radioactive.

2. Bastnaesite is a mixed fluorocarbonate  $M^{III}CO_3F$  where M is La or the lanthanides. Large amounts are mined in the USA, and it provides 22% of the total supply of lanthanides. It is only found in the USA and Madagascar.
3. Very small amounts of another mineral, xenotime, are also mined.

Monazite is treated with hot concentrated  $H_2SO_4$ . Th, La and the lanthanides dissolve as sulphates, and are separated from insoluble material. Th is precipitated as  $ThO_2$  by partial neutralization with  $NH_4OH$ .  $Na_2SO_4$  is used to salt out La and the light lanthanides as sulphates, leaving the heavy lanthanides in solution. The light lanthanides are oxidized with bleaching powder  $Ca(OCl)_2$ .  $Ce^{3+}$  is oxidized to  $Ce^{4+}$  which is precipitated as  $Ce(IO_3)_4$  and removed.  $La^{3+}$  may be removed by solvent extraction with tri-n-butylphosphate. The individual elements can be obtained by ion exchange if required. The treatment of bastnaesite is slightly simpler as it does not contain Th.

Once the different lanthanide elements have been separated completely or partially, the metal may be obtained as follows:

1. By electrolysis of the fused  $LnCl_3$ , with NaCl or  $CaCl_2$  added to lower the melting point.
2. La and the lighter metals Ce to Eu are obtained by reducing anhydrous  $LnCl_3$  with Ca at  $1000-1100^\circ C$  in an argon-filled vessel. The heavier elements have higher melting points and so require a temperature of  $1400^\circ C$ . At this temperature  $CaCl_2$  boils, so  $LnF_3$  are used instead, and in some cases Li is used instead of Ca.

About 5000 tonnes of La and 13000 tonnes of the lanthanides are produced annually. The metals are of little use on their own. The main use is for an unseparated mixture of La and the lanthanides called Mischmetal (50% Ce, 40% La, 7% Fe, 3% other metals). This is added to steel to improve its strength and workability. It is also used in Mg alloys. Mischmetal is also used in small amounts as 'lighter flints'.  $La_2O_3$  is used in Crooke's lenses, which give protection from UV light by absorbing it.  $CeO_2$  is used to polish glass and as a coating in 'self-cleaning' ovens.  $Ce^{IV}(SO_4)_2$  is used as an oxidizing agent in volumetric analysis. Gas mantles are treated with a mixture of 1%  $CeO_2$  and 99%  $ThO_2$  to increase the amount of light emitted by coal gas flames. Other lanthanide oxides are used as phosphors in colour TV tubes. 'Didymium oxide' (a mixture of praseodymium and neodymium oxides) is used with  $CuCl_2$  as the catalyst in the new Deacon process to make  $Cl_2$  from HCl.  $Nd_2O_3$  is used dissolved in  $SeOCl_2$  as a liquid laser. (Selenium oxochloride is used as the solvent because it contains no light atoms which would convert the input energy into heat.) Lanthanide elements are present in *warm superconductors* such as  $La_{(2-x)}Ba_xCuO_{(4-x)}$  and  $YBa_2Cu_3O_{7-x}$ , and others (Sm, Eu, Nb, Dy and Yb) have been substituted. These are described at the end of Chapter 5.

## SEPARATION OF THE LANTHANIDE ELEMENTS

The properties of metal ions are determined by their size and charge. The lanthanides are all typically trivalent and are almost identical in size, and so their chemical properties are almost identical. The separation of one lanthanide from another is an exceedingly difficult task, almost as difficult as the separation of isotopes of one element. The classical methods of separation exploit slight differences in basic properties, stability or solubility. These are outlined below. However, in recent years the only methods used are ion exchange and valency change.

### Precipitation

With a limited amount of precipitating agent the substance with the lowest solubility is precipitated most rapidly and most completely. Suppose hydroxyl ions are added to a solution containing a mixture of  $\text{Ln}(\text{NO}_3)_3$ . The weakest base  $\text{Lu}(\text{OH})_3$  is precipitated first, and the strongest base  $\text{La}(\text{OH})_3$  is precipitated last. The precipitate contains more of the elements at the right of the series. Thus the solution contains more of the elements at the left of the series. The precipitate can be filtered off. Only partial separation is effected, but the precipitate can be redissolved in  $\text{HNO}_3$  and the process repeated to obtain greater purity.

### Thermal reaction

If a mixture of  $\text{Ln}(\text{NO}_3)_3$  is fused, a temperature will be reached when the least basic nitrate changes to the oxide. The mixture is leached with water. The nitrates dissolve and can be filtered off, leaving the insoluble oxides. The oxides are dissolved in  $\text{HNO}_3$  and the process repeated.

### Fractional crystallization

This can be used to separate lanthanide salts. The solubility decreases from La to Lu. Thus salts at the Lu end of the series will crystallize out first. Nitrates, sulphates, bromates, perchlorates and oxalates have all been used as also have double salts such as  $\text{Ln}(\text{NO}_3)_3 \cdot 3\text{Mg}(\text{NO}_3)_2 \cdot 24\text{H}_2\text{O}$  because they crystallize well. The process needs repeating many times to obtain good separations. Non aqueous solvents such as diethyl ether have been used to separate  $\text{Nd}(\text{NO}_3)_3$  and  $\text{Pr}(\text{NO}_3)_3$ .

### Complex formation

A mixture of lanthanide ions is treated with a complexing agent such as EDTA (ethylenediaminetetraacetic acid). All the ions form complexes. Those ions at the right hand side of the lanthanide series such as  $\text{Lu}^{3+}$  form the strongest complexes as they have the smallest ions. Oxalates of the lanthanides are insoluble. However, addition of oxalate ions to this solution does not give a precipitate since the  $\text{Ln}^{3+}$  ions are all complexed with EDTA.




Figure 29.1 EDTA.

If some acid is added to the solution, the least stable EDTA complexes are dissociated. This releases ions at the left hand side of the series  $\text{Ce}^{3+}$ ,  $\text{Pr}^{3+}$ ,  $\text{Nd}^{3+}$  which are immediately precipitated as the oxalates. These are filtered off. Separation is not complete, so the oxalates are redissolved and the process repeated many times.

#### Solvent extraction

The heavier  $\text{Ln}^{3+}$  ions are more soluble in tri-*n*-butylphosphate than are the lighter  $\text{Ln}^{3+}$  ions. Their solubilities in water and ionic solvents, however, are reversed. The ratios of the partition coefficients of  $\text{La}(\text{NO}_3)_3$  and  $\text{Gd}(\text{NO}_3)_3$  between a solution of the metal ions in strong  $\text{HNO}_3$  and tri-*n*-butylphosphate is 1 : 1.06. This difference is quite small, but by using a continuous counter-current apparatus a very large number of partitions can be performed automatically. This is much less tedious than performing 10 000 or 20 000 crystallizations. Kilogram quantities of 95% pure Gd have been obtained by this method. The technique was originally developed in the early days of atomic energy to separate and identify the lanthanide elements produced by fission of uranium.

#### Valency change

A few lanthanides have oxidation states of (+IV) or (+II). The properties of  $\text{Ln}^{4+}$  or  $\text{Ln}^{2+}$  are so different from those of  $\text{Ln}^{3+}$  that separation is fairly easy.

Cerium can be separated from lanthanide mixtures quite easily as it is the only lanthanide which has  $\text{Ln}^{4+}$  ions stable in aqueous solution. Oxidizing a solution containing a mixture of  $\text{Ln}^{3+}$  ions with  $\text{NaOCl}$  under alkaline conditions produces  $\text{Ce}^{4+}$ . Because of the higher charge,  $\text{Ce}^{4+}$  is much smaller and less basic than  $\text{Ce}^{3+}$  or any other  $\text{Ln}^{3+}$ . The  $\text{Ce}^{4+}$  is separated by carefully controlled precipitation of  $\text{CeO}_2$  or  $\text{Ce}(\text{IO}_3)_4$ , leaving the trivalent ions in solution.

Alternatively  $\text{Ce}^{4+}$  can readily be extracted from other  $\text{Ln}^{3+}$  lanthanides by solvent extraction in  $\text{HNO}_3$  solution using tributyl phosphate. Ninety-nine per cent pure Ce can be obtained in one stage from a mixture containing 40% Ce.


In a similar way the properties of  $\text{Eu}^{2+}$  are very different from those of  $\text{Ln}^{3+}$ . Europium sulphate  $\text{Eu}^{2+}\text{SO}_4^{2-}$  resembles the Group 2 sulphates and is insoluble in water.  $\text{Ln}^{3+}$  sulphates are soluble. If a solution of  $\text{Ln}^{3+}$  ions is reduced electrolytically using a mercury cathode, or by using zinc amalgam, then  $\text{Eu}^{2+}$  will be produced. If  $\text{H}_2\text{SO}_4$  is present  $\text{EuSO}_4$  will be

precipitated. This can be filtered off ( $\text{Sm}^{2+}$  and  $\text{Yb}^{2+}$  may also be produced in the same way, but these are oxidized slowly by water).


Valency change is still a useful method for purifying Ce and Eu despite the advent in recent years of ion exchange.

### Ion exchange

This is the most important, the most rapid and most effective general method for the separation and purification of the lanthanides. A solution of lanthanide ions is run down a column of synthetic ion exchange resin such as Dowex-50. This is a sulphonated polystyrene and contains the functional groups  $-\text{SO}_3\text{H}$ . The  $\text{Ln}^{3+}$  ions are absorbed onto the resin and replace the hydrogen atom on  $-\text{SO}_3\text{H}$ .



The  $\text{H}^{+}$  ions produced are washed through the column. Then the metal ions are eluted—that is, are washed off the column in a selective manner. The eluting agent is a complexing agent, for example a buffered solution of citric acid/ammonium citrate or a dilute solution of  $(\text{NH}_4)_4\text{H}_2\text{EDTA}$  at pH 8. Consider the citrate case. An equilibrium is set up



As the citrate solution flows down the column,  $\text{Ln}^{3+}$  ions are removed from the resin and form the citrate complex. A little lower down the column the  $\text{Ln}^{3+}$  ions go back onto the resin. As the citrate solution runs down the column the metal ions form complexes alternately with the resin and the citrate solution many times. The metal ion gradually travels down the column and eventually passes out of the bottom of the column as the citrate complex. The smaller lanthanide ions such as  $\text{Lu}^{3+}$  form stronger complexes with the citrate ions than do the larger ions like  $\text{La}^{3+}$ . Thus the smaller and heavier ions spend more time in solution and less time on the column, and are thus eluted from the column first. The different metal ions present separate into bands which pass down the column. The progress of the bands may be followed spectroscopically by atomic fluorescence. The solution leaving the column is collected by means of an automatic fraction collector in separate containers. By this means the individual elements can be separated. The metals may be precipitated as insoluble oxalates and then heated to give the oxides.

The chromatographic process is analogous to carrying out many separations or many crystallizations, but the separation is carried out on a single column. By using a long ion exchange column the elements may be obtained 99.9% pure with one pass.

### CHEMICAL PROPERTIES OF (+III) COMPOUNDS


The metals are all soft and silvery white. They are electropositive and therefore they are very reactive. The heavier metals are less reactive than the lighter ones because they form a layer of oxide on the surface. The

chemical properties of the group are essentially the properties of trivalent ionic compounds.



The sum of the first three ionization energies varies with minima at  $\text{La}^{3+}$ ,  $\text{Gd}^{3+}$  and  $\text{Lu}^{3+}$  which are associated with attaining an empty, half full or full  $f$  shell. Maxima occur at  $\text{Eu}^{3+}$  and  $\text{Yb}^{3+}$  associated with breaking a half full or full shell.

The standard reduction potentials ( $E^\circ$ ) are all high (Table 29.2). They vary in a regular way over a small range from  $-2.48$  to  $-2.26$  volts, depending on the size of the ions.

The lanthanides are all much more reactive than is Al ( $E^\circ = -1.66$  volts) and are slightly more reactive than Mg ( $E^\circ = -2.37$  volts). Thus they react slowly with cold water, but more rapidly on heating.




The hydroxides  $\text{Ln}(\text{OH})_3$  are precipitated as gelatinous precipitates by the addition of  $\text{NH}_4\text{OH}$  to aqueous solutions. These hydroxides are ionic and basic. They are less basic than  $\text{Ca}(\text{OH})_2$  but more basic than  $\text{Al}(\text{OH})_3$  which is amphoteric. The metals, oxides and hydroxides all dissolve in dilute acids, forming salts.  $\text{Ln}(\text{OH})_3$  are sufficiently basic to absorb  $\text{CO}_2$  from the air and form carbonates. The basicity decreases as the ionic radius decreases from Ce to Lu. Thus  $\text{Ce}(\text{OH})_3$  is the most basic, and  $\text{Lu}(\text{OH})_3$ , which is the least basic, is intermediate between scandium and yttrium in basic strength. The decrease in basic properties is illustrated by the hydroxides of the later elements dissolving in hot concentrated  $\text{NaOH}$ , forming complexes.




The metals tarnish readily in air, and on heating in  $\text{O}_2$  they all give oxides  $\text{Ln}_2\text{O}_3$ . Yb and Lu form a protective oxide film, which prevents the bulk of the metal forming the oxide unless it is heated to  $1000^\circ\text{C}$ . The one exception is Ce which forms  $\text{Ce}^{\text{IV}}\text{O}_2$  rather than  $\text{Ce}_2\text{O}_3$ . The oxides are ionic and basic. Basic strength decreases as the ions get smaller.

The metals react with  $\text{H}_2$ , but often require heating up to  $300\text{--}400^\circ\text{C}$  to start the reaction. The products are solids of formula  $\text{LnH}_2$ . Eu and Yb both have a tendency to form divalent compounds and  $\text{EuH}_2$  and  $\text{YbH}_2$  are salt-like hydrides and contain  $\text{M}^{2+}$  and two  $\text{H}^-$ . The others all form hydrides  $\text{LnH}_2$  which are black, metallic and conduct electricity. These are better formulated as  $\text{Ln}^{3+}$ ,  $2\text{H}^-$  and an electron which occupies a conduction band. In addition Yb forms a nonstoichiometric compound approximating to  $\text{YbH}_{2.5}$ . The hydrides are remarkably stable to heat, often up to  $900^\circ\text{C}$ . They are decomposed by water, and react with oxygen.




These 'dihydrides' take up H if heated under pressure, and all except Eu form salt-like hydrides  $\text{LnH}_3$  made up of  $\text{Ln}^{3+}$  and three  $\text{H}^-$ . These do not have a delocalized electron, and do not show metallic conduction.

The anhydrous halides  $\text{MX}_3$  can be made by heating the metal and halogen or by heating the oxide with the appropriate ammonium halide




The fluorides are very insoluble and can be precipitated from solutions of  $\text{Ln}^{3+}$  by addition of  $\text{Na}^+\text{F}^-$  or  $\text{HF}$ . This is used as a test for the lanthanides in qualitative analysis. However with excess  $\text{F}^-$  the smaller lanthanide ions may form soluble complexes  $[\text{LnF}(\text{H}_2\text{O})_n]^{2+}$ . The chlorides are deliquescent and soluble and crystallize with six or seven molecules of water of crystallization. If the hydrated halides are heated they form oxohalides instead of dehydrating to anhydrous halides




Heating  $\text{CeX}_3 \cdot (\text{H}_2\text{O})_n$  results in  $\text{CeO}$ . The bromides and iodides are similar to the chlorides.

At elevated temperatures the lanthanides react with B giving  $\text{LnB}_4$  and  $\text{LnB}_6$ .

On arc melting the metals with C in an inert atmosphere they form carbides of stoichiometry  $\text{LnC}_2$  and  $\text{Ln}_3(\text{C}_2)_3$ . The carbides can also be made by reducing  $\text{Ln}_2\text{O}_3$  with C in an electric furnace.  $\text{LnC}_2$  are more reactive than  $\text{CaC}_2$ . They react with water giving ethyne and also some hydrogen  $\text{C}_2\text{H}_4$  and  $\text{C}_2\text{H}_6$ . They also show metallic conductivity. They do not contain  $\text{Ln}(+II)$  and are best described as acetylides of  $\text{Ln}^{3+}$  and  $\text{C}_2^{2-}$  with the extra electron in a conduction band



At elevated temperatures the metals also react with N, P, As, Sb and Bi giving  $\text{LnN}$  etc. The latter is hydrolysed by water in a similar way to  $\text{AlN}$




A wide variety of oxosalts are known including nitrates, carbonates, oxalates, sulphates, phosphates and also salts of strongly oxidizing ions such as perchlorates.

### OXIDATION STATE (+IV)

The only (+IV) lanthanide which exists in solution and has any aqueous chemistry is  $\text{Ce}^{4+}$ . It is rare to find 4+ ions in solution. The high charge on the ion leads to it being heavily hydrated and except in strongly acidic solutions the hydrated  $\text{Ce}^{4+}$  is hydrolysed giving polymeric species and  $\text{H}^+$ .  $\text{Ce}(+IV)$  solutions are widely used as an oxidizing agent in volumetric analysis instead of  $\text{KMnO}_4$  and  $\text{K}_2\text{Cr}_2\text{O}_7$ . In classical analysis burettes containing  $\text{Ce}^{4+}$  must be washed with acid since washing with water gives

the hydrated ion. Aqueous cerium(IV) solutions can be prepared by oxidizing a  $\text{Ce}^{3+}$  solution with a very strong oxidizing agent such as ammonium peroxodisulphate  $(\text{NH}_4)_2\text{S}_2\text{O}_8$ .  $\text{Ce}(+\text{IV})$  is also used in organic reactions, for example the oxidation of alcohols, aldehydes and ketones at the  $\alpha$ -carbon atom. The common compounds are  $\text{CeO}_2$  (white when pure) and  $\text{CeO}_2 \cdot (\text{H}_2\text{O})_n$  (a yellow gelatinous precipitate).  $\text{CeO}_2$  can be obtained by heating the metal, or  $\text{Ce}(\text{OH})_3$  or  $\text{Ce}_2^{III}(\text{oxalate})_3$ , in air.  $\text{CeO}_2$  has a fluorite type of structure. It is insoluble in acids and alkalis, but dissolves if reduced, giving  $\text{Ce}^{3+}$  solutions.



$\text{Ce}(\text{SO}_4)_2$  (formerly called ceric sulphate) is well known and is yellow like  $\text{K}_2\text{CrO}_4$ .  $\text{CeF}_4$  is obtained from  $\text{CeF}_3$  and  $\text{F}_2$ . It is white, and is rapidly hydrolysed by water. It has a three-dimensional crystal structure with the metal at the centre of a square antiprism. A number of complexes are stable, for example ammonium cerium(IV) nitrate  $(\text{NH}_4)_2[\text{Ce}(\text{NO}_3)_6]$ . The crystal structure is unusual and contains bidentate  $\text{NO}_3^-$  groups. The Ce atom has a coordination number of 12, and the shape is an icosahedron. This structure is stable even in solution. Two of the  $\text{NO}_3^-$  ions may be replaced by phosphine ligands  $\text{Ph}_3\text{PO}$ , giving a neutral 10-coordinate complex  $[\text{Ce}^{IV}(\text{NO}_3)_4(\text{Ph}_3\text{PO})_2]$ .


The other (+IV) compounds are not stable in water and are known only as oxides, fluorides and a few fluoro complexes. Thus  $\text{PrO}_2$ ,  $\text{PrF}_4$ ,  $\text{Na}_2[\text{PrF}_6]$ ,  $\text{TbO}_2$ ,  $\text{TbF}_4$ ,  $\text{DyF}_4$  and  $\text{Cs}_3[\text{DyF}_7]$  are all known.

The elements Pr, Nd, Tb and Dy also form (+IV) states. These are generally unstable, occur only as solids, and are found as fluorides or oxides which may be nonstoichiometric.

## OXIDATION STATE (+II)

The only (+II) states which have any aqueous chemistry are  $\text{Sm}^{2+}$ ,  $\text{Eu}^{2+}$  and  $\text{Yb}^{2+}$ .

The most stable divalent lanthanide is  $\text{Eu}^{2+}$ . This is stable in water, but the solution is strongly reducing.  $\text{Eu}^{II}\text{SO}_4$  can be prepared by electrolysis of  $\text{Eu}^{III}(\text{SO}_4)_3$  solutions, when the divalent sulphate is precipitated.  $\text{Eu}^{II}\text{Cl}_2$  can be made as a solid by reducing  $\text{Eu}^{III}\text{Cl}_3$  with  $\text{H}_2$ .



Aqueous  $\text{Eu}^{3+}$  solutions can be reduced by Mg, Zn, zinc amalgam or electrolytically to give  $\text{Eu}^{2+}$ .  $\text{EuH}_2$  is ionic and similar to  $\text{CaH}_2$ .  $\text{Eu}(\text{II})$  resembles Ca in several ways:

1. The insolubility of the sulphate and carbonate in water.
2. The insolubility of the dichloride in strong HCl.
3. The solubility of the metals in liquid  $\text{NH}_3$ .

One major difference between Eu and Ca is that the dihalides  $\text{EuX}_2$  have a magnetic moment of 7.9 Bohr magnetons corresponding to seven unpaired electrons, whereas Ca compounds are diamagnetic.

The couple  $\text{Eu}^{3+}|\text{Eu}^{2+}$  has a standard reduction potential of  $-0.41$  volts. This is about the same as for  $\text{Cr}^{3+}|\text{Cr}^{2+}$ , and these are both about the strongest reducing agents that do not reduce water.

$\text{Yb}^{2+}$  and  $\text{Sm}^{2+}$  can be prepared by electrolytic reduction of their trivalent ions in aqueous solution. However, the  $\text{Ln}^{2+}$  ions are readily oxidized by air. These two elements form hydroxides, carbonates, halides, sulphates and phosphates.

The states  $\text{Nd}(+II)$ ,  $\text{Pm}(+II)$ ,  $\text{Sm}(+II)$  and  $\text{Gd}(+II)$  are only found in solid dihalides  $\text{LnCl}_2$  and  $\text{LnI}_2$ . These dihalides can be made by reducing the trihalide with hydrogen, with the metal, or with sodium amalgam. The dihalides such as  $\text{LaI}_2$  and  $\text{NdI}_2$  tend to be nonstoichiometric. They show metallic conduction, and are better represented as  $\text{La}^{3+} + 2\text{I}^- + \text{electron}$ .

A detailed study of the third ionization energy shows the stability of a half filled and completely filled shell. The ionization energies also suggest that there may also be extra stability associated with a three quarters filled shell.

## SOLUBILITY

Salts of the lanthanides usually contain water of crystallization. Solubility depends on the small difference between the lattice energy and the solvation energy, and there is no obvious trend in the group. The solubility of many of the salts follows the pattern of Group 2 elements. Thus the chlorides and nitrates are soluble in water and the oxalates, carbonates and fluorides are almost insoluble. Unlike Group 2, however, the sulphates are soluble. Many of the lanthanides form double salts with the corresponding Group 1 or ammonium salts, e.g.  $\text{Na}_2\text{SO}_4\text{Ln}_2(\text{SO}_4)_3 \cdot 8\text{H}_2\text{O}$  and as these double salts crystallize well, they have been used to separate the lanthanides from one another.

## COLOUR AND SPECTRA

Many trivalent lanthanide ions are strikingly coloured both in the solid state and in aqueous solution. The colour seems to depend on the number of unpaired  $f$  electrons. Elements with  $(n)$   $f$  electrons often have a similar colour to those with  $(14 - n)$   $f$  electrons (See Table 29.6). However, the elements in other valency states do not all have colours similar to their isoelectronic  $3+$  counterparts (Table 29.7).

Colour arises because light of a particular wavelength is absorbed in the visible region. The wavelength absorbed corresponds to the energy required to promote an electron to a higher energy level. In the lanthanides spin orbit coupling is more important than crystal field splitting. In the spectra of transition metals, crystal field splitting is of major importance. All but one of the lanthanide ions show absorptions in the visible or near



Table 29.6 Colour of  $\text{Ln}^{3+}$  ions

	Number of 4f electrons	Colour		Number of 4f electrons	Colour
$\text{La}^{3+}$	0	Colourless	$\text{Lu}^{3+}$	14	Colourless
$\text{Ce}^{3+}$	1	Colourless	$\text{Yb}^{3+}$	13	Colourless
$\text{Pr}^{3+}$	2	Green	$\text{Tm}^{3+}$	12	Pale green
$\text{Nd}^{3+}$	3	Lilac	$\text{Er}^{3+}$	11	Pink
$\text{Pm}^{3+}$	4	Pink	$\text{Ho}^{3+}$	10	Pale yellow
$\text{Sm}^{3+}$	5	Yellow	$\text{Dy}^{3+}$	9	Yellow
$\text{Eu}^{3+}$	6	Pale pink	$\text{Tb}^{3+}$	8	Pale pink
$\text{Gd}^{3+}$	7	Colourless	$\text{Gd}^{3+}$	7	Colourless

Table 29.7 Colours of  $\text{Ln}^{4+}$ ,  $\text{Ln}^{2+}$  and their isoelectronic  $\text{Ln}^{3+}$  counterparts

	Electronic configuration	Isoelectronic $\text{M}^{3+}$
$\text{Ce}^{4+}$ Orange-red	$4f^0$	$\text{La}^{3+}$ Colourless
$\text{Sm}^{2+}$ Blood-red	$4f^6$	$\text{Eu}^{3+}$ Pale pink
$\text{Eu}^{2+}$ Pale greenish yellow	$4f^7$	$\text{Gd}^{3+}$ Colourless
$\text{Yb}^{2+}$ Yellow	$4f^{14}$	$\text{Lu}^{3+}$ Colourless

UV regions of the spectrum. The exception is  $\text{Lu}^{3+}$  which has a full  $f$  shell. These colours arise from  $f-f$  transitions. Strictly these transitions are Laporte forbidden (since the change in the subsidiary quantum number is zero). Thus the colours are pale because they depend on relaxation of the rule. The  $f$  orbitals are deep inside the atom. Thus they are largely shielded from environmental factors such as the nature and number of ligands which form the complexes, and from vibration of the ligands. Thus the position of the absorption band (i.e. the colour) does not change with different ligands. Vibration of the ligands changes the external fields. However, this only splits the various spectroscopic states by about  $100\text{ cm}^{-1}$ , so the absorption bands are unusually sharp. The lanthanides are used for wavelength calibration of instruments because of their sharp absorption bands. For an  $f$  electron the subsidiary quantum number  $l = 3$ , so  $m_l$  may have values 3, 2, 1, 0, -1, -2, -3. Thus a large number of transitions are usually possible. This is in marked contrast to the transition elements where  $d-d$  spectra give absorption bands whose position changes from ligand to ligand, and the width of the peak is greatly broadened because of the vibration of the ligands. It is also possible to get transitions from the  $4f$  to the  $5d$  level. Such transitions give broader peaks and their position is affected by the nature of the ligands.

Absorption spectra of lanthanide ions are useful both for the qualitative detection and the quantitative estimation of lanthanides. Lanthanide elements are sometimes used as biological tracers for drugs in humans and animals. This is because lanthanide elements can quite easily be followed

in the body by spectroscopy, because their peaks are narrow and very characteristic

$\text{Ce}^{3+}$  and  $\text{Yb}^{3+}$  are colourless because they do not absorb in the visible region. However, they show exceptionally strong absorption in the UV region, because of transitions from  $4f$  to  $5d$ . Absorption is very strong for two reasons. Since  $\Delta l = 1$  this is an allowed transition and so gives stronger absorption than forbidden  $f-f$  transitions. Furthermore, promotion of electrons in these ions is easier than for other ions. The electronic configuration of  $\text{Ce}^{3+}$  is  $f^1$  and  $\text{Yb}^{3+}$  is  $f^{14}$ . Loss of one electron gives the extra stability of an empty or half full shell.  $f-d$  peaks are broad, in contrast to the narrow  $f-f$  peaks.

Charge transfer spectra are possible due to the transfer of an electron from the ligand to the metal. This is more probable if the metal is in a high oxidation state or the ligand has reducing properties. Charge transfer usually produces intense colours. The strong yellow colour of  $\text{Ce}^{4+}$  solutions arises from charge transfer rather than  $f-f$  spectra. The blood red colour of  $\text{Sm}^{2+}$  is also due to charge transfer.

### MAGNETIC PROPERTIES

$\text{La}^{3+}$  and  $\text{Ce}^{4+}$  have an  $f^0$  configuration and  $\text{Lu}^{3+}$  has an  $f^{14}$  configuration. These have no unpaired electrons and are diamagnetic. All other  $f$  states contain unpaired electrons and are therefore paramagnetic.

The magnetic moment of transition elements may be calculated from the equation

$$\mu_{(S+L)} = \sqrt{4S(S+1) + L(L+1)}$$

$\mu_{(S+L)}$  is the magnetic moment in Bohr magnetons calculated using both the spin and orbital momentum contributions.  $S$  is the resultant spin quantum number and  $L$  is the resultant orbital momentum quantum number. For the first row transition elements, the orbital contribution is usually quenched out by interaction with the electric fields of the ligands in its environment. Thus as a first approximation the magnetic moment can be calculated using the simple spin only formula ( $\mu_S$  is the spin only magnetic moment in Bohr magnetons,  $S$  is the resultant spin quantum number and  $n$  is the number of unpaired electrons)

$$\mu_S = \sqrt{4S(S+1)}$$

$$\mu_S = \sqrt{n(n+2)}$$

This simple relationship works with  $\text{La}^{3+}$  ( $f^0$ ) and two of the lanthanides  $\text{Gd}^{3+}$  ( $f^7$ ) and  $\text{Lu}^{3+}$  ( $f^{14}$ ).

$\text{La}^{3+}$  and  $\text{Lu}^{3+}$  have no unpaired electrons,  $n = 0$  and  $\mu_S = \sqrt{0(0+2)} = 0$

$\text{Gd}^{3+}$  has seven unpaired electrons,  $n = 7$  and

$$\mu_S = \sqrt{7(7+2)} = \sqrt{63} = 7.9 \text{ BM}$$

The other lanthanide ions do not obey this simple relationship. The  $4f$  electrons are well shielded from external fields by the overlying  $5s$  and  $5p$

electrons. Thus the magnetic effect of the motion of the electron in its orbital is not quenched out. Thus the magnetic moments must be calculated taking into account both the magnetic moment from the unpaired electron spins and that from the orbital motion. This also happens with the second and third row transition elements. However, the magnetic properties of the lanthanides are fundamentally different from those of the transition elements. In the lanthanides the spin contribution  $S$  and orbital contribution  $L$  couple together to give a new quantum number  $J$ .

$$J = L - S \quad \text{when the shell is less than half full}$$

$$\text{and} \quad J = L + S \quad \text{when the shell is more than half full}$$

The magnetic moment  $\mu$  is calculated in Bohr magnetons (BM) by:

$$\mu = g\sqrt{J(J+1)}$$

where

$$g = 1\frac{1}{2} + \frac{S(S+1) - L(L+1)}{2J(J+1)}$$

Figure 29.2 shows the calculated magnetic moments for the lanthanides using both the simple spin only formula, and the coupled spin plus orbital momentum formula. For most of the elements there is excellent agreement between the calculated values using the coupled spin + orbital momentum formula and experimental values measured at 300 K. The range of experimental values are shown as bars.

The agreement for  $\text{Eu}^{3+}$  is poor, and that for  $\text{Sm}^{3+}$  is not very good. The reason is that with  $\text{Eu}^{3+}$  the spin orbit coupling constant is only about  $300\text{ cm}^{-1}$ . This means that the difference in energy between the ground




Figure 29.2 Paramagnetic moments of  $\text{Ln}^{3+}$  lanthanide ions at 300 K. Spin-only values are shown as a broken line, and the spin plus orbital motion as solid lines.

Table 29 8 Magnetic moments of  $\text{La}^{3+}$  and the lanthanide $^{3+}$  ions

Element		Electronic structure of $\text{M}^{3+}$	Magnetic moment	
			Calculated (BM)	Observed (BM)
Lanthanum	La	$[\text{Xe}] 4f^0$	0	0
Cerium	Ce	$[\text{Xe}] 4f^1$	2.54	2.3–2.5
Praseodymium	Pr	$[\text{Xe}] 4f^2$	3.58	3.4–3.6
Neodymium	Nd	$[\text{Xe}] 4f^3$	3.62	3.5–3.6
Promethium	Pm	$[\text{Xe}] 4f^4$	2.68	2.7
Samarium	Sm	$[\text{Xe}] 4f^5$	0.84	1.5–1.6
Europium	Eu	$[\text{Xe}] 4f^6$	0	3.4–3.6
Gadolinium	Gd	$[\text{Xe}] 4f^7$	7.94	7.8–8.0
Terbium	Tb	$[\text{Xe}] 4f^8$	9.72	9.4–9.6
Dysprosium	Dy	$[\text{Xe}] 4f^9$	10.63	10.4–10.5
Holmium	Ho	$[\text{Xe}] 4f^{10}$	10.60	10.3–10.5
Erbium	Er	$[\text{Xe}] 4f^{11}$	9.57	9.4–9.6
Thulium	Tm	$[\text{Xe}] 4f^{12}$	7.63	7.1–7.4
Ytterbium	Yb	$[\text{Xe}] 4f^{13}$	4.50	4.4–4.9
Lutetium	Lu	$[\text{Xe}] 4f^{14}$	0	0

state and the next state is small. Thus the energy of thermal motion is sufficient to promote some electrons and partially populate the higher state. Because of this the magnetic properties are not solely determined by the ground state configuration. Measuring the magnetic moment at a low temperature prevents the population of higher energy levels. The magnetic moment of  $\text{Eu}^{3+}$  at low temperature is close to zero as expected. (The measurement of magnetic moments is described in Chapter 17.)

The unusual shape of the spin plus orbital motion curve arises because of Hund's third rule. When the  $f$  level is less than half full the spin and orbital momenta contributions work in opposition ( $J = L - S$ ). When the  $f$  shell is more than half full they work together ( $J = L + S$ ).

### LANTHANIDE CONTRACTION

Covalent and ionic radii normally increase on descending a group in the periodic table due to the presence of extra filled shells of electrons. On moving from left to right across a period, the covalent and ionic radii decrease. This is because the extra orbital electrons incompletely shield the extra nuclear charge. Thus all the electrons are pulled in closer. The shielding effect of electrons decreases in the order  $s > p > d > f$ . The contraction in size from one element to another is fairly small. However the additive effect over the 14 lanthanide elements from Ce to Lu is about 0.2 Å, and this is known as the lanthanide contraction.

The hardness, melting points and boiling points of the elements all increase from Ce to Lu. This is because the attraction between the atoms increases as the size decreases.

The properties of an ion depend on its size and its charge. The  $\text{Ln}^{3+}$  lanthanide ions change by only a small amount from one element to the next (Table 29.9), and their charge is the same, and so their chemical properties are very similar. Since  $\text{Lu}^{3+}$  is the smallest ion it is the most heavily hydrated. Though the lanthanides do not form complexes very extensively, since  $\text{Lu}^{3+}$  is the smallest ion the complexes formed by  $\text{Lu}^{3+}$  are the strongest.  $\text{La}^{3+}$  and  $\text{Ce}^{3+}$  are the largest ions so  $\text{La}(\text{OH})_3$  and  $\text{Ce}(\text{OH})_3$  are the strongest bases.

The lanthanide contraction reduces the radii of the last four elements in the series below that for Y in the preceding transition series. Since the size of the heavier lanthanide ions, particularly  $\text{Dy}^{3+}$  and  $\text{Ho}^{3+}$ , are similar to that of  $\text{Y}^{3+}$  it follows that their chemical properties are also very similar. As a result the separation of these elements is very difficult.

Table 29.9 Ionic radii of  $\text{Sc}^{3+}$ ,  $\text{Y}^{3+}$  and  $\text{La}^{3+}$  and the  $\text{Ln}^{3+}$  ions (Å)

Sc															
0.745															
Y															
0.900															
La	Ce	Pr	Nd	Pm	Sm	Eu	Gd	Tb	Dy	Ho	Er	Tm	Yb	Lu	
1.032	1.02	0.99	0.983	0.97	0.958	0.947	0.938	0.923	0.912	0.901	0.890	0.880	0.868	0.861	

Ionic radii depend on how many electrons are removed. For simplicity, the radii of ions with the same charge are compared in Table 29.9. A similar change in size across the series is observed if covalent radii are compared (Table 29.10).

Because of this contraction in size across the lanthanide series, the elements which follow in the third transition series are considerably smaller than would otherwise be expected. The normal size increase  $\text{Sc} \rightarrow \text{Y} \rightarrow \text{La}$  disappears after the lanthanides. Thus pairs of elements such as Zr/Hf, Nb/Ta and Mo/W are almost identical in size. The close similarity of properties in such a pair makes chemical separation very difficult. The sizes of the third row of transition elements are very similar to those of the second row of transition elements (see Table 29.10). Thus the second and third rows of transition elements resemble each other more closely than do the first and second rows.

Table 29.10 Covalent radii of the transition elements (Å)

Sc	Ti	V	Cr	Mn	Fe	Co	Ni
1.44	1.32	1.22	1.17	1.17	1.17	1.16	1.15
Y	Zr	Nb	Mo	Tc	Ru	Rh	Pd
1.62	1.45	1.34	1.29	—	1.24	1.25	1.28
La	Hf	Ta	W	Re	Os	Ir	Pt
1.69	1.44	1.34	1.30	1.28	1.26	1.26	1.29

14 Lanthanide elements

## COMPLEXES

The lanthanide ions  $\text{Ln}^{3+}$  have a high charge, which favours the formation of complexes. However, the ions are rather large ( $1.03\text{--}0.86 \text{ \AA}$ ) compared with the transition elements ( $\text{Cr}^{3+} = 0.615 \text{ \AA}$ ,  $\text{Fe}^{3+} = 0.55 \text{ \AA}$  (low spin)) and consequently they do not form complexes very readily. Complexes with amines are not formed in aqueous solution because water is a stronger ligand than the amine. However, amine complexes can be made in non-aqueous solvents. Very few stable complexes are formed with  $\text{CO}$ ,  $\text{CN}^-$  and organometallic groups. This is in contrast to the transition metals. The difference arises because the  $4f$  orbitals are well shielded and are 'inside the atom'. Thus they cannot take part in  $\pi$  back bonding, whereas in the transition elements the  $d$  orbitals are involved in  $\pi$  bonding. The most common and stable complexes are those with chelating oxygen ligands such as citric acid, oxalic acid,  $\text{EDTA}^{4-}$  and acetylacetonate. These complexes frequently have high and variable coordination numbers, and water or solvent molecules are often attached to the central metal.  $\beta$ -Diketone complexes of  $\text{Eu}^{3+}$  and  $\text{Pr}^{3+}$  dissolved in organic solvents are used as lanthanide shift reagents in nmr spectroscopy.

Coordination numbers below 6 are uncommon and occur only with bulky ligands such as  $(2,6\text{-dimethylphenyl})^-$  and  $[\text{N}(\text{SiMe}_3)_2]^-$ . In contrast to the transition elements, the coordination number 6 is not common. The most common coordination numbers are 7, 8 and 9 and these give a variety of stereochemistries. Coordination numbers 10 and 12 occur with the larger (lighter) lanthanides and small chelating ligands  $\text{NO}_3^-$  and  $\text{SO}_4^{2-}$  (Table 29.11).

Complexes with monodentate oxygen ligands are much less stable than the chelates, and tend to dissociate in aqueous solution. There are hardly any complexes with nitrogen donor ligands except ethylenediamine and  $\text{NCS}^-$ , and these are decomposed by water. Fluoride complexes  $\text{LnF}_{(\text{aq})}^{2+}$  are formed particularly by the smaller ions, but chloride complexes are not formed in aqueous media or concentrated  $\text{HCl}$ . This is an important distinction between the lanthanide and actinide groups.

$\text{Ce}^{4+}$  is smaller and more highly charged, and  $[\text{Ce}(\text{NO}_3)_6]^{2-}$  is formed in the non-aqueous solvent  $\text{N}_2\text{O}_4$ , and is 12 coordinate. Each  $\text{NO}_3^-$  uses two oxygen atoms to coordinate to the metal.

The lanthanides form no complexes with  $\pi$  bonding ligands, and the lack of  $\pi$  bonding is attributed to the unavailability of the  $f$  orbitals for bonding.

It is difficult to explain the bonding in complexes with high coordination numbers. If one  $s$  orbital, three  $p$  orbitals and all six  $d$  orbitals in the valency shell are used for bonding, this accounts for a maximum coordination number of 9. The higher coordination numbers of 10 and 12 present a problem. They imply either participation of  $f$  orbitals in bonding, or bond orders of less than one.

There are few organic compounds of the lanthanides. Alkyls and aryls can be made with lithium reagents in ether solution.



Table 29.11 Some lanthanide complexes

Coordination number	Complex	Shape
4	$[\text{Lu}(\text{2,6-dimethylphenyl})_4]^-$	Tetrahedral
6	$[\text{Ce}^{\text{IV}}\text{Cl}_6]^{2-}$	Octahedral
6	$[\text{Er}(\text{NCS})_6]$	Octahedral
7	$[\text{Y}(\text{acetylacetonate})_3\text{H}_2\text{O}]$	Mono-capped trigonal prism
8	$[\text{La}(\text{acetylacetonate})_3(\text{H}_2\text{O})_2]$	Square antiprism
8	$[\text{Ce}^{\text{IV}}(\text{acetylacetonate})_4]$	Square antiprism
8	$[\text{Eu}(\text{acetylacetonate})_3(\text{phenanthroline})]$	Square antiprism
8	$[\text{Ho}(\text{tropolonate})_4]^-$	Dodecahedral
9	$[\text{Nd}(\text{H}_2\text{O})_9]^{3+}$	Tri-capped trigonal prism
10	$[\text{Ce}^{\text{IV}}(\text{NO}_3)_4(\text{Ph}_3\text{PO})_2]$	Complex (each $\text{NO}_3^-$ is bidentate)
12	$[\text{Ce}^{\text{IV}}(\text{NO}_3)_6]^{2-}$	Icosahedral (each $\text{NO}_3^-$ is bidentate)

Cyclopentadienyl compounds  $[\text{Ln}(\text{C}_5\text{H}_5)_3]$ ,  $[\text{Ln}(\text{C}_5\text{H}_5)_2\text{Cl}]$  and  $[\text{Ln}(\text{C}_5\text{H}_5)\text{Cl}_2]$  are known but are sensitive to water and air.


## FURTHER READING

- Bagnall, K.W. (ed.) (1975) *MTP International Review of Science, Inorganic Chemistry* (Series 2), Vol. 7, Lanthanides and Actinides, Butterworths, London.
- Bevan, D.J.M. (1973) *Comprehensive Inorganic Chemistry*, Vol. 3 (Chapter 49: Nonstoichiometric compounds), Pergamon Press, Oxford.
- Brown, D. (1968) *Halides of the Transition Elements*, Vol. I (Halides of the lanthanides and actinides), Wiley, London and New York.
- Bunzli, J.G. and Wessner, D. (1984) Rare earth complexes with neutral macrocyclic ligands, *Coordination Chem. Rev.*, **60**, 191.
- Burgess, J. (1988) *Ions in Solution*, Ellis Horwood, Chichester.
- Callow, R.J. (1967) *The Industrial Chemistry of the Lanthanons, Yttrium, Thorium and Uranium*, Pergamon Press, New York.
- Cotton, S.A. and Härt, F.A. (1975) *The Heavy Transition Metals*, Macmillan, London. (See Chapter 10.)
- Emeléus, H.J. and Sharpe, A.G. (1973) *Modern Aspects of Inorganic Chemistry*, 4th ed. (Chapter 22: Inner transition elements I, the lanthanides), Routledge and Kegan Paul, London.
- Evans, W.J. (1985) Organolanthanide chemistry, *Adv. Organometallic Chem.*, **24**, 131–173.
- Evans, W.J. (1987) Organolanthanide chemistry, *Polyhedron*, **6**, 803–835.
- Greenwood, N.N. (1968) *Ionic Crystals, Lattice Defects and Non-Stoichiometry* (Chapter 6), Butterworths, London.
- Gschneidner, K.A. Jr, and LeRoy, K.A. (eds) (1988) *Handbook on the Physics and Chemistry of the Rare Earths*, North Holland, Amsterdam.
- Johnson D.A. (1977) *Adv. Inorg. Chem. Radiochem.*, **20**, 1. (An excellent review on recent advances in the chemistry of the less common oxidation states of the lanthanide elements.)
- Johnson D.A. (1980) Principles of lanthanide chemistry, *J. Chem. Ed.*, **57**, 475–477.

- Lanthanide and Actinide Chemistry and Spectroscopy* (1980) ACS Symposium, Series 131, American Chemical Society, Washington
- Moller, M., Cerny, P. and Saupe, F. (eds) (1988) *Rare Earth Elements* (Special Publication of the Society for Geology Applied to Mineral Deposits, Vol. 7), Springer Verlag, Berlin
- Muetterties, E. L. and Wright, C. M. (1967) High coordination numbers, *Q. Rev. Chem. Soc.*, **21**, 109
- Subbarao, E. C. and Wallace, W. E. (eds) (1980) *Science and Technology of Rare Earth Materials*, Academic Press, New York
- Yatsimirskii, K. B. and Davidenko, N. K. (1979) Absorption spectra and structure of lanthanide coordination compounds in solution, *Coordination Chem. Rev.*, **27**, 223–273

### PROBLEMS

- 1 Name the lanthanide elements in the correct order, and give their chemical symbols and electronic structures
- 2 In what way are the observed oxidation states of the lanthanides related to their electronic structures?
- 3 Why is it difficult to separate compounds of the lanthanide elements? What methods have been used, and which of these is still used?
- 4 What is the lanthanide contraction, and what are its consequences?
- 5 In what ways does the filling of the 4f energy level affect the rest of the periodic table?
- 6 Contrast the electronic spectra of the lanthanide and transition metal ions. Why do the lanthanide ions give rise to very sharp bands in their electronic spectra, and why are the magnetic properties of their complexes little affected by the nature of the ligands?
- 7 Compare the coordination numbers and stereochemistries commonly found in lanthanide complexes with those commonly found in transition metal complexes
- 8 Work out the number of unpaired electrons in the ground state of the following ions





# The actinides

30

Table 30.1 The elements and their oxidation states

Atomic number	Element	Symbol	Outer electronic structure	Oxidation states*
89	Actinium	Ac	$6d^1 7s^2$	<b>III</b>
90	Thorium	Th	$6d^2 7s^2$	<b>III IV</b>
91	Protactinium	Pa	$5f^2 6d^1 7s^2$	<b>III IV V</b>
92	Uranium	U	$5f^3 6d^1 7s^2$	<b>III IV V VI</b>
93	Neptunium	Np	$5f^4 6d^1 7s^2$	<b>III IV V VI VII</b>
94	Plutonium	Pu	$5f^6 7s^2$	<b>III IV V VI VII</b>
95	Americium	Am	$5f^7 7s^2$	<b>II III IV V VI</b>
96	Curium	Cm	$5f^7 6d^1 7s^2$	<b>III IV</b>
97	Berkelium	Bk	$5f^9 7s^2$	<b>III IV</b>
98	Californium	Cf	$5f^{10} 7s^2$	<b>II III</b>
99	Einsteinium	Es	$5f^{11} 7s^2$	<b>II III</b>
100	Fermium	Fm	$5f^{12} 7s^2$	<b>II III</b>
101	Mendelevium	Md	$5f^{13} 7s^2$	<b>II III</b>
102	Nobelium	No	$5f^{14} 7s^2$	<b>II III</b>
103	Lawrencium	Lr	$5f^{14} 6d^1 7s^2$	<b>III</b>
104	Rutherfordium	Rf	$4f^{14} 6d^2 7s^2$	

\* The most important oxidation states (generally the most abundant and stable) are shown in bold. Other well-characterized but less important states are shown in normal type.

## ELECTRONIC STRUCTURE AND POSITION IN THE PERIODIC TABLE

Examination of the preceding elements in the periodic table shows that francium Fr and radium Ra belong to Groups 1 and 2 and their outermost electrons must be in  $7s$  orbitals. The next element actinium Ac begins to fill the penultimate  $d$  shell ( $—6d^1 7s^2$ ). It has properties typical of the Sc, Y, La group. By analogy with what happened after La, it might be expected that in the following 14 elements electrons would enter the  $5f$  shell and form a second inner transition series. The next 14 elements from atomic number

Immediately after La the  $4f$  orbitals become appreciably lower in energy than the  $5d$  orbitals. Thus in the lanthanides the electrons fill the  $4f$  orbitals in a regular way (apart from minor differences where it is possible to attain a half filled shell). It might have been expected that after Ac the  $5f$  orbitals would become lower in energy than the  $6d$  orbitals. However, for the first four actinide elements Th, Pa, U and Np the difference in energy between  $5f$  and  $6d$  orbitals is small. Thus in these elements (and their ions) electrons may occupy the  $5f$  or the  $6d$  levels, or sometimes both. Later in the actinide series the  $5f$  orbitals do become appreciably lower in energy. Thus from Pu onwards the  $5f$  shell fills in a regular way and the elements become very similar.

However, as the transuranium elements were discovered and studied it became apparent that they were *f*-block elements from

- 1 the sharpness of the lines in their UV-visible spectra
- 2 magnetic studies
- 3 the increasing importance of the (+III) oxidation state

The lanthanide and actinide elements may be compared (Table 30 2)

**Table 30.2** The lanthanide and actinide elements

Transition elements	Lanthanides													
La	Ce	Pr	Nd	Pm	Sm	Eu	Gd	Tb	Dy	Ho	Er	Tm	Yb	Lu
Ac	Th	Pa	U	Np	Pu	Am	Cm	Bk	Cf	Es	Fm	Md	No	Lr
	Actinides													

There are many similarities between the lanthanides and the later actinides. Cm closely resembles Gd, and both have the electronic configuration  $f^7, d^1, s^2$ . The elution of Am, Cm, Bk and Cf from an ion-exchange column exactly parallels that of the lanthanides Eu, Gd, Tb and Dy. The melting points and densities of the actinide elements do not fit with the values for the  $d$ -block (see Appendices II and III).

The elements Pa, U, Np, Pu and Cm have very sharp lines in their absorption spectra. This is a characteristic feature of  $f$ - $f$  spectra. Spectral lines from the actinides are about ten times as intense as those from the lanthanides. If there is only one  $f$  electron present there will be only one peak in the spectrum, and therefore it will be easy to interpret. Usually the spectra are very complex, and are very difficult to interpret. The magnetic properties of the actinides are also difficult to interpret.

Whether the elements possess any  $d$  electrons in their ground state configuration is of little practical importance. In the most common oxidation state (+III) the two  $s$  electrons and the  $d$  electron (if present), will be removed. The energies of the  $5f$  and  $6d$  orbitals are very close. The bond energy is greater than the promotion energy  $5f \rightarrow 6d$ . The  $7s$  and  $7p$  orbitals are of comparable energy. Thus the levels occupied by electrons may change depending on the nature of the ligands, or between the solid state and a solution. It is often impossible to say which orbitals are being used.

The  $5f$  orbitals extend into space beyond the  $6s$  and  $6p$  orbitals and participate in bonding. This is in direct contrast to the lanthanides where the  $4f$  orbitals are buried deep inside the atom, totally shielded by outer orbitals and thus unable to take part in bonding. The participation of the  $5f$  orbitals explains the higher oxidation states shown by the earlier actinide elements. The greater extension of the  $5f$  orbitals compared with the  $4f$  is shown by the difference in electron resonance spectra of  $\text{Nd}^{3+}$  and  $\text{U}^{3+}$  ions in  $\text{CaF}_2$  or  $\text{SrF}_2$ . Both ions have an  $f^3$  ground state (spectroscopic term symbol  $^4I_{9/2}$  – see Chapter 29). The  $\text{U}^{3+}$  signal shows hyperfine structure caused by interaction with fluorine nuclei, whilst  $\text{Nd}^{3+}$  ions do not.

## OXIDATION STATES

The known oxidation states of the elements are shown in Table 30.1.

The (+II) state is quite rare.  $\text{Am}^{2+}$  has an  $f^7$  configuration. It is the analogue of  $\text{Eu}^{2+}$  in the lanthanides, but it only exists in the solid as the fluoride. In contrast  $\text{Cf}^{2+}$ ,  $\text{Es}^{2+}$ ,  $\text{Fm}^{2+}$ ,  $\text{Md}^{2+}$  and  $\text{No}^{2+}$  exist as ions in solution. Their properties are like the Group 2 metals, particularly  $\text{Ba}^{2+}$ . It is the most stable oxidation state for No, and corresponds to an  $f^{14}$  arrangement.


The actinides all have an oxidation state of (+III), like the lanthanides. However, this is not always the most stable oxidation state in the actinides. (+III) is not the most stable oxidation state for the first four elements Th, Pa, U and Np. For example,  $\text{U}^{3+}$  is readily oxidized in air, and in solution. The (+III) state is the most stable state for the later elements  ${}_{95}\text{Am} \rightarrow$

$_{103}\text{Lw}$  (excluding  $_{102}\text{No}$ ) Their properties are similar to those of the lanthanides

The most stable oxidation states for the first four elements are Th (+IV), Pa (+V) and U (+VI). These high oxidation states involve using all the outer electrons (including *f* electrons) for bonding. Though Np(+VII) exists, it is oxidizing and the most stable state is (+V). Pu shows all the oxidation states from (+III) to (+VII), but the most stable is Pu(IV). Am has a range of oxidation states from (+II) to (+VI). However, for Am and almost all the remaining elements the (+III) state is the most stable.

The (+IV) state exists for all the elements from  $_{91}\text{Th}$  to  $_{97}\text{Bk}$ , and it is the most important state for Th and Pu.  $\text{M}^{4+}$  ions are known in acid solution, and are precipitated by  $\text{F}^-$ ,  $\text{PO}_4^{3-}$  and  $\text{IO}_3^-$  ions. The elements all form solid dioxides  $\text{MO}_2$  and fluorides  $\text{MF}_4$ .

The (+V) state occurs for the elements  $_{91}\text{Pa} \rightarrow _{95}\text{Am}$ , and it is the most stable state for Pa and Np. A few solid compounds are known.  $\text{M}^{5+}$  ions do not occur in solution, but  $\text{MO}_2^+$  ions exist between pH 2–4, and these oxoions are linear  $[\text{O}-\text{M}-\text{O}]^+$ . These ions disproportionate rapidly in solution, but are found in solid compounds



The (+VI) state exists as fluorides  $\text{MF}_6$  for the elements U, Np, Pu and Am. The (+VI) state is more widely found as the dioxo ion  $\text{MO}_2^{2+}$ . This ion is linear  $[\text{O}-\text{M}-\text{O}]^{2+}$ , and is stable. It exists both in solution and in crystals. The crystal structure of uranyl nitrate  $\text{UO}_2(\text{NO}_3)_2(\text{H}_2\text{O})_2$  consists of the linear  $(\text{O}-\text{U}-\text{O})^{2+}$  ion surrounded by two  $\text{NO}_3^-$  groups and two  $\text{H}_2\text{O}$  molecules. The  $\text{NO}_3^-$  groups are bidentate, so two O atoms from each  $\text{NO}_3^-$  bond to the U. O atoms from the two  $\text{H}_2\text{O}$  atoms also bond to U, giving a coordination number of 8. Similarly in the crystal structure of sodium uranyl acetate  $\text{Na}[\text{UO}_2(\text{CH}_3\text{COO})_3]$  the acetate groups are bidentate using both O atoms, so U is eight coordinate.

The lower oxidation states tend to be ionic, and the higher ones covalent.  $\text{M}^{2+}$ ,  $\text{M}^{3+}$  and  $\text{M}^{4+}$  ions are all known. Hydrolysis of these ions occurs quite readily, but can be suppressed by using acid solutions. Perchloric acid is often the most suitable as it has little tendency to form complexes. Hydrolysis of compounds in the higher oxidation states give (+V)  $\rightarrow \text{MO}_2^+$  ions and (+VI)  $\rightarrow \text{MO}_2^{2+}$  ions.

## OCCURRENCE AND PREPARATION OF THE ELEMENTS

All the elements after  $_{82}\text{Pb}$ , that is from  $_{81}\text{Bi}$  onwards, have unstable nuclei and undergo radioactive decay. The elements up to and including  $_{92}\text{U}$  occur in nature and have been known for a long time. Even though they undergo radioactive decay, Th and U are by no means rare. They make up 8.1 ppm and 2.3 ppm of the earth's crust respectively. The fact that Th and U occur at all on the earth is because the isotopes  $^{232}_{90}\text{Th}$ ,  $^{235}_{92}\text{U}$  and  $^{238}_{92}\text{U}$  have half-lives sufficiently long for some to have remained since the earth

was formed ( $t_{1/2}$  for  $^{238}_{92}\text{U}$  is  $4.5 \times 10^9$  years, and  $t_{1/2}$  for  $^{235}_{92}\text{U}$  is  $7.04 \times 10^8$  years). The elements following U have shorter half lives, and any present when the earth was formed has already decayed.

If the elements are significantly radioactive they must be handled with care. The later actinides have very short half lives (often a few minutes or less). Thus it is not possible to get high concentrations, or perform anything other than quick tracer experiments. Studying some of the elements is complicated because the radiation decomposes water into H and OH radicals. These radicals may reduce higher oxidation states such as Pu(+VI), Pu(+V), Am(+VI), Am(+V) and Am(+IV).

The radioactivity produces self-heating. Ten grams of  $^{239}\text{Pu}$  generates 0.02 watts of heat. This cannot be used as a large scale power source since this isotope is fissile and thus undergoes nuclear fission. (The critical mass of  $^{239}\text{Pu}$  is only about 1 kg.) The heat may decompose some compounds. It also prevents accurate structure determination by X-ray diffraction, since the atoms have an unusually high degree of thermal motion. The production of heat in this way by some of the actinides is used in light-weight power sources. For example, the heat is used to produce electricity with a thermopile in heart 'pace-makers'. They were used in the first moon probes, the Apollo space mission and in satellites. The isotopes  $^{238}_{94}\text{Pu}$  and  $^{242}_{96}\text{Cm}$  are used for this purpose. They are  $\alpha$  emitters, and very little shielding is required as  $\alpha$  particles are easily stopped by surrounding material.  $^{241}_{95}\text{Am}$  has also been used, but it emits  $\gamma$  rays in addition to  $\alpha$  rays, and thus requires extensive shielding.


Up to 10% Th is found in Monazite sand, mixed with the lanthanides as  $(\text{ThLn})\text{PO}_4$ . It is also found as the ore thorite  $\text{ThSiO}_4$ . U is mined as the ore pitchblende  $\text{UO}_2$ . Very small amounts of Ac, Pa, Np and Pu have been detected in these ores. These four elements are only available by synthetic routes. Plutonium is formed in large amounts by irradiating uranium fuel in nuclear reactors. This is important because plutonium is fissile, and can be used for military purposes (to make atomic weapons) and also as a fuel for nuclear generating stations to make electricity.

The chemistry of Th and U resembles that of the Ti and Cr groups of transition metals in several respects. The elements with higher atomic numbers than U are called the transuranium elements. These have all been produced artificially in the period since 1940. These elements were produced using a nuclear reactor to irradiate suitable elements with neutrons. They are also made using an accelerator to bombard a sample with  $\alpha$  particles (He nuclei), or the nuclei of light atoms such as C, B, N, O or Ne. Most of the transuranium elements were discovered (first made) at the University of California.

## PREPARATION OF THE ACTINIDES

The early members of the series are usually formed by  $(n, \gamma)$  reactions which are usually followed by  $\beta$  emission. They were first made in 1940 by bombardment of U in a cyclotron at Berkeley. They are now obtained


from spent U fuel rods. Though the main reaction in a reactor is fission of  $^{235}_{92}\text{U}$  into two smaller nuclei with the release of a lot of energy, several secondary reactions occur. The U fuel rod is irradiated with *slow neutrons* (of energy 1 MeV). A neutron may be captured by the nucleus in a  $(n, \gamma)$  reaction. The neutron increases the mass number of the nucleus by one and some energy is released as  $\gamma$  radiation. Further neutrons may be added in a similar way. Addition of neutrons increases the neutron to proton ratio (the  $n/p$  ratio). This eventually makes the nucleus unstable because it contains too many neutrons. The nuclei decay by converting a neutron into a proton and a  $\beta$  particle (electron). This reduces the  $n/p$  ratio and also increases the atomic number by one. Thus a new element is formed, one place to the right in the periodic table of the original element (see Chapter 31, under Stability and the ratio of neutrons and protons). When the fuel rod is eventually removed from the reactor, it is processed and the new elements can be recovered. There is not much use for Np so normally only Pu is recovered. (Pu is useful both as a nuclear fuel, and for weapons.)




The yield of the heavier elements is controlled by two factors

- 1 The half lives of the various isotopes
- 2 By their ability to absorb neutrons that is their neutron cross section

Isotopes of elements after Pu can be made by a succession of  $(n, \gamma)$  reactions starting with Pu in a nuclear reactor



The stepwise addition of slow neutrons is tedious. A quicker method is to subject the sample to a very high flux or density of fast neutrons, without allowing time for the intermediate products to decay. This happened during the hydrogen bomb explosions when elements  $_{99}\text{Es}$  einsteinium and  $_{100}\text{Fm}$  fermium were formed. As yet this does not provide a convenient and practicable synthetic route. In reactor fuel elements  $^{238}\text{U}$  adds a fast neutron and then loses two neutrons



An alternative method is to bombard the sample with small ions. These must have sufficient energy to overcome the coulombic repulsion between the ion and the heavy nucleus. These ions are given a high kinetic energy of motion by accelerating them to a great speed in a linear accelerator, or in a


Table 30.3 The main isotopes and their sources

Atomic number Z	Element	Main isotopes	Half life	Source
89	Actinium	$^{227}\text{Ac}$	21.7 years	Natural $^{226}_{88}\text{Ra} \xrightarrow{n\gamma} ^{227}_{88}\text{Ra} \xrightarrow[41 \text{ min}]{\beta} ^{227}_{89}\text{Ac}$
90	Thorium	$^{232}\text{Th}$	$1.4 \times 10^{10}$ years	Naturally occurring ores
91	Protactinium	$^{231}\text{Pa}$	$3.3 \times 10^4$ years	Natural (0.1 ppm in U ores) and from $^{235}\text{U}$ fuel elements
92	Uranium	$^{235}\text{U}$ $^{238}\text{U}$	$7.1 \times 10^8$ years $4.5 \times 10^9$ years	Natural (0.7% abundance in U ores) Natural (99.3% abundance in U ores)
93	Neptunium	$^{237}\text{Np}$	$2.2 \times 10^6$ years	Formed from U fuel elements $^{235}_{92}\text{U} \xrightarrow{n\gamma} ^{236}_{92}\text{U} \xrightarrow{n\gamma} ^{237}_{92}\text{U} \xrightarrow[6.7 \text{ d}]{\beta} ^{237}_{93}\text{Np}$
94	Plutonium	$^{238}\text{Pu}$ $^{239}\text{Pu}$ $^{242}\text{Pu}$ $^{244}\text{Pu}$	86.4 years $2.4 \times 10^4$ years $3.8 \times 10^5$ years $8.2 \times 10^7$ years	Several isotopes are formed in fuel elements $^{237}_{93}\text{Np} \xrightarrow{n\gamma} ^{238}_{93}\text{Np} \xrightarrow[2.1 \text{ d}]{\beta} ^{238}_{94}\text{Pu}$ $^{238}_{92}\text{U} \xrightarrow{n\gamma} ^{239}_{92}\text{U} \xrightarrow[23 \text{ min}]{\beta} ^{239}_{93}\text{Np} \xrightarrow[2.3 \text{ d}]{\beta} ^{239}_{94}\text{Pu}$ $^{239}_{94}\text{Pu} \xrightarrow{\text{three } (n\gamma)} ^{242}_{94}\text{Pu}$ $^{239}_{94}\text{Pu} \xrightarrow{\text{five } (n\gamma)} ^{244}_{94}\text{Pu}$ $^{238}_{92}\text{U} \xrightarrow{(n, 2n)} ^{237}_{92}\text{U} \xrightarrow{n\gamma} ^{238}_{92}\text{U}$ $^{238}_{92}\text{U} \xrightarrow{\alpha n} ^{241}_{94}\text{Pu} \xrightarrow[13.2 \text{ yr}]{\beta} ^{241}_{95}\text{Am}$ $^{239}_{94}\text{Pu} \xrightarrow{\text{four } (n\gamma)} ^{243}_{94}\text{Pu} \xrightarrow{\beta} ^{243}_{95}\text{Am}$ $^{241}_{95}\text{Am} \xrightarrow{(n\gamma)} ^{242}_{95}\text{Am} \xrightarrow[16.0 \text{ h}]{\beta} ^{242}_{96}\text{Cm}$ $^{239}_{94}\text{Pu} \xrightarrow{\alpha n} ^{242}_{96}\text{Cm}$ $^{239}_{94}\text{Pu} \xrightarrow{\text{four } (n\gamma)} ^{243}_{94}\text{Pu} \xrightarrow[5.0 \text{ h}]{\beta} ^{243}_{95}\text{Am} \xrightarrow{n\gamma} ^{244}_{95}\text{Am} \xrightarrow[26 \text{ min}]{\beta} ^{244}_{96}\text{Cm}$ $^{244}_{95}\text{Am} \xrightarrow{\beta} ^{244}_{96}\text{Cm}$
95	Americium	$^{241}\text{Am}$ $^{243}\text{Am}$	433 years $7.7 \times 10^3$ years	
96	Curium	$^{242}\text{Cm}$ $^{244}\text{Cm}$	162 days 17.6 years	
97	Berkelium	$^{249}\text{Bk}$	314 days	Intense and prolonged neutron bombardment of $^{239}\text{Pu}$ in nuclear reactors
98	Californium	$^{249}\text{Cf}$ $^{252}\text{Cf}$	360 years 2.6 years	
99	Einsteinium	$^{254}\text{Es}$	250 days	
100	Fermium	$^{253}\text{Fm}$	4.5 days	
101	Mendelevium	$^{256}\text{Md}$	1.5 hours	
102	Nobelium	$^{254}\text{No}$	3 seconds	Bombardment of $^{252}\text{Cf}$ with $\text{He}^{2+}$ followed by $\beta$
103	Lawrencium	$^{257}\text{Lr}$	8 seconds	Bombardment of $^{246}\text{Cm}$ with $\text{C}^{6+}$
104	Rutherfordium	$^{261}\text{Rf}$	Approx. 70 seconds	Bombardment of $^{252}\text{Cf}$ with $\text{B}^{5+}$






cyclotron The simplest ion used is the  $\alpha$  particle (that is a He nucleus) These increase the mass number by four and the atomic number by two







Often the addition of the helium nucleus upsets the ratio of neutrons to protons (see Chapter 31), and one or more neutrons are emitted The equations for nuclear reactions may either be written showing all the particles in the equation, e g



or in a shorthand way with the particles added and lost shown in brackets



The heaviest elements were obtained by bombarding the sample with accelerated ions  $\text{B}^{5+}$ ,  $\text{C}^{6+}$ ,  $\text{N}^{7+}$  or  $\text{O}^{8+}$



The sources, half lives and mass numbers of the most accessible isotopes are given in Table 30.3

Other isotopes are known, and some have long half lives  $^{247}\text{Bk}$  is only prepared with difficulty by ion bombardment in an accelerator, but it has a half life of about 7000 years

The quantities of these elements which are available are given in Table 30.4 The elements above atomic number 100 fermium exist only as short lived species, and only minute quantities (a few atoms) have been prepared The most stable isotopes are  $^{258}_{101}\text{Md} = 53$  days,  $^{255}_{102}\text{No} = 185$  seconds,  $^{256}_{103}\text{Lr} = 45$  seconds and  $^{261}_{104}\text{Rf} = \text{approx } 70$  seconds

## GENERAL PROPERTIES

Some properties of the elements are given in Table 30.5 The elements are all silvery metals Their melting points are moderately high but are considerably lower than those for the transition elements The size of the ions decreases regularly along the series, because the extra charge on the



Table 30.4 Availability of various isotopes

Tonnes	Kilograms	100 grams	Milligrams	Micrograms
$^{232}\text{Th}$ $^{238}\text{U}$	$^{237}\text{Np}$ $^{239}\text{Pu}$	$^{231}\text{Pa}$ $^{238}\text{Pu}$ $^{242}\text{Pu}$ $^{241}\text{Am}$ $^{243}\text{Am}$ $^{244}\text{Cm}$	$^{244}\text{Pu}$ $^{249}\text{Bk}$ $^{242}\text{Cm}$ $^{252}\text{Cf}$ $^{253}\text{Es}$ $^{254}\text{Es}$	$^{257}\text{Fm}$

Table 30.5 Some properties of the actinides

	m.p. (°C)	b.p. (°C)	Density (g cm <sup>-3</sup> )	Radius M <sup>3+</sup> (Å)	Radius M <sup>4+</sup> (Å)
Ac	817	2470	—	1.12	—
Th	1750	4850	11.8	(1.08)	0.94
Pa	1552	4227	15.4	1.04	0.90
U	1130	3930	19.1	1.025	0.89
Np	640	5235	20.5	1.01	0.87
Pu	640	(3230)	19.9	1.00	0.86
Am	1170	2600	13.7	0.975	0.85
Cm	1340		13.5	0.97	0.85
Bk	986		14.8	0.96	0.83
Cf	(900)			0.95	0.82
Es	(860)				

nucleus is poorly screened by the *f* electrons. This results in an 'actinide contraction' similar to the lanthanide contraction. Comparison of the M<sup>3+</sup> ionic radii with those for lanthanides (Table 29.9) shows that the actinide and lanthanide ions are very similar in size. Hence their chemical properties are alike. However, the actinides have much higher densities and a much greater tendency to form complexes.

The actinides are reactive metals like lanthanum and the lanthanides. They react with hot water, and tarnish in air, forming an oxide coating. In the case of Th this coating is protective, but this is not so with the others. The metals react readily with HCl, but reaction with other acids is slower than expected. Concentrated HNO<sub>3</sub> passivates Th, U and Pu. The metals are basic and do not react with NaOH. They react with oxygen, the halogens and with hydrogen. The hydrides are nonstoichiometric and have ideal formulae MH<sub>2</sub> or MH<sub>3</sub>.

The metals are usually obtained by electrolysis of fused salts, or by reducing the halides with Ca at high temperatures.

## THORIUM

Thorium is by no means rare. It comprises 8.1 ppm of the earth's crust and is the thirty-ninth most abundant element. The main source is monazite

sand in which it occurs up to 10% as the phosphate mixed with phosphates of the lanthanides. Thorium is also found as uranothorite (a mixed silicate of Th and U) in the Sudbury ores (Canada). Monizite is treated with NaOH. The insoluble hydroxides are filtered off and dissolved in HCl. The pH is adjusted to 6 when the hydroxides of Th(IV), U(IV) and Ce(IV) are precipitated. This separates them from the trivalent lanthanides. The hydroxide precipitates are dissolved in 6M HCl and extracted with tributylphosphate and kerosene. If required the metal can be obtained by reducing ThO<sub>2</sub> with Ca or ThCl<sub>4</sub> with Ca or Mg. These reactions must be carried out under an atmosphere of argon as Th is very reactive when hot.


The only stable oxidation state is Th(+IV) and the Th<sup>4+</sup> ion is known both in the solid and in solution. Th(NO<sub>3</sub>)<sub>4</sub> · 5H<sub>2</sub>O is the best known salt and it is very soluble in water. In dilute solutions hydrated ions [Th(H<sub>2</sub>O)<sub>9</sub>]<sup>4+</sup> exist and on adding NaOH a precipitate of Th(OH)<sub>4</sub> is produced. The oxide ThO<sub>2</sub> is formed by heating the nitrate or by heating the metal in air. The oxide is white and has the highest melting point of any oxide (3220°C). It is unreactive except that it dissolves in a mixture of HNO<sub>3</sub> and HF. The other actinide oxides are also refractory.

Anhydrous halides ThX<sub>4</sub> are formed by direct reaction. They are also formed by strongly heating the oxide with the appropriate halogen acid or heating the oxide with CCl<sub>4</sub> at 600°C. The halides are high melting and white. On strong heating ThI<sub>4</sub> decomposes to the elements. This has been used to purify the metal by the van Arkel method (see Chapter 6 under Thermal decomposition methods of extraction). The halides hydrolyse in moist air giving oxohalides ThOX. The white colour of Th(IV) compounds is associated with the absence of *d* or *f* electrons. The high charge of Th<sup>4+</sup> favours the formation of complexes. These often have high coordination numbers and uncommon structures (Table 30.6).

Table 30.6 Some high coordination numbers

	Coordination number	Shape
K <sub>4</sub> [Th(oxalate) <sub>4</sub> ] · 4H <sub>2</sub> O	8	Square antiprism
(NH <sub>4</sub> ) <sub>4</sub> [ThF <sub>8</sub> ]	9	Tricapped trigonal prism (ThF <sub>9</sub> ) sharing two edges to give infinite chains
Mg[Th(NO <sub>3</sub> ) <sub>6</sub> ]	12	Icosahedral. The NO <sub>3</sub> groups are bidentate

Th(III) compounds are rare and are only found as solids. ThI<sub>3</sub> and ThOF have been made but they react with water forming Th(IV) and liberating hydrogen. ThI<sub>3</sub> and ThI can be made




ThI is a gold coloured solid and is a good electrical conductor. These lower valent compounds all have some metallic conduction. ThI is

probably  $\text{Th}^{4+}$ ,  $2\text{I}^-$  and 2 electrons in a conduction band.  $\text{ThI}_3$  is probably  $\text{Th}^{4+}$ ,  $3\text{I}^-$  and an electron in a conduction band.  $\text{ThS}$  has also been made.

About 500 tonnes of thorium compounds are produced annually. The two industrial uses are as follows:

1. When thorium dioxide containing 1% cerium is heated in a gas flame it emits a brilliant white light. Because of this it was widely used for making incandescent gas mantles. At one time gas lighting provided the main source of artificial light. (Electric light bulbs and fluorescent tubes have largely replaced gas lighting except for mobile use, e.g. in caravans. However, making gas mantles still accounts for half the Th produced.)
2. Naturally occurring thorium is almost entirely  $^{232}\text{Th}$ . This isotope is not fissionable, but if irradiated in the outer part of a nuclear reactor,  $^{233}\text{U}$  is formed.



This isotope of uranium does not occur in nature, and has a half life of  $1.6 \times 10^5$  years. It is fissionable. Since more reactor fuel is produced than is consumed by the reactor it is important as the basis of 'breeder-reactors'.

## PROTACTINIUM

Traces of Pa (about 0.1 ppm of  $^{231}\text{Pa}$ ) are found in the uranium ore pitchblende  $\text{UO}_2$ . The Pa is formed as a decay product of  $^{235}\text{U}$  in the actinium decay series (see Chapter 31). It also occurs in the neptunium and uranium natural decay series. It is difficult to isolate Pa from minerals. It is usually prepared artificially either from Th by the reaction given above, or obtained as  $^{231}\text{Pa}$  from processing spent uranium fuel elements removed from nuclear reactors.

The study of protactinium is a story of scientific cooperation which is rarely encountered. The chemistry of this element was almost unknown until 1960 when A.G. Maddock and a team at the UK Atomic Energy Authority extracted 130 g of the element from over 50 tonnes of waste from the extraction of U. They sent samples to major laboratories throughout the world. This rapidly produced most of the information on this element.

The chemistry of Pa is particularly difficult to study because the compounds hydrolyse readily. In addition the ions polymerize forming colloidal precipitates in water and most acids. These precipitates are adsorbed on to the vessel walls or onto other precipitates. Colloidal precipitates are not formed when Pa is handled in fluoride solutions, because it forms fluoride complexes.

Pa can be extracted from solutions in  $\text{HCl}$  or  $\text{HNO}_3$  by tributyl phosphate. It is then precipitated as  $\text{PaF}_4$ , and reduced to the metal with

Ba at 1400°C Pa has been obtained in 100 g quantities. The metal is shiny, malleable, and tarnishes in air.

The most stable oxidation state is (+V).  $\text{Pa}_2\text{O}_5$  is obtained as a white solid by igniting Pa compounds in air. The oxide is weakly acidic as it is attacked by fused alkali. Heating in a vacuum, or reduction with hydrogen at 1500°C, gives a black nonstoichiometric phase  $\text{PaO}_{2.3}$  and eventually  $\text{PaO}_2$ .  $\text{PaF}_5$  can be made by the action of  $\text{F}_2$  on  $\text{PaF}_4$ , or  $\text{BrF}_3$  on  $\text{Pa}_2\text{O}_5$ . It is reactive, and can be sublimed.  $\text{PaCl}_5$  and oxohalides  $\text{PaOX}_3$  and  $\text{PaO}_2\text{X}$  are also known. Pa(V) complexes with oxalate, citrate, tartrate, sulphate and phosphate ions are known, and some unusual fluoride complexes have been studied. In  $\text{Rb}[\text{PaF}_6]$  the Pa atom is eight coordinate. The complex  $\text{K}_2[\text{PaF}_7]$  contains nine coordinate  $\text{PaF}_9$  groups. These form two F bridges to neighbouring groups on either side, giving a chain. In  $\text{Na}_3[\text{PaF}_8]$  the  $[\text{PaF}_8]^{3-}$  ion is a slightly distorted cube. In the (+IV) state,  $\text{PaO}_2$  and the halides  $\text{PaX}_4$  are all known, and also oxohalides  $\text{PaOX}_2$ . Reduction of aqueous Pa(V) solutions with zinc amalgam or  $\text{Cr}^{2+}$  gives Pa(IV), but this is readily oxidized by air. Spectra of  $\text{PaCl}_4$  in  $\text{HCl}$  or  $\text{HClO}_4$  are similar to those for  $\text{Ce}^{3+}(4f^1)$ . This suggests that Pa(IV) has a  $5f^1$  configuration, and is an actinide. Pa(III) has been detected polarographically.

## URANIUM

Uranium ores were originally mined as a source of Ra, which was used for radiotherapy treatment of cancer. Small amounts of U were (and still are) used to produce pale yellow or green coloured glass. This glass fluoresces under UV light. Some uranium oxide is used for colouring ceramics.

The discovery of uranium fission by Otto Hahn in December 1938 stimulated a very detailed study of nuclear physics and of uranium chemistry. The liberation of energy by splitting a nucleus was of such importance that on 2 August 1939 Albert Einstein wrote about it to Franklin D. Roosevelt (the President of the USA). He said 'Some recent work by E. Fermi and L. Szilard leads me to expect that the element uranium may be turned to a new and important source of energy in the immediate future'. History shows how right he was.

Enrico Fermi (a refugee from Italy working at the University of Chicago) used the fission process to create the first man made nuclear chain reaction on 2 December 1942. His reactor consisted of a pile of alternate layers of fuel (U and  $\text{UO}_2$ ) and moderator (graphite). Strips of Cd served to absorb neutrons and thus control the chain reaction. Fermi used 400 tonnes of graphite, 50 tonnes of  $\text{UO}_2$  and 6 tonnes of U metal.

This led to the Manhattan Project to make atomic bombs, to the discovery of the transuranium elements (elements with higher atomic numbers than U) and the development of nuclear power. Two atomic bombs were used against Japan in 1945. Uranium is now of great commercial importance as a nuclear fuel. In 1989 there were over 120 nuclear power plants producing electricity in the USA, and over 400 in the rest of the world.

### Occurrence


Uranium vanadates such as carnotite  $K_2(UO_2)_2(VO_4)_2 \cdot 3H_2O$  constitute the chief ore of U. It occurs as a distinctive yellow or green–yellow crust, or in sandstones and soft aggregates. U is also mined as oxide ores, the most important being uraninite and pitchblende. These are black–brown coloured, nonstoichiometric and approximate to  $UO_2$ . They are often oxidized, and gummite is orange–yellow, brown or black and is a mixture of weathered U and Th ores. The stoichiometric oxides  $UO_2$ ,  $U_3O_8$  and  $UO_3$  are black–brown, green–black and orange–yellow respectively. U is the forty-eighth most abundant element in the earth's crust (2.3 ppm). It is more abundant than some 'well known' elements such as Ag, Hg, Cd and I. World production of U was 34 400 tonnes in 1992. This is based on the metal content, and is equivalent to 40 600 tonnes of  $U_3O_8$ . The main producers of U ores are the Soviet Union 32%, Canada 27%, Niger 9%, Australia and Namibia 7% each, France 6%, and the USA and South Africa 5% each. Half of the USA production comes from the Grants area of New Mexico.

### Extraction

The extraction processes are complex. Ores are crushed and concentrated by physical and chemical means. Ore may contain 0.2% U, so 1 tonne of ore yields only 4 lbs or under 2 kg of  $U_3O_8$ . First the ore is concentrated using the very high density of U in flotation methods. Then it is roasted in air, and leached with  $H_2SO_4$  (often with an oxidizing agent such as  $MnO_2$  to ensure conversion to U(+VI)). This is precipitated as sodium diuranate  $Na_2U_2O_7$ , a bright yellow solid called 'yellowcake'. This dissolves in  $HNO_3$ , forming uranyl nitrate  $UO_2(NO_3)_2 \cdot (H_2O)_n$ . Uranyl nitrate is purified either by adding ammonia to precipitate  $UO_3$ , or by solvent extraction of uranyl nitrate from aqueous solution into tributyl phosphate in an inert hydrocarbon diluent. The final steps are conversion to  $UF_4$  followed by reduction of  $UF_4$  with Ca or Mg to give the metal.

### Nuclear fission

Naturally occurring uranium contains three isotopes: 99.3%  $^{238}U$ , 0.7%  $^{235}U$  and traces of  $^{234}U$ . The isotope  $^{235}U$  is fissile, and if it is irradiated with thermal (slow) neutrons the nucleus breaks up into two smaller nuclei. At least a million times more energy is liberated by this fission than from a chemical reaction. The nucleus may split giving several products (see 'Induced nuclear reactions', Chapter 31), one such reaction being:





If one of the neutrons evolved splits another  $^{235}U$  nucleus then a self-perpetuating nuclear chain reaction will be started. This liberates energy at a constant rate. Since three neutrons are evolved per fission, these could in

principle split three further  $^{235}\text{U}$  nuclei. This would liberate even more neutrons and start a branched chain reaction. This would run out of control liberating energy at an ever increasing rate, resulting in an explosion.

It is very difficult to start and maintain a chain reaction. The neutrons produced by the fission are 'fast neutrons', and have energies of  $2 \times 10^8 \text{ kJ mol}^{-1}$ . They tend to escape and are not very effective at causing further fission. They are much less effective than 'slow neutrons' with an energy of about  $2 \text{ kJ mol}^{-1}$ . (These are sometimes called 'thermal neutrons', because their energy is equivalent to thermal energy attainable at room temperature.) Two things can be done to increase the chance of a chain reaction.

- 1 The fast neutrons may be slowed down by collision with atoms of hydrogen, deuterium or carbon. These materials are called moderators.
- 2 A large enough mass of  $^{235}\text{U}$  is needed to ensure that sufficient neutrons hit another fissile U nucleus rather than escape. Thus there is a critical mass. The size of this depends on the shape of the material and on its purity. A sphere has the minimum surface area, which minimizes the chance of neutrons escaping. Rods or sheets have a much larger area, hence neutrons can escape more easily. The chance of neutrons causing fission increases if the proportion of the fissile isotope is increased. Thus it is usual to 'enrich' the fuel.


Control rods are used to make sure that the reaction does not get out of control. The control rods absorb neutrons. The rods are lowered into the reactor to absorb neutrons and slow it down, or are raised out of the reactor to allow it to speed up. Control rods may be made of boron, steel, cadmium or hafnium.



Paradoxically chain reactions can only be made to result in an explosion with difficulty. To get an explosion, conditions must be such that the neutron propagation factor is greater than one. This means that more than one neutron from each fission is effective at causing another fission. This is called a branched chain reaction. To attain these conditions bomb grade fuel is very highly enriched. It may contain up to 80%  $^{235}\text{U}$ . There are great difficulties in achieving this magnitude of enrichment. Normally the energy liberated melts the radioactive material, thus allowing it to spread out. Because of the increased surface area, more neutrons escape, hence the chain reaction ceases. Only if the fissile material is prevented from spreading out by some form of containment will a chain reaction result in an explosion. The temperatures reached are similar to that of the sun, and there is no casing that will withstand such temperatures. The first atomic bomb dropped on Hiroshima used  $^{235}\text{U}$ . Two sub-critical masses of enriched  $^{235}\text{U}$  at opposite ends of a gunbarrel were shot together by a small conventional explosion, which held them together long enough for a nuclear explosion to occur.

In a nuclear reactor, the neutron propagation factor is very close to one. This means that only one neutron from each fission is allowed to cause another fission. Thus the release of energy is controlled, and can be used for peaceful purposes such as generating electricity. The surplus neutrons may escape, or may be absorbed by the neutron absorbing control rods or by  $^{238}\text{U}$  which is also present in the fuel rods.

The preparation of enriched U fuels containing large amounts of fissile  $^{235}\text{U}$  is difficult. Fuel is usually enriched to between 2% and 4% of  $^{235}\text{U}$  for civil nuclear reactors in power stations. A much higher enrichment is required for bombs and reactors for submarines (70% or 80%). There are four methods of separating the isotopes of U: thermal diffusion, gaseous diffusion, electromagnetic separation and using a gas centrifuge. Large scale separation is now carried out using the different rates of diffusion of gaseous  $^{235}\text{UF}_6$  and  $^{238}\text{UF}_6$  (see Chapter 31). The gas centrifuge method is increasing in importance.



When  $^{238}\text{U}$  absorbs neutrons it forms the heavier element Pu which is itself fissile and can be used as a nuclear fuel. Since a larger quantity of Pu may be formed than the quantity of  $^{235}\text{U}$  that is consumed, the reactor is called a fast breeder reactor.





### Chemical properties

Uranium and the next three elements Np, Pu and Am show oxidation states of (+III), (+IV), (+V) and (+VI). These are similar to each other, except that the most stable state drops from U(VI) to Np(V) to Pu(IV) to Am(III). In the (+III) and (+IV) states the compounds are similar to lanthanides. The ions formed in the oxidation states (+III), (+IV), (+V) and (+VI) are  $\text{M}^{3+}$ ,  $\text{M}^{4+}$ ,  $\text{MO}_2^+$  and  $\text{MO}_2^{2+}$  respectively. Oxidation-reduction reactions are rapid between  $\text{M}^{3+}$  and  $\text{M}^{4+}$ , or  $\text{MO}_2^+$  and  $\text{MO}_2^{2+}$ , as these only involve the transfer of an electron. Oxidation of  $\text{M}^{4+}$  to  $\text{MO}_2^{2+}$  is slow because it involves transfer of oxygen.

Uranium is a reactive metal. Finely divided metal reacts with boiling water to give a mixture of  $\text{UH}_3$  and  $\text{UO}_2$ . The metal dissolves in acids, and reacts with hydrogen, oxygen, the halogens and many elements.


### Hydrides

Uranium reacts with hydrogen even at room temperature, though the reaction is faster at  $250^\circ\text{C}$ , giving  $\text{UH}_3$  as a black pyrophoric powder. The hydride is very reactive, and is often more suitable than the metal for making other compounds:



### Oxides

The U–O system is complicated because there are several stable oxidation states, and the compounds are often nonstoichiometric.  $\text{UO}_2$  is brown-black and occurs in pitchblende.  $\text{U}_3\text{O}_8$  is greenish black, whilst  $\text{UO}_3$  is orange-yellow. Some reactions are given



All three oxides are basic and dissolve in acids.  $\text{UO}_3$  dissolves in  $\text{HNO}_3$  forming the yellow uranyl ion  $[\text{O}=\text{U}=\text{O}]^{2+}$ . Crystallizing this solution gives uranyl nitrate  $\text{UO}_2(\text{NO}_3)_2(\text{H}_2\text{O})_n$ . The number of molecules of water of crystallization may be two, three or six depending on whether it is crystallized from fuming, concentrated or dilute  $\text{HNO}_3$ . Crystals of the dihydrate have an unusual eight-coordinate structure. This comprises a linear  $[\text{O}=\text{U}=\text{O}]^{2+}$  group perpendicular to a hexagon of six oxygen atoms (four from two bidentate  $\text{NO}_3^-$  groups and two from water molecules) (Figure 30.1).





Figure 30.1 Uranyl nitrate dihydrate  $\text{UO}_2(\text{NO}_3)_2 \cdot 2\text{H}_2\text{O}$


### Halides

The main uranium halides and their colours are listed in Table 30.7. Some of the reactions of the fluorides are given





$\text{UF}_6$  and  $\text{UCl}_6$  are octahedral but all the other halides are polymeric, and have high coordination numbers. The halides are all hydrolysed by water. The hexahalides dissolve in strong acid and give the  $\text{UO}_2^{2+}$  ion. At higher pH values this hydrolyses and polymerizes via hydroxyl bridges, giving:



$\text{UF}_6$  is obtained as colourless crystals, m.p.  $64^\circ\text{C}$ . It is a powerful fluorinating agent, and is rapidly hydrolysed by water.  $\text{UF}_5$  tends to disproportionate to  $\text{UF}_4$  and  $\text{UF}_6$ . The tetrahalides are the most stable.

Table 30.7 Halides of uranium

Oxidation state	Fluorides	Chlorides	Bromides	Iodides
+III	$\text{UF}_3$ green	$\text{UCl}_3$ red	$\text{UBr}_3$ red	$\text{UI}_3$ black
+IV	$\text{UF}_4$ green	$\text{UCl}_4$ green	$\text{UBr}_4$ brown	$\text{UI}_4$ black
+V	$\text{UF}_5$ white-blue	$\text{U}_2\text{Cl}_{10}$ red-brown		
+VI	$\text{UF}_6$ white $\text{U}_2\text{F}_9$ black $\text{U}_4\text{F}_{14}$ black $\text{U}_5\text{F}_{22}$ black	$\text{UCl}_6$ black		

## NEPTUNIUM, PLUTONIUM AND AMERICIUM

Except for  $^{239}_{94}\text{Pu}$ , which is very important as a nuclear fuel and for bombs, the other transuranium elements have few uses outside research.  $^{237}_{93}\text{Np}$  and  $^{239}_{94}\text{Pu}$  can be extracted in kilogram quantities, and  $^{241}_{95}\text{Am}$  and  $^{243}_{95}\text{Am}$  in 100 g quantities from spent uranium fuel rods which have been used in a nuclear reactor. Their separation is extremely difficult and hazardous. Not only are they mixed with highly radioactive fission products, but the material is also fissile. The critical mass for a sphere of Pu metal is about 10 kg but in solution less than 1 kg may be critical. Furthermore, Pu is extremely toxic (a dose of  $10^{-6}$  g may be fatal and smaller doses are carcinogenic). Am can be obtained from spent fuel rods. It is produced by intense neutron irradiation of pure Pu at the Oak Ridge National Laboratories in Tennessee.

The reprocessing of nuclear fuel rods is an important new technology. Plainly, reprocessing is necessary in breeder reactors to extract the new elements produced so that they may be used as fuel. Reprocessing is also essential in normal thermal reactors. This is because some of the fission products that are produced absorb neutrons. Thus they will stop the chain reaction before all the  $^{235}\text{U}$  or  $^{239}\text{Pu}$  has been used. There are over 30 different elements produced, including Sr, the second row transition elements, I, Xe, Cs, Ba, La and the lanthanides. (Many of the isotopes formed are radioactive: the best known are  $^{90}\text{Sr}$  and  $^{138}\text{I}$ .) There are large amounts of U and Pu, and small amounts of the other transuranium elements.

Fuel rods removed from a reactor are immersed in water for 100 days. This keeps them cool while the highly radioactive isotopes with short half-lives such as  $^{131}\text{I}$  ( $t_{1/2} = 8$  days) lose most of their activity.

In the Purex process the fuel rods are dissolved in 7M  $\text{HNO}_3$  and extracted with tributyl phosphate.  $\text{UO}_2^{2+}$  and  $\text{Pu}(+\text{IV})$  are extracted in the same way. This leaves the other transuranium elements (mainly Np, Am and Cm) together with other fission products (mainly second row transition elements and lanthanides) in the aqueous solution. Careful reduction of the  $\text{UO}_2^{2+}/\text{Pu}(+\text{IV})$  solution with  $\text{SO}_2$ ,  $\text{NH}_4\text{OH}$  or iron(II)sulphamate  $\text{Fe}(\text{NH}_2\text{SO}_4)_2$  gives  $\text{Pu}(+\text{III})$ . This is easily separated from  $\text{UO}_2^{2+}$  and  $\text{U}^{4+}$  by solvent extraction. U is precipitated as uranyl nitrate and Pu as the oxalate or fluoride. Eventually  $\text{UO}_2$  and  $\text{PuO}_2$  are recovered.

Np, Pu and Am are reactive metals similar to U. They dissolve in acids, and react with hydrogen, oxygen, the halogens and many elements. The oxidation states  $(+\text{III}) \rightarrow (+\text{VI})$  are present in solution as  $\text{M}^{3+}$ ,  $\text{M}^{4+}$ ,  $\text{MO}_2^+$  and  $\text{MO}_2^{2+}$ . The  $(+\text{VI})$  state becomes increasingly oxidizing in the order  $\text{U} \rightarrow \text{Np} \rightarrow \text{Pu} \rightarrow \text{Am}$ .  $\text{AmO}_2^{2+}$  is as strongly oxidizing as  $\text{KMnO}_4$ . The most stable states are  $\text{Np}(+\text{V})$ ,  $\text{Pu}(+\text{IV})$  and  $\text{Am}(+\text{III})$ . Very strong oxidation of alkaline solutions of  $\text{NpO}_2^{2+}$  and  $\text{PuO}_2^{2+}$  with ozone or  $\text{HIO}_4$  yields the  $(+\text{VII})$  state which has been isolated as  $\text{Li}_4[\text{NpO}_6]$  and  $\text{Li}_4[\text{PuO}_6]$ . The  $(+\text{VII})$  state is strongly oxidizing and when acidified it is rapidly reduced to the  $(+\text{VI})$  state and  $\text{H}_2\text{O}$  is oxidized to  $\text{O}_2$ .

The most important oxides are the dioxides  $\text{MO}_2$ , but the oxide systems may be nonstoichiometric, and contain various solid solutions. The halides are similar to those of uranium in structure, properties and preparation. A list of known compounds is given in Table 30.8.

All isotopes of plutonium are important as nuclear fuels.  $^{239}\text{Pu}$  is converted by neutron irradiation to  $^{241}\text{Pu}$  for use as a power source in satellites.  $^{241}\text{Am}$  is a valuable laboratory source of  $\alpha$  particles.

## THE LATER ACTINIDE ELEMENTS

Much less is known about the later elements: curium, einsteinium, fermium, mendelevium, nobelium and lawrencium. This is due in part to their limited availability and partly to their instability. Table 30.4 shows that only Cm is available in macroscopic quantities and information on the others is largely from tracer studies.

Table 30.8 Halides of neptunium, plutonium and americium

+III	NpF <sub>3</sub> purple-black	PuF <sub>3</sub> purple	AmF <sub>3</sub> pink
	NpCl <sub>3</sub> white	PuCl <sub>3</sub> emerald green	AmCl <sub>3</sub> pink
	NpBr <sub>3</sub> green	PuBr <sub>3</sub> green	AmBr <sub>3</sub> white
	NpI <sub>3</sub> brown	PuI <sub>3</sub> brown	AmI <sub>3</sub> yellow
+IV	NpF <sub>4</sub> green	PuF <sub>4</sub> brown	AmF <sub>4</sub> tan
	NpCl <sub>4</sub> red-brown		
	NpBr <sub>4</sub> red-brown		
+VI	NpF <sub>6</sub> brown	PuF <sub>6</sub> red-brown	

Interest in these elements is largely concerned with showing that the second half of the actinides resemble the lanthanides quite closely. In spite of similarities, the actinides can be separated from the lanthanides quite easily, as the actinides form complexes more readily. For example, with concentrated HCl the actinides form chloro complexes. If both groups of ions are adsorbed on a cation exchange column, the actinides can be eluted with concentrated HCl. The actinide ions are separated from each other by ion exchange using citrate solutions to elute them. The order in which the actinides are eluted shows a close similarity to the order in which the lanthanides are eluted.

The (+III) oxidation state is the most stable for all but one of the elements with atomic numbers 96–103, i.e. Cm, Bk, Cf, Es, Fm, Md, (No) and Lw. The exception is No, which is most stable as No(+II). This is stable because it has a favourable  $f^{14}$  electronic configuration.

There is evidence of (+II) states for the elements 98–102, i.e. californium to nobelium. Except for nobelium this state is reducing or strongly reducing in nature. Higher oxidation states of Cm(+IV) are found in the solid but not in solution with compounds such as CmF<sub>4</sub> and Rb[CmF<sub>6</sub>]. Bk(+IV) compounds are oxidizing. They exist in both the solid and in solution, and BkO<sub>2</sub> and Cs<sub>2</sub>[BkCl<sub>6</sub>] have been isolated. Lawrencium exists only in the (+III) state and resists both oxidation and reduction, again illustrating the stability of an  $f^{14}$  electronic arrangement.

The first three elements curium, berkelium and californium have been obtained in milligram quantities. Their chemistry has been studied by normal small scale methods, and compounds have been isolated. The remaining elements have been studied by radioactive tracer methods, because they are only available in such minute amounts. In this technique the traces of the heavy elements are precipitated, or form complexes, in the presence of major quantities of a carrier element which has similar chemical properties. Thus mendelevium is studied using the lanthanide europium, and the mendelevium is detected and followed by its radioactivity.

The elements up to 100 fermium undergo radioactive decay mainly by emitting  $\alpha$  particles or  $\beta$  particles (see Chapter 31). The elements become increasingly unstable as the atomic number increases, and nobelium has a half life of only three seconds (Table 30.3). With these very heavy

elements spontaneous nuclear fission becomes the most important method of decay  $^{252}\text{Cf}$  could become a valuable neutron source

### FURTHER EXTENSION OF THE PERIODIC TABLE

The actinide series is complete at element 103 lawrencium. Elements 104–109 have been reported recently and are *d* block elements. There are currently two major groups working on producing superheavy elements one in California USA and the other at Dubna near Moscow in the USSR. By convention the workers who discover a new element have the right to name it. Element 104 (Unq) was first reported by Russian workers and named kurchatovium Ku (after Igor Kurchatov). However their work was repeated by American workers who obtained different results and named the element rutherfordium Rf (after Ernest Rutherford). It appears to resemble hafnium in the *d* block. Tracer studies have been carried out and  $\text{UnqCl}_4$  seems to be similar to  $\text{HfCl}_4$ . Element 105 (Unp) provisionally named hahnium Ha (after Otto Hahn) seems to resemble tantalum.  $\text{UnpCl}_5$  and  $\text{UnpBr}_5$  have both been studied. Element 105 Unp has a half life of about 1.5 seconds and  $\text{UnpBr}_5$  was observed from only 18 atoms. Both elements 104 and 105 have been made by bombarding actinides with the accelerated nuclei of light atoms. For example element 105 was made from californium by ion bombardment with  $^{15}\text{N}$  nuclei. The very short half lives of the isotopes and the increasing importance of spontaneous fission as the mode of decay of the elements with atomic numbers greater than 100 would suggest that extension of the periodic table to much higher atomic numbers is not very likely.

The IUPAC proposed a system for naming elements with  $Z > 100$

- 1 The names are derived by using roots for the three digits in the atomic number of the element and adding the ending -ium. The roots for the numbers are

0	1	2	3	4	5	6	7	8	9
nil	un	bi	tri	quad	pent	hex	sept	oct	enn

- 2 In certain cases the names are shortened for example bium and trium are shortened to bium and trium and enn nil is shortened to enn
- 3 The symbol for the element is made up from the first letters from the roots which make up the name. The strange mixture of Latin and Greek roots has been chosen to ensure that the symbols are all different.

Though the names are written as a complete word in the examples below a hyphen has been inserted between each part of the name to make them more understandable. These hyphens should be omitted.

Isotopes of the superheavy elements which were known with reasonable certainty in 1989 are listed in Table 30.10 together with their half lives.

Table 30.9 IUPAC nomenclature for the superheavy elements

Atomic number	Name	Symbol	Atomic number	Name	Symbol
			110	un-un-nilium	Uun
101	un-nil-unium	Unu	111	un-un-unium	Uuu
102	un-nil-bium	Unb	112	un-un-bium	Uub
103	un-nil-trium	Unt	113	un-un-trium	Uut
104	un-nil-quadium	Unq	114	un-un-quadium	Uuq
105	un-nil-pentium	Unp	115	un-un-pentium	Uup
106	un-nil-hexium	Unh	116	un-un-hexium	Uuh
107	un-nil-septium	Uns	117	un-un-septium	Uus
108	un-nil-octium	Uno	118	un-un-octium	Uuo
109	un-nil-ennium	Une	119	un-un-ennium	Uue
			120	un-bi-nilium	Ubn
			130	un-tri-nilium	Utn
			140	un-quad-nilium	Uqn
			150	un-pent-nilium	Upn

Hyphens have been put in the names for clarity. They should be omitted.

Table 30.10 Superheavy elements and their half lives

Atomic number	Name	Symbol	Half life
104	un-nil-quadium	$^{259}_{104}\text{Unq}$	3 s or 255 257 s
		$^{261}_{104}\text{Unq}$	65 s
105	un-nil-pentium	$^{258}_{105}\text{Unp}$	4 s
		$^{260}_{105}\text{Unp}$	1.5 s
		$^{262}_{105}\text{Unp}$	34 s
106	un-nil-hexium	$^{260}_{106}\text{Unh}$	180 s
		$^{263}_{106}\text{Unh}$	0.9 s or 259 264 s
107	un-nil-septium	$^{262}_{107}\text{Uns}$	0.12 s
108	un-nil-octium	$^{265}_{108}\text{Uno}$	$2 \times 10^{-6}$ s or 263 264 s
109	un-nil-ennium	$^{266}_{109}\text{Une}$	$5 \times 10^{-6}$ s

Hyphens have been put in the names for clarity. They should be omitted.

Elements with an even number of protons in the nucleus (even atomic number) are usually more stable than their neighbours with odd atomic numbers (Harkins' rule). This means that they are less likely to decay, and are more abundant. Also nuclei with both an even number of protons and an even number of neutrons are more likely to be stable. The nucleus has a shell structure, with different energy levels, broadly similar to the energy levels of extra-nuclear electrons. A nucleus is more stable than average if the number of neutrons or protons is 2, 8, 20, 28, 50, 82 or 126. These are called 'magic numbers', and can be explained by the shell structure of the

nucleus. This theory also requires the inclusion of numbers 114, 164 and 184 in the series of magic numbers. The stability is particularly high if both the number of protons and the number of neutrons are magic numbers. Thus  $^{208}_{82}\text{Pb}$  is very stable with 82 protons and  $208 - 82 = 126$  neutrons. This suggests that nuclides such as  $^{278}_{114}\text{Uuq}$ ,  $^{298}_{114}\text{Uuq}$  and  $^{310}_{126}\text{Ubh}$  might be stable enough to exist.

It is just possible that stable isotopes of the very heavy elements could be made, but that the preparative techniques have so far only succeeded in producing unstable isotopes. Considerable efforts are being made to produce elements 114 and 126 which seem to be favourable nuclear arrangements. The elements up to atomic number 105 have been made by bombarding actinides with light nuclei such as He, B, C, N and O. Instead of continuing to build up the elements gradually in small steps, attempts are being made to make elements beyond  $Z = 105$  by bombarding fairly heavy nuclei such as  $^{82}\text{Pb}$  or  $^{83}\text{Bi}$  with nuclei of medium sized atoms. The nucleus formed when they fuse is chosen to be close to a magic number. The newly formed nucleus will decay, emitting various particles, and the energy of the accelerated particle is kept as low as possible to lessen the chance of fission. There are enormous practical difficulties. In addition it is extremely expensive to build accelerators capable of imparting sufficient energy to the medium weight nuclei prior to bombardment. Element 107 has been made by bombarding  $^{209}_{83}\text{Bi}$  with accelerated  $^{54}_{24}\text{Cr}$ .



Element 109 has been reported from the USSR and was made by bombarding  $^{209}_{83}\text{Bi}$  with accelerated  $^{56}_{26}\text{Fe}$  forming  $^{265}_{109}\text{Une}$ . Only a few atoms have been prepared. There are islands of stability around  $Z = 114$  which should be like lead, and around  $Z = 126$ . The latter is interesting and could contain a new series with  $g$  electrons.

## FURTHER READING

- Abelson, P. H. (1989) Products of neutron irradiation. *J. Chem. Ed.* **66**, 364–366 (Reflections on nuclear fission at its half century).
- Bagnall, K. W. (ed.) (1975) *MTP International Review of Science: Inorganic Chemistry (Series 2)*, Vol. 7, Lanthanides and Actinides. Butterworths, London.
- Brown, D. (1968) *Halides of the Transition Elements*, Vol. I (Halides of the lanthanides and actinides). Wiley, London and New York.
- Cadman, P. (1986) Fuel processing and reprocessing. *Education in Chemistry* **23**, 47–50.
- Callow, R. J. (1967) *The Industrial Chemistry of the Lanthanons, Yttrium, Thorium, and Uranium*. Pergamon Press, New York.
- Cleveland, J. M. (1970) *The Chemistry of Plutonium*. Gordon and Breach, New York.
- Cordfunke, E. H. P. (1969) *The Chemistry of Uranium*. Elsevier, Amsterdam.
- Edelstein, N. M. (ed.) (1982) *Actinides in Perspective*. Pergamon Press, New York.
- Edelstein, N. M., Navratil, J. D. and Schulz, W. W. (eds) (1985) *Americium and Curium: Chemistry and Technology*. Dordrecht/Lancaster/Reidel (Papers from a symposium in 1984 at Honolulu).

- Emeléus, H.J. and Sharpe, A.G. (1973) *Modern Aspects of Inorganic Chemistry*, 4th ed. (Chapter 23: Inner transition elements, the actinides), Routledge and Kegan Paul, London.
- Erds, P. and Robinson, J.M. (1983) *The Physics of Actinide Compounds*, Plenum, New York and London.
- Evans, C.H. (1989) The discovery of the rare earth elements, *Chemistry in Britain*, **25**, 880–882.
- Handbook on the Physics and Chemistry of the Actinides*, North Holland, Amsterdam and Oxford.
- Herrmann, C. (1979) Superheavy element research, *Nature*, **280**, 543.
- Katz, J.J., Seaborg, G.T. and Morss L.R. (eds) (1986) *The Chemistry of the Actinide Elements*, 2nd ed., Chapman and Hall, London and New York.
- Kumar, K. (1989) *Superheavy Elements*, Hilger.
- Lanthanide and Actinide Chemistry and Spectroscopy* (1980) ACS Symposium, series 131, American Chemical Society, Washington.
- Lodhi, M.A.K. (1978) *Superheavy Elements*, Pergamon Press, New York.
- Organessian, Y.T. et al. (1984) Experimental studies on the formation of radioactive decay isotopes with  $Z = 104\text{--}109$ , *Radiochim. Acta*, **37**, 113–120.
- Seaborg, G.T. (1963) *Man-Made Transuranium Elements*, Prentice Hall, New York.
- Seaborg G.T. (ed.) (1978) *The Transuranium Elements: Products of Modern Alchemy*, Dowden, Hutchinson and Ross, Stroudsburg. (This gives 120 of the most important papers in the history of making these man-made elements.)
- Seaborg, G.T. (1989) Nuclear fission and transuranium elements, *J. Chem. Ed.*, **66**, 379–384. (Reflections on nuclear fission at its half century.)
- Sime, R.L. (1986) The discovery of protoactinium, *J. Chem. Ed.*, **63**, 653–657.
- Spirlet, J.C., Peterson, J.R. and Asprey, L.B. (1987) Purification of actinide metals, *Adv. Inorg. Chem.*, **31**, 1–41.
- Steinberg, E.P. (1989) Radiochemistry of the fission products, *J. Chem. Ed.*, **66**, 367–372. (Reflections on Nuclear Fission at its half century.)
- Taube, M. (1974) *Plutonium: A General Survey*, Verlag Chemie, Weinheim.
- Thompson, R. (ed.) (1986) *The Modern Inorganic Chemicals Industry*, Special Publication No. 31, The Chemical Society, London. (See the chapter 'The Inorganic Chemistry of Nuclear Fuels' by Findlay, J.R. et al.)
- Tominaga, T. and Tachikawa, E. (1981) *Modern Hot-Atom Chemistry and Its Applications* (Inorganic Chemistry Concepts Series), Springer-Verlag, New York.
- Wolke, R.L. (1988) Marie Curie's Doctoral Thesis: Prelude to a Nobel Prize, *J. Chem. Ed.*, **65**, 561–573.

## PROBLEMS

1. Name the actinide elements in their correct order, and give their chemical symbols.
2. Which actinide isotopes are available (a) in tonnes, (b) in kilograms and (c) in gram quantities?
3. Compare and contrast the pyramid of oxidation states found in the first row of the transition elements with the oxidation states found in lanthanides and in the actinides.
4. What are the main sources of Th and U? How are the metals obtained?
5. Describe the methods which have been used to separate the isotopes of uranium. Explain the difficulties.

- 6 Give some typical reactions and comment on the structures of +3 and +4 ions of the actinides
- 7 What elements would you expect rutherfordium (atomic number 104) and the elements of atomic numbers 105 106 107 and 112 to resemble?
- 8 The electronic configurations and position of the heavier elements in the periodic table are controversial. What are the possibilities, and what is the evidence?



# Other Topics

## Part Six

## STRUCTURE OF THE NUCLEUS

An atom consists of a positively charged nucleus, surrounded by a cloud of one or more negatively charged electrons. The charges balance exactly and the atom is electrically neutral. The nucleus is made up of positively charged *protons* and electrically neutral *neutrons*, which are bound together by very strong forces. These are short range forces, which fall off very rapidly as the distance between the particles increases. The particles which make up the nucleus are called collectively *nucleons*.

The radius of a nucleus is incredibly small, roughly  $10^{-15}$  m. Nuclear distances are measured in femtometres ( $1 \text{ fm} = 10^{-15} \text{ m}$ ). (Most atoms are  $1-2 \text{ \AA}$ , i.e.  $1-2 \times 10^{-10} \text{ m}$  in radius. The nucleus of oxygen, for example, has a radius of  $2.5 \text{ fm}$ .) To get some feel for how small the nucleus really is, imagine the nucleus measures  $1 \text{ cm}$  in diameter. On the same scale the diameter of the atom would be about  $1000 \text{ m}$ . Most of the mass of an atom is concentrated in the nucleus. As a result its density is very high, approximately  $2.4 \times 10^{14} \text{ g cm}^{-3}$  or about  $10^{13}$  times the density of the densest element iridium ( $22.61 \text{ g cm}^{-3}$ ).

The *atomic number*  $Z$  of an element is the number of protons in the nucleus. This is equal to the number of orbital electrons round the atom. The *mass number*  $A$  is the sum of the neutrons and protons in the nucleus.

### Liquid drop model

The nucleus is sometimes described in terms of a 'liquid drop'. A small liquid drop is almost spherical. It is held together by short range forces – the attraction to near neighbours. Molecules at the edge of the drop feel the attractive force on one side only: this is the surface tension effect. A large liquid drop becomes elongated, and needs only a little disturbance to make it break into pieces.

In a similar way a nucleus is held together by short range forces (the exchange of  $\pi$  mesons). The 'surface tension effect' ensures that small nuclei are spherical. As the mass of the nucleus increases, the repulsion between protons increases more rapidly than the attractive forces. To

minimize the repulsive force, the shape of the nucleus is deformed, just like the elongation of a large liquid drop

This model was suggested by the Danish physicist Niels Bohr to explain why heavy nuclei undergo nuclear fission. Uranium (element number 92) of mass number 235,  $^{235}_{92}\text{U}$ , is so deformed that the addition of a little extra energy, e.g. absorption of a neutron, causes the nucleus to break into two smaller nuclei. This is called nuclear fission, and when it occurs a large amount of energy is released. Nuclei with mass numbers larger than that of uranium are so deformed that they undergo spontaneous fission. This means that the nuclei disintegrate (break up on their own) without any external perturbation.

The density of all nuclei except the very lightest is almost constant. Thus the volume of the nucleus is directly proportional to the number of nucleons present. Nuclei with differing numbers of nucleons are regarded as different sizes of drop. The range of nuclear attractive forces is very small (2 fm–3 fm). The nucleons can move inside the nucleus rather like the particles in a liquid.

### Shell model

In the electron cloud surrounding an atom we can distinguish different electronic energy levels. The electrons are arranged in different shells and orbitals which may be described by four quantum numbers. The nucleons are thought to be arranged in a definite way in the nucleus. Thus the nucleons are arranged in shells, corresponding to different energy levels. When the nucleons occupy the lowest energy levels this corresponds to the ground state. Under different conditions the nucleons may occupy different (higher or excited) energy levels. Usually the population of these higher nuclear energy levels is so short-lived that it cannot be observed. Thus the properties of the nucleus depend only on the number of neutrons and protons, and not on the energy levels they occupy.

In a few cases the excited nuclear states have a measurable life, and when this occurs nuclear isomers can exist. Nuclear isomers are simply nuclei with the same number of neutrons and protons, but whose energies differ. It follows that the masses of the isomers differ by a very small amount corresponding to the difference in energy.

Many nuclei are *unstable* even when they correspond to the ground state. Unstable nuclei decompose by emitting various particles and electromagnetic radiation, and this is called radioactive decay. Over 1500 unstable nuclei are known. If no radioactive decomposition can be detected the nucleus is said to be *stable*.

The shell structure is supported by a periodicity in nuclear properties. Certain combinations of neutrons and protons are particularly stable.

- 1 Elements of even atomic number are more stable and more abundant than neighbouring elements of odd atomic number. This is known as Harkin's rule. (The rule applies almost universally, but  $^1\text{H}$  is a notable exception.)

2. Elements of even atomic number are richer in isotopes and never have less than three stable isotopes (average 5.7). Elements with odd atomic numbers often have only one stable isotope and never have more than two.
3. There is a tendency for the number of neutrons and the number of protons in the nucleus to be even (Table 31.1).

**Table 31.1** The number of neutrons, protons and stable nuclei

Number of protons $P (= Z)$	Number of neutrons $N$	Number of stable isotopes
Even	Even	164
Even	Odd	55
Odd	Even	50
Odd	Odd	4

This suggests that nucleons may be paired in the nucleus in a similar way to the pairing of electrons in atomic and molecular orbitals. If two protons spin in opposite directions, the magnetic fields they produce will mutually cancel each other. The small amount of binding energy generated is sufficient to stabilize the nucleus. However, this is not the most important source of energy in the nucleus.

Certain nuclei are extra-stable, and this is attributable to a filled shell. Nuclei with 2, 8, 20, 28, 50, 82 or 126 neutrons or protons are particularly stable and have a large number of isotopes. These numbers are termed 'magic numbers'. The numbers 114, 164 and 184 should also be included in the series of magic numbers. When both the number of protons and the number of neutrons are magic numbers the nucleus is very stable. For example,  $^{208}_{82}\text{Pb}$  is very stable and has 82 protons, and  $208 - 82 = 126$  neutrons. The emission of  $\gamma$  rays by the nucleus is readily explained by the shell model. If nucleons in an excited state fall to a lower nuclear energy level, they will emit energy as  $\gamma$  rays.

Thus some nuclear properties imply that the nucleons are free to move within the nucleus, and others suggest that nucleons exist in energy levels.

## FORCES IN THE NUCLEUS


Protons have a positive charge. In any nucleus containing two or more protons there will be electrostatic repulsion between the like charges. In a stable nucleus, the attractive forces are greater than the repulsive forces. In an unstable nucleus the repulsive forces exceed the attractive forces and spontaneous fission occurs. The attractive forces in the nucleus cannot be electrostatic for two reasons:

1. There are no oppositely charged particles.
2. The forces only act over a very short distance of 2–3 fm.

If the nuclear particles are separated by a distance much greater than this, attraction ceases. Electrostatic forces diminish only slowly with distance.

The attractive force does not depend on the charge as the same attractive force binds protons to protons protons to neutrons and neutrons to neutrons

Two atoms may be held together by a sharing of electrons because the exchange forces result in a covalent bond By analogy two nuclear particles may be held together by sharing a particle The particle exchanged is called a  $\pi$  meson Mesons may have a positive charge  $\pi^+$  a negative charge  $\pi^-$  or no charge  $\pi^0$  Exchange of  $\pi^-$  and  $\pi^+$  mesons accounts for the binding energy between neutrons and protons The transfer of a charge converts a neutron to a proton or vice versa The resultant attractive forces are indicated by dotted lines in the examples below



A  $\pi^0$  meson is exchanged between two protons or between two neutrons



The attractive forces between p-n n-n and p-p are probably all similar in strength The different types of mesons have similar masses The mass of a  $\pi^0$  meson is 264 times that of an electron and the masses of both  $\pi^+$  and  $\pi^-$  mesons are 273 times that of an electron All mesons are very unstable outside the nucleus There are many other less common elementary particles in the nucleus This topic is really within the field of particle physics and is beyond the scope of this book The number of charged particles in a nucleus remains constant However the continual transfer of mesons means that the particles representing neutrons and protons are constantly changing The transformation of neutrons into protons and vice versa are first order reactions The rates of the reactions depend on the relative numbers of neutrons and protons present In a stable nucleus these two changes are in equilibrium

### STABILITY AND THE RATIO OF NEUTRONS TO PROTONS

The stability of a nucleus depends on the number of protons and neutrons present For elements of low atomic number (up to  $Z = 20$  i.e. Ca) the most stable nuclei exist when the nucleus contains an equal number of protons  $P$  and neutrons  $N$  This means that the ratio  $N/P = 1$  Elements with higher atomic numbers are more stable if they have a slight excess of neutrons as this increases the attractive force and also reduces repulsion between protons Thus the ratio  $N/P$  increases progressively up to about

1.6 at  $Z = 92$  (uranium). In elements with still higher atomic numbers, the nuclei have become so large they undergo spontaneous fission. These trends are shown in the graphs of neutron number  $N$  against proton number  $P$ , and  $N/P$  ratio against proton number for the stable nuclei (Figure 31.1).




Figure 31.1 Neutron to proton ratio.


## MODES OF DECAY

Stable nuclei lie near to these curves. Nuclei with  $N/P$  ratios appreciably higher or lower than the stable ratio are radioactive. When they decay they form nuclei closer to the line of maximum stability.


If the  $N/P$  ratio is high, the isotope lies above the curve. Such a nucleus will decay in such a way that it reduces the  $N/P$  ratio and forms a stable arrangement. The ratio can be reduced in two ways.

### Beta emission


Electrons or  $\beta$  radiation may be emitted from the nucleus when a neutron is converted into a proton, an electron and a neutrino. This reduces the  $N/P$  ratio. The neutrino  $\nu$  is a strange particle. It has zero mass and zero charge, and is postulated to balance the spins. A neutrino is emitted in almost all nuclear transformations. The change of a neutron into a proton may be written:



The mass numbers are shown at the top and must be balanced on both sides of this equation. The nuclear charges are shown at the bottom. These too must be balanced on both sides of the equation. The loss of an electron from the nucleus in this way decreases the  $N/P$  ratio. If an isotope is not far from the stable  $N/P$  line one  $\beta$  decay process may be sufficient:




Isotopes further from the stable line may undergo a series of  $\beta$  decays. The resultant nuclei become progressively more stable and have a longer half life period, until eventually a stable isotope is formed.



In  $\beta$  decay the mass number remains unchanged but the nuclear charge increases by one unit. Thus when  $\beta$  decay occurs the element moves one place to the right in the periodic table.

### Neutron emission


An obvious way to decrease the  $N/P$  ratio would seem to be to emit a neutron from the nucleus. This form of decay is rare and only takes place with highly energetic nuclei. This is because the binding energy of the neutron in the nucleus is high (about 8 MeV). One of the few examples involves  ${}^{87}_{36}\text{Kr}$  which can decay either by neutron emission or  $\beta$  decay.




If the  $N/P$  ratio is too low, the isotope lies below the curve. There are three possible modes of decay.

### Positron emission

Positrons or  $\beta^+$  radiation (positive electrons) result from the transformation of a proton to a neutron. The positron is ejected from the nucleus together with an anti neutrino  $\bar{\nu}$ .




The anti neutrino is postulated to balance the spins. When the positron is ejected from the nucleus it very quickly collides with an electron in the surroundings. The two particles annihilate each other and their energy is released as two  $\gamma$  ray photons. These photons are released in opposite directions ( $180^\circ$  apart), so there is no resultant linear or angular momentum. Thus each photon has exactly half of the annihilation energy of 1.022 Mev, i.e. each photon has an energy of 0.511 Mev. This energy came originally from the parent nucleus. It follows that the mass of the parent nucleus is greater than the mass of the daughter nucleus. This process increases the  $N/P$  ratio. Gamma radiation usually arises in another way, as described later. Some examples of positron emission are




### Orbital or K electron capture


The nucleus may capture an orbital electron and thus convert a proton into a neutron with the emission of a neutrino.



This process increases the  $N/P$  ratio. Usually an electron from the shell closest to the nucleus is captured. This is called the K shell, so the process is called K-electron capture. An electron from a higher energy level drops back to fill the vacancy in the K shell and characteristic X-radiation is emitted. Electron capture is not common. It occurs in nuclei where the  $N/P$  ratio is low and the nucleus has insufficient energy for positron emission, that is  $2 \times 0.51 = 1.02 \text{ MeV}$ . Some examples are:



Where the difference in mass of parent and daughter nuclei is equivalent to more than the required  $1.02 \text{ MeV}$  for positron emission, both positron emission and K capture occur.



### Proton emission

Except for nuclei in a very high energy state, proton emission is unlikely as the energy needed to remove a proton is about  $8 \text{ MeV}$ .

## GAMMA RADIATION

Immediately following any nuclear change, the neutrons and protons often have not arranged themselves in their most stable positions. The newly formed daughter nucleus is thus in an excited state, and has a higher energy than the ground state. Generally the nucleons rearrange themselves quite rapidly, thus lowering the energy of the daughter nucleus to the ground state. The corresponding amount of energy is emitted. This is in the range  $0.1\text{--}1 \text{ MeV}$ , and is emitted as electromagnetic radiation of very short wavelength, called  $\gamma$  rays.

## HALF LIFE PERIOD

The time taken for half the radioactive nuclei in a sample to decay is called the half life period. This is a characteristic of a particular isotope.

For a single radioactive decay process, the number of nuclei which disintegrate in a short time period depends only on the relative number of radioactive atoms present. Thus the size of the sample does not affect the time taken to undergo radioactive decay. Nuclear decay is therefore a first order reaction. If  $n$  is the number of radioactive nuclei and  $t$  the time interval, the rate of decay (that is the change in the number of radioactive nuclei with time) is given by:



$$\frac{dn}{dt} = -\lambda n \quad (31.1)$$

$\lambda$  is the decay constant for the process which indicates how rapidly the sample is decaying ( $\lambda$  has the units  $\text{time}^{-1}$ ). It is usual to quote the time of half life rather than the decay constant. The two are related. Integrating equation (31.1) between limits from time = 0 to time =  $t$  gives

$$\frac{n}{n_0} = e^{-\lambda t}$$

where  $n_0$  is the original number of nuclei at time 0, and  $n$  the number remaining at time  $t$ . The half life  $t_{1/2}$  is the time taken for the number of radioactive nuclei to fall to half the original number, that is to reach  $n = \frac{1}{2}n_0$ . Since there is no way of counting the number of radioactive nuclei present, we cannot calculate  $\lambda$  in this way. However, we can substitute the activity at time = 0 ( $A_0$ ) and the activity at time =  $t$  ( $A$ ) for the number of atoms. The activity can be measured and is the number of counts recorded in a fixed time on a Geiger counter or a scintillation counter. Thus we can evaluate  $\lambda$ .

$$\frac{A}{A_0} = \frac{n}{n_0} = e^{-\lambda t} = \frac{1}{2}$$

Taking natural logarithms of both sides of the equation

$$-\lambda t_{1/2} = \ln\left(\frac{1}{2}\right)$$

hence 
$$t_{1/2} = -\frac{\ln\left(\frac{1}{2}\right)}{\lambda} = +\frac{0.693}{\lambda}$$

Nuclear energies are of the order of  $10^9 \text{ kJ mol}^{-1}$  of nucleons. The energies involved in chemical reactions are about  $10\text{--}10^2 \text{ kJ mol}^{-1}$ . Clearly transmutation of one element to another by chemical means is impossible, because of the exceedingly high nuclear energy. For the same reason a change in temperature has no observable effect on the rate of decay.

The radioactivity of a sample is traditionally measured in curies (Ci). Originally a curie was taken as the amount of radioactive disintegration in 1 g of  $^{226}_{88}\text{Ra}$ . It is more precisely defined as the amount of a radioisotope which gives  $3.7 \times 10^{10}$  disintegrations per second. Thus one curie of different radioisotopes contains a widely different number of atoms. The SI unit of activity is the becquerel (Bq), and is defined as the amount of a radioisotope which gives one disintegration per second. Thus  $1 \text{ Bq} = 2.7 \times 10^{-12} \text{ Ci}$ .

## BINDING ENERGY AND NUCLEAR STABILITY

The mass of a hydrogen atom  $^1_1\text{H}$  is equal to the sum of the mass of one proton and the mass of one electron. For all other atoms the mass of the atom is less than the sum of the constituent neutrons, protons and

electrons. The difference is called the *mass defect*. The mass defect is related to the *binding energy* holding the neutrons and protons together in the nucleus. A stable nucleus must have less energy than its constituent particles or it would not form.

Energy and mass are related by the Einstein equation  $\Delta E = \Delta mc^2$  where  $\Delta E$  is the energy liberated,  $\Delta m$  the loss in mass (the mass defect) and  $c$  the velocity of light ( $2.998 \times 10^8 \text{ m s}^{-1}$ ). The mass defect can be calculated, and converted to the binding energy in the nucleus. The larger the mass defect, the larger the binding energy, and therefore the more stable the nucleus.

Mass of  ${}^1_1\text{p} = 1.007277 \text{ a.m.u.}$ , Mass of  ${}^1_0\text{n} = 1.008665 \text{ a.m.u.}$

(931 is the conversion factor from atomic mass units a.m.u. to MeV).

Mass of  ${}^4_2\text{He}$  nucleus = 4.0028 amu

Mass of  $2\text{n} + 2\text{p} = 4.0319$

Mass defect = 0.0291

Binding energy =

$$0.0291 \times 931 = 27.1 \text{ MeV}$$

$$\text{or } 2.6 \times 10^9 \text{ kJ mol}^{-1}$$

Mass of  ${}^6_3\text{Li}$  nucleus = 6.0170

Mass of  $3\text{n} + 3\text{p} = 6.0478$







Mass defect = 0.0308

Binding energy =

$$0.0327 \times 931 = 28.7 \text{ MeV}$$

$$\text{or } 2.8 \times 10^9 \text{ kJ mol}^{-1}$$

It is quite easy to calculate whether a nucleus is stable against decay. Some possible decay processes are given below.



In each of the above reactions the mass of the parent is less than the combined mass of the suggested products. Thus none of the above decay processes occur.

The total binding energy of the nucleus increases with the number of nucleons present. To compare the stability of nuclei of different elements we calculate the average binding energy per nucleon:

$$\text{binding energy per nucleon} = \frac{\text{total binding energy}}{\text{number of nucleons}}$$

The graph of binding energy per nucleon against atomic number, for the different elements, shows that nucleons are held together with increasing force up to a mass number of about 65. The binding energy for each additional nucleon decreases as the nuclei get larger (Figure 31.2). For most nuclei the average binding energy per nucleon is about 8 MeV. Consequently 8 MeV of energy is needed to remove either a proton or a neutron from the nucleus.

## ALPHA DECAY

As nuclei get larger, the repulsive force between protons increases and the energy of the nucleus increases. A point is reached where the attractive






Figure 31.2 Binding energy per nucleon

forces are unable to hold the nucleons together. Thus part of the nucleus breaks off. An  $\alpha$  particle is emitted from the nucleus. An  $\alpha$  particle is a helium nucleus  $^4_2\text{He}$ . This is a particularly stable nuclear fragment, as all the nucleons are in the lowest possible energy level, and both the number of neutrons and the number of protons are magic numbers. At the same time energy is liberated. In the decay of  $^{238}_{92}\text{U}$ , 4.2 MeV of energy is released because the mean binding energy per nucleon of the two daughter nuclei  $^{234}_{90}\text{Th}$  and  $^4_2\text{He}$  is greater than for the parent nucleus  $^{238}_{92}\text{U}$ . This is an enormous amount of energy ( $1 \text{ MeV} = 96.48 \times 10^6 \text{ kJ mol}^{-1}$ ).



Alpha particles have no electron cloud, and have a charge of +2. Once emitted, an  $\alpha$  particle quickly takes up two electrons from any atom in the vicinity, thus becoming a neutral He atom. The formation of He can be detected when  $\alpha$  decay occurs.



The mass of the parent nucleus must provide both the mass of the daughter nucleus and that of the  $\alpha$  particle, plus the small amount of mass which is converted into energy. It can be calculated from the mass of the nucleus whether  $\alpha$  decay in any element is energetically possible. Natural  $\alpha$  activity is only possible among elements with mass numbers greater than 209, as only these elements have the required energy. Conversely 209 is the largest number of nucleons which will fit into a stable nucleus.

If ejection of one  $\alpha$  particle does not completely stabilize the nucleus, then further  $\alpha$  particles may be emitted. However,  $\alpha$  decay raises the  $N/P$  ratio so it is often followed by  $\beta$  emission.

Nuclei of mass number above 230 may undergo spontaneous fission, forming two lighter nuclei. Thus two elements of lower atomic number are


formed. Elements of low atomic number have a smaller  $N/P$  ratio, so some neutrons will be left over after fission. Most of these neutrons are emitted, but a few may change to protons with  $\beta$  emission. The neutrons emitted may be captured (absorbed) by another nucleus. This nucleus then becomes unstable and itself undergoes fission, liberating more neutrons. Thus a chain reaction has been started.

Alpha decay occurs only very rarely with nuclides with  $Z < 83$  (atoms lighter than Bi). However, the great stability of the  $\alpha$  particle causes a few very light, unstable atoms whose nuclear composition corresponds to, or nearly corresponds to, two or three  $\alpha$  particles to undergo decay. When  ${}^8_4\text{Be}$  undergoes this type of  $\alpha$  decay the energy released is 0.09 MeV.



### RADIOACTIVE DISPLACEMENT LAWS

1. Emission of an  $\alpha$  particle produces an element which is four mass units lighter and the atomic number decreases by two. The daughter element is therefore two places to the left of the parent in the periodic table.
2. When a  $\beta$  particle is emitted the mass number remains the same. However, the atomic number increases by one and the new element is one place to the right of the parent in the periodic system. These changes are shown in the following series:



### RADIOACTIVE DECAY SERIES

The heavy radioactive elements may be grouped into four decay series. The common radioactive elements thorium, uranium and actinium occur naturally and belong to three different series named after them. They are the parent members of their respective series and have the longest half life periods. They decay by a series of  $\alpha$  and  $\beta$  emissions, and produce radioactive elements which are successively more stable until finally a stable isotope is reached. All three series terminate with lead ( ${}^{206}_{82}\text{Pb}$ ,  ${}^{207}_{82}\text{Pb}$  and  ${}^{208}_{82}\text{Pb}$ ). Following the discovery of the artificial post-uranium elements, the neptunium series has been added, which ends with bismuth,  ${}^{209}_{83}\text{Bi}$ .

Thorium ( $4n$ ) series

Neptunium ( $4n + 1$ ) series

Uranium ( $4n + 2$ ) series

Actinium ( $4n + 3$ ) series

The numbers in brackets indicate that the parent and all the members of a particular series have mass numbers exactly divisible by four, or divisible by four with a remainder of one, two or three. There is no natural cross-linking between the four series, although this can be performed artificially.

[illegible]

$^{241}_{94}\text{Pu} \xrightarrow{\beta} ^{241}_{95}\text{Am} \xrightarrow{\alpha} ^{237}_{93}\text{Np} \xrightarrow{\alpha} ^{233}_{91}\text{Pa} \xrightarrow{\beta} ^{233}_{92}\text{U} \xrightarrow{\alpha} ^{229}_{90}\text{Th} \xrightarrow{\alpha} ^{225}_{88}\text{Ra} \xrightarrow{\beta} ^{225}_{89}\text{Ac}$   
 $^{237}_{92}\text{U} \xrightarrow{\beta} ^{237}_{93}\text{Np} \xrightarrow{\alpha} ^{233}_{91}\text{Pa} \xrightarrow{\beta} ^{233}_{92}\text{U} \xrightarrow{\alpha} ^{229}_{90}\text{Th} \xrightarrow{\alpha} ^{225}_{88}\text{Ra} \xrightarrow{\beta} ^{225}_{89}\text{Ac}$   
 $^{237}_{92}\text{U} \xrightarrow{\alpha} ^{229}_{87}\text{Fr} \xrightarrow{\alpha} ^{225}_{85}\text{At} \xrightarrow{\alpha} ^{213}_{83}\text{Bi} \xrightarrow{\beta} ^{213}_{84}\text{Po} \xrightarrow{\alpha} ^{209}_{82}\text{Pb} \xrightarrow{\beta} ^{209}_{83}\text{Bi}$   
 $^{213}_{83}\text{Bi} \xrightarrow{\alpha} ^{209}_{81}\text{Tl} \xrightarrow{\beta} ^{209}_{82}\text{Pb} \xrightarrow{\beta} ^{209}_{83}\text{Bi}$

The diagram illustrates the decay chain of Uranium-238 ( $^{238}_{92}\text{U}$ ). The series begins with  $^{238}_{92}\text{U}$  undergoing alpha decay to  $^{234}_{90}\text{Th}$ , which then undergoes beta decay to  $^{234}_{91}\text{Pa}$ .  $^{234}_{91}\text{Pa}$  decays via beta emission to  $^{234}_{92}\text{U}$ . This  $^{234}_{92}\text{U}$  then undergoes alpha decay to  $^{230}_{90}\text{Th}$ , followed by alpha decay to  $^{226}_{88}\text{Ra}$ , and finally alpha decay to  $^{222}_{86}\text{Rn}$ .  $^{222}_{86}\text{Rn}$  decays via alpha emission to  $^{218}_{82}\text{Pb}$ .  $^{218}_{82}\text{Pb}$  has two decay paths: alpha decay to  $^{214}_{80}\text{Pb}$  and beta decay to  $^{218}_{83}\text{Bi}$ .  $^{218}_{83}\text{Bi}$  decays via alpha emission to  $^{214}_{81}\text{Pb}$  and beta emission to  $^{214}_{83}\text{Bi}$ .  $^{214}_{81}\text{Pb}$  decays via beta emission to  $^{214}_{82}\text{Pb}$ .  $^{214}_{82}\text{Pb}$  decays via alpha emission to  $^{210}_{80}\text{Pb}$  and beta emission to  $^{214}_{83}\text{Bi}$ .  $^{214}_{83}\text{Bi}$  decays via alpha emission to  $^{210}_{81}\text{Bi}$  and beta emission to  $^{214}_{83}\text{Bi}$ .  $^{210}_{81}\text{Bi}$  decays via beta emission to  $^{210}_{82}\text{Pb}$ .  $^{210}_{82}\text{Pb}$  decays via alpha emission to  $^{206}_{80}\text{Pb}$ .  $^{210}_{83}\text{Bi}$  decays via alpha emission to  $^{206}_{81}\text{Bi}$  and beta emission to  $^{210}_{83}\text{Bi}$ .  $^{206}_{81}\text{Bi}$  decays via beta emission to  $^{206}_{82}\text{Pb}$ .  $^{206}_{82}\text{Pb}$  is the stable end product of the series.


The diagram illustrates the decay series of  $^{238}_{92}\text{U}$ . The sequence of decays is as follows:

- $^{238}_{92}\text{U} \xrightarrow{\alpha} ^{234}_{90}\text{Th} \xrightarrow{\beta} ^{234}_{91}\text{Pa} \xrightarrow{\beta} ^{234}_{92}\text{U} \xrightarrow{\alpha} ^{230}_{88}\text{Th} \xrightarrow{\alpha} ^{226}_{86}\text{Ra} \xrightarrow{\alpha} ^{222}_{84}\text{Rn} \xrightarrow{\alpha} ^{218}_{82}\text{Po} \xrightarrow{\alpha} ^{214}_{80}\text{Pb} \xrightarrow{\beta} ^{214}_{81}\text{Bi} \xrightarrow{\beta} ^{214}_{82}\text{Po} \xrightarrow{\alpha} ^{210}_{82}\text{Pb} \xrightarrow{\beta} ^{210}_{83}\text{Bi} \xrightarrow{\beta} ^{210}_{84}\text{Po} \xrightarrow{\alpha} ^{206}_{82}\text{Pb}$


The diagram shows the path of the decay series, with alpha decays represented by straight lines and beta decays represented by curved lines. The final stable product is  $^{206}_{82}\text{Pb}$ .

Natural radioactivity also occurs in nine of the lighter elements. It is possible that as the sensitivity of detecting instruments increases other radioactive elements will be found. Of these the two most important are  $^{14}\text{C}$  and  $^{40}\text{K}$ . The  $^{40}\text{K}$  isotope was probably formed when the earth was created. Its existence on earth is due to its long half life of  $1.25 \times 10^9$  years. This isotope only constitutes 0.01% of naturally occurring potassium but

its presence makes living tissue appreciably radioactive. It may decay either by  $\beta$  emission or K capture.



${}^{14}_6\text{C}$  has a half life of 5720 years and any originally present in the earth will have decayed before now. The fact that some exists shows that it must have been produced since the earth was formed.  ${}^{14}_6\text{C}$  is produced continuously from the action of the neutrons in cosmic rays on nitrogen in the atmosphere. This involves a nuclear reaction:




It is important in radiocarbon dating (see Chapter 12 under 'Carbon dating').

## INDUCED NUCLEAR REACTIONS


Many nuclear reactions can be brought about by bombarding the nucleus with  $\gamma$  rays or various particles. The particles include electrons, neutrons, protons,  $\alpha$  particles or the nuclei of other atoms such as carbon. The nuclei of C atoms which have had the orbital electrons removed are called 'stripped carbon'. The particle may be captured by the nucleus (fusion), or the nucleus may undergo fission, depending on the conditions of the bombardment.

Natural radiation may be used to induce nuclear reactions, but this limits the energy of the bombarding particle. More usually the charged particles are accelerated by a high voltage using a linear accelerator, or by alternate attraction and repulsion using a cyclotron or a synchrotron. (There are very large accelerators at CERN in France and Switzerland, at Berkeley USA and in the USSR.) In this way particles can be accelerated, giving them a very high kinetic energy which can be used to promote the nuclear reaction. This high energy is necessary to overcome the repulsion between a positively charged nucleus and a positively charged bombarding particle. Neutrons have no charge so they would not be repelled by the nucleus, but the absence of a charge means that they cannot be accelerated in this manner. Thus neutron bombardment can only be carried out using neutrons produced by nuclear reactions.


Some nuclear transformations are given below.



In the first example the nitrogen is bombarded with  $\alpha$  particles and a proton is formed. This is described as an ( $\alpha$ , p) reaction. An alternative way of writing the reaction is:




This reaction was first carried out by E. Rutherford in 1919 and this was the first induced nuclear transformation (He was awarded the Nobel Prize for Chemistry in 1908). The second example was carried out in 1932 by F. Joliot and Irene Joliot-Curie and is an  $(\alpha, n)$  reaction (They were awarded the Nobel Prize for Chemistry in 1935).



In a similar way the third example is a  $(p, n)$  reaction. In the last example the energy is emitted as  $\gamma$  rays and so this is an  $(n, \gamma)$  reaction. The nuclei formed in this way may be stable or may subsequently decay. The transuranic elements are all obtained by bombarding a heavy nucleus with  $\alpha$  particles, stripped carbon, or the nuclei of other light atoms to produce an even heavier nucleus.

## NUCLEAR FISSION



Very heavy nuclei have a lower binding energy per nucleon than nuclei with an intermediate mass. Thus nuclei of intermediate mass are more stable than heavy nuclei. When a slow neutron enters a nucleus of a fissionable atom such as uranium (which is already distorted) the extra energy may cause the nucleus to split into two fragments and spontaneously emit two or more neutrons. This is called fission. The fission process results in the release of large amounts of energy (about  $8 \times 10^9 \text{ kJ mol}^{-1}$ ). In the case of  ${}^{235}_{92}\text{U}$  several different primary fission products are formed depending on exactly how the nucleus splits up. Three of the more common reactions are



Note that the daughter nuclei formed fall into two classes. The heavier group have masses from 130 to 160 and the lighter group have masses from 80 to 110. It is rare for the two daughter nuclei of about the same mass to be formed (Figure 31.3).

The total mass of the fission products is some 0.22 mass units less than the mass of the uranium atom and neutron. This corresponds to an energy release of over 200 MeV. This is more than twelve times the energy liberated in a normal nuclear reaction. The complete fission of 1 lb (0.45 kg) of uranium releases as much energy as the explosion of 8000 tonnes of TNT.

The nuclei formed as primary fission products have a high neutron to proton ratio and decay by  $\beta$  emission to lower this ratio. Usually several such steps are required before a stable nucleus is obtained. Thus each of the primary decay products is associated with a decay chain, for example



About 90 decay chains have been identified from the fission of  ${}_{92}^{238}\text{U}$ , giving a total of several hundred different nuclides.




Figure 31.3 Percentage yields of elements from slow neutron fission of  ${}_{92}^{235}\text{U}$ .

### Chain reaction

One fission reaction can cause another. The neutron produced by a fission will either:

1. Cause another nuclear fission reaction.
2. Be lost from the fissionable material
3. Be used in a non-fission reaction.

When neutrons produced in fission reactions initiate new fissions, this is called a chain reaction. There are two major applications of chain reactions – the atomic bomb (A-bomb) and nuclear powered electricity generating stations.

If more than one neutron per fission causes another fission we have a branched chain reaction, and a rapidly increasing release of energy takes place. This is what happens in the atomic bomb. In a nuclear reactor, control rods are used to absorb some of the neutrons, so that on average only one neutron per fission causes another fission. A chain reaction of this kind is self-perpetuating. The energy is released at a slow enough rate to be used.



### Critical mass

There is a minimum amount of fissionable material that can produce a self sustaining chain reaction. This is called the critical mass. The critical mass depends on several factors

- 1 The purity of the sample
- 2 The density of the material
- 3 Its geometric shape and its surroundings

These all affect the neutron propagation ratio. If the sample is impure many neutrons will be lost through colliding with non fissile atoms. The more dense the material the greater the chance that neutrons will collide with another nucleus. The shape of the sample is also important since neutrons are more likely to escape from a long thin strip of material than from a sphere.

### THE STORY BEHIND PRODUCTION OF THE ATOMIC BOMB

Nuclear fission of heavy nuclei was first achieved in Berlin in December 1939 and in 1944 Otto Hahn received the Nobel Prize for Chemistry for this work. The first German reactor (sub critical Pile B III) was surprisingly housed in the Virus House at the Kaiser Wilhelm Institute for Biology at Dahlem. At that time nuclear reactors were called atomic piles and the German reactor consisted of alternate layers of uranium metal and paraffin wax in an aluminium sphere which was immersed in water. Though the pile contained 551 kg of uranium it was sub-critical. This means that less than one neutron produced from each fission caused another fission. Thus a neutron source was placed in a chimney at the centre of the sphere to keep the pile running.

Two years later Enrico Fermi made a pile go critical (self supporting) at the University of Chicago, USA. (Fermi was an Italian and was awarded the Nobel Prize for Physics in 1938 for producing new radioactive elements by neutron irradiation. He fled from World War II and Fascist Italy to the USA.) The Chicago pile consisted of a huge block of graphite surrounded by several feet of high density concrete. Horizontal channels in the graphite were used to insert enough slugs of uranium to produce the chain reaction. Air was blown through to cool the pile and to remove the energy produced. One thousand kilowatts of heat were extracted. The pile was housed in the squash courts! Larger piles were then built at Clinton, Tennessee and Hanford, Washington.

A secret military base was built at Oak Ridge in Tennessee as part of the Manhattan Project to conduct research into making an atomic bomb. Naturally occurring U consists largely of two isotopes, 99.3% of  $^{238}\text{U}$  which is non fissile and 0.7% of  $^{235}\text{U}$  which is fissile.

### Separation of isotopes

Enormous efforts were made to separate the isotopes to obtain sufficient fissile  $^{235}\text{U}$  to make a bomb. Four methods were used.

*Thermal diffusion*

Two gases of different density are placed in a long vertical tube with an electrically heated wire down the centre of the tube. The lighter gas diffuses more readily towards the hot wire, where it is heated and rises in a convection current. Thus the lighter gas accumulates at the top of the tube, and the heavier gas streams downwards on the surface of the tube.

*Electromagnetic separation of  $\text{UCl}_4$  using a mass spectrometer*

Ions must first be produced by bombarding the sample with electrons at low pressure. The ions are attracted by a high voltage across a vacuum chamber. A magnetic field deflects the particles by different amounts depending on their mass. This method can deliver pure isotopes, and though it is primarily used for small quantities, kilogram quantities have been produced.

*Gaseous diffusion of  $\text{UF}_6$* 

$\text{UF}_6$  is gaseous above its sublimation temperature of  $56^\circ\text{C}$ . The gas is pumped through thousands of filter barriers (pinholes) in the enrichment process. The slightly smaller  $^{235}\text{U}$  passed through the barriers a little more easily. The rate of diffusion of a gas is determined by Graham's law of diffusion:

$$\text{rate of diffusion} = K/\sqrt{D}$$


where  $K$  is a constant and  $D$  is the density of the gas. The vapour density is equal to the molecular weight/2. Thus the rate of diffusion of  $^{235}\text{UF}_6$  is marginally faster than that of  $^{238}\text{UF}_6$  by a factor  $\sqrt{(352/349)} = 1.0043$ . This operation is repeated many thousands of times by pumping the gas in a cascade process. After each stage the lighter fraction is passed forwards and the heavier fraction backwards. Gaseous diffusion plants are very large. The K25 building at Oak Ridge housed the original gaseous diffusion plant and occupied  $10^6$  square feet of floor space. A second plant was built at Hanford in Washington State. The method uses an enormous amount of electrical energy. (The Oak Ridge site had two advantages in the wartime period. Its remoteness and low population were advantages as the work had unknown hazards. In addition cheap electricity was available from numerous hydroelectric power stations built in the Tennessee valley in the 1930s to make work during the years of the depression.) Gaseous diffusion was once important but now is only carried out at one site in the USA.

*Using a gas centrifuge to separate  $^{235}\text{UF}_6$  and  $^{238}\text{UF}_6$* 

This has subsequently become the method used in the UK and the Netherlands. Centrifuges rotating at 1700 revolutions per second concentrate  $^{235}\text{UF}_6$  towards the centre and  $^{238}\text{UF}_6$  towards the walls of a cylindrical centrifuge.

There were immense difficulties in obtaining a sufficient quantity of  $^{235}\text{U}$  to make a bomb. The critical mass depends on the purity, and the bomb had to be light enough to carry in an aeroplane.

Meanwhile a second fissile element plutonium Pu was discovered by Glenn Seaborg at the University of California (Berkeley) in 1940. Pu is produced by irradiating the relatively plentiful  $^{238}\text{U}$  with neutrons in a nuclear reactor.



All isotopes of Pu are fissile, and Pu became important as a nuclear fuel. Work on plutonium was mainly carried out at Hanford.

### Bomb making

A third site at Los Alamos (New Mexico) concentrated mainly on the technical problems of how to make bombs. The problems are how to transport sub-critical masses of Pu or U in an aeroplane, and combine them to give a critical mass when over the target. Then the material must be contained for a long enough time for the nuclear reaction to occur.

In the case of the Pu bomb an implosion device was used. Several sub-critical masses of  $^{239}\text{Pu}$  were placed round the edges of a sphere and surrounded by high explosives. The conventional explosives were detonated. The implosion blew the sub-critical masses of Pu into the centre where they formed a critical mass. The force of the explosion held the Pu together for long enough for a nuclear explosion to occur. The first atomic bomb used this principle and was tested on a 100 foot-high tower at Trinity in New Mexico at 5.29 a.m. (just before sunrise) on 16 July 1945. It worked! Fermi estimated that the temperature produced was four times that at the centre of the sun, and a pressure of over 100 billion atmospheres was produced. The radioactivity emitted was a million times greater than from the world's total radium supply. Parts for another similar atomic bomb were shipped to the Far East to be assembled and dropped on Japan.

Meanwhile sufficient  $^{235}\text{U}$  to make a bomb had laboriously been collected. The most practical way to make a bomb was to use a gun barrel and shoot a sub-critical mass of  $^{235}\text{U}$  down the barrel into another sub-critical mass at the end of the barrel. This had not been tested, since up till then there had not been enough  $^{235}\text{U}$  for a test. Parts to assemble this bomb were shipped to the Far East.

The Pu bomb was called 'Fat Man', and was 10 feet 8 inches long and 60 inches in diameter, and weighed 10 800 lb. The bomb was so wide that the doors on the bomb bay of the aeroplane had to be altered to get the bomb in and to allow it to be dropped. The U bomb was called 'Little Boy' and was 10 feet long, but only 28 inches in diameter, and weighed 8900 lb. The smaller diameter allowed it to fit in the aeroplane, and made it possible to use the U bomb first.

The U bomb 'Little Boy' was dropped on Hiroshima on 6 August 1945.

The yield was equivalent to 13 kilotonnes of TNT. Four square miles were devastated, and there were 70 000 immediate deaths. On 9 August 1945 the Pu bomb 'Fat Man' was dropped on Nagasaki. The yield was equivalent to 23 kilotonnes of TNT. Two square miles were devastated, and there were 45 000 immediate fatalities.

## NUCLEAR POWER STATIONS

A nuclear power station consists of a nuclear reactor in which a controlled chain reaction occurs using either U or Pu as fuel. The heat produced is extracted from the reactor and used to generate steam, which drives a turbine and produces electricity. The earliest nuclear reactors were built to irradiate U and produce plutonium for bombs, and for experimental purposes. The first commercial nuclear power station was commissioned in 1956 at Calder Hall (Cumberland, UK). In 1989 there were over 120 nuclear power plants in the USA and over 400 in the rest of the world. France produces two thirds of its electricity from nuclear plants.

Table 31.2 Countries with seven or more nuclear plants

USA	129	Spain	18
France	67	Czechoslovakia	13
USSR	61	Sweden	12
UK	42	India	10
Japan	42	Korea	9
West Germany	28	East Germany	7
Canada	22		

### Moderators

Neutrons can only be obtained by nuclear reactions, and they are divided into three groups depending on their kinetic energy:

1. Slow neutrons, with an energy  $< 0.1$  eV
2. Intermediate neutrons, with an energy 0.1 eV to 2 MeV
3. Fast neutrons, with an energy  $> 2$  MeV


Neutrons ejected from a nucleus usually have a very high energy and are called 'fast neutrons'. These travel so fast that they escape. 'Slow neutrons' are needed to cause fission and maintain a chain reaction.

In a *thermal reactor* a moderator is used to slow down some of the fast neutrons. The neutrons collide with the nuclei of the moderator, and thus lose some of their kinetic energy. The best moderators are light atoms which do not capture neutrons, for example  $^1_1\text{H}$ ,  $^3_2\text{He}$ ,  $^9_4\text{Be}$  and  $^{12}_6\text{C}$ . Graphite is the most widely used. Heavy water  $\text{D}_2\text{O}$  which contains  $^2_1\text{H}$  is also used. Sometimes ordinary  $\text{H}_2\text{O}$  is used. Be and He are not used because Be is poisonous and expensive, and He, being gaseous, is not sufficiently dense. *Fast breeder reactors* do not use a moderator.


### Fuel

Early reactors used uranium metal. Most thermal reactors now use  $\text{UO}_2$  as this has a higher melting point and is less chemically reactive. Natural U may be used as fuel (99.3%  $^{238}\text{U}$  and 0.7%  $^{235}\text{U}$ ). However, it is usual to enrich the fuel to between 2% and 3%  $^{235}\text{U}$  to allow for some neutrons being absorbed by the metal case cladding the fuel rods, or by the moderator. Enriching U reduces the critical mass, and hence the size of the reactor. However, it is very expensive. Enrichment beyond 3% is only carried out for military purposes – to make bombs or for special small high temperature reactors for submarines. The latter use  $\text{UC}_2$  enriched to over 90% as fuel.

Fast (breeder) reactors use plutonium oxide as fuel. They have no moderator, so the fast neutrons produced can convert non-fissile  $^{238}\text{U}$  into fissile Pu by the reactions



More Pu is produced than is used, hence the name 'breeder reactor'. Sometimes thorium (which is non fissile) is incorporated into the fuel. When this is irradiated with fast neutrons, the isotope  $^{233}\text{U}$  is formed and this is fissionable by slow neutrons.



## TYPES OF REACTOR IN USE

Gas cooled thermal reactors (all use graphite as moderator)

### *Magnox reactors*

These use U metal rods as fuel, enclosed in a Mg/Al (magnox) casing. The fuel is natural, i.e. not enriched, and  $\text{CO}_2$  gas is used as the coolant. Most of the early reactors in the UK are of this type. These are now nearing the end of their life.

### *Advanced gas cooled reactors (AGR)*

These use  $\text{UO}_2$  pellets enriched to 2% as fuel with  $\text{CO}_2$  as the coolant.

### *High temperature reactor (HTR)*

These are used for military purposes such as submarines. The fuel is  $\text{UC}_2$  which is enriched to over 90% thus allowing the reactor to be small. The coolant is He and the control rods are made of Cd.

Water cooled thermal reactors (all use  $\text{H}_2\text{O}$  or  $\text{D}_2\text{O}$  as moderator)

*Canadian deuterium uranium reactor (CANDU)*

These are a Canadian design, and use natural (not enriched)  $\text{UO}_2$  as fuel, and heavy water  $\text{D}_2\text{O}$  as both moderator and coolant.

*Pressurized water reactor (PWR)*

These are a US design, and use  $\text{UO}_2$  pellets enriched to 3% as fuel. Water is used as both moderator and coolant. The casing must withstand the huge pressure from the steam produced, and is typically 10 inches (25 cm) of stainless steel surrounded by concrete.

*Boiling water reactor (BWR)*

This is similar to the PWR except that the  $\text{UO}_2$  fuel is only enriched to 2.2%. It works at a much lower pressure, and so the reactor casing need not be so strong.

*Steam generating heavy water reactor (SGHWR)*

These use  $\text{UO}_2$  pellets enriched to 2.3% as fuel, with  $\text{D}_2\text{O}$  as moderator and  $\text{H}_2\text{O}$  as coolant.

Fast breeder reactors (these do not use a moderator)

These are much less developed than are thermal reactors. They use  $\text{PuO}_2$  as fuel. Enrichment is not necessary as all isotopes of Pu are fissile. No moderator is used, and so the neutrons in the reactor are 'fast neutrons'. Some reactors use liquid Na as coolant, whilst others use He gas under a high pressure. If depleted  $\text{UO}_2$  (i.e.  $\text{UO}_2$  which has had the fissile  $^{235}\text{U}$  removed) is put in such a reactor, then the non-fissile  $^{238}\text{U}$  is converted into fissile Pu. The name 'breeder reactor' arises because more fissile material is produced than is used in the process. Potentially this process could provide an unlimited source of energy.

In Great Britain there are three generations of nuclear power stations:


1. The ageing Magnox reactors (British design).
2. The second generation advanced gas cooled reactors (British design).
3. A limited number of American designed pressurized water reactors. These are claimed to be the design which will be used into the twenty-first century. However, the cost, the time taken to commission and the safety aspects (particularly of the pressure casing) of these PWRs have been called into question.

## NUCLEAR FUSION


Nuclear fusion is the process of releasing energy from matter, which occurs in the sun, the stars and the hydrogen bomb. During fusion, atoms of light

elements combine to form heavier elements. The binding energy per nucleon for light elements is less than that for elements of intermediate mass. Thus the fusion of two light nuclei results in a more stable nucleus, and a large amount of energy is liberated. Both fusion and fission are methods of releasing large amounts of energy. In fusion, light atoms are combined to give heavier elements, whilst in fission heavy radioactive atoms are split into atoms of intermediate mass.


The simplest nuclear fusion reaction involves the isotopes of hydrogen, deuterium  ${}^2_1\text{H}$  and tritium  ${}^3_1\text{H}$ . A large amount of energy is required to overcome the repulsion between the positively charged nuclei to get them close enough (1–2 fm) to react. One way of producing high energy particles is an accelerator. This is not appropriate in this case. The other way to produce high energy nuclei is to raise them to a very high temperature (roughly  $10^8\text{ K}$ ). If deuterium and tritium are heated to a temperature of over a million degrees a gas plasma is produced. (A plasma is a fourth state of matter, which is composed essentially of gaseous ions and a matrix of free electrons.) Since the atoms have been stripped of their electrons, collisions will be between nuclei. Some nuclear collisions will occur with enough energy for the nuclei to approach closely enough to experience each others' strong attraction, and a fusion reaction occurs. The mass lost in this reaction is converted into energy according to Einstein's equation  $E = mc^2$ .



This fusion reaction has a relatively low ignition temperature, and produces a large amount of energy. Deuterium is available from natural sources, but tritium is difficult to obtain and is extremely expensive. Tritium could be generated in a fusion reactor by bombarding a blanket of lithium with neutrons.



Similar reactions are carried out using only deuterium, but these reactions require a temperature of several million degrees. Several reactions could occur, of which the simplest are



Fusion is in principle a thermal reaction not inherently different in its kindling from an ordinary fire. Unlike fission, it does not require a critical mass. Once ignited its extent depends on the amount of fuel available. However, for fusion to occur, extreme physical conditions must be achieved.

- 1 A very high temperature must be attained
- 2 Sufficient plasma density is required

3. The plasma must be confined for an adequate time to allow fusion to occur.

These and other 'hydrogen burning' processes occur at the centre of the sun. This provides the enormous amount of solar energy which is radiated to earth and the rest of the solar system.

### Thermonuclear weapons

The only fusion processes carried out successfully on earth have been the hydrogen bomb and other similar thermonuclear weapons. The very high temperatures and high densities required to bring about nuclear fusion reactions have been brought about by means of a small uranium fission bomb. This heats a jacket of lighter elements to a sufficiently high temperature to start the fusion reactions in the hydrogen and nitrogen bombs. These are called thermonuclear reactions. The first thermonuclear device was detonated at Eniwetoc in 1952. The energy yield is 100 times greater than that from an atomic bomb using U or Pu fission. The complete fusion of the nuclei in 1 lb (0.4 kg) of deuterium would result in the same energy release as 26 000 tonnes of TNT.

### Controlled fusion reactions

Many attempts have been made to build apparatus in which controlled fusion reactions will occur. So far none have been successful. The problem is how to handle very hot gas plasmas. If the plasma touches a solid (e.g. a steel vessel), the solid is vaporized and the plasma cools down rapidly. The two main methods of confinement are magnetic and inertial. Since a plasma consists of charged particles moving at high speed, it can be deflected by a magnetic field. Plasma can be contained inside a doughnut shaped 'magnetic bottle'. (The extremely high magnetic fields required are obtained with electromagnets using a superconducting niobium/titanium alloy cooled in liquid helium to about 4 K.) Inertial confinement involves the rapid collapse of the fuel container to make the fuel so dense that the fusion reactions occur. Alternatively laser fusion can be used, when high powered, pulsed laser beams are used to heat and compress small 'pellets' of fuel.

It is just possible that fusion may be achieved by some totally different technique without using plasma to attain the high energy conditions. There was great excitement in March 1989 when Fleischmann and Pons claimed to have achieved 'cold fusion' in the laboratory at the University of Utah, USA. They electrolysed 99.5% enriched heavy water  $D_2O$  made conducting by dissolving in it some  $LiOD$  (D is  $^2H$ ). Heat appeared to be generated, and this was attributed to D-D fusion. In a similar experiment Jones at Brigham Young University claimed neutrons were released. Unfortunately they were wrong.



Another interesting technique which may show promise is to replace an electron in a  $D_2^+$  molecule by a negatively charged muon which weighs 207 times as much as an electron. This should reduce the D-D spacing by a factor of 200 which should make fusion easier.

Nuclear fusion holds the promise of being an important future source of energy. World energy consumption is high, and fuel resources are finite and limited. Oil and natural gas reserves may well be exhausted in 50 years. Coal may last rather longer, perhaps 200 years. Uranium resources are finite, and the use of nuclear powered electricity generating stations will only delay an eventual energy shortfall. All these fuels pose environmental problems. Fossil fuels (oil, gas and coal) contribute to the Greenhouse Effect and acid rain. A long term energy replacement needs to be found. There is concern over the safety of nuclear power stations, and even greater concern over the storage of nuclear waste products. If fusion can be fully developed:

- 1 The fuel for fusion (hydrogen) is almost infinitely available
- 2 The nuclear processes in fusion are inherently safer than those of fission
- 3 Fusion promises to have minimal pollution problems
- 4 Difficulties with spent fuel rods and reaction by products are far less than with fission

Fusion is an advancing research programme, but many breakthroughs are required. The severe and demanding conditions for controlled fusion in the laboratory have yet to be achieved. If a controlled fusion reactor can be built it will supply almost unlimited power.


## THE GENESIS OF THE ELEMENTS

It is an interesting philosophical point to consider how the universe was formed, how the various elements were formed, and why the different elements and their individual isotopes occur in the relative abundances we observe on earth.


The Doppler effect provides evidence that the universe is expanding. Light from the outermost galaxies has a longer wavelength than expected, that is it is towards the red end of the spectrum, because these galaxies are moving away from us. There are several theories for the origin of the universe.

The 'steady state theory' suggests that hydrogen is created continuously to fill the gaps in space created by the expanding universe. The other elements are formed from hydrogen by nuclear reactions.

The 'big bang theory' is currently the most favoured. It assumes that all the matter in the universe was packed as elementary particles into a 'nucleus' of immense density, temperature and pressure. This exploded, hence the name big bang, and dispersed the matter uniformly throughout space as neutrons. The neutrons then decayed, giving protons, electrons and anti neutrinos.



During the big bang and the fireball which followed, temperatures of  $10^6$ – $10^9$  K occurred, and in the first hour or so a number of nuclear reactions occurred:



The isotope  ${}_2^5\text{He}$  has a half life of only  $2 \times 10^{-21}$  s, so building progressively heavier nuclei by the sequential addition of neutrons or protons stopped at this point. Once the temperature had fallen all of these reactions stopped. Thus most of the universe was in the form of H, with a small amount of He, and from this matter the galaxies of stars condensed.


Regardless of the origin of the universe, it is generally accepted that heavier elements may be produced by reactions in the stars. H still accounts for 88.6% and He for about 11.3% of all the atoms in the universe. Together these constitute 99.9% of the atoms, and over 99% of the mass of the universe.

The first process in the synthesis of heavier nuclei in stars is hydrogen burning. Stars are extremely dense ( $10^8 \text{ g cm}^{-3}$ ) and there is an enormously large gravitational force. Some of this force is converted into heat and the temperature rises to about  $10^7$  K. It has been mentioned previously (under 'Nuclear fusion') that this temperature is sufficient to overcome the repulsion between two positively charged H nuclei, and so these nuclei can undergo nuclear fusion, forming deuterium.




	Energy evolved (MeV)
${}_1^1\text{H} + {}_1^1\text{H} \rightarrow {}_1^2\text{H} + \beta^+ + \nu$	1.44
${}_1^2\text{H} + {}_1^1\text{H} \rightarrow {}_2^3\text{He} + \gamma$	5.49
${}_2^3\text{He} + {}_2^3\text{He} \rightarrow {}_2^4\text{He} + 2({}_1^1\text{H})$	12.86
overall $4({}_1^1\text{H}) \rightarrow {}_2^4\text{He} + 2\beta^+ + 2\nu + 2\gamma$	

The process is exothermic. A small amount of mass is lost and energy is evolved. Thus more stable nuclei are formed. The process is also slow. The sun is estimated to be 5 billion years old, but still has about 90% of the hydrogen left.

As hydrogen is used up, helium accumulates in the core. The temperature at the core of the star drops, and the star expands to conserve heat. The star is cooler than before and is called a *red giant*. The core eventually collapses under intense pressure and the temperature rises to over  $10^8$  K. At this point the nuclei begin to fuse.





The nuclei formed in this way fuse with more He






These reactions use up the He in the core and replace it with C, O and Ne. When most of the H and He have been used, small stars contract and become hotter and are called *white dwarfs*.







However, in larger stars (1.4 times the mass of the sun or greater) contraction gives even higher temperatures than before ( $6 \times 10^8 \text{ K}$ ) and a carbon-nitrogen cycle occurs involving the reaction of these elements with hydrogen, provided some  ${}^{12}_6\text{C}$  is available as catalyst.




In addition these nuclei may fuse with helium







At these temperatures carbon and oxygen burning may occur



In some cases the star may contract further and the temperature rises to  $10^9 \text{ K}$ . At this point the  $\gamma$  radiation produced in many of the nuclear changes has sufficient energy to promote endothermic reactions such as



The He so produced reacts further




These fusion reactions are exothermic up to  ${}_{26}^{56}\text{Fe}$ , and Figure 31.2 shows that the binding energy per nucleon increases from H up to Fe, and then decreases with the heavier elements.


The discussion so far explains why H and He make up so much of the universe. The most abundant and stable nuclei up to atomic number 20 have a 1:1 ratio of neutrons to protons, e.g.  ${}_2^4\text{He}$ ,  ${}_7^{14}\text{N}$ ,  ${}_8^{16}\text{O}$ ,  ${}_{12}^{24}\text{Mg}$  and  ${}_{20}^{40}\text{Ca}$ . Most of these (except N) have an even number of neutrons and an even number of protons (even atomic number). A few light isotopes are common and abundant but do not have a 1:1  $N/P$  ratio, e.g.  ${}_9^{19}\text{F}$ ,  ${}_{11}^{23}\text{Na}$  and  ${}_{13}^{27}\text{Al}$ . These elements have an odd atomic number and hence an odd number of protons, but they have an even number of neutrons. These odd-even nuclei are more stable than the corresponding odd-odd nucleus which has a 1:1  $N/P$  ratio. The elements Li, Be and B are of very low abundance compared with their neighbours. It is surprising that they occur at all since the small amounts produced by H and He burning are converted into heavier elements. The small amounts that are found are probably produced by *spallation reactions* where cosmic rays collide with C, N and O nuclei and cause them to break into lighter nuclei. This is sometimes called the *x-process*. A number of elements such as  ${}_{6}^{12}\text{C}$ ,  ${}_8^{16}\text{O}$  and  ${}_{10}^{20}\text{Ne}$  are more abundant than their neighbours, and they differ by a  ${}_2^4\text{He}$  nucleus, which reflects their mode of formation by fusing with helium. The nucleus  ${}_{26}^{56}\text{Fe}$  is particularly abundant because it has the largest binding energy per nucleon. It is thus the most stable nucleus and is formed by fusion. The abundances of the elements preceding Fe (Sc, Ti, V and Cr) are also higher than expected, and this is probably due to spallation reactions where high speed cosmic rays collide with Fe, producing Sc, Ti, V or Cr as well as some Li, Be and B.

Nuclei heavier than  ${}_{26}^{56}\text{Fe}$  are endothermic, and can only be produced by supplying energy. Thus it becomes increasingly difficult to make these elements by fusion. The heavier elements are synthesized by neutron capture reactions in stars. There are two main processes by which this may occur, called the *s-process* (slow neutron capture) and the *r-process* (rapid neutron capture).


In the slow neutron capture process neutrons are added one by one to the nucleus. The addition of a neutron increases the  $N/P$  ratio, and eventually the addition of a neutron makes the nucleus unstable. Because of the long time scale the nucleus has time to decay, and the unfavourable  $N/P$  ratio is corrected by  $\beta$  decay. Then the process is repeated and another neutron is added.



The neutrons are produced in red giants and in second generation stars by the normal processes in the star, such as





or



The slow addition of neutrons can produce nuclei up to  ${}^{209}_{83}\text{Bi}$ . There are much higher than expected abundances of elements round about mass numbers 90, 138 and 208, and the isotopes  ${}^{89}_{39}\text{Y}$  and  ${}^{90}_{40}\text{Zr}$ ,  ${}^{138}_{56}\text{Ba}$  and  ${}^{140}_{58}\text{Ce}$ , and  ${}^{208}_{82}\text{Pb}$  and  ${}^{209}_{83}\text{Bi}$  occur in relatively high abundance. In the discussion on the number of neutrons and protons in the nucleus at the beginning of this chapter it was noted that nuclei with 2, 8, 20, 28, 50, 82 or 126 neutrons or protons are particularly stable, and that these numbers are termed 'magic numbers'. The three clusters of elements with high abundances are close to the neutron magic numbers 50, 82 and 126. This means that they have unusually low neutron absorption cross-sections so they do not capture neutrons very readily and hence their concentration builds up. The s process produces the lighter or proton-rich isotopes of an element.

A different source of neutrons occurs just prior to and during a *supernova* period in a star. In this, big stars become extremely hot ( $8 \times 10^9 \text{ K}$ ), and nuclei in the core break down into neutrons, protons and  $\alpha$  particles which undergo a variety of reactions. The core contracts and eventually implodes, resulting in an explosion of the outer shell which scatters material out into space. In the r-process, many neutrons are added in a period of a few seconds before  $\beta$  decay eventually takes place



The very heavy elements are produced in this way by adding many neutrons at once, and traces of  ${}^{254}_{98}\text{Cf}$  are present in stars and this isotope is also formed during nuclear explosions. In a similar way the elements  ${}_{99}\text{Es}$  einsteinium and  ${}_{100}\text{Fm}$  fermium were formed during the hydrogen bomb explosions. The r-process gives neutron rich isotopes. It is also possible that neutron-rich isotopes of several lighter isotopes, e.g.  ${}^{76}_{16}\text{S}$ ,  ${}^{46}_{20}\text{Ca}$  and  ${}^{48}_{20}\text{Ca}$ , may be formed by the r-process. It is possible that proton capture may also occur in a supernova on a very short time scale. This is called the p-process and it is possible that a range of isotopes from  ${}^{74}_{34}\text{Se}$ ,  ${}^{113}_{50}\text{Sn}$ ,  ${}^{114}_{50}\text{Sn}$  and  ${}^{115}_{50}\text{Sn}$  up to  ${}^{190}_{80}\text{Hg}$  are formed in this way.

The short half life periods of all the isotopes of technetium and promethium explains why they are absent on earth.

### SOME APPLICATIONS OF RADIOACTIVE ISOTOPES

The applications of radioisotopes are so numerous that only a small selection of them is covered here.


Measurements of radioactivity are used to estimate the age of various

objects.  $^{14}\text{C}$  occurs naturally and is used in radiocarbon dating of materials of plant and animal origin. This is described in Chapter 12. It depends on calculating when the sample was removed from free exchange with its surroundings.  $^{14}\text{C}$  is produced continuously from the action of the neutrons in cosmic rays on nitrogen in the atmosphere. Whilst the plant or animal is alive it will have the same proportion of  $^{14}\text{C}$  as the surroundings. When the plant or animal dies, the intake of radiocarbon stops and that already present gradually decays. In a similar way helium dating may be used to estimate the age of certain mineral deposits. Uranium minerals decay by emitting  $\alpha$  particles, thus producing helium. One gram of U produces about  $10^{-7}$  g of He in a year. The age of the mineral can be estimated if both the U and He contents are known. Corrections must be made for some He escaping, and for the production of He from other elements such as Th which may be present.

Isotope dilution analysis can be used to determine the solubility of sparingly soluble materials. For example, a solid sample containing radioactive  $^{90}_{38}\text{SrSO}_4$  and normal  $\text{SrSO}_4$  can be prepared and the activity per gram measured. A known volume of a saturated solution is evaporated and the activity of the residue measured. Comparison of the activities gives the solubility. In a similar way the isotope  $^{32}_{15}\text{P}$  has been used to measure the solubility of  $\text{MgNH}_4\text{PO}_4 \cdot 6\text{H}_2\text{O}$ , and  $^{131}_{53}\text{I}$  has been used to measure the solubility of  $\text{PbI}_2$ . A similar technique can be applied to vapour pressures of rather involatile materials.

Activation analysis is used to determine the amount of an element in a sample. The sample to be analysed and another sample containing a known amount of the element are placed in a nuclear reactor where they are bombarded (usually with neutrons). After irradiation for a suitable period (several times the half life of the expected radioisotope) the samples are removed from the reactor. The induced radioactivity in both samples is measured. The amount of the element present in the unknown sample is obtained from the ratio of the activities of unknown and standard samples. More than 50 elements (or strictly isotopes) can be determined in this way. The method is most used to determine trace quantities. It has the advantage that the sample is not destroyed, but the disadvantage that it requires access to a reactor. Not all elements can be determined in this way; for example, it is not feasible to determine C because  $^{12}_6\text{C}$  has a very low absorption cross-section for neutrons, though activation analysis of C can be performed by bombarding with deuterium in a cyclotron.

Isotope exchange reactions provide information on the mechanisms of certain reactions. Thus exchange of  $^2_1\text{D}$  in heavy water  $\text{D}_2\text{O}$  for  $^1_1\text{H}$  in a compound occurs rapidly if H is bonded to N or O, but exchange is slow or hardly occurs in most cases where H is bonded to C. This is related to the mobility of protons and the higher polarity of N—H and O—H bonds.




If labelled  $^{15}_7\text{NH}_4\text{Cl}$  is dissolved in liquid  $\text{NH}_3$ , and the solvent evaporated, the activity from  $^{15}_7\text{N}$  is evenly distributed between the  $\text{NH}_4\text{Cl}$  and the


$\text{NH}_3$  Since  $^{15}\text{NH}_4\text{Cl}$  ionizes into  $^{15}\text{NH}_4^+$  and  $\text{Cl}^-$ , this provides evidence for the ionization of liquid  $\text{NH}_3$



Similarly the lack of exchange between  $^{14}\text{C}$  in a solution containing labelled  $\text{CN}^-$  and the complex  $[\text{Fe}(\text{CN})_6]^{3-}$  shows that the  $\text{CN}^-$  groups in the complex are not labile. Proof that the two S atoms in the thiosulphate ion  $\text{S}_2\text{O}_3^{2-}$  are not identical can be obtained by heating labelled  $^{35}\text{S}$  with an aqueous solution of sodium sulphite to form the thiosulphate



If the thiosulphate so formed is decomposed by treatment with acid, all the radioactivity returns to the sulphur, and none to the  $\text{SO}_2$  formed



The isotope  $^{60}_{27}\text{Co}$  emits both  $\beta$  and  $\gamma$  radiation. It is used for  $\gamma$  radiography to detect cracks and flaws in metal parts such as pipes, aircraft parts and welded joints, for example in the pressure vessels for nuclear reactors. It is also used to irradiate malignant tumours in the body as one method of cancer therapy.

The nuclide  $^{131}_{53}\text{I}$  is used to locate brain tumours and also in the diagnosis and treatment of disorders of the thyroid gland. In the case of brain tumours, the isotope is incorporated into a dye and injected into the patient. It is preferentially absorbed by the cancerous cells, and the position of the tumour can be found by scanning the skull. For thyroid cases the patient consumes a low dose of this isotope as  $\text{NaI}$ . The radioactive I concentrates in the thyroid gland and can be measured by counting the  $\gamma$  activity.

Labelled  $\text{NaCl}$  solution which contains the isotope  $^{24}_{11}\text{Na}$  is injected into the veins to discover the location and extent of blood clots and other circulation disorders.

### SOME UNITS AND DEFINITIONS

amu = atomic mass unit =  $\frac{1}{12}$  the mass of the  $^{12}\text{C}$  carbon atom

Mass number = number of neutrons + number of protons

Mass of hydrogen atom  $^1_1\text{H} = 1.007825$  amu

Mass of proton  $^1_1\text{p}$  or  $^1_1\text{H} = 1.007277$  amu

Mass of neutron  $^1_0\text{n} = 1.008665$  amu

Mass of electron  $^0_{-1}\text{e} = 0.00054859$  amu

Mass of helium atom  $^4_2\text{He} = 4.00260$  amu

Mass of helium nucleus ( $\alpha$  particle  $^4_2\text{He}$ ) =  $4.00150$  amu

MeV = million electron volts ( $1\text{ MeV} = 9.648 \times 10^7 \text{ kJ mol}^{-1}$ )

$1\text{ amu} = 931.4812\text{ MeV} = 8.982 \times 10^{10} \text{ kJ mol}^{-1}$

## FURTHER READING


- Abelson, P.H. (1989) Products of neutron irradiation, *J. Chem. Ed.*, **66**, 364–366.
- Ahrens, L.H. (ed.) (1979) *Origin and Distribution of the Elements*, Pergamon Press, Oxford. (Proceedings of second UNESCO symposium.)
- Cadman, P. (1986) Energy from the nucleus, *Education in Chemistry*, **23**, 8–11.
- Choppin, G.R. and Rydberg, J. (1980) *Nuclear Chemistry – Theory and Applications*, Pergamon, Oxford.
- Cunninghame, J.G. (1972) *Chemical Aspects of the Atomic Nucleus*, Monographs for Teachers, No. 23, Royal Society for Chemistry, London.
- Fergusson, J.E. (1982) *Inorganic Chemistry and the Earth* (Chapter 1, Origins: the Chemical Elements and the Earth), Pergamon, Oxford.
- Grabowski, K.F.M. (1986) The early use of radioactive tracers in chemistry, *Education in Chemistry*, **23**, 174–176.
- Nier, A.O. (1989) Some reminiscences of mass spectrometry and the Manhattan Project, *J. Chem. Ed.*, **66**, 385–388. (Reflections on nuclear fission at its half century.)
- Peacocke, T.A.H. (1978) *Radiochemistry: Theory and Experiment*, Wykeham Publications, London. (A good elementary text.)
- Rhodes, R. (1989) The complementarity of the Bomb, *J. Chem. Ed.*, **66**, 376–379. (Reflections on nuclear fission at its half century.)
- Seaborg, G.T. (1989) Nuclear fission and transuranium elements, *J. Chem. Ed.*, **66**, 379–384. (Reflections on nuclear fission at its half century.)
- Selbin, J. (1973) Stellar nucleosynthesis, *J. Chem. Ed.*, **50**, 306, 380.
- Sime, R.L. (1989) Lise Meitner and the discovery of fission, *J. Chem. Ed.*, **66**, 373–376. (Reflections on nuclear fission at its half century.)
- Steinberg, E.P. (1989) Radiochemistry of the fission products, *J. Chem. Ed.*, **66**, 367–372. (Reflections on nuclear fission at its half century.)
- Taylor, R.J. (1972) *The Origin of the Chemical Elements*, Wykenham Publications, London. (A relatively straightforward account.)
- Thompson, R. (ed.) (1986) *The Modern Inorganic Chemicals Industry*, Special Publication No. 31, The Chemical Society, London. (See the chapter 'The Inorganic Chemistry of Nuclear Fuels' by Findlay, J.R. et al.)
- Vertes, A. and Kiss, I. (1987) *Nuclear Chemistry* (Topics in Inorganic and General Chemistry Series: No. 22), Elsevier.

## PROBLEMS

1. What is the nature of the binding forces in atomic nuclei? How does the average binding energy per nucleon vary with the atomic number of the element?
2. Define the following terms: atomic number, mass number, isotope,  $\alpha$  decay,  $\beta$  decay,  $\gamma$  radiation, nuclear fission, nuclear fusion.
3. In what way is the mode of decay of a particular nucleus related to (a) the ratio of neutrons and protons, and (b) the size?
4. Explain the terms mass number, isotopic mass and nuclear binding energy used in the description of an isotope.
5. Draw a diagram to illustrate how the binding energy per nucleon varies with the mass number. Comment on the shape of the curve.



- 6 How would you work out the binding energy per nucleon for a given atomic nucleus? What is the significance of this value?
- 7 Work out the binding energy per nucleon (in MeV per nucleon) for the isotope  $^{56}_{26}\text{Fe}$  given the masses  $^{56}\text{Fe}$  55.93494 amu, neutron 1.008665 amu, proton 1.00783 amu, electron 0.00054859 amu (Answer 8.79 MeV per nucleon)
- 8  $^{24}_{11}\text{Na}$  is an unstable isotope of sodium with a half life of 15 hours. Calculate the value of the radioactive decay constant. Explain how you would attempt to predict the mode of decay.
- 9 What is the radioactive displacement law? Illustrate the radioactive displacement law by reference to the four radioactive decay series.
- 10 Write equations showing how the following nuclei undergo  $\alpha$  decay  
(a)  $^{238}_{92}\text{U}$ , (b)  $^{232}_{90}\text{Th}$ , (c)  $^{191}_{83}\text{Bi}$ , (d)  $^{212}_{86}\text{Rn}$ , (e)  $^{215}_{84}\text{Po}$
- 11 Write equations showing how the following nuclei undergo  $\beta$  decay  
(a)  $^{27}_{12}\text{Mg}$ , (b)  $^{211}_{82}\text{Pb}$ , (c)  $^{24}_{10}\text{Ne}$ , (d)  $^{60}_{27}\text{Co}$ , (e)  $^{14}_6\text{C}$
- 12 Write equations showing how the following nuclei undergo electron capture  
(a)  $^{40}_{19}\text{K}$ , (b)  $^7_4\text{Be}$ , (c)  $^{71}_{32}\text{Ge}$ , (d)  $^{119}_{51}\text{Sb}$ , (e)  $^{75}_{34}\text{Se}$
- 13 Write equations showing how the following nuclei undergo positron  $\beta^+$  emission  
(a)  $^{13}_7\text{N}$ , (b)  $^{18}_9\text{F}$ , (c)  $^{22}_{11}\text{Na}$ , (d)  $^{19}_{10}\text{Ne}$ , (e)  $^{60}_{30}\text{Zn}$
- 14 Write an equation to show what would happen if a nuclide  $^{256}_{118}\text{Fm}$  underwent spontaneous fission producing two identical daughter nuclei and liberating four neutrons. Write another equation assuming that the daughter nuclei differ from each other by 40 mass numbers.
- 15 In the naturally occurring uranium decay series the nuclide  $^{238}_{92}\text{U}$  decays in succession by  $\alpha$ ,  $\beta$ ,  $\beta$ ,  $\alpha$ ,  $\alpha$ ,  $\alpha$ ,  $\beta$  decay. Write an equation showing the mass numbers, atomic numbers and symbols for the nuclides formed by these decays.
- 16 In the naturally occurring thorium decay series, the nuclide  $^{232}_{90}\text{Th}$  decays in succession by  $\alpha$ ,  $\beta$ ,  $\beta$ ,  $\alpha$ ,  $\alpha$ ,  $\alpha$ ,  $\beta$  decay. Write an equation showing the mass numbers, atomic numbers and symbols for the nuclides formed by these decays.
- 17 The following reaction is one of the processes which occurs during fission



Given that the masses are U 235.0439 amu, Ce 139.9054 amu, Zr 93.9063 amu, n 1.008665 amu, e 0.00054859 amu, calculate how much energy is released in MeV per fission (Answer 205 MeV per fission)

18. Explain the main differences between the two atomic bombs that were dropped on Japan.
19. (a) What is the difference between a chain reaction and a branched chain reaction.  
(b) What is a moderator? Give examples.  
(c) Explain what the critical mass of a fissile material is, and why does the critical mass vary?
20. Compare the processes of nuclear fission and fusion as sources of energy.
21. Calculate the energy released in MeV per fusion in the following process:



given that the atomic masses are:  ${}^2\text{D}$  2.01410 amu,  ${}^1\text{H}$  1.007825 amu,  ${}^3\text{He}$  3.01603 amu. (Answer: 5.5 MeV per fusion.)

22. Explain how nuclei heavier than uranium can be prepared.
23. List uses for radioactive isotopes.

Electronic spectra from transition metal ions and complexes are observed in the visible and UV regions. Absorption spectra show the particular wavelengths of light absorbed, that is the particular amount of energy required to promote an electron from one energy level to a higher level, whilst emission spectra show the energy emitted when the electron falls back from the excited level to a lower level. Transitions involving the outer shell of electrons are generally observed in the wavenumber region  $100\,000\text{ cm}^{-1}$  to  $10\,000\text{ cm}^{-1}$ , but most spectra are measured in the  $50\,000\text{--}10\,000\text{ cm}^{-1}$  region (200–1000 nm). The interpretation of spectra provides a most useful tool for the description and understanding of the energy levels present.

### ENERGY LEVELS IN AN ATOM

The energy levels in an atom are described in Chapter 1 in terms of four quantum numbers

- 1  $n$  the principal quantum number which may have values 1, 2, 3, 4 corresponding to the first, second, third or fourth shell of electrons around the nucleus
- 2  $l$  is the subsidiary quantum number, and may have  $n$  values. These values are 0, 1, 2, ...,  $(n - 1)$ . They describe the orbital angular momentum or shape of the orbital. Thus

$n = 1$	$l = 0$	spherical $s$ orbital
$n = 2$	$l = 0$	spherical $s$ orbital
	$l = 1$	dumb bell shaped $p$ orbital
$n = 3$	$l = 0$	$s$ orbital
	$l = 1$	$p$ orbital
	$l = 2$	$d$ orbital

- 3  $m$  the magnetic quantum number may have values from  $+l$ ,  $(l - 1)$ , 0, ...,  $-l$
- 4  $m_s$  the electron spin quantum number which has a value of either  $+\frac{1}{2}$  or  $-\frac{1}{2}$

The build-up of electrons in the elements follows three simple rules:

1. Electrons normally occupy the orbitals of lowest energy.
2. Hund's rule: when several orbitals have the same energy, electrons are not paired if this can be avoided. Thus in the ground state, an atom will contain the maximum number of unpaired electron spins.
3. The Pauli exclusion principle: no two electrons in one atom can have all four quantum numbers the same.

This can be illustrated using boxes for orbitals, and arrows for electrons (Figure 32.1). The two electrons in the 1s orbital for He have opposite spins; thus  $\uparrow$  denotes  $m_s = +\frac{1}{2}$  and  $\downarrow$  denotes  $m_s = -\frac{1}{2}$ . The filling of the 1s and 2s energy levels is straightforward.

At boron, an electron occupies a 2p orbital. The three 2p orbitals have identical values of  $n = 2$ , and  $l = 1$ , but have different values of  $m$  (+1, 0

Principal quantum no. $n$	1	2		
Subsidiary quantum no. $l$	0	0	1	
Magnetic quantum no. $m$	0	0	+1	-1
	1s	2s	2p	
H	$\uparrow$			
He	$\uparrow\downarrow$			
Li	$\uparrow\downarrow$	$\uparrow$		
Be	$\uparrow\downarrow$	$\uparrow\downarrow$		
B	$\uparrow\downarrow$	$\uparrow\downarrow$	$\uparrow$	
C	$\uparrow\downarrow$	$\uparrow\downarrow$	$\uparrow$	$\uparrow$
N	$\uparrow\downarrow$	$\uparrow\downarrow$	$\uparrow$	$\uparrow$
O	$\uparrow\downarrow$	$\uparrow\downarrow$	$\uparrow\downarrow$	$\uparrow$

Figure 32.1 Electronic arrangements of the elements.

and  $-1$ ) giving the  $p_x$ ,  $p_y$ , and  $p_z$  orbitals. Allowing for two values for  $m_s$  for each of these, there is a total of six possible arrangements for this single electron. The three  $p$  orbitals are degenerate, so it does not matter which arrangement is adopted. When only one electron is present in a degenerate energy level or subshell such as  $2p$ ,  $3p$  or  $3d$ , the energy depends on  $l$  the orbital quantum number.

$p_x \quad p_y \quad p_z$			$p_x \quad p_y \quad p_z$		
↑	↑		↑	↓	
	↑	↑		↑	↓
↑		↑	↑		↓
↓	↓		↓	↑	
	↓	↓		↓	↑
↓		↓	↓		↑
			↑↓		
				↑↓	
					↑↓

Figure 32.2 Electronic arrangements of microstates for  $p^2$  configuration

In the case of carbon, two electrons occupy the  $2p$  level, and there are 15 possible electronic arrangements (Figure 32.2). These can be divided into three main groups of different energy – called three energy states. Thus even though the  $p$  orbitals are degenerate and have the same energy the electrons present in them interact with each other and result in the formation of a ground state (lowest energy) and one or more excited states for the atom or ion. In addition to the electrostatic repulsion between electrons, they influence each other (1) by the interaction or coupling of the magnetic fields produced by their spins and (2) by coupling of the fields produced by the orbital motion of the electrons (orbital angular momentum). When several electrons occupy a subshell the energy states obtained depend on the result of the orbital angular quantum numbers of each of the electrons. This resultant of all the  $l$  values is denoted by a new quantum number  $L$ , which defines the energy state for the atom.

$L =$	0	1	2	3	4	5	6		7	8
state	<i>S</i>	<i>P</i>	<i>D</i>	<i>F</i>	<i>G</i>	<i>H</i>	<i>I</i>	✱	<i>K</i>	<i>L</i>

(The letter  $J$  is omitted since this is used for another quantum number described later.)

### Coupling of orbital angular momenta

#### $p^2$ configuration

Angular momentum is quantized into 'packets' of magnitude  $h/2\pi$  (where  $h$  is Planck's constant). For a  $p$  electron, the subsidiary or azimuthal quantum number  $l = 1$ , and the orbital angular momentum  $= 1(h/2\pi)$  and is




Figure 32.3 Resultant of  $l$  terms for  $p^2$  configuration.

shown as an arrow of unit length. The ways in which the  $l$  values for two  $p$  electrons may interact with each other are shown diagrammatically using vector diagrams (Figure 32.3). Because angular momentum is quantized, the only permissible arrangements are those where the resultant is a whole number of quanta. Thus three possible states of spectroscopic terms  $D$ ,  $P$  and  $S$  arise. For the  $P$  state, the vectors  $l$  must be at an angle to each other such that the resultant is a whole number of quanta and in this case  $L = 1$ .

### $p^3$ configuration

The coupling of the  $l$  values of three  $p$  electrons by vectorial addition can be considered in an analogous way, and for simplicity this is considered as the interaction of a third  $p$  electron on the states obtained for the  $p^2$  case (Figure 32.4). The result of coupling the orbital angular momenta is the production of one  $F$  state, two  $D$  states, three  $P$  states and one  $S$  state.




Figure 32.4 Resultant of  $l$  terms for  $p^3$  configuration.

### $d^2$ configuration

The coupling of  $l$  values for  $d$  electrons follows a similar pattern, except that for a  $d$  electron  $l = 2$ , so the arrows are of double length (Figure 32.5).




Figure 32.5 Resultant of  $l$  terms for  $d^2$  configuration

### Coupling of spin angular momenta

For a single electron, the spin quantum number  $m_s$  has a value of  $+\frac{1}{2}$  or  $-\frac{1}{2}$ . If two or more electrons are present in a subshell, the magnetic fields produced interact with each other, that is 'couple', giving a resultant spin quantum number  $S$  (It is unfortunate that the symbol  $S$  is used both for the resultant spin quantum number, and for the spectroscopic state when  $L = 0$ , but in practice this does not normally cause confusion.)

### $p^2$ or $d^2$ case

By using arrows to depict the quantized amounts of energy associated with the  $m_s$  value of each electron, it can be seen that the resultant spin quantum number  $S$  must have a value of 0 or 1 (Figure 32.6)



Figure 32.6 Resultant of  $m_s$  terms for  $p^2$  or  $d^2$  configuration

### $p^3$ or $d^3$ case

Here  $S$  has a value of  $1\frac{1}{2}$  or  $\frac{1}{2}$  (Figure 32.7)



Figure 32.7 Resultant of  $m_s$  terms for  $p^3$  or  $d^3$  configuration.

### Spin orbit coupling

When several electrons are present in a subshell, the overall effect of the individual orbital angular momenta  $l$  is given by the resultant angular quantum number  $L$ , and the overall effect of the individual spins  $m_s$  is given by the resultant spin quantum number  $S$ . In an atom, the magnetic effects of  $L$  and  $S$  may interact or 'couple', giving a new quantum number  $J$  called the total angular momentum quantum number, which results from vectorial combination of  $L$  and  $S$ . This coupling of the resulting spin and orbital quantum numbers is called Russell–Saunders or LS coupling.

### Spin orbit coupling $p^2$ case

It has been shown previously that with a  $p^2$  arrangement, resultant orbital quantum number values of  $L = 2, 1$  and  $0$ , and also resultant spin quantum number values of  $S = 1$  and  $0$ , are obtained. These may be coupled to give the total angular quantum number  $J$  (Figure 32.8).




Figure 32.8 Obtaining spectroscopic term symbols by combining the resultant  $L$  and  $S$  terms.



Each of these arrangements corresponds to an electronic arrangement sometimes called a spectroscopic state which is described by a full term symbol. The letter  $D$  indicates that the  $L$  quantum number has a value of two.  $P$  indicates that  $L = 1$  and  $S$  denotes a value of  $L = 0$  as described previously. The lower right hand subscript denotes the value of the total quantum number  $J$  and the upper left superscript indicates the multiplicity which has the value of  $2S + 1$  (where  $S$  is the resultant spin quantum number). The relation between the number of unpaired electrons, the resultant spin quantum number  $S$  and the multiplicity is given in Table 32.1.

Table 32.1

Unpaired electrons	$S$	Multiplicity	Name of state
0	0	1	Singlet
1	$\frac{1}{2}$	2	Doublet
2	1	3	Triplet
3	$\frac{3}{2}$	4	Quartet
4	2	5	Quintet

Thus the symbol  ${}^3D_2$  (pronounced triplet  $D$  two) indicates a  $D$  state hence  $L = 2$ , the multiplicity is three hence  $S = 1$  and the number of unpaired electrons is 2 and the total quantum number  $J = 2$ .

All of the spectroscopic terms derived above for a  $p^2$  configuration would occur for an excited state of carbon  $1s^2 2s^2 2p^1 3p^1$ . However in the ground state of the atom  $1s^2 2s^2 2p^2$  the number of states is limited by the Pauli exclusion principle since no two electrons in the same atom can have all four quantum numbers the same. In the ground state configuration the two  $p$  electrons both have the same values of  $n = 2$  and  $l = 1$  so they must differ in at least one of the remaining quantum numbers  $m$  or  $m_s$ . This restriction reduces the number of terms from  ${}^3D$ ,  ${}^3P$ ,  ${}^3S$ ,  ${}^1D$ ,  ${}^1P$  and  ${}^1S$  to  ${}^1D$ ,  ${}^3P$  and  ${}^1S$ .

This can be shown by writing down only those electronic arrangements of  $m$  and  $m_s$  which do not violate the Pauli exclusion principle. For  $p$  electrons the subsidiary quantum number  $l = 1$  and the magnetic quantum number  $m$  may have values from  $+l \rightarrow 0 \rightarrow -l$  giving in this case values of  $m = +1, 0$  and  $-1$ . There are 15 possible combinations (Table 32.2). The values of  $M_s$  and  $M_L$  (the total spin and total orbital quantum numbers in the  $z$  direction) are obtained by adding the appropriate  $m_s$  and  $m$  values

$$M_s = \sum m_s$$

$$M_L = \sum m$$

$M_L$  has values from  $+L$  0  $-L$  (a total of  $2L + 1$  values) and

$M_s$  has values from  $+S$  0  $-S$  (a total of  $2S + 1$  values)

Table 32.2 Allowed values of  $m$  and  $m_s$  for the  $p^2$  configuration

	$m = +1 \ 0 \ -1$	$M_S$	$M_L$	Term symbol
1	$\uparrow\downarrow$	0	2	$^1D$
2		0	-2	$^1D$
3	$\uparrow\downarrow$	0	0	$\left. \begin{array}{l} \\ \\ \end{array} \right\} ^3P, ^1D, ^1S$
4	$\uparrow$	0	0	
5	$\downarrow$	0	0	
6	$\uparrow\downarrow$	0	1	$\left. \begin{array}{l} \\ \end{array} \right\} ^3P, ^1D$
7	$\downarrow\uparrow$	0	1	
8	$\uparrow\downarrow$	0	-1	$\left. \begin{array}{l} \\ \end{array} \right\} ^3P, ^1D$
9	$\downarrow\uparrow$	0	-1	
10	$\uparrow\uparrow$	1	1	$^3P$
11	$\uparrow$	1	0	$^3P$
12	$\uparrow\uparrow$	1	-1	$^3P$
13	$\downarrow\downarrow$	-1	1	$^3P$
14	$\downarrow$	-1	0	$^3P$
15	$\downarrow\downarrow$	-1	-1	$^3P$

The  $L$  and  $S$  quantum numbers associated with each electronic configuration (and hence the spectroscopic term symbol) can be worked out from the  $M_L$  and  $M_S$  quantum numbers in Table 32.2. First choose the maximum  $M_S$  value, and select the maximum  $M_L$  associated with it. This gives  $M_S = 1$  and  $M_L = 1$  (number 10 in table), and corresponds to a group of terms where  $L = 1$  and  $S = 1$ . Since  $L = 1$ , this must be a  $P$  state, and since  $S = 1$ , the multiplicity  $(2S + 1) = 3$ , so it is in fact a triplet  $P$  state  $^3P$ . Using the equations above:

if  $L = 1$ ,  $M_L$  may have the values  $+1, 0$  and  $-1$

and

if  $S = 1$ ,  $M_S$  may have the values  $+1, 0$  and  $-1$

There are nine combinations of these two terms:

$$M_L = +1 \quad M_S = +1, 0, -1$$

$$M_L = 0 \quad M_S = +1, 0, -1$$

$$M_L = -1 \quad M_S = +1, 0, -1$$

Examination of Table 32.2 shows that 13 of the allowed values could be assigned a  $^3P$  term symbol.

From the unassigned combinations we next pick out the maximum  $M_S$  and  $M_L$ . In this case  $M_S = 0$  and  $M_L = 2$ . From this it is deduced that  $L = 2$  and  $S = 0$ . Since  $L = 2$  this must be a  $D$  state. The value of  $S = 0$  gives a multiplicity of  $2S + 1 = 1$ , so it is a singlet  $D$  state  $^1D$ .

If  $L = 2$ , then  $M_L$  may have values  $+2, +1, 0, -1$  and  $-2$ , and since  $S = 0$ ,  $M_S = 0$ . This gives five combinations of  $M_L$  and  $M_S$ . Examination of

Table 32.2 shows that nine of the allowed values could be assigned a  $^1D$  term symbol

The  $^3P$  and  $^1D$  states account for  $9 + 5 = 14$  combinations, and the remaining one which corresponds to  $M_L = 0$  and  $M_S = 0$ , must correspond to  $L = 0$  and  $S = 0$ . This gives a singlet  $S$  state  $^1S$ . Thus all 15 permissible electronic arrangements are accounted for by the  $^1D$ ,  $^3P$  and  $^1S$  states. Where two or more allowed electronic configurations have the same values for  $M_L$  and  $M_S$  (for example configurations 3, 4 and 5 in Table 32.2), more than one term symbol will describe the arrangement. In these cases a linear combination of the functions should be taken, and it is incorrect to attribute any one term to a particular arrangement.

### DETERMINING THE GROUND STATE TERMS – HUND'S RULES

Once the terms are known, they can be arranged in order of energy and the ground state term identified by using Hund's rules

- 1 The terms are placed in order depending on their multiplicities and hence their  $S$  values. The most stable state has the largest  $S$  value, and stability decreases as  $S$  decreases. The ground state therefore possesses the most unpaired spins because this gives the minimum electrostatic repulsion.
- 2 For a given value of  $S$ , the state with the highest  $L$  value is the most stable.
- 3 If there is still ambiguity, for given values of  $S$  and  $L$ , the smallest  $J$  value is the most stable if the subshell is less than half filled, and the biggest  $J$  is most stable if the subshell is more than half filled.

(Hund's rules should not be used to predict the order of excited configurations such as  $C 1s^2, 2s^2, 2p^1, 3p^1$ .)

Applying the first rule to the terms arising from  $p^2$  in the ground state of carbon the  $^3P$  state must be the ground state since there is only one triplet state,  $^1D$  and  $^1S$  being singlets. Using the second rule the  $^1D$  state corresponds to a value of  $L = 2$  and is more stable than the  $^1S$  state where  $L = 0$ . Finally, the triplet  $P$  state has three terms  $^3P_2$ ,  $^3P_1$  and  $^3P_0$  so from the third rule  $^3P_0 < ^3P_1 < ^3P_2$ . The experimentally measured energies for the terms arising from the ground state of carbon are shown in Figure 32.9. It can be seen that for a light atom like carbon, the splitting of the  $^3P$  terms because of the  $J$  terms from spin orbit coupling is much smaller than the splitting into  $^1S$ ,  $^1D$  and  $^3P$  terms resulting from coupling of  $l$  quantum numbers. For the lighter elements below atomic number 30, the splitting of levels of different  $J$  is small compared with the splitting of levels of different  $L$  (see Figure 32.9), hence Russell–Saunders coupling gives the correct result for the sequence of energy levels or terms for the first row of transition elements. For the heavier elements, the  $J$  splitting is greater than the  $L$  splitting and Russell–Saunders coupling can no longer be used and an alternative form of  $j-j$  coupling is used instead.




Figure 32.9 Splitting of terms in carbon ground state.

## HOLE FORMULATION

When a subshell is more than half full, it is simpler and more convenient to work out the terms by considering the 'holes' – that is the vacancies in the various orbitals – rather than the larger number of electrons actually present. The terms derived in this way for the ground state of oxygen which has a  $p^4$  configuration and hence two 'holes' are the same as for carbon with a  $p^2$  configuration, that is  $1S$ ,  $1D$  and  $3P$ . However, oxygen has a more than half filled subshell, and hence when applying Hund's third rule, the energy of the triplet  $P$  states for oxygen are  $^3P_2 < ^3P_1 < ^3P_0$ , making  $^3P_2$  the ground state. In a similar way, by considering 'holes', the terms which arise for pairs of atoms with  $p^n$  and  $p^{6-n}$  arrangements, and also  $d^n$  and  $d^{10-n}$ , give rise to identical terms (Table 32.3).

Table 32.3 Terms arising for  $p$  and  $d$  configurations

Electronic configuration	Ground state term	Other terms
$p^1, p^5$	$2P$	
$p^2, p^4$	$3P$	$1S, 1D$
$p^3$	$4S$	$2P, 2D$
$p^6$	$1S$	
$d^1, d^9$	$2D$	
$d^2, d^8$	$3F$	$3P, 1G, 1D, 1S$
$d^3, d^7$	$4F$	$4P, 2H, 2G, 2F, 2D, 2P$
$d^4, d^6$	$5D$	$3H, 3G, 3F, 3D, 3P, 1I, 1G, 1F, 1D, 1S$
$d^5$	$6S$	$4G, 4F, 4D, 4P, 2I, 2H, 2G, 2F, 2D, 2P, 2S$
$d^{10}$	$1S$	

### Derivation of the term symbol for a closed subshell

If a subshell is completely filled with electrons for example  $p^6$  or  $d^{10}$  arrangements the derivation of terms is greatly simplified

$$\begin{array}{rcc}
 & m = +1 & 0 & -1 & M_s & M_L \\
 p^6 & \boxed{\uparrow\downarrow} & \boxed{\uparrow\downarrow} & \boxed{\uparrow\downarrow} & 0 & 0 \\
 \\
 & m = +2 & +1 & 0 & -1 & -2 \\
 d^{10} & \boxed{\uparrow\downarrow} & \boxed{\uparrow\downarrow} & \boxed{\uparrow\downarrow} & \boxed{\uparrow\downarrow} & \boxed{\uparrow\downarrow} & 0 & 0
 \end{array}$$

In both of these cases the total spin quantum number in the  $z$  direction  $M_s$ , which equals the sum of all the individual  $m_s$  values is zero hence  $S = 0$  and the multiplicity  $2S + 1 = 1$ . Also in both  $p^6$  and  $d^{10}$  cases the total orbital angular quantum number in the  $z$  direction  $M_L = \sum m_l = 0$  hence  $L = 0$  corresponding to an  $S$  state. Thus a closed shell of electrons always produces a singlet  $S$  state  $^1S_0$ .

### Derivation of the terms for a $d^2$ configuration

For  $d$  electrons the subsidiary quantum number  $l$  is 2 and the magnetic quantum number  $m$  has values from  $+l \rightarrow 0 \rightarrow -l$  giving in this case  $m = +2, +1, 0, -1$  and  $-2$ . There are 45 ways in which two  $d$  electrons may be arranged which do not violate the Pauli exclusion principle. These arrangements are shown in Table 32.4.

The terms are assigned in a similar way as for the  $p^2$  case. The highest value of  $M_L = 4$  can only arise if  $L = 4$  corresponding to a  $G$  state and since  $M_S = 0$ ,  $S$  must be 0, and it is a singlet  $G$  term  $^1G$ .  $M_L$  can have values from  $+L$  to  $-L$  in this case  $+4, +3, +2, +1, 0, -1, -2, -3$  and  $-4$  but  $M_s$  has only one value so there are nine configurations associated with this term.

The highest unassigned  $M_L$  value is  $+3$  indicating an  $F$  state and this occurs with  $M_s = +1, 0$  and  $-1$ , suggesting a triplet  $F$  state  $^3F$ .  $M_L$  may have values of  $+3, +2, +1, 0, -1, -2$  and  $-3$  and since  $M_s$  has three values there are 21 configurations associated with the  $^3F$  term.

Thirty of the 45 configurations have been accounted for and examination of the groups of configurations which have the same  $M_L$  and  $M_s$  values shows that the remaining 15 terms are the same as for the  $p^2$  case that is  $^1D$ ,  $^3P$  and  $^1S$ . The full list of terms for a  $d^2$  configuration is therefore  $^1G$ ,  $^3F$ ,  $^1D$ ,  $^3P$  and  $^1S$ . Applying Hund's rules, the ground state is  $^3F$ , and the energy of the various states is  $^3F < ^3P < ^1G < ^1D < ^1S$ .

The spectra of a number of  $d^2$  ions have been measured and the energy of the  $^3P$  state is shown to be higher than the  $^3F$  ground state in each case (Table 32.5). Quantitative data are available for the energy levels in free metal ions in the gas phase, and the next step is to find how these energy levels change when ligands approach to form a complex.

Table 32.4 Allowed values of  $m$  and  $m_s$  for the  $d^2$  configuration

$m = +2 \ +1 \ 0 \ -1 \ -2$						$\Sigma m_s = M_s$	$\Sigma m = M_l$	Term symbol
1	↑↓					0	4	$^1G$
2	↑	↑				1	3	$^3F$
3	↑	↓				0	3	} $^1G, ^3F$
4	↓	↑				0	3	
5	↓	↓				-1	3	$^3F$
6	↑		↑			1	2	$^3F$
7	↑		↓			0	2	} $^1G, ^3F, ^1D$
8	↓		↑			0	2	
9		↑↓				0	2	} $^3F$
10	↓		↓			-1	2	
11	↑			↑		1	1	} $^3F, ^3P$
12		↑	↑			1	1	
13	↓			↓		-1	1	} $^3F, ^3P$
14		↓	↓			-1	1	
15	↑			↓		0	1	} $^1G, ^3F, ^1D, ^3P$
16	↓			↑		0	1	
17		↑	↓			0	1	
18		↓	↑			0	1	
19	↑				↑	1	0	} $^3F, ^3P$
20		↑		↑		1	0	
21	↑				↓	0	0	} $^1G, ^3F, ^1D, ^3P, ^1S$
22	↓				↑	0	0	
23		↑		↓		0	0	
24		↓		↑		0	0	
25			↑↓			0	0	} $^3F, ^3P$
26	↓				↓	-1	0	
27		↓		↓		-1	0	} $^1G, ^3F, ^1D, ^3P$
28		↑			↓	0	-1	
29		↓			↑	0	-1	
30			↑	↓		0	-1	
31			↓	↑		0	-1	} $^3F, ^3P$
32		↑			↑	1	-1	
33			↑	↑		1	-1	} $^3F, ^3P$
34		↓			↓	-1	-1	
35			↓	↓		-1	-1	} $^3F$
36			↑		↑	1	-2	
37			↑		↓	0	-2	} $^1G, ^3F, ^1D$
38			↓		↑	0	-2	
39				↑↓		0	-2	} $^3F$
40			↓		↓	-1	-2	
41				↑	↑	1	-3	$^3F$
42				↑	↓	0	-3	} $^1G, ^3F$
43				↓	↑	0	-3	
44				↓	↓	-1	-3	$^3F$
45					↑↓	0	-4	$^1G$

Table 32.5 Energy of  $^3F$  and  $^3P$  states for  $d^2$  free ions

	$Ti^{2+}$	$V^{3+}$	$Cr^{4+}$
$^3P$	$10600\text{ cm}^{-1}$	$13250\text{ cm}^{-1}$	$15700\text{ cm}^{-1}$
$^3F$	0	0	0

## CALCULATION OF THE NUMBER OF MICROSTATES

Each different arrangement of electrons in a set of orbitals has a slightly different energy and is called a microstate, e.g. Table 32.2 for a  $p^2$  arrangement or Table 32.4 for a  $d^2$  arrangement. The number of microstates may be calculated from the number of orbitals and the number of electrons, using the formula

$$\binom{n}{r} = \frac{n!}{r!(n-r)!}$$

where  $n$  is twice the number of orbitals and  $r$  is the number of electrons (Note  $n!$  is factorial  $n$  and  $r!$  is factorial  $r$ ). Thus for a  $p^3$  case there are three orbitals so  $n = 6$ , and three electrons so  $r = 3$ . Hence

$$\binom{6}{3} = \frac{6!}{3!(6-3)!} = \frac{6!}{3! \times 3!} = \frac{6 \times 5 \times 4 \times 3 \times 2 \times 1}{3 \times 2 \times 1 \times 3 \times 2 \times 1} = 20 \text{ microstates}$$

Similarly, for a  $d^2$  case there are five orbitals so  $n = 10$ , and two electrons so  $r = 2$ . Hence

$$\begin{aligned} \binom{10}{2} &= \frac{10!}{2!(10-2)!} = \frac{10!}{2! \times 8!} \\ &= \frac{10 \times 9 \times 8 \times 7 \times 6 \times 5 \times 4 \times 3 \times 2 \times 1}{2 \times 1 \times 8 \times 7 \times 6 \times 5 \times 4 \times 3 \times 2 \times 1} = 45 \text{ microstates} \end{aligned}$$

In a similar way the number of microstates can be worked out for all of the electronic arrangements  $p^1$ – $p^6$  and  $d^1$ – $d^{10}$ .

Table 32.6 The number of microstates for various electron arrangements

Electronic arrangement	Number of microstates	Electronic arrangement	Number of microstates
$p^1$	6	$d^1$	10
$p^2$	15	$d^2$	45
$p^3$	20	$d^3$	120
$p^4$	15	$d^4$	210
$p^5$	6	$d^5$	252
$p^6$	1	$d^6$	210
		$d^7$	120
		$d^8$	45
		$d^9$	10
		$d^{10}$	1

## ELECTRONIC SPECTRA OF TRANSITION METAL COMPLEXES

Spectra arise because electrons may be promoted from one energy level to another. Such electronic transitions are of high energy, and in addition much lower energy vibrational and rotational transitions always occur. The vibrational and rotational levels are too close in energy to be resolved into separate absorption bands, but they result in considerable broadening of the electronic absorption bands in  $d-d$  spectra. Band widths are commonly found to be of the order of  $1000-3000\text{ cm}^{-1}$ .

The spectrum of a coloured solution may be measured quite easily using a spectrophotometer. A beam of monochromatic light obtained using a prism and a narrow slit is passed through the solution and on to a photoelectric cell. The amount of light absorbed at any particular frequency can be read off, or a whole frequency range can be scanned, and the absorbance  $A$  plotted as a graph on a paper chart recorder. The absorbance was formerly called the optical density. If  $I_0$  is the intensity of the original beam of light, and  $I$  the intensity after passing through the solution, then

$$\log \left( \frac{I_0}{I} \right) = A$$

The molar absorption coefficient  $\epsilon$  is usually calculated from the absorbance

$$\epsilon = \frac{A}{cl}$$

where  $c$  is the concentration of the solution in  $\text{mol l}^{-1}$ , and  $l$  is the path length in centimetres. (Cells are commonly 1 cm long.)

Not all of the theoretically possible electronic transitions are actually observed. The position is formalized into a set of selection rules which distinguish between 'allowed' and 'forbidden' transitions. 'Allowed' transitions occur commonly. 'Forbidden' transitions do occur, but much less frequently, and they are consequently of much lower intensity.

## Laporte 'orbital' selection rule

Transitions which involve a change in the subsidiary quantum number  $\Delta l = \pm 1$  are 'Laporte allowed' and therefore have a high absorbance. Thus for Ca,  $s^2 \rightarrow s^1p^1$ ,  $l$  changes by  $+1$  and the molar absorption coefficient  $\epsilon$  is  $5000-10\,000\text{ litres per mol per centimetre}$ . In contrast  $d-d$  transitions are 'Laporte forbidden', since the change in  $l = 0$ , but spectra of much lower absorbance are observed ( $\epsilon = 5-10\text{ l mol}^{-1}\text{ cm}^{-1}$ ) because of



Table 32.7 Molar absorption coefficients for different types of transition

Laporte (orbital)	Spin	Type of spectra	$\epsilon$	Example
Allowed	Allowed	Charge transfer	10 000	$[\text{TiCl}_6]^{3-}$
Partly allowed some $p-d$ mixing	Allowed	$d-d$	500	$[\text{CoBr}_4]^{2-}$ , $[\text{CoCl}_4]^{2-}$
Forbidden	Allowed	$d-d$	8–10	$[\text{Ti}(\text{H}_2\text{O})_6]^{3+}$ , $[\text{V}(\text{H}_2\text{O})_6]^{3+}$
Partly allowed, some $p-d$ mixing	Forbidden	$d-d$	4	$[\text{MnBr}_4]^{2-}$
Forbidden	Forbidden	$d-d$	0.02	$[\text{Mn}(\text{H}_2\text{O})_6]^{2+}$

slight relaxation in the Laporte rule. When the transition metal ion forms a complex it is surrounded by ligands and some mixing of  $d$  and  $p$  orbitals may occur, in which case transitions are no longer pure  $d-d$  in nature. Mixing of this kind occurs in complexes which do not possess a centre of symmetry for example tetrahedral complexes, or asymmetrically substituted octahedral complexes. Thus  $[\text{MnBr}_4]^{2-}$  which is tetrahedral and  $[\text{Co}(\text{NH}_3)_5\text{Cl}]^{3+}$  which is octahedral but non centrosymmetric are both coloured. Mixing of  $p$  and  $d$  orbitals does not occur in octahedral complexes which have a centre of symmetry such as  $[\text{Co}(\text{NH}_3)_6]^{3+}$  or  $[\text{Cu}(\text{H}_2\text{O})_6]^{2+}$ . However, in these cases the metal–ligand bonds vibrate so that the ligands spend an appreciable amount of time out of their centrosymmetric equilibrium position. Thus a very small amount of mixing occurs, and low-intensity spectra are observed. Thus Laporte allowed transitions are very intense whilst Laporte forbidden transitions vary from weak intensity if the complex is non-centrosymmetric to very weak if it is centrosymmetric (Table 32.7).

### Spin selection rule

During transitions between energy levels, an electron does not change its spin, that is  $\Delta S = 0$ . There are fewer exceptions than for the Laporte selection rule. Thus in the case of  $\text{Mn}^{2+}$  in a weak octahedral field such as  $[\text{Mn}(\text{H}_2\text{O})_6]^{2+}$  the  $d-d$  transitions are spin forbidden because each of the  $d$  orbitals is singly occupied. Many  $\text{Mn}^{2+}$  compounds are off white or pale flesh coloured, but the intensity is only about one hundredth of that for a 'spin allowed' transition (Table 32.7). Since the spin forbidden transitions are very weak, analysis of the spectra of transition metal complexes can be greatly simplified by ignoring all spin forbidden transitions and considering only those excited states which have the same multiplicity as the ground state. Thus for a  $d^5$  configuration the only terms which need be considered are the ground state  $^6F$  and the excited state  $^6P$ .




Figure 32.10  $\text{Mn}^{2+}$  in weak octahedral field

## SPLITTING OF ELECTRONIC ENERGY LEVELS AND SPECTROSCOPIC STATES

An  $s$  orbital is spherically symmetrical and is unaffected by an octahedral (or any other) field.  $p$  orbitals are directional, and  $p$  orbitals are affected by an octahedral field. However, since a set of three  $p$  orbitals are all affected equally, their energy levels remain equal, and no splitting occurs. A set of  $d$  orbitals is split by an octahedral field into two levels  $t_{2g}$  and  $e_g$ . The difference in energy between these may be written as  $\Delta_o$  or  $10D_q$ . The  $t_{2g}$  level is triply degenerate and is  $4D_q$  below the barycentre, and the  $e_g$  level is doubly degenerate and is  $6D_q$  above the barycentre. For a  $d^1$  configuration, the ground state is a  ${}^2D$  state, and the  $t_{2g}$  and  $e_g$  electronic energy levels correspond with the  $T_{2g}$  and  $E_g$  spectroscopic states. A set of  $f$  orbitals is split by an octahedral field into three levels. For an  $f^1$  arrangement the ground state is a  ${}^3F$  state and is split into a triply degenerate  $T_{1g}$  state which is  $6D_q$  below the barycentre, a triply degenerate  $T_{2g}$  level which is  $2D_q$  above the barycentre and a single  $A_{2g}$  state which is  $12D_q$  above the barycentre (Figure 32.11). We will see later that the same arrangement of states occurs with  $d^2$  arrangement.




Figure 32.11 Splitting of spectroscopic terms arising from (a)  $d^1$  electronic arrangement and (b)  $d^2$  electronic arrangement.


In the 'one electron cases'  $s^1$ ,  $p^1$ ,  $d^1$  and  $f^1$  there is a direct correspondence between the splitting of electronic energy levels which occurs in a crystal field and the splitting of spectroscopic states. Thus in an octahedral field the  $S$  and  $P$  states are not split.  $D$  states are split into two states and  $F$  states are split into three states.

Table 32.8 Transforming spectroscopic terms into Mulliken symbols


Spectroscopic term	Mulliken symbols	
	Octahedral field	Tetrahedral field
<i>S</i>	$A_{1g}$	$A_1$
<i>P</i>	$T_{1g}$	$T_1$
<i>D</i>	$E_g + T_{2g}$	$E + T_2$
<i>F</i>	$A_{1g} + T_{1g} + T_{2g}$	$A_2 + T_1 + T_2$
<i>G</i>	$A_{1g} + E_g + T_{1g} + T_{2g}$	$A_1 + E + T_1 + T_2$

SPECTRA OF  $d^1$  AND  $d^9$  IONS

In a free gaseous metal ion the  $d$  orbitals are degenerate, and hence there will be no spectra from  $d-d$  transitions. When a complex is formed, the electrostatic field from the ligands splits the  $d$  orbitals into two groups  $t_{2g}$  and  $e_g$  (This crystal field splitting is described in Chapter 7.) The simplest example of a  $d^1$  complex is  $Ti(III)$  in octahedral complexes such as  $[TiCl_6]^{3-}$ , or  $[Ti(H_2O)_6]^{3+}$ . The splitting of the  $d$  orbitals is shown in Figure 32.12a. In the ground state the single electron occupies the lower  $t_{2g}$  level, and only one transition is possible to the  $e_g$  level. Consequently the



(a)



(b)

Figure 32.12 (a) Diagram of energy levels in octahedral field (b) Ultraviolet and visible absorption spectrum of  $[Ti(H_2O)_6]^{3+}$




Figure 32.13 Splitting of energy levels for  $d^1$  configuration in octahedral field.

absorption spectrum of  $[\text{Ti}(\text{H}_2\text{O})_6]^{3+}$  which is shown in Figure 32.12b, shows only one band with a peak at  $20\,300\text{ cm}^{-1}$ . The magnitude of the splitting  $\Delta_0$  depends on the nature of the ligands, and affects the energy of the transition, and hence the frequency of maximum absorption in the spectrum. Thus the peak occurs at  $13\,000\text{ cm}^{-1}$  in  $[\text{TiCl}_6]^{3-}$ ,  $18\,900\text{ cm}^{-1}$  in  $[\text{TiF}_6]^{3-}$ ,  $20\,300\text{ cm}^{-1}$  in  $[\text{Ti}(\text{H}_2\text{O})_6]^{3+}$  and  $22\,300\text{ cm}^{-1}$  in  $[\text{Ti}(\text{CN})_6]^{3-}$ . The amount of splitting caused by various ligands is related to their position in the spectrochemical series (see Chapter 7). The effect of an octahedral ligand field on a  $d^1$  ion is shown in Figure 32.13. The symbol  $^2D$  at the left is the ground state term for a free ion with a  $d^1$  configuration (see Table 32.3). Under the influence of a ligand field this splits into two states which are described by the Mulliken symbols  $^2E_g$  and  $^2T_{2g}$ . (These symbols originate in group theory, and are used here without attempting to derive them. Useful references are given at the end of the chapter.) The lower  $T_{2g}$  state corresponds to the single  $d$  electron occupying one of the  $t_{2g}$  orbitals, and the  $^2E_g$  state corresponds to the electron occupying one of the  $e_g$  orbitals. The two states are separated more widely as the strength of the ligand field increases.

Octahedral complexes of ions with a  $d^9$  configuration such as  $[\text{Cu}(\text{H}_2\text{O})_6]^{2+}$  can be described in a similar way to the  $\text{Ti}^{3+}$  octahedral complexes with a  $d^1$  arrangement. In the  $d^1$  case there is a single electron in the lower  $t_{2g}$  level whilst in the  $d^9$  case there is a single hole in the upper  $e_g$  level. Thus the transition in the  $d^1$  case is promoting an electron from the  $t_{2g}$  level to the  $e_g$  level, whilst in the  $d^9$  case it is simpler to consider the promotion of an electron as the transfer of a 'hole' from  $e_g$  to  $t_{2g}$ . The energy diagram for  $d^9$  is therefore the other way round, that is the inverse of that for a  $d^1$  configuration (Figure 31.14).

If the effect of a tetrahedral ligand field is now considered, the degen-




Figure 32.14 Splitting of energy levels for  $d^9$  configuration in octahedral field

erate  $d$  orbitals split into two  $e_g$  orbitals of lower energy and three  $t_{2g}$  orbitals of higher energy (see Chapter 7). The energy level diagram for  $d^1$  complexes in a tetrahedral field is the inverse of that in an octahedral field, and is similar to the  $d^9$  octahedral case (Figure 32.13), except that the amount of splitting in a tetrahedral field is only about  $\frac{4}{9}$  of that in an octahedral field.

In a similar way the  $d^6$  high-spin octahedral arrangement (Figure 32.15a) is related to the  $d^1$  octahedral case. Since transitions which involve reversal of the electron spin are 'forbidden', and hence give extremely weak bands, the only permitted transition is the paired electron in the  $t_{2g}$  level, which




Figure 32.15 (a)  $d^6$  and (b)  $d^4$  high spin octahedral arrangements

has the opposite spin to all the other electrons, to the  $e_g$  level. The energy level diagram for  $d^6$  high-spin octahedral complexes is the same as the  $d^1$  case (Figure 32.13).

By similar reasoning, octahedral complexes containing  $d^4$  ions in a high-spin arrangement (Figure 32.15b) may be considered as having one 'hole' in the upper  $e_g$  level and thus they are analogous to the  $d^9$  octahedral case (Figure 32.14).

In addition,  $d^6$  tetrahedral complexes have only one electron which can be promoted without changing the spin, and have a diagram like that for  $d^1$  tetrahedral, which is qualitatively similar to that for the  $d^9$  octahedral case. Finally,  $d^4$  and  $d^9$  tetrahedral complexes with one 'hole' are qualitatively like the  $d^1$  octahedral example with one electron.

Figures 32.13 and 32.14 can be combined into a single diagram (Figure 32.16) called an Orgel diagram, which describes in a qualitative way the effect of electron configurations with one electron, one electron more than a half filled level, one electron less than a full shell, and one electron less than a half filled shell.




Figure 32.16 Orgel combined energy level diagram for  $d^1$ . (Note that g subscripts are dropped in tetrahedral cases.)

## SPECTRA OF $d^2$ AND $d^8$ IONS

The ground state for a  $d^2$  electronic arrangement has two electrons in different orbitals. In an octahedral field the  $d$  orbitals are split into three  $t_{2g}$  orbitals of lower energy and two  $e_g$  orbitals of higher energy, and the electrons will occupy two of the  $t_{2g}$  orbitals. When an electron is promoted  $(e_g)^2 \rightarrow (e_g)^1(t_{2g})^1$  there are two possibilities. It requires less energy to promote an electron from the  $d_{xz}$  or  $d_{yz}$  orbitals to the  $d_{z^2}$  orbital than it

does to promote the electron to the  $d_{x^2-y^2}$  orbital. This difference in energy arises because the former transition gives a  $(d_{xy})^1(d_{x^2-y^2})^1$  arrangement where the electrons are spread around all three directions  $x$ ,  $y$  and  $z$  which reduces electron-electron repulsion compared with the  $(d_{xy})^1(d_{xz})^1$  arrangement where the electrons are confined to the  $xy$  plane. If both electrons are promoted another high energy state will be formed. Thus from a consideration of the electrons we would expect four energy levels.

Table 32.3 shows that the terms arising for a  $d^2$  configuration are the ground state  $^3F$  and the excited states  $^3P$ ,  $^1G$ ,  $^1D$  and  $^1S$ . The ground state contains two electrons with parallel spins, but the  $^1G$ ,  $^1D$  and  $^1S$  states contain electrons with opposite spins. Thus transitions from the ground state to these three states are spin forbidden, will be very weak, and can be ignored. The two remaining states  $^3F$  and  $^3P$  can have spin permitted transitions. It will be remembered that  $p$  orbitals are not split by an octahedral field, but that  $f$  orbitals are split into three levels. Similarly in an octahedral field  $P$  states are not split (but are transformed into a  $T_{1g}$  state, and  $F$  states split into  $A_{2g} + T_{1g} + T_{2g}$  (see Figure 32.11 and Table 32.8). The energy level diagram for these is shown in Figure 32.17a.

Three transitions are possible from the ground state  $^3T_{1g}(F)$  to  $^3T_{2g}$ ,  $^3T_{1g}(P)$  and  $^1A_{2g}$  respectively, and hence three peaks should appear in the spectrum. (This may be compared with only one transition in the  $d^1$  case.)

Table 32.9 Ground terms for  $d^1$ – $d^{10}$  configurations

Configuration	Example	Ground term	$m_l$	$M_L$	$S$
			2 1 0 -1 -2		
$d^1$	$Ti^{3+}$	$^2D$		2	$\frac{1}{2}$
$d^2$	$V^{3+}$	$^3F$		3	1
$d^3$	$Cr^{3+}$	$^4F$		3	$1\frac{1}{2}$
$d^4$	$Cr^{2+}$	$^5D$		2	2
$d^5$	$Mn^{2+}$	$^6S$		0	$2\frac{1}{2}$
$d^6$	$Fe^{2+}$	$^5D$		2	2
$d^7$	$Co^{2+}$	$^4F$		3	$1\frac{1}{2}$
$d^8$	$Ni^{2+}$	$^3F$		3	1
$d^9$	$Cu^{2+}$	$^2D$		2	$\frac{1}{2}$




Figure 32.17 Orgel diagram and spectrum for a  $d^2$  ion. (a) Energy diagram for  $d^2$  configuration in octahedral field (simplified by including only the triplet states) showing three possible transitions. (b) Ultraviolet-visible absorption spectrum for the  $d^2$  complex  $[V(H_2O)_6]^{3+}$ .

The spectrum of a  $d^2$  complex ion  $[V(H_2O)_6]^{3+}$  is shown in Figure 32.17. Only two peaks occur in this spectrum because the ligand field strength of water results in transitions occurring close to the cross-over point between the  $^3T_{1g}(P)$  and  $^3A_{2g}$  levels, and hence these two transitions are not resolved into two separate peaks. A  $V^{3+}$  ion complexed with a different ligand would show three peaks.

Complexes of metals such as  $Ni^{2+}$  with a  $d^8$  configuration in an octahedral field can be treated in a similar way. There are two 'holes' in the  $e_g$  level, and hence promoting an electron is equivalent to transferring a 'hole' from  $e_g$  to  $t_{2g}$ . This is the inverse of the  $d^2$  case. The  $^3P$  state is not split, and is not inverted, but the  $^3F$  state is split into three states and is inverted (Figure 32.18). Thus the ground state term for  $Ni^{2+}$  is  $^3A_{2g}$ . Note that in both the  $d^2$  case and the  $d^8$  case the  $^3F$  state is the lowest in energy.

Three spin allowed transitions are observed in the spectra of  $[Ni(H_2O)_6]^{2+}$ ,  $[Ni(NH_3)_6]^{2+}$  and  $[Ni(ethylenediamine)_3]^{2+}$ .

Using the same arguments as applied to the  $d^1$  case, the  $d^2$  octahedral energy diagram is similar to the high-spin  $d^7$  octahedral, and  $d^3$  and  $d^8$  tetrahedral cases. The inverse diagram applies to the  $d^3$  and  $d^8$  octahedral as well as  $d^2$  and  $d^7$  tetrahedral complexes. As before, the g subscript is omitted in tetrahedral complexes.

In a similar way  $Cr(III)$  has a  $d^3$  configuration, and for octahedral complexes the inverted diagram at the left hand side of Figure 32.19 applies. This is similar to the  $d^2$  diagram except that the energies of the three states derived from the  $^3F$  state are inverted in order. The spectra of chromium complexes would be expected to show three absorption bands from the ground state  $^3A_{2g}$  to  $^3T_{2g}$ ,  $^3T_{1g}(F)$  and  $^3T_{1g}(P)$  respectively.







Figure 32 18 Orgel diagram and spectrum for a  $d^8$  ion (a) Energy diagram for  $d^8$  configuration in an octahedral field (simplified by including only the triplet states) showing three spin allowed transitions (b) Ultraviolet-visible absorption spectrum for the  $d^8$  complex  $[\text{Ni}(\text{H}_2\text{O})_6]^{2+}$ . Note the middle peak shows signs of splitting into two peaks because of Jahn-Teller distortion

Chromium(III) complexes show at least two well defined absorption peaks in the visible region. In some cases the third band can be seen though it is often hidden by a very intense charge transfer band.

The combined Orgel energy level diagram for two electron and two 'hole' configurations is shown in Figure 32 19. Note that there are two  $T_{1g}$  states: one from the  $P$  state and the other from the  $F$  state. The two  $T_{1g}$  states are slightly curved lines because they have the same symmetry and they interact with one another. This interelectronic repulsion lowers the energy of the lower state and increases the energy of the higher state. The



**Figure 32.19** Combined Orgel energy level diagram for two-electron and two-hole configurations. (Note that the  $g$  subscript is omitted in tetrahedral cases. The same diagram also applies to the  $d^1$  and  $d^9$  arrangements except that the spectroscopic terms are  $^4F$  and  $^4P$ , and the Mulliken terms have a multiplicity of 4.)

effect is much more marked on the left of the diagram because the two levels are close in energy. If the lines had been straight, they would cross each other, implying at the cross-over point that two electrons in one atom may have the same symmetry and the same energy. This would be impossible, and is prohibited by the non-crossing rule, which says that states of the same symmetry cannot cross each other. The mixing or interelectronic repulsion which causes the bending of the lines is expressed by the Racah parameters  $B$  and  $C$ .


The Racah parameters can in principle be calculated from linear combinations of exchange integrals and coulomb integrals, but they are usually obtained empirically from the spectra of free ions. The difference in energy between states of the same multiplicity for example in a  $d^3$  ion such as  $V^{2+}$  the separation between  $^4F$  and  $^4P$  is  $15B$ . Thus if all three bands are observed in the spectrum,  $B$  is readily obtained. In many cases it is sufficient to use only the parameter  $B$  to explain the positions of the bands in the spectrum. Both the  $B$  and  $C$  parameters are necessary for terms of different multiplicity. For example, in the  $d^3 V^{2+}$  ion the separation between  $^4F$  and  $^2G$  is  $4B + 3C$ . For most transition metal ions  $B$  is approximately  $700\text{--}1000\text{ cm}^{-1}$  and  $C$  is approximately four times  $B$ .

Experimentally measured spectra may be compared with those expected from theory. Consider for example the spectra of  $Cr(III)$ .  $Cr^{3+}$  is a  $d^3$  ion. (See also Chapter 22.) In the ground state, the  $d_{xy}$ ,  $d_{xz}$  and  $d_{yz}$  orbitals each contain one electron and the two  $e_g$  orbitals are empty. The  $d^3$  arrangement gives rise to two states  $^4F$  and  $^4P$ . In an octahedral field the  $^4F$

Table 32 10 Racah parameters  $B$  for transition metal ions in  $\text{cm}^{-1}$ 

Metal	$M^{2+}$	$M^{3+}$
Ti	695	—
V	755	861
Cr	810	918
Mn	860	965
Fe	917	1015
Co	971	1065
Ni	1030	1115

From Sutton D *Electronic Spectra of Transition Metal Complexes* McGraw Hill 1968

Figure 32 20 The splitting of the  $^4F$  and  $^4P$  states in  $\text{Cr}^{3+}$ 

state is split into  $^4A_{2g}(F)$ ,  $^4T_{2g}(F)$  and  $^4T_{1g}(F)$  states, and the  $^4P$  state is not split but transforms into a  $^4T_{1g}(P)$  state (Figure 32 20)

Three transitions are possible  $^4A_{2g} \rightarrow ^4T_{2g}$ ,  $^4A_{2g} \rightarrow ^4T_{1g}(F)$  and  $^4A_{2g} \rightarrow ^4T_{1g}(P)$ . The Racah parameters for the free  $\text{Cr}^{3+}$  ion are known exactly ( $B = 918 \text{ cm}^{-1}$  and  $C = 4133 \text{ cm}^{-1}$ )

Table 32 11 Correlation of spectra for  $[\text{CrF}_6]^{3-}$  ( $\text{in cm}^{-1}$ )

Observed spectra			Predicted	
$^4A_{2g} \rightarrow ^4T_{1g}(P)$	$\nu_1$	34 400	30 700	$(12D_q + 15B)$
$^4A_{2g} \rightarrow ^4T_{1g}(F)$	$\nu_2$	22 700	26 800	$(18D_q)$
$^4A_{2g} \rightarrow ^4T_{2g}$	$\nu_1$	14 900	14 900	$(10D_q)$

(The crystal field splitting may be defined as  $\Delta_0$  or as  $10 D_q$ )

The lowest energy transition correlates perfectly, but agreement for the other two bands is not very good. Two corrections must be made to improve the agreement.

1. If some mixing of the  $P$  and  $F$  terms occurs (bending of lines on the Orgel diagram), then the energy of the  ${}^4T_{1g}(P)$  state is increased by an amount  $x$  and the energy of the  ${}^4T_{1g}(F)$  state is reduced by  $x$ .
2. The value for the Racah parameter  $B$  relates to a free ion. The apparent value  $B'$  in a complex is always less than the free ion value because electrons on the metal can be delocalized into molecular orbitals covering both the metal and the ligands. The use of adjusted  $B'$  values improves the agreement. This delocalization is called the nephelauxetic effect, and the nephelauxetic ratio  $\beta$  is defined:

$$\beta = \frac{B'}{B}$$

$\beta$  decreases as delocalization increases, and is always less than one, and  $B'$  is usually  $0.7B$  to  $0.9B$ ).  $B'$  is easily obtained if all three transitions are observed since:

$$15B' = \nu_3 + \nu_2 - 3\nu_1$$

Using both of these corrections gives much better correlation between observed and improved theoretical results (Table 32.12). (The use of adjusted  $B$  and  $C$  terms is the basis of ligand field calculations.)

Table 32.12 Correlation of spectra for  $[\text{CrF}_6]^{3-}$  (using corrected constants) (in  $\text{cm}^{-1}$ )

		Observed spectra	Corrected theoretical	
${}^4A_{2g} \rightarrow {}^4T_{1g}(P)$	$\nu_3$	34 400	34 800	$(12D_q + 15B' + x)$
${}^4A_{2g} \rightarrow {}^4T_{1g}(F)$	$\nu_2$	22 700	22 400	$(18D_q - x)$
${}^4A_{2g} \rightarrow {}^4T_{2g}$	$\nu_1$	14 900	14 900	$(10D_q)$

As a second example consider the spectrum of crystals of  $\text{KCoF}_3$ . There are three absorption bands at  $7150 \text{ cm}^{-1}$ ,  $15\,200 \text{ cm}^{-1}$  and  $19\,200 \text{ cm}^{-1}$ . The compound contains  $\text{Co}^{2+}$  ions ( $d^7$ ) surrounded octahedrally by six  $\text{F}^-$  ions. This case should be similar to the  $d^2$  case and we would expect transitions  $\nu_1$  ( ${}^4T_{1g} \rightarrow {}^4T_{2g}$ ),  $\nu_2$  ( ${}^4T_{1g} \rightarrow {}^4A_{2g}$ ) and  $\nu_3$  ( ${}^4T_{1g} \rightarrow {}^4T_{1g}(P)$ ).  $D_q$  may be calculated from  $\nu_1$  since:

$$\nu_1 = 8D_q$$

However, this makes no allowance for the configuration interaction between the  ${}^4T_{1g}$  and  ${}^4T_{2g}$  states (i.e. bending of lines on the Orgel diagram). It is therefore better to evaluate  $D_q$  from the equation:

$$\nu_2 - \nu_1 = 10D_q$$

since this is not affected by configuration interaction. Thus:

$$15\,200 - 7\,200 = 10D_q$$

hence

$$D_q \approx 800\text{ cm}^{-1}$$

The value of the configuration interaction term  $x$  is obtained either from the equation

$$v_1 \approx 8D_q + x$$

or from

$$v_2 \approx 18D_q + x$$

The Racah parameter  $B$  for a free  $\text{Co}^{2+}$  ion is  $971\text{ cm}^{-1}$  (Table 32.10) but the corrected value  $B'$  may be calculated from the equation

$$v_3 = 15B' + 6D_q + 2x$$

The pale pink colour of many octahedral complexes of  $\text{Co(II)}$  are of interest. The spectrum of  $[\text{Co}(\text{H}_2\text{O})_6]^{2+}$  is shown in Figure 32.21




Figure 32.21 Electronic spectrum of  $[\text{Co}(\text{H}_2\text{O})_6]^{2+}$

The spectrum of  $[\text{Co}(\text{H}_2\text{O})_6]^{2+}$  is less easy to interpret. It shows a weak but well resolved absorption band at about  $8000\text{ cm}^{-1}$ , and a multiple absorption band comprising three overlapping peaks at about  $20\,000\text{ cm}^{-1}$ . The lowest energy band  $v_1$  at  $8000\text{ cm}^{-1}$  is assigned to the  ${}^4T_{1g} \rightarrow {}^4T_{2g}$  transition. The multiple band has three peaks at about  $16\,000$ ,  $19\,400$  and  $21\,600\text{ cm}^{-1}$ . Two of these are the  ${}^4T_{1g} \rightarrow {}^4A_{2g}$  and  ${}^4T_{1g} \rightarrow {}^4T_{1g}(P)$  transitions, and since the peaks are close together this indicates that this complex is close to the cross-over point between the  ${}^4A_{2g}$  and  ${}^4T_{1g}$  states on the energy diagram. This means that the assignments are only tentative but the following assignments are commonly accepted

$$v_2 ({}^4T_{1g} \rightarrow {}^4A_{2g}) \quad 16\,000\text{ cm}^{-1}$$

and

$$v_3 ({}^4T_{1g} \rightarrow {}^4T_{1g}(P)) \quad 19\,400\text{ cm}^{-1}$$

The extra band is attributed either to spin orbit coupling effects or to transitions to doublet states

Tetrahedral complexes of  $\text{Co}^{2+}$  such as  $[\text{CoCl}_4]^{2-}$  are intensely blue in colour with an intensity  $\epsilon$  of about  $600 \text{ l mol}^{-1} \text{ cm}^{-1}$  compared with the pale pink colour of octahedral complexes with an intensity  $\epsilon$  of only about  $6 \text{ l mol}^{-1} \text{ cm}^{-1}$ .  $\text{Co}^{2+}$  has a  $d^7$  electronic configuration, and in  $[\text{CoCl}_4]^{2-}$  the electrons are arranged  $(e_g)^4(t_{2g})^3$ . This is similar to the  $\text{Cr}^{3+}$  ( $d^3$ ) octahedral case since only two electrons can be promoted. There are three possible transitions:  ${}^4A_2 \rightarrow {}^4T_2(F)$ ,  ${}^4A_2(F) \rightarrow {}^4T_1(F)$  and  ${}^4A_2(F) \rightarrow {}^4T_{1g}(P)$ . Only one band appears in the visible region at  $15000 \text{ cm}^{-1}$  (Figure 32.22). This band is assigned  $\nu_3$ . There are two bands in the infrared region at  $5800 \text{ cm}^{-1}$  assigned  $\nu_2$  and the lowest energy transition (assigned  $\nu_1$ ) is expected at  $3300 \text{ cm}^{-1}$ .

${}^4A_2 \rightarrow {}^4T_1(P)$	$\nu_3$	$15000 \text{ cm}^{-1}$ in the visible region
${}^4A_2 \rightarrow {}^4T_1(F)$	$\nu_2$	$5800 \text{ cm}^{-1}$ in the visible region
${}^4A_2 \rightarrow {}^4T_2$	$\nu_1$	$(3300 \text{ cm}^{-1})$ in the infrared region)




Figure 32.22 Electronic spectrum of  $[\text{CoCl}_4]^{2-}$ .

### SPECTRA OF $d^5$ IONS

The  $d^5$  configuration occurs with  $\text{Mn(II)}$  and  $\text{Fe(III)}$ . In high-spin octahedral complexes formed with weak ligands, for example  $[\text{Mn}^{\text{II}}\text{F}_6]^{4-}$ ,  $[\text{Mn}^{\text{II}}(\text{H}_2\text{O})_6]^{2+}$  and  $[\text{Fe}^{\text{III}}\text{F}_6]^{3-}$ , there are five unpaired electrons with parallel spins. Any electronic transition within the  $d$  level must involve a reversal of spins, and in common with all other 'spin forbidden' transitions any absorption bands will be extremely weak. This accounts for the very pale pink colour of most  $\text{Mn(II)}$  salts, and the pale violet colour of iron(III) alum. The ground state term is  ${}^6S$ . None of the 11 excited states shown in Table 32.3 can be attained without reversing the spin of an electron, and hence the probability of such transitions is extremely low. Of the 11 excited

states, the four quartets  ${}^4G$ ,  ${}^4F$ ,  ${}^4D$  and  ${}^4P$  involve the reversal of only one spin. The other seven states are doublets, are doubly spin forbidden, and are unlikely to be observed. In an octahedral field these four split into ten states, and hence up to ten extremely weak absorption bands may be observed. The spectrum of  $[\text{Mn}(\text{H}_2\text{O})_6]^{2+}$  is shown in Figure 32.23. Several features of this spectrum are unusual:

1. The bands are extremely weak. The molar absorption coefficient  $\epsilon$  is about  $0.02\text{--}0.03 \text{ l mol}^{-1} \text{ cm}^{-1}$ , compared with  $5\text{--}10 \text{ l mol}^{-1} \text{ cm}^{-1}$  for spin allowed transitions.
2. Some of the bands are sharp and others are broad. Spin allowed bands are invariably broad.




Figure 32.23 Electronic spectrum of  $[\text{Mn}(\text{H}_2\text{O})_6]^{2+}$

The Orgel energy level diagram for octahedral  $\text{Mn}^{2+}$  is shown in Figure 32.24. Only the quartet terms have been included because transitions to the others are doubly spin forbidden.

Note that the ground state  ${}^6S$  is not split, and transforms to the  ${}^6A_{1g}$  state which is drawn along the horizontal axis. Note also that the  ${}^4E_g(G)$ ,  ${}^4A_{1g}$ ,  ${}^4E_g(D)$ , and  ${}^4A_{2g}(F)$  terms are also horizontal lines on the diagram, so their energies are independent of the crystal field. The ligands in a complex vibrate about mean positions, so the crystal field strength  $10D_q$  varies about a mean value. Thus the energy for a particular transition varies about a mean value, and hence the absorption peaks are broad. The degree of broadening of the peaks is related to the slope of the lines on the Orgel diagram. Since the slope of the ground state term  ${}^6A_{1g}$  is zero, and the slopes of the  ${}^4E_g(G)$ ,  ${}^4A_{1g}$ ,  ${}^4E_g(D)$  and  ${}^4A_{2g}(F)$  terms are also zero, transitions from the ground state to these four states should give rise to sharp peaks. By the same reasoning, transitions to states which slope appreciably such as  ${}^4T_{1g}(G)$  and  ${}^4T_{2g}(G)$  give broader bands.

The bands are assigned as follows:




Figure 32.24 Orgel energy level diagram for  $\text{Mn}^{2+}$  ( $d^5$ ) octahedral.

${}^6A_{1g} \rightarrow {}^4T_{1g}$	18 900 $\text{cm}^{-1}$
${}^6A_{1g} \rightarrow {}^4T_{2g}(G)$	23 100 $\text{cm}^{-1}$
${}^6A_{1g} \rightarrow {}^4E_g$	} 24 970 and 25 300 $\text{cm}^{-1}$
${}^6A_{1g} \rightarrow {}^4A_{1g}$	
${}^6A_{1g} \rightarrow {}^4T_{2g}(D)$	28 000 $\text{cm}^{-1}$
${}^6A_{1g} \rightarrow {}^4E_g(D)$	29 700 $\text{cm}^{-1}$

The same diagram applies to tetrahedral  $d^5$  complexes if the g subscripts are omitted.

## TANABE-SUGANO DIAGRAMS

The simple Orgel energy level diagrams are useful for interpreting spectra, but they suffer from two important limitations:

1. They treat only the high-spin (weak field) case.
2. They are only useful for spin allowed transitions when the number of observed peaks is greater than or equal to the number of empirical parameters: crystal field splitting  $D_q$ , modified Racah parameter  $B'$  and bending constant  $x$ .






Figure 32 25 Tanabe-Sugano diagram for  $d^2$  case, e.g.  $V^{3+}$

Though it is possible to add low spin states to an Orgel diagram Tanabe-Sugano diagrams are commonly used instead for the interpretation of spectra including both weak and strong fields. Tanabe-Sugano diagrams are similar to Orgel diagrams in that they show how the energy levels change with  $D_q$ , but they differ in several ways

- 1 The ground state is always taken as the abscissa (horizontal axis) and provides a constant reference point. The other energy states are plotted relative to this.
- 2 Low-spin terms, i.e. states where the spin multiplicity is lower than the ground state, are included.
- 3 In order to make the diagrams general for different metal ions with the same electronic configuration, and to allow for different ligands both of which affect  $D_q$  and  $B$  (or  $B'$ ), the axes are plotted in units of energy/ $B$  and  $D_q/B$ .

A different diagram is required for each electronic arrangement. Only two examples are shown here. The T-S diagram for a  $d^2$  case such as  $V^{3+}$  is shown in Figure 32 25. Note that in this case there is no fundamental difference between strong and weak fields.

The Tanabe-Sugano diagram for a  $d^6$  ion such as  $Co^{3+}$  is shown in Figure 32 26. This is a simplified version and only the singlet and quintet




Figure 32.26 Tanabe–Sugano diagram for  $d^6$  case, e.g.  $Co^{3+}$

terms are shown. There is a discontinuity at  $10Dq/B = 20$ , and this is shown by a vertical line. At this point spin pairing of electrons occurs. To the left of this line we have high-spin complexes (weak ligand field), and to the right we have low-spin complexes (strong ligand field). The free ion ground state is  $^5D$ . This is split by an octahedral field into the  $^5T_{2g}$  ground state and the  $^5E_g$  excited state. The singlet  $^1I$  state in the free ion is of high energy. This is split by the octahedral field into five different states, of which the  $^1A_{1g}$  is important. This state is greatly stabilized by the ligand and drops rapidly in energy as the ligand field strength increases. At the point where  $10Dq/B = 20$  the  $^1A_{1g}$  line crosses the horizontal line for the  $^5T_{2g}$  state (which is the ground state). At still higher field strengths the  $^1A_{1g}$  state is the lowest in energy, and becomes the ground state. Since the ground state is taken as the horizontal axis, the right hand part of the diagram must be redrawn.

Since the fluoride ion is a weak field ligand, the complex  $[CoF_6]^{3-}$  is high spin. The complex is blue in colour, and a single peak occurs at  $13000\text{ cm}^{-1}$ . This is explained by the transition  $^5T_{2g} \rightarrow ^5E_g$  shown as an

arrow in the left hand part of the diagram. The spectrum of a low-spin complex such as  $[\text{Co}(\text{ethylenediamine})_3]^{3+}$  should show the transitions  ${}^1A_{1g} \rightarrow {}^1T_{1g}$  and  ${}^1A_{1g} \rightarrow {}^1T_{2g}$  (shown as two arrows in the right hand part of the diagram)

## FURTHER READING

- Emeléus, H J and Sharpe, A G (1973) *Modern Aspects of Inorganic Chemistry*, 4th ed (Complexes of Transition Metals Chapter 17, Electronic Spectra), Routledge and Kegan Paul, London
- Figgis, B N (1966) *Introduction to Ligand Fields*, John Wiley, London (UV spectra of hydrated transition metal ions Chapter 7 gives an account of the splitting of spectroscopic terms Suitable for advanced readers)
- Gerloch, M (1986) *Orbitals, Terms and States*, John Wiley, Chichester (A more basic approach)
- Herzberg, G (1966) *Molecular Spectra and Molecular Structure*, Vol III, Electronic spectra and electronic structure of polyatomic molecules, Van Nostrand Reinhold, London
- Hyde, K E (1975) Methods for obtaining Russell-Saunders term symbols from electronic configurations *J Chem Ed*, **52**, 87-89
- Jotham, R W (1975) Why do energy levels repel one another? *J Chem Ed*, **52**, 377-378
- Lever, A B P (1964) *Inorganic Electronic Spectroscopy*, Elsevier, Amsterdam (Up-to date and comprehensive, and a good source of spectral data)
- McClure, D S and Stephens, P J (1971) *Electronic Spectra of Coordination Compounds in Coordination Chemistry* (ed Martell, A E), Van Nostrand Reinhold
- Nicholls, D (1974) *Complexes and First Row Transition Elements*, Macmillan London (Chapter 6 gives a good and readable explanation of electronic spectra of transition-metal complexes)
- Orgel, L E (1955) *J Chem Phys*, **23**, 1004 (Original paper using Orgel diagrams)
- Richards, W G and Scott, P R (1976) *Structure and Spectra of Atoms* John Wiley, London (A more basic approach, particularly Chapters 3 and 4)
- Sutton, D (1968) *Electronic Spectra of Transition Metal Complexes*, McGraw Hill London
- Tanabe, Y and Sugano, S (1954) Semiquantitative energy-level diagrams for octahedral symmetry, *J Phys Soc Japan*, **9**, 753-766 (Original paper on Tanabe-Sugano diagrams)
- Urch, D S (1970) *Orbitals and Symmetry*, Penguin, Harmondsworth
- Vicente, J (1983) A simple method for obtaining Russell-Saunders term symbols *J Chem Ed*, **60**, 560-561

An alternative approach to spectra is through Group Theory. This is a mathematical approach, which some may find particularly difficult

- Atkins, P.W., Child, M S and Phillips, C S G (1970) *Tables for Group Theory*, Oxford University Press, London
- Ballhausen, C J (1962) *Introduction to Ligand Field Theory*, McGraw Hill
- Cotton, F A (1970) *Chemical Applications of Group Theory*, 2nd ed, Interscience, New York and Wiley, Chichester (An excellent introductory text)
- Davidson, G (1971) *Introductory Group Theory for Chemists*, Applied Science Publishers Ltd, Barking (An excellent and readable introductory text)

## PROBLEMS

1. Electronic transitions of the  $d-d$  type displayed in spectra of octahedral transition metal complexes should be forbidden by the Laporte selection rule. Why are moderately strong spectra actually observed?
2. Why do tetrahedral complexes of an element give much more intense  $d-d$  spectra than its octahedral complexes?

# Abundance of the elements in the earth's crust

APPENDIX

A

Name	Symbol	Abundance*	Name	Symbol	Abundance
1 Oxygen	O	455 000	40 Samarium	Sm	7.0
2 Silicon	Si	272 000	41 Gadolinium	Gd	6.1
3 Aluminium	Al	83 000	42 Dysprosium	Dy	4.5
4 Iron	Fe	62 000	43 Erbium	Er	3.5
5 Calcium	Ca	46 600	44 Ytterbium	Yb	3.1
6 Magnesium	Mg	27 640	45 Hafnium	Hf	2.8
7 Sodium	Na	22 700	46 Caesium	Cs	2.6
8 Potassium	K	18 400	47 Bromine	Br	2.5
9 Titanium	Ti	6 320	48 Uranium	U	2.3
10 Hydrogen	H	1 520	49 = Tin	Sn	2.1
11 Phosphorus	P	1 120	49 = Europium	Eu	2.1
12 Manganese	Mn	1 060	51 Beryllium	Be	2.0
13 Fluorine	F	544	52 Arsenic	As	1.8
14 Barium	Ba	390	53 Tantalum	Ta	1.7
15 Strontium	Sr	384	54 Germanium	Ge	1.5
16 Sulphur	S	340	55 Holmium	Ho	1.3
17 Carbon	C	180	56 = Molybdenum	Mo	1.2
18 Zirconium	Zr	162	56 = Tungsten	W	1.2
19 Vanadium	V	136	56 = Terbium	Tb	1.2
20 Chlorine	Cl	126	59 Lutetium	Lu	0.8
21 Chromium	Cr	122	60 Thallium	Tl	0.7
22 Nickel	Ni	99	61 Thulium	Tm	0.5
23 Rubidium	Rb	78	62 Iodine	I	0.46
24 Zinc	Zn	76	63 Indium	In	0.24
25 Copper	Cu	68	64 Antimony	Sb	0.20
26 Cerium	Ce	66	65 Cadmium	Cd	0.16
27 Neodymium	Nd	40	66 = Silver	Ag	0.08
28 Lanthanum	La	35	66 = Mercury	Hg	0.08
29 Yttrium	Y	31	68 Selenium	Se	0.05
30 Cobalt	Co	29	69 Palladium	Pd	0.015
31 Scandium	Sc	25	70 Platinum	Pt	0.01
32 Niobium	Nb	20	71 Bismuth	Bi	0.008
33 = Nitrogen	N	19	72 Osmium	Os	0.005
33 = Gallium	Ga	19	73 Gold	Au	0.004
35 = Lithium	Li	18	74 = Iridium	Ir	0.001
36 Lead	Pb	13	74 = Tellurium	Te	0.001
37 Praseodymium	Pr	9.1	76 Rhenium	Re	0.0007
38 Boron	B	9.0	77 = Ruthenium	Ru	0.0001
39 Thorium	Th	8.1	77 = Rhodium	Rh	0.0001

\* Units are ppm of the earth's crust, which is the same as g/tonne. Values mainly from *Geochemistry* by W.S. Fyfe, Oxford University Press, 1974, with some newer data.

APPENDIX

**B**

# Melting points of the elements

Group Period	1	2	Group										13	14	15	16	17	18
1																	H • -253	He • -269
2	Li • 1347	Be • (2500)											B ● 3650	C • -195.8	N • -183.1	O • -246	F • -188	Ne • -246
3	Na • 881	Mg • 1105											Al • 2467	Si ● 3280	P • 281	S • 445	Cl • -34	Ar • -186
4	K • 766	Ca • 1494	Sc • 2748	Ti • 3285	V • 3350	Cr • 2960	Mn • 2060	Fe • 2750	Co • 3100	Ni • 2920	Cu • 2570	Zn • 907	Ga • 2403	Ge • 2850	As • 615	Se • 685	Br • 60	Kr • -153.6
5	Rb • 688	Sr • 1381	Y • 3264	Zr • 4200	Nb • 4758	Mo • 4650	Tc • 4567	Ru • (4050)	Rh • 3760	Pd • 2940	Ag • 2155	Cd • 765	In • 2080	Sn • 2623	Sb • 1587	Te • 1087	I • 185	Xe • -108.1
6	Cs • 705	Ba • (1850)	La • 3420	Hf • 4450	Ta • 5534	W • 5500	Re • 5650	Os • (5025)	Ir • (4550)	Pt • 4170	Au • 2808	Hg • 357	Tl • 1457	Pb • 1751	Bi • 1564	Po • 962	At • -	Rn • -62
7	Fr	Ra • (1700)	Ac • 2470															

Temperatures are in degrees Celsius. Large circles indicate high values and small circles low values. Values given in parentheses are approximate. s indicates sublimation.

• <0  
 • 1-1500  
 • 1501-3000  
 • >3000

APPENDIX

C

## Boiling points of the elements



<div>Group Period</div>	1	2	Group										13	14	15	16	17	18
1	H • -259																H • -259	He • —
2	Li • 181	Be • 1287											B • 2180	C • 4100	N • -210	O • -229	F • -219	Ne • -249
3	Na • 98	Mg • 649											Al • 660	Si • 1420	P • 44	S • 114	Cl • -101	Ar • -189
4	K • 63	Ca • 839	Sc • 1539	Ti • 1667	V • 1915	Cr • 1900	Mn • 1244	Fe • 1535	Co • 1495	Ni • 1452	Cu • 1083	Zn • 420	Ga • 30	Ge • 945	As • 816	Se • 221	Br • -7	Kr • -157
5	Rb • 39	Sr • 768	Y • 1530	Zr • 1857	Nb • 2468	Mo • 2620	Tc • 2200	Ru • 2282	Rh • 1960	Pd • 1552	Ag • 961	Cd • 321	In • 157	Sn • 232	Sb • 631	Te • 452	I • 114	Xe • -112
6	Cs • 28.5	Ba • 727	La • 920	Hf • 2222	Ta • 2980	W • 3380	Re • 3180	Os • 3045	Ir • 2443	Pt • 1769	Au • 1064	Hg • -39	Tl • 303	Pb • 327	Bi • 271	Po • 254	At • 302 <sup>e</sup>	Rn • -71 <sup>e</sup>
7	Fr • 27 <sup>e</sup>	Ra • (700)	Ac • 817															

Temperatures are in degrees Celsius. Large circles indicate high values and small circles low values; e indicates estimated value. Values given in parentheses are approximate.

• <0  
 • 1-1500  
 • 1501-3000  
 • >3000

APPENDIX

**D**

## Densities of the solid and liquid elements

Group Period	1	2	Group										13	14	15	16	17	18	
1	H																	H	He
2	Li • 0.54	Be • 1.85											B • 2.35	C • 2.26	N •	O •		F •	Ne
3	Na • 0.97	Mg • 1.74	Group										Al • 2.70	Si • 2.34	P • 1.82	S • 2.1		Cl •	Ar
4	K • 0.86	Ca • 1.55	Sc • 3.0	Ti • 4.50	V • 6.11	Cr • 7.14	Mn • 7.43	Fe • 7.87	Co • 8.90	Ni • 8.91	Cu • 8.95	Zn • 7.14	Ga • 5.90	Ge • 5.32	As • 5.77	Se • 4.19		Br • 3.19	Kr
5	Rb • 1.53	Sr • 2.63	Y • 4.5	Zr • 6.51	Nb • 8.57	Mo • 10.28	Tc • 11.5	Ru • 12.41	Rh • 12.39	Pd • 11.99	Ag • 10.49	Cd • 8.65	In • 7.31	Sn • 7.27	Sb • 6.70	Te • 6.25		I • 4.94	Xe
6	Cs • 1.90	Ba • 3.62	La • 6.17	Hf • 13.28	Ta • 16.65	W • 19.3	Re • 21.0	Os • 22.57	Ir • 22.61	Pt • 21.41	Au • 19.32	Hg • 13.53	Tl • 11.85	Pb • 11.34	Bi • 9.81	Po • 9.14		At •	Rn
7	Fr • —	Ra • 5.5	Ac • —																—

Densities are given in  $\text{g cm}^{-3}$  (which equals  $10^{-3} \text{ kg m}^{-3}$ ). The value for carbon is the value for graphite. Large circles indicate large values and small circles small values.

## APPENDIX

## E

Electronic structures of  
the elements

Z	Element	Symbol	Structure
1	Hydrogen	H	$1s^1$
2	Helium	He	$1s^2$
3	Lithium	Li	$[\text{He}] 2s^1$
4	Beryllium	Be	$[\text{He}] 2s^2$
5	Boron	B	$[\text{He}] 2s^2 2p^1$
6	Carbon	C	$[\text{He}] 2s^2 2p^2$
7	Nitrogen	N	$[\text{He}] 2s^2 2p^3$
8	Oxygen	O	$[\text{He}] 2s^2 2p^4$
9	Fluorine	F	$[\text{He}] 2s^2 2p^5$
10	Neon	Ne	$[\text{He}] 2s^2 2p^6$
11	Sodium	Na	$[\text{Ne}] 3s^1$
12	Magnesium	Mg	$[\text{Ne}] 3s^2$
13	Aluminium	Al	$[\text{Ne}] 3s^2 3p^1$
14	Silicon	Si	$[\text{Ne}] 3s^2 3p^2$
15	Phosphorus	P	$[\text{Ne}] 3s^2 3p^3$
16	Sulphur	S	$[\text{Ne}] 3s^2 3p^4$
17	Chlorine	Cl	$[\text{Ne}] 3s^2 3p^5$
18	Argon	Ar	$[\text{Ne}] 3s^2 3p^6$
19	Potassium	K	$[\text{Ar}] 4s^1$
20	Calcium	Ca	$[\text{Ar}] 4s^2$
21	Scandium	Sc	$[\text{Ar}] 3d^1 4s^2$
22	Titanium	Ti	$[\text{Ar}] 3d^2 4s^2$
23	Vanadium	V	$[\text{Ar}] 3d^3 4s^2$
24	Chromium	Cr	$[\text{Ar}] 3d^5 4s^1$
25	Manganese	Mn	$[\text{Ar}] 3d^5 4s^2$
26	Iron	Fe	$[\text{Ar}] 3d^6 4s^2$
27	Cobalt	Co	$[\text{Ar}] 3d^7 4s^2$
28	Nickel	Ni	$[\text{Ar}] 3d^8 4s^2$
29	Copper	Cu	$[\text{Ar}] 3d^{10} 4s^1$
30	Zinc	Zn	$[\text{Ar}] 3d^{10} 4s^2$
31	Gallium	Ga	$[\text{Ar}] 3d^{10} 4s^2 4p^1$
32	Germanium	Ge	$[\text{Ar}] 3d^{10} 4s^2 4p^2$

Z	Element	Symbol	Structure
33	Arsenic	As	[Ar] $3d^{10} 4s^2 4p^3$
34	Selenium	Se	[Ar] $3d^{10} 4s^2 4p^4$
35	Bromine	Br	[Ar] $3d^{10} 4s^2 4p^5$
36	Krypton	Kr	[Ar] $3d^{10} 4s^2 4p^6$
37	Rubidium	Rb	[Kr] $5s^1$
38	Strontium	Sr	[Kr] $5s^2$
39	Yttrium	Y	[Kr] $4d^1 5s^2$
40	Zirconium	Zr	[Kr] $4d^2 5s^2$
41	Niobium	Nb	[Kr] $4d^4 5s^1$
42	Molybdenum	Mo	[Kr] $4d^5 5s^1$
43	Technetium	{ Tc	[Kr] $4d^5 5s^2$
		{ Tc	[Kr] $4d^6 5s^1$
44	Ruthenium	Ru	[Kr] $4d^7 5s^1$
45	Rhodium	Rh	[Kr] $4d^8 5s^1$
46	Palladium	Pd	[Kr] $4d^{10} 5s^0$
47	Silver	Ag	[Kr] $4d^{10} 5s^1$
48	Cadmium	Cd	[Kr] $4d^{10} 5s^2$
49	Indium	In	[Kr] $4d^{10} 5s^2 5p^1$
50	Tin	Sn	[Kr] $4d^{10} 5s^2 5p^2$
51	Antimony	Sb	[Kr] $4d^{10} 5s^2 5p^3$
52	Tellurium	Te	[Kr] $4d^{10} 5s^2 5p^4$
53	Iodine	I	[Kr] $4d^{10} 5s^2 5p^5$
54	Xenon	Xe	[Kr] $4d^{10} 5s^2 5p^6$
55	Caesium	Cs	[Xe] $6s^1$
56	Barium	Ba	[Xe] $6s^2$
57	Lanthanum	La	[Xe] $5d^1 6s^2$
58	Cerium	Ce	[Xe] $4f^1 5d^1 6s^2$
59	Praseodymium	Pr	[Xe] $4f^3 5d^0 6s^2$
60	Neodymium	Nd	[Xe] $4f^4 5d^0 6s^2$
61	Promethium	Pm	[Xe] $4f^5 5d^0 6s^2$
62	Samarium	Sm	[Xe] $4f^6 5d^0 6s^2$
63	Europium	Eu	[Xe] $4f^7 5d^0 6s^2$
64	Gadolinium	Gd	[Xe] $4f^7 5d^1 6s^2$
65	Terbium	Tb	[Xe] $4f^9 5d^0 6s^2$
66	Dysprosium	Dy	[Xe] $4f^{10} 5d^0 6s^2$
67	Holmium	Ho	[Xe] $4f^{11} 5d^0 6s^2$
68	Erbium	Er	[Xe] $4f^{12} 5d^0 6s^2$
69	Thulium	Tm	[Xe] $4f^{13} 5d^0 6s^2$
70	Ytterbium	Yb	[Xe] $4f^{14} 5d^0 6s^2$
71	Lutetium	Lu	[Xe] $4f^{14} 5d^1 6s^2$
72	Hafnium	Hf	[Xe] $4f^{14} 5d^2 6s^2$
73	Tantalum	Ta	[Xe] $4f^{14} 5d^3 6s^2$
74	Tungsten	W	[Xe] $4f^{14} 5d^4 6s^2$
75	Rhenium	Re	[Xe] $4f^{14} 5d^5 6s^2$
76	Osmium	Os	[Xe] $4f^{14} 5d^6 6s^2$
77	Iridium	Ir	[Xe] $4f^{14} 5d^7 6s^2$
78	Platinum	Pt	[Xe] $4f^{14} 5d^9 6s^1$
79	Gold	Au	[Xe] $4f^{14} 5d^{10} 6s^1$
80	Mercury	Hg	[Xe] $4f^{14} 5d^{10} 6s^2$

Z	Element	Symbol	Structure
81	Thallium	Tl	[Xe] $4f^{14} 5d^{10} 6s^2 6p^1$
82	Lead	Pb	[Xe] $4f^{14} 5d^{10} 6s^2 6p^2$
83	Bismuth	Bi	[Xe] $4f^{14} 5d^{10} 6s^2 6p^3$
84	Polonium	Po	[Xe] $4f^{14} 5d^{10} 6s^2 6p^4$
85	Astatine	At	[Xe] $4f^{14} 5d^{10} 6s^2 6p^5$
86	Radon	Rn	[Xe] $4f^{14} 5d^{10} 6s^2 6p^6$
87	Francium	Fr	[Rn] $7s^1$
88	Radium	Ra	[Rn] $7s^2$
89	Actinium	Ac	[Rn] $6d^1 7s^2$
90	Thorium	Th	[Rn] $6d^2 7s^2$
91	Protactinium	Pa	[Rn] $5f^2 6d^1 7s^2$
92	Uranium	U	[Rn] $5f^3 6d^1 7s^2$
93	Neptunium	Np	[Rn] $5f^4 6d^1 7s^2$
94	Plutonium	Pu	[Rn] $5f^6 6d^0 7s^2$
95	Americium	Am	[Rn] $5f^7 6d^0 7s^2$
96	Curium	Cm	[Rn] $5f^7 6d^1 7s^2$
97	Berkelium	Bk	[Rn] $5f^7 6d^1 7s^2$
		Bk	[Rn] $5f^8 6d^0 7s^2$
98	Californium	Cf	[Rn] $5f^{10} 6d^0 7s^2$
99	Einsteinium	Es	[Rn] $5f^{11} 6d^0 7s^2$
100	Fermium	Fm	[Rn] $5f^{12} 6d^0 7s^2$
101	Mendelevium	Md	[Rn] $5f^{13} 6d^0 7s^2$
102	Nobelium	No	[Rn] $5f^{14} 6d^0 7s^2$
103	Lawrencium	Lr	[Rn] $5f^{14} 6d^1 7s^2$
104	Rutherfordium	Rf	[Rn] $5f^{14} 6d^2 7s^2$
105	Hahnium	Ha	[Rn] $5f^{14} 6d^3 7s^2$

# Some average single bond energies ( $\text{kJ mol}^{-1}$ )

APPENDIX

F

	I	Br	Cl	F	S	O	P	N	Si	C	H
H	297	368	431	565	339	464	318	389	293	414	435
C	238	276	330	439	259	351	263	293	289	347	
Si	213	289	360	539	226	368	213 <sup>c</sup>	–	176		
N	–	243	201	272	–	201	209 <sup>c</sup>	159			
P	213	272	330	489	230 <sup>c</sup>	351 <sup>c</sup>	213				
O	201	–	205	184	–	138					
S	–	213	251	284	213						
F	–	255	184	159							
Cl	209	217	243								
Br	180	193									
I	151										

<sup>c</sup>Indicates value estimated using electronegativity difference.

## Some double and triple bond energies ( $\text{kJ mol}^{-1}$ )

$\text{C}=\text{C}$	611	$\text{C}\equiv\text{C}$	836
$\text{C}=\text{N}$	615	$\text{C}\equiv\text{N}$	891
$\text{C}=\text{O}$	740	$\text{C}\equiv\text{O}$	1071
$\text{N}=\text{N}$	418	$\text{N}\equiv\text{N}$	945

## APPENDIX

## G

## Solubilities of main group compounds in water

	F	Cl	Br	I	OH <sup>-</sup>	NO <sub>3</sub>	CO <sub>3</sub>	SO <sub>4</sub> <sup>2-</sup>	HCO <sub>3</sub> <sup>-</sup>
NH <sub>4</sub> <sup>+</sup>	vs	37	75	172		192	12	76	
Li <sup>+</sup>	0.27 <sup>a</sup>	83	177	165	12.8	70	1.33	35	
Na <sup>+</sup>	4.0	36	91	179	109	87	21	19.4	9.6
K <sup>+</sup>	95	34.7	67	144	112	31.6	112	11.1	22.4
Rb <sup>+</sup>	131	91	110	152	177	53	450	48	
Cs <sup>+</sup>	370	186	108	79	330	23	vs	179	
Ba <sup>2+</sup>	vs	vs	s	dec	ss	107		39	
Mg <sup>2+</sup>	0.008	54.2	102	148	0.0009	70	ss	33	
Ca <sup>2+</sup>	0.0016	74.5	147	209	0.156	129	ss	0.21	
Sr <sup>2+</sup>	0.012	53.8	100	178	0.80	71	ss	0.013	
Bi <sup>3+</sup>	0.12	36	104	205	3.9	8.7	ss	0.00024	
Al <sup>3+</sup>	0.55	70 dec	dec	dec	ss	63		38	
Cr <sup>3+</sup>	0.002	vs	s	dec	ss			vs	
In <sup>3+</sup>	0.04	vs	vs	dec	ss				
Tl <sup>+</sup>	78.6 <sup>b</sup>	0.33	0.05	0.0006	25.9	9.55	4.0 <sup>l</sup>	s	
Tl <sup>3+</sup>	dec	vs	s	s		s		4.87	
Ga <sup>III</sup>	s	dec	dec	s					
Ge <sup>IV</sup>	dec	dec	dec	dec					
Sn <sup>II</sup>	s	270 dec <sup>l</sup>	s	0.98	ss	dec		33 <sup>l</sup>	
Sn <sup>IV</sup>	vs	dec	dec	dec					
Pb <sup>II</sup>	0.064	0.99	0.844	0.063	0.016	55	0.00011	ss	
Pb <sup>IV</sup>		dec							
As <sup>III</sup>	dec	dec	dec	6.0 <sup>l</sup>					
As <sup>V</sup>									
Sb <sup>III</sup>	dec	dec	dec	dec		dec		ss	
Sb <sup>V</sup>		dec							
Bi <sup>III</sup>	ss	dec	dec	ss	0.00014	dec		dec	

Solubilities in grams of solute per 100 grams of water at 20°C unless otherwise indicated: vs = very soluble, s = soluble, ss = slightly soluble, dec = decomposes, a = at 0°C, b = at 15°C, c = at 18°C, d = at 25°C.



# Atomic weights based on $^{12}\text{C} = 12.000$

APPENDIX

H

Element	Atomic weight	Element	Atomic weight
Actinium	227	Holmium	164.93
Aluminium	26.982	Hydrogen	1.00797
Americium	(243)	Indium	114.82
Antimony	121.75	Iodine	126.904
Argon	39.948	Iridium	192.2
Arsenic	74.922	Iron	55.847
Astatine	(210)	Krypton	83.80
Barium	137.34	Lanthanum	138.91
Berkelium	(249)	Lead	207.19
Beryllium	9.102	Lithium	6.939
Bismuth	208.98	Lutetium	174.97
Boron	10.811	Magnesium	24.312
Bromine	79.909	Manganese	54.938
Cadmium	112.40	Mendelevium	(256)
Caesium	132.905	Mercury	200.59
Calcium	40.08	Molybdenum	95.94
Californium	(251)	Neodymium	144.24
Carbon	12.01115	Neon	20.183
Cerium	140.12	Neptunium	(237)
Chlorine	35.453	Nickel	58.71
Chromium	51.996	Niobium	92.91
Cobalt	58.933	Nitrogen	14.0067
Copper	63.54	Nobelium	(254)
Curium	(247)	Osmium	190.2
Dysprosium	162.50	Oxygen	15.9994
Einsteinium	(254)	Palladium	106.4
Erbium	167.26	Phosphorus	30.9738
Europium	151.96	Platinum	195.09
Fermium	(253)	Plutonium	(242)
Fluorine	18.993	Polonium	(210)
Francium	(223)	Potassium	39.102
Gadolinium	157.25	Praseodymium	140.91
Gallium	69.72	Promethium	(147)
Germanium	72.59	Protactinium	(231)
Gold	196.967	Radium	(226)
Hafnium	178.49	Radon	(222)
Helium	4.003	Rhenium	186.22

Element	Atomic weight	Element	Atomic weight
Rhodium	102.91	Terbium	153.92
Rubidium	85.47	Thallium	204.37
Ruthenium	101.07	Thorium	232.04
Samarium	150.35	Thulium	168.93
Scandium	44.96	Tin	118.69
Selenium	78.96	Titanium	47.90
Silicon	28.086	Tungsten	183.85
Silver	107.870	Uranium	238.03
Sodium	22.9898	Vanadium	50.942
Strontium	87.62	Xenon	131.30
Sulphur	32.064	Ytterbium	173.04
Tantalum	180.95	Yttrium	88.91
Technetium	(99)	Zinc	65.37
Tellurium	127.60	Zirconium	91.22

Values in parentheses are for the most stable isotope

# Values of some fundamental physical constants

APPENDIX

## I

Planck's constant  $h = 6.6262 \times 10^{-34} \text{ J s}$

mass of electron  $m = 9.1091 \times 10^{-31} \text{ kg}$

charge on electron  $e = 1.60210 \times 10^{-19} \text{ C}$

permittivity of a vacuum  $\epsilon_0 = 8.854\,185 \times 10^{-12} \text{ kg}^{-1} \text{ m}^{-3} \text{ A}^2$

permeability of a vacuum  $\mu_0 = 4\pi \times 10^{-7} \text{ kg m s}^{-2} \text{ A}^{-2}$

velocity of light in a vacuum  $c = 2.997\,925 \times 10^8 \text{ m s}^{-1}$

Avogadro constant  $N^0 = 6.022\,045 \times 10^{23} \text{ mol}^{-1}$

Boltzmann constant  $k = 1.3805 \times 10^{-23} \text{ J K}^{-1}$

Bohr magneton  $\mu_B = 9.2732 \times 10^{-24} \text{ A m}^2 = \text{J T}^{-1}$

magnetic moment and dipole moment  $\mu$  units are  $\text{A m}^2 = \text{J T}^{-1}$

## APPENDIX

## J

# Electrical resistivity of the elements at the stated temperature

Element	Symbol	Temp (°C)	Resistivity (μohm cm)	Element	Symbol	Temp (°C)	Resistivity (μohm cm)
Silver	Ag	20	1.59	Vanadium	V	20	25
Copper	Cu	20	1.673	Gallium*	Ga	20	27
Gold	Au	20	2.35	Ytterbium	Yb	25	29
Aluminium	Al	20	2.655	Uranium	U	20	30
Calcium	Ca	20	3.5	Arsenic α	As	20	33.3
Beryllium	Be	20	4.0	Hafnium	Hf	25	35.1
Sodium	Na	0	4.2	Zirconium	Zr	20	40
Magnesium	Mg	20	4.46	Antimony α	Sb	20	41.7
Rhodium	Rh	20	4.51	Titanium	Ti	20	42
Molybdenum	Mo	0	5.2	Barium	Ba	20	50
Iridium	Ir	20	5.3	Yttrium	Y	25	57
Tungsten	W	27	5.65	Dysprosium	Dy	25	57
Lanthanum	La	25	5.7	Scandium	Sc	22	61
Zinc	Zn	20	5.92	Neodymium	Nd	25	64
Potassium	K	0	6.15	Praseodymium	Pr	25	68
Cobalt	Co	20	6.24	Cerium	Ce	25	75
Cadmium	Cd	0	6.83	Thulium	Tm	25	79
Nickel	Ni	20	6.84	Lutetium	Lu	25	79
Ruthenium	Ru	0	7.6	Holmium	Ho	25	87
Indium	In	20	8.37	Samarium	Sm	25	88
Lithium	Li	20	8.55	Europium	Eu	25	90
Osmium	Os	20	9.5	Mercury	Hg	20	95.8
Iron	Fe	20	9.71	Erbium	Er	25	107
Platinum	Pt	20	10.6	Bismuth α	Bi	20	120
Palladium	Pd	20	10.8	Gadolinium	Gd	25	140.5
Tin β	Sn	0	11	Plutonium	Pu	107	141.4
Tantalum	Ta	25	12.45	Manganese α	Mn	23	185
Rubidium	Rb	20	12.5	Ytterbium	Yb	25	$4.5 \times 10^5$
Niobium	Nb	0	12.5	Germanium	Ge	22	$4.7 \times 10^7$
Chromium	Cr	0	12.9	Silicon	Si	20	$4.8 \times 10^7$
Thorium	Th	0	13	Boron	B	20	$6.7 \times 10^{11}$
Thallium	Tl	0	18	Iodine	I	20	$1.3 \times 10^{14}$
Rhenium	Re	20	19.3	Selenium	Se	20	$1.2 \times 10^8$
Cesium	Cs	20	20	Phosphorus #	P	11	$1 \times 10^{12}$
Lead	Pb	20	20.648	Carbon	C	20	$\sim 1 \times 10^{20}$
Strontium	Sr	20	21	Sulphur	S	20	$2 \times 10^8$

Resistivity of Ge is  $8.2-17.5$  or  $55-3$  μohm cm depending on direction

# White phosphorus

# Top fifty chemicals in the USA, 1994

APPENDIX

K

Position	Chemical	Billion lb/year	Million tons/year
1	Sulphuric acid	89.20	44.6
2	Nitrogen	67.54	33.8
3	Oxygen	49.67	24.8
4	Ethylene	48.52	24.3
5	Lime	38.35	19.2
6	Ammonia	37.93	19.0
7	Propylene	28.84	14.4
8	Sodium hydroxide	25.83	12.9
9	Phosphoric acid	25.26	12.6
10	Chlorine	24.20	12.1
11	Sodium carbonate	20.56	10.3
12	Ethylene dichloride	18.70	9.4
13	Nitric acid	18.65	9.3
14	Ammonium nitrate	17.61	8.8
15	Urea	16.13	8.1
16	Vinyl chloride	14.81	7.4
17	Benzene	14.66	7.3
18	Methyl <i>t</i> -butyl ether	13.67	6.8
19	Ethyl benzene	11.87	5.9
20	Styrene	11.27	5.6
21	Carbon dioxide	10.99	5.5
22	Methanol	10.81	5.4
23	Xylene	9.06	4.5
24	Terephthalic acid	8.64	4.3
25	Formaldehyde	7.94	4.0
26	Ethylene oxide	6.78	3.4
27	Toluene	6.75	3.4
28	Hydrochloric acid	6.71	3.4
29	<i>p</i> -Xylene	6.23	3.1
30	Ethylene glycol	5.55	2.8
31	Cumene	5.16	2.6
32	Ammonium sulphate	5.08	2.5
34	Phenol	4.05	2.0
34	Acetic acid	3.82	1.9
35	Propylene oxide	3.70	1.9
36	Butadiene	3.40	1.7
37	Carbon black	3.31	1.7

Position	Chemical	Billion lb/year	Million tons/year
38	Potash	3.14	1.6
39	Acrylonitrile	3.08	1.5
40	Vinyl acetate	3.02	1.5
41	Acetone	2.77	1.4
42	Titanium dioxide	2.74	1.4
43	Aluminium sulphate	2.30	1.2
44	Sodium silicate	2.13	1.1
45	Cyclohexane	2.11	1.1
46	Adipic acid	1.80	0.9
47	Caprolactam	1.68	0.8
48	Bisphenol A	1.48	0.7
49	n Butyl alcohol	1.45	0.7
50	Isopropyl alcohol	1.39	0.7

Inorganic chemicals are shown in bold type. Data are reproduced from *Chemical & Engineering News*, page 39, 26 June issue, 1995. These figures are updated annually and published under *Facts and Figures* in June/July.

# Inorganic chemicals manufactured in large tonnages (worldwide)

APPENDIX

L

Chemical	Million tonnes/year	Chemical	Million tonnes/year
Cement	1396	(Polystyrene)	9.9
Cast iron and steel	717	Bentonite	9.2
Coke	390	Mn	9
NaCl	183.5	Talc	8.4
H <sub>2</sub> SO <sub>4</sub>	145.5	Soap	7.4
CaO	127.9	Zn	7.3
NH <sub>3</sub>	110	Pb	5.3
O <sub>2</sub>	100	CaC <sub>2</sub>	4.9
CaSO <sub>4</sub>	88.2	BaSO <sub>4</sub>	4.9
N <sub>2</sub>	60	Carbon black	4.5
S	57	Na <sub>2</sub> SO <sub>4</sub>	4.3
Cl <sub>2</sub>	35.3	Fuller's earth	4.2
NaOH	38.7	TiO <sub>2</sub>	4.1
CO(NH <sub>2</sub> ) <sub>2</sub>	35	Al <sub>2</sub> (SO <sub>4</sub> ) <sub>3</sub>	3.7
Phosphates	34	CaF <sub>2</sub>	3.6
(based on P <sub>2</sub> O <sub>5</sub> content)		Ferrosilicon	3.5
Glass	33.4	Ferromanganese	3.4
Na <sub>2</sub> CO <sub>3</sub>	31.5	Cr	3.3
HNO <sub>3</sub>	24.7	Ferrochrome	3.1
(Polythene)	24.6	Asbestos	2.8
Potassium salts	24.5	Soluble silicates	2.6
(based on K <sub>2</sub> O content)		(in terms of SiO <sub>2</sub> content)	
Al	24.4	Explosives	2.5
Kaolin	22.5	Na <sub>2</sub> B <sub>4</sub> O <sub>7</sub>	2.2
(Polyvinyl chloride)	14.9	Kieselguhr	2
Chalk	14.2	HF	1.5
Tin plate	14	CaNCN	1
HCl	12.3	P	1
(Polypropylene)	12	H <sub>2</sub> O <sub>2</sub>	1
Cu	11	Si	>1
MgCO <sub>3</sub>	10.8	Na <sub>2</sub> SO <sub>3</sub>	>1
CO <sub>2</sub>	10		

Organic compounds in parentheses.

Chemical	Tonnes/year	Chemical	Tonnes/year
NaOCl	950 000	AlCl <sub>3</sub>	50 000
Natural graphite	930 000	Lanthanides	47 900
Zircon/baddeleyite	918 000	(based on Ln <sub>2</sub> O <sub>3</sub> content)	
NaHCO <sub>3</sub>	900 000	As <sub>2</sub> O <sub>3</sub>	47 000
Active charcoal	864 200	Organotin	40 000
Ni	850 000	W	39 000
Ar	700 000	U	34 400
PbO/Pb ('black oxide')	700 000	Co	30 100
Sodium peroxoborate	700 000	V	28 400
Ferronickel	596 000	Cd	20 700
Vermiculite	500 900	PCl <sub>4</sub>	20 000
Br <sub>2</sub>	370 000	N <sub>2</sub> H <sub>4</sub>	20 000
ZnO	366 500	He	18 800
Mg	303 000	Pb <sub>3</sub> O <sub>4</sub>	18 000
SiC	300 000	I <sub>2</sub>	17 500
Silicones	300 000	Nb	15 200
HCN	300 000	Ag	13 818
Strontium compounds	283 100	Lithium salts	8 900
CS <sub>2</sub>	280 400	(based on Li content)	
PbO (litharge)	250 000	La	5 000
PCl <sub>3</sub>	250 000	Bi	3 600
P <sub>4</sub> S <sub>10</sub>	250 000	Hg	3 200
Mica	214 000	BF <sub>3</sub>	3 000
H <sub>3</sub> BO <sub>3</sub>	211 000	Au	2 134
Sn	177 000	Se	1 670
Ca(OCl) <sub>2</sub>	150 000	Ca	1 000
PbEt <sub>4</sub>	150 000	n-Butyl lithium	1 000
Mo	129 000	Ta	600
CuSO <sub>4</sub>	123 956	Th compounds	500
NaCN	120 000	Boron	300
Garnet	106 099	Pt group metals	281
Freons	100 000	Te	152
Sb	84 000	In	145
Na	80 000	Ge	50
Na <sub>2</sub> Cr <sub>2</sub> O <sub>7</sub>	69 300	Re	32
Li <sub>2</sub> CO <sub>3</sub>	50 000	Ga	28
Ti	50 000	Diamonds	19 68
		Ti	14 5



# Minerals used in large amounts

APPENDIX

M

Mineral	Million tonnes/year	Uses
Coal	4530	Energy, chemicals, coke
Crude oil	3034	Energy, petrochemicals
Iron ore	959	Iron, steel and ferrous alloys
Sodium chloride	183.5	Chlor-alkali industry, NaOH, Cl <sub>2</sub> , Na <sub>2</sub> CO <sub>3</sub> , HCl
Phosphate rock	145	Fertilizers, detergents, water treatment, phosphorus, H <sub>3</sub> PO <sub>4</sub>
Limestone	127.9	CaCO <sub>3</sub> , CaO, Ca(OH) <sub>2</sub> , CaC <sub>2</sub> , Ca
Bauxite	108.6	Al, Al <sub>2</sub> O <sub>3</sub> , Al(OH) <sub>3</sub> , Al <sub>2</sub> (SO <sub>4</sub> ) <sub>3</sub>
Gypsum	88.2	Used in plasterboard, plaster, cement retarder
Sulphur	54.1	Sulphuric acid manufacture
Sodium carbonate	31.5	Cleaning products
Potassium compounds (sylvite, sylvinite, carnallite)	24.5	Fertilizers, KOH, KO <sub>2</sub> , K
Pyrolusite	22.7	Mn alloys, MnO <sub>2</sub> , paint driers
Kaolin	22.5	Ceramics (porcelain), paint, filling paper, roofing, plastics filler
Chalk	14.2	Filler
Magnesite	10.8	Mg and its compounds
Copper ores	9.3	Cu
Bentonite	9.2	Drilling mud, thixotropic paint
Talc	8.4	Ceramics, paint, paper, roofing, plastics, cosmetics
Ilmenite and rutile	8.3	TiO <sub>2</sub> pigments (paint, paper, plastics, rubber), and Ti (jet engines, space, missiles)
Zinc ores	7.3	Zn alloys and rustproofing
Barytes	4.9	Slurry used for oil/gas drilling, Ba compounds, fillers, pigments
Fullers earth	4.2	Absorbent, and used to decolorize and deodorize mineral and vegetable fats/oils
Sodium sulphate	4.3	Paper, glass, detergents
Fluorite	3.6	HF, AlF <sub>3</sub> , Na <sub>3</sub> [AlF <sub>6</sub> ], F <sub>2</sub> , organic fluorides
Chromite	3.2	Chromates, dichromates, ceramics, pigments, chromium
Galena	3.1	Pb batteries, Pb sheet, solder, bearings
Asbestos	2.8	Heat-resistant material, filler, reinforced cement, roofing sheets

Mineral	Million tonnes/year	Uses
Kieselguhr $\text{SiO}_2$	2.0	Inert filler, filtration plants, abrasive
Borates	1.0	Borax, boric acid, perborates, glazes
Graphite	0.93	Refractories, brake linings, lubricants, pencils, moulds and used in reactors
Zircon/baddeleyite	0.87	Zr (cladding for nuclear fuel rods)
Nickel ores	0.66	Ni and alloys
Sodium nitrate	0.55	Fertilizers, explosives
Vermiculite	0.5	Packing and artificial soil
Bromine compounds (sea water)	0.37	Bromides, agricultural chemicals
Cobalt ores	0.31	Alloys
Mica	0.21	Cement, paint, roofing, electrical insulation, filler
Cassiterite	0.18	Sn
Strontianite	0.17	Sr compounds
Molybdenite	0.13	Alloys, $\text{MnO}_2$
Garnets	0.106	Sandpaper, gemstone
Monazite/bastnaesite	0.08	Lanthanide and thorium compounds
Uranium ores	0.034	Nuclear power and weapons
Iodine compounds	0.017	Pharmaceuticals, photography, iodates, iodides, iodine, animal feed supplements, catalysts, inks
Li minerals (spodumene/lepidolite)	0.009	$\text{Li}_2\text{CO}_3$ (Al production), Li stearate (greases), LiOH, ceramics/glass
Beryl	0.005	Be

# Hardness of minerals – Mohs' scale

APPENDIX

N

Sometimes rocks are called soft because individual particles, which may be quite hard in themselves, are loosely held as an aggregate and fall apart fairly readily. The hardness of a mineral is something quite different and refers to the resistance of the whole surface to be scratched.

More than a century ago a mineralogist called Friedrich Mohs devised a scale of hardness called after him. He arbitrarily assigned talc (the softest known mineral) a hardness of 1, and diamond, (the hardest known mineral) a value of 10. The scale is arbitrary and does not indicate any exact hardness. Thus a mineral of hardness 6 can scratch those below it in the scale but it does not imply that it is twice as hard as a mineral of hardness 3. Two minerals of the same hardness will both scratch each other. There is a very large difference between 9 and 10 on the scale.

**Table N.1** Mohs' scale of hardness

Mohs' scale	Mineral
10	Diamond
9	Corundum
8	Topaz
7	Quartz
6	Microcline
5	Apatite
4	Fluorite
3	Calcite
2	Gypsum
1	Talc

Common objects such as a fingernail, a copper coin, a knife blade or a metal file can also be used as test instruments. It may be convenient to use these to test samples for hardness quickly and easily when out in the field.

Table N 2 Tools for hardness testing

Mohs' scale	Tool
6.5	Steel nail file
5.5	Penknife blade or window glass
3.5	Copper coin
2.5	Fingernail

Minerals of hardness below 6.5 can be scratched by a nail file, those under 5.5 are scratched by a penknife, those under 3.5 are scratched by a copper coin and those under 2.5 are scratched by a fingernail and will leave a mark on paper. Conversely minerals over 5.5 will scratch glass.

# Standard textbooks

APPENDIX

O

## FURTHER READING

In addition to the further reading lists given at the end of each chapter, further information or a different treatment may be found in the following.

### Advanced and reference

- Bailar, J.C., Eméleus, H.J., Nyholm, R.S. and Trotman-Dickinson, A.F. (eds) *Comprehensive Inorganic Chemistry*, (5 vols), Pergamon, 1973. (A collection of reviews systematically covering the elements with a few special topics. Slightly dated, it still provides much detailed information and many earlier references.)
- Cotton, F.A. and Wilkinson, G., *Advanced Inorganic Chemistry*, 5th ed., John Wiley, 1988. (A comprehensive research level text by the well-known Nobel laureate. It contains extensive up-to-date references to the original literature.)
- Eméleus, H.J., gen. ed., *MTP International Review of Science*, (10 vols), Butterworths, 1975. Individual volumes are edited by Lappert, M.F., Sowerby, D.B., Gutmann, V., Aylett, B.J., Sharp, D.W.A., Mays, M., Bagnall, K.W., Maddock, A.G., Tobe, M.L. and Roberts, L.E.J. (Like *Comprehensive Inorganic Chemistry* it collects reviews systematically covering the elements with a few special topics. It too is slightly dated but still provides much detailed information and many earlier references.)
- Greenwood, N.N. and Earnshaw, A., *Chemistry of the Elements*, Pergamon, 1984. (A large and comprehensive advanced text for undergraduates and post-graduates. Best in its class, it provides an excellent treatment of systematic inorganic chemistry including both theoretical and practical aspects and many up-to-date references to the literature.)
- Kirk, R.E. and Othmer, D.F. (eds), *Encyclopedia of Chemical Technology*, 3rd. ed., (26 vols), Wiley, 1984. (A comprehensive treatment of the chemicals used in the chemical industry, how they are made and what they are used for.)

### Other general university-level texts

- Burns, D.T., Carter, A.H. and Townshend, A., *Inorganic Reaction Chemistry: Reactions of the Elements and Their Compounds*, (Ellis Horwood Series in Analytical Chemistry), Halsted Press, 1981.
- Cotton, F.A., Gaus, P.L. and Wilkinson, G., *Basic Inorganic Chemistry*, 2nd ed., John Wiley, 1986.
- Douglas, B., McDaniel, D.H. and Alexander, J.J., *Concepts and Models of Inorganic Chemistry*, 2nd ed., John Wiley & Sons, 1983.

- Jolly, W L , *Principles of Inorganic Chemistry*, McGraw Hill, 1985  
Mackay, K and Mackay, A , *Introduction to Modern Inorganic Chemistry*, 4th ed ,  
Prentice Hall, 1989  
Massey, A G , *Main Group Chemistry*, Ellis Horwood, 1990  
Mortimer, C E , *Chemistry*, 6th ed , Wadsworth, 1986  
Sharpe, A G , *Inorganic Chemistry*, 2nd ed , John Wiley, 1987  
Shriver D F , Atkins, P W and Langford, C H *Inorganic Chemistry*, Oxford  
University Press, 1990

### Bioinorganic chemistry

- Bioinorganic Chemistry*, Journal of Chemical Education, 1986 (ISBN 0-910362-  
25-4)  
Hay, R W , *Bio Inorganic Chemistry*, (Ellis Horwood Series in Chemical Science)  
Halsted Press, 1984  
Hughes, M N , *The Inorganic Chemistry of Biological Processes*, 2nd ed , John  
Wiley, 1981

# Index

Page numbers in **bold** refer to the most important reference for the entry.

- Absorbance 951
- Abundance of gases in dry air 470
- Abundance of elements 178,
  - Appendix A
- Acetaldehyde (ethanal), manufacture of 803, 810, 851
- Acetone, manufacture of 810
- Acetylene, *see* Ethyne
- Acids and bases, theories of 256, 257, 258, 260–68
  - Arrhenius theory 258
  - Bronsted–Lowry theory 262–64
  - hard and soft 267–68
  - in proton solvents 260–62
  - Lewis theory 265
  - Lux–Flood theory 267
  - pH scale 261–62
  - Usanovich theory 267
- Acid rain 245, **538–39**
- Actinides 879–902
  - americium 895–96
  - availability of isotopes 887
  - comparison with lanthanides 880
  - electronic structure 879
  - Fermi, E. 890, 920, 922
  - further extension of the periodic table 898–900
  - general properties 886–87
  - later actinides 896–98
  - Maddock, A.G. 889
  - main isotopes and their sources 885
  - Manhattan project 890, 920
  - neptunium 895–96
    - decay series 915–16
  - nomenclature for the superheavy elements 898–99
  - nuclear fission 891–93, 918–20
  - occurrence and preparation 882–86
  - oxidation states 881–82
  - physical properties 887
  - plutonium 895–96
  - position in the periodic table 879–80
  - protactinium 889–90
  - superheavy elements
    - half lives 899
    - nomenclature 898–99
  - thorium 887–89
    - decay series 915–16
    - monazite sand 679, 862–63, 883, **887–88**
    - thorite 883
  - uranium 890–95
    - carnotite 697, 891
    - chemical properties 893
    - decay series 915, 916
    - extraction 891
    - fission 891–93, 918–20
    - fluorides 586, 599
    - halides 894–95
    - hydrides 893–94
    - occurrence 891
    - oxides 894
    - pitchblende 883, 891
    - uraninite 891
    - uranyl nitrate 894
- Actinium 679, 680
  - decay series 915, 916
  - see also* Scandium group

- Activation analysis 933
- Adipic acid 506 698
- Alkali metals *see* Group 1
- Alkaline earth metals *see* Group 2
- Alkyl chlorosilanes 447–51
- Alloys 132–40
  - Hume Rothery rules 135–40
  - interstitial 132–35
  - substitutional 135–40
  - superconducting 141
  - types 132
- Allred and Rochow electronegativity 162–63
- Alnico 784 802
- Alpha radiation 913–15
- Aluminium
  - alkyl catalysts 397–98
  - alumina 381–82
  - aluminates 291 382–83
  - alums 194 372 723 770
  - amphoteric behaviour 382–83
  - bauxite 360
  - boiling point 360
  - carbide 417
  - cement 373
  - chloride 387–88
  - complexes 389
  - cryolite 362 586
  - electronegativity value 367
  - electronic structure 359
  - ethyl 397–98
  - extraction and uses 362–63
  - fluoride 362 586 599
  - Friedel-Crafts reaction 386
  - Hall-Héroult process (Al) 362–63
  - ionic radius 367
  - ionization energy 149 369–70
  - lithium aluminium hydride 297 384–85
  - melting point 366
  - metallic radius 337 367
  - organometallic compounds 397–98
  - occurrence and abundance 360
  - oxide 381–82
  - reactions of 370–77
  - standard reduction potentials 167 368–69
  - sulphate 372
  - uses 363
  - see also* Group 13
- Aluminates 291 382–83
- Alums 194 372 723 770
- Americium *see* Actinides
- Ammonia 479–80 492–94
  - bonding 34
  - cyanamide process 492
  - detection 479
  - liquid 263–64 302–03 335 486–87
  - production by Haber-Bosch process 242 243 244 491, 492–94
  - soda process 323
  - structure 73 77, 81
- Ammonium ion 35
  - dichromate 722
  - nitrate 499
  - perchlorate 619
  - pertechnetate 735
  - salts 480
- Amphiboles 438–39
- Andrussow process (HCN) 453
- Angular part of wave function 17–9
- Aniline 506
- Antimony
  - allotropic forms 475–76
  - boiling point 472
  - covalent radius 475
  - electronegativity 475
  - electronic structure 468
  - halides 494–98
  - hydride 481
  - ionization energy 475
  - melting point 472
  - occurrence extraction and uses 471–72
  - oxide ion  $\text{SbO}^+$  495
  - oxides 508–11
  - standard reduction potentials 167 490
  - see also* Group 15
- Anti neutrino 910
- Applications of radioisotopes 932–34
- Aragonite 426
- Argon *see* Group 18
- Arrangement of the elements in groups 25–7
- Arrhenius theory of acids 258
- Arsenic
  - allotropic forms 475–76
  - boiling point 472
  - covalent radius 475
  - electronegativity 475
  - electronic structure 468
  - halides 494–98



- hydride 481  
ionization energy 475  
melting point 472  
occurrence, extraction and uses 471–72  
oxides 508–11  
standard reduction potentials 167, 490  
*see also* Group 15
- Arsine 481  
Asbestos 319, 438–39  
Astatine 583, 590
- Atomic  
bomb 892  
number 1, 905  
orbitals 13–21  
orbitals and quantum numbers 15  
size 905  
structure 1, 2
- Atomic spectra 2–10  
Balmer series 2, 8–9  
Brackett series 2, 3, 8–9  
Humphries series 2, 8–9  
Lyman series 2, 8–9  
Paschen series 2, 3, 8–9  
Pfund series 2, 3, 8–9
- ATP 471
- Attainment of a stable configuration 30
- Aufbau build-up principle 21, 23–4, 98–9
- Azeotropic mixture 560, 602
- Azides 117, 487–89, 488, 499
- Azotobacter 474
- Baking powder 294
- Balmer series 2, 8–9
- Band gaps in semiconductors 64
- Band theory of metals 128–31
- Barium, *see* Group 2
- Basic beryllium acetate 350–51
- Basic beryllium nitrate 343
- Basic oxygen process (steel) 535–36, 759
- Bessemer–Thomas process 757–58
- Kaldo and LD processes 759
- puddling 757
- Siemens electric arc furnace 758–59
- Siemens open hearth furnace 758
- Basic properties of the halogens 629–31
- Bastnaesite 863
- Bauxite 360
- Bednorz and Müller 142
- Benzene ammino nickel cyanide (clathrate) 807
- Berkelium, *see* Actinide
- Beryllium  
anomalous properties 325, 332–34, 353–54  
atomic structure 2  
basic acetate 350–51  
basic nitrate 343  
carbide 417  
electronic structure 325  
extraction 327–28  
fluoride 73, 83–4  
metallic structure 125  
molecule 100–01  
occurrence and abundance 326  
oxalate complex 350–51  
tetrafluoroberyllate ion 350  
uses 328  
*see also* Group 2
- Bessemer–Thomas converter 757–58
- Beta emission 909–10
- Bicarbonates 294–95
- Bidentate ligands 223
- Binding energy 912–13, 914
- Bioinorganic chemistry of iron 775–79
- Biodegradable detergents 555–56
- Biological importance  
of calcium and magnesium 353  
of chromium and molybdenum 732  
of cobalt 796–97  
of copper 816, 832–33  
of manganese 734, 751  
of sodium and potassium 279, 308  
of zinc 851–52
- Birkeland–Eyde process ( $\text{HNO}_3$ ) 505
- Bismuth  
boiling point 472  
bismuthine 481  
covalent radius 475  
electronegativity 475  
electronic structure 468  
halides 494–98  
hydride 481  
ionization energy 475  
melting point 472  
occurrence, extraction and uses 471–72  
oxides 508–11  
oxide ion  $\text{BiO}^+$  495  
standard reduction potentials 490

- Bismuth (*cont.*)  
   structure 476  
   *see also* Group 15  
 Bismuthine 481  
 Blast furnace 755-57  
 Blister copper 817  
 Blue baby syndrome 494  
 Body centred cubic structure 36-9  
 Bohr  
   theory 6-8  
   orbits 9  
   refinements to theory 8-10  
   Sommerfield orbits 10  
 Bomb making 922  
 Bond  
   coordinate 34-5  
   covalent 30-1, 33-4 72-119  
     MO theory 89-119  
       heteronuclear diatomic examples 109-12  
       homonuclear diatomic examples 99-107  
       examples of delocalized multi-centre  $\pi$  bonds 112-18  
     Sidgwick-Powell theory 74-5  
     table of shapes 75  
     valence bond theory 80-9  
     VSEPR theory 74-80  
   delta 96, 830  
   double 35-6, 73  
   extent of *d* orbital participation 85-7  
   four centred 114, 304, 386, 507  
   hydrogen 255-57, 533  
   ionic 30-3, 43-68  
   metallic 36-9, 121-45  
     free electron theory 128  
     valence bond theory 128  
     MO or band theory 128-31  
   M-M bonds in compounds 674, 703, 706, 709, 711, 722, 726, 737, 738, 745, 747, 763, 787, 797, 810  
   multicentre 112-18, 252, 381, 422  
   of intermediate character 31-2  
   order of 105  
    $p\pi-d\pi$  456, 509-10  
   quadruple 713, 725-26  
   three-centred 116, 117, 333, 384, 395-97, 424, 489, 504, 541, 606  
   transition metal complexes  
     crystal field theory 202, 204-10  
     molecular orbital theory 202-03, 227-30  
     valence bond theory 202, 203-04  
   triple 35-6  
   types of 30-1  
 Bondorizing 762  
 Bonding  
   extent of *d* orbital participation 85-7  
   in  $\text{CaCl}_2$  33  
   in  $\text{CCl}_4$  33  
   in  $\text{Cl}_2$  33  
   in HF 34  
   in  $\text{H}_2\text{O}$  34  
   in  $\text{NaCl}$  31-2  
   in  $\text{NH}_3$  34  
 Borates 374-79  
 Bordeaux mixture 818  
 Borides 380-81  
 Born exponent 55-7  
 Born-Haber type of cycle 154-56, 169, 282-84, 595, 603-04  
 Bornite 817  
 Born-Landé equation 56  
 Boron  
   atomic structure 2  
   boiling point 360  
   borates 374-79  
   borax 360-61, 377  
   borax-bead test 374  
   borazine 393-94  
   borides 380-81  
   borohydrides (tetrahydridoborates) 297, 383-85  
   borosilicate glass 445  
   carbide 361, 381, 418  
   carboranes 397  
   differences B and rest of group 389  
   dihalides 388  
   electronegativity value 367  
   electronic structure 359  
   extraction 360-61  
   fluoboric acid 380  
   Friedel-Crafts reaction 386  
   hydrides 390-97  
     compounds known 390  
     preparation 390-92  
     reactions of 392-94  
   hydroboration 392-93  
   ionization energy 149, 369-70  
   isopoly acids 379-80  
   nitride 393-94

- melting point 366
- metallic radii 137, 367
- molecule 101–02
- monohalides 388–89
- nitride 393–94
- occurrence and abundance 360
- order of MO energy levels 98, 102
- organometallic compounds 397–98
- orthoboric acid 375–77
- Pyrex glass 362, 445
- qualitative analysis 380
- reactions of 370
- steel 892
- structure of
  - boron 366, 395
  - borates 376–79
- sodium peroxoborate 361–62, 379
- sesquioxide 362, 374
- sodium borohydride 297, 384–85
- tetrahydridoborates 383–85
- trifluoride 73, 82, 84, 385–87
- uses 361–62
- see also* Group 13
- Borohydrides (tetrahydridoborates)
  - 383–85
- Borosilicate glass 445
- Brackett series 2, 3, 8–9
- Brass 139, 818, 838
- Bridging halides 606
- de Broglie dual nature of electrons 11
- Bronsted–Lowry theory of acids 262–64
- Bronze 406
- Bromine
  - colour of  $X_2$  583
  - covalent radius 591
  - electron affinity 154, 591
  - electronegativity 160, 592
  - electronic structure 582
  - extraction and uses 588–89
  - hydration energy 591
  - interhalogen compounds 621–27
  - ionic radius 591
  - ionization energy 149, 592
  - melting point 593
  - occurrence and abundance 583–84
  - oxides 611–12
  - oxidizing power of  $X_2$  594–96
  - oxoacids 614–21
  - polyhalides 628–29
  - positive bromine 629–31
  - reaction with water 596–97
  - reactivity 597–98
  - standard reduction potentials 592, 613–14
  - trifluoride 626
  - see also* Group 17
- Brown ring test 500, 765
- Build up of the elements 21, 23–4, 98–9
- Cadmium, *see* Zinc Group
- Caesium
  - chloride structure 48
  - see also* Group 1
- Calamine 836
- Calcite 425–26
- Calcium
  - biological role 353
  - carbonate 425–26
  - electronic structure 325
  - extraction 329
  - carbide 51–2, 346–47, 417
  - chloride 33, 323, 345
  - cyanamide 346–47, 417, 492
  - fluoride 48, 327, 345
  - fluoroapatite 327
  - hydroxide 315–17, 323, 337
  - hypochlorite (bleaching powder) 340
  - occurrence and abundance 326–27
  - phosphate 470–71
  - sulphate 327, 341–42
  - uses 329
  - see also* Group 2
- Calgon 516
- Californium, *see* Actinides
- Cancer treatment 811, 934
- Carats (gold) 819
- Car batteries 407
- Carbides
  - covalent 418
  - crystal structure  $CaC_2$  51–2
  - interstitial 417–18
  - of Group 1 303
  - of Group 2 346–47
- Carbon
  - activated charcoal 404
  - allotropy 407–09
  - atomic structure 2
  - black 403
  - $C_2$  molecule 102–03
  - carbides 416–18
    - covalent 418

- Carbon  
   *carbides (cont)*  
     interstitial 417-18  
     salt like 416-17  
   carbonyls 420-23, 711, 727, 739-40, 763-64, 765, 768, 787-88, 805-06  
   carbonyl halides 422-23  
   catenation 409-10  
   coal gas 419  
   coke 403, 755  
   cycle 427-28  
   covalent radius 411  
   dating 410-11, 917 932-33  
   diamond 404 407-08  
   differences from Si and Group 14 409-10  
   dioxide 73, 87-8, 116-17, 423-25  
     abundance in dry air 470  
     solid 423  
   disulphide 428-29, 458, 539  
   electronic structure 402  
   electronegativity values 160, 411  
   extraction and uses 403-04  
   graphite 404, 408-09  
     compounds 414-16  
   halides 33, 73, 457, 586  
   hydrides 451  
   ionization energy 411  
   melting point 411  
   mixed chlorofluorocarbons 458 586-87 599  
   monoxide 419-23  
     estimation 612  
     molecular structure 100-12  
   multiple bonds 409  
   occurrence and abundance 403  
   order of MO energy levels 98  
   producer gas 419-20  
   reactivity 412-13  
   suboxides 425  
   tetrachloride (tetrachloromethane) 33 73 457 771  
   tetrafluoride (tetrafluoromethane) 457 586  
   water gas 419  
   *see also* Group 14  
 Carbonate ion 112-14  
 Carbonyl halides 422 457  
 Carbonyls 420-22 711 727, 39-40 763-64 765 768, 787-88 805-06  
 Carborundum 418  
 Cardice 423  
 Carnallite 194  
 Carnotite 697, 891  
 Caro's acid 563  
 Cartesian and polar coordinates 16  
 Cassiterite 405  
 Cast iron (pig iron) 755  
 Castner Kellner process (NaOH) 318  
 Castner process (NaCN) 453  
 Catalase and peroxidase 775, 778  
 Catalytic convertors (cars) 803  
 Catalytic properties of transition metals 671-72  
 Cavendish 635  
 Cellophane 428-29  
 Cement 373  
 Cementite 418  
 Ceramics 444  
 Cerium *see* Lanthanides  
 Chain reactions 919  
 Chalcocite 817  
 Chalcopyrites 817  
 Charge transfer spectra 460, 702, 705, 707, 719, 724, 738, 750, 766, 767, 771, 773, 822, 833, 840, 844, 845  
 Chelates 222-24  
 Chile saltpetre 295-96, 539, 590  
 Chlor-alkali industry 243, 315-24  
 Chlorine  
   bonding 33 594  
   colour of  $X_2$  583  
   covalent radius 591  
   dioxide 583 610  
   electron affinity 154 591  
   electronegativity 160 592  
   electronic structure 582  
   extraction and uses 587-89  
   hydration energy 591  
   interhalogen compounds 621-27  
   ionic radius 591  
   ionization energy 149 592  
   manufacture and uses of 315-21  
   melting point 593  
   occurrence and abundance 583-84  
   oxides 609-11  
   oxidizing power of  $X_2$  594-96  
   oxoacids 614-21  
   perchlorate 610-11  
   polyhalides 628-29  
   reaction with water 596-97

- reactivity 597–98
  - standard reduction potentials 592, 613–14
  - trifluoride 586, 624–26
  - see also* Group 12
- Chlorophyll 351–52
- Chromates 718, 728–31
- Chromite 713–14
- Chromium group 713–33
  - abundance, extraction and uses 713–15
  - biological importance Cr and Mo 732
  - carbonyls 727
  - chromates 718, 728–31
  - chromite 713–14
  - chromium(II) acetate 713, 725–26
  - chromium(III) oxide/chromic acid 719–20
  - cluster compounds 713, 726–27
  - (+V) compounds 721
  - (+IV) compounds 722
  - (+III) compounds 722–25
  - (+II) compounds 725–27
  - (+I) compounds 727
  - (0), (–I) and (–II) compounds 727–28
  - cutting steel 715
  - cyclopentadienyl compounds 727–28
  - dibenzene chromium 727–28
  - dichromate 713, 718
  - electronic structures 713
  - ferrochrome 714
  - Fischer, E.O. 727–28
  - general properties 716–18
  - halides 716, 721
  - M–M bonds 726, 727
  - molybdates 713, 728–31
  - molybdenite 714
  - molybdenoferredoxin 732
  - molybdenum disulphide 715
  - nitrogen fixation 713, 732
  - oxidation states 715–16
  - oxides 716, 719–20
  - oxohalides 712
  - peroxo compounds 719
  - physical properties 716
  - polyacids 713, 728–31
  - quadruple bond 713, 725–26
  - qualitative analysis 717
  - reactivity 716
  - spectra Cr(+III) ( $d^3$ ) 724
  - scheelite 715
  - standard reduction potentials 167, 717
  - tungstates 713, 728–31
  - tungsten bronzes 731–32
  - tungsten carbide 417, 715
  - Wilkinson, G. 727–28
  - wolframite 715
- Chrysotile 440
- Cinnabar 836
- Cis-isomers 197–98, 234–35
- Cisplatin (anti cancer drug) 811
- Clathrate compounds 638–39, 807
- Clay minerals 442
- Close packing of spheres 36–9, 46–7
- Clostridium botulinum 504
- Clostridium pastorianum 474
- Cluster compounds 461, 674, 697, 705–07, 713, 726–27, 743–45
- Coal gas 419
- Cobalt group 753, 783–99
  - basic acetate 797
  - biological importance of cobalt 796–97
  - carbonyls 787–88
  - cyclopentadienyl compounds 793
  - (–I) and (0) compounds 787
  - (+I) compounds 788
  - (+II) compounds 790–94
  - (+III) compounds 794–98
  - (+IV) compounds 798
  - (+V) and (+VI) compounds 799
  - electronic structures 783
  - general properties 785
  - halides 786
  - Hodgkin, D.C. 796
  - nitrogen complex 788
  - OXO process 789–90
  - oxides 786
  - occurrence, extraction and uses 783–85
  - oxidation states 785
  - oxidative addition reaction 788
  - physical properties 786
  - some reactions 786
  - spectra
    - of  $[\text{Co}(\text{Cl}_4)]^{2-}$  965
    - of  $[\text{Co}(\text{H}_2\text{O})_6]^{2+}$  964
  - speisses 783
  - Vaska's compound 788–89
  - vitamin B<sub>12</sub> 784, 793, 796
  - Wilkinson's catalyst 788–89
- Cobaltite 783
- Cohesive force in metals 122–26, 285
- Colour 662–63

- Columbite 698
- Complexes
- bonding in 202-10
  - by transition elements 657-59, 675
  - chelate 222-24
  - class-a and class-b acceptors 659
  - conductivity of 198-99
  - crown ethers and crypts 306-08, 353
  - cryoscopic measurements 199-200
  - dipole moments of 200
  - distorted octahedral 214-17
  - effective atomic numbers of 200-01
  - electronic spectra 200, 207
  - isomerism 197-98, 232-36
  - Jahn-Teller distortion 214-19
  - magnetic moment of 225-26
  - nomenclature 230-32
  - number of isomers 197-98
  - $\pi$  acceptors 229
  - $\pi$  donors 229-30
  - octahedral 205-14
  - polynuclear 230-31, 235
  - shapes of  $d$  orbitals 201
  - spectrochemical series 208
  - square-planar 217-19
  - see also Nickel group
  - tetrahedral 219-22
  - Werner's work 195-98
  - with alkenes 808-10
- Computer chips manufacture 68
- Conductivity
- measurements of complexes 198-99
  - of ionic covalent compounds and metals 40
  - of metals 121-22
- Conductors insulators and semi-conductors 131-33
- Conductors, one dimensional 810-11, 812
- Contact process (for  $\text{SO}_2$ ) 552, 553, 698, 803
- Controlled fusion reactions 927-28
- Coordinate bond 34-5
- Coordination
- compounds 194-239
  - isomerism 233
  - number 196
  - position isomerism 234
- Copper group 816-34
- abundance, extraction and uses 816-19
  - alloys
    - brass 139, 818, 838
    - nickel silver 818
  - anhydrous copper(II) acetate 829-30
  - anhydrous copper(II) nitrate 829, 830
  - biological importance of copper 816, 832-33
  - blister copper 817
  - Bordeaux mixture 818
  - carats (gold) 819
  - catalytic properties 822
  - colour 822, 827
  - complexes with alkenes 824
  - (+I) compounds 822-26
  - (+II) compounds 827-31
  - (+III) compounds 831-32
  - copper(II) chloride as a catalyst 317
  - conductivity 816, 820
  - cyanide process (gold) 819, 824
  - disproportionation 820, 822-23
  - electronic structures 816
  - general properties 820-22
  - halides 589-90, 820
  - oxidation states 819
  - oxides 820
  - panning (gold) 819
  - Paris green 818
  - Parke's process (silver) 818
  - photography 562, 589-90, 826-27
  - physical properties 821
  - reactivity 816, 821
  - standard reduction potentials 167, 820
  - tetragonal (Jahn-Teller) distortion 827-28
  - turquoise 817
- Correlation diagram 118
- Corundum 381
- Coupling
- of orbital angular momenta 940-42
  - of spin momenta 942-43
  - of spins and angular momenta 943-46
- Covalent bond 30-1, 33-4, 72-119
- Covalent radii, table of 147
- Cracking of hydrocarbons 242
- $\beta$ -Cristobalite 49, 430
- Critical mass 920
- Crown ethers 306-08, 353
- Cryolite 362
- Cryoscopic measurements 199-200
- Cryptands 306-08, 353

- Crystal field theory 202, 204–10  
  assumptions made 204–05  
  magnitude of  $\Delta_o$  207–09  
  octahedral complexes 204–11  
  spectrochemical series 208  
  splitting by various ligands 208  
  splitting on descending a group 209  
  splitting related to charge 208–09  
  square-planar complexes 217–19  
  stabilization of lattice energy 213  
  tetrahedral complexes 219–22
- Crystal structures of metals 36–9, 125–26
- Cubic close packing 36–9
- Cuprite 817
- Cupronickel (coins) 802
- Curie law (magnetism) 670–71
- Curium, *see* Actinides
- Crooke's lenses 680, 863
- Coinage metals, *see* Copper group
- Cyanamide 346–47, 492
- Cyanates 454
- Cyanides 453–54
- Cyanide process (gold) 819, 824
- Cyanogen 454
- Cyanuric triazide 488
- Cyclohexanol 506, 698
- Cyclohexanone 485–86, 506, 698
- Cyclopentadienyl compounds 695–96, 711, 727–28, 779–81, 793
- Cyclotron 883, 917
- Cytochrome 754, 777
- Daniell cell
- Dative bonding, *see* Bond,  $p\pi-d\pi$
- d* block 651–56  
  abundance 673–74, 676  
  boiling points 661, Appendix C  
  catalytic properties 671–72  
  CFSE of dihalides 213  
  chromium group 713–33  
  class-a and class-b acceptors 659  
  cobalt group 753, 783–99  
  colour 662–63  
  complexes 657–59, 675  
  copper group 816–34  
  covalent radii 147, 659–60, 675  
    and the lanthanide contraction 660  
  density 661, Appendix D  
  differences between 1st row and  
    other two rows 674–76  
  electronegativity values 160
- Gouy magnetic balance 664–65  
  magnetic moments of some 1st row  
    complexes 669  
  measurement of magnetic  
    properties 666
- horizontal comparisons in the Fe, Co,  
  Ni groups 814–15
- introduction to transition elements  
  653–77
- ionic radii, effect of lanthanide  
  contraction 660
- ionization energies 151, 661–62
- iron group 753–82
- lattice energy and CFSE 213
- magnetic properties 663–71, 675–76  
  Curie law 670–71  
  of octahedral complexes 211  
  of tetrahedral complexes 222
- manganese group 734–52
- measurement of magnetic properties  
  666
- melting points 661, Appendix B
- metallic  
  character 654  
  radii 137
- metalloenzymes and metalloproteins  
  673
- metal-metal bonding and cluster  
  compounds 674, 697, 705–07,  
  713, 726–27
- names 653
- nickel group 753, 800–15
- noble character 661
- nonstoichiometry 672
- reactivity of the metals 661
- scandium group 679–83
- stability of various oxidation states  
  656–57, 674
- standard reduction potentials 167,  
  172–73, 681, 688, 706, 717,  
  737, 820, 842
- titanium group 684–96
- vanadium group 697–712
- variable oxidation states 654–56
- zinc group 835–56
- Deacon process 317, 587–88, 863
- Defects 58–63  
  *F*-centres 61–2  
  Frenkel 59–61  
  extrinsic conduction 64  
  intrinsic semiconduction 60, 64

- Defects (*cont.*)  
 metal deficient 63  
 metal excess 61–2  
*n*-type semiconduction 62  
 nonstoichiometric 61–3  
 number of defects 59–60  
*p* type semiconduction 63, 65  
 Schottky 59–60  
 stoichiometric 59–61  
 Degussa process (HCN) 453  
 Delta bond 96, 830  
 Denitrifying bacteria 473–74  
 Density  
   of elements Appendix D  
   of nucleus 905–06  
 Depression of freezing point 199  
 Detergents 315, 555–56, 599  
 Deuterium 245–48  
   preparation of compounds 247  
 Devarda's alloy 507  
 Diagonal relations 189–90, 311 353–54  
   389  
 Diamond 404 407–08  
 1,2-dibromoethane (ethylene dibromide) 589  
 1,2-dichloroethane (ethylene dichloride) 600  
 Diaphragm cell 318–19  
 Dibenzene chromium 727–28  
 Didymium catalyst 317, 863  
 Differences between 1st row TE and  
   other two rows 674–76  
 Differentiating solvents 264  
 Dimethyl glyoxime complex (Ni) 807  
 Dinitrogen tetroxide 265–66 501–02  
 Dinitrogen pentoxide 503  
 Dipyrrolyl complexes 655  
 Direct process (Rochow) 447  
 Disproportionation 174–77  
 Dithionous acid 556 559  
*d* orbitals  
   extent of *d* orbital participation 85–7  
   shape 201  
 Double bonds 35–6  
 Double salts 194–95 764 770  
 Dow natural brine process (Mg) 329  
 Dow sea water process (Mg) 329  
 Downs cell 277–78  
 Drude free electron theory of metals 128  
 Dry ice 423  
 Dysprosium, *see* Lanthanides  
 EDTA 352–53  
 Effective atomic number rule 200–01  
 Einsteinium, *see* Actinides  
 Electrochemical series 165–67  
 Electrode potentials 165–78  
 Electron  
   affinity 153–54  
   deficiency 385, 395  
   diffraction 11  
   dual nature of 10–1  
   mass 1  
   pair repulsion theory of molecular  
     shapes 74–80  
   particles or waves 10–1  
   reduced mass 8  
   wave nature of 11  
 Electronegative elements 30–3  
 Electronegativity 157–63  
   Allred and Rochow 162–63  
   Mulliken 161–62  
   Pauling 157–60  
     table of values 160  
 Electronic structure, different ways of  
   showing 23–4  
 Electropositive  
   character 163–64  
   elements 30–2  
 Ellingham diagrams 185–86  
 Engel's sulphur 542  
 Emission spectra 287  
 Energy levels  
   for heteronuclear diatomic molecules  
     109–11  
   for homonuclear diatomic molecules  
     98–108  
   for CO 110–12  
   for NO 109–10  
   sequence of 98  
 Environmental problems with  
   acid rain 245, 538–39  
   asbestos 439  
   catalytic converters (cars) 803  
   detergents 555–56  
   fluoride ions in drinking water 587  
   mercury and cadmium 838–39 852–53  
   nitrogenous fertilizers 493–94  
   ozone layer 494, 543–44 599  
   phosphates 515 521  
   photochemical smog 544  
   water, EEC limits for contaminants  
     566



- EPNS 802  
Ethanal (acetaldehyde), manufacture of 803, 810, 851  
Ethanolamine 242, 423, 493  
Erbium, *see* Lanthanides  
Essential elements 308–09  
Ethanolamine 242, 423, 493  
Ethene 35–6  
Ethylene, *see* Ethene  
Ethyne 35–6, 346  
Europium, *see* Lanthanides  
Explosives 506  
Extent of *d* orbital participation 85–7  
Extraction and isolation of elements 178–88.  
    general methods  
        displacement method 180–81  
        electrolytic reduction 182–83  
        high temperature reduction 181–82  
        mechanical separation 178–79  
        thermal decomposition 179–80  
    thermodynamics of extraction processes 183–87  
Extraction methods  
    and position in periodic table 188  
    and reduction potentials 184  
  
Face-centred cubic, *see* Close packing  
Facial isomers 197, 797  
Fajan's rules 156–57, 364  
Fat man (bomb) 922–23  
*f* block 857–902  
*F*-centres 61–2  
Feldspars 443  
Femtometres 905  
Fermentation 423  
Fermium, *see* Actinides  
Ferredoxin 732, 754, 778–79  
Ferretin 778  
Ferrite (Lowig) process for NaOH 770  
Ferrocene 779–81  
Ferrochrome 714  
Ferrocyanide ion 766–77  
Ferroun 767  
Ferromanganese 735  
Ferronickel 801  
Ferrosilicon 404  
Ferrous metals 753  
Ferrovanadium 697  
Fertilizer 470, 489, 493–94  
    problems with 493–94  
  
Fission 890, 891–93  
Flame colouration  
    Group 1 286–87  
    sodium 2, 61  
Fluoborate ion 380  
Fluoride ions in drinking water 587  
Fluorine  
    atomic structure 2  
    colour of  $X_2$  583  
    covalent radius 591  
    electron affinity 154, 591  
    electronegativity 160, 592  
    electronic structure 582  
    extraction and uses 584–87  
    hydration energy 591  
    interhalogen compounds 621–27  
    ionic radius 591  
    ionization energy 149, 592  
    melting point 593  
    molecular structure 107  
    occurrence and abundance 583–84  
    oxides 608  
    oxidizing power of  $X_2$  594–96  
    reaction with water 596–97  
    reactivity 597–98  
    standard reduction potentials 592, 613–14  
    weakness of F–F bond 594  
Fluorite 48, 345  
Fluoroapatite 470, 494  
Forsterite 434  
Francium, *see* Group 1  
Frankland 850  
Frasch process (sulphur) 536  
Free energy (Ellingham) diagrams 185–86  
Frenkel defects 59–61  
Freons 458, 586–87, 599  
Friedel–Crafts reaction 386  
Fullers earth 442  
Fusion reactions 247, 254  
  
Gadolinium, *see* Lanthanides  
Galena 406–07  
Gallium, *see* Group 13  
Galvanizing iron 762  
Gamma radiation 911  
Garnets 435, 680  
Gemstones 431  
General properties of metals 121–27

- Genesis of the elements 928-32
  - r process 931
  - s process 931
  - x-process 931
  - red giants 929
  - spallation reactions 931
  - supernova 932
  - white dwarfs 930
- Geometric isomerism 234
- Germanes 453
- Germanium
  - as a semiconductor 63-5
  - boiling point 411
  - covalent radius 411
  - electronegativity values 160, 411
  - electronic structure 402
  - extraction and uses 405
  - halides 460-61
  - hydrides 453
  - ionization energy 411
  - melting point 411
  - occurrence and abundance 403
  - oxides 431-32
  - reactivity 412-13
  - ultrapure 65, 405
  - see also* Group 14
- Glass 316, 322, 362 445-56
- Glycol splitting agent 620
- Gold, *see* Copper group
- Gouy magnetic balance 664-65
- Graham's salt 516-17
- Graphite 404 408-09
  - compounds 414-16
- Greenhouse effect 245 427-28, 458
- Grignard compounds 328 347-49, 446
- Group 1 275-314
  - alkyls 305
  - atomic structure of Li 1, 2
  - baking powder 294
  - bicarbonates 294-95
  - boiling points 286
  - biological importance 279 308
  - bond type 281-82
  - Born-Haber cycle 282-83
  - carbides 303
  - carbonates 279, 315-22
  - cohesive energy 285
  - colour of compounds 287-88
  - complexes 305-08
  - covalent radii 147
  - crowns and crypts 306-08
  - density 280-81
  - diagonal relationship 310-11
  - differences Li and rest 309
  - electronegativity 160 281-82
  - electronic structure 275
  - extraction 277-78
    - Downs cell 277-78
  - flame colourations 286-87
  - halides and polyhalides 296-97
  - hardness of metals 285
  - hydrides 297-98
  - hydroxides 279 290-91, 294
  - ionization energy 149 151, 281
  - melting points 286
  - metallic radii 137
  - metallic structures 125, 285
  - occurrence and abundance 275-77
  - organic and organometallic compounds 303-05
  - oxides
    - normal 290
    - peroxide 291-93
    - superoxide 105-07, 291-93
  - phosphates 512-17
  - radius ratios of halides 52
  - reactions of 288
    - air 289-90
    - nitrogen 289
    - water 288-89
  - solubility in liquid ammonia 302-03
  - solubility of salts 298-302
  - sulphides 293-94
  - uses 278-80
- Group 2 325-56
  - atomic structure of Be 2
  - anomalous behaviour of Be 325, 332-34, 353-54
  - bicarbonates 337
  - biological role 353
  - boiling points 331
  - carbonates 340
  - carbides 51-2, 346-47
  - complexes 349-53
    - basic beryllium acetate 350-51
    - basic beryllium nitrate 343
    - beryllium oxalate 350-51
    - chlorophyll 351-52
    - EDTA 352-53
    - tetrafluoroberyllate ion 350
  - cyanamide 346-47, 417, 492
  - covalent radii 147

- crown ethers and crypts 353
- Curie, Marie 327
- density 330
- electronegativity values 160, 331
- extraction 327–29
- Grignard compounds 328, 347–49
- halides 344–45
- hardness of water 337–38
- hydration energy 331–32
- hydrides 342–44
- hydrolysis of salts 333
- hydroxides 336–37
- insoluble salts 347
- ionic radii 330
- ionization energy 149, 151, 331
- lime 315–17, 322–23, 340
- melting points 331
- metallic radii 137, 330
- metallic structures 125
- nitrates 342–43
  - basic beryllium nitrate 343
- nitrides 345
- occurrence and abundance 326–27
- organometallic compounds 347–49
- oxides 338–41
- radius ratios of oxides, sulphides etc.  
52, 339
- reactions
  - acids and bases 338
  - water 335–36
- solubility of salts and lattice energy  
334–35
- solutions in liquid ammonia 335
- sulphates 341–42
- uses 328, 329
- Group 13 359–401
  - alumina 381–82
  - aluminates 291, 382–83
  - aluminium chloride 387–88
  - aluminium sulphate 372
  - alums 372
  - amphoteric behaviour 382–83
  - atomic structure of boron 2
  - boiling points 360
  - borates 374–79
  - borax 360, 361, 377
  - borax-bead test 374
  - borazine 393–94
  - borides 380–81
  - boron carbide 361, 381
  - boron nitride 393–94
  - boron sesquioxide 362, 374
  - boron trifluoride 73, 82, 84, 385–87
  - Brown, H.C. 393
  - carboranes 397
  - cement 373
  - complexes 389
  - corundum 381
  - cryolite 362
  - electronegativity value 36 /
  - electronic structure 359
  - ethyl 397–98
  - extraction and uses 362–63
  - Friedel–Crafts reaction 386
  - Hall–Héroult process 362–63
  - ionic radii 367
  - ionization energy 149, 369–70
  - lithium aluminium hydride 297,  
384–85
  - melting point 366
  - metallic radii 137, 367
  - occurrence and abundance 360
  - organometallic compounds 397–98
  - oxide 381–82
  - qualitative analysis 380, 382
  - reactions of 370–72
  - standard reduction potentials 167,  
368–69
  - sulphate 372
- Group 14 402–67
  - allotropy 407–09
  - atomic structure of C 2
  - bicarbonates 424, 425
  - boiling points 411
  - carbides 416–19
  - carbonates 424, 425–26
  - carbon cycle 427–28
  - carbon dating 410–11, 917
  - carbon disulphide 428–30
  - carbonyls 420–23, 711, 727, 739–40,  
763–64, 765, 768, 787–88,  
805–06
  - carbonyl halides 422, 423
  - catenation 409–10
  - cluster compounds 462
  - complexes 455–56
  - covalent radii 147, 411
  - cyanides 453–55
  - differences from Si and Group 14  
409–10
  - electronic structures 402
  - electronegativity values 160, 411

Group 14 (*cont.*)

- extraction and uses 403–07
- graphite compounds 414–16
- greenhouse effect 245 427–28 458
- halides 457–6
- hydrides 451–53
- inert pair effect 413
- internal  $\pi$  bonding using  $d$  orbitals 456
- ionization energy 149 411
- melting points 411
- metallic and nonmetallic character 412
- metallic radii 137
- metallic structures 125
- occurrence and abundance 403
- organic derivatives 446–51 463
- oxides 419–26 430–32
- reaction mechanisms 462–63
- reactivity 413
- silicates 432–46
- silicones 446–51
- standard reduction potentials 167 414

## Group 15 468–531

- allotropic forms 474–76
- ammonia 479–80 492 94
  - bonding 34
  - cyanamide process 492
  - detection 479
  - liquid 263–64 302–03 335 486–87
  - production by Haber–Bosch process 242 243 244 491 492–94
  - Solvay process 323
  - structure 73 77 81
- atomic structure of  $N_2$
- azides 117 487–89 488 499
- boiling points 472
- bond lengths and  $p\pi-d\pi$  bonding 546–47
- bond type 476–77
- covalent radii 147 475
- denitrifying bacteria 473–74
- electronegativity values 160 475
- electronic structures 468
- environmental problems with phosphates 515 521
- fertilizer 470 489 493–94
- halides 494–98
- hydrazine 483–85
- hydrides 478–85
  - donor properties of 482–83
  - structures of 481–82

- hydroxylamine 485–86
  - ionization energy 149 475
  - liquid ammonia as a solvent 486–87
  - Marsh's test 481
  - melting points 472
  - metallic and nonmetallic properties 477–78
  - metallic radii 137
  - metallic structures 125
  - nitrifying bacteria 473–74
  - nitrogen cycle 473–74
  - nitrogen fixation 473–74 489 491–93 713 732
  - occurrence extraction and uses 468–72
  - organometallic compounds 526–27
  - oxides 498–503
  - oxoacids of
    - nitrogen 503–11
    - phosphorus 511–21
  - $p\pi-d\pi$  bonding 509–10
  - phosphazenes (phosphonitrilic compounds) 498 524–26
  - phosphonic acid series 511–19
  - phosphorous acid series 519–21
  - problems with nitrogenous fertilizers 493–94
  - reactivity of the elements 478
  - standard reduction potentials 167 490
  - structures of the elements 472 474–76
  - sulphides 521–24
  - uses of phosphates 520–21
- Group 16 532–634
- abundance 534
  - allotropy and structures 540–43
  - atomic structure of  $O_2$
  - boiling points 545
  - chemistry of ozone 115–16 540–41 543–45
  - compounds of sulphur and nitrogen 576–77
  - contact process (for  $SO_2$ ) 552 553 698 803
  - covalent radii 147 545
  - differences between O and the other elements 547
  - electronegativity values 160 545
  - electronic structures 532
  - extraction and uses 535–36
  - Frasch process (sulphur) 536
  - halides 572–75
  - hydrides 565–69

- hydrogen sulphide 536–37
- ionic radii 545
- ionization energy 149, 545
- melting points 545
- metallic radii 137
- organo derivatives 577–78
- oxides 537–39, 547–54
- oxoacids
  - of S 556–63
  - of Se and Te 564
- oxohalides of Se 564–65
- pπ-dp* bonding 546–47
- peroxides and polysulphides 570–72
- reactions between oxides 549–51
- ring compounds of S and N 575–77
- standard reduction potentials 167, 546
- sulphide ores 537
- Group 17 582–634
  - acid strength of HX 602–05
  - atomic structure of F 2
  - basic properties 629–31
  - bond energy
    - of halogen compounds 598
    - of  $X_2$  594
  - bonding in HF 34
  - colour of  $X_2$  583
  - covalent radii 147, 591
  - electron affinity 154, 591
  - electronegativity 160, 592
  - electronic structures 582
  - energy cycle for
    - oxidation potential of  $X_2$  595
    - acid strengths of HX 603–04
  - extraction and uses 584–90
  - halides 605–07
  - hydration energy 591
  - hydrogen halides HX 599–605
    - table of properties 601
  - interhalogen compounds 621–27
  - ionic radii 591
  - ionization energy 149, 592
  - metallic properties 629–31
  - melting points 593
  - occurrence and abundance 583–84
  - oxides 607–14
  - oxidizing power of  $X_2$  594–96
  - oxoacids 614–21
  - polyhalides 628–29
  - positive bromine and iodine 629–31
  - preparation of anhydrous halides 606–07
  - pseudohalogens 632
  - reactions of the halogens 598
  - reaction with water 596–97
  - reactivity of the elements 597–98
  - standard reduction potentials 592, 613–14
  - strengths of oxoacids 621
  - types of bond formed 592–93
- Group 18 635–49
  - abundance in the atmosphere 637
  - atomic radii 637
  - Bartlett (first true Xe compound) 639
  - argon
    - molecular ion 638
  - boiling points 637
  - Cavendish 635
  - chemistry of xenon 639–43
  - clathrate 'compounds' 638–39
  - electronic structures 30, 635
  - helium
    - atomic structure 1, 2
    - molecule 99
    - molecular ion 99, 638
  - ionization energy 149, 637
  - melting points 637
  - neon atomic structure 2
  - occurrence and recovery 635–37
  - radon, formation of 636
  - special properties of helium 637–38
  - structure and bonding in xenon
    - compounds 643–48
  - superconductivity 638
  - uses 636–37
  - xenon
    - chemistry of 639–43
    - difluoride 640, 641, 642, 643–45
    - fluoride complexes 642–43
    - hexafluoride 640, 641, 642, 643, 645–46
    - hexafluoroplatinate 639
    - oxofluorides 640, 641
    - perxenate ion 640, 641
    - tetrafluoride 640, 641, 645
    - trioxide 640, 641
    - xenate ion 641
- Gun metal 406
- Gunpowder 539
- Haber–Bosch process 242, 243, 244, 491, 492–94
- Hadfield steel 735
- Haemerythrin 779
- Haemoglobin 775–77
- Hafnium, *see* Titanium group

- Hahn O 920  
 Half life period 911-12  
 Halic acids 617-18  
 Halides of transition elements (tables) 656-58  
 Hall-Héroult process 362-63  
 Halogen  
   acids 599-605  
   oxides 607-14  
   oxoacids 614-21  
 Halogens *see* Group 17  
 Halous acids 617  
 Hard and soft acids and bases 267-68  
 Hardness  
   of minerals 58  
   *see also* Appendix N Mohs scale  
   of water 337-38  
 Harkins rule 673 861 899 906  
 Hastelloy C alloy 802  
 Heavier elements *see* Actinides  
 Heisenberg uncertainty principle 11-2  
 Helium *see* Group 18  
 Heteropolyacids 710 730  
 Hexacyanoferrate(II) (ferrocyanide) 766  
 Hexagonal close packing 36-9  
 High alumina cement 373  
 High temperature reduction methods 181-82  
 Holmium *see* Lanthanides  
 Horizontal comparisons in the Fe-Co-Ni groups 814-15  
 Horizontal relationships in the periodic table 189-90  
 Hot dipping 762 835  
 Hume-Rothery's rules 135-40  
 Humphries series 2 8-9  
 Hund's rule 21-5 98-9 939  
   for determining ground state 946  
 Hybrid orbitals  
    $sp$  83-5  
    $sp^2$  82-5  
    $sp^3$  81-2 85  
    $sp^3d$  85-6  
    $sp^3d^2$  86  
 Hybridization 81-7  
 Hydrate isomerism 233  
 Hydrazine 483-85  
   Raschig process 484-85  
 Hydrides 248-54  
   covalent 250-52  
   melting points of 251  
   intermediate 254  
   interstitial (metallic) 245, 252-54  
   ionic 249-50  
   table of 249  
 Hydrides of  
   Group 1 297-98  
   Group 2 342-44  
   Group 13 252  
   Group 14 451-53  
   Group 15 478-85  
   Group 16 565-69  
   Group 17 599-605  
 Hydroboration 392-93  
 Hydrogen 240-71  
   abundance 241  
   abundance of gas in dry air 470  
   angular part of wave function 17-9  
   atomic spectra 5  
   atomic structure 1 2  
   azide 487-89  
   Balmer series 2 8-9  
   bonding 255-57 533 602  
   Brackett series 2 3 8-9  
   chlorine flame 600  
   economy 245  
   electronic structure 240  
   Humphries series 2 8-9  
   ion 240 254-55  
   isotopes 245-48 279  
   Lyman series 2 8-9  
   manufacture 241-43  
   molecule 99-100  
   molecule ion 99  
   ortho and para 248  
   Paschen series 2 3 8-9  
   peroxide 291-93 532 570-72  
   Pfund series 2 3 8-9  
   position in the periodic table 27 240-41  
   properties 243-45  
   radial part of wave function 17  
   solutions in metals 245  
   unique properties 27  
 Hydrogen bromide 601  
   acidic strength 602-05  
   ionic character 161  
   preparation 601  
 Hydrogen chloride 583 600-01  
   acidic strength 602-05  
   ionic character 161

- molecular structure 112
- preparation 600–02
- Hydrogen cyanide 453
- Hydrogen fluoride 583, 599
  - acidic strength 602–05
  - as a non-aqueous solvent 605
  - ionic character 161
  - preparation 599
  - structure 73
- Hydrogen iodide 601
  - acidic strength 602–05
  - ionic character 161
  - preparation 601
- Hydrogen peroxide 291–93, 532, 570–72
- Hydrogen selenide 565
- Hydrogen sulphide 536–37, 565–66, 568
- Hydroxylamine 485–86
- Hypohalous acids 615–16
- Hypophosphoric acid 518–19
- Hypophosphorous acid 520
- Ilmenite 684, 689
- IMI process for Ti 686
- Indium, *see* Group 13
- Induced nuclear reactions 917–18
- Inert pair effect 365
- Inner transition elements 24, 857–902
- Insulators 131–33
- Integrated circuits 68
- Interhalogen compounds 621–27
- Intrinsic semiconduction 60, 64
- Introduction to the transition elements 653–77
- Iodine
  - basic properties 629–31
  - colour of  $X_2$  583
  - covalent radius 591
  - electron affinity 154, 591
  - electronegativity 160, 592
  - electronic structure 582
  - extraction and uses 589
  - halides 605–07
  - heptafluoride 627
  - hydration energy 591
  - interhalogen compounds 621–27
  - ionic radius 591
  - ionization energy 149, 592
  - melting point 593
  - monochloride 623, 630–31
  - monocyanide 630
  - number 623
  - occurrence and abundance 583–84
  - oxides 612–13
  - oxidizing power of  $X_2$  594–96
  - oxoacids 614–21
  - pentafluoride 627
  - polyhalides 628–29
  - positive iodine 629–31
  - reaction with water 596–97
  - reactivity 597–98
  - standard reduction potentials 592, 613–14
  - trichloride 624–26, 631
  - triiodide ion 628
  - Wij's reagent 623
  - see also* Group 17
- Ion bombardment 883, 898, 917
- Ionic
  - bond 30–3, 43–71
  - radii 146, 148–49
- Ionic structures
  - based on close packing 46
  - cadmium chloride 51
  - cadmium iodide 49–50
  - calcium carbide 51–2
  - caesium chloride 48
  - calcium fluoride 48
  - close packing 46–7
  - lattice energy 54–8
  - layer structures 49–51
  - limiting radius ratios 44–6
  - nickel arsenide 51
  - perovskite 691, 749
  - rhenium trioxide 748–49
  - rutile 48–9
  - silica 49
  - sodium chloride 47–8
  - wurtzite 47
  - zinc blende 47
- Ionization energy 149–53
  - table of 151
- Ionization isomerism 232–33
- Iridium, *see* Cobalt group
- Iron group 753–82
  - abundance, extraction and uses 755–60
  - alums 194, 372, 723, 770
  - bioinorganic chemistry of iron 775–79
  - catalase and peroxidase 778
  - cytochrome 754, 777
  - ferredoxin 778–79

**Iron group (*cont.*)**

ferretin 778  
 haemerythrin 779  
 haemoglobin 775-77  
 myoglobin 777  
 blast furnace 755-57  
 brown ring test 500, 765  
 carbonyls 763-64, 765, 768  
 classification  
   as ferrous and platinum metals 753  
   as iron, cobalt and nickel triads 753  
 comparison of various steels 759  
 complexes 766-69, 772-73  
 (-II) and (0) compounds 763-65  
 (+II) compounds 764-69  
 (+III) compounds 769-73  
 (+IV) compounds 773  
 (+V) compounds 773  
 (+VI) compounds 774  
 (+VIII) compounds 774-75  
 cyclopentadienyl compounds 695-96, 711, 727-28, 779-81  
 double salts 764, 770  
 electronic structures 754  
 ferroin 767  
*ferrocene* 779-781  
 galvanizing 762  
 general properties 761-63  
 hexacyanoferrate(II) (ferrocyanide) 766  
 hot dipping 762  
 nitrogen fixation by Ru complexes 768-69  
 oxidation states 760-61  
 oxides 765, 770, 774  
 1,10 phenanthroline ( $\alpha$ -phenanthroline) 767  
 physical properties 763  
 pi-bonded complexes 766-69, 779-80  
 production and uses of steel 760  
 Prussian blue 766  
 rusting 762  
 standard reduction potentials 172-73  
 steel making 535-36, 757-60  
   basic oxygen process 759  
   Bessemer-Thomas converter 757-58  
   Kaldo and LD processes 759  
   puddling 757  
   Siemens electric arc furnace 758-59

**Siemens open hearth furnace 758**

Turnbull's blue 766

**Isomerism 232-36**

coordination 233  
 coordination position 234  
 facial 197, 797  
 geometric 198, 234  
 hydrate 233  
 ionization 232-33  
 linkage 233  
 meridional 197, 797  
 number of isomers 198  
 optical 234-35  
 polymerization 232

**Isomorphous replacement 443****Isopolyacids**

borates 379-80  
 chromates 713, 728-31  
 molybdates 713, 728-31  
 phosphates 511-21  
 silicates 432-46  
 tungstates 713, 728-31  
 vanadates 709-10

**Isoprene 398****Isotope dilution analysis 933****Isotope exchange reactions 933-34****Jahn-Teller 214-19**

square-planar complexes 217-19  
 tetragonal distortion 214-17  
 theorem 216

**Kaldo process (steel) 535, 759****Kaolin 440-41****K electron capture 910-11****Kieselguhr 431****Kroll process 686****Krypton, *see* Group 18****Kurrol's salt 516-17****Lanthanide contraction 874-75****Lanthanides 24, 859-78**

abundance and number of isotopes 861-62

**bastnaesite 863****Crooke's lenses 680, 863****colour and spectra 870-72****complexes 875-77****(+II) compounds 869-70****(+III) compounds 866-68****(+IV) compounds 868-69**



- contraction in size 874–75  
coordination numbers 877  
Deacon process 317, 587–88, 863  
didymium catalyst 317, 863  
electronic structure 859–60  
extraction and uses 862–63  
Harkins' rule 861  
ionization energies 861  
ionic radii 861  
lighter flints 680, 863  
magnetic properties 872–74  
mischmetal 680, 863  
monazite sand 679, 862–3, 883, 887–88  
oxidation states 860  
position in periodic table 859  
properties of (+III) states 866–68  
separation methods 864–66  
stable nuclei related to number of  
neutrons 863, 907  
solubility 870  
standard reduction potentials 861  
warm superconductors 143–44, 863  
Lanthanum, *see* Scandium group  
Laporte selection rule 771, 951–52  
Lattice energy 54–8  
and CFSE 212–13  
and hardness 58  
equation 54–6  
Lawrencium, *see* Actinides  
Layer structures 49–51  
LCAO method 90  
rules for combination of orbitals  
97–8  
LD process (steel) 535, 759  
Lead  
azide 488  
boiling point 411  
Chamber process 559–60  
chromate 407  
covalent radius 411  
electronic structure 402  
electronegativity values 160, 411  
extraction and uses 406–07  
galena 406–07  
halides 460–61  
hydride 453  
ionization energy 411  
melting point 411  
nitrate 501  
occurrence and abundance 403  
oxides 432  
red lead 407, 432  
reactivity 412–13  
scavenger 589  
standard reduction potentials 41  
storage batteries 407  
sulphide 406–07  
tetra acetate 456  
tetraethyl 464  
toxicity 464  
white lead 407  
*see also* Group 14  
Leblanc process 315–17  
Leclanché cell 838  
Levelling solvents 264  
Lewis  
octet theory 72–4  
theory of acids and bases 265  
Ligands, field strength 208  
Lighter flints 680, 863  
Lime 315–17, 322–23, 340  
caustic soda process 315, 322  
water 337, 424  
Linnaeite 783  
Linear accelerator 883, 898, 917  
Linkage isomerism 233  
Liquid ammonia 263–64, 302–03, 335,  
486–87  
Liquid dinitrogen tetroxide 265–66, 502  
Litharge 432  
Lithium  
alkyls and aryls 305  
aluminium hydride 297, 384–85  
atomic structure 1, 2  
carbonate 278, 295, 309–10  
diagonal relations 310–11  
differences from the rest of the group  
309  
electronic structure 275  
flame colouration 286–87  
halides 310  
hydroxide 290, 309–10  
metallic structure 125  
molecule 100–01  
n-butyl 305  
nitrate 295–96, 309–10  
nitride 289, 310  
oxide 290  
stearate 278, 304  
*see also* Group 1  
Little boy (bomb) 922–23  
Liquid drop model of nucleus 905–06

- Lowig (ferrite) process for NaOH 770  
 Lustre of metals 122  
 Lutetium, *see* Lanthanides  
 Lux-Flood theory of acids and bases 267  
   Lyman series 2, 8–9
- Maddrell's salt 516–17  
 Madelung constants 55–7  
 Magic numbers 907  
 Magnesium  
   biological role 353  
   chlorophyll 351–52  
   electronic structure 325  
   extraction 327–29  
     Dow natural brine process 329  
     Dow sea water process 329  
     Pidgeon process 328–29  
   Grignard compounds 328, 347–49  
   occurrence and abundance 326  
   uses 328  
   *see also* Group 2  
 Magnetic moment 225–26, 872–73  
   Curie law (magnetism) 670–71  
   measurement of magnetic properties 666  
   of octahedral complexes 211  
   of some 1st row complexes 669  
   of tetrahedral complexes 222  
 Magnetic properties 663–71, 675–76  
 Magnetic quantum number 10, 13–5, 22  
 Magnus' green 810  
 Malachite 817  
 Malonic acid 425  
 Malleability and cohesive force 122–26  
 Manhattan project 890, 920  
 Manganese group 734–52  
   abundance, extraction and uses 734–36  
   ammonium pertechnetate 735  
   basic acetate 734, 743  
   biological importance 734, 751  
   carbonyls 739–40  
   cluster compounds 743–45  
   colour 738, 740–42  
   complexes 742–45  
   (–I), (0) and (+I) compounds 739–40  
   (+II) compounds 740–42  
   (+III) compounds 742–45  
   (+IV) compounds 745–47  
   (+V) compounds 748  
   (+VI) compounds 748  
   (+VII) compounds 748–51  
   electronic structures 734  
   ferromanganese 735  
   general properties 737–39  
   manganese dioxide 745–47  
   manganin 735  
   oxidation states 736–37  
   perrhenates 735, 750  
   photosynthesis 743  
   physical properties 739  
   potassium permanganate 279, 734, 748–50  
   preparation of Tc 735  
   pyru'site 734  
    $\text{Re}_3\text{Cl}_9$  units 743–45  
   rhenium trioxide 748–49  
   spectra of  $[\text{Mn}(\text{H}_2\text{O})_6]^{2+}$  966  
   standard reduction potentials 167, 737  
 Manganin 735  
 Manufacture of computer chips 68  
 Marsh's test (As and Sb) 481  
 Mass number 905  
 Mattauch's rule 861  
 Melamine 347, 492  
 Melting points of  
   ionic and covalent compounds 39  
   the elements Appendix B  
 Mendelevium, *see* Actinides  
 Mercury, *see* Zinc group  
 Meridional isomers 197, 797  
 $\pi$ -Mesons 905, 908  
 Metallic  
   bonds 36–9, 121–45  
   *see also* Bond, metallic  
   character 163–64, 654  
   radii 137  
 Metalloenzymes and metalloproteins 673  
 Metals  
   alloys 132–40  
   bond lengths 127  
   clusters, *see* Cluster compounds  
   cohesive force 122–26, 285  
   conductivity 121–22  
   coordination number 126  
   crystal structures 36–9, 125–26  
   general properties 121–27  
   Hume-Rothery rules 135–40  
   lustre 122  
   M–M bonds  
     *see* Bond M–M

- malleability and cohesive force  
     122–26  
 radii 137  
 solutions in liquid  $\text{NH}_3$  263–64,  
     302–03, 335  
 superconducting alloys 141, 687, 698,  
     927  
 theories of bonding 127–31  
     free electron theory 128  
     valence bond theory 128  
     MO or band theory 128–31  
 Metaphosphorous acid 520  
 Methane 81  
 Methanol 243  
 Micas 440, 441–42  
 Millerite 800  
 Mischmetal 680, 863  
 Modes of decay  
      $\alpha$  decay 913–15  
      $\beta$  decay 909–10  
      $\gamma$  emission 911  
     K-electron capture 910–11  
     neutron emission 910  
     positron emission 910  
     proton emission 911  
     spontaneous fission 914  
 Mohs' scale of hardness 58, 404, 408,  
     417, 418, Appendix N  
 Moissan (preparation fluorine) 585  
 Molecular orbital theory 89–119  
     Aufbau build-up principle 98–9  
     bond order 105  
     combinations of orbitals  
         *d-d* 96  
         *p-d* 96  
         *p-p* 94–6  
         *s-p* 93–4  
         *s-s* 90–3  
     examples  
          $\text{B}_2$  101–02  
          $\text{Be}_2$  100–01  
          $\text{C}_2$  102–03  
          $\text{CO}$  110–12  
          $\text{F}_2$  107  
          $\text{H}_2^+$  99  
          $\text{H}_2$  99–100  
          $\text{HCl}$  112  
          $\text{He}_2^+$  99  
          $\text{He}_2$  99  
          $\text{Li}_2$  100–01  
          $\text{N}_2$  104–05  
          $\text{NO}$  109–10  
          $\text{O}_2$  105–06  
          $\text{O}_2^-$  105–07  
          $\text{O}_2^{2-}$  107  
     examples involving delocalized  
          $\pi$  bonding  
          $\text{CO}_2$  116–17  
          $\text{CO}_3^{2-}$  112–14  
          $\text{N}_3$  117  
          $\text{NO}_2^-$  116  
          $\text{NO}_3^-$  114  
          $\text{O}_3$  115–16  
          $\text{SO}_3$  114–15  
     in transition metal complexes  
          $[\text{CoF}_6]^{3+}$  227–28  
          $[\text{Co}(\text{NH}_3)_6]^{3+}$  227  
     LCAO method 90  
     non-bonding combinations 96–7  
     of complexes 202–03, 227–30  
     of inert gas compounds 645–46  
     of metals 128–31  
     order of MO energy levels 98  
     rules for LCAO 97–8  
     summary of multicentre  $\pi$ -bonded  
         structures 117–18  
     united atom method 118–19  
 Molybdenite 714  
 Molybdenum, *see* Chromium group  
 Monazite sand 679, 862–63, 883, 887–88  
 Mond (nickel) process 420, 801  
 Monel metal 599, 802  
 Monoclinic sulphur 542  
 Mulliken electronegativity 161–62  
 Multiplicity 944–46  
 Mustard gas 574  
 Myoglobin 777  
  
 Nafion 319  
 Natta catalysts 398  
 Natrolite 443  
 n-butyl lithium 305  
 Neodymium, *see* Lanthanides  
 Neon, *see* Group 18  
 Neptunium, *see* Actinides  
 Nernst equation (electrode potentials)  
     165  
 Nessler's reagent 479, 590, 845  
 Neutrino 909, 911  
 Neutron 1, 905  
     emission 910  
     fast 892  
     /proton ratio 908–09  
     slow 891

- Nicad batteries 838  
 Niccolite 800  
 Nickel glance 800  
 Nickel group 753, 800–15  
   alloys  
     alnico 802  
     cupronickel (coins) 802  
     EPNS 802  
     ferronickel 801  
     Hastelloy, C 802  
     Monel metal 599, 802  
     Nimonic 802  
     stainless steel 802  
   arsenide 51  
   basic acetate 810  
   benzene ammino nickel cyanide (clathrate) 807  
   carbonyls 805–06  
   catalytic convertors (cars) 803  
   cisplatin (anti cancer drug) 811  
   complexes with alkenes 808–10  
   contact process (for  $\text{SO}_2$ ) 552, 553, 698, 803  
   dimethyl glyoxime complex 807  
   electronic structures 800  
   general properties 803–05  
   halides 804  
   horizontal comparisons in the Fe, Co, Ni groups 814–15  
   Magnus green 810  
   Mond process 420, 801  
   occurrence, extraction and uses 800–03  
   one dimensional conductors 810–11, 812  
   oxidation states 803  
   oxides 804  
   physical properties 804  
   (–I), (0) and (+I) states 805–06  
   (+II) state 806–11  
   (+III) state 811, 813  
   (+IV) state 813  
   (+V) and (+VI) states 814  
   Raney nickel 802  
   Wacker process (ethanal) 803, 810  
 Nimonic alloys 802  
 Niobium, *see* Vanadium group  
 Nitrate ion 114  
 Nitric acid 504–07  
 Nitric oxide 109–10, 499–500  
 Nitrifying bacteria 473–74  
 Nitrite ion 116  
 Nitrogen  
   abundance of gases in dry air 470  
   atomic structure 2  
   azides 117, 487–89  
   boiling point 472  
   compounds of sulphur and nitrogen 576–77  
   covalent radius 475  
   cycle 473–74  
   denitrifying bacteria 473–74  
   differences from rest of group 472  
   electronegativity 475  
   electronic structure 468  
   fertilizer 470, 489, 493–94  
   fixation 473–74, 489, 491–93, 696, 713, 732  
   halides 494–96  
   ionization energy 475  
   nitrifying bacteria 473–74, 491  
   melting point 472  
   molecular structure 104–05  
   occurrence, extraction and uses 468–70  
   order of MO energy levels 104–05  
   oxides 498–503  
   oxoacids 503–07  
   standard reduction potentials 167, 490  
   *see also* Group 15  
 Nitrogenase 732, 775  
 Nitrogen cycle 473–74  
 Nitrogen dioxide 501–02  
 Nitrogen sesquioxide 501  
 Nitronium ion 505–06, 561  
 Nitrosyl complexes 500  
 Nitrous acid 503–04  
 Nitrous oxide 499  
 Nobel Laureates  
   Becquerel, H A , Curie, P and Curie, Marie (Physics 1903) 540  
   Bednorz, G and Muller, A (Physics 1987) 142  
   Bohr, N (Physics 1922) 6  
   Bosch, C and Bergius, F (Chemistry 1931) 492  
   Brown, H C and Wittig G (Chemistry 1979) 393  
   Curie, Marie (Chemistry 1911) 327  
   Fermi E (Physics 1938) 890, 920, 922

- Fischer, E.O. and Wilkinson, G.  
(Chemistry 1973) 728, 781
- Grignard, V. (Chemistry 1912) 347
- Haber, F. (Chemistry 1918) 492
- Hahn, O. (Chemistry 1944) 920
- Hodgkin, Dorothy Crowfoot  
(Chemistry 1964) 796
- Joliot, F. and Joliot-Curie, Irene  
(Chemistry 1935) 918
- Libby, W.F. (Chemistry 1960) 411
- Moissan, H. (Chemistry 1906) 585
- Ostwald, W. (Chemistry 1909) 505
- Pedersen, C.J., Lehn, J.M. and  
Cram, D. (Chemistry 1987)  
306
- Pauling, L. (Chemistry 1954) 80
- Rutherford, E. (Chemistry 1908)  
918
- Thomson, J.J. (Physics 1906) 6
- Werner, A. (Chemistry 1913) 195
- Ziegler, K. and Natta, G.  
(Chemistry 1963) 694
- Nobelium, *see* Actinides
- Noble gases, *see* Group 18  
abundance of gases in dry air 470  
electronic structure of 30
- Nomenclature for the superheavy  
elements 898–99
- Nomenclature of complexes 230–32
- Non-aqueous solvents  
HF 605  
NH<sub>3</sub> 263–64, 486–87  
N<sub>2</sub>O<sub>4</sub> 265–66, 502
- Non-bonding combinations of orbitals  
96–7
- Nonstoichiometry in the *d* block 672,  
705, 708–09
- Normal oxides 547–48
- n*-type semiconductors 62
- Nuclear  
binding energy 912–13, 914  
controlled fusion reactions 927–28  
distances 905  
fission 906, 918–20  
fuel 924  
fusion 925–28  
H-bomb 927  
moderators 923  
power stations 923–24  
reactors, types of  
fast breeder 924, 925  
gas cooled thermal 924  
water cooled thermal 925  
reprocessing 625, 896  
stability and N/P ratio 908–09  
thermonuclear weapons 927  
types of reactor 924–25
- Nucleus 905–37  
applications of radioisotopes 932–34  
atomic number 905  
atomic bomb 922  
Fat man (bomb) 922–23  
Little boy (bomb) 922–23  
production of 920–23  
carbon dating 410–11, 917, 932–33  
controlled fusion reactions 927–28  
chain reactions 919  
critical mass 920  
density 905, 906  
femtometres 905  
Fermi, E. 890, 920, 922  
fission 906, 918–20  
forces in 907–08  
fusion 925–28  
genesis of the elements 928–32  
r-process 931  
s-process 931  
x-process 931  
red giants 929  
spallation reactions 931  
supernova 932  
white dwarfs 930
- H-bomb 927
- Hahn, O. 920
- half-life period 911–12
- induced reactions 917–18
- Joliot, F. and Joliot-Curie, Irene 918
- magic numbers 907
- mass number 905
- $\pi$ -mesons 905, 908
- moderators 923
- modes of decay 909–11  
 $\alpha$  decay 913–15  
 $\beta$  decay 909–10  
 $\gamma$  emission 911  
K-electron capture 910–11  
neutron emission 910  
positron emission 910  
proton emission 911
- natural decay in lighter elements  
916–17
- nuclear distances 905

- Nucleus (*cont.*)  
   nucleons 905  
   number of stable nuclei and number of neutrons 863, 907  
   oscillation 8  
   radioactive  
     decay series 915–17  
     displacement laws 915  
   radius 905  
   Rutherford 10, 918  
   separation of isotopes 920–22  
     electromagnetic separation 921  
     gas centrifuge 921–22  
     gaseous diffusion 921  
     thermal diffusion 921  
   stability and N/P ratio 908–09  
   structure of nucleus 905  
     liquid drop model 905–06  
     shell structure 906–07  
   units and definitions 934  
 Number of stable nuclei and number of neutrons 863, 907  
 Nylon-6 485–86  
 Nylon-66 506, 698  
  
 Occurrence of the elements Appendix A  
 Octahedral complexes 205–17  
   asymmetrical electronic arrangements 215  
   crystal field theory 202, 204–14  
   crystal field splittings for hexa aqua complexes 209  
   crystal field splittings by various ligands 208  
   distortion of 214–17  
   MO theory 202–03, 227–30  
      $[\text{CoF}_6]^{3+}$  227–28  
   MO theory  $[\text{Co}(\text{NH}_3)_6]^{3+}$  227  
   symmetrical electronic arrangements 215  
   valence bond theory 202, 203–04  
 Octahedral holes 46–7  
 Octet rule 72–4  
   exceptions to rule 73–4  
 Oleum 559, 629  
 Olivine 435  
 Optical isomerism 234–35  
 Orbitals – shapes of  
   d 14, 18, 20, 201  
   f 15  
   p 14, 18, 20  
   s 14, 18, 20  
 Orbits  
   Bohr–Sommerfield 10  
   circular 1, 2  
   elliptical 9–10  
 Order of MO energy levels 98  
 Orthophosphoric acid 511–13  
 Orgel combined energy diagrams  
    $d^1$  and  $d^9$  957  
    $d^2$  and  $d^8$  961  
    $d^3$  967  
 Osazones 484  
 Osmium, *see* Iron group  
 Ostwald process ( $\text{HNO}_3$ ) 501, 505, 785  
 OXO process (addition of CO to alkenes) 789–90  
 Oxidation  
   number 164–65  
   states 164–65  
 Oxidation-reduction reactions 170–72  
 Oxide ion 107  
 Oxides 537–39, 547–54  
   classification of 547–49  
     normal, peroxide, suboxide 547–48  
     basic, amphoteric, acidic, neutral 548–49  
   general properties of 547–51  
   of transition elements (tables) 656–58  
   reactions between 549–51  
 Oxoacids strengths of 621  
 Oxygen  
   abundance 534  
   abundance of gases in dry air 470  
   allotropy and structures 540–41  
   atomic structure 2  
   boiling point 545  
   bond lengths and  $p\pi-d\pi$  bonding 546–47  
   carriers 775–76  
   covalent radius 545  
   differences from rest of group 547  
   electronic structure 532  
   electronegativity values 160, 545  
   extraction and uses 535–36  
   halides 572  
   hydrides 566–69  
   ionic radius 545  
   ionization energy 149, 545  
   melting point 545  
   molecular structure 105–06

- organo derivatives 577–78  
peroxides 570–72  
preparation 535, 618  
singlet 552  
standard reduction potentials 546  
uses 532  
*see also* Group 16
- Ozone 115–16, 540–41, **543–45**  
layer 494, **543–44**, 599  
ozonides 544–45
- Palladium, *see* Nickel group
- Panning (gold) 819
- Parathion 523–24
- Paris green 818
- Parkerizing 762
- Parke's process (silver) 818
- Participation of *d* orbitals in bonding 85–7
- Paschen series 2, 3, 8–9
- Pauli exclusion principle 21, 939
- Pauling's electronegativity 157–60  
table of values 160
- Pauling's valence bond theory 80–9
- p* block 357–649  
orbitals 14, 18, 20
- p*-type semiconduction 63, 65
- Pentlandite 800
- Peroxyborates 361–62, 379
- Periodic acid 620
- Periodic table (Preface) xxxv, 25–7
- Permittivity of vacuum 6–8
- Permutit 443
- Perovskite 749
- Peroxides 107, 279, 291–93, 361–62, 532, 547–48, 570–72, 691, 719
- Peroxo sulphuric acids 563, 571
- Pfund series 2, 3, 8–9
- pH scale 261–62
- Phase diagrams  
copper/nickel solid solutions 135  
copper/zinc 139  
iron/carbon 134  
tin/lead 138
- Phenacite 434
- 1,10-Phenanthroline (*o*-phenanthroline) 767
- Phosgene 457
- Phosphates 511–21  
environmental problems 515, 521  
Graham's salt 516–17  
Maddrell's salt 516–17  
sodium pyrophosphate 514–15  
sodium tetrametaphosphate 517–18  
sodium trimetaphosphate 516–18  
sodium tripolyphosphate 515–16  
qualitative analysis 512  
triethyl 496, 512, 521  
tritollyl 496, 521  
uses 520–21
- Phosphazenes 498, **524–26**
- Phosphine 481
- Phosphonitrilic compounds 498, **524–26**
- Phosphorus  
allotropic forms 474–75  
boiling point 472  
covalent radius 475  
electronegativity 475  
electronic structure 468  
halides 494–98  
hydrides 481  
in fertilizers 470, 494  
ionization energy 475  
melting point 472  
-nitrogen compounds (phosphazenes) 498, **524–26**  
occurrence, extraction and uses 470–71  
organometallic compounds 526–27  
oxides 508–11  
oxoacids 511–21  
oxochloride 496  
*p* $\pi$ -*d* $\pi$  bonding 509–10  
pentachloride 85–6  
phosphoric acids 511–19  
phosphorous acids 519–21  
standard reduction potentials 167, 490  
superphosphate 494  
sulphides 521–24  
test for phosphates 512  
*see also* Group 15
- Photocopiers 539
- Photochemical smog 544
- Photoelectric effect 11
- Photography 562, 589–90, 826–27
- Photosynthesis 424–25
- Photovoltaic cell 66
- Pi bonds 87–9
- Pig iron (cast iron) 755
- Pi mesons 905, 908
- Pidgeon process 328–29
- Pitchblende 883, 891

- Planck's constant 7, 10, 11  
     quantum theory 7  
 Planetary theory of atom 1-2, 10-1  
 Platinum, *see* Nickel group  
 Platinum metals 753  
 Plumbane 453  
 Plutonium, *see* Actinides  
 Polar and cartesian coordinates 16  
 Polarizability 156-57  
 Polarizing power 156-57  
 Polonium  
     abundance 534  
     discovery and production 540  
     electronic structure 532  
     standard reduction potentials 546  
     *see also* Group 16  
 Polyhalides 296-97  
 Polymerization isomerism 232  
 Polyphosphates 513-17  
 Polysulphides 293-94  
     oligomer 397-98  
     high density (stereoregular) 694-95  
     low density 694-95  
 Polyvinyl chloride 321  
 Polywater 569  
 Porphyrin 224 577-78 776  
 Portland cement 373  
 Positive bromine and iodine 629-31  
 Positron emission 910  
 Potassium  
     alum 194  
     bicarbonate 295  
     bromide 589  
     chloride 276, 279  
     cobaltinitrite 300  
     complexes 305-08  
     electronic structure 275  
     flame colouration 286-87  
     hydrogen carbonate 295  
     hydroxide 290  
     in fertilizers 279  
     nitrate 295-96  
     ozonide 544-45  
     perbromate 620  
     perchlorate 300 619  
     permanganate 279 734 748-50  
     perthenate 735 750  
     photoelectric effect 11  
     superoxide 279 290-93  
     tetraphenyl borate 300  
     *see also* Group 1  
 Praseodymium, *see* Lanthanides  
 Preparation of anhydrous halides 606-07  
 Principal quantum number 10, 13, 22  
 Problems with  
     acid rain 245, 538-39  
     asbestos 439  
     detergents 555-56  
     fluoride ions in drinking water 587  
     mercury and cadmium 838-39, 852-53  
     nitrogenous fertilizers 493-94  
     ozone layer 494, 543-44, 599  
     phosphates 515, 521  
     photochemical smog 544  
     water purity, EEC limits for contaminants 566  
 Producer gas 419-20  
 Production of the atomic bomb 920-23  
 Promethium, *see* Lanthanides  
 Protactinium, *see* Actinides  
 Proton 1, 905  
 Proton emission 911  
 Prussian blue 766  
 Pseudohalogens 632  
*p* type semi-conductors 63, 65  
 PTFE 457  
 Puddling (steel) 757  
 Pyrex glass 362 445  
 Pyrochlorite 698  
 Pyrolusite 734  
 Pyrosulphates 562  
 Pyroxenes 437-38  
  
 Quantum numbers 10, 13, 22  
     and atomic orbitals 15  
         magnetic 13-5  
         *n* 1, *m* *m*, 9-10, 13-5, 22  
         principal 9-10 13  
         spin 10  
         subsidiary 9-10, 13-5  
     and shape of periodic table 22  
     spectroscopic coupling  
         J 943  
         L 940-42  
         S 942-43  
 Quantum theory 7  
 Quartz 430  
  
 Racah parameters 227 961-63  
 Radial distribution functions 17



Radial part of wave function 15–7

Radii

- covalent 147
- ionic 146, 148–49
- metallic 137

Radioactive decay series 915–17

- actinium 915, 916
- neptunium 915, 916
- thorium 915–16
- uranium 915, 916

Radioactive displacement laws 915

Radiography 934

Radioisotopes, applications of 932–34

- activation analysis 933
- cancer treatment 934
- carbon dating 932–33
- isotope dilution analysis 933
- isotope exchange reactions 933–34
- radiography 934

Radius ratios

- calculation of limiting values 44–6
- cautionary word 52–4
- rules 43–4
- table of limiting values 44

Radon, *see* Group 18

Raney nickel 802

Rare earths 24, *see* Lanthanides

Raschig process (hydrazine) 484–85

Reaction mechanisms 461–63

Reactors

- fast breeder 924, 925
- gas cooled thermal 924
- water cooled thermal 925

Rectifiers 65–6

Red lead 407, 432

Reduced mass 8

Reduction potentials 165–78

- and methods of extracting elements 184

chromium group 717

copper group 820

examples of use of diagrams

- Am 175–76
- Cl<sub>2</sub> 176
- Cu 174
- Fe 172–73
- H<sub>2</sub>O<sub>2</sub> 174–75
- I<sub>2</sub> 177
- Mn 177

Group 13 368–69

Group 14 413

Group 15 490

lanthanides 681

manganese group 737

table of values 167

vanadium group 706

zinc group 842

Reformer (steam) 242

Refractory 381

Rhenium, *see* Manganese group

Rhizobium 474, 491, 732

Rhodium, *see* Cobalt group

Rhombic sulphur 542

Rochow direct process (alkylchloro-silanes) 447

Rubidium, *see* Group 1

Rules for LCAO 97–8

Russell–Saunders coupling 943–46

Rusting of iron 762

Ruthenium, *see* Iron group

Rutherford 10, 918

Rutherfordium, *see* Actinides

Rutile 48–9, 684, 689

Rydberg constant 8

Salt cake method (HCl) 600

Samarium, *see* Lanthanides

s block 273–356

orbitals 14, 18, 20

Scandium group 679–83

electronic structures 679

carbides 682–83

chemical properties 681–83

complexes 683

extraction, separation and uses 679–80

halides 682

hydrides 682

monazite sand 679, 862–63, 883, 887–88

oxidation state 680

oxides and hydroxides 681–82

physical properties 681

size 680–81

standard reduction potentials 681

Scheele 315, 587

Scheelite 715

Schottky defects 59–60

Schrodinger wave equation 12–21

angular part of 17–9

conditions for acceptable solutions 13

radial part of 15–7

- Selection rules 951–52
- Selenium
  - abundance 534
  - allotropy and structures 543
  - boiling point 545
  - bond lengths and  $p\pi-d\pi$  bonding 546–47
  - covalent radius 545
  - electronic structure 532
  - electronegativity values 160, 545
  - extraction and uses 539–40
  - halides 572, 574–75
  - hydrides 565, 568–69
  - ionic radius 545
  - ionization energy 149, 545
  - melting point 545
  - molecular structure 543
  - oxides 553, 554
  - oxoacids 564
  - oxohalides 564–65
  - photocopyers 539
  - standard reduction potentials 546
  - see also* Group 16
- Semiconductors
  - and transistors 63, 364
  - band gaps in 64
  - conductors, insulators and 131–33
  - extrinsic conduction 64
  - germanium 63–5
  - intrinsic conduction of 60–1, 64
  - ionic mechanism 60–1
  - n* type 62
  - p* type 63, 65
  - silicon 63–5
  - ultrapure materials 65
- Semiconductor devices
  - p-n* junction 65–6
  - integrated circuits 68
  - photovoltaic cell 66
  - rectifiers 65
  - transistors 66–9, 364
- Separation of isotopes 920–22
  - electromagnetic separation 921
  - gas centrifuge 921–22
  - gaseous diffusion 921
  - thermal diffusion 921
- Sequence of atomic energy levels 24
- Shapes of covalent molecules 74–80, 112–18
- Shapes of atomic orbitals 13
- Shapes of *d* orbitals 201
- Shell structure of nucleus 906–07
- Sherardizing 762
- Shift convertor 242
- Sidgwick–Powell theory 74–5
  - table of shapes 85
- Siemens electric arc furnace 758–59
- Siemens open hearth furnace 758
- Sigma bonds 87–9
- Silanes 451–52
  - alkylchloro substituted 447–51
- Silica 49, 429–31
  - gel 431
- Silicates 432–46
  - Bowen's reaction series 432–33
  - chain 437–39
  - cyclic 436–37
  - 3 dimensional 443
  - in technology 444–46
  - orthosilicates 434–35
  - pyrosilicates 435–36
  - sheet 440
  - soluble 433
- Silicon
  - as semiconductor 63–5
  - boiling point 411
  - carbide 418
  - covalent radius 411
  - electronic structure 402
  - electronegativity values 160, 411
  - extraction and uses 404
  - ferrosilicon 404
  - halides 459
  - hydrides 451–52
  - ionization energy 411
  - melting point 411
  - occurrence and abundance 403
  - organo derivatives 446–47
  - oxides 430–31
  - reaction mechanisms 462–63
  - reactivity 412–13
  - silicates 432–46
  - silicones 447–51
  - ultrapure 65, 405
  - see also* Group 14
- Silicones 447–51
- Silver, *see* Copper group
- Size of atoms 146–48
- Smaltite 783
- Smithsonite 836
- Soap 304, 315, 322
- Soda ash 322

- Sodamide 488, 499
- Sodium
- aluminate 291
  - argentocyanide 819
  - azide 499
  - bicarbonate 294, 295
    - baking powder 294
  - borohydride (tetrahydridoborate) 297, 384–85
  - carbonate 279
    - manufacture and uses of 315–22
  - chlorate 618
  - chloride 31–2, 47–8, 61
  - complexes 305–08
  - compounds with carbon 303
  - cyanide 453
  - dithionite 559
  - electronic structure 275
  - extraction 277–78
  - flame colouration 2, 286–87
  - hydrogen carbonate 294, 295
  - hydrogen sulphite (bisulphite) 552, 557, 558
  - hydroxide 278–94
    - manufacture and uses of 315–22
  - hypochlorite 615–16
  - in liquid ammonia 302–03
  - iodate 590
  - ion transport 309
  - /lead alloy 279
  - nitrate 295–96
  - nitrite 296, 504
  - nitroprusside 500
  - oxides 290–93
  - palmitate (soap) 304
  - peroxide 279, 290–93
  - peroxoborate 361–62, 379
  - pump 309
  - pyrophosphate 514–15
  - stearate (soap) 294
  - sulphate 279, 294–95, 316
  - sulphide 293–94
  - sulphite 532, 552, 558
  - tetrametaphosphate 517–18
  - thiosulphate 552, 559, 561–62
  - trimetaphosphate 516–18
  - tripolyphosphate 515–16
  - trithiocarbonate 429
  - see also* Group 1
- Solder 138, 406
- Solubility in
- polar and non polar solvents 40
  - liquid ammonia 302–03
- Solvay process ( $\text{Na}_2\text{CO}_3$ ) 323
- Solvent system of acids 265–66
- Sommerfeld elliptical orbits 9–10
- s orbital 14, 18, 20
- Spectra 938–71
- absorbance 951
  - allowed and forbidden transitions 951–52
  - atomic (hydrogen) 5
  - atomic absorption 287
  - charge transfer 460, 702, 705, 707, 719, 724, 738, 750, 766, 767, 771, 773, 822, 833, 840, 844, 845
  - coupling
    - spin-orbit 943–46
    - of angular orbital momenta 940–42
    - of spin angular momenta 942–43
  - $d^1$  and  $d^9$  ions 954–58
  - $d^2$  and  $d^8$  ions 958
  - $d^5$  ions 965
  - $d-d$  662–63, 938–71
  - derivation of term symbols
    - for closed subshell 948
    - for  $d^2$  configuration 948–50
    - for  $p^2$  configuration 943–46
  - determination of ground state 946
  - electronic arrangements of the elements 939
  - energy levels in an atom 938–46
  - emission 287
  - $f-f$  870, 880
  - Group 1 286–87
  - hole formulation 947
  - Hund's rule 21–5, 98–9, 939
    - for determining ground state 946
  - microstates
    - calculation of possible number 950
    - for  $p^2$  configuration 940, 944
    - for  $d^2$  configuration 949
  - of  $[\text{Co}(\text{Cl}_4)]^{2-}$  965
  - of  $[\text{Co}(\text{H}_2\text{O})_6]^{2+}$  964
  - of  $[\text{Mn}(\text{H}_2\text{O})_6]^{2+}$  966
  - of  $[\text{Ni}(\text{H}_2\text{O})_6]^{2+}$  960
  - of  $[\text{Ti}(\text{H}_2\text{O})_6]^{3+}$  207, 954
  - of  $[\text{V}(\text{H}_2\text{O})_6]^{3+}$  959
  - Orgel combined energy diagrams
    - $d^1$  and  $d^9$  957

- Spectra  
 Orgel combined energy diagrams  
 (*cont.*)  
 $d^2$  and  $d^8$  961  
 $d^3$  967  
 Pauli exclusion principle 21 939  
 Racah parameters 227 961–63  
 selection rules  
 Laporte 951–52  
 spin 952  
 splitting of electronic energy levels  
 953–54  
 Tanabe–Sugano diagrams 967–70  
 Spectrochemical series 208  
 Spectroscopic states 940  
 Spectroscopic term symbols 944–45  
 Speed of reactions 40–2  
 Speisses 783  
 Sphaelerite (zinc blende) 47 836  
 Spin orbit coupling 943–46  
 Spin selection rule 952  
 Spin quantum number 10 22  
 Spontaneous fission 914  
 Square planar complexes 217–19  
 Stability of various oxidation states in  
 $d$  block 656–57 674  
 Standard electrode potentials 165–78  
 Standard reduction potentials table of  
 167  
 Stainless 453  
 Steam reformer 242  
 Steel 134 340 404 418 469 535–36  
 734 735 759–60 787  
 cutting 715  
 Hadfield 735  
 phase diagram 760  
 stainless 695 802  
 Steel making 535–36 757–60  
 basic oxygen process 759  
 Bessemer–Thomas furnace 757–58  
 Kildar and LD processes 759  
 puddling 757  
 Siemens electric arc furnace 758–59  
 Siemens open hearth furnace 758  
 Stellite 783  
 Stereoisomerism 234  
 Stereoregular polymers 694  
 Stribine 481  
 Strontium *see* Group 2  
 Structures  
 based on close packing 36–9 46  
 of covalent compounds 72–117  
 of ionic solids 47–9 51–2  
 of layer compounds 49 51  
 of metals 36–9 125–26  
 Suboxides 547–48  
 Subsidiary quantum number 13–5 22  
 Sulphamic acid 554  
 Sulphide ores 537  
 Sulphur  
 abundance 534  
 allotropy and structures 542–43  
 boiling point 545  
 bond lengths and  $p\pi-d\pi$  bonding  
 546–47  
 compounds of sulphur and nitrogen  
 576–77  
 Contact process (for  $\text{SO}_2$ ) 552, 553  
 698 803  
 covalent radius 545  
 dioxide 88 551–52  
 acid rain 245 538–39  
 detection and analysis 551–52  
 non aqueous solvent 552  
 electronic structure 532  
 electronegativity values 160 545  
 extraction and uses 536–39  
 Frasch process 536  
 halides 572–75  
 hexafluoride 86–7 587  
 hydride 536–37 565–66 568–69  
 ionic radius 545  
 ionization energy 149 545  
 melting point 545  
 molecular structure 541–43  
 oxoacids 556–63  
 oxohalides 564–65  
 polysulphides 570–72  
 standard reduction potentials 546  
 trioxide 89 114–15 553–54  
 uses 532  
*see also* Group 16  
 Sulphuric acid 532 553 559–62  
 Sulphurous acid series 556 558–59  
 Sulphur compounds 567  
 Superconductors 140–44  
 1 2 3 structures 142–43  
 alloys 141 687 698 927  
 Bednorz and Muller 141  
 helium 638  
 possible future uses 143–44  
 present uses of 141

- warm 143–44, 863  
Superheavy elements  
  half lives 899  
  nomenclature 898–99  
Superoxides 105–07, 291–93  
Superphosphates 494
- Talc (soapstone) 441  
Tanabe–Sugano diagrams 967–70  
Tantalite 698  
Tantalum, *see* Vanadium group  
Technetium, *see* Manganese group  
Teflon 457  
Tellurium  
  abundance 534  
  allotropy and structures 543  
  boiling point 545  
  covalent radius 545  
  electronic structure 532  
  electronegativity values 160, 545  
  extraction and uses 539–40  
  halides 572, 574  
  hydrides 565, 568–69  
  ionic radius 545  
  ionization energy 149, 545  
  melting point 545  
  oxides 552–53, 554  
  oxoacids 564  
  standard reduction potentials 546  
  *see also* Group 16  
Tetrachloromethane (carbon tetra-  
  chloride) 33, 73, 457, 771  
Tetraethyl lead 463  
Terbium, *see* Lanthanides  
Terylene 506  
Tetragonal distortion 214–16  
Tetrahedral complexes 219–22  
  electronic arrangement 222  
  factors favouring formation 221  
  magnetic moments of 222  
  splitting energy levels 220–21  
Tetrahedral holes 46–7  
Thallium, *see* Group 13  
Theories of bonding in covalent  
  compounds  
  MO theory 89–119  
  Sidgwick–Powell theory 74–5  
  VSEPR theory 74–80  
  delocalized multicentre  $\pi$  bonds  
    112–18
- Theories of bonding in metals  
  free electron theory 128  
  MO or band theory 128–31  
  valence bond theory 128  
Thermal decomposition 179–80  
Thermite reaction 182  
Thermonuclear devices 247  
Thermodynamics of reduction processes  
  183–87  
Thionic acid series 562–63  
Thionyl compounds 564  
Thompson, J.J. 6  
Thorite 883  
Thorium, *see* Actinides  
Three-centre bonds 116, 117, 333, 384,  
  395–97, 424, 489, 504, 541,  
  606  
Thulium, *see* Lanthanides  
Tin  
  boiling point 411  
  bronze 406  
  cassiterite 405  
  complexes 460  
  covalent radius 411  
  electronic structure 402  
  electronegativity values 160, 411  
  extraction and uses 405–06  
  gun metal 406  
  halides 460–61  
  hydride 451  
  ionization energy 411  
  melting point 411  
  organo compounds 463  
  oxides 405, 432  
  plate 406  
  reactivity 412–13  
  solder 138, 406  
  standard reduction potentials 413  
  occurrence and abundance 403  
  organotin compounds 406  
  oxides 43–2  
  *see also* Group 14  
Titanium group 684–96  
  (+III) compounds 692–95  
  (+IV) compounds 689–92  
  cyclopentadienyl compounds 695–96  
  electronic structures 684  
  extraction and uses 685–87  
    IMI process Ti 686  
    Kroll process 686  
    van Arkel de Boer process 686–87

- Titanium (*cont.*)  
   ilmenite 684–689  
   nitrogen fixation 491–93, 696  
   occurrence and abundance 684  
   organometallic compounds 694–95  
   oxidation states 687  
   oxides  
     dioxide 48–9, 536, 684, 689–90  
     mixed oxides 690–91  
     peroxides 691  
   perovskite 691, 749  
   phosphate 512  
   physical properties 685  
   polythene 694–65  
   reactivity/passive behaviour 688  
   rutile 48–9, 684, 689  
   size 687–88  
   spectra and colour  $[\text{Ti}(\text{H}_2\text{O})_6]^{3+}$  207, 954  
   standard reduction potentials 688  
   stereoregular polymers 694  
   superconducting alloys 687  
   tetrahalides 691–92  
   Ziegler–Natta catalyst 556, 694–95  
 TNT 506  
 Tonnages of heavy chemicals produced 316, Appendix K, Appendix L  
 Trans isomers 197–98, 234–35  
 Transistors 66–8, 364  
 Transition elements, *see d block*  
 Transition series 24  
 Tridymite 430  
 Tl iodine ion 628  
 Triple bonds 35–6  
 Trisilylamine 456  
 Tritium 245–48, 279  
 Triethyl phosphate 496, 512, 521  
 Tritolyl phosphate 496, 521  
 Tungsten  
   bronzes 731–32  
   carbide 417, 715  
   tungstates 713, 728–31  
   *see also* Chromium group  
 Turnbull's blue 766  
 Turquoise 817  
  
 Ultramarines 443–44  
 Ultrapure materials 64, 405  
 United atom method 118–19  
 Uraninite 891  
 Uranium, *see* Actinides  
  
 Uranyl nitrate 894  
 Urea 423–24, 494, 554  
 Usanovich theory of acids 267  
  
 Valence bond theory 80–9  
   applied to complexes 202, 203–04  
   applied to metals 128  
   extent of *d* orbital participation 85–7  
   hybridization 81–6  
   sigma and pi bonds 87–9  
   some examples  
     BeF<sub>2</sub> 83–4  
     BF<sub>3</sub> 82–4  
     CH<sub>4</sub> 81  
     HF 80  
     H<sub>2</sub>O 80  
     NH<sub>3</sub> 81  
     PCl<sub>5</sub> 85–6  
     SF<sub>6</sub> 86  
   table of shapes and number of orbitals 85  
 Vanadates 709–10  
 Vanadinite 697  
 Vanadium group 697–712  
   abundance, extraction and uses 697–98  
   addition to steel 698  
   electronic structure 697  
   carbides 417, 698, 700–01  
   carbonyls 711  
   carnotite 697  
   cluster compounds 697, 705–07  
   colour 700  
   columbite 698  
   complexes 708–09  
   cyclopentadienyl compounds 711  
   ferrovanadium 697  
   general properties 699–700  
   halides 701–06  
   hydrides 701  
   low oxidation states 710–11  
   M–M bonds 703, 705–07  
   nitrides 700–01  
   nonstoichiometric compounds 705–07  
   708–09  
   organometallic compounds 711  
   oxidation states 699  
   oxides 707–09  
   pentoxide catalyst 697, 698  
   physical properties 699  
   pyrochlorite 698

- reactivity 699
- standard reduction potentials 706
- size 699
- spectra  $V^{3+}$  ( $d^1$ ) 704–05
  - of  $[V(H_2O)_6]^{3+}$  959
- superconducting alloy 698
- tantalite 698
- vanadates 709–10
- vanadinite 697
- vanadyl compounds 708
- van Arkel de Boer process 686–87
- van der Waals forces 39, 50, 51, 56, 124, 250
- van der Waals radii 637
- Variable valency 164–65
  - in the  $d$  block 654–56
- Vaska's compound 788–89
- Vertical relationships in the periodic table 189–90
- Viscose rayon 428–29
- Vitamin B<sub>12</sub> 784, 793, 796
- VSEPR theory 74–80
  - effect of lone pairs 75–6
  - effect of electronegativity 76
  - some examples
    - BF<sub>3</sub> 77
    - BF<sub>4</sub>P<sup>–</sup> 77
    - ClF<sub>3</sub> 78–9
    - H<sub>2</sub>O 77–8
    - I<sub>3</sub> 79
    - IF<sub>7</sub> 80
    - NH<sub>3</sub> 77
    - PCl<sub>5</sub> 78
    - SF<sub>4</sub> 79
    - SF<sub>6</sub> 80
- Vulcanizing of rubber 539
- Wackenroder reaction 563
- Wacker process (ethanal) 803, 810
- Walden inversion 462
- Water 566–69
  - bonding 34
  - EEC limits for contaminants 566
  - fluoride ions in drinking water 587
  - structure 73, 77–8, 80
- Water gas 242, 419
- Water softening 337–38, 566–67
- Wave equation 12–21
  - angular part of 17–9
  - radial part of 15–7
  - total function 20
- Weldon process 317
- Wave mechanics 11–21
- Werner theory of complexes 195–98
  - primary valencies 195
  - secondary valencies 195
  - isomers 197–98
- 'Wet ashing' 619
- Widia metal 783
- Wij's reagent 623
- Wilkinson's catalyst 788–89
- Willemite 434
- Wolframite 715
- Wrought iron 757, 758
- Xenon
  - bonding 643–48
  - chemistry of 639–43
  - difluoride 640, 641, 642, 643–45
  - fluoride complexes 642–43
  - hexafluoride 640, 641, 642, 643, 645–46
  - hexafluoroplatinate 639
  - oxofluorides 640, 641
  - perxenate ion 640, 641
  - tetrafluoride 640, 641, 645
  - trioxide 640, 641
  - uses 636
  - xenate ion 641
  - see also* Group 18
- Ytterbium, *see* Lanthanides
- Yttrium, *see* Scandium group
- Zeeman 10
- Zeolites 443–44
- Zeise's salt 809, 850
- Ziegler catalysts 397–98
- Ziegler–Natta catalysts 556, 694–95
- Zinc group 835–56
  - abundance, extraction and uses 835–39
  - basic zinc acetate 846
  - biological role of zinc 851–52
  - brass 139, 818, 838
  - cadmium chloride structure 51
  - cadmium control rods 890, 892
  - cadmium iodide structure 49–50
  - calamine 836
  - cinnabar 836
  - complexes 845–46
  - conductivity cell 848

**Zinc group (*cont.*)**

electronic structure 835

Frankland 850

general properties 840–42

halides 843–44

hot dipping 762 838

Leclanché cell 838

mercury cathode cell (NaOH) 319–21

mercury (+I) compounds 846–47

nicad batteries 838

polycations 849–50

Nessler's reagent 479 590 845

organometallic compounds 850–51

oxidation states 839

oxides 842–43

physical properties 840

size 839–40

smithsonite 836

standard reduction potentials 842

toxicity of mercury and cadmium  
838–39 852–53

Zeise's salt 850

zinc blende (sphalerite) 47 836

Zircon 435 684

Zirconium *see* Titanium group

Zone refining 64 405